# District 10 Mobility Performance Report

2017 Fourth Quarter

### DEPARTMENT OF TRANSPORTATION

February 8, 2018 : Jaime Q. Quesada

### **District 10 Mobility Performance Report**

2017 Fourth Quarter

### **EXECUTIVE SUMMARY**

### Overview

Caltrans District 10 contains eight counties located within the Central Valley (San Joaquin / Stanislaus / Merced) and the Sierra Nevada (Amador / Calaveras / Tuolumne / Mariposa / Alpine). Over the years detection in Alpine and Calaveras Counties has been sparse, so the District 10 Mobility Performance Report (MPR) no longer includes these two counties in the quarterly or annual analysis.

The MPR quarterly analysis compares information in the current quarter to that of the previous quarter and the quarter one year prior. The following are the performance measures reported in the MPR:

- Vehicle Miles Traveled (VMT)
- Vehicle Hours of Delay (VHD)
- Lost Lane Miles (LLM)
- Detector Health (DH)

This information is based on data collected every day of the quarter, twenty–four hours a day, by automated vehicle detector stations deployed on urban-area freeways where congestion is regularly experienced. The MPR presents congestion information at two speed thresholds: delay from vehicles traveling below 35 miles per hour (mph), and delay from vehicles traveling below 60 mph. The delay at the 35 mph threshold represents severe congestion while delay at 60 mph represents all congestion, both light and heavy. These thresholds are set by Caltrans and are based upon engineering experience and District input.

### FINDINGS

In the fourth quarter, total delay equaled 151 thousand vehicle hours of delay (VHD) at the 35 mph speed threshold (13.4% increase over one year ago; 31.3% increase over last quarter),

and 596 thousand VHD at the 60 mph threshold (34% increase over one year ago; 25.8% increase over last quarter). The average weekday delay experienced in this quarter was approximately 2,181 VHD at 35 mph (25.9% increase over one year ago; 44.7% increase over last quarter), and 8,508 VHD at 60 mph (37.9% increase over one year ago; 29.1% increase over last quarter). The increases in VHD over one year ago and over the last quarter can be attributed to an overall 41% decrease in detection reliability (-5% reduction in good detection and 36% increase in bad detection) and to yearly growth in District 10.

FWY	COUNTY	LOCATION	SHIFT	ABS. PM	CA PM	# DAYS ACTVE	AVG. EXTENT (MILES)	TOTAL DELAY (VEH-HRS)	TOTAL DURATION (MINS)
1205-W	SJ	E of Hansen Rd	AM	3.310	2.38	50	4.9	98,336	6,930
SR99-S	STA	Kansas Ave	PM	227.834	R16.799	53	1.1	10,577	6,075
1205-W	SJ	E-O Mountain House Pkwy	AM	2.900	1.97	19	1.4	7,697	2,270
SR99-N	STA	Crows Landing Rd OC	PM	225.533	R14.473	57	0.4	6,613	7,540
SR99-S	SJ	N-O Jack Tone Rd	PM	238.974	3.189	56	0.4	6,533	8,950
SR99-S	SJ	S-O Austin Rd OC	PM	240.425	4.64	56	0.2	4,705	9,145
SR99-S	SJ	S-O Rte 120	PM	241.202	5.417	43	0.5	4,452	5,430
SR99-N	STA	Crows Landing Rd OC	AM	225.533	R14.473	50	0.4	3,321	4,310
SR99-S	STA	Service Rd OC	PM	221.613	R10.578	23	1.7	4,427	1,885
15-N	SJ	N-O French Camp Rd	PM	468.140	R22.648	39	0.2	835	3,085

# Top Ten Bottlenecks for 2017 Quarter 4

The following District 10 projects are currently being constructed or are scheduled for construction effective February 2018. These current and future (planned) projects will further relieve congestion in District 10:

### MERCED COUNTY

**MER 99 MISSION AVENUE INTERCHANGE / FREEWAY; EA 10-36311** Convert from 4 lane expressway to 6 lane freeway on an 8 lane right of way Approve Construction Contract Date – 04/07/2008 End Project – 04/02/2018

MER 99 NB LIVINGSTON MEDIAN WIDENING; EA 10-0Q121

Lane widening from 2 to 3 lanes Approve Construction Contract Date – 08/01/2021 End Project – 10/02/2023

### MER 99 SB LIVINGSTON MEDIAN WIDENING; EA 10-0Q122

Lane widening from 2 to 3 lanes Approve Construction Contract Date -01/19/2019End Project -10/01/2021

### MER 152 – LOS BANOS BYPASS SEGMENT I; EA 10-41911

Convert 4 lane expressway to 6 lane freeway Approve Construction Contract Date -05/15/2018End Project -10/01/2020

### <u>SAN JOAQUIN COUNTY</u>

# **SJ 4 RAMP METERING IMPROVEMENTS; EA 10-1F180**

Install ramp meters along SR 4 between the I-5 and SR 99 Connectors Currently in PRS/PDS; PA&ED Scheduled for mid-2016 End Project – Estimated to be mid 2020

### SJ 120 RAMP METERING IMPROVEMENTS; EA 10-1F040

Install ramp meters along SR 4 between the I-5 and SR 99 Connectors Currently in PRS/PDS; PA&ED Scheduled for mid-2016 End Project – Estimated to be mid 2020

### I-205 SMART CORRIDOR PHASE 2; EA 10-1C330

Install ramp meters and ITS elements along I205 from MacArthur to Grant Line Road Currently in PA&ED End Project – 11/01/2021

### STANISLAUS COUNTY

**STA 99 / SJ 99 RAMP METERING & MAINLINE IMPROVEMENTS; EA 10-1C300** Improve Mainline and Ramp Operations; Standardize Structure Clearance; Add Auxiliary Lane Currently in PA&ED End Project – Estimated to be mid 2020

The above capacity increasing, ramp metering, interchange improvement, and interchange construction projects are located on the routes, in the cities, and in the counties that experience the most congestion in District 10. It is expected that the projects will help increase the Vehicle Miles Traveled while reducing congestion and delay as the population and demand in District 10 grows over the next 10 years.

The next section of this report summarizes the District 10 2017 Q3 Quarterly Mobility Statistics.



# 2017 Q4 Quarterly Mobility Statistics – District 10

4





# District 10 Mobility Performance Report | 2/8/2018

Congestion by Route											
		Vehicle Hours of Delay at 35 mph			Difference 2017 Q4-2016 Q4		Differ 2017 Q4	ence -2017 Q3	Rank		
Route	County	2016 Q4	2017 Q3	2017 Q4	Absolute	Percentage	Absolute	Percentage	2016 Q4	2017 Q3	2017 Q4
1205	San Joaquin	274,610	191,624	154,421	-120,189	-43.8%	-37,203	-19.4%	1	1	1
SR99	Stanislaus	14,101	30,507	44,825	30,724	217.9%	14,318	46.9%	5	3	2
SR99	San Joaquin	64,509	61,140	42,712	-21,796	-33.8%	-18,428	-30.1%	2	2	3
SR132	Stanislaus	0	10,577	24,394	24,394		13,818	130.6%		4	4
1580	San Joaquin	57,976	5,206	14,743	-43,233	-74.6%	9,537	183.2%	3	5	5
15	San Joaquin	3,315	2,220	7,654	4,339	130.9%	5,434	244.8%	8	6	6
SR219	Stanislaus	3,857	1,870	3,258	-599	-15.5%	1,389	74.3%	7	7	7
SR99	Merced	25,734	1,256	1,619	-24,116	-93.7%	363	28.9%	4	8	8
SR4	San Joaquin	10,360	308	390	-9,970	-96.2%	82	26.7%	6	11	9
SR120	San Joaquin	0	752	355	355		-397	-52.8%		10	10
SR132	San Joaquin	0	1,131	9	9	8500.0%	-1,123	-99.2%	13	9	11
SR12	San Joaquin	1	3	0	-1	-84.6%	-3	-94.1%	12	12	12
Б	Merced	0	0	0	0		0				
15	Stanislaus	717	0	0	-717	-100.0%	0		10		
SR104	Amador	0	0	0	0		0				
SR108	Tuolunne	0	0	0	0		0				
SR120	Tuolunne	0	0	0	0		0				
SR152	Merced	1,636	0	0	-1,636	-100.0%	0		9		
SR49	Mariposa	67	0	0	-67	-100.0%	0		11		
SR88	Amador	0	0	0	0		0				
TOTALS		456,883	306,594	294,381	-162,502	-35.6%	-12,213	-4.0%			

### Data may change in coming months due to on-going data reconciliation process

SR 132 Stanislaus: No delay detected in 2016 Q4.

SR 120 San Joaquin: No delay detected in 2016 Q4.

SR 132 San Joaquin: No delay detected in 2016 Q4.

SR 12 San Joaquin: No delay detected in 2017 Q4.

I5 Merced: No delay detected in 2016 Q4, 2017 Q3, and 2017 Q4.

I5 Stanislaus: No delay detected in 2017 Q3 and 2017 Q4.

SR 104 Amador: No delay detected in 2016 Q4, 2017 Q3, and 2017 Q4.

SR 108 Tuolumne: No delay detected in 2016 Q4, 2017 Q3, and 2017 Q4.

SR 120 Tuolumne: No delay detected in 2016 Q4, 2017 Q3, and 2017 Q4.

SR 152 Merced: No delay detected in 2017 Q3 and 2017 Q4.

SR 49 Mariposa: No delay detected in 2017 Q3 and 2017 Q4.

SR 88 Amador: No delay detected in 2016 Q4, 2017 Q3, and 2017 Q4.