

DEPARTMENT OF TRANSPORTATION
DIVISION OF ENGINEERING SERVICES
OFFICE ENGINEER, MS 43
1727 30TH STREET
P.O. BOX 168041
SACRAMENTO, CA 95816-8041
FAX (916) 227-6214
TTY 711



*Flex your power!
Be energy efficient!*

February 26, 2010

03-Sac-5501
03-2C8444

Addendum No. 2

Dear Contractor:

This addendum is being issued to the contract for BUILDING CONSTRUCTION IN SACRAMENTO COUNTY IN SACRAMENTO AT THE TRANSPORTATION LABORATORY AT 5900 FOLSOM BOULEVARD.

Submit bids for this work with the understanding and full consideration of this addendum. The revisions declared in this addendum are an essential part of the contract.

Bids for this work will be opened on Tuesday, March 9, 2010.

This addendum is being issued to revise the Project Plans, the Notice to Bidders and Special Provisions, and the Bid book.

Project Plan Sheets 1, 2 and 25 are revised. Copies of the revised sheets are attached for substitution for the like-numbered sheets.

Project Plan Sheet 34A is added. A copy of the added sheet is attached for addition to the project plans.

Project Plan Sheet 34 is deleted.

In the Special Provisions, Section 10-1.05, "TEMPORARY FENCE (TYPE ESA)," is deleted.

In the Special Provisions, Section 10-1.05, "TEMPORARY FENCE AND GATES," is added as attached.

In the Amendments to the Standard Specifications Dated May 2006, Section 2-1.12, "BID DOCUMENT COMPLETION," subsection 2-1.12A, "General," is revised as follows:

"2-1.12A General

Complete forms in the Bid book.

On the Subcontractor List you may either submit each subcontracted bid item number and corresponding percentage with your bid or fax this information to (916) 227-6282 within 24 hours after bid opening. If you fail to submit this information within the time specified, your bid is nonresponsive.

Except for the bid item number and the percentage of each item subcontracted, do not fax submittals."

In the Bid book, the "SUBCONTRACTOR LIST" form is revised as attached.

Addendum No. 2
Page 2
February 26, 2010

03-Sac-5501
03-2C8444

In the Bid book, in the "Bid Item List," Item 26 is added and Item 3 is deleted as attached.

To Bid book holders:

Replace the entire "Bid Item List" in the Bid book with the attached revised Bid Item List. The revised Bid Item List is to be used in the bid.

Inquiries or questions in regard to this addendum must be communicated as a bidder inquiry and must be made as noted in the Notice to Bidders section of the Notice to Bidders and Special Provisions.

Indicate receipt of this addendum by filling in the number of this addendum in the space provided on the signature page of the Bid book.

Submit bids in the Bid book you now possess. Holders who have already mailed their book will be contacted to arrange for the return of their book.

Inform subcontractors and suppliers as necessary.

This addendum and attachments are available for the Contractors' download on the Web site:

http://www.dot.ca.gov/hq/esc/oe/project_ads_addenda/03/03-2C8444

If you are not a Bid book holder, but request a book to bid on this project, you must comply with the requirements of this letter before submitting your bid.

Sincerely,

ORIGINAL SIGNED BY

REBECCA D. HARNAGEL
Chief, Office of Plans, Specifications & Estimates
Office Engineer
Division of Engineering Services

Attachments

10-1.05 TEMPORARY FENCE AND GATES

Temporary fence and gates shall be furnished, constructed, maintained, and later removed as specified in these special provisions and as directed by the Engineer.

Except as otherwise specified in this section, temporary fence and gates shall conform to the plan details and the specifications for permanent fence and gates of similar character as provided in Section 80, "Fences," of the Standard Specifications.

Used materials may be installed provided the used materials are good, sound and are suitable for the purpose intended, as determined by the Engineer.

Materials may be commercial quality provided the dimensions and sizes of the materials are equal to, or greater than, the dimensions and sizes shown on the plans or specified herein.

Posts shall be either metal or wood at the Contractor's option.

Galvanizing and painting of steel items will not be required.

Treating wood with a wood preservative will not be required.

Concrete footings for metal posts will not be required. For posts over pavement, use steel post plates or precast concrete blocks secured in place as approved by the Engineer.

Temporary fence and gates that are damaged during the progress of the work shall be repaired or replaced by the Contractor at the Contractor's expense. In the event that the temporary fence on pavement is shifted or dislocated from its original position, the temporary fence shall be brought back to its original position by the end of the work shift.

When no longer required for the work, as determined by the Engineer, temporary fence and gates shall be removed. Removed facilities shall become the property of the Contractor and shall be removed from the site of the work, except as otherwise provided in this section.

Removed temporary fence and gate materials that are not damaged may be constructed in the permanent work provided the materials conform to the requirements specified for the permanent work and such materials are new when used for the temporary fence and gates.

Holes caused by the removal of temporary fence and gates shall be backfilled in conformance with the provisions in the second paragraph of Section 15-1.02, "Preservation of Property," of the Standard Specifications.

The various types and kinds of temporary fence will be measured and paid for in the same manner specified for permanent fence of similar character as provided in Section 80, "Fences," of the Standard Specifications.

Full compensation for temporary gates is included in the contract unit price paid per linear foot for temporary fence (type CL-6) and no separate payment will be made therefor.

Full compensation for maintaining, removing, and disposing of temporary fence and gates is included in the contract prices paid per linear foot for temporary fence (type CL-6) and no additional compensation will be allowed therefor.

Bidder Name: _____

The bidder must identify each subcontractor performing work in an amount in excess of 1/2 of 1 percent of the total bid or \$10,000, whichever is greater (Pub Cont Code § 4100 et seq.). Complete columns 1 and 4 and submit with the bid. Complete columns 2 and 3 and submit with the bid or fax to (916) 227-6282 within 24 hours after the bid opening. Failure to provide complete information in columns 1 through 4 within the time specified will result in a non-responsive bid.

| Column 1: Business Name and Location | Column 2: Bid Item No.(s) | Column 3: Percent of Bid Item Subcontracted | Column 4: Description of Subcontracted Work |
|---|----------------------------------|--|--|
| | | | |

ADA Notice For individuals with sensory disabilities, this document is available in alternate formats. For information call (916) 654-6410 or TDD (916) 654-3880 or write Records and Forms Management, 1120 N Street, MS-89, Sacramento, CA 95814.

**BID ITEM LIST
03-2C8444**

| Item No. | Item Code | Item Description | Unit of Measure | Estimated Quantity | Unit Price | Item Total |
|----------|-----------|--|-----------------|--------------------|------------|------------|
| 1 | 070012 | PROGRESS SCHEDULE (CRITICAL PATH METHOD) | LS | LUMP SUM | LUMP SUM | |
| 2 | 070013 | SMALL BUSINESS UTILIZATION REPORT | EA | 5 | 250.00 | 1,250.00 |
| 3 | BLANK | | | | | |
| 4 | 074016 | CONSTRUCTION SITE MANAGEMENT | LS | LUMP SUM | LUMP SUM | |
| 5 | 074017 | PREPARE WATER POLLUTION CONTROL PROGRAM | LS | LUMP SUM | LUMP SUM | |
| 6 | 074033 | TEMPORARY CONSTRUCTION ENTRANCE | EA | 1 | | |
| 7 | 074038 | TEMPORARY DRAINAGE INLET PROTECTION | EA | 12 | | |
| 8 | 074042 | TEMPORARY CONCRETE WASHOUT (PORTABLE) | LS | LUMP SUM | LUMP SUM | |
| 9 | 150206 | ABANDON CULVERT | EA | 6 | | |
| 10 | 150221 | ABANDON INLET | EA | 10 | | |
| 11 | 150224 | ABANDON MANHOLE | EA | 2 | | |
| 12 | 150805 | REMOVE CULVERT | EA | 1 | | |
| 13 | 150820 | REMOVE INLET | EA | 1 | | |
| 14 | 190101 | ROADWAY EXCAVATION | CY | 1,660 | | |
| 15 | 260201 | CLASS 2 AGGREGATE BASE | CY | 1,800 | | |
| 16 | 390130 | HOT MIX ASPHALT | TON | 1,290 | | |
| 17 (F) | 510502 | MINOR CONCRETE (MINOR STRUCTURE) | CY | 30 | | |
| 18 | 510526 | MINOR CONCRETE (BACKFILL) | CY | 23 | | |
| 19 | 620080 | 15" ALTERNATIVE PIPE CULVERT | LF | 1,110 | | |
| 20 | 707225 | 48" PRECAST CONCRETE PIPE MANHOLE | LF | 40 | | |

**BID ITEM LIST
03-2C8444**

| Item No. | Item Code | Item Description | Unit of Measure | Estimated Quantity | Unit Price | Item Total |
|-----------|-----------|-----------------------------------|-----------------|--------------------|------------|------------|
| 21 (F) | 750001 | MISCELLANEOUS IRON AND STEEL | LB | 7,593 | | |
| 22 | 840656 | PAINT TRAFFIC STRIPE (2-COAT) | LF | 1,530 | | |
| 23 | 842000 | PARKING BUMPER (PRECAST CONCRETE) | EA | 49 | | |
| 24 | 994650 | BUILDING WORK | LS | LUMP SUM | LUMP SUM | |
| 25 | 190110 | LEAD COMPLIANCE PLAN | LS | LUMP SUM | LUMP SUM | |
| 26 | 071321 | TEMPORARY FENCE (TYPE CL-6) | LF | 1,520 | | |

TOTAL BID: _____