

**DEPARTMENT OF TRANSPORTATION**  
DIVISION OF ENGINEERING SERVICES  
OFFICE ENGINEER, MS 43  
1727 30<sup>TH</sup> STREET  
P.O. BOX 168041  
SACRAMENTO, CA 95816-8041  
FAX (916) 227-6214  
TTY 711



*Flex your power!  
Be energy efficient!*

February 23, 2009

03-Yo1-50-0.9/3.0  
03-388004  
STPLN-6203(007)

Addendum No. 4

Dear Contractor:

This addendum is being issued to the contract for CONSTRUCTION ON STATE HIGHWAY IN YOLO COUNTY IN WEST SACRAMENTO FROM 1.1 KM WEST TO 1.0 KM EAST OF HARBOR BOULEVARD OVERCROSSING.

Submit bids for this work with the understanding and full consideration of this addendum. The revisions declared in this addendum are an essential part of the contract.

Bids for this work will be opened on April 15, 2009 instead of the original date March 3, 2009.

This addendum is being issued to set a new bid opening date as shown herein and revise the Project Plans, the Notice to Bidders and Special Provisions, and the Bid book, the Federal Minimum Wages with Modification Number 23 dated February 6, 2009.

Project Plan Sheets 4, 225, 311 and 318 are revised. Half-sized copies of the revised sheets are attached for substitution for the like-numbered sheets.

In the Special Provisions, Section 10-1.29, "EXISTING HIGHWAY FACILITIES," subsection "OBLITERATE SURFACING," the first paragraph is revised as follows:

"Existing asphalt concrete and aggregate base surfacing, when no longer required for the passage of public traffic, shall be obliterated at the locations shown on the plans to a depth of 900 mm."

In the Special Provisions, Section 10-1.33, "CONTAMINATED MATERIAL," subsection "MATERIALS," the second paragraph is revised as follows:

"Provide a 10,000 gallon holding tank to meet the needs of all dewatering activities described in the dewatering plan. The holding tank must be transportable and totally enclosed. The holding tank must have an inlet and outlet capable of receiving and discharging minimum flows. The holding tank must be able to accommodate temporary installation of submersible pumps of such capability to discharge water. The tank must remain on the job site until de-watering operations are no longer necessary as determined by the Engineer. If additional holding capacity is needed for dewatering activities, it will be paid for as extra work as provided in Section 4-1.03D of the Standard Specifications."

03-Yo1-50-0.9/3.0  
03-388004  
STPLN-6203(007)

In the Special Provisions, Section 10-2, "HIGHWAY PLANTING AND IRRIGATION SYSTEM," in the "IRRIGATION SYSTEM COST BREAK-DOWN," table the following is added to the table.

"

**IRRIGATION SYSTEM COST BREAK-DOWN**

**Contract No. 03-388004**

UNIT DESCRIPTION	UNIT	APPROXIMATE QUANTITY	VALUE	AMOUNT
75 MM PLASTIC PIPE (PR 315) (SUPPLY LINE)	M	250		

"

In the Bid book, in the "Bid Item List," Item 100 is revised as attached.

To Bid book holders:

Replace page 7 of the "Bid Item List" in the Bid book with the attached revised page 7 of the Bid Item List. The revised Bid Item List is to be used in the bid.

Inquiries or questions in regard to this addendum must be communicated as a bidder inquiry and must be made as noted in the Notice to Bidders section of the Notice to Bidders and Special Provisions.

Indicate receipt of this addendum by filling in the number of this addendum in the space provided on the signature page of the Bid book.

Submit bids in the Bid book you now possess. Holders who have already mailed their book will be contacted to arrange for the return of their book.

Inform subcontractors and suppliers as necessary.

This office is sending this addendum by GSO overnight mail to Bid book holders to ensure that each receives it. A copy of this addendum and the modified wage rates are available for the Contractors' use on the Web site:

**[http://www.dot.ca.gov/hq/esc/oe/weekly\\_ads/addendum\\_page.html](http://www.dot.ca.gov/hq/esc/oe/weekly_ads/addendum_page.html)**

If you are not a Bid book holder, but request a book to bid on this project, you must comply with the requirements of this letter before submitting your bid.

Sincerely,

ORIGINAL SIGNED BY

REBECCA D. HARNAGEL, Chief  
Office of Plans, Specifications & Estimates  
Division of Engineering Services - Office Engineer

Attachments

## BID ITEM LIST

03-388004

Item No.	Item Code	Item Description	Unit of Measure	Estimated Quantity	Unit Price	Item Total
81	394040	PLACE ASPHALT CONCRETE DIKE (TYPE A)	M	130		
82	394044	PLACE ASPHALT CONCRETE DIKE (TYPE C)	M	30		
83	394048	PLACE ASPHALT CONCRETE DIKE (TYPE E)	M	940		
84	041249	FURNISH PILING (CLASS 900) (ALTERNATIVE X)	M	564		
85 (S)	041250	DRIVE CONCRETE PILE (CLASS 900) (ALTERNATIVE X)	EA	32		
86	041251	FURNISH PILING (CLASS 625) (ALTERNATIVE X)	M	573		
87 (S)	041252	DRIVE CONCRETE PILE (CLASS 625) (ALTERNATIVE X)	EA	32		
88 (S)	500001	PRESTRESSING CAST-IN-PLACE CONCRETE	LS	LUMP SUM	LUMP SUM	
89 (F)	510051	STRUCTURAL CONCRETE, BRIDGE FOOTING	M3	95		
90 (F)	510053	STRUCTURAL CONCRETE, BRIDGE	M3	517		
91 (F)	510060	STRUCTURAL CONCRETE, RETAINING WALL	M3	401		
92 (F)	510314	CLASS 4 CONCRETE (BACKFILL)	M3	43.4		
93 (F)	510413	CLASS 1 CONCRETE (BOX CULVERT)	M3	460.1		
94 (F)	510502	MINOR CONCRETE (MINOR STRUCTURE)	M3	53.9		
95	510524	MINOR CONCRETE (SOUND WALL)	M3	280		
96	BLANK					
97 (S)	041253	ERECT PRECAST PRESTRESSED CONCRETE BATHTUB GIRDER	EA	20		
98 (S)	041254	FURNISH PRECAST PRESTRESSED CONCRETE BATHTUB GIRDER (15M -20M)	EA	10		
99 (S)	041255	FURNISH PRECAST PRESTRESSED CONCRETE BATHTUB GIRDER (20M -25M)	EA	10		
100 (S-F)	518002	SOUND WALL (MASONRY BLOCK)	M2	2872		