

DEPARTMENT OF TRANSPORTATION
DES-OE MS #43
1727 30TH Street, 2ND Floor
Sacramento, CA 95816



**** WARNING ** WARNING ** WARNING ** WARNING ****
This document is intended for informational purposes only.

Users are cautioned that California Department of Transportation (Department) does not assume any liability or responsibility based on these electronic files or for any defective or incomplete copying, excerpting, scanning, faxing or downloading of the contract documents. As always, for the official paper versions of the bidders packages and non-bidder packages, including addenda write to the California Department of Transportation, Plans and Bid Documents, Room 0200, P.O. Box 942874, Sacramento, CA 94272-0001, telephone (916) 654-4490 or fax (916) 654-7028. Office hours are 7:30 a.m. to 4:15 p.m. When ordering bidder or non-bidder packages it is important that you include a telephone number and fax number, P.O. Box and street address so that you can receive addenda.

October 26, 2001

04-CC,Sol-680,780-39.4/41.0(680),L0.0/R1.3(680),1.1/2.3(780)
04-006064
ACIM-680-1(054)56N

Addendum No. 2

Dear Contractor:

This addendum is being issued to the contract for construction on State highway in SOLANO AND CONTRA COSTA COUNTIES IN BENICIA AND MARTINEZ ON ROUTE 680 FROM MOCOCO OVERHEAD TO BAYSHORE ROAD AND ON ROUTE 780 FROM ROUTE 680 TO EAST FIFTH STREET.

Submit bids for this work with the understanding and full consideration of this addendum. The revisions declared in this addendum are an essential part of the contract.

Bids for this work will be opened on November 14, 2001 instead of the original date of October 30, 2001.

This addendum is being issued to set a new bid opening date as shown herein and revise the Project Plans, the Notice to Contractors and Special Provisions, and the Proposal and Contract.

Project Plan Sheet 787 is revised as follows:

In the PILE ELEVATION detail, the callout "#29 hoops @ 150" is changed to "#19 hoops bundled @ 150."

In the PILE ELEVATION detail, the callout "#29 hoops @ 100" is changed to "#19 hoops bundled @ 100."

In the SECTION A-A detail, the callout "#29 hoops" is changed to "#19 hoops bundled.

Project Plan Sheet 780 is revised as follows:

The quantity for "BAR REINFORCING STEEL (RETAINING WALL)" is revised to 4,000 kg.

In the Special Provisions, Section 10-1.01, "ORDER OF WORK," the following paragraph, added in addendum no. 1, is deleted.

"The work consisting of electrical work on the Main Span, Bridge No. 28-153R, shall not begin prior to 630 working days from the fifteenth calendar day after the approval of contract."

In the Proposal and Contract, the Engineer's Estimate Item 150 is revised.

Addendum No. 2
Page 2
October 26, 2001

04-CC, Sol-680, 780-39.4/41.0(680), L0.0/R1.3(680), 1.1/2.3(780)
04-006064
ACIM-680-1(054)56N

To Proposal and Contract book holders:

Replace page 10 of the Engineer's Estimate in the Proposal with the attached revised page 10 of the Engineer's Estimate. The revised Engineer's Estimate is to be used in the bid.

Indicate receipt of this addendum by filling in the number of this addendum in the space provided on the signature page of the proposal.

Submit bids in the Proposal and Contract book you now possess. Holders who have already mailed their book will be contacted to arrange for the return of their book.

Inform subcontractors and suppliers as necessary.

This office is sending this addendum by confirmed facsimile to all book holders to ensure that each receives it.

If you are not a Proposal and Contract book holder, but request a book to bid on this project, you must comply with the requirements of this letter before submitting your bid.

Sincerely,

ORIGINAL SIGNED BY

REBECCA D. HARNAGEL, Chief
Office of Plans, Specifications & Estimates
Office Engineer

ENGINEER'S ESTIMATE

04-006064

Item	Item Code	Item	Unit of Measure	Estimated Quantity	Unit Price	Item Total
141	519010	NEOPRENE STRIP	M2	53		
142 (S)	519121	JOINT SEAL (TYPE B - MR 30 MM)	M	42		
143 (S)	519123	JOINT SEAL (TYPE B - MR 50 MM)	M	37		
144 (S)	519129	JOINT SEAL ASSEMBLY (MR 101 MM - 160 MM)	M	33		
145	519130	JOINT SEAL ASSEMBLY (MR 161 MM - 240 MM)	M	11		
146 (S)	519131	JOINT SEAL ASSEMBLY (MR 241 MM - 320 MM)	M	48		
147 (S)	048700	JOINT SEAL ASSEMBLY (MR 800 MM)	M	31		
148 (S)	048701	JOINT SEAL ASSEMBLY (MR 980 MM)	M	18		
149 (S-F)	520102	BAR REINFORCING STEEL (BRIDGE)	KG	5 502 700		
150 (F)	520103	BAR REINFORCING STEEL (RETAINING WALL)	KG	154 490		
151 (S-F)	048702	WELDED HEADED BAR REINFORCING	EA	41 778		
152 (S)	022195	BAR REINFORCING STEEL (HEAD WALL)	KG	181		
153 (F)	540101	ASPHALT MEMBRANE WATERPROOFING	M2	49		
154	560218	FURNISH SIGN STRUCTURE (TRUSS)	KG	45 046		
155 (S)	560219	INSTALL SIGN STRUCTURE (TRUSS)	KG	45 046		
156	561008	760 MM CAST-IN-DRILLED-HOLE CONCRETE PILE (SIGN FOUNDATION)	M	45		
157	561009	920 MM CAST-IN-DRILLED-HOLE CONCRETE PILE (SIGN FOUNDATION)	M	17		
158	562004	METAL (RAIL MOUNTED SIGN)	KG	350		
159	566011	ROADSIDE SIGN - ONE POST	EA	7		
160	566012	ROADSIDE SIGN - TWO POST	EA	7		