STATE OF CALIFORNIA

DEPARTMENT OF TRANSPORTATION

# NOTICE TO BIDDERS

# AND

# SPECIAL PROVISIONS

**FOR BUILDING CONSTRUCTION ADJACENT TO STATE HIGHWAY IN SAN MATEO COUNTY NEAR HILLSBOROUGH AT CRYSTAL SPRINGS SAFETY ROADSIDE REST AREA.**

**In District 04 On Route 280**

**Under**

| | |
|---|---|
| Bid book dated May 26, 2009 | Standard Specifications dated 2006 |
| Project Plans approved May 4, 2009 | Standard Plans dated 2006 |

**Identified by**

**Contract No. 04-0A9204**

**04-SM-280-13.3/13.6**

**Federal-Aid Project**
**ACIM-280-1(117)E**

Bids open Tuesday, July 7, 2009 OSD

Dated May 26, 2009 IH

**********

# SPECIAL NOTICES

**********

- The Department moved the Amendments to the Standard Specifications to the back of the book titled "Notice to Bidders and Special Provisions."

- The Department retitled the "Proposal and Contract" book to "Bid" book and:

  1. Simplified the language
  2. Moved clauses and the contract form from the "Proposal and Contract" book into the Amendments to the Standard Specifications
  3. Standardized the forms

- The Department retitled the "Notice to Contractors" to "Notice to Bidders" and:

  1. Simplified the language
  2. Moved clauses from the "Notice to Contractors" into the Amendments to the Standard Specifications
  3. Standardized instructions for bidders' inquiries

- The Department incorporated boilerplate special provisions into the Amendments to the Standard Specifications.

- The Department is implementing new Disadvantaged Business Enterprise requirements for Underutilized Disadvantaged Business Enterprises (UDBE). Section 2, "Bidding," under subsection titled "Disadvantaged Business Enterprises" and Section 5, "General," under subsection titled "Performance of UDBEs" of these special provisions cover the UDBE requirements.

- The contract award period has been extended for this project.

- See Section 5 of the special provisions for new specifications regarding retentions.

- The Department is implementing new contract requirements for submittal of Small Business Utilization Report forms. See section titled "Small Business Utilization Report" of these special provisions and bid item list.

- The Department has replaced Section 8, "Prosecution and Progress." This replacement affects references in a large number of other specifications. Due to the extent of affected specifications, these references will not be corrected until there is a change in technical content that merits a specification revision. Section 0, "Global Revisions," of the Amendments to the Standard Specifications covers references affected by the Section 8 replacement.

- For this contract, the trigger threshold for asphalt price fluctuations is reduced from 10 to 5 percent. See section titled "Compensation Adjustments for Price Index Fluctuations" in Section 5 of these special provisions.

# TABLE OF CONTENTS

NOTICE TO BIDDERS ..... 7
COPY OF BID ITEM LIST ..... 9
SPECIAL PROVISIONS ..... 14
SECTION 1. (BLANK) ..... 14
SECTION 2. BIDDING ..... 14
2-1.01 DISADVANTAGED BUSINESS ENTERPRISES ..... 14
SECTION 3. CONTRACT AWARD AND EXECUTION ..... 15
3-1.01 CONTRACT AWARD ..... 15
SECTION 4. BEGINNING OF WORK, TIME OF COMPLETION AND LIQUIDATED DAMAGES ..... 15
SECTION 5. GENERAL ..... 15
5-1.01 PERFORMANCE OF UDBEs ..... 15
5-1.02 TRAINING ..... 16
5-1.03 RETENTION EXCLUSION ..... 16
5-1.04 COMPENSATION ADJUSTMENTS FOR PRICE INDEX FLUCTUATIONS ..... 16
5-1.05 COMPENSATION ADJUSTMENTS FOR PRICE INDEX FLUCTUATIONS ..... 17
5-1.06 AREAS FOR CONTRACTOR'S USE ..... 18
5-1.07 PAYMENTS ..... 19
5-1.08 PROJECT INFORMATION ..... 19
5-1.09 SOUND CONTROL REQUIREMENTS ..... 19
5-1.10 RELATIONS WITH CALIFORNIA REGIONAL WATER QUALITY CONTROL BOARD ..... 20
5-1.11 NATURALLY OCCURRING ASBESTOS ..... 21
5-1.12 ENVIRONMENTALLY SENSITIVE AREA ..... 22
5-1.13 PRESERVATION OF PROPERTY ..... 22
5-1.14 DAMAGE REPAIR ..... 22
5-1.15 RELIEF FROM MAINTENANCE AND RESPONSIBILITY ..... 23
SECTION 6. (BLANK) ..... 23
SECTION 7. (BLANK) ..... 23
SECTION 8. MATERIALS ..... 23
SECTION 8-1. MISCELLANEOUS ..... 23
8-1.01 PREQUALIFIED AND TESTED SIGNING AND DELINEATION MATERIALS ..... 23
8-1.02 STATE-FURNISHED MATERIALS ..... 28
SECTION 8-2. CONCRETE ..... 29
8-2.01 PORTLAND CEMENT CONCRETE ..... 29
SECTION 8-3. WELDING ..... 29
8-3.01 WELDING ..... 29
SECTION 9. (BLANK) ..... 32
SECTION 10. CONSTRUCTION DETAILS ..... 32
SECTION 10-1. GENERAL ..... 32
10-1.01 CONSTRUCTION PROJECT INFORMATION SIGNS ..... 32
10-1.02 ORDER OF WORK ..... 33
10-1.03 WATER POLLUTION CONTROL ..... 33
10-1.04 CONSTRUCTION SITE MANAGEMENT ..... 39
10-1.05 STREET SWEEPING ..... 48
10-1.06 TEMPORARY CONCRETE WASHOUT FACILITY ..... 48
10-1.07 TEMPORARY SILT FENCE ..... 50
10-1.08 TEMPORARY FENCE AND GATE (TYPE CL-6) ..... 52
10-1.09 TEMPORARY FENCE (TYPE ESA) ..... 52
10-1.10 TEMPORARY CONSTRUCTION ENTRANCE ..... 54
10-1.11 TEMPORARY DRAINAGE INLET PROTECTION ..... 56
10-1.12 COOPERATION ..... 60
10-1.13 PROGRESS SCHEDULE (CRITICAL PATH METHOD) ..... 60
10-1.14 OBSTRUCTIONS ..... 62
10-1.15 SMALL BUSINESS UTILIZATION REPORT ..... 63
10-1.16 CONSTRUCTION AREA TRAFFIC CONTROL DEVICES ..... 63

10-1.17 CONSTRUCTION AREA SIGNS ..... 64
10-1.18 MAINTAINING TRAFFIC ..... 65
10-1.19 CLOSURE REQUIREMENTS AND CONDITIONS ..... 66
CLOSURE SCHEDULE ..... 66
CONTINGENCY PLAN ..... 66
LATE REOPENING OF CLOSURES ..... 67
COMPENSATION ..... 67
10-1.20 TRAFFIC CONTROL SYSTEM FOR LANE CLOSURE ..... 67
10-1.21 BARRICADE ..... 68
10-1.22 PORTABLE CHANGEABLE MESSAGE SIGN ..... 68
10-1.23 CHANNELIZER ..... 68
10-1.24 TEMPORARY CRASH CUSHION MODULE ..... 68
10-1.25 EXISTING HIGHWAY FACILITIES ..... 69
ABANDON SEWER AND WATER PIPE LINE ..... 70
REMOVE GATE AND FENCE ..... 70
REMOVE ROADSIDE SIGN AND ROADSIDE SIGN (STRAP AND SADDLE BRACKET) ..... 70
RELOCATE ROADSIDE SIGN ..... 70
RELOCATE BLUE STAR MEMORIAL ..... 70
REMOVE MANHOLE ..... 70
COLD PLANE ASPHALT CONCRETE PAVEMENT ..... 71
REMOVE CONCRETE ..... 71
REMOVE RETAINING WALL ..... 71
10-1.26 CLEARING AND GRUBBING ..... 71
10-1.27 EARTHWORK ..... 72
10-1.28 CONTROLLED LOW STRENGTH MATERIAL ..... 72
10-1.29 MATERIAL CONTAINING NATURALLY OCCURRING ASBESTOS ..... 73
10-1.30 EROSION CONTROL (TYPE D) ..... 75
10-1.31 IRRIGATION CROSSOVERS ..... 79
10-1.32 IRRIGATION SLEEVE ..... 79
10-1.33 IMPORTED TOPSOIL ..... 79
10-1.34 AGGREGATE BASE ..... 79
10-1.35 PARKING AREA SEAL COAT ..... 80
10-1.36 HOT MIX ASPHALT ..... 82
10-1.37 MINOR HOT MIX ASPHALT ..... 82
10-1.38 REPLACE ASPHALT CONCRETE SURFACING ..... 83
10-1.39 CONCRETE STRUCTURES ..... 84
STAIR NOSING INSERTS ..... 84
MEASUREMENT AND PAYMENT ..... 84
10-1.40 REINFORCEMENT ..... 84
10-1.41 ROADSIDE SIGNS ..... 84
10-1.42 FURNISH SIGN ..... 85
SHEET ALUMINUM ..... 86
RETROREFLECTIVE SHEETING ..... 86
PROCESS COLOR AND FILM ..... 87
SINGLE SHEET ALUMINUM SIGN ..... 87
FIBERGLASS REINFORCED PLASTIC PANEL SIGN ..... 87
MEASUREMENT AND PAYMENT ..... 88
10-1.43 PREPARING AND PAINTING CONCRETE CURB ..... 88
10-1.44 PLASTIC PIPE ..... 88
10-1.45 PLANTER DRAIN ..... 88
10-1.46 UNDERDRAIN ..... 88
10-1.47 WELDED STEEL PIPE ..... 88
10-1.48 SEWER MANHOLE ..... 88
10-1.49 DIRECTIONAL HORIZONTAL BORING ..... 90
10-1.50 SLOPE PROTECTION ..... 94
10-1.51 MISCELLANEOUS CONCRETE CONSTRUCTION ..... 94
10-1.52 STONE PAVER BAND ..... 95
10-1.53 MISCELLANEOUS IRON AND STEEL ..... 96

10-1.54 CHAIN LINK FENCE....96
10-1.55 DECORATIVE METAL GATE AND FENCE....96
10-1.56 THERMOPLASTIC TRAFFIC STRIPE AND PAVEMENT MARKING....97
10-1.57 PARKING BUMPER....98
10-1.58 SITE FURNISHINGS....98
10-1.59 PET WASTE BAG DISPENSER....98
10-1.60 FLAGPOLE....99
SECTION 10-2 HIGHWAY PLANTING AND IRRIGATION SYSTEMS....99
10-2.01 GENERAL....99
PROGRESS INSPECTIONS....99
COST BREAK-DOWN....100
10-2.02 EXISTING HIGHWAY PLANTING....104
MAINTAIN EXISTING PLANTED AREAS....104
REMOVE EXISTING PLANTS FOR TRENCHING....104
10-2.03 EXISTING HIGHWAY IRRIGATION FACILITIES....105
CHECK AND TEST EXISTING IRRIGATION FACILITIES....105
MAINTAIN EXISTING IRRIGATION FACILITIES....105
REMOVE EXISTING IRRIGATION FACILITIES....106
10-2.04 HIGHWAY PLANTING....106
HIGHWAY PLANTING MATERIALS....106
PESTICIDES....107
PLACE BOULDERS....107
PREPARING PLANTING AREAS....108
CULTIVATE....108
PLANTING....108
PLANT ESTABLISHMENT WORK....108
10-2.05 IRRIGATION SYSTEMS....109
VALVE BOXES....109
GATE VALVES....110
ELECTRIC AUTOMATIC IRRIGATION COMPONENTS....110
ARMOR-CLAD CONDUCTORS....112
IRRIGATION SYSTEMS FUNCTIONAL TEST....112
PIPE....113
THRUST BLOCK....113
BACKFLOW PREVENTER ASSEMBLIES....113
BACKFLOW PREVENTER ASSEMBLY ENCLOSURE....114
TESTING NEW BACKFLOW PREVENTERS....114
BACKFLOW PREVENTER ASSEMBLY BLANKET....114
SPRINKLERS....115
SPRINKLER (TYPE D)....115
WYE STRAINERS....115
FLUSH VALVES....115
FINAL IRRIGATION SYSTEM CHECK....115
SECTION 10-3. (BLANK)....116
SECTION 11. (BLANK)....116
SECTION 12. BUILDING WORK....116
SECTION 12-1. GENERAL REQUIREMENTS....116
12-1.01 SCOPE....116
12-1.02 ABBREVIATIONS....116
12-1.03 GUARANTEE....117
12-1.04 AREAS FOR CONTRACTOR'S USE....117
12-1.05 COOPERATION....117
12-1.06 SUBMITTALS....117
12-1.07 SCHEDULE OF VALUES....118
12-1.08 INSPECTION....119
12-1.09 OBSTRUCTIONS....119
12-1.10 PRESERVATION OF PROPERTY....119
12-1.11 UTILITY CONNECTION....119

12-1.12 TEMPORARY UTILITIES....120
12-1.13 SANITARY FACILITIES....120
12-1.14 MEASUREMENT AND PAYMENT....120
12-1.15 PROJECT RECORD DRAWINGS....120
12-1.16 FIELD ENGINEERING....121
SECTION 12-2. SITEWORK....122
12-2.01 BUILDING DEMOLITION AND REMOVAL OF MISCELLANEOUS FACILITIES....122
12-2.02 ASBESTOS ABATEMENT....124
12-2.03 LEAD RELATED CONSTRUCTION WORK....131
12-2.04 EARTHWORK FOR BUILDING WORK....135
12-2.05 AGGREGATE BASE....139
12-2.06 FREE DRAINING GRANULAR MATERIAL....140
12-2.07 TERMITE CONTROL....140
SECTION 12-3. CONCRETE AND REINFORCEMENT....142
12-3.01 CAST-IN-PLACE CONCRETE....142
SECTION 12-4. MASONRY....150
12-4.01 CONCRETE MASONRY UNITS....150
SECTION 12-5. METALS....154
12-5.01 STRUCTURAL STEEL FOR BUILDINGS....154
12-5.02 METAL DECK....159
12-5.03 COLD FORMED METAL FRAMING....161
12-5.04 BUILDING MISCELLANEOUS METAL....164
SECTION 12-6. WOOD AND PLASTICS....166
12-6.01 ROUGH CARPENTRY....166
12-6.02 FINISH CARPENTRY....168
12-6.03 CABINETS....170
SECTION 12-7. THERMAL AND MOISTURE PROTECTION....173
12-7.01 WATER REPELLENT SEALANT....173
12-7.02 CORRUGATED ALUMINUM SIDING....174
12-7.03 METAL ROOFING....176
12-7.04 SHEET METAL FLASHING....180
12-7.05 ROOF SPECIALTIES....182
12-7.06 JOINT SEALANT....183
12-7.07 SEALANTS AND CAULKING....184
SECTION 12-8. DOORS AND WINDOWS....186
12-8.01 HINGED DOORS....186
12-8.02 PRESSED METAL FRAMED WINDOWS....187
12-8.03 FINISH HARDWARE....187
12-8.04 GLAZING....193
SECTION 12-9. FINISHES....195
12-9.01 PORTLAND CEMENT PLASTER....195
12-9.02 GYPSUM WALLBOARD....196
12-9.03 CERAMIC TILE....198
12-9.04 RESILIENT BASE....205
12-9.05 VINYL COMPOSITION TILE....205
12-9.06 RESILIENT SHEET FLOORING....206
12-9.07 PAINTING....208
12-9.08 FIBERGLASS REINFORCED PLASTIC PANELS....213
SECTION 12-10. SPECIALTIES....214
12-10.01 TACKBOARDS....214
12-10.02 MARKER BOARDS....214
12-10.03 METAL TOILET PARTITIONS....215
12-10.04 LOUVERS....216
12-10.05 INFORMATION DISPLAY CASES....217
12-10.06 SIGNS....218
12-10.07 WARDROBE LOCKERS....219
12-10.08 FIRE EXTINGUISHERS....220
12-10.09 FREE STANDING STEEL SHELVING....221

12-10.10 TELEPHONE ENCLOSURES ..... 222
12-10.11 TOILET ROOM ACCESSORIES ..... 223
SECTION 12-11. (BLANK) ..... 224
SECTION 12-12. FURNISHINGS ..... 224
12-12.01 HORIZONTAL BLINDS ..... 224
SECTION 12-13. (BLANK) ..... 225
SECTION 12-14. (BLANK) ..... 225
SECTION 12-15. MECHANICAL ..... 225
12-15.01 MECHANICAL WORK ..... 225
12-15.02 PIPE, FITTINGS, VALVES AND FIRE PROTECTION SYSTEM ..... 226
12-15.03 MECHANICAL INSULATION ..... 237
12-15.04 PLUMBING FIXTURES ..... 239
12-15.05 HEATING, VENTILATING AND AIR CONDITIONING EQUIPMENT AND SYSTEMS ..... 244
SECTION 12-16. ELECTRICAL ..... 246
12-16.01 ELECTRICAL WORK ..... 246
12-16.02 BASIC MATERIALS AND METHODS ..... 247
12-16.03 SERVICE AND DISTRIBUTION ..... 255
12-16.04 ELECTRICAL EQUIPMENT ..... 256
12-16.05 LIGHTING ..... 258
12-16.06 CLOSED CIRCUIT TELEVISION SYSTEM (CCTV) ..... 260
AMENDMENTS TO THE STANDARD SPECIFICATIONS ..... 263

# STANDARD PLANS LIST

The Standard Plan sheets applicable to this contract include, but are not limited to, those indicated below. Applicable Revised Standard Plans (RSP) and New Standard Plans (NSP) indicated below are included in the project plans as Standard Plan sheets.

| | |
|---|---|
| A10A | Acronyms and Abbreviations (Sheet 1 of 2) |
| A10B | Acronyms and Abbreviations (Sheet 2 of 2) |
| A10C | Symbols (Sheet 1 of 2) |
| A10D | Symbols (Sheet 2 of 2) |
| A20A | Pavement Markers and Traffic Lines, Typical Details |
| A24A | Pavement Markings – Arrows |
| A24B | Pavement Markings – Arrows |
| A24C | Pavement Markings – Symbols and Numerals |
| A24E | Pavement Markings – Words and Crosswalks |
| A62A | Excavation and Backfill – Miscellaneous Details |
| A62F | Excavation and Backfill – Metal and Plastic Culverts |
| A85 | Chain Link Fence |
| RSP A87A | Curbs and Driveways |
| RSP A88A | Curb Ramp Details |
| A90A | Accessible Parking – Off-Street |
| D73 | Drainage Inlets |
| D75C | Pipe Inlets – Ladder and Trash Rack Details |
| RSP D77A | Grate Details |
| D88 | Construction Loads on Culverts |
| D99C | Edge Drain Cleanout and Vent Details |
| D102 | Underdrains |
| H1 | Planting and Irrigation – Abbreviations |
| RSP H2 | Planting and Irrigation – Symbols |
| H3 | Planting and Irrigation Details |
| H4 | Planting and Irrigation Details |
| H5 | Planting and Irrigation Details |
| H6 | Planting and Irrigation Details |
| H7 | Planting and Irrigation Details |
| H8 | Planting and Irrigation Details |
| T1A | Temporary Crash Cushion, Sand Filled (Unidirectional) |
| T1B | Temporary Crash Cushion, Sand Filled (Bidirectional) |
| T2 | Temporary Crash Cushion, Sand Filled (Shoulder Installations) |
| T3 | Temporary Railing (Type K) |
| RSP T7 | Construction Project Funding Identification Signs |
| T10 | Traffic Control System for Lane Closure On Freeways and Expressways |
| T14 | Traffic Control System for Ramp Closure |
| T51 | Temporary Water Pollution Control Details (Temporary Silt Fence) |
| T58 | Temporary Water Pollution Control Details (Temporary Construction Entrance) |
| T59 | Temporary Water Pollution Control Details (Temporary Concrete Washout Facility) |
| RS1 | Roadside Signs, Typical Installation Details No. 1 |
| RS2 | Roadside Signs – Wood Post, Typical Installation Details No. 2 |
| RS3 | Roadside Signs – Laminated Wood Box Post Typical Installation Details No. 3 |
| RS4 | Roadside Signs, Typical Installation Details No. 4 |
| S93 | Framing Details for Framed Single Sheet Aluminum Signs, Rectangular Shape |
| S94 | Roadside Framed Single Sheet Aluminum Signs, Rectangular Shape |
| S95 | Roadside Single Sheet Aluminum Signs, Diamond Shape |

# NOTICE TO BIDDERS

Bids open Tuesday, July 7, 2009
Dated May 26, 2009
General work description: Replace Safety Roadside Rest Area

The Department will receive sealed bids for BUILDING CONSTRUCTION ADJACENT TO STATE HIGHWAY IN SAN MATEO COUNTY NEAR HILLSBOROUGH AT CRYSTAL SPRINGS SAFETY ROADSIDE REST AREA.

District-County-Route-Post Mile: 04-SM-280-13.3/13.6

Contract No. 04-0A9204

The Contractor must have either a Class A license or Class B license or a combination of Class C licenses which constitutes a majority of the work.

The UDBE Contract goal is 5 percent.

Federal-aid project no.:
ACIM-280-1(117)E

Bids must be on a unit price basis.
Complete the work, including plant establishment work, within 500 working days.
The estimated cost of the project is $4,080,000.
No prebid meeting is scheduled for this project.

The Department will receive bids until 2:00 p.m. on the bid open date at 1120 N Street, Room 0200, MS 26, Sacramento, CA 95814. Bids received after this time will not be accepted.

The Department will open and publicly read the bids at the above location immediately after the specified closing time.

District office addresses are provided in the Standard Specifications.

Bidders' inquiries may be presented to the Department by following the instructions at:
http://www.dot.ca.gov/hq/esc/oe/project_status/bid_inq.html

The Department posts responses to the questions at the District Web sites.
Questions about alleged patent ambiguity of the plans, specifications, or estimate must be asked before bid opening. After bid opening, such questions will not be treated as bid protests.

Submit your bid with bidder's security equal to at least 10 percent of the bid.

Prevailing wages are required on this Contract. The Director of the California Department of Industrial Relations determines the general prevailing wage rates. Obtain the wage rates at the DIR Web site, http://www.dir.ca.gov, or from the Department's Labor Compliance Office of the district in which the work is located.

The federal minimum wage rates for this Contract as determined by the United States Secretary of Labor are available at http://www.dot.ca.gov/hq/esc/oe/federal-wages.

If the minimum wage rates as determined by the United States Secretary of Labor differs from the general prevailing wage rates determined by the Director of the California Department of Industrial Relations for similar classifications of labor, the Contractor and subcontractors must not pay less than the higher wage rate. The Department does not accept lower State wage rates not specifically included in the Federal minimum wage determinations. This includes helper, or other classifications based on hours of experience, or any other classification not appearing in the Federal wage determinations. Where Federal wage determinations do not contain the State wage rate determination otherwise available for use by the Contractor and subcontractors, the Contractor and subcontractors must not pay less than the Federal minimum wage rate that most closely approximates the duties of the employees in question.

DEPARTMENT OF TRANSPORTATION

MAG

## COPY OF BID ITEM LIST

| Item No. | Item Code | Item Description | Unit of Measure | Estimated Quantity |
|---|---|---|---|---|
| 1 | 070012 | PROGRESS SCHEDULE (CRITICAL PATH METHOD) | LS | LUMP SUM |
| 2 | 070013 | SMALL BUSINESS UTILIZATION REPORT | EA | 6 |
| 3 | 071321 | TEMPORARY FENCE (TYPE CL-6) | LF | 40 |
| 4 | 071325 | TEMPORARY FENCE (TYPE ESA) | LF | 300 |
| 5 | 014526 | 12" TEMPORARY GATE (TYPE CL-6) | EA | 2 |
| 6 | 074016 | CONSTRUCTION SITE MANAGEMENT | LS | LUMP SUM |
| 7 | 074019 | PREPARE STORM WATER POLLUTION PREVENTION PLAN | LS | LUMP SUM |
| 8 | 074029 | TEMPORARY SILT FENCE | LF | 200 |
| 9 | 074032 | TEMPORARY CONCRETE WASHOUT FACILITY | EA | 2 |
| 10 | 074033 | TEMPORARY CONSTRUCTION ENTRANCE | EA | 1 |
| 11 | 074038 | TEMPORARY DRAINAGE INLET PROTECTION | EA | 5 |
| 12 | 074041 | STREET SWEEPING | LS | LUMP SUM |
| 13 | 120090 | CONSTRUCTION AREA SIGNS | LS | LUMP SUM |
| 14 | 120100 | TRAFFIC CONTROL SYSTEM | LS | LUMP SUM |
| 15 | 120120 | TYPE III BARRICADE | EA | 5 |
| 16 | 120165 | CHANNELIZER (SURFACE MOUNTED) | EA | 18 |
| 17 | 128650 | PORTABLE CHANGEABLE MESSAGE SIGN | EA | 1 |
| 18 | 014527 | ABANDON TELEPHONE CABLE | LF | 410 |
| 19 | 014528 | ABANDON WATER PIPELINE | LF | 620 |
| 20 | 014529 | ABANDON ELECTRIC CABLE | LF | 410 |

| Item No. | Item Code | Item Description | Unit of Measure | Estimated Quantity |
|---|---|---|---|---|
| 21 | 014530 | ABANDON SEWER PIPELINE | LF | 590 |
| 22 | 150608 | REMOVE CHAIN LINK FENCE | LF | 310 |
| 23 | 150620 | REMOVE GATE | EA | 1 |
| 24 | 150711 | REMOVE PAINTED TRAFFIC STRIPE | LF | 1,800 |
| 25 | 150712 | REMOVE PAINTED PAVEMENT MARKING | SQFT | 350 |
| 26 | 150744 | REMOVE ROADSIDE SIGN (WOOD POST) | EA | 2 |
| 27 | 150745 | REMOVE ROADSIDE SIGN (METAL POST) | EA | 1 |
| 28 | 150747 | REMOVE ROADSIDE SIGN (STRAP AND SADDLE BRACKET METHOD) | EA | 1 |
| 29 | 150826 | REMOVE MANHOLE | EA | 1 |
| 30 | 150829 | REMOVE RETAINING WALL | LF | 250 |
| 31 | 150841 | REMOVE SEWER PIPE | LF | 45 |
| 32 | 014531 | SALVAGE MANHOLE FRAME AND COVER | EA | 1 |
| 33 | 014532 | REMOVE AND SALVAGE SITE FURNISHINGS | LS | LUMP SUM |
| 34 | 014533 | RELOCATE BLUE STAR MEMORIAL | LS | LUMP SUM |
| 35 | 152390 | RELOCATE ROADSIDE SIGN | EA | 4 |
| 36 | 153103 | COLD PLANE ASPHALT CONCRETE PAVEMENT | SQYD | 250 |
| 37 | 153210 | REMOVE CONCRETE | CY | 120 |
| 38 | 160101 | CLEARING AND GRUBBING | LS | LUMP SUM |
| 39 | 190109 | ROADWAY EXCAVATION (NATURALLY OCCURRING ASBESTOS) | CY | 250 |
| 40 | 190115 | ASBESTOS COMPLIANCE PLAN (NATURALLY OCCURING ASBESTOS) | LS | LUMP SUM |

| Item No. | Item Code | Item Description | Unit of Measure | Estimated Quantity |
|---|---|---|---|---|
| 41 | 190116 | DUST CONTROL PLAN (NATURALLY OCCURRING ASBESTOS) | LS | LUMP SUM |
| 42 | 192009 | STRUCTURE EXCAVATION (NATURALLY OCCURRING ASBESTOS) | CY | 435 |
| 43 | 193013 | STRUCTURE BACKFILL (RETAINING WALL) | CY | 275 |
| 44 | 194001 | DITCH EXCAVATION | CY | 7 |
| 45 | 198001 | IMPORTED BORROW | CY | 42 |
| 46 | 200001 | HIGHWAY PLANTING | LS | LUMP SUM |
| 47 | 200101 | IMPORTED TOPSOIL | CY | 300 |
| 48 | 203016 | EROSION CONTROL (TYPE D) | SQYD | 9,700 |
| 49 | 204096 | MAINTAIN EXISTING PLANTED AREAS | LS | LUMP SUM |
| 50 | 204099 | PLANT ESTABLISHMENT WORK | LS | LUMP SUM |
| 51 | 206401 | MAINTAIN EXISTING IRRIGATION FACILITIES | LS | LUMP SUM |
| 52 | 208000 | IRRIGATION SYSTEM | LS | LUMP SUM |
| 53 | 208310 | IRRIGATION SLEEVE | LF | 20 |
| 54 | 014534 | 4" CORRUGATED HIGH DENSITY POLYETHYLENE PIPE | LF | 31 |
| 55 | 014535 | 6" CORRUGATED HIGH DENSITY POLYETHYLENE PIPE | LF | 57 |
| 56 | 260301 | CLASS 3 AGGREGATE BASE | CY | 110 |
| 57 | 390095 | REPLACE ASPHALT CONCRETE SURFACING | CY | 35 |
| 58 | 390132 | HOT MIX ASPHALT (TYPE A) | TON | 110 |
| 59 | 397005 | TACK COAT | TON | 61 |
| 60 | 510502 | MINOR CONCRETE (MINOR STRUCTURE) | CY | 36 |

| Item No. | Item Code | Item Description | Unit of Measure | Estimated Quantity |
|---|---|---|---|---|
| 61 | 014536 | PORTLAND CEMENT CONCRETE SPLASH PAD | CY | 1 |
| 62 (F) | 520101 | BAR REINFORCING STEEL | LB | 8,000 |
| 63 | 560248 | FURNISH SINGLE SHEET ALUMINUM SIGN (0.063"-UNFRAMED) | SQFT | 51 |
| 64 | 560249 | FURNISH SINGLE SHEET ALUMINUM SIGN (0.080"-UNFRAMED) | SQFT | 23 |
| 65 | 566011 | ROADSIDE SIGN - ONE POST | EA | 13 |
| 66 | 597401 | PAINT CURB (2-COAT) | SQFT | 250 |
| 67 | 014537 | 4" POLYVINYL CHLORIDE PIPE (PLANTER DRAIN) | LF | 60 |
| 68 | 014538 | PARKING AREA SEAL COAT | TON | 63 |
| 69 | 014539 | PLANTER DRAIN | EA | 7 |
| 70 | 680902 | 6" PERFORATED PLASTIC PIPE UNDERDRAIN | LF | 280 |
| 71 | 014540 | 6" PLASTIC PIPE (UNDERDRAIN AND TERMINAL RISER) | LF | 50 |
| 72 | 014541 | 6" RISER SAFETY CAGE | EA | 2 |
| 73 | 014542 | 4" WELDED STEEL PIPE | LF | 210 |
| 74 | 014543 | 6" WELDED STEEL PIPE | LF | 140 |
| 75 | 719110 | SEWER TERMINAL CLEANOUT | EA | 1 |
| 76 | 719190 | SEWER MANHOLE FRAME AND COVER | EA | 2 |
| 77 | 719200 | SEWER MANHOLE | EA | 2 |
| 78 | 014544 | LATERAL CONNECTION SEWER | EA | 1 |
| 79 | 727901 | MINOR CONCRETE (DITCH LINING) | CY | 8 |
| 80 | 731502 | MINOR CONCRETE (MISCELLANEOUS CONSTRUCTION) | CY | 160 |

| Item No. | Item Code | Item Description | Unit of Measure | Estimated Quantity |
|---|---|---|---|---|
| 81 | 731530 | MINOR CONCRETE (TEXTURED PAVING) | SQFT | 520 |
| 82 | 014545 | STONE PAVER BAND | SQFT | 45 |
| 83 (F) | 750001 | MISCELLANEOUS IRON AND STEEL | LB | 253 |
| 84 | 014546 | CHAIN LINK FENCE GATE (3 FEET) (VINYL CLAD) | EA | 1 |
| 85 | 014547 | CHAIN LINK FENCE GATE (12 FEET) (VINYL CLAD) | EA | 1 |
| 86 | 800361 | CHAIN LINK FENCE (TYPE CL-6, VINYL-CLAD) | LF | 310 |
| 87 | 014548 | 4' DECORATIVE METAL GATE | LF | 8 |
| 88 | 014549 | DECORATIVE METAL FENCE | LF | 2 |
| 89 | 014550 | 6' DECORATIVE METAL GATE | LF | 4 |
| 90 | 840504 | 4" THERMOPLASTIC TRAFFIC STRIPE | LF | 1,930 |
| 91 | 840515 | THERMOPLASTIC PAVEMENT MARKING | SQFT | 360 |
| 92 | 842000 | PARKING BUMPER (PRECAST CONCRETE) | EA | 34 |
| 93 | 014551 | 2" HIGH DENSITY POLYETHYLENE PIPE (HORIZONTAL DIRECTIONAL BORING) | LF | 420 |
| 94 | 014552 | 3" HIGH DENSITY POLYETHYLENE PIPE (HORIZONTAL DIRECTIONAL BORING) | LF | 700 |
| 95 | 014553 | 4" HIGH DENSITY POLYETHYLENE PIPE (HORIZONTAL DIRECTIONAL BORING) | LF | 420 |
| 96 | 014554 | 6" HIGH DENSITY POLYETHYLENE PIPE (HORIZONTAL DIRECTIONAL BORING) | LF | 710 |
| 97 | 014555 | FLAGPOLE | EA | 1 |
| 98 | 014556 | PLACE SITE FURNISHINGS | LS | LUMP SUM |
| 99 | 014557 | PET WASTE BAG DISPENSER | EA | 1 |
| 100 | 994650 | BUILDING WORK | LS | LUMP SUM |

# SPECIAL PROVISIONS

## SECTION 1. (BLANK)

## SECTION 2. BIDDING

### 2-1.01 DISADVANTAGED BUSINESS ENTERPRISES

The second paragraph in Section 2-1.05, "Disadvantaged Business Enterprises," of the Standard Specifications does not apply.

Take necessary and reasonable steps to ensure that DBEs have opportunity to participate in the contract (49 CFR 26).

To ensure there is equal participation of the DBE groups specified in 49 CFR 26.5, the Department specifies a goal for Underutilized Disadvantaged Business Enterprises (UDBEs). UDBE is a firm that meets the definition of DBE and is a member of one of the following groups:

1. Black Americans
2. Native Americans
3. Asian-Pacific Americans
4. Women

References to DBEs include UDBEs, but references to UDBEs do not include all DBEs.

Make work available to UDBEs and select work parts consistent with available UDBE subcontractors and suppliers.

Meet the UDBE goal shown in the Notice to Bidders or demonstrate that you made adequate good faith efforts to meet this goal.

It is your responsibility to verify that the UDBE firm is certified as DBE at date of bid opening. For a list of DBEs certified by the California Unified Certification Program, go to:

http://www.dot.ca.gov/hq/bep/find_certified.htm

Only UDBE participation will count towards the UDBE goal. DBE participation will count towards the Department's federally mandated statewide overall DBE goal.

Credit for materials or supplies you purchase from UDBEs counts towards the goal in the following manner:

1. 100 percent counts if the materials or supplies are obtained from a UDBE manufacturer
2. 60 percent counts if the materials or supplies are obtained from a UDBE regular dealer
3. Only fees, commissions, and charges for assistance in the procurement and delivery of materials or supplies counts if obtained from a UDBE that is neither a manufacturer or regular dealer. 49 CFR 26.55 defines "manufacturer" and "regular dealer."

You receive credit towards the goal if you employ a UDBE trucking company that performs a commercially useful function as defined in 49 CFR 26.55.

#### UDBE Commitment Submittal

Submit UDBE information on the Caltrans Bidder - UDBE - Commitment form included in the Bid book. If the form is not submitted with the bid, remove the forms from the Bid book before submitting your bid.

If the UDBE Commitment form is not submitted with the bid, the apparent low bidder, the 2nd low bidder, and the 3rd low bidder must complete and submit the UDBE Commitment form to Office Engineer. UDBE Commitment form must be received by the Department no later than 4:00 p.m. on the 4th business day after bid opening.

Other bidders do not need to submit the UDBE Commitment form unless the Department requests it. If the Department requests you to submit a UDBE Commitment form, submit the completed form within 4 business days of the request.

Submit written confirmation from each UDBE stating that it is participating in the contract. Include confirmation with the UDBE Commitment form. A copy of a UDBE's quote will serve as written confirmation that the UDBE is participating in the contract.

If you do not submit the UDBE Commitment form within the specified time, the Department finds your bid nonresponsive.

**Good Faith Efforts Submittal**

If you have not met the UDBE goal, complete and submit the Good Faith Efforts Documentation form with the bid showing that you made adequate good faith efforts to meet the goal. Only good faith efforts directed towards obtaining participation by UDBEs will be considered. If good faith efforts documentation is not submitted with the bid, it must be received by the Department no later than 4:00 p.m. on the 4th business day after bid opening.

If your UDBE Commitment form shows that you have met the UDBE goal or if you are required to submit the UDBE Commitment form, you must also submit good faith efforts documentation within the specified time to protect your eligibility for award of the contract in the event the Department finds that the UDBE goal has not been met.

Good faith efforts documentation must include the following information and supporting documents, as necessary:

1. Items of work you have made available to UDBE firms. Identify those items of work you might otherwise perform with its own forces and those items that have been broken down into economically feasible units to facilitate UDBE participation. For each item listed, show the dollar value and percentage of the total contract. It is your responsibility to demonstrate that sufficient work to meet the goal was made available to UDBE firms.
2. Names of certified UDBEs and dates on which they were solicited to bid on the project. Include the items of work offered. Describe the methods used for following up initial solicitations to determine with certainty if the UDBEs were interested, and the dates of the follow-up. Attach supporting documents such as copies of letters, memos, facsimiles sent, telephone logs, telephone billing statements, and other evidence of solicitation. You are reminded to solicit certified UDBEs through all reasonable and available means and provide sufficient time to allow UDBEs to respond.
3. Name of selected firm and its status as a UDBE for each item of work made available. Include name, address, and telephone number of each UDBE that provided a quote and their price quote. If the firm selected for the item is not a UDBE, provide the reasons for the selection.
4. Name and date of each publication in which you requested UDBE participation for the project. Attach copies of the published advertisements.
5. Names of agencies and dates on which they were contacted to provide assistance in contacting, recruiting, and using UDBE firms. If the agencies were contacted in writing, provide copies of supporting documents.
6. List of efforts made to provide interested UDBEs with adequate information about the plans, specifications, and requirements of the contract to assist them in responding to a solicitation. If you have provided information, identify the name of the UDBE assisted, the nature of the information provided, and date of contact. Provide copies of supporting documents, as appropriate.
7. List of efforts made to assist interested UDBEs in obtaining bonding, lines of credit, insurance, necessary equipment, supplies, and materials, excluding supplies and equipment that the UDBE subcontractor purchases or leases from the prime contractor or its affiliate. If such assistance is provided by you, identify the name of the UDBE assisted, nature of the assistance offered, and date. Provide copies of supporting documents, as appropriate.
8. Any additional data to support demonstration of good faith efforts.

## SECTION 3. CONTRACT AWARD AND EXECUTION

### 3-1.01 CONTRACT AWARD

If the Department awards the Contract, the award is made to the lowest responsible bidder within 60 days.

## SECTION 4. BEGINNING OF WORK, TIME OF COMPLETION AND LIQUIDATED DAMAGES

Complete the work, except plant establishment work, within 250 working days starting on the 15th day after contract approval or on the day you start work at the job site, whichever occurs first.

Complete the work, including plant establishment work, within 500 working days starting on the 15th day after contract approval or on the day you start work at the job site, whichever occurs first.

## SECTION 5. GENERAL

### 5-1.01 PERFORMANCE OF UDBEs

UDBEs must perform work or supply materials as listed in the Caltrans Bidder - UDBE - Commitment form specified under Section 2, "Bidding," of these special provisions. Do not terminate a UDBE listed subcontractor for convenience and perform the work with your own forces or obtain materials from other sources without prior written authorization from the Department.

The Department grants authorization to use other forces or sources of materials for requests that show any of the following justifications:

1. Listed UDBE fails or refuses to execute a written contract based on plans and specifications for the project.
2. You stipulated that a bond is a condition of executing the subcontract and the listed UDBE fails to meet your bond requirements.
3. Work requires a contractors license and listed UDBE does not have a valid license under Contractors License Law.
4. Listed UDBE fails or refuses to perform the work or furnish the listed materials.
5. Listed UDBE's work is unsatisfactory and not in compliance with the contract.
6. Listed UDBE delays or disrupts the progress of the work.
7. Listed UDBE becomes bankrupt or insolvent.

If a listed UDBE subcontractor is terminated, you must make good faith efforts to find another UDBE subcontractor to substitute for the original UDBE. The substitute UDBE must perform at least the same amount of work as the original UDBE under the contract to the extent needed to meet the UDBE goal.

The substitute UDBE must be certified as a DBE at the time of request for substitution.

The Department does not pay for work or material unless it is performed or supplied by the listed UDBE or an authorized substitute.

**5-1.02 TRAINING**

For the Federal training program, the number of trainees or apprentices is 7.

**5-1.03 RETENTION EXCLUSION**

The Department does not retain moneys from progress payments due to the Contractor for work performed (Pub Cont Code § 7202). The 3rd paragraph in Section 9-1.06, "Partial Payments," of the Standard Specifications does not apply.

**5-1.04 COMPENSATION ADJUSTMENTS FOR PRICE INDEX FLUCTUATIONS**

The provisions of this section shall apply only to the following contract items:

| ITEM CODE | ITEM |
|---|---|
| 390132 | HOT MIX ASPHALT (TYPE A) |
| 397005 | TACK COAT |

The compensation payable for asphalt binder used in hot mix asphalt and tack coat will be increased or decreased in conformance with the provisions of this section for paving asphalt price fluctuations exceeding 5 percent (Iu/Ib is greater than 1.05 or less than 0.95) which occur during performance of the work.

The quantity of asphalt binder used in tack coat will be determined by multiplying the item quantity for tack coat included in a monthly estimate by the minimum percent residue specified in Section 94, "Asphaltic Emulsions," of the Standard Specifications. The asphaltic emulsion minimum percent residue will be based on the type of emulsion used by the Contractor.

At the Contractor's option, the Contractor may provide actual daily test results for asphalt binder residue for the tack coat used. Test results provided by the Contractor shall be from an independent testing laboratory that participates in the AASHTO Proficiency Sample Program. The Contractor shall take samples of asphaltic emulsion from the distributor truck at mid-load from a sampling tap or thief. Two separate 1/2 gallon samples shall be taken in the presence of the Engineer. The Contractor shall provide one sample to the Contractor's independent testing laboratory within 24 hours of sampling. The second sample shall be given to the Engineer. The test results from the Contractor's independent testing laboratory shall be delivered to the Engineer within 10 days from sample date.

The adjustment in compensation will be determined in conformance with the following formulae when the item of hot mix asphalt or tack coat or both are included in a monthly estimate:

A. Total monthly adjustment = AQ
B. For an increase in paving asphalt price index exceeding 5 percent:

$$A = 0.90\ (Iu/Ib - 1.05)\ Ib$$

C. For a decrease in paving asphalt price index exceeding 5 percent:

$$A = 0.90 (Iu/Ib - 0.95) Ib$$

D. Where:

A = Adjustment in dollars per ton of paving asphalt used to produce hot mix asphalt and asphaltic emulsion residue used as tack coat rounded to the nearest $0.01.
Iu = The California Statewide Paving Asphalt Price Index which is in effect on the first business day of the month within the pay period in which the quantity subject to adjustment was included in the estimate.
Ib = The California Statewide Paving Asphalt Price Index for the month in which the bid opening for the project occurred.
Q = Quantity in tons of asphalt binder that was used in producing the quantity of hot mix asphalt shown under "This Estimate" on the monthly estimate using the amount of asphalt binder determined by the Engineer plus the quantity in tons of asphalt binder that would have been used as residue in the tack coat shown under "This Estimate" on the monthly estimate.

The adjustment in compensation will also be subject to the following:

A. The compensation adjustments provided herein will be shown separately on payment estimates. The Contractor shall be liable to the State for decreased compensation adjustments and the Department may deduct the amount thereof from moneys due or that may become due the Contractor.
B. Compensation adjustments made under this section will be taken into account in making adjustments in conformance with the provisions in Section 4-1.03B, "Increased or Decreased Quantities," of the Standard Specifications.
C. In the event of an overrun of contract time, adjustment in compensation for asphalt binder included in estimates during the overrun period will be determined using the California Statewide Paving Asphalt Price Index in effect on the first business day of the month within the pay period in which the overrun began.

The California Statewide Paving Asphalt Price Index is determined each month on the first business day of the month by the Department using the median of posted prices in effect as posted by Chevron, ExxonMobil, and Union 76 for the Buena Vista, Huntington Beach, and Midway Sunset fields.

In the event that the companies discontinue posting their prices for a field, the Department will determine an index from the remaining posted prices. The Department reserves the right to include in the index determination the posted prices of additional fields.

The California Statewide Paving Asphalt Price Index is available on the Division of Engineering Services website at:

http://www.dot.ca.gov/hq/esc/oe/asphalt_index/astable.html

**5-1.05 COMPENSATION ADJUSTMENTS FOR PRICE INDEX FLUCTUATIONS**

The provisions of this section shall apply only to the following contract item:

| ITEM CODE | ITEM |
|---|---|
| 390095 | REPLACE ASPHALT CONCRETE SURFACING |

The compensation payable for asphalt binder used in hot mix asphalt will be increased or decreased in conformance with the provisions of this section for paving asphalt price fluctuations exceeding 5 percent (Iu/Ib is greater than 1.05 or less than 0.95) which occur during performance of the work.

The Contractor shall provide a weight slip, certified by a weighmaster, for each load of hot mix asphalt. The scales used to determine the weight will be considered "commercial devices" and shall be sealed by the Division of Measurement Standards or its authorized representative as often as the Engineer may deem necessary. The scales shall be operated by a weighmaster licensed in conformance with the requirements in the California Business and Professional Code, Division 5, Chapter 7.

The quantity of asphalt binder used in hot mix asphalt will be calculated by the Engineer using the percentage of asphalt binder determined by the Engineer multiplied by the tons of hot mix asphalt shown on certified load weight slips. Quantities of hot mix asphalt wasted or disposed of will not be included in any adjustment of compensation.

The adjustment in compensation will be determined in conformance with the following formulae when the item of replace asphalt concrete surfacing is included in a monthly estimate:

A. Total monthly adjustment = AQ
B. For an increase in paving asphalt price index exceeding 5 percent:

$$A = 0.90 (Iu/Ib - 1.05) Ib$$

C. For a decrease in paving asphalt price index exceeding 5 percent:

$$A = 0.90 (Iu/Ib - 0.95) Ib$$

D. Where:

A = Adjustment in dollars per ton of asphalt binder used to produce hot mix asphalt rounded to the nearest $0.01.
Iu = The California Statewide Paving Asphalt Price Index which is in effect on the first business day of the month within the pay period in which the quantity subject to adjustment was included in the estimate.
Ib = The California Statewide Paving Asphalt Price Index for the month in which the bid opening for the project occurred.
Q = Quantity in tons of asphalt binder that was used in producing the quantity of hot mix asphalt used in replace asphalt concrete surfacing shown under "This Estimate" on the monthly estimate using the amount of asphalt determined by the Engineer.

The adjustment in compensation will also be subject to the following:

A. The compensation adjustments provided herein will be shown separately on payment estimates. The Contractor shall be liable to the State for decreased compensation adjustments and the Department may deduct the amount thereof from moneys due or that may become due the Contractor.
B. Compensation adjustments made under this section will be taken into account in making adjustments in conformance with the provisions in Section 4-1.03B, "Increased or Decreased Quantities," of the Standard Specifications.
C. In the event of an overrun of contract time, adjustment in compensation for asphalt binder included in estimates during the overrun period will be determined using the California Statewide Paving Asphalt Price Index in effect on the first business day of the month within the pay period in which the overrun began.

The California Statewide Paving Asphalt Price Index is determined each month on the first business day of the month by the Department using the median of posted prices in effect as posted by Chevron, ExxonMobil, and Union 76 for the Buena Vista, Huntington Beach, and Midway Sunset fields.

In the event that the companies discontinue posting their prices for a field, the Department will determine an index from the remaining posted prices. The Department reserves the right to include in the index determination the posted prices of additional fields.

The California Statewide Paving Asphalt Price Index is available on the Division of Engineering Services website at:

http://www.dot.ca.gov/hq/esc/oe/asphalt_index/astable.html

**5-1.06 AREAS FOR CONTRACTOR'S USE**

Attention is directed to the provisions in Section 7-1.19, "Rights in Land and Improvements," of the Standard Specifications and these special provisions.

The highway right of way shall be used only for purposes that are necessary to perform the required work. The Contractor shall not occupy the right of way, or allow others to occupy the right of way, for purposes which are not necessary to perform the required work.

No State-owned parcels adjacent to the right of way are available for the exclusive use of the Contractor within the contract limits. The Contractor shall secure, at the Contractor's own expense, areas required for plant sites, storage of equipment or materials, or for other purposes.

No area is available within the contract limits for the exclusive use of the Contractor. However, temporary storage of equipment and materials on State property may be arranged with the Engineer, subject to the prior demands of State maintenance forces and to other contract requirements. Use of the Contractor's work areas and other State-owned property shall be at the Contractor's own risk, and the State shall not be held liable for damage to or loss of materials or equipment located within such areas.

## 5-1.07 PAYMENTS

Attention is directed to Sections 9-1.06, "Partial Payments," and 9-1.07, "Payment After Acceptance," of the Standard Specifications and these special provisions.

For the purpose of making partial payments pursuant to Section 9-1.06, "Partial Payments," of the Standard Specifications, the amount set forth for the contract items of work hereinafter listed shall be deemed to be the maximum value of the contract item of work which will be recognized for progress payment purposes:

| | | |
|---|---|---|
| A. | Clearing and Grubbing | $33,000 |
| B. | Progress Schedule (Critical Path Method) | $ 2,750 |

After acceptance of the contract pursuant to the provisions in Section 7-1.17, "Acceptance of Contract," of the Standard Specifications, the amount, if any, payable for a contract item of work in excess of the maximum value for progress payment purposes hereinabove listed for the item, will be included for payment in the first estimate made after acceptance of the contract.

In determining the partial payments to be made to the Contractor, only the following listed materials will be considered for inclusion in the payment as materials furnished but not incorporated in the work:

A. Irrigation controllers
B. Pipe (Irrigation Systems)
C. Bar reinforcing steel
D. Miscellaneous iron and steel
E. Fences and gates
F. Sewer pipe and appurtenances

## 5-1.08 PROJECT INFORMATION

The information in this section has been compiled specifically for this project and is made available for bidders and Contractors. Other information referenced in the Standard Specifications and these special provisions do not appear in this section. The information is subject to the conditions and limitations set forth in Section 2-1.03, "Examination of Plans, Specifications, Contract, and Site of Work," and Section 6-2, "Local Materials," of the Standard Specifications. Bidders and Contractors shall be responsible for knowing the procedures for obtaining information.

Information attached to the project plans is as follows:

A. Log of Test Borings.

Information included in the Information Handout provided to bidders and Contractors is as follows:

1. Foundation Investigation Report, Feb. 14, 2006
2. Asbestos and Lead-based Paint/Material Demolition Survey, by CSC of Pleasanton, CA, March 31, 2005
3. Asbestos & Deteriorated Lead Paint Survey Report, by Geocon, March 2007
4. Retaining wall asbestos report by EMSL, April 27, 2007
5. Site Investigation Report, Crystal Springs Rest Area, Hillsborough, March, 2007
6. Revocable Permit issued by the San Francisco Public Utilities Commission
7. Boring Logs for the area of utility easement

Cross sections are not available for this project.

The District Office in which the work is situated is located at Duty Senior's Office, 111 Grand Ave., Oakland, CA. 94623.

## 5-1.09 SOUND CONTROL REQUIREMENTS

Sound control shall conform to these special provisions.

The noise level from the Contractor's operations, between the hours of 9:00 p.m. and 6:00 a.m., shall not exceed 86 dBa (Lmax) at a distance of 50 feet, except for the following work:

A. Remove concrete.
B. Remove retaining wall.
C. Cold plane AC pavement.

The Contractor shall provide one "Type 1" sound level meter and one acoustic calibrator which will be used by the Department during the life of the contract. The Contractor shall provide training by a person trained in noise monitoring to one Department employee designated by the Engineer. The sound level meter shall be calibrated and certified by the manufacturer or other independent acoustical laboratory prior to delivery to the Department. The Contractor shall provide annual recalibration by the manufacturer or other independent acoustical laboratory. All equipment shall be capable of taking measurements using the A-weighting network and the "slow" response of the sound level meter. The measurement microphone shall be fitted with an appropriate windscreen. All equipment shall be returned to the Contractor at the acceptance of the contract. Equipment damaged by actions of the Department or the public shall be paid for as extra work as provided in Section 4-1.03D for the Standard Specifications.

Each internal combustion engine, used for any purpose on the job or related to the job, shall be equipped with a muffler of a type recommended by the manufacturer. No internal combustion engine shall be operated on the project without the muffler.

The noise level requirement shall apply to the equipment on the job or related to the job, including but not limited to trucks, transit mixers or transient equipment that may or may not be owned by the Contractor. The use of loud sound signals shall be avoided in favor of light warnings except those required by safety laws for the protection of personnel.

Full compensation for conforming to the requirements of this section shall be considered as included in the prices paid for the various contract items of work involved and no additional compensation will be allowed therefor.

### 5-1.10 RELATIONS WITH CALIFORNIA REGIONAL WATER QUALITY CONTROL BOARD

This project lies within the boundaries of the San Francisco Bay Region 2 Regional Water Quality Control Board (RWQCB).

The State Water Resources Control Board (SWRCB) has issued to the Department a permit that governs storm water and non-storm water discharges from the Department's properties, facilities, and activities. The Department's permit is entitled "Order No. 99 - 06 - DWQ, NPDES No. CAS000003, National Pollutant Discharge Elimination System (NPDES) Permit, Statewide Storm Water Permit and Waste Discharge Requirements (WDRs) for the State of California, Department of Transportation (Caltrans)." Copies of the Department's permit are available for review from the SWRCB, Storm Water Permit Unit, 1001 "I" Street, P.O. Box 1977, Sacramento, California 95812-1977, Telephone: (916) 341-5254, and may also be obtained at:

http://www.swrcb.ca.gov/stormwtr/caltrans.html

The Department's permit references and incorporates by reference the current statewide general permit issued by the SWRCB entitled "Order No. 99-08-DWQ, National Pollutant Discharge Elimination System (NPDES) General Permit No. CAS000002, Waste Discharge Requirements (WDRs) for Discharges of Storm Water Runoff Associated with Construction Activity" that regulates discharges of storm water and non-storm water from construction activities disturbing one acre or more of soil in a common plan of development. Sampling and analysis requirements as specified in SWRCB Resolution No. 2001-46 are added to the statewide general permit. Copies of the statewide permit and modifications thereto are available for review from the SWRCB, Storm Water Permit Unit, 1001 "I" Street, P.O. Box 1977, Sacramento, California 95812-1977, Telephone: (916) 341-5254 and may also be obtained at:

http://www.swrcb.ca.gov/stormwtr/construction.html

This project shall conform to the permits and modifications thereto. The Contractor shall maintain copies of the permits at the project site and shall make them available during construction.

The Contractor shall know and comply with provisions of Federal, State, and local regulations and requirements that govern the Contractor's operations and storm water and non-storm water discharges from the project site and areas of disturbance outside the project limits during construction. Attention is directed to Sections 7-1.01, "Laws to be Observed," 7-1.11, "Preservation of Property," and 7-1.12, "Indemnification and Insurance," of the Standard Specifications.

The Contractor shall be responsible for penalties assessed on the Contractor or the Department as a result of the Contractor's failure to comply with the provisions in "Water Pollution Control" of these special provisions or with the applicable provisions of the Federal, State, and local regulations and requirements.

Penalties as used in this section shall include fines, penalties, and damages, whether proposed, assessed, or levied against the Department or the Contractor, including those levied under the Federal Clean Water Act and the State Porter-Cologne Water Quality Control Act, by governmental agencies or as a result of citizen suits. Penalties shall also include payments made or costs incurred in settlement for alleged violations of applicable laws, regulations, or requirements. Costs incurred could include sums spent instead of penalties, in mitigation or to remediate or correct violations.

**WITHHOLDS**

The Department will withhold money due the Contractor, in an amount estimated by the Department, to include the full amount of penalties and mitigation costs proposed, assessed, or levied as a result of the Contractor's violation of the permits, or Federal or State law, regulations, or requirements. Funds will be withheld by the Department until final disposition of these costs has been made. The Contractor shall remain liable for the full amount until the potential liability is finally resolved with the entity seeking the penalties. Instead of the withhold, the Contractor may provide a suitable bond in favor of the Department to cover the highest estimated liability for any disputed penalties proposed as a result of the Contractor's violation of the permits, law, regulations, or requirements.

If a regulatory agency identifies a failure to comply with the permits and modifications thereto, or other Federal, State, or local requirements, the Department will withhold money due the Contractor, subject to the following:

A. The Department will give the Contractor 30 days notice of the Department's intention to withhold funds from payments which may become due to the Contractor before acceptance of the contract. Funds withheld after acceptance of the contract will be made without prior notice to the Contractor.
B. No withholds of additional amounts out of payments will be made if the amount to be withheld does not exceed the amount being withheld from partial payments in accordance with Section 9-1.06, "Partial Payments," of the Standard Specifications.
C. If the Department has withheld funds and it is subsequently determined that the State is not subject to the entire amount of the costs and liabilities assessed or proposed in connection with the matter for which the withhold was made, the Department will return the excess amount withheld to the Contractor in the progress payment following the determination. If the matter is resolved for less than the amount withheld, the Department will pay interest at a rate of 6 percent per year on the excess withhold.

The Contractor shall notify the Engineer immediately upon request from the regulatory agencies to enter, inspect, sample, monitor, or otherwise access the project site or the Contractor's records pertaining to water pollution control work. The Contractor and the Department shall provide copies of correspondence, notices of violation, enforcement actions, or proposed fines by regulatory agencies to the requesting regulatory agency.

## 5-1.11 NATURALLY OCCURRING ASBESTOS

Naturally occurring asbestos (NOA) is present within the project limits. Material containing NOA is material that has an asbestos content of 0.25 percent or greater as defined in California Code of Regulations, Title 17, Section 93105 "Asbestos Airborne Toxic Control Measure for Construction, Grading, Quarrying, and Surface Mining Operations." These provisions are also applicable when work is located in serpentine and ultramafic rock.

Handling, stockpiling, transporting, and disposing of material containing NOA must comply with "Material Containing Naturally Occurring Asbestos" of these special provisions.

Notify the Engineer and the Air Pollution Control District (APCD) at least 15 days before starting work that disturbs material containing NOA. Maintain and make available at the job site a copy of the APCD notification and exemption, if appropriate. Provide the Engineer a copy of the APCD notification and exemption, if approved.

The site investigation report is available as specified in "Project Information" of these special provisions.

After you have completed the handling and placement of material containing NOA in accordance with these special provisions, as certified by the Engineer, you will have no further responsibility for the NOA material in place within the right-of-way. You will not be considered a generator of the hazardous material, and the Department requires no further cleanup, removal, or remedial actions for the material containing NOA will be required within the right-of-way.

Excavate, stockpile, reuse, and dispose of material containing hazardous levels of NOA under the rules and regulations of the following agencies:

1. United States Environmental Protection Agency
2. Department of Toxic Substances Control, Region North
3. California Integrated Waste Management Board
4. California Department of Health Services
5. California Division of Occupational Safety and Health Administration
6. California Air Resources Board
7. San Francisco Bay Area Air Quality District
8. California Department of Motor Vehicles
9. Regional Water Quality Control Board (Region 2), San Francisco Bay Area

Handle and transport material containing hazardous levels of NOA to comply under Federal and State laws and regulations and county and municipal ordinances and regulations. Laws and regulations that govern this work include:

1. California Code of Regulations, Title 8, Section 1529 (Asbestos) and Section 5192 (Hazardous Waste Operations and Emergency Response)
2. California Code of Regulations, Title 17, Section 93105 (Asbestos Airborne Toxic Control Measure for Construction, Grading, Quarrying, and Surface Mining Operations) and Section 93106 (Asbestos Airborne Toxic Control Measure for Surfacing Applications)
3. California Code of Regulations, Title 22, Division 4.5, Chapter 10 (Environmental Health Standards for the Management of Hazardous Waste)
4. Health and Safety Code, Division 20, Chapter 6.5 (Hazardous Waste Control)
5. Code of Federal Regulations, Part 1926, Section 1101, (Asbestos)

### 5-1.12 ENVIRONMENTALLY SENSITIVE AREA

An environmentally sensitive area (ESA) shall consist of an area within and near the limits of construction where access is prohibited or limited for the preservation of archeological site or existing vegetation, or protection of biological habitat as shown on the plans. The Engineer will determine the exact location of the boundaries of the ESA. No work shall be conducted within the ESA.

Attention is directed to Section 7—1.01 "Laws to be Observed," and Section 7—1.04 "Permits and Licenses," of the Standard Specifications regarding State and Federal regulations, permits, or agreements which pertain to an ESA.

Prior to beginning work, the boundaries of the ESA shall be clearly delineated by the placement of temporary fence (Type ESA) in conformance with the provisions in "Temporary Fence (Type ESA)" of these special provisions.

Vehicle access, storage or transport of materials or equipment, or other project related activities are prohibited within the boundaries of the ESA.

The Contractor shall mitigate damage or impacts to the ESA caused by the Contractor's operations, at the Contractor's expense. If the Engineer determines mitigation work will be performed by others, or if mitigation fees are assessed the Department, deductions from moneys due or to become due the Contractor will be made for the mitigation costs.

### 5-1.13 PRESERVATION OF PROPERTY

Attention is directed to Section 7-1.11, "Preservation of Property," of the Standard Specifications and these special provisions.

Existing trees, shrubs and other plants, that are not to be removed as shown on the plans or specified in these special provisions, and are injured or damaged by reason of the Contractor's operations, shall be replaced by the Contractor. The minimum size of tree replacement shall be 24 inch box and the minimum size of shrub replacement shall be 15-gallon. Replacement ground cover plants shall be from flats and shall be planted 12 inches on center. Replacement planting shall conform to the requirements in Section 20-4.07, "Replacement," of the Standard Specifications. The Contractor shall water replacement plants in conformance with the provisions in Section 20-4.06, "Watering," of the Standard Specifications.

Damaged or injured plants shall be removed and disposed of in conformance with the provisions in Section 7-l.13,"Disposal of Material Outside the Highway Right of Way," of the Standard Specifications. At the option of the Contractor, removed trees and shrubs may be reduced to chips. The chipped material shall be spread within the highway right of way at locations designated by the Engineer.

Replacement planting of injured or damaged trees, shrubs, and other plants shall be completed prior to the start of the plant establishment period. Replacement planting shall conform to the provisions in Section 20-4.05, "Planting," of the Standard Specifications.

### 5-1.14 DAMAGE REPAIR

Attention is directed to Section 7-1.16, "Contractor's Responsibility for the Work and Materials," and Section 7-1.165, "Damage by Storm, Flood, Tsunami or Earthquake," of the Standard Specifications and these special provisions.

When as a result of freezing conditions (as defined herein) during the plant establishment period, plants have died or, in the opinion of the Engineer, have deteriorated to a point beyond which the plants will not mature as typical examples of their species, the Engineer may direct replacement of the affected plants. The total cost of ordered plant replacement work will be paid for as extra work as provided in Section 4-1.03D of the Standard Specifications. A freezing condition, for the purpose of this specification, occurs when the temperature at or near the affected area has been officially recorded below 0°C and plants have been killed or damaged to the degree described above.

When, as a result of drought conditions (as defined herein) during the plant establishment period, plants have died or, in the opinion of the Engineer, have deteriorated to a point beyond which the plants will not mature as typical examples of their species, the Engineer may direct replacement of the affected plants. The total cost of ordered plant replacements, after water

has been restricted or stopped, will be paid for as extra work as provided in Section 4-1.03D of the Standard Specifications. Restriction or shutoff of available water shall not relieve the Contractor from performing other contract work. A drought condition occurs when the Department, or its supplier, restricts or stops delivery of water to the Contractor to the degree that plants have died or deteriorated as described above.

When the provisions in Section 7-1.165, "Damage by Storm, Flood, Tsunami or Earthquake," of the Standard Specifications are applicable, the provisions above for payment of costs for repair of damage due to rain, freezing conditions and drought shall not apply.

### 5-1.15 RELIEF FROM MAINTENANCE AND RESPONSIBILITY

The Contractor may be relieved of the duty of maintenance and protection for those items not directly connected with plant establishment work in conformance with the provisions in Section 7-1.15, "Relief From Maintenance and Responsibility," of the Standard Specifications. Water pollution control, maintain existing planted areas, maintain existing irrigation facilities, transplant trees, and transplant palm trees shall not be relieved of maintenance.

## SECTION 6. (BLANK)

## SECTION 7. (BLANK)

## SECTION 8. MATERIALS

## SECTION 8-1. MISCELLANEOUS

### 8-1.01 PREQUALIFIED AND TESTED SIGNING AND DELINEATION MATERIALS

The Department maintains the following list of Prequalified and Tested Signing and Delineation Materials. The Engineer shall not be precluded from sampling and testing products on the list of Prequalified and Tested Signing and Delineation Materials.

The manufacturer of products on the list of Prequalified and Tested Signing and Delineation Materials shall furnish the Engineer a Certificate of Compliance in conformance with the provisions in Section 6-1.07, "Certificates of Compliance," of the Standard Specifications for each type of traffic product supplied.

For those categories of materials included on the list of Prequalified and Tested Signing and Delineation Materials, only those products shown within the listing may be used in the work. Other categories of products, not included on the list of Prequalified and Tested Signing and Delineation Materials, may be used in the work provided they conform to the requirements of the Standard Specifications.

Materials and products may be added to the list of Prequalified and Tested Signing and Delineation Materials if the manufacturer submits a New Product Information Form to the New Product Coordinator at the Transportation Laboratory. Upon a Departmental request for samples, sufficient samples shall be submitted to permit performance of required tests. Approval of materials or products will depend upon compliance with the specifications and tests the Department may elect to perform.

**PAVEMENT MARKERS, PERMANENT TYPE**

**Retroreflective With Abrasion Resistant Surface (ARS)**

1. Apex, Model 921AR (4" x 4")
2. Ennis Paint, Models C88 (4" x 4"), 911 (4" x 4") and C80FH
3. Ray-O-Lite, Models "AA" ARS (4" x 4") and ARC Round Shoulder (4" x 4")
4. 3M Series 290 (3.5" x 4")
5. 3M Series 290 PSA
6. Glowlite, Inc Model 988AR (4" x 4")

**Retroreflective With Abrasion Resistant Surface (ARS)**

(for recessed applications only)

1. Ennis Paint, Model 948 (2.3" x 4.7")
2. Ennis Paint, Model 944SB (2" x 4")*
3. Ray-O-Lite, Model 2002 (2" x 4.6")
4. Ray-O-Lite, Model 2004 ARS (2" x 4")*

*For use only in 4.5 inch wide (older) recessed slots

**Non-Reflective, 4-inch Round**

1. Apex Universal (Ceramic)
2. Apex Universal, Models 929 (ABS) and 929PP (Polypropylene)
3. Glowlite, Inc. (Ceramic) and PP (Polypropylene)
4. Hi-Way Safety, Inc., Models P20-2000W and 2001Y (ABS)
5. Interstate Sales, "Diamond Back" (Polypropylene)
6. Novabrite Models Cdot (White) Cdot-y (Yellow), Ceramic
7. Novabrite Models Pdot-w (White) Pdot-y (Yellow), Polypropylene
8. Three D Traffic Works TD10000 (ABS), TD10500 (Polypropylene)

**PAVEMENT MARKERS, TEMPORARY TYPE**

**Temporary Markers For Long Term Day/Night Use (180 days or less)**

1. Vega Molded Products "Temporary Road Marker" (3" x 4")

**Temporary Markers For Short Term Day/Night Use (14 days or less)**

(For seal coat or chip seal applications, clear protective covers are required)

1. Apex Universal, Model 932
2. Filtrona Extrusion, Models T.O.M., T.R.P.M., and "HH" (High Heat)
3. Hi-Way Safety, Inc., Model 1280/1281
4. Glowlite, Inc., Model 932

**STRIPING AND PAVEMENT MARKING MATERIAL**

**Permanent Traffic Striping and Pavement Marking Tape**

1. Advanced Traffic Marking, Series 300 and 400
2. Brite-Line, Series 1000
3. Brite-Line, "DeltaLine XRP"
4. Swarco Industries, "Director 35" (For transverse application only)
5. Swarco Industries, "Director 60"
6. 3M, "Stamark" Series 380 and 5730
7. 3M, "Stamark" Series 420 (For transverse application only)

**Temporary (Removable) Striping and Pavement Marking Tape (180 days or less)**

1. Advanced Traffic Marking, Series 200
2. Brite-Line, Series 100
3. Garlock Rubber Technologies, Series 2000
4. P.B. Laminations, Aztec, Grade 102
5. Swarco Industries, "Director-2"
6. Trelleborg Industries, R140 Series
7. 3M Series 620 "CR", and Series A750
8. 3M Series A145, Removable Black Line Mask
   (Black Tape: for use only on Hot mix asphalt surfaces)
9. Advanced Traffic Marking Black "Hide-A-Line"
   (Black Tape: for use only on Hot mix asphalt surfaces)
10. Brite-Line "BTR" Black Removable Tape
    (Black Tape: for use only on Hot mix asphalt surfaces)
11. Trelleborg Industries, RB-140
    (Black Tape: for use only on Hot mix asphalt surfaces)

**Preformed Thermoplastic (Heated in place)**

1. Flint Trading Inc., "Hot Tape"
2. Flint Trading Inc., "Premark Plus"
3. Ennis Paint Inc., "Flametape"

**Ceramic Surfacing Laminate, 6" x 6"**

1. Highway Ceramics, Inc.

**CLASS 1 DELINEATORS**

**One Piece Driveable Flexible Type, 66-inch**

1. Filtrona Extrusion, "Flexi-Guide Models 400 and 566"
2. Carsonite, Curve-Flex CFRM-400
3. Carsonite, Roadmarker CRM-375
4. FlexStake, Model 654 TM
5. GreenLine Model CGD1-66

**Special Use Type, 66-inch**

1. Filtrona Extrusion, Model FG 560 (with 18-inch U-Channel base)
2. Carsonite, "Survivor" (with 18-inch U-Channel base)
3. Carsonite, Roadmarker CRM-375 (with 18-inch U-Channel base)
4. FlexStake, Model 604
5. GreenLine Model CGD (with 18-inch U-Channel base)
6. Impact Recovery Model D36, with #105 Driveable Base
7. Safe-Hit with 8-inch pavement anchor (SH248-GP1)
8. Safe-Hit with 15-inch soil anchor (SH248-GP2) and with 18-inch soil anchor (SH248-GP3)

**Surface Mount Type, 48-inch**

1. Bent Manufacturing Company, Masterflex Model MF-180EX-48
2. Carsonite, "Channelizer"
3. FlexStake, Models 704, 754 TM, and EB4
4. Impact Recovery Model D48, with #101 Fixed (Surface-Mount) Base
5. Three D Traffic Works "Channelflex" ID No. 522248W

**CHANNELIZERS**

**Surface Mount Type, 36-inch**

1. Bent Manufacturing Company, Masterflex Models MF-360-36 (Round) and MF-180-36 (Flat)
2. Filtrona Extrusion, Flexi-Guide Models FG300PE, FG300UR, and FG300EFX
3. Carsonite, "Super Duck" (Round SDR-336)
4. Carsonite, Model SDCF03601MB "Channelizer"
5. FlexStake, Models 703, 753 TM, and EB3
6. GreenLine, Model SMD-36
7. Hi-way Safety, Inc. "Channel Guide Channelizer" Model CGC36
8. Impact Recovery Model D36, with #101 Fixed (Surface-Mount) Base
9. Safe-Hit, Guide Post, Model SH236SMA and Dura-Post, Model SHL36SMA
10. Three D Traffic Works "Boomerang" 5200 Series

**Lane Separation System**

1. Filtrona Extrusion, "Flexi-Guide (FG) 300 Curb System"
2. Qwick Kurb, "Klemmfix Guide System"
3. Dura-Curb System
4. Tuff Curb

**CONICAL DELINEATORS, 42-inch**

(For 28-inch Traffic Cones, see Standard Specifications)

1. Bent Manufacturing Company "T-Top"
2. Plastic Safety Systems "Navigator-42"
3. TrafFix Devices "Grabber"
4. Three D Traffic Works "Ringtop" TD7000, ID No. 742143
5. Three D Traffic Works, TD7500
6. Work Area Protection Corp. C-42

**OBJECT MARKERS**

**Type "K", 18-inch**

1. Filtrona Extrusion, Model FG318PE
2. Carsonite, Model SMD 615
3. FlexStake, Model 701 KM
4. Safe-Hit, Model SH718SMA

**Type "K-4" / "Q" Object Markers, 24-inch**

1. Bent Manufacturing "Masterflex" Model MF-360-24
2. Filtrona Extrusion, Model FG324PE
3. Carsonite, "Channelizer"
4. FlexStake, Model 701KM
5. Safe-Hit, Models SH824SMA_WA and SH824GP3_WA
6. Three D Traffic Works ID No. 531702W and TD 5200
7. Three D Traffic Works ID No. 520896W

**CONCRETE BARRIER MARKERS AND**
**TEMPORARY RAILING (TYPE K) REFLECTORS**

**Impactable Type**

1. ARTUK, "FB"
2. Filtrona Extrusion, Models PCBM-12 and PCBM-T12
3. Duraflex Corp., "Flexx 2020" and "Electriflexx"
4. Hi-Way Safety, Inc., Model GMKRM100
5. Plastic Safety Systems "BAM" Models OM-BARR and OM-BWAR
6. Three D Traffic Works "Roadguide" Model TD 9304

**Non-Impactable Type**

1. ARTUK, JD Series
2. Plastic Safety Systems "BAM" Models OM-BITARW and OM-BITARA
3. Vega Molded Products, Models GBM and JD
4. Plastic Vacuum Forming, "Cap-It C400"

**METAL BEAM GUARD RAIL POST MARKERS**

(For use to the left of traffic)

1. Filtrona Extrusion, "Mini" (3" x 10")
2. Creative Building Products, "Dura-Bull, Model 11201"
3. Duraflex Corp., "Railrider"
4. Plastic Vacuum Forming, "Cap-It C300"

**CONCRETE BARRIER DELINEATORS, 16-inch**

(For use to the right of traffic)

1. Filtrona Extrusion, Model PCBM T-16
2. Safe-Hit, Model SH216RBM

**CONCRETE BARRIER-MOUNTED MINI-DRUM (10" x 14" x 22")**

1. Stinson Equipment Company "SaddleMarker"

**GUARD RAILING DELINEATOR**

(Place top of reflective element at 48 inches above plane of roadway)

**Wood Post Type, 27-inch**

1. Filtrona Extrusion, FG 427 and FG 527
2. Carsonite, Model 427
3. FlexStake, Model 102 GR
4. GreenLine GRD 27
5. Safe-Hit, Model SH227GRD

6. Three D Traffic Works "Guardflex" TD9100
7. New Directions Mfg, NDM27

**Steel Post Type**

1. Carsonite, Model CFGR-327

**RETROREFLECTIVE SHEETING**

**Channelizers, Barrier Markers, and Delineators**

1. Avery Dennison T-6500 Series (For rigid substrate devices only)
2. Avery Dennison WR-7100 Series
3. Nippon Carbide Industries, Flexible Ultralite Grade (ULG) II
4. Reflexite, PC-1000 Metalized Polycarbonate
5. Reflexite, AC-1000 Acrylic
6. Reflexite, AP-1000 Metalized Polyester
7. Reflexite, Conformalight, AR-1000 Abrasion Resistant Coating
8. 3M, High Intensity

**Traffic Cones, 4-inch and 6-inch Sleeves**

1. Nippon Carbide Industries, Flexible Ultralite Grade (ULG) II
2. Reflexite, Vinyl, "TR" (Semi-transparent) or "Conformalight"
3. 3M Series 3840
4. Avery Dennison S-9000C

**Drums**

1. Avery Dennison WR-6100
2. Nippon Carbide Industries, Flexible Ultralite Grade (ULG) II
3. Reflexite, "Conformalight", "Super High Intensity" or "High Impact Drum Sheeting"
4. 3M Series 3810

**Barricades: Type I, Medium-Intensity (Typically Enclosed Lens, Glass-Bead Element)**

1. Nippon Carbide Industries, CN8117
2. Avery Dennison, W 1100 series
3. 3M Series CW 44

**Barricades: Type II, Medium-High-Intensity (Typically Enclosed Lens, Glass-Bead Element)**

1. Avery Dennison, W-2100 Series

**Signs: Type II, Medium-High-Intensity (Typically Enclosed Lens, Glass-Bead Element)**

1. Avery Dennison, T-2500 Series
2. Nippon Carbide Industries, Nikkalite 18000

**Signs: Type III, High-Intensity (Typically Encapsulated Glass-Bead Element)**

1. Avery Dennison, T-5500A and T-6500 Series
2. Nippon Carbide Industries, Nikkalite Brand Ultralite Grade II
3. 3M 3870 and 3930 Series

**Signs: Type IV, High-Intensity (Typically Unmetallized Microprismatic Element)**

1. Avery Dennison, T-6500 Series
2. Nippon Carbide Industries, Crystal Grade, 94000 Series
3. Nippon Carbide Industries, Model No. 94847 Fluorescent Orange
4. 3M Series 3930 and Series 3924S

**Signs: Type VI, Elastomeric (Roll-Up) High-Intensity, without Adhesive**

1. Avery Dennison, WU-6014
2. Novabrite LLC, "Econobrite"

3. Reflexite "Vinyl"
4. Reflexite "SuperBright"
5. Reflexite "Marathon"
6. 3M Series RS20

**Signs: Type VII, Super-High-Intensity (Typically Unmetallized Microprismatic Element)**

1. 3M Series 3924S, Fluorescent Orange
2. 3M LDP Series 3970

**Signs: Type VIII, Super-High-Intensity (Typically Unmetallized Microprismatic Element)**

1. Avery Dennison, T-7500 Series
2. Avery Dennison, T-7511 Fluorescent Yellow
3. Avery Dennison, T-7513 Fluorescent Yellow Green
4. Avery Dennison, W-7514 Fluorescent Orange
5. Nippon Carbide Industries, Nikkalite Crystal Grade Series 92800
6. Nippon Carbide Industries, Nikkalite Crystal Grade Model 92847 Fluorescent Orange

**Signs: Type IX, Very-High-Intensity (Typically Unmetallized Microprismatic Element)**

1. 3M VIP Series 3981 Diamond Grade Fluorescent Yellow
2. 3M VIP Series 3983 Diamond Grade Fluorescent Yellow/Green
3. 3M VIP Series 3990 Diamond Grade
4. Avery Dennison T-9500 Series
5. Avery Dennison, T9513, Fluorescent Yellow Green
6. Avery Dennison, W9514, Fluorescent Orange
7. Avery Dennison, T-9511 Fluorescent Yellow

**SPECIALTY SIGNS**

1. Reflexite "Endurance" Work Zone Sign (with Semi-Rigid Plastic Substrate)

**ALTERNATIVE SIGN SUBSTRATES**

**Fiberglass Reinforced Plastic (FRP) and Expanded Foam PVC**

1. Fiber-Brite (FRP)
2. Sequentia, "Polyplate" (FRP)
3. Inteplast Group "InteCel" (0.5 inch for Post-Mounted CZ Signs, 48-inch or less)(PVC)

**Aluminum Composite, Temporary Construction Signs and Permanent Signs up to 4 foot, 7 Inches**

1. Alcan Composites "Dibond Material, 80 mils"
2. Mitsubishi Chemical America, Alpolic 350

## 8-1.02 STATE-FURNISHED MATERIALS

Attention is directed to Section 6-1.02, "State-Furnished Materials," of the Standard Specifications and these special provisions.

The following materials will be furnished to the Contractor:

A. Site furnishings as follows:

1. Picnic table
2. Trash receptacles
3. Water post
4. Padlocks for backflow preventer assembly enclosures and
5. Walk gates

Site furnishings will be furnished to the Contractor at the District Warehouse located at the Landscape Maintenance Station located at Sawyer Camp Trail and Hillcrest Boulevard, Millbrae, CA, 94030.

The Contractor shall notify the District 4 Maintenance Area Superintendent (San Francisco), Telephone (415) 330-6536 and the Engineer not less than 48 hours before State-furnished material is to be picked up by the Contractor. A full

description of the material and the time the material will be picked up shall be provided. The contract number shall also be provided to the District 4 Maintenance Area Superintendent.

## SECTION 8-2. CONCRETE

### 8-2.01 PORTLAND CEMENT CONCRETE

Portland cement concrete shall conform to the provisions in Section 90, "Portland Cement Concrete," of the Standard Specifications and these special provisions.

The Department maintains a list of sources of fine and coarse aggregate that have been approved for use with a reduced amount of supplementary cementitious material in the total amount of cementitious material to be used. A source of aggregate will be considered for addition to the approved list if the producer of the aggregate submits to the Transportation Laboratory certified test results from a qualified testing laboratory that verify the aggregate complies with the requirements. Before the testing starts, the aggregate test shall be registered with the Department. A registration number can be obtained by calling (916) 227-7228. The registration number shall be used as the identification for the aggregate sample in correspondence with the Department. Upon request, a split of the tested sample shall be provided to the Department. Approval of aggregate will depend upon compliance with the specifications, based on the certified test results submitted, together with any replicate testing the Department may elect to perform. Approval will expire 3 years from the date the most recent registered and evaluated sample was collected from the aggregate source.

Qualified testing laboratories shall conform to the following requirements:

1. Laboratories performing ASTM Designation: C 1293 shall participate in the Cement and Concrete Reference Laboratory (CCRL) Concrete Proficiency Sample Program and shall have received a score of 3 or better on each test of the previous 2 sets of concrete samples.
2. Laboratories performing ASTM Designation: C 1260 shall participate in the Cement and Concrete Reference Laboratory (CCRL) Pozzolan Proficiency Sample Program and shall have received a score of 3 or better on the shrinkage and soundness tests of the previous 2 sets of pozzolan samples.

Aggregates on the list shall conform to one of the following requirements:

1. When the aggregate is tested in conformance with the requirements in California Test 554 and ASTM Designation: C 1293, the average expansion at one year shall be less than or equal to 0.040 percent; or
2. When the aggregate is tested in conformance with the requirements in California Test 554 and ASTM Designation: C 1260, the average of the expansion at 16 days shall be less than or equal to 0.15 percent.

If the aggregates used in the concrete are on the Department's list, the minimum amount of supplementary cementitious material shall conform to the following:

1. If fly ash or natural pozzolan conforming to the provisions in Section 90-2.01C, "Required Use of Supplementary Cementitious Materials," of the Standard Specifications is used, the minimum amount of supplementary cementitious material shall be 15 percent by weight of the total cementitious material; or
2. If silica fume conforming to the provisions in Section 90-2.01C, "Required Use of Supplementary Cementitious Materials," of the Standard Specifications is used, the minimum amount of supplementary cementitious material shall be 7 percent by weight of the total cementitious material.

The limitation on tricalcium silicate ($C_3S$) content in Type II cement specified in Section 90-2.01A, "Cement," of the Standard Specifications shall not apply.

## SECTION 8-3. WELDING

### 8-3.01 WELDING

**GENERAL**

Flux cored welding electrodes conforming to the requirements of AWS A5.20 E6XT-4 or E7XT-4 shall not be used to perform welding for this project.

Wherever reference is made to the following AWS welding codes in the Standard Specifications, on the plans, or in these special provisions, the year of adoption for these codes shall be as listed:

| AWS Code | Year of Adoption |
|---|---|
| D1.1 | 2006 |
| D1.4 | 2005 |
| D1.5 | 2002 |
| D1.6 | 1999 |

Requirements of the AWS welding codes shall apply unless otherwise specified in the Standard Specifications, on the plans, or in these special provisions. Wherever the abbreviation AWS is used, it shall be equivalent to the abbreviations ANSI/AWS or AASHTO/AWS.

Section 6.1.1.1 of AWS D1.5 is replaced with the following:

Quality Control (QC) shall be the responsibility of the Contractor. As a minimum, the Contractor shall perform inspection and testing of each weld joint prior to welding, during welding, and after welding as specified in this section and as necessary to ensure that materials and workmanship conform to the requirements of the contract documents.

Unless otherwise specified, Sections 6.1.3 through 6.1.4.3 of AWS D1.1, Section 7.1.2 of AWS D1.4, and Sections 6.1.1.2 through 6.1.3.3 of AWS D1.5 are replaced with the following:

The QC Inspector shall be the duly designated person who acts for and on behalf of the Contractor for inspection, testing, and quality related matters for all welding.

Quality Assurance (QA) is the prerogative of the Engineer. The QA Inspector is the duly designated person who acts for and on behalf of the Engineer.

The QC Inspector shall be responsible for quality control acceptance or rejection of materials and workmanship, and shall be currently certified as an AWS Certified Welding Inspector (CWI) in conformance with the requirements in AWS QC1, "Standard for AWS Certification of Welding Inspectors."

The QC Inspector may be assisted by an Assistant QC Inspector provided that this individual is currently certified as an AWS Certified Associate Welding Inspector (CAWI) in conformance with the requirements in AWS QC1, "Standard for AWS Certification of Welding Inspectors." The Assistant QC Inspector may perform inspection under the direct supervision of the QC Inspector provided the assistant is always within visible and audible range of the QC Inspector. The QC Inspector shall be responsible for signing all reports and for determining if welded materials conform to workmanship and acceptance criteria. The ratio of QC Assistants to QC Inspectors shall not exceed 5 to 1.

When the term "Inspector" is used without further qualification, it shall refer to the QC Inspector.

When any work is welded in conformance with the provisions in Section 75, "Miscellaneous Metal," of the Standard Specifications, not including Section 75-1.035, "Bridge Joint Restrainer Units," of the Standard Specifications, Section 6.1.4 of AWS D1.1 is replaced with the following:

The QC Inspector shall be responsible for quality control acceptance or rejection of materials and workmanship and shall be currently certified as an AWS CWI in conformance with the requirements in AWS QC1, "Standard for AWS Certification of Welding Inspectors," or as a Welding Inspector Specialist (WIS) in conformance with the requirements in AWS B5.2, "Specification for the Qualification of Welding Inspector Specialists and Welding Inspector Assistants."

Section 6.14.6, "Personnel Qualification," of AWS D1.1, Section 7.8, "Personnel Qualification," of AWS D1.4, and Section 6.1.3.4, "Personnel Qualification," of AWS D1.5 are replaced with the following:

Personnel performing nondestructive testing (NDT) shall be qualified and certified in conformance with the requirements of the American Society for Nondestructive Testing (ASNT) Recommended Practice No. SNT-TC-1A and the Written Practice of the NDT firm. The Written Practice of the NDT firm shall meet or exceed the guidelines of the ASNT Recommended Practice No. SNT-TC-1A. Individuals who perform NDT, review the results, and prepare the written reports shall be either:

A. Certified NDT Level II technicians, or;
B. Level III technicians who hold a current ASNT Level III certificate in that discipline and are authorized and certified to perform the work of Level II technicians.

Section 6.5.4 of AWS D1.5 is replaced with the following:

The QC Inspector shall inspect and approve each joint preparation, assembly practice, welding technique, joint fit-up, and the performance of each welder, welding operator, and tack welder to make certain that the applicable requirements of this code and the approved Welding Procedure Specification (WPS) are met. The QC Inspector shall examine the work to make certain that it meets the requirements of Sections 3 and 6.26. The size and contour of all welds shall be measured using suitable gages. Visual inspection for cracks in welds and base metal, and for other discontinuities shall be aided by strong light, magnifiers, or such other devices as may be helpful. Acceptance criteria different from those specified in this code may be used when approved by the Engineer.

Section 6.6.5, "Nonspecified NDT Other than Visual," of AWS D1.1, Section 7.6.5 of AWS D1.4 and Section 6.6.5 of AWS D1.5 shall not apply.

For any welding, the Engineer may direct the Contractor to perform NDT that is in addition to the visual inspection or NDT specified in the AWS or other specified welding codes, in the Standard Specifications, or in these special provisions. Except as provided for in these special provisions, additional NDT required by the Engineer, and associated repair work, will be paid for as extra work as provided in Section 4-1.03D, "Extra Work," of the Standard Specifications. Prior to release of welded material by the Engineer, if testing by NDT methods other than those originally specified discloses an attempt to defraud or reveals a gross nonconformance, all costs associated with the repair of the deficient area, including NDT of the weld and of the repair, and any delays caused by the repair, shall be at the Contractor's expense. A gross nonconformance is defined as the sum of planar type rejectable indications in more than 20 percent of the tested length.

When less than 100 percent of NDT is specified for any weld, it is expected that the entire length of weld meet the specified acceptance-rejection criteria. Should any welding deficiencies be discovered by additional NDT directed or performed by the Engineer that utilizes the same NDT method as that originally specified, all costs associated with the repair of the deficient area, including NDT of the weld and of the weld repair, and any delays caused by the repair, shall be at the Contractor's expense.

Repair work to correct welding deficiencies discovered by visual inspection directed or performed by the Engineer, and any associated delays or expenses caused to the Contractor by performing these repairs, shall be at the Contractor's expense.

The Engineer shall have the authority to verify the qualifications or certifications of any welder, QC Inspector, or NDT personnel to specified levels by retests or other means approved by the Engineer.

Inspection and approval of all joint preparations, assembly practices, joint fit-ups, welding techniques, and the performance of each welder, welding operator, and tack welder shall be documented by the QC Inspector on a daily basis for each day welding is performed. For each inspection, including fit-up, Welding Procedure Specification (WPS) verification, and final weld inspection, the QC Inspector shall confirm and document compliance with the requirements of the AWS or other specified code criteria and the requirements of these special provisions on all welded joints before welding, during welding, and after the completion of each weld.

In addition to the requirements specified in the applicable code, the period of effectiveness for a welder's or welding operator's qualification shall be a maximum of 3 years for the same weld process, welding position, and weld type. If welding will be performed without gas shielding, then qualification shall also be without gas shielding. Excluding welding of fracture critical members, a valid qualification at the beginning of work on a contract will be acceptable for the entire period of the contract, as long as the welder's or welding operator's work remains satisfactory.

In addition to the requirements of AWS D1.1, welding procedures qualification for work welded in conformance with that code shall conform to the following requirements:

A. The travel speed, amperage, and voltage values that are used for tests conducted per AWS D1.1, Section 4.1.1, shall be consistent for each pass in a weld joint and shall in no case vary by more than ±10 percent for travel speed, ±10 percent for amperage, and ±7 percent for voltage as measured from a predetermined target value or average within each weld pass. The travel speed shall in no case vary by more than ±15 percent when using submerged arc welding.
B. When a nonstandard weld joint is to be made using a combination of WPSs, a single test may be conducted combining the WPSs to be used in production, provided the essential variables, including weld bead placement, of each process are limited to those established in Table 4.5.

In addition to the requirements of AWS D1.5, Section 5.12 or 5.13, welding procedures qualification for work welded in conformance with that code shall conform to the following requirements:

A. Unless considered prequalified, fillet welds shall be qualified in each position. The fillet weld soundness test shall be conducted using the essential variables of the WPS as established by the Procedure Qualification Record (PQR).
B. For qualification of joints that do not conform to Figures 2.4 and 2.5 of AWS D1.5, a minimum of two WPS qualification tests are required. The tests shall be conducted using both Figure 5.1 and Figure 5.3. The test conforming to Figure 5.1 shall be conducted in conformance with AWS D1.5, Section 5.12 or 5.13. The test

conforming to Figure 5.3 shall be conducted using the welding electrical parameters that were established for the test conducted conforming to Figure 5.1. The ranges of welding electrical parameters established during welding per Figure 5.1 in conformance with AWS D1.5, Section 5.12, shall be further restricted according to the limits in Table 5.3 during welding per Figure 5.3.

C. Multiple zones within a weld joint may be qualified. The travel speed, amperage, and voltage values that are used for tests conducted per AWS D1.5 Section 5.13 shall be consistent for each pass in a weld joint, and shall in no case vary by more than ±10 percent for travel speed, ±10 percent for amperage, and ±7 percent for voltage as measured from a predetermined target value or average within each weld pass or zone. The travel speed shall in no case vary by more than ±15 percent when using submerged arc welding.

D. For a WPS qualified in conformance with AWS D1.5 Section 5.13, the values to be used for calculating ranges for current and voltage shall be based on the average of all weld passes made in the test. Heat input shall be calculated using the average of current and voltage of all weld passes made in the test for a WPS qualified in conformance with Section 5.12 or 5.13.

E. Macroetch tests are required for WPS qualification tests, and acceptance shall be per AWS D1.5 Section 5.19.3.

F. When a nonstandard weld joint is to be made using a combination of WPSs, a test conforming to Figure 5.3 may be conducted combining the WPSs to be used in production, provided the essential variables, including weld bead placement, of each process are limited to those established in Table 5.3.

G. Prior to preparing mechanical test specimens, the PQR welds shall be inspected by visual and radiographic tests. Backing bar shall be 3 inches in width and shall remain in place during NDT testing. Results of the visual and radiographic tests shall comply with AWS D1.5 Section 6.26.2, excluding Section 6.26.2.2. Test plates that do not comply with both tests shall not be used.

**PAYMENT**

Full compensation for conforming to the requirements of "Welding" shall be considered as included in the contract prices paid for the various items of work involved and no additional compensation will be allowed therefor.

## SECTION 9. (BLANK)

## SECTION 10. CONSTRUCTION DETAILS

## SECTION 10-1. GENERAL

### 10-1.01 CONSTRUCTION PROJECT INFORMATION SIGNS

Before any major physical construction work readily visible to highway users is started on this contract, the Contractor shall furnish and erect 1 Type 2 Construction Project Information signs at the locations designated by the Engineer.

The signs and overlays shall be of a type and material consistent with the estimated time of completion of the project and shall conform to the details shown on the plans.

The sign letters, the border and the Department's construction logos shall conform to the colors (non-reflective) and details shown on the plans, and shall be on a white background (non-reflective). The colors blue and orange shall conform to PR Color Number 3 and Number 6, respectively, as specified in the Federal Highway Administration's Color Tolerance Chart.

The sign message to be used for fund types shall consist of the following, in the order shown:

| |
|---|
| FEDERAL HIGHWAY TRUST FUNDS |
| STATE HIGHWAY FUNDS |

The sign message to be used for type of work shall consist of the following:

ROADSIDE WORK

The sign message to be used for the Year of Completion of Project Construction will be furnished by the Engineer. The Contractor shall furnish and install the "Year" sign overlay within 10 working days of notification of the year date to be used.

The letter sizes to be used shall be as shown on the plans. The information shown on the signs shall be limited to that shown on the plans.

The signs shall be kept clean and in good repair by the Contractor.

Upon completion of the work, the signs shall be removed and disposed of outside the highway right of way in conformance with the provisions in Section 7-1.13 of the Standard Specifications.

Full compensation for furnishing, erecting, maintaining, and removing and disposing of the construction project information signs shall be considered as included in the contract lump sum price paid for construction area signs and no additional compensation will be allowed therefor.

## 10-1.02 ORDER OF WORK

Order of work shall conform to the provisions in Section 5-1.05, "Order of Work," of the Standard Specifications and these special provisions.

Attention is directed to "Miscellaneous Concrete Construction" of these special provisions regarding constructing a 2' x 2' test panel prior to constructing curb ramps with detectable warning surfaces.

Temporary railing (Type K) and temporary crash cushions shall be secured in place prior to commencing work for which the temporary railing and crash cushions are required.

Attention is directed to "Environmentally Sensitive Area" and "Temporary Fence (Type ESA)" of these special provisions. Prior to beginning work, the locations and boundaries of the Environmentally Sensitive Areas and Temporary Fence (Type ESA) shall be clearly delineated in the field. The boundaries shall be delineated by the installation of temporary fence (Type ESA).

Attention is directed to "Water Pollution Control" of these special provisions regarding the submittal and approval of the Storm Water Pollution Prevention Plan prior to performing work having potential to cause water pollution.

The uppermost layer of new pavement shall not be placed until all underlying conduits have been installed.

At least 60 days before planting the plants, furnish the Engineer a statement from the vendor that the order for the plants required for this contract, including inspection plants, has been received and accepted by the vendor. The statement from the vendor must include the names, sizes, and quantities of plants ordered and the anticipated date of delivery.

Place orders for replacement plants with the vendor at the appropriate time so that the roots of the replacement plants are not in a root-bound condition.

At least 60 days before applying seeds, furnish the Engineer a statement from the vendor that the order for the seed required for this contract has been received and accepted by the vendor. The statement from the vendor must include the names and quantity of seed ordered and the anticipated date of delivery.

The Engineer designates ground locations of erosion control by directing the placing of stakes or other suitable markers before application of erosion control materials as specified under "Erosion Control (Type D)," of these special provisions.

Before the start of irrigation work, check for deficiencies of existing plants that are to remain in place as specified under "Maintain Existing Planted Areas" of these special provisions.

Unless otherwise shown on the plans or specified in these special provisions, conduits to be jacked or drilled or installed by the open trench method for water line crossovers and sprinkler control crossovers must be installed before the installation of other pipe supply lines.

Do not perform clearing, grubbing, and earthwork operations in areas where existing irrigation facilities are to remain in place until existing irrigation facilities have been checked for proper operation as specified under "Existing Highway Irrigation Facilities" of these special provisions.

Locate existing conduits to be extended as specified under "Extend Irrigation Crossovers" of these special provisions before the start of other work in these areas.

## 10-1.03 WATER POLLUTION CONTROL

### GENERAL

Water pollution control work shall conform to the provisions in Section 7-1.01G, "Water Pollution," of the Standard Specifications, section of these special provisions entitled "Relations With California Regional Water Quality Control Board," and these special provisions.

The Contractor may obtain other National Pollutant Discharge Elimination System (NPDES) permits that apply to activities and mobile operations within or outside of the project limits including hot mix asphalt batch plants, material borrow areas, concrete plants, staging areas, storage yards, or access roads.

The Contractor shall perform water pollution control work in conformance with the requirements in the "Storm Water Pollution Prevention Plan (SWPPP) and Water Pollution Control Program (WPCP) Preparation Manual" and its addenda in effect on the day the Notice to Contractors is dated. This manual is referred to as the "Preparation Manual." Copies of the Preparation Manual may be obtained from:

State of California
Department of Transportation
Publication Distribution Unit
1900 Royal Oaks Drive
Sacramento, California 95815
Telephone: (916) 445-3520

The Preparation Manual and other references for performing water pollution control work are available from the Department's Construction Storm Water and Water Pollution Control web site at:

http://www.dot.ca.gov/hq/construc/stormwater/stormwater1.htm

Before the start of job site activities, the Contractor shall provide training for project managers, supervisory personnel, and employees involved with water pollution control work. The training shall include:

A. Rules and regulations
B. Implementation and maintenance for:

    1. Temporary Soil Stabilization
    2. Temporary Sediment Control
    3. Tracking Control
    4. Wind Erosion Control

The Contractor shall designate in writing a Water Pollution Control Manager (WPCM). The Contractor shall submit a statement of qualifications describing the training, work history, and expertise of the proposed WPCM. The qualifications shall include either:

A. A minimum of 24 hours of Department approved storm water management training described at Department's Construction Storm Water and Water Pollution Control web site.
B. Certification as a Certified Professional in Erosion and Sediment Control (CPESC).

The WPCM shall be:

A. Responsible for water pollution control work.
B. The primary contact for water pollution control work.
C. Have authority to mobilize crews to make immediate repairs to water pollution control practices.

The Contractor may designate one manager to prepare the SWPPP and a different manager to implement the plan. The WPCP preparer shall meet the training requirements for the WPCM.

**STORM WATER POLLUTION PREVENTION PLAN**

The Contractor shall submit a Storm Water Pollution Prevention Plan (SWPPP) to the Engineer for approval. The SWPPP shall conform to the requirements in the Preparation Manual, the NPDES permit, and these special provisions. The SWPPP shall be submitted in place of the water pollution control program required by the provisions in Section 7-1.01G, "Water Pollution," of the Standard Specifications.

The SWPPP shall include water pollution control practices:

A. For storm water and non-storm water from areas outside of the job site related to construction activities for this contract such as:

    1. Staging areas.
    2. Storage yards.
    3. Access roads.

B. Appropriate for each season as described in "Implementation Requirements" of these special provisions.
C. For activities or mobile operations related to all NPDES permits.

The SWPPP shall include a schedule that:

A. Describes when work activities that could cause water pollution will be performed.
B. Identifies soil stabilization and sediment control practices for disturbed soil area.
C. Includes dates when these practices will be 25, 50, and 100 percent complete.
D. Shows 100 percent completion of these practices before the rainy season.

The SWPPP shall include the following temporary water pollution control practices and their associated contract items of work as shown on the plans or specified in these special provisions:

A. Temporary Soil Stabilization

    1. Temporary Fence (Type ESA)

B. Temporary Sediment Control

    1. Temporary Drainage Inlet Protection
    2. Temporary Silt Fence
    3. Street Sweeping

C. Tracking Control

    1. Street Sweeping
    2. Temporary Construction Entrance

D. Wind Erosion Control

    1. Construction Site Management

E. Non-Storm Water Management

    1. Construction Site Management

F. Waste Management and Materials Pollution Control

    1. Construction Site Management
    2. Temporary Concrete Washout Facility

The SWPPP shall include the following contract items of work for permanent water pollution control as shown on the plans or as specified in these special provisions:

A. Erosion Control (Type D)
B. Mulch

Within 20 days after contract approval, the Contractor shall submit 3 copies of the SWPPP to the Engineer. The Contractor shall allow 20 days for the Engineer's review. If revisions are required, the Engineer will provide comments and specify the date that the review stopped. The Contractor shall revise and resubmit the SWPPP within 15 days of receipt of the Engineer's comments. The Engineer's review will resume when the complete SWPPP is resubmitted. When the Engineer approves the SWPPP, the Contractor shall submit 4 copies of the approved SWPPP to the Engineer. The Contractor may proceed with construction activities if the Engineer conditionally approves the SWPPP while minor revisions are being completed. If the Engineer fails to complete the review within the time allowed and if, in the opinion of the Engineer, completion of the work is delayed or interfered with by reason of the Engineer's delay, the Contractor will be compensated for resulting losses, and an extension of time will be granted, as provided for in Section 8-1.09, "Right of Way Delays," of the Standard Specifications.

The Contractor shall not perform work that may cause water pollution until the SWPPP has been approved by the Engineer. The Engineer's review and approval shall not waive any contract requirements and shall not relieve the Contractor from complying with Federal, State and local laws, regulations, and requirements.

The Contractor shall amend the SWPPP annually and shall resubmit it to the Engineer 25 days before the defined rainy season.

If there is a change in construction schedule or activities, the Contractor shall prepare an amendment to the SWPPP to identify additional or revised water pollution control practices. The Contractor shall submit the amendment to the Engineer for review within a time agreed to by the Engineer not to exceed the number of days specified for the initial submittal of the SWPPP. The Engineer will review the amendment within the same time allotted for the review of the initial submittal of the SWPPP.

If directed by the Engineer or requested in writing by the Contractor and approved by the Engineer, changes to the water pollution control work specified in these special provisions will be allowed. Changes may include addition of new water pollution control practices. The Contractor shall incorporate these changes in the SWPPP. Additional water pollution control work will be paid for as extra work in accordance with Section 4-1.03D, "Extra Work," of the Standard Specifications.

The Contractor shall keep a copy of the approved SWPPP at the job site. The SWPPP shall be made available when requested by a representative of the Regional Water Quality Control Board, State Water Resources Control Board, United States Environmental Protection Agency, or the local storm water management agency. Requests from the public shall be directed to the Engineer.

**SAMPLING AND ANALYSIS**

The Contractor shall include a Sampling and Analysis Plan (SAP) in the SWPPP to monitor the effectiveness of the water pollution control practices. The Contractor shall prepare the SAP in conformance with the Preparation Manual.

The Contractor shall designate trained personnel to collect water quality samples. The personnel and training shall be documented in the SAP. Training shall consist of the following elements:

A. SAP review,
B. Health and safety review, and
C. Sampling simulations.

In the SAP the Contractor shall describe the following water quality sampling procedures:

A. Sampling preparation,
B. Collection,
C. Quality assurance and quality control,
D. Sample labeling,
E. Collection documentation,
F. Sample shipping,
G. Chain of custody,
H. Sample numbering, and
I. Precautions from the construction site health and safety plan.

The Contractor shall document sample collection during precipitation.

Samples to be analyzed in the field shall be taken by the Contractor's designated sampling personnel using collection and analysis methods, and equipment calibration specified by the manufacturer of the sampling equipment. Samples to be analyzed by a laboratory, shall be sampled, preserved, and analyzed by a State-certified laboratory in conformance with the requirements in 40 CFR Part 136, "Guidelines Establishing Test Procedures for the Analysis of Pollutants." The Contractor shall identify the State-certified laboratory, sample containers, preservation requirements, holding times, and analysis method in the SAP. A list of State-certified laboratories that are approved by the Department is available at:

http://www.dhs.ca.gov/ps/ls/ELAP/html/lablist.htm

**Non-Visible Pollutants**

This project has the potential to discharge non-visible pollutants in storm water from the construction site. The Contractor shall include in the SAP a description of the sampling and analysis strategy to be implemented on the project for monitoring non-visible pollutants.

In the SAP the Contractor shall identify potential non-visible pollutants that will be present on the construction site associated with the following:

A. Construction materials and wastes;
B. Existing contamination due to historical site usage; or
C. Application of soil amendments, including soil stabilization products, with the potential to alter pH or contribute toxic pollutants to storm water.

The Contractor shall show the locations planned for storage and use of the potential non-visible pollutants on the SWPPP Water Pollution Control Drawings.

The Contractor shall include in the SAP the following list of conditions that require sampling when observed during a storm water inspection:

A. Materials or wastes containing potential non-visible pollutants are not stored under watertight conditions.
B. Materials or wastes containing potential non-visible pollutants are stored under watertight conditions, but:

    1. A breach, leakage, malfunction, or spill is observed;
    2. The leak or spill has not been cleaned up before precipitation; and
    3. There is the potential for discharge of non-visible pollutants to surface waters or drainage system.

C. Construction activities; such as application of fertilizer, pesticide, herbicide, methyl methacrylate concrete sealant, or non-pigmented curing compound; have occurred during precipitation or within 24 hours preceding precipitation, and have the potential to discharge pollutants to surface waters or drainage system.
D. Soil amendments, including soil stabilization products, with the potential to alter pH levels or contribute toxic pollutants to storm water runoff have been applied, and have the potential to discharge pollutants to surface waters or drainage system (unless independent test data are available that demonstrate acceptable concentrations of non-visible pollutants in the soil amendment).
E. Storm water runoff from an area contaminated by historical usage of the site has the potential to discharge pollutants to surface waters or drainage system.

The Contractor shall describe in the SAP the schedule for collecting a sample downhill from each non-visible pollutant source and an uncontaminated control sample, during the first 2 hours of discharge from precipitation during daylight hours that result in enough discharge for sample collection. If discharge flows to the non-visible pollutant source, a sample shall be collected immediately downhill from where the discharge enters the Department's right of way. If precipitation occurs again after at least 72 hours of dry weather the Contractor shall take new samples.

In the SAP the Contractor shall identify sampling locations for collecting downstream and control samples, and the reason for their selection. The control sampling location shall be selected so the sample does not come into contact with materials, wastes or areas associated with potential non-visible pollutants or disturbed soil areas. The Contractor shall show non-visible pollutant sampling locations on the SWPPP Water Pollution Control Drawings.

The Contractor shall identify in the SAP the analytical method to be used for downhill and control samples for potential non-visible pollutants on the project.

**Analytical Results and Evaluation**

The Contractor shall submit a hard copy and electronic copy of water quality analytical results, and quality assurance and quality control data to the Engineer within 5 days of sampling for field analyses, and within 30 days for laboratory analyses. The Contractor shall also provide an evaluation of whether the downhill samples show levels of the tested parameter higher than in the control sample. If downhill or downstream samples show increased levels, the Contractor will assess the water pollution control measures, site conditions, and surrounding influences to determine the probable cause for the increase. As determined by the assessment, the Contractor will repair or modify water pollution control measures to address increases and amend the SWPPP as necessary. Electronic results (in one of the following file formats: .xls, .txt, .csv, .dbs, or .mdb) shall have the following information:

A. Sample identification number.
B. Contract number.
C. Constituent.
D. Reported value.
E. Analytical method.
F. Method detection limit.
G. Reported limit.

The Contractor shall maintain the water quality sampling documentation and analytical results with the SWPPP on the project site.

If construction activities or knowledge of site conditions change such that discharges or sampling locations change, the Contractor shall amend the SAP in conformance with this section, "Water Pollution Control."

**IMPLEMENTATION REQUIREMENTS**

The Contractor's responsibility for SWPPP implementation shall continue throughout any temporary suspension of work ordered in conformance with the provisions in Section 8-1.05, "Temporary Suspension of Work," of the Standard Specifications.

If the Contractor or the Engineer identifies a deficiency in the implementation of the approved SWPPP, the deficiency shall be corrected immediately, unless an agreed date for correction is approved in writing by the Engineer. The deficiency shall be corrected before the onset of precipitation. If the Contractor fails to correct the deficiency by the agreed date or before the onset of precipitation, the Department may correct the deficiency and deduct the cost of correcting deficiencies from payments.

If the Contractor fails to conform to the provisions of this section, "Water Pollution Control," the Engineer may order the suspension of work until the project complies with the requirements of this section.

**Year-Round**

The Contractor shall monitor the National Weather Service weather forecast on a daily basis during the contract. The Contractor may use an alternative weather forecasting service if approved by the Engineer. Appropriate water pollution control practices shall be in place before precipitation.

The Contractor may discontinue earthwork operations for a disturbed area for up to 21 days and the disturbed soil area will still be considered active. When earthwork operations in the disturbed area have been completed, the Contractor shall implement appropriate water pollution control practices within 15 days, or before predicted precipitation, whichever occurs first.

**Rainy Season**

The Contractor shall provide soil stabilization and sediment control practices during the rainy season between October 15 and April 15.

The Contractor shall implement soil stabilization and sediment control practices a minimum of 10 days before the start of the rainy season.

During the defined rainy season, the active disturbed soil area of the project site shall be not more than 1.77 acres. The Engineer may approve expansions of the active disturbed soil area limit if requested in writing. The Contractor shall maintain soil stabilization and sediment control materials on site to protect disturbed soil areas.

**INSPECTION AND MAINTENANCE**

The WPCM shall inspect the water pollution control practices identified in the SWPPP as follows:

A. Before a forecasted storm,
B. After precipitation that causes site runoff,
C. At 24-hour intervals during extended precipitation,
D. On a predetermined schedule, a minimum of once every 2 weeks outside of the defined rainy season, and
E. On a predetermined schedule, a minimum of once a week during the defined rainy season.

The WPCM shall oversee the maintenance of the water pollution control practices.

The WPCM shall use the Storm Water Quality Construction Site Inspection Checklist provided in the Preparation Manual or an alternative inspection checklist provided by the Engineer. A copy of the completed site inspection checklist shall be submitted to the Engineer within 24 hours of finishing the inspection.

The Contractor may request approval from the Engineer to suspend inspections of water pollution control practices after work except plant establishment is complete. The Engineer's approval is contingent on approval from the Regional Water Quality Control Board. The Contractor shall not suspend inspections until written approval from the Engineer is received.

**REPORTING REQUIREMENTS**

If the Contractor identifies discharges into surface waters or drainage systems causing or potentially causing pollution, or if the project receives a written notice or order from a regulatory agency, the Contractor shall immediately inform the

Engineer. The Contractor shall submit a written report to the Engineer within 7 days of the discharge, notice or order. The report shall include the following information:

A. The date, time, location, and nature of the operation, type of discharge and quantity, and the cause of the notice or order.
B. The water pollution control practices used before the discharge, or before receiving the notice or order.
C. The date of placement and type of additional or altered water pollution control practices placed after the discharge, or after receiving the notice or order.
D. A maintenance schedule for affected water pollution control practices.

**Annual Certifications**

By June 15 of each year, the Contractor shall complete and submit to the Engineer an Annual Certification of Compliance, as contained in the Preparation Manual.

**PAYMENT**

During each estimate period the Contractor fails to conform to the provisions in this section, "Water Pollution Control," or fails to implement the water pollution control practices shown on the plans or specified elsewhere in these special provisions as items of work, the Department will withhold 25 percent of the progress payment.

Withholds for failure to perform water pollution control work will be in addition to all other withholds provided for in the contract. The Department will return performance-failure withholds in the progress payment following the correction of noncompliance.

The contract lump sum price paid for prepare storm water pollution prevention plan shall include full compensation for furnishing all labor, materials, tools, equipment, and incidentals and for doing all the work involved in preparing, obtaining approval of, and amending the SWPPP and inspecting water pollution control practices as specified in the Standard Specifications and these special provisions, and as directed by the Engineer.

Payments for prepare storm water pollution prevention plan will be made as follows:

A. After the SWPPP has been approved by the Engineer, 50 percent of the contract item price for prepare storm water pollution prevention plan will be included in the monthly progress estimate.
B. Forty percent of the contract item price for prepare storm water pollution prevention plan will be paid over the life of the contract.
C. After acceptance of the contract in conformance with the provisions in Section 7-1.17, "Acceptance of Contract," of the Standard Specifications, payment for the remaining 10 percent of the contract item price for prepare storm water pollution prevention plan will be made in conformance with the provisions in Section 9-1.07A, "Payment Prior to Proposed Final Estimate."

Storm water sampling and analysis will be paid for as extra work as provided in Section 4-1.03D, "Extra Work," of the Standard Specifications. No payment will be made for the preparation, collection, analysis, and reporting of storm water samples where appropriate water pollution control practices are not implemented before precipitation or if a failure of a water pollution control practice is not corrected before precipitation.

Implementation of water pollution control practices in areas outside the highway right of way not specifically provided for in the SWPPP or in these special provisions will not be paid for.

Water pollution control practices for which there are separate contract items of work will be measured and paid for as those contract items of work.

## 10-1.04 CONSTRUCTION SITE MANAGEMENT

Construction site management shall consist of controlling potential sources of water pollution before they come in contact with storm water systems or watercourses. The Contractor shall control material pollution and manage waste and non-storm water existing at the construction site by implementing effective handling, storage, use, and disposal practices.

Attention is directed to "Water Pollution Control" of these special provisions regarding the Contractor's appointment of a water pollution control manager (WPCM) for the project.

The Contractor shall train all employees and subcontractors regarding:

A. Material pollution prevention and control;
B. Waste management;
C. Non-storm water management;

D. Identifying and handling hazardous substances; and
E. Potential dangers to humans and the environment from spills and leaks or exposure to toxic or hazardous substances.

Training shall take place before starting work on this project. New employees shall receive the complete training before starting work on this project. The Contractor shall have regular meetings to discuss and reinforce spill prevention and control; material delivery, storage, use, and disposal; waste management; and non-storm water management procedures.

Instructions for material and waste handling, storage, and spill reporting and cleanup shall be posted at all times in an open, conspicuous, and accessible location at the construction site.

Nonhazardous construction site waste and excess material shall be recycled when practical or disposed of in accordance with the provisions in Section 7-1.13, "Disposal of Material Outside the Highway Right of Way," of the Standard Specifications, unless otherwise specified.

Vehicles and equipment at the construction site shall be inspected by the WPCM on a frequent, predetermined schedule, and by the operator each day of use. Leaks shall be repaired immediately, or the vehicle or equipment shall be removed from the construction site.

**SPILL PREVENTION AND CONTROL**

The Contractor shall implement spill and leak prevention procedures when chemicals or hazardous substances are stored. Spills of petroleum products; substances listed under CFR Title 40, Parts 110, 117, and 302; and sanitary and septic waste shall be contained and cleaned up as soon as is safe.

Minor spills involve small quantities of oil, gasoline, paint, or other material that can be controlled by the first responder upon discovery of the spill. Cleanup of minor spills includes:

A. Containing the spread of the spill,
B. Recovering the spilled material using absorption,
C. Cleaning the contaminated area, and
D. Disposing of contaminated material promptly and properly.

Semi-significant spills are those that can be controlled by the first responder with the help of other personnel. Cleanup of semi-significant spills shall be immediate. Cleanup of semi-significant spills includes:

A. Containing the spread of the spill;
B. Recovering the spilled material using absorption if the spill occurs on paved or an impermeable surface;
C. Containing the spill with an earthen dike and digging up contaminated soil for disposal if the spill occurs on dirt;
D. Covering the spill with plastic or other material to prevent contaminating runoff if the spill occurs during precipitation; and
E. Disposing of contaminated material promptly and properly.

Significant or hazardous spills are those that cannot be controlled by construction personnel. Notifications of these spills shall be immediate. The following steps shall be taken:

A. Construction personnel shall not attempt to cleanup the spill until qualified staff have arrived;
B. Notify the Engineer and follow up with a written report;
C. Obtain the services of a spills contractor or hazardous material team immediately;
D. Notify the local emergency response team by dialing 911 and county officials at the emergency phone numbers kept on the construction site;
E. Notify the Governor's Office of Emergency Services Warning Center at (805) 852-7550;
F. Notify the National Response Center at (800) 424-8802 regarding spills of Federal reportable quantities in conformance with CFR Title 40, Parts 110, 119, and 302;
G. Notify other agencies as appropriate, including:

    1. Fire Department,
    2. Public Works Department,
    3. Coast Guard,
    4. Highway Patrol,
    5. City Police or County Sheriff Department,
    6 Department of Toxic Substances,
    7. California Division of Oil and Gas,

8. Cal OSHA, or
9. Regional Water Resources Control Board.

The WPCM shall oversee and enforce proper spill prevention and control measures. Minor, semi-significant, and significant spills shall be reported to the Contractor's WPCM who shall notify the Engineer immediately.

The Contractor shall prevent spills from entering storm water runoff before and during cleanup. Spills shall not be buried or washed with water.

The Contractor shall keep material or waste storage areas clean, well organized, and equipped with enough cleanup supplies for the material being stored. Plastic shall be placed under paving equipment when not in use to catch drips.

**MATERIAL MANAGEMENT**

Material shall be delivered, used, and stored for this contract in a manner that minimizes or eliminates discharge of material into the air, storm drain systems, or watercourses.

The Contractor shall implement the practices described in this section when taking delivery of, using, or storing the following materials:

A. Hazardous chemicals including:

   1. Acids,
   2. Lime,
   3. Glues,
   4. Adhesives,
   5. Paints,
   6. Solvents, and
   7. Curing compounds;

B. Soil stabilizers and binders;
C. Fertilizers;
D. Detergents;
E. Plaster;
F. Petroleum products including:

   1. Fuel,
   2. Oil, and
   3. Grease;

G. Asphalt components and concrete components; and
H. Pesticides and herbicides.

The Contractor shall supply the Material Safety Data Sheet to the Engineer for material used or stored. The Contractor shall keep an accurate inventory of material delivered and stored at the construction site.

Employees trained in emergency spill cleanup procedures shall be present when hazardous materials or chemicals are unloaded.

The Contractor shall use recycled or less hazardous products when practical.

**Material Storage**

The Contractor shall store liquids, petroleum products, and substances listed in CFR Title 40, Parts 110, 117, and 302 in containers or drums approved by the United States Environmental Protection Agency, and place them in secondary containment facilities.

Secondary containment facilities shall be impervious to the materials stored there for a minimum contact time of 72 hours.

Throughout the rainy season secondary containment facilities shall be covered during non-working days and when precipitation is predicted. Secondary containment facilities shall be adequately ventilated.

The Contractor shall keep the secondary containment facility free of accumulated rainwater or spills. After precipitation, or in the event of spills or leaks, accumulated liquid shall be collected and placed into drums within 24 hours. These liquids shall be handled as hazardous waste in accordance with the provisions in "Hazardous Waste" of these special provisions, unless testing determines them to be nonhazardous.

Incompatible materials, such as chlorine and ammonia, shall not be stored in the same secondary containment facility.

Materials shall be stored in the original containers with the original product labels maintained in legible condition. Damaged or illegible labels shall be replaced immediately.

The secondary containment facility shall have the capacity to contain precipitation from a 24-hour-long, 25-year storm; and 10 percent of the aggregate volume of all containers, or all of the volume of the largest container within the facility, whichever is greater.

The Contractor shall store bagged or boxed material on pallets. Throughout the rainy season, bagged or boxed material shall be protected from wind and rain during non-working days and when precipitation is predicted.

The Contractor shall provide sufficient separation between stored containers to allow for spill cleanup or emergency response access. Storage areas shall be kept clean, well organized, and equipped with cleanup supplies appropriate for the materials being stored.

The Contractor shall repair or replace perimeter controls, containment structures, covers, and liners as needed. Storage areas shall be inspected before and after precipitation, and at least weekly during other times.

### Stockpile Management

The Contractor shall reduce or eliminate potential air and water pollution from stockpiled material including soil, paving material, or pressure treated wood. Stockpiles shall be located out of floodplains when possible, and at least 50 feet from concentrated flows of storm water, drainage courses, or inlets unless written approval is obtained from the Engineer.

The Contractor may discontinue adding or removing material for up to 21 days and a stockpile will still be considered active.

The Contractor shall protect active stockpiles with plastic or geotextile cover, soil stabilization measures, or with linear sediment barrier when precipitation is predicted. Active stockpiles of cold mix asphalt concrete shall be placed on an impervious surface and covered with plastic when precipitation is predicted.

The Contractor shall protect inactive soil stockpiles with a plastic or geotextile cover, or with soil stabilization measures at all times during the rainy season. A linear sediment barrier around the perimeter of the stockpile shall also be used. During the non-rainy season soil stockpiles shall be covered and protected with a linear sediment barrier when precipitation is predicted. The Contractor shall control wind erosion during dry weather as provided in Section 10, "Dust Control," of the Standard Specifications.

Stockpiles of portland cement concrete rubble, asphalt concrete (AC), hot mix asphalt (HMA), AC and HMA rubble, aggregate base, or aggregate subbase shall be covered with plastic or geotextile, or protected with a linear sediment barrier at all times during the rainy season, and when precipitation is predicted during the non-rainy season.

Stockpiles of cold mix asphalt concrete shall be placed on and covered with impermeable material at all times during the rainy season, and when precipitation is predicted during the non-rainy season.

Stockpiles of pressure treated wood shall be covered with impermeable material and placed on pallets at all times during the rainy season, and when precipitation is predicted during the non-rainy season.

The Contractor shall repair or replace linear sediment barriers and covers as needed or as directed by the Engineer to keep them functioning properly. Sediment shall be removed when it accumulates to 1/3 of the linear sediment barrier height.

## WASTE MANAGEMENT

### Solid Waste

The Contractor shall not allow litter or debris to accumulate anywhere on the construction site, including storm drain grates, trash racks, and ditch lines. The Contractor shall pick up and remove trash and debris from the construction site at least once a week. The WPCM shall monitor solid waste storage and disposal procedures on the construction site. The Contractor shall provide enough dumpsters of sufficient size to contain the solid waste generated by the project. Dumpsters shall be emptied when refuse reaches the fill line. Dumpsters shall be watertight. The Contractor shall not wash out dumpsters on the construction site. The Contractor shall provide additional containers and more frequent pickup during the demolition phase of construction

Solid waste includes:

A. Brick,
B. Mortar,
C. Timber,
D. Metal scraps,
E. Sawdust,
F. Pipe,
G. Electrical cuttings,
H. Non-hazardous equipment parts,

I. Styrofoam and other packaging materials,
J. Vegetative material and plant containers from highway planting, and
K. Litter and smoking material, including litter generated randomly by the public.

Trash receptacles shall be provided and used in the Contractor's yard, field trailers, and locations where workers gather for lunch and breaks.

**Hazardous Waste**

The Contractor shall implement hazardous waste management practices when waste is generated on the construction site from the following substances:

A. Petroleum products,
B. Asphalt products,
C. Concrete curing compound,
D. Pesticides,
E. Acids,
F. Paints,
G. Stains,
H. Solvents,
I. Wood preservatives,
J. Roofing tar, and
K. Materials classified as hazardous by California Code of Regulations, Title 22, Division 4.5; or listed in CFR Title 40, Parts 110, 117, 261, or 302.

Nothing in these special provisions shall relieve the Contractor of the responsibility for compliance with Federal, State, and local laws regarding storage, handling, transportation, and disposal of hazardous wastes.

Hazardous material existing on the construction site before mobilization shall be handled and disposed of in accordance with "Material Containing Naturally Occurring Asbestos" of these special provisions.

The WPCM shall oversee and enforce hazardous waste management practices. Production of hazardous materials and hazardous waste on the construction site shall be kept to a minimum. Perimeter controls, containment structures, covers, and liners shall be repaired or replaced when damaged.

The Contractor shall have a laboratory certified by the Department of Health Services (DHS) sample and test waste when hazardous material levels are unknown to determine safe methods for storage and disposal.

The Contractor shall segregate potentially hazardous waste from nonhazardous waste at the construction site. Hazardous waste shall be handled, stored, and disposed of as required in California Code of Regulations, Title 22, Division 4.5, Section 66262.34; and in CFR Title 49, Parts 261, 262, and 263.

The Contractor shall store hazardous waste in sealed containers constructed and labeled with the contents and date accumulated as required in California Code of Regulations, Title 22, Division 4.5; and in CFR Title 49, Parts 172, 173, 178, and 179. Hazardous waste containers shall be kept in temporary containment facilities conforming to the provisions in "Material Storage" of these special provisions.

There shall be adequate storage volume and containers shall be conveniently located for hazardous waste collection. Containers of hazardous waste shall not be overfilled and hazardous wastes shall not be mixed. Containers of dry waste that are not watertight shall be stored on pallets. The Contractor shall not allow potentially hazardous waste to accumulate on the ground. Hazardous waste shall be stored away from storm drains, watercourses, moving vehicles, and equipment.

The Contractor shall clean water based or oil based paint from brushes or equipment within a contained area and shall not contaminate soil, watercourses, or storm drain systems. Paints, thinners, solvents, residues, and sludges that cannot be recycled or reused shall be disposed of as hazardous waste. When thoroughly dry, latex paint and paint cans, used brushes, rags, absorbent materials, and drop cloths shall be disposed of as solid waste.

The Contractor shall dispose of hazardous waste within 90 days of being generated. Hazardous waste shall be disposed of by a licensed hazardous waste transporter using uniform hazardous waste manifest forms and taken to a Class I Disposal Site. A copy of the manifest shall be provided to the Engineer.

**Contaminated Soil**

The Contractor shall identify contaminated soil from spills or leaks by noticing discoloration, odors, or differences in soil properties. Soil with evidence of contamination shall be sampled and tested by a laboratory certified by DHS. If levels of contamination are found to be hazardous, the soil shall be handled and disposed of as hazardous waste.

The Contractor shall prevent the flow of water, including ground water, from mixing with contaminated soil by using one or a combination of the following measures:

A. Berms,
B. Cofferdams,
C. Grout curtains,
D. Freeze walls, or
E. Concrete seal course.

If water mixes with contaminated soil and becomes contaminated, the water shall be sampled and tested by a laboratory certified by the DHS. If levels of contamination are found to be hazardous, the water shall be handled and disposed of as hazardous waste.

**Concrete Waste**

The Contractor shall implement practices to prevent the discharge of portland cement concrete, AC, or HMA waste into storm drain systems or watercourses.

Portland cement concrete, AC, or HMA waste shall be collected at the following locations and disposed of:

A. Where concrete material, including grout, is used;
B. Where concrete dust and debris result from demolition;
C. Where sawcutting, coring, grinding, grooving, or hydro-concrete demolition of portland cement concrete, AC, or HMA creates a residue or slurry; or
D. Where concrete trucks or other concrete-coated equipment is cleaned at the construction site.

**Sanitary and Septic Waste**

Wastewater from sanitary or septic systems shall not be discharged or buried within the Department right of way. The WPCM shall inspect sanitary or septic waste storage and monitor disposal procedures at least weekly. Sanitary facilities that discharge to the sanitary sewer system shall be properly connected and free from leaks.

The Contractor shall obtain written approval from the local health agency, city, county, and sewer district before discharging from a sanitary or septic system directly into a sanitary sewer system, and provide a copy to the Engineer. The Contractor shall comply with local health agency requirements when using an on-site disposal system.

**Liquid Waste**

The Contractor shall not allow construction site liquid waste, including the following, to enter storm drain systems or watercourses:

A. Drilling slurries or fluids,
B. Grease-free or oil-free wastewater or rinse water,
C. Dredgings,
D. Liquid waste running off a surface including wash or rinse water, or
E. Other non-storm water liquids not covered by separate permits.

The Contractor shall hold liquid waste in structurally sound, leak proof containers such as:

A. Sediment traps,
B. Roll-off bins, or
C. Portable tanks.

Liquid waste containers shall be of sufficient quantity and volume to prevent spills and leaks. The containers shall be stored at least 50 feet from storm drains, watercourses, moving vehicles, and equipment.

The Contractor shall remove and dispose of deposited solids from sediment traps as provided in "Solid Waste" of these special provisions, unless determined infeasible by the Engineer.

Liquid waste may require testing to determine hazardous material content before disposal.

Drilling fluids and residue shall be disposed of outside the highway right of way. If the Engineer determines that an appropriate location is available, fluids and residue exempt under California Code of Regulations, Title 23, Section 2511(g) may be dried by infiltration and evaporation in a leak proof container. The remaining solid waste may be disposed of as provided in "Solid Waste" of these special provisions.

## NON-STORM WATER MANAGEMENT

### Water Control and Conservation

The Contractor shall prevent erosion or the discharge of pollutants into storm drain systems or watercourses by managing the water used for construction operations. The Contractor shall obtain the Engineer's approval before washing anything on the construction site with water that could discharge into a storm drain system or watercourse. Discharges shall be reported to the Engineer immediately.

The Contractor shall implement water conservation practices when water is used on the construction site. Irrigation areas shall be inspected and watering schedules shall be adjusted to prevent erosion, excess watering, or runoff. The Contractor shall shut off the water source to broken lines, sprinklers, or valves, and they shall be repaired as soon as possible. When possible, water from waterline flushing shall be reused for landscape irrigation. Paved areas shall be swept and vacuumed, not washed with water.

Construction water runoff, including water from water line repair, shall be directed to areas to infiltrate into the ground and shall not be allowed to enter storm drain systems or watercourses. Spilled water shall not be allowed to escape water truck filling areas. When possible, the Contractor shall direct water from off-site sources around the construction site, or shall minimize contact with the construction site.

### Illegal Connection and Discharge Detection and Reporting

The Contractor shall inspect the construction site and the site perimeter before beginning work for evidence of illegal connections, discharges, or dumping. Subsequently, the construction site and perimeter shall be inspected on a frequent, predetermined schedule.

The Contractor shall immediately notify the Engineer when illegal connections, discharges, or dumping are discovered. The Contractor shall take no further action unless directed by the Engineer. Unlabeled or unidentifiable material shall be assumed to be hazardous.

The Contractor shall look for the following evidence of illegal connections, discharges, or dumping:

A. Debris or trash piles,
B. Staining or discoloration on pavement or soils,
C. Pungent odors coming from drainage systems,
D. Discoloration or oily sheen on water,
E. Stains or residue in ditches, channels or drain boxes,
F. Abnormal water flow during dry weather,
G. Excessive sediment deposits,
H. Nonstandard drainage junction structures, or
I. Broken concrete or other disturbances near junction structures.

### Vehicle and Equipment Cleaning

The Contractor shall limit vehicle and equipment cleaning or washing on the construction site to that necessary to control vehicle tracking or hazardous waste. Vehicles and equipment shall not be cleaned on the construction site with soap, solvents, or steam until the Engineer has been notified. The resulting waste shall be contained and recycled, or disposed of as provided in "Liquid Waste" or "Hazardous Waste" of these special provisions, whichever is applicable. The Contractor shall not use diesel to clean vehicles or equipment, and shall minimize the use of solvents.

The Contractor shall clean or wash vehicles and equipment in a structure equipped with disposal facilities. If using a structure is not possible, vehicles and equipment shall be cleaned or washed in an outside area with the following characteristics:

A. Located at least 50 feet from storm drainage systems or watercourses,
B. Paved with AC, HMA, or portland cement concrete,
C. Surrounded by a containment berm, and
D. Equipped with a sump to collect and dispose of wash water.

When washing vehicles or equipment with water, the Contractor shall use as little water as possible. Hoses shall be equipped with a positive shutoff valve.

Wash racks shall discharge to a recycle system or to another system approved by the Engineer. Sumps shall be inspected regularly, and liquids and sediments shall be removed as needed.

### Vehicle and Equipment Fueling and Maintenance

The Contractor shall fuel or perform maintenance on vehicles and equipment off the construction site whenever practical. When fueling or maintenance must be done at the construction site, the Contractor shall designate a site, or sites, and obtain approval from the Engineer before using. The fueling or maintenance site shall be protected from storm water, shall be on level ground, and shall be located at least 50 feet from drainage inlets or watercourses. The WPCM shall inspect the fueling or maintenance site regularly. Mobile fueling or maintenance shall be kept to a minimum.

The Contractor shall use containment berms or dikes around the fueling and maintenance area. Adequate amounts of absorbent spill cleanup material and spill kits shall be kept in the fueling and maintenance area and on fueling trucks. Spill cleanup material and kits shall be disposed of immediately after use. Drip pans or absorbent pads shall be used during fueling or maintenance unless performed over an impermeable surface.

Fueling or maintenance operations shall not be left unattended. Fueling nozzles shall be equipped with an automatic shutoff control. Vapor recovery fueling nozzles shall be used where required by the Air Quality Management District. Nozzles shall be secured upright when not in use. Fuel tanks shall not be topped-off.

The Contractor shall recycle or properly dispose of used batteries and tires.

### Material and Equipment Used Over Water

Drip pans and absorbent pads shall be placed under vehicles or equipment used over water, and an adequate supply of spill cleanup material shall be kept with the vehicle or equipment. Drip pans or plastic sheeting shall be placed under vehicles or equipment on docks, barges, or other surfaces over water when the vehicle or equipment will be idle for more than one hour.

The Contractor shall provide watertight curbs or toe boards on barges, platforms, docks, or other surfaces over water to contain material, debris, and tools. Material shall be secured to prevent spills or discharge into water due to wind.

### Structure Removal Over or Adjacent to Water

The Contractor shall not allow demolished material to enter storm water systems or watercourses. The Contractor shall use covers and platforms approved by the Engineer to collect debris. Attachments shall be used on equipment to catch debris on small demolition operations. Debris catching devices shall be emptied regularly and debris shall be handled as provided in "Waste Management" of these special provisions.

The WPCM shall inspect demolition sites within 50 feet of storm water systems or watercourses every day.

### Paving, Sealing, Sawcutting, and Grinding Operations

The Contractor shall prevent the following material from entering storm drain systems or water courses:

A. Cementitious material,
B. Asphaltic material,
C. Aggregate or screenings,
D. Grinding or sawcutting residue,
E. Pavement chunks, or
F. Shoulder backing.

The Contractor shall cover drainage inlets and use linear sediment barriers to protect downhill watercourses until paving, sealing, sawcutting, or grinding operations are completed and excess material has been removed. Drainage inlets and manholes shall be covered during the application of seal coat, tack coat, slurry seal, or fog seal.

During the rainy season or when precipitation is predicted, paving, sawcutting, and grinding operations shall be limited to places where runoff can be captured. Seal coat, tack coat, slurry seal, or fog seal operations shall not begin if precipitation is predicted for the application or the curing period. The Contractor shall not excavate material from existing roadways during precipitation.

The Contractor shall vacuum up slurry from sawcutting operations immediately after the slurry is produced. Slurry shall not be allowed to run onto lanes open to public traffic or off the pavement.

The Contractor shall collect residue from portland cement concrete grinding operations with a vacuum attachment on the grinding machine. The residue shall not be left on the pavement or allowed to flow across the pavement.

Material excavated from existing roadways may be stockpiled as provided in "Stockpile Management" of these special provisions if approved by the Engineer. AC or HMA chunks used in embankment shall be placed above the water table and covered by at least one foot of material.

Substances used to coat asphalt trucks and equipment shall not contain soap, foaming agents, or toxic chemicals.

### Thermoplastic Striping and Pavement Markers

Thermoplastic striping and preheating equipment shutoff valves shall work properly at all times when on the construction site. The Contractor shall not preheat, transfer, or load thermoplastic within 50 feet of drainage inlets or watercourses. The Contractor shall not fill the preheating container to more than 6 inches from the top. Truck beds shall be cleaned daily of scraps or melted thermoplastic.

The Contractor shall not unload, transfer, or load bituminous material for pavement markers within 50 feet of drainage inlets or watercourses. All pressure shall be released from melting tanks before removing the lid to fill or service. Melting tanks shall not be filled to more than 6 inches from the top.

The Contractor shall collect bituminous material from the roadway after marker removal.

### Pile Driving

The Contractor shall keep spill kits and cleanup material at pile driving locations. Pile driving equipment shall be parked over drip pans, absorbent pads, or plastic sheeting where possible. When not in use, pile driving equipment shall be stored at least 50 feet from concentrated flows of storm water, drainage courses, or inlets. The Contractor shall protect pile driving equipment by parking it on plywood and covering it with plastic when precipitation is predicted. The WPCM shall inspect the pile driving area every day for leaks and spills.

The Contractor shall use vegetable oil instead of hydraulic fluid when practical.

### Concrete Curing

The Contractor shall not overspray chemical curing compound. Drift shall be minimized by spraying as close to the concrete as possible. Drainage inlets shall be covered before applying curing compound.

The Contractor shall minimize the use and discharge of water by using wet blankets or similar methods to maintain moisture when curing concrete.

### Concrete Finishing

The Contractor shall collect and dispose of water and solid waste from high-pressure water blasting. Drainage inlets within 50 feet shall be covered before sandblasting. The nozzle shall be kept as close to the surface of the concrete as possible to minimize drift of dust and blast material. Blast residue may contain hazardous material.

Containment structures for concrete finishing operations shall be inspected for damage before each day of use and before predicted precipitation. Liquid and solid waste shall be removed from the containment structure after each work shift.

## DEWATERING

Dewatering shall consist of discharging accumulated storm water, ground water, or surface water from excavations or temporary containment facilities. The Contractor shall discharge water within the limits of the project.

Dewatering discharge shall not cause erosion, scour, or sedimentary deposits that impact natural bedding materials.

The Contractor shall conduct dewatering activities in accordance with the Field Guide for Construction Dewatering available at:

http://www.dot.ca.gov/hq/construc/stormwater/manuals.htm

Before dewatering the Contractor shall submit a Dewatering and Discharge Plan to the Engineer in conformance with the provisions in Section 5-1.02, "Plans and Working Drawings," of the Standard Specifications and "Water Pollution Control," of these special provisions. At a minimum, the Dewatering and Discharge Plan shall include the following:

A. A title sheet and table of contents;
B. A description of the dewatering and discharge operations detailing the locations, quantity of water, equipment, and discharge point;
C. The estimated schedule for dewatering and discharge (begin and end dates, intermittent or continuous);
D. Discharge alternatives such as dust control or percolation; and
E. Visual monitoring procedures with inspection log.

The Contractor shall not discharge storm water or non-storm water that has an odor, discoloration other than sediment, an oily sheen, or foam on the surface and shall notify the Engineer immediately upon discovery.

If water cannot be discharged within the project limits due to site constraints it shall be disposed of in the same manner specified for material in Section 7-1.13, "Disposal of Material Outside the Highway Right of Way," of the Standard Specifications.

### PAYMENT

The contract lump sum price paid for construction site management shall include full compensation for furnishing all labor, materials, tools, equipment, and incidentals and for doing all the work involved in spill prevention and control, material management, waste management, non-storm water management, and dewatering and identifying, sampling, testing, handling, and disposing of hazardous waste, as specified in the Standard Specifications and these special provisions, and as directed by the Engineer.

## 10-1.05 STREET SWEEPING

Street sweeping shall be conducted where sediment is tracked from the job site onto paved roads, as described in the approved Storm Water Pollution Prevention Plan (SWPPP) in accordance with "Water Pollution Control" of these special provisions, and as directed by the Engineer.

Street sweeping shall be one of the water pollution control practices for sediment control. The SWPPP shall include the use of street sweeping. Street sweeping shall be performed in accordance with Section 4, SC-7 in the Construction Site Best Management Practices Manual of the Caltrans Storm Water Quality Handbooks.

The number of street sweepers shall be as designated in the approved SWPPP. The Contractor shall maintain at least one sweeper on the job site at all times during the period that sweeping work is required. Sweepers shall be self-loading, motorized, and shall have spray nozzles. Sweepers may include a vacuum apparatus.

Street sweeping shall start at the beginning of clearing and grubbing and shall continue until completion of the project, or as directed by the Engineer. Street sweeping shall be performed immediately after soil disturbing activities occur or offsite tracking of material is observed. Street sweeping shall be performed so that dust is minimized. If dust generation is excessive or sediment pickup is ineffective as determined by the Engineer, the use of water or a vacuum will be required.

At the option of the Contractor, collected material may be temporarily stockpiled in accordance with the approved SWPPP. Collected material shall be disposed of at least once per week.

Material collected during street sweeping operations shall be disposed of in conformance with Section 7-1.13, "Disposal of Material Outside The Highway Right Of Way," of the Standard Specifications.

### MEASUREMENT AND PAYMENT

The contract lump sum price paid for street sweeping shall include full compensation for furnishing all labor, materials, tools, equipment, and incidentals and for doing all the work involved in street sweeping, including disposal of collected material, as shown on the plans, as specified in the Standard Specifications, these special provisions, and as directed by the Engineer.

## 10-1.06 TEMPORARY CONCRETE WASHOUT FACILITY

Temporary concrete washout facilities shall be constructed, maintained, and later removed at the locations shown on the approved Storm Water Pollution Prevention Plan (SWPPP) in conformance with "Water Pollution Control" of these special provisions, and in conformance with details shown on the plans and these special provisions.

Temporary concrete washout facilities shall be one of the water pollution control practices for waste management and materials pollution control. The SWPPP shall include the use of temporary concrete washout facilities.

### MATERIALS

#### Plastic Liner

Plastic liners shall be single ply, new polyethylene sheeting, a minimum of 10 mils thick and shall be free of holes, punctures, tears or other defects that compromise the impermeability of the material. Plastic liners shall not have seams or overlapping joints.

#### Gravel-filled Bags

Gravel bag fabric shall be nonwoven polypropylene geotextile (or comparable polymer) and shall conform to the following requirements:

| Specification | Requirements |
|---|---|
| Weight per unit area, ounces per square yard, min.<br>ASTM Designation: D 5261 | 8.0 |
| Grab tensile strength (one inch grip), kilonewtons, min.<br>ASTM Designation: D 4632* | 205 |
| Ultraviolet stability, percent tensile strength retained after 500 hours,<br>ASTM Designation: D 4355, xenon arc lamp method | 70 |

* or appropriate test method for specific polymer

Gravel bags shall be between 24 inches and 32 inches in length, and between 16 inches and 20 inches in width.

Yarn used for binding gravel bags shall be as recommended by the manufacturer or bag supplier and shall be of a contrasting color.

Gravel shall be between 3/8 inch and 3/4 inch in diameter, and shall be clean and free from clay balls, organic matter, and other deleterious materials.

The opening of gravel-filled bags shall be secured to prevent gravel from escaping. Gravel-filled bags shall be between 30 pounds and 50 pounds in weight.

**Straw Bales**

Straw for straw bales shall conform to the provisions in Section 20-2.06, "Straw," of the Standard Specifications.

Straw bales shall be a minimum of 14 inches in width, 18 inches in height, 36 inches in length and shall have a minimum weight of 50 pounds. The straw bale shall be composed entirely of vegetative matter, except for binding material.

Straw bales shall be bound by either wire, nylon or polypropylene string. Jute or cotton binding shall not be used. Baling wire shall be a minimum of 16 gage in diameter. Nylon or polypropylene string shall be approximately 0.08-inch in diameter with 80 pounds of breaking strength.

**Stakes**

Stakes shall be wood or metal. Wood stakes shall be untreated fir, redwood, cedar, or pine and cut from sound timber. They shall be straight and free of loose or unsound knots or other defects which would render them unfit for the purpose intended. Wood stakes shall be a minimum 2" x 2" in size. Metal stakes may be used as an alternative, and shall be a minimum of 0.5-inch in diameter. Stakes shall be a minimum of 4 feet in length. The tops of the metal stakes shall be bent at a 90-degree angle or capped with an orange or red plastic safety cap that fits snugly to the metal stake. The Contractor shall submit a sample of the metal stake and plastic cap, if used, for the Engineer's approval before installation.

**Staples**

Staples shall be as shown on the plans. An alternative attachment device such as geotextile pins or plastic pegs may be used instead of staples. The Contractor shall submit a sample of the alternative attachment device for the Engineer's approval before installation.

**Signs**

Wood posts for signs shall conform to the provisions in Section 56-2.02B, "Wood Posts," of the Standard Specifications. Lag screws shall conform to the provisions in Section 56-2.02D, "Sign Panel Fastening Hardware," of the Standard Specifications.

Plywood shall be freshly painted for each installation with not less than 2 applications of flat white paint. Sign letters shown on the plans shall be stenciled with commercial quality exterior black paint. Testing of paint will not be required.

**INSTALLATION**

Temporary concrete washout facilities shall be as follows:

1. Temporary concrete washout facilities shall be installed before beginning placement of concrete and located a minimum of 50 feet from storm drain inlets, open drainage facilities, and water courses unless determined infeasible by the Engineer. Temporary concrete washout facilities shall be located away from construction traffic or access areas at a location determined by the Contractor and approved by the Engineer.
2. A sign shall be installed adjacent to each washout facility at a location determined by the Contractor and approved by the Engineer. Signs shall be installed in conformance with the provisions in Section 56-2.03, "Construction," and Section 56-2.04, "Sign Panel Installation," of the Standard Specifications.

3. The length and width of a temporary concrete washout facility may be increased from the minimum dimensions shown on the plans upon approval of the Engineer.
4. Temporary concrete washout facilities shall be constructed in sufficient quantity and size to contain liquid and concrete waste generated by washout operations for concrete wastes. These facilities shall be constructed to contain liquid and concrete waste without seepage, spills, or overflow.
5. Berms for below grade temporary concrete washout facilities shall be constructed from compacted native material. Gravel may be used in conjunction with compacted native material.
6. A plastic liner shall be installed in below grade temporary concrete washout facilities.

Details for an alternative temporary concrete washout facility shall be submitted to the Engineer for approval at least 7 days before installation.

When temporary concrete washout facilities are no longer required for the work, as determined by the Engineer, the hardened concrete and liquid residue shall be removed and disposed of in conformance with the provisions in Section 15-3.02, "Removal Methods," of the Standard Specifications. Temporary concrete washout facilities shall be disposed of in conformance with the provisions in Section 7-1.13, "Disposal of Material Outside the Highway Right of Way," of the Standard Specifications.

Ground disturbance, including holes and depressions, caused by the installation and removal of the temporary concrete washout facilities shall be backfilled and repaired in conformance with the provisions in Section 15-1.02, "Preservation of Property," of the Standard Specifications.

### MAINTENANCE

Temporary concrete washout facilities shall be maintained to provide adequate holding capacity with a minimum freeboard of 12 inches. Maintaining temporary concrete washout facilities shall include removing and disposing of hardened concrete and returning the facilities to a functional condition. Hardened concrete materials shall be removed and disposed of in conformance with the provisions in Section 15-3.02, "Removal Methods," of the Standard Specifications. Holes, rips, and voids in the plastic liner shall be patched and repaired by taping or the plastic liner shall be replaced. The plastic liner shall be replaced when patches or repairs compromise the impermeability of the material as determined by the Engineer.

Gravel bags shall be replaced when the bag material is ruptured or when the yarn has failed, allowing the bag contents to spill out.

Temporary concrete washout facilities shall be repaired or replaced on the same day the damage occurs. Damage to temporary concrete washout facilities resulting from the Contractor's vehicles, equipment, or operations shall be repaired at the Contractor's expense.

### MEASUREMENT AND PAYMENT

Quantities of temporary concrete washout facilities will be measured as units determined from actual count in place.

The contract unit price paid for temporary concrete washout facility shall include full compensation for furnishing all labor, materials, tools, equipment and incidentals, and for doing all the work involved in constructing a temporary concrete washout facility, complete in place, including excavation and backfill, maintenance, and removal, as shown on the plans, as specified in the Standard Specifications and these special provisions, and as directed by the Engineer.

## 10-1.07 TEMPORARY SILT FENCE

Temporary silt fence shall be furnished, installed, maintained, and later removed at the locations shown on the approved Storm Water Pollution Prevention Plan (SWPPP) in conformance with "Water Pollution Control" of these special provisions, and in conformance with details shown on the plans and these special provisions.

Temporary silt fence shall be one of the water pollution control practices for sediment control. The SWPPP shall include the use of temporary silt fence.

### MATERIALS

Temporary silt fence shall be either prefabricated or constructed with silt fence fabric, posts, and fasteners.

#### Silt Fence Fabric

Silt fence fabric shall be geotextile manufactured from woven polypropylene or polymer material. Silt fence fabric may be virgin, recycled, or a combination of virgin and recycled polymer materials. No virgin or recycled polymer materials shall contain biodegradable filler materials that can degrade the physical or chemical characteristics of the finished fabric. The Engineer may order tests to confirm the absence of biodegradable filler materials in conformance to the requirements in ASTM Designation: E 204 (Fourier Transformed Infrared Spectroscopy-FTIR).

Silt fence fabric shall conform to the following requirements:

| Specification | Requirements |
|---|---|
| Width, inches, min. | 36 |
| Grab tensile strength (one inch grip), pounds, min. in each direction<br>ASTM Designation: D 4632* | 124 |
| Elongation, percent minimum in each direction<br>ASTM Designation: D 4632* | 15 |
| Permittivity, 1/sec., min.<br>ASTM Designation: D 4491 | 0.05 |
| Flow rate, gallons per minute per square foot, min.<br>ASTM Designation: D 4491 | 10 |
| Ultraviolet stability, percent tensile strength retained after 500 hours, min.<br>ASTM Designation: D 4355 (xenon-arc lamp and water spray weathering method) | 70 |

* or appropriate test method for specific polymer

**Posts**

Posts for temporary silt fence shall be one of the following:

1. Untreated fir or pine, a minimum of 2" x 2" in size, and 4 feet in length. One end of the post shall be pointed.
2. Steel and have a "U," "T," "L," or other cross sectional shape that can resist failure from lateral loads. The steel posts shall have a minimum weight of 0.8-pound per foot and a minimum length of 4 feet. One end of the steel posts shall be pointed and the other end shall be capped with an orange or red plastic safety cap which fits snugly to the steel post. The Contractor shall submit to the Engineer for approval a sample of the capped steel post before installation.

**Fasteners**

Fasteners for attaching silt fence fabric to posts shall be as follows:

1. When prefabricated silt fence is used, posts shall be inserted into sewn pockets.
2. Silt fence fabric shall be attached to wooden posts with nails or staples as shown on the plans or as recommended by the manufacturer or supplier. Tie wire or locking plastic fasteners shall be used to fasten the silt fence fabric to steel posts. Maximum spacing of fasteners shall be 8 inches along the length of the steel post.

**INSTALLATION**

Temporary silt fence shall be installed parallel with the slope contour in reaches not to exceed 500 feet. A reach is considered a continuous run of temporary silt fence from end to end or from an end to an opening, including joined panels. Each reach shall be constructed so that the elevation at the base of the fence does not deviate from the contour more than 1/3 of the fence height.

The silt fence fabric shall be installed on the side of the posts facing the slope. The silt fence fabric shall be anchored in a trench as shown on the plans. The trench shall be backfilled and mechanically or hand tamped to secure the silt fence fabric in the bottom of the trench.

Mechanically pushing 12 inches of the silt fence fabric vertically through the soil may be allowed if the Contractor can demonstrate to the Engineer that the silt fence fabric will not be damaged and will not slip out of the soil resulting in sediment passing under the silt fence fabric.

The maximum post spacing may be increased to 10 feet if the fence is reinforced by a wire or plastic material by prefabrication or by field installation. The field-assembled reinforced temporary silt fence shall be able to retain saturated sediment without collapsing.

Temporary silt fence shall be joined as shown on the plans. The tops of the posts shall be tied together by minimum of 2 wraps of tie wire of a minimum 16-gage diameter. The silt fence fabric shall be attached to the posts at the joint as specified in these special provisions.

When no longer required as determined by the Engineer, temporary silt fence shall be removed and disposed of in conformance with the provisions in Section 7-1.13, "Disposal of Material Outside the Highway Right of Way," of the Standard Specifications. Trimming the silt fence fabric and leaving it in place will not be allowed.

Ground disturbance, including holes and depressions, caused by the installation and removal of the temporary silt fence shall be backfilled and repaired in conformance with the provisions in Section 15-1.02, "Preservation of Property," of the Standard Specifications.

**MAINTENANCE**

Temporary silt fence shall be maintained to provide a sediment holding capacity of approximately 1/3 the height of the silt fence fabric above ground. When sediment exceeds this height or when directed by the Engineer, sediment shall be removed. The removed sediment shall be deposited within the project limits so that the sediment is not subject to erosion by wind or by water.

Temporary silt fence shall be repaired or replaced the same day the damage occurs. Damage to the temporary silt fence resulting from the Contractor's vehicles, equipment, or operations shall be repaired at the Contractor's expense.

**MEASUREMENT AND PAYMENT**

Quantities of temporary silt fence to be paid for will be determined by the linear foot, measured parallel with the ground slope along the line of the installed temporary silt fence, deducting the widths of openings.

The contract price paid per linear foot for temporary silt fence shall include full compensation for furnishing all labor, materials, tools, equipment, and incidentals, and for doing all the work involved in installing temporary silt fence, complete in place, including trench excavation and backfill, maintenance, and removal, as shown on the plans, as specified in the Standard Specifications and these special provisions, and as directed by the Engineer.

## 10-1.08 TEMPORARY FENCE AND GATE (TYPE CL-6)

Temporary fence (Type CL-6) and temporary gate (Type CL-6) shall be furnished, constructed, maintained, and later removed as shown on the plans, as specified in these special provisions and as directed by the Engineer. Temporary fence (Type CL-6) shall be used at the off-ramp from Route 280 as shown on the plans to exclude the public from the site during the period of closure.

Except as otherwise specified in this section, temporary fence (Type CL-6) and temporary gate (Type CL-6) shall conform to the plan details and the specifications for permanent fence of similar character as provided in Section 80, "Fences," of the Standard Specifications.

Used materials may be installed provided the used materials are good, sound and are suitable for the purpose intended, as determined by the Engineer.

Materials may be commercial quality provided the dimensions and sizes of the materials are equal to, or greater than, the dimensions and sizes shown on the plans or specified herein.

Posts shall be either metal or wood at the Contractor's option.

Temporary gate posts shall be metal.

Galvanizing and painting of steel items will not be required.

Treating wood with a wood preservative will not be required.

Temporary fence (Type CL-6) and temporary gate (Type CL-6) that is damaged during the progress of the work shall be repaired or replaced by the Contractor at the Contractor's expense.

When no longer required for the work, as determined by the Engineer, temporary fence (Type CL-6) and temporary gate (Type CL-6) shall be removed. Removed facilities shall become the property of the Contractor and shall be removed from the site of the work, except as otherwise provided in this section.

Removed temporary fence (Type CL-6) and temporary gate (Type CL-6) materials that are not damaged may be constructed in the permanent work provided the materials conform to the requirements specified for the permanent work and such materials are new when used for the temporary fence.

Holes caused by the removal of temporary fence (Type CL-6) and temporary gate (Type CL-6) shall be backfilled in conformance with the provisions in the second paragraph of Section 15-1.02, "Preservation of Property," of the Standard Specifications.

The various types and kinds of temporary fence will be measured and paid for in the same manner specified for permanent fence of similar character as provided in Section 80, "Fences," of the Standard Specifications.

The various types and kinds of temporary gate will be measured and paid for in the same manner specified for permanent gate of similar character as provided in Section 80, "Fences," of the Standard Specifications.

Full compensation for maintaining, removing, and disposing of temporary fence shall be considered as included in the contract prices paid per linear foot for the various types of temporary fence and no additional compensation will be allowed therefor.

Full compensation for maintaining, removing, and disposing of temporary gate shall be considered as included in the contract unit price paid for the various types of temporary gate and no additional compensation will be allowed therefor.

## 10-1.09 TEMPORARY FENCE (TYPE ESA)

Temporary fence (Type ESA) shall be furnished, installed, maintained, and later removed in conformance with the details shown on the plans, as specified in these special provisions and as directed by the Engineer.

## MATERIALS

Used materials may be installed provided the used materials conform to these special provisions.

### High Visibility Fabric

High visibility fabric shall be machine produced, orange colored mesh manufactured from polypropylene or polyethylene. High visibility fabric may be made of recycled materials. Materials shall not contain biodegradable filler materials that can degrade the physical or chemical characteristics of the finished fabric. High visibility fabric shall be fully stabilized ultraviolet resistant, shall be a minimum of 4 feet in width with a maximum mesh opening of 2" x 2". High visibility fabric shall be furnished in one continuous width and shall not be spliced to conform to the specified width dimension.

### Posts

Posts for temporary fence (Type ESA) shall be of one of the following:

A. Wood posts shall be fir or pine, shall have a minimum cross section of 2" x 2", and a minimum length of 5.25 feet. The end of the post to be embedded in the soil shall be pointed. Wood posts shall not be treated with wood preservative.
B. Steel posts shall have a "U," "T," "L," or other cross sectional shape that resists failure from lateral loads. Steel posts shall have a minimum weight of 0.75 pounds per linear foot and a minimum length of 5.25 feet. One end of the steel post shall be pointed and the other end shall have a high visibility colored top.

### Fasteners

Fasteners for attaching high visibility fabric to the posts shall be as follows:

A. The high visibility fabric shall be attached to wooden posts with commercial quality nails or staples, or as recommended by the manufacturer or supplier.
B. Tie wire or locking plastic fasteners shall be used for attaching the high visibility fabric to steel posts. Maximum spacing of tie wire or fasteners shall be 24 inches along the length of the steel post.

## INSTALLATION

Temporary fence (Type ESA) shall be installed as follows:

A. All fence construction activities shall be conducted from outside the ESA as shown on the plans or as staked .
B. Posts shall be embedded in the soil a minimum of 16 inches. Post spacing shall be 8 feet maximum from center to center and shall at all times support the fence in a vertical position.
C. Temporary fence (Type ESA) shall be constructed prior to clearing and grubbing work, shall enclose the foliage canopy (drip line) of protected plants, and shall not encroach upon visible roots of the plants.

When Type ESA temporary fence is no longer required, as determined by the Engineer, the temporary fence shall be removed and disposed of in conformance with the provisions in Section 7-1.13, "Disposal of Material Outside the Highway Right of Way," of the Standard Specifications, except when reused as provided in this section.

Holes caused by the removal of temporary fence (Type ESA) shall be backfilled in conformance with the provisions in Section 15-1.02, "Preservation of Property," of the Standard Specifications.

## MAINTENANCE

Temporary fence (Type ESA) that is damaged during the progress of the work shall be repaired or replaced by the Contractor the same day the damage occurs.

## MEASUREMENT AND PAYMENT

Temporary fence (Type ESA) shall be measured and paid for in the same manner specified for fence (Type BW or WM, wood or metal posts) as provided in Section 80, "Fences," of the Standard Specifications.

Full compensation for maintaining, removing, and disposing of temporary fence (Type ESA) shall be considered as included in the contract price paid per linear foot for temporary fence (Type ESA) and no additional compensation will be allowed therefor.

## 10-1.10 TEMPORARY CONSTRUCTION ENTRANCE

Temporary construction entrances shall be constructed, maintained, and later removed at the locations shown on the approved Storm Water Pollution Prevention Plan (SWPPP) in conformance with "Water Pollution Control" of these special provisions, and in conformance with details shown on the plans and these special provisions.

Temporary construction entrances shall be one of the water pollution control practices for tracking control. The SWPPP shall include the use of temporary construction entrances.

Temporary construction entrances shall be either Type 1 or Type 2.

### MATERIALS

#### Temporary Entrance Fabric

Temporary entrance fabric shall be manufactured from polyester, nylon, or polypropylene material, or any combination thereof. Temporary entrance fabric shall be a nonwoven, needle-punched fabric, free of needles which may have broken off during the manufacturing process. Temporary entrance fabric shall be permeable and shall not act as a wicking agent.

Temporary entrance fabric shall be manufactured from virgin, recycled, or a combination of virgin and recycled polymer materials. No virgin or recycled materials shall contain biodegradable filler materials that can degrade the physical or chemical characteristics of the finished fabric. The Engineer may order tests to confirm the absence of biodegradable filler materials in conformance to the requirements in ASTM Designation: E 204 (Fourier Transformed Infrared Spectroscopy-FTIR).

Temporary entrance fabric shall conform to the following requirements:

| Specification | Requirements |
|---|---|
| Weight per unit area, ounces per square yard, min.<br>ASTM Designation: D 5261 | 6.5 |
| Grab tensile strength (one inch grip), pounds, min.<br>ASTM Designation: D 4632* | 200 |
| Elongation at break, percent min.<br>ASTM Designation: D 4632* | 50 |
| Toughness, pounds, min.<br>(percent elongation x grab tensile strength) | 12,000 |

* or appropriate test method for specific polymer

#### Rocks

Rocks shall conform to the material quality requirements in Section 72-2.02, "Materials," of the Standard Specifications for shape and for apparent specific gravity, absorption, and durability index. Rocks used for the temporary entrance shall conform to the following sizes:

| Square Screen Size (inch) | Percentage Passing | Percentage Retained |
|---|---|---|
| 6 | 100 | 0 |
| 3 | 0 | 100 |

#### Corrugated Steel Panels

Corrugated steel panels shall be prefabricated and shall be pressed or shop welded, with a slot or hooked section to facilitate coupling at the ends of the panels.

### INSTALLATION

Temporary construction entrances shall be installed as follows:

1. Before placing the temporary entrance fabric, the areas shall be cleared of all trash and debris. Vegetation shall be removed to the ground level. Trash, debris, and removed vegetation shall be disposed of in conformance with the provisions in Section 7-1.13, "Disposal of Material Outside the Highway Right of Way," of the Standard Specifications.
2. A sump shall be constructed within 20 feet of each temporary construction entrance as shown on the plans.

3. Before placing the temporary entrance fabric, the ground shall be graded to a uniform plane. The relative compaction of the top 1.5 feet shall be not less than 90 percent. The ground surface shall be free of sharp objects that may damage the temporary entrance fabric, and shall be graded to drain to the sump as shown on the plans.
4. Temporary entrance fabric shall be positioned longitudinally along the alignment of the entrance, as directed by the Engineer.
5. The adjacent ends of the fabric shall be overlapped a minimum length of 12 inches.
6. Rocks to be placed directly over the fabric shall be spread in the direction of traffic, longitudinally and along the alignment of the temporary construction entrance.
7. During spreading of the rocks, vehicles or equipment shall not be driven directly on the fabric. A layer of rocks a minimum 6 inches thick shall be placed between the fabric and the spreading equipment to prevent damage to the fabric.
8. For Type 2 temporary construction entrances, a minimum of 6 coupled panel sections shall be installed for each temporary construction entrance. Before installing the panels, the ground surface shall be cleared of all debris to ensure uniform contact with the ground surface.

Fabric damaged during rock placement shall be repaired by placing a new piece of fabric over the damaged area. The piece of fabric shall be large enough to cover the damaged area and provide a minimum 18-inch overlap on all edges.

Details for a proposed alternative temporary construction entrance or alternative sump shall be submitted to the Engineer for approval at least 7 days before installation. The Contractor may eliminate the sump if approved in writing by the Engineer.

When no longer required as determined by the Engineer, temporary construction entrances shall be removed and disposed of in conformance with the provisions in Section 7-1.13, "Disposal of Material Outside the Highway Right of Way," of the Standard Specifications.

Ground disturbance, including holes and depressions, caused by the installation and removal of the temporary construction entrance, including the sumps, shall be backfilled and repaired in conformance with the provisions in Section 15-1.02, "Preservation of Property," of the Standard Specifications.

While the temporary construction entrance is in use, pavement shall be cleaned and sediment removed at least once a day, and as often as necessary when directed by the Engineer. Soil and sediment or other extraneous material tracked onto existing pavement shall not be allowed to enter drainage facilities.

**MAINTENANCE**

The Contractor shall maintain temporary construction entrances throughout the contract or until removed. The Contractor shall prevent displacement or migration of the rock surfacing or corrugated steel panels. Significant depressions resulting from settlement or heavy equipment shall be repaired by the Contractor as directed by the Engineer.

Temporary construction entrances shall be maintained to minimize tracking of soil and sediment onto existing public roads.

If buildup of soil and sediment deter the function of the temporary construction entrance, the Contractor shall immediately remove and dispose of the soil and sediment, and install additional corrugated steel panels and spread additional rocks to increase the capacity of the temporary construction entrance.

Temporary construction entrances shall be repaired or replaced on the same day the damage occurs. Damage to the temporary construction entrance resulting from the Contractor's vehicles, equipment, or operations shall be repaired at the Contractor's expense.

**MEASUREMENT AND PAYMENT**

Quantities of temporary construction entrances will be determined from actual count in place.

The contract unit price paid for temporary construction entrance shall include full compensation for furnishing all labor, materials, tools, equipment, and incidentals, and for doing all the work involved in constructing temporary construction entrance, complete in place, including excavation, backfill, and removal, as shown on the plans, as specified in the Standard Specifications and these special provisions, and as directed by the Engineer.

The cost of maintaining the temporary construction entrance will be borne equally by the State and the Contractor. The division of cost will be made be determining the cost of maintaining temporary construction entrance in conformance with the provisions in Section 9-1.03, "Force Account Payment," of the Standard Specifications and paying to the Contractor one-half of that cost.

Cleanup, repair, removal, disposal, or replacement due to improper installation or the Contractor's negligence will not be considered as included in the cost for performing maintenance.

## 10-1.11 TEMPORARY DRAINAGE INLET PROTECTION

Temporary drainage inlet protection shall be constructed, maintained, and removed at the locations shown on the approved Storm Water Pollution Prevention Plan (SWPPP) in accordance with "Water Pollution Control" of these special provisions, and in accordance with the details shown on the plans and these special provisions.

Temporary drainage inlet protection shall be one of the water pollution control practices for sediment control. The SWPPP shall include the use of temporary drainage inlet protection.

The Contractor shall select the appropriate drainage inlet protection in accordance with the details to meet the conditions around the drainage inlet. Throughout the duration of the contract, the Contractor shall provide protection to meet the changing conditions around the drainage inlet.

Temporary drainage inlet protection shall be Type 1, 3A, 3B, 4A, and 5.

### MATERIALS

#### Erosion Control Blanket

The erosion control blanket shall be a rolled erosion control product (RECP) and shall be classified either as temporary and degradable or long-term and nondegradable, and shall conform to one of the following:

A. Temporary and degradable:

1. Machine produced mats consisting of curled wood excelsior with 80 percent of the fiber 6 inches or longer. The excelsior blanket shall be of consistent thickness with wood fiber evenly distributed over the entire area of the blanket. The top surface of the blanket shall be covered with extruded photodegradable plastic netting or lightweight nonsynthetic netting. The blanket shall be smolder resistant without the use of chemical additives and shall be nontoxic and noninjurious to plant and animal life. The excelsior blanket shall be furnished in rolled strips with a minimum weight per unit area of 11.8 ounces per square yard.
2. Machine produced mats consisting of 70 percent straw and 30 percent coconut fiber with extruded photodegradable plastic netting or lightweight nonsynthetic netting on the top and bottom surfaces of the blanket. The straw and coconut shall adhere to the netting using thread or glue strip. The straw and coconut blanket shall be of consistent thickness, and straw and coconut fiber shall be evenly distributed over the entire area of the blanket. The straw and coconut fiber blanket shall be furnished in rolled strips with a minimum weight of 8.0 ounces per square yard.
3. Machine produced mats that are 100 percent coir consisting of coconut fiber with extruded photodegradable plastic netting or lightweight nonsynthetic netting on the top and bottom surfaces of the blanket. The coconut fiber shall adhere to the netting using thread or glue strip. The coconut blanket shall be of consistent thickness, with coconut fiber evenly distributed over the entire area of the blanket. The coconut fiber blanket shall be furnished in rolled strips with a minimum weight of 8.0 ounces per square yard.
4. Machine woven netting that is 100 percent spun coir consisting of coconut fiber with an average open area of 63 percent to 70 percent. Coconut coir netting shall be furnished in rolled strips with a minimum weight of 11.8 ounces per square yard.

B. Long-term and nondegradable:

1. Geotextile blanket shall conform to the provisions for rock slope protection fabric (Type A) in Section 88-1.04, "Rock Slope Protection Fabric," of the Standard Specifications.

#### Staples

Staples shall be as shown on the plans. An alternative attachment device such as geotextile pins or plastic pegs may be used instead of staples. The Contractor shall submit a sample of the alternative attachment device for the Engineer's approval before installation.

#### Rocks

Rocks shall conform to the requirements in Section 72-2.02, "Materials," of the Standard Specifications except that grading shall conform to the following sizes:

| Square Screen Size (inch) | Percentage Passing | Percentage Retained |
|---|---|---|
| 6 | 100 | 0 |
| 3 | 0 | 100 |

**Fiber Roll**

A fiber roll shall be one of the following:

A. Constructed with a premanufactured blanket made of one material or a combination of materials consisting of wood excelsior, rice or wheat straw, or coconut fibers. The blanket shall be between 6 feet and 8 feet in width and between 65 feet and 95 feet in length. Wood excelsior shall be individual fibers, of which 80 percent shall be 6 inches or longer in length. The blanket shall have a photodegradable plastic netting or biodegradable jute, sisal, or coir fiber netting on at least one side. The blanket shall be rolled along the width and secured with jute twine spaced 6 feet apart along the full length of the roll and placed 6 inches from the ends of each roll. The finished roll shall be between 8 inches and 10 inches in diameter, between 10 feet and 20 feet in length, and shall weigh at least 0.5 pound per linear foot. More than one blanket may be required to achieve the finished roll diameter. When more than one blanket is required, blankets shall be jointed longitudinally with an overlap of 6 inches along the length of the blanket.

B. A premanufactured roll of rice or wheat straw, wood excelsior, or coconut fiber encapsulated within a photodegradable plastic or biodegradable jute, sisal, or coir fiber netting. The rolls shall be between 8 inches and 10 inches in diameter, between 10 feet and 20 feet in length, and shall weigh at least 1.1 pounds per linear foot. The netting shall have a minimum durability of one year after installation. The netting shall be secured tightly at each end of the roll.

**Wood Stakes**

Wood stakes shall be a minimum of 1" x 1" x 24" in size for Type 1 installation, or shall be a minimum of 1" x 2" x 24" in size for Type 2 installation. Wood stakes shall be untreated fir, redwood, cedar, or pine and cut from sound timber. They shall be straight and free of loose or unsound knots and other defects which would render them unfit for the purpose intended.

**Rope**

Rope shall be biodegradable, such as sisal or manila, with a minimum diameter of 1/4 inch.

**Gravel-filled Bags**

Gravel-filled bag fabric shall be nonwoven polypropylene geotextile or polymer material and shall conform to the following requirements:

| Specification | Requirements |
|---|---|
| Weight per unit area, ounces per square yard, minimum<br>ASTM Designation: D 5261 | 8.0 |
| Grab tensile strength (one inch grip), pounds, minimum<br>ASTM Designation: D 4632* | 200 |
| Ultraviolet stability, percent tensile strength retained after 500 hours minimum<br>ASTM Designation: D 4355, xenon arc lamp method | 70 |

* or appropriate test method for specific polymer

Gravel-filled bags shall be between 24 inches and 32 inches in length, and between 16 inches and 20 inches in width.

Yarn used for binding gravel bags shall be as recommended by the manufacturer or bag supplier and shall be of a contrasting color.

Gravel shall be between 3/8 inch and 3/4 inch in diameter, and shall be clean and free from clay balls, organic matter, and other deleterious materials. The opening of gravel-filled bags shall be secured to prevent gravel from escaping. Gravel-filled bags shall be between 30 pounds and 50 pounds in weight.

**Silt Fence**

At the Contractor's option, temporary silt fence shall be prefabricated or constructed with silt fence fabric, posts, and fasteners.

Silt fence fabric shall conform to the following requirements:

| Specification | Requirements |
|---|---|
| Width, inches, minimum | 36 |
| Grab tensile strength (one inch grip), pounds, minimum, in each direction<br>ASTM Designation: D 4632 or appropriate test method for specific polymer | 124 |
| Elongation, percent, minimum, in each direction<br>ASTM Designation: D 4632 or appropriate test method for specific polymer | 15 |
| Permittivity, 1/sec., minimum<br>ASTM Designation: D 4491 | 0.05 |
| Flow rate, gallons per minute per square foot, minimum<br>ASTM Designation: D 4491 | 10 |
| Ultraviolet stability, percent, tensile strength retained after 500 hours, minimum<br>ASTM Designation: D 4355 (xenon-arc lamp and water spray weathering method) | 70 |

Silt fence fabric shall be geotextile manufactured from woven polypropylene or polymer material. Silt fence fabric may be made of recycled materials. No materials shall contain biodegradable filler materials that can degrade the physical or chemical characteristics of the finished fabric. The Engineer may order tests to confirm the absence of biodegradable filler materials in conformance to the requirements in ASTM Designation: E 204.

Posts for temporary silt fences shall be one of the following:

A. Posts shall be untreated fir, redwood, cedar, or pine, shall be cut from sound timber, and shall be straight and free of loose or unsound knots and other defects which would render them unfit for the purpose intended. Wood post shall be a minimum of 2" x 2" in size, and 4 feet in length. The end of the post to be embedded in the soil shall be pointed.
B. Posts shall be steel and have a "U," "T," "L," or other cross sectional shape that can resist failure from lateral loads. The steel posts shall have a minimum weight of 0.75-pound per foot and a minimum length of 4 feet. One end of the steel posts shall be pointed and the other end shall be capped with an orange or red plastic safety cap which fits snugly to the steel post. The Contractor shall submit to the Engineer for approval a sample of the capped steel post before installation.

Fasteners for attaching silt fence fabric to posts shall be as follows:

A. When prefabricated silt fence is used, posts shall be inserted into sewn pockets.
B. Silt fence fabric shall be attached to wooden posts with nails or staples as shown on the plans or as recommended by the manufacturer or supplier. Tie wire or locking plastic fasteners shall be used to fasten the silt fence fabric to steel posts. Maximum spacing of fasteners shall be 8 inches along the length of the steel post.

**Sediment Filter Bag**

Sediment filter bag fabric shall be geotextile manufactured from woven polypropylene or polymer material. Sediment filter bag fabric may be made from recycled polymer materials. Polymer materials shall not contain biodegradable filler materials and shall conform to the requirements in ASTM Designation: E 204.

Sediment filter bag fabric shall conform to the following requirements:

| Specification | Requirements |
|---|---|
| Grab tensile strength (one inch grip), pounds, minimum in each direction<br>ASTM Designation: D 4632 or appropriate test method for specific polymer | 255 |
| Elongation, percent, minimum in each direction<br>ASTM Designation: D 4632 or appropriate test method for specific polymer | 15 |
| Permittivity, 1/sec., minimum<br>ASTM Designation: D 4491 | 1.5 |
| Flow rate, gallons per minute per square foot, minimum<br>ASTM Designation: D 4491 | 200 |
| Ultraviolet stability, percent tensile strength retained after 500 hours, minimum<br>ASTM Designation: D 4355 (xenon-arc lamp and water spray weathering method) | 80 |

The sediment filter bag shall be sized to fit the catch basin or drainage inlet and shall be complete with lifting loops and dump straps attached at the bottom to facilitate emptying of the sediment filter bag. The sediment filter bags shall have a restraint cord approximately halfway up the bag to keep the sides away from the catch basin walls.

**INSTALLATION**

Temporary drainage inlet protection shall be installed at drainage inlets in paved and unpaved areas as follows:

A. Temporary drainage inlet protection shall be installed such that ponded runoff does not encroach on the traveled way or overtop the curb or dike. Gravel-filled bags shall be placed to control ponding and prevent runoff from overtopping the curb or dike.
B. The bedding area for the temporary drainage inlet protection shall be cleared of obstructions including rocks, clods, and debris greater than one inch in diameter before installation.
C. A temporary linear sediment barrier shall be installed up-slope of the existing drainage inlet and parallel with the curb, dike, or flow line to prevent sediment from entering the drainage inlet.

**Erosion Control Blanket and Geotextile Fabric**

The erosion control blanket and geotextile fabric shall be secured to the surface of the excavated sediment trap with staples and embedded in a trench adjacent to the drainage inlet. The perimeter edge of the erosion control blanket and geotextile fabric shall be anchored in a trench.

**Silt Fence**

Silt fence shall be installed along the perimeter of the erosion control blanket or geotextile fabric, with the posts facing the drainage inlet. The trench shall be backfilled and tamped to secure the silt fence fabric in the bottom of the trench.

**Gravel-filled Bags**

Gravel-filled bags shall be stacked to form a gravel bag barrier. The gravel-filled bags shall be placed so that the bags are tightly abutted and overlap the joints in adjacent rows. A spillway shall be created by removing one or more gravel-filled bags from the upper layer of the gravel bag barrier.

Gravel-filled bags shall only be used within shoulder areas when placed behind temporary railing (Type K).

**Fiber Rolls**

Fiber rolls shall be placed over the erosion control blanket or geotextile fabric with the ends of the fiber roll abutted tightly together. Fiber rolls shall be secured with stakes installed along the length of the fiber rolls. Stakes shall not be installed within 12 inches of the end of the rolls.

**Sediment Filter Bags**

Sediment filter bags shall be installed by removing the drainage inlet grate, placing the sediment bag in the opening, and replacing the grate to secure the sediment filter bag in place.

**MAINTENANCE**

Temporary drainage inlet protection shall be maintained to provide sediment holding capacity and to reduce runoff velocities. Temporary drainage inlet protection shall be repaired or replaced immediately after the damage occurs.

Sediment deposits, trash, and debris shall be removed from temporary drainage inlet protection as needed or when directed by the Engineer. Removed sediment shall be deposited within the project limits so that the sediment is not subject to erosion by wind or by water. Trash and debris shall be removed and disposed of in accordance with the provisions in Section 7-1.13, "Disposal of Material Outside the Highway Right of Way," of the Standard Specifications.

At locations where rills and other evidence of concentrated runoff have occurred beneath the drainage inlet protection, the protection shall be adjusted to prevent another occurrence.

Temporary silt fence shall be repaired or replaced when silt fence fabric becomes split, torn, or unraveled. Sagging or slumping silt fence shall be repaired with additional stakes or replaced. Broken or split stakes shall be replaced. Temporary silt fence shall be maintained to provide a sediment holding capacity of approximately 1/3 the height of the silt fence fabric above ground.

Sediment in excess of 2 inches above the surface of the erosion control blanket or geotextile fabric shall be removed.

Sediment shall be removed from the sediment trap when the volume has been reduced by approximately one-half.

Sediment deposits shall be removed when the deposit is 1/3 the height of the gravel bag barrier or one half the height of the spillway; whichever is less.

Gravel-filled bags shall be replaced when the bag material ruptures or when the binding fails.

Split, torn, unraveling, sagging, or slumping fiber rolls shall be replaced or repaired.

Sediment filter bags shall be emptied when the restraint cords are no longer visible. Sediment filter bags shall be emptied by placing one inch steel reinforcing bars through the lifting loops. The bag shall be emptied of its contents and rinsed before replacement in the drainage inlet.

**REMOVAL**

When the temporary drainage inlet protection is no longer required the protection materials shall be removed and disposed of in accordance with the provisions in Section 7-1.13, "Disposal of Material Outside the Highway Right of Way," of the Standard Specifications.

Holes, depressions, or other ground disturbance caused by the removal of the temporary drainage inlet protection shall be backfilled and repaired in accordance with the provisions in Section 15-1.02, "Preservation of Property," of the Standard Specifications.

**MEASUREMENT**

Quantities of temporary drainage inlet protection will be determined from actual count in place. The protection will be measured one time only and no additional measurement will be recognized.

**PAYMENT**

The contract unit price paid for temporary drainage inlet protection shall include full compensation for furnishing all labor, materials, tools, equipment, and incidentals, and for doing all the work involved in constructing the temporary drainage inlet protection, complete in place, including maintenance, removal of materials, including cleanup and disposal of retained sediment and debris, and backfilling and repairing holes, depressions and other ground disturbance, as shown on the plans, as specified in the Standard Specifications and these special provisions, and as directed by the Engineer.

No additional compensation will be made if the temporary drainage inlet protection changes during the course of construction.

## 10-1.12 COOPERATION

It is anticipated that work by another contractor may be in progress adjacent to or within the limits of this project during progress off the work on this contract. The following table lists contracts anticipated to be in progress during this contract.

| Contract No. | Co-Rte-PM | Location | Type of Work |
|---|---|---|---|
| 04-06NAS1861 | 13.5 | Adjacent to north end of parking lot at the Crystal Springs Rest Area | Installation of Sprint Cellular phone tower and related equipment |

Work between the Rest Area and Lakeview Drive shall be performed within the confines of utility easements crossing property owned by the San Francisco Public Utility Commission (SF PUC) and a private residential property owner. Work at these locations shall be performed only within the easements, or as covered in a Permit issued by the SF PUC, or as approved by the owner of the property and as approved by the Engineer.

Work under this contract may impact residents on Lakeview Drive in Hillsborough. The Contractor shall coordinate his activities and provide 72 hours notice to Engineer prior to beginning any work involved with existing or proposed utilities in order to minimize utility service disruption or other inconveniencies to residents on Lakeview Drive.

Comply with Section 7-1.14, "Cooperation," of the Standard Specifications.

## 10-1.13 PROGRESS SCHEDULE (CRITICAL PATH METHOD)

**GENERAL**

**Summary**

Comply with Section 8-1.04, "Progress Schedule," of the Standard Specifications, except you must:

1. Use a computer software to prepare the schedule
2. Furnish compatible software for the Engineer's exclusive possession and use

You are responsible for assuring that all activity sequences are logical and that each schedule shows a coordinated plan for complete performance of the work.

### Definitions

**contract completion date:** The current extended date for completion of the contract shown on the weekly statement of working days furnished by the Engineer as specified in Section 8-1.06, "Time of Completion," of the Standard Specifications.

**data date:** The day after the date through which a schedule is current. Everything occurring earlier than the data date is "as-built" and everything on or after the data date is "planned."

**float:** The difference between the earliest and latest allowable start or finish times for an activity.

**milestone:** An event activity that has zero duration and is typically used to represent the beginning or end of a certain stage of the project.

**near critical path:** A chain of activities with total float exceeding that of the critical path but having no more than 10 working days of total float.

**time-scaled network diagram:** A graphic depiction of a CPM schedule comprised of activity bars with relationships for each activity represented by arrows. The tail of each arrow connects to the activity bar for the predecessor and points to the successor.

**total float:** The amount of time that an activity or chain of activities can be delayed before extending the scheduled completion date.

### Submittals

#### General Requirements

Submit to the Engineer baseline, monthly updated, and final updated schedules, each consistent in all respects with the time and order of work requirements of the contract. Perform work in the sequence indicated on the current accepted schedule.

Each schedule must show:

1. Calculations using critical path method to determine controlling activities.
2. Duration activities less than 20 working days.
3. Each required constraint. Constraints other than those required by the special provisions may be included only if authorized.

The Engineer's review and acceptance of schedules does not waive any contract requirements and does not relieve you of any obligation or responsibility for submitting complete and accurate information. Correct rejected schedules and resubmit them within 7 days of notification by the Engineer, at which time a new review period of 7 days will begin.

Errors or omissions on schedules do not relieve you from finishing all work within the time limit specified for completion of the contract. If, after a schedule has been accepted by the Engineer, either you or the Engineer discover that any aspect of the schedule has an error or omission, you must correct it on the next updated schedule.

#### Computer Software

Submit to the Engineer for review a description of proposed schedule software to be used. After the Engineer accepts the proposed software, furnish schedule software and all original software instruction manuals. All software must be compatible with the current version of the Windows operating system in use by the Engineer. The schedule software must include:

1. Latest version of Primavera SureTrak Project Manager for Windows, or equivalent
2. Latest version of schedule-comparing HST SureChange, or equivalent

If a schedule software equivalent to SureTrak is proposed, it must be capable of generating files that can be imported into SureTrak. The schedule-comparing software must be compatible with schedule software submitted and must be able to compare two schedules and provide reports of changes in activity ID, activity description, constraints, calendar assignments, durations, and logic ties.

The schedule software and schedule-comparing software will be returned to you before the final estimate. The Department will compensate you as specified in Section 4-1.03, "Extra Work," of the Standard Specifications for replacement of software or manuals damaged, lost, or stolen after delivery to the Engineer.

Instruct the Engineer in the use of the software and provide software support until the contract is accepted. Within 15 days of contract approval, provide a commercial 8-hour training session for 2 Department employees in the use of the software at a location acceptable to the Engineer. It is recommended that you also send at least 2 employees to the same

training session to facilitate development of similar knowledge and skills in the use of the software. If schedule software other than SureTrak is submitted, then the training session must be a total of 16-hours for each Department employee.

**Network Diagrams, Reports, and Data**

Include the following with each schedule submittal:

1. Two sets of originally plotted, time-scaled network diagrams
2. One read-only compact disk or floppy diskette containing the schedule data

The time-scaled network diagrams must conform to the following:

1. Show a continuous flow of information from left to right
2. Be based on early start and early finish dates of activities
3. Clearly show the critical path using graphical presentation
4. Be prepared on 11" x 17" or larger size
5. Include a title block and a timeline on each page

**Baseline Schedule**

Submit to the Engineer a baseline schedule within 20 days of approval of the contract. Allow 20 days for the Engineer's review after the baseline schedule and all support data are submitted. Beginning the week the baseline schedule is first submitted, meet with the Engineer weekly to discuss and resolve schedule issues until the baseline schedule is accepted.

The baseline schedule must include the entire scope of work and must show how you plan to complete all work contemplated. Multiple critical paths and near-critical paths must be kept to a minimum. A total of not more than 50 percent of the baseline schedule activities must be critical or near critical, unless otherwise authorized by the Engineer.

The baseline schedule must not extend beyond the number of working days originally provided in these special provisions.

**Updated Schedule**

Submit an updated schedule and meet with the Engineer to review contract progress on or before the 1st day of each month, beginning one month after the baseline schedule is accepted. Allow 15 days for the Engineer's review after the updated schedule and all support data are submitted, except that the review period will not start until any previous month's required schedule is accepted. Updated schedules that are not accepted or rejected within the review period are considered accepted by the Engineer.

The updated schedule must show:

1. Data date of the 21st day of the month or other date established by the Engineer
2. Changes from approved revised schedules

**Final Updated Schedule**

Submit a final updated schedule with actual start and finish dates for the activities within 30 days after completion of contract work. Provide a written certificate with this submittal signed by your project manager or an officer of the company stating, "To my knowledge and belief, the enclosed final updated schedule reflects the actual start and finish dates of the actual activities for the project contained herein." An officer of the company may delegate in writing the authority to sign the certificate to a responsible manager.

**PAYMENT**

Full compensation for furnishing software is considered as included in the contract prices paid for the various items of work involved and no additional compensation will be allowed.

## 10-1.14 OBSTRUCTIONS

Attention is directed to Section 8-1.10, "Utility and Non-Highway Facilities," and Section 15, "Existing Highway Facilities," of the Standard Specifications and these special provisions.

Attention is directed to the existence of certain underground facilities that may require special precautions be taken by the Contractor to protect the health, safety and welfare of workers and of the public. Facilities requiring special precautions include, but are not limited to: conductors of petroleum products, oxygen, chlorine, and toxic or flammable gases; natural gas in pipelines greater than 6 inches in diameter or pipelines operating at pressures greater than 60 pounds per square inch

(gage); underground electric supply system conductors or cables, with potential to ground of more than 300 V, either directly buried or in a duct or conduit which do not have concentric grounded or other effectively grounded metal shields or sheaths.

The Contractor shall notify the Engineer and the appropriate regional notification center for operators of subsurface installations at least 2 business days, but not more than 14 days, prior to performing any excavation or other work close to any underground pipeline, conduit, duct, wire or other structure. Regional notification centers include, but are not limited to, the following:

| Notification Center | Telephone Number |
|---|---|
| Underground Service Alert | 811 |

**10-1.15 SMALL BUSINESS UTILIZATION REPORT**

Submit a completed Small Business Utilization Report form on or before the following dates for the prior reporting period:

1. January 15th
2. April 15th
3. July 15th
4. October 15th

Submit a completed final Small Business Utilization Report form within 30 days after contract acceptance.

The Department pays $250 for each report submitted. The contract unit price paid for small business utilization report includes full compensation for doing all the work involved in submitting the completed Small Business Utilization Report form. If you fail to submit a completed form by the specified time, you will not receive payment for that report.

The Department does not adjust payment for an increase or decrease in the quantity of small business utilization reports submitted. Section 4-1.03B, "Increased or Decreased Quantities," of the Standard Specifications does not apply.

The work to complete the final Small Business Utilization Report contract item is excluded from Section 7-1.17, "Acceptance of Contract," of the Standard Specifications.

Failure to submit the Small Business Utilization Report is not considered a performance failure. Section 9-1.053, "Performance Failure Withholds," of the Standard Specifications does not apply.

**10-1.16 CONSTRUCTION AREA TRAFFIC CONTROL DEVICES**

Flagging, signs, and temporary traffic control devices furnished, installed, maintained, and removed when no longer required shall conform to the provisions in Section 12, "Construction Area Traffic Control Devices," of the Standard Specifications and these special provisions.

Category 1 temporary traffic control devices are defined as small and lightweight (less than 100 pounds) devices. These devices shall be certified as crashworthy by crash testing, crash testing of similar devices, or years of demonstrable safe performance. Category 1 temporary traffic control devices include traffic cones, plastic drums, portable delineators, and channelizers.

If requested by the Engineer, the Contractor shall provide written self-certification for crashworthiness of Category 1 temporary traffic control devices at least 5 days before beginning any work using the devices or within 2 days after the request if the devices are already in use. Self-certification shall be provided by the manufacturer or Contractor and shall include the following:

A. Date,
B. Federal Aid number (if applicable),
C. Contract number, district, county, route and post mile of project limits,
D. Company name of certifying vendor, street address, city, state and zip code,
E. Printed name, signature and title of certifying person; and
F. Category 1 temporary traffic control devices that will be used on the project.

The Contractor may obtain a standard form for self-certification from the Engineer.

Category 2 temporary traffic control devices are defined as small and lightweight (less than 100 pounds) devices that are not expected to produce significant vehicular velocity change, but may cause potential harm to impacting vehicles. Category 2 temporary traffic control devices include barricades and portable sign supports.

Category 2 temporary traffic control devices shall be on the Federal Highway Administration's (FHWA) list of Acceptable Crashworthy Category 2 Hardware for Work Zones. This list is maintained by FHWA and can be located at:

http://safety.fhwa.dot.gov/roadway_dept/road_hardware/listing.cfm?code=workzone

The Department also maintains this list at:

http://www.dot.ca.gov/hq/traffops/signtech/signdel/pdf/Category2.pdf

Category 2 temporary traffic control devices that have not received FHWA acceptance shall not be used. Category 2 temporary traffic control devices in use that have received FHWA acceptance shall be labeled with the FHWA acceptance letter number and the name of the manufacturer. The label shall be readable and permanently affixed by the manufacturer. Category 2 temporary traffic control devices without a label shall not be used.

If requested by the Engineer, the Contractor shall provide a written list of Category 2 temporary traffic control devices to be used on the project at least 5 days before beginning any work using the devices or within 2 days after the request if the devices are already in use.

Category 3 temporary traffic control devices consist of temporary traffic-handling equipment and devices that weigh 100 pounds or more and are expected to produce significant vehicular velocity change to impacting vehicles. Temporary traffic-handling equipment and devices include crash cushions, truck-mounted attenuators, temporary railing, temporary barrier, and end treatments for temporary railing and barrier.

Type III barricades may be used as sign supports if the barricades have been successfully crash tested, meeting the NCHRP Report 350 criteria, as one unit with a construction area sign attached.

Category 3 temporary traffic control devices shall be shown on the plans or on the Department's Highway Safety Features list. This list is maintained by the Division of Engineering Services and can be found at:

http://www.dot.ca.gov/hq/esc/approved_products_list/HighwaySafe.htm

Category 3 temporary traffic control devices that are not shown on the plans or not listed on the Department's Highway Safety Features list shall not be used.

Full compensation for providing self-certification for crashworthiness of Category 1 temporary traffic control devices and for providing a list of Category 2 temporary traffic control devices used on the project shall be considered as included in the prices paid for the various items of work requiring the use of the Category 1 or Category 2 temporary traffic control devices and no additional compensation will be allowed therefor.

### 10-1.17 CONSTRUCTION AREA SIGNS

Construction area signs for temporary traffic control shall be furnished, installed, maintained, and removed when no longer required in conformance with the provisions in Section 12, "Construction Area Traffic Control Devices," of the Standard Specifications and these special provisions.

Attention is directed to "Furnish Sign" of these special provisions.

Attention is directed to the provisions in "Prequalified and Tested Signing and Delineation Materials" of these special provisions. Type II retroreflective sheeting shall not be used on construction area sign panels. Type III, IV, VII, VIII, or IX retroreflective sheeting shall be used for stationary mounted construction area sign panels.

Attention is directed to "Construction Project Information Signs" of these special provisions regarding the number and type of construction project information signs to be furnished, erected, maintained, and removed and disposed of.

Unless otherwise shown on the plans or specified in these special provisions, the color of construction area warning and guide signs shall have black legend and border on orange background, except W10-1 or W47(CA) (Highway-Rail Grade Crossing Advance Warning) sign shall have black legend and border on yellow background.

Repair to construction area sign panels will not be allowed, except when approved by the Engineer. At nighttime under vehicular headlight illumination, sign panels that exhibit irregular luminance, shadowing or dark blotches shall be immediately replaced at the Contractor's expense.

The Contractor shall notify the appropriate regional notification center for operators of subsurface installations at least 2 business days, but not more than 14 days, prior to commencing excavation for construction area sign posts. The regional notification centers include, but are not limited to, the following:

| Notification Center | Telephone Number |
|---|---|
| Underground Service Alert | 811 |

Excavations required to install construction area signs shall be performed by hand methods without the use of power equipment, except that power equipment may be used if it is determined there are no utility facilities in the area of the proposed post holes. The post hole diameter, if backfilled with portland cement concrete, shall be at least 4 inches greater than the longer dimension of the post cross section.

Construction area signs placed within 15 feet from the edge of the travel way shall be mounted on stationary mounted sign supports as specified in "Construction Area Traffic Control Devices" of these special provisions.

The Contractor shall maintain accurate information on construction area signs. Signs that are no longer required shall be immediately covered or removed. Signs that convey inaccurate information shall be immediately replaced or the information shall be corrected. Covers shall be replaced when they no longer cover the signs properly. The Contractor shall immediately restore to the original position and location any sign that is displaced or overturned, from any cause, during the progress of work.

**10-1.18 MAINTAINING TRAFFIC**

Maintaining traffic shall conform to the provisions in Sections 7-1.08, "Public Convenience," Section 7-1.09, "Public Safety," and Section 12, "Construction Area Traffic Control Devices," of the Standard Specifications, "Public Safety" of these special provisions and these special provisions.

Closure is defined as the closure of a traffic lane or lanes, including shoulder, ramp or connector lanes, within a single traffic control system.

Closures shall conform to the provisions in "Traffic Control System for Lane Closure" of these special provisions.

Closures are only allowed during the hours shown in the lane requirement charts included in this section "Maintaining Traffic," except for work required under Sections 7-1.08, "Public Convenience," and Section 7-1.09, "Public Safety."

The full width of the traveled way shall be open for use by public traffic when construction operations are not actively in progress.

Personal vehicles of the Contractor's employees shall not be parked within the right of way except in the rest area parking lot.

When work vehicles or equipment are parked on the shoulder within 6 feet of a traffic lane, the shoulder area shall be closed as shown on the plans.

If minor deviations from the lane requirement charts are required, a written request shall be submitted to the Engineer at least 15 days before the proposed date of the closure. The Engineer may approve the deviations if there is no significant increase in the cost to the State and if the work can be expedited and better serve the public traffic.

Designated legal holidays are: January 1st, the third Monday in February, the last Monday in May, July 4th, the first Monday in September, November 11th, Thanksgiving Day, and December 25th. When a designated legal holiday falls on a Sunday, the following Monday shall be a designated legal holiday. When November 11th falls on a Saturday, the preceding Friday shall be a designated legal holiday.

**Chart No. 1**
**Freeway/Expressway Lane Requirements**

| County: San Mateo | Route/Direction: NB Route 280 | PM: 13.3/13.6 |
|---|---|---|

Closure Limits: At Crystal Springs Safety Roadside Rest Area

| FROM HOUR TO HOUR | 24 | 1 | 2 | 3 | 4 | 5 | 6 | 7 | 8 | 9 | 10 | 11 | 12 | 13 | 14 | 15 | 16 | 17 | 18 | 19 | 20 | 21 | 22 | 23 | 24 |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| Mondays through Thursdays | 3 | 3 | 3 | 3 | 3 | 3 | 3 | S | S | 3 | 3 | 3 | 3 | 3 | 3 | S | S | | | 3 | 3 | 3 | 3 | 3 | |
| Fridays | 3 | 3 | 3 | 3 | 3 | 3 | 3 | S | S | 3 | 3 | 3 | 3 | 3 | 3 | S | | | | 3 | 3 | 3 | 3 | 3 | |
| Saturdays | 3 | 3 | 3 | 3 | 3 | 3 | 3 | 3 | 3 | 3 | 3 | 3 | 3 | 3 | 3 | 3 | 3 | 3 | 3 | 3 | 3 | 3 | 3 | 3 | |
| Sundays | 3 | 3 | 3 | 3 | 3 | 3 | 3 | 3 | 3 | 3 | 3 | 3 | 3 | 3 | 3 | 3 | 3 | 3 | 3 | 3 | 3 | 3 | 3 | 3 | |

Legend:

| | |
|---|---|
| 3 | Provide at least three adjacent through freeway lanes open in direction of travel; shoulder may be closed. |
| S | Shoulder closure permitted (right / left) |
| | No lane closure permitted |

REMARKS:

**10-1.19 CLOSURE REQUIREMENTS AND CONDITIONS**

Closures shall conform to the provisions in "Maintaining Traffic" of these special provisions and these special provisions.

**CLOSURE SCHEDULE**

By noon Monday, the Contractor shall submit a written schedule of planned closures for the following week period, defined as Sunday noon through the following Sunday noon. Closures involving work (temporary barrier placement and paving operations) that will reduce horizontal clearances, traveled way inclusive of shoulders, to 2 lanes or less shall be submitted not less than 25 days and not more than 125 days before the anticipated start of operation. Closures involving work (pavement overlay, overhead sign installation, falsework and girder erection) that will reduce the vertical clearances available to the public, shall be submitted not less than 25 days and not more than 125 days before the anticipated start of operation.

The Closure Schedule shall show the locations and times of the proposed closures. The Closure Schedule request forms furnished by the Engineer shall be used. Closure Schedules submitted to the Engineer with incomplete or inaccurate information will be rejected and returned for correction and resubmittal. The Contractor will be notified of disapproved closures or closures that require coordination with other parties as a condition of approval.

Closure Schedule amendments, including adding additional closures, shall be submitted by noon to the Engineer, in writing, at least 3 business days in advance of a planned closure. Approval of Closure Schedule amendments will be at the discretion of the Engineer.

The Engineer shall be notified of cancelled closures 2 business days before the date of closure.

Closures that are cancelled due to unsuitable weather may be rescheduled at the discretion of the Engineer.

**CONTINGENCY PLAN**

A detailed contingency plan shall be prepared for reopening closures to public traffic. If required by "Beginning of Work, Time of Completion and Liquidated Damages" of these special provisions, the contingency plan shall be submitted to the Engineer before work at the job site begins. Otherwise, the contingency plan shall be submitted to the Engineer within one business day of the Engineer's request.

**LATE REOPENING OF CLOSURES**

If a closure is not reopened to public traffic by the specified time, work shall be suspended in conformance with the provisions in Section 8-1.05, "Temporary Suspension of Work," of the Standard Specifications. No further closures are to be made until the Engineer has accepted a work plan, submitted by the Contractor, that will insure that future closures will be reopened to public traffic at the specified time. The Engineer will have 2 business days to accept or reject the Contractor's proposed work plan. The Contractor will not be entitled to compensation for the suspension of work resulting from the late reopening of closures.

For each 10-minute interval, or fraction thereof past the time specified to reopen the closure, the Department will deduct $1,000 per interval from moneys due or that may become due the Contractor under the contract.

**COMPENSATION**

The Engineer shall be notified of delays in the Contractor's operations due to the following conditions, and if, in the opinion of the Engineer, the Contractor's controlling operation is delayed or interfered with by reason of those conditions, and the Contractor's loss due to that delay could not have been avoided by rescheduling the affected closure or by judicious handling of forces, equipment and plant, the delay will be considered a right of way delay and will be compensated in conformance with the provisions in Section 8-1.09, "Right of Way Delays," of the Standard Specifications:

1. The Contractor's proposed Closure Schedule is denied and his planned closures are within the time frame allowed for closures in "Maintaining Traffic" of these special provisions, except that the Contractor will not be entitled to compensation for amendments to the Closure Schedule that are not approved.
2. The Contractor is denied a confirmed closure.

Should the Engineer direct the Contractor to remove a closure before the time designated in the approved Closure Schedule, delay to the Contractor's schedule due to removal of the closure will be considered a right of way delay and compensation for the delay will be determined in conformance with the provisions in Section 8-1.09, "Right of Way Delays," of the Standard Specifications.

**10-1.20 TRAFFIC CONTROL SYSTEM FOR LANE CLOSURE**

A traffic control system shall consist of closing traffic lanes in conformance with the details shown on the plans, the provisions in Section 12, "Construction Area Traffic Control Devices," of the Standard Specifications, the provisions under "Maintaining Traffic" and "Construction Area Signs" of these special provisions, and these special provisions.

The provisions in this section will not relieve the Contractor from the responsibility to provide additional devices or take measures as may be necessary to comply with the provisions in Section 7-1.09, "Public Safety," of the Standard Specifications.

Each vehicle used to place, maintain and remove components of a traffic control system on multilane highways shall be equipped with a Type II flashing arrow sign which shall be in operation when the vehicle is being used for placing, maintaining or removing components. Vehicles equipped with Type II flashing arrow sign not involved in placing, maintaining or removing components when operated within a stationary lane closure shall only display the caution display mode. The sign shall be controllable by the operator of the vehicle while the vehicle is in motion. The flashing arrow sign shown on the plans shall not be used on vehicles which are being used to place, maintain and remove components of a traffic control system and shall be in place before a lane closure requiring its use is completed.

The traffic cones shown to be placed transversely across closed traffic lanes and shoulders on the plans entitled "Traffic Control System for Lane Closures on Freeways and Expressways" and "Traffic Control System for Lane and Complete Closures on Freeways and Expressways" shall not be placed.

If components in the traffic control system are displaced or cease to operate or function as specified, from any cause, during the progress of the work, the Contractor shall immediately repair the components to the original condition or replace the components and shall restore the components to the original location.

When lane closures are made for work periods only, at the end of each work period, components of the traffic control system, except portable delineators placed along open trenches or excavation adjacent to the traveled way, shall be removed from the traveled way and shoulder. If the Contractor so elects, the components may be stored at selected central locations designated by the Engineer within the limits of the highway right of way.

The contract lump sum price paid for traffic control system shall include full compensation for furnishing all labor, materials (including signs), tools, equipment, and incidentals, and for doing all the work involved in placing, removing, storing, maintaining, moving to new locations, replacing, and disposing of the components of the traffic control system shown on the plans, as specified in the Standard Specifications and these special provisions, and as directed by the Engineer.

The adjustment provisions in Section 4-1.03, "Changes," of the Standard Specifications shall not apply to the item of traffic control system. Adjustments in compensation for traffic control system will be made only for increased or decreased

traffic control system required by changes ordered by the Engineer and will be made on the basis of the cost of the increased or decreased traffic control necessary. The adjustment will be made on a force account basis as provided in Section 9-1.03, "Force Account Payment," of the Standard Specifications for increased work and estimated on the same basis in the case of decreased work.

Traffic control system required by work which is classed as extra work, as provided in Section 4-1.03D of the Standard Specifications, will be paid for as a part of the extra work.

### 10-1.21 BARRICADE

Barricades shall be furnished, placed and maintained at the locations shown on the plans, specified in the Standard Specifications or in these special provisions or where designated by the Engineer. Barricades shall conform to the provisions in Section 12, "Construction Area Traffic Control Devices," of the Standard Specifications and these special provisions.

Attention is directed to "Prequalified and Tested Signing and Delineation Materials" of these special provisions regarding retroreflective sheeting for barricades.

Construction area sign and marker panels conforming to the provisions in Section 12-3.06, "Construction Area Signs," of the Standard Specifications shall be installed on barricades in a manner determined by the Engineer at the locations shown on the plans.

Sign panels for construction area signs and marker panels installed on barricades shall conform to the provisions in Section 12-3.06A, "Stationary Mounted Signs," of the Standard Specifications.

Full compensation for furnishing, installing, maintaining, and removing construction area signs and marker panels on barricades shall be considered as included in the contract unit price paid for the type of barricade involved and no separate payment will be made therefor.

Barricades shown on the plans as part of a traffic control system will be paid for as provided in "Traffic Control System for Lane Closure" of these special provisions and will not be included in the count for payment of barricades.

### 10-1.22 PORTABLE CHANGEABLE MESSAGE SIGN

Portable changeable message signs shall be furnished, placed, operated, and maintained at locations shown on the plans or where designated by the Engineer and shall conform to the provisions in Section 12, "Construction Area Traffic Control Devices," of the Standard Specifications and these special provisions. Messages displayed on the portable changeable message signs shall be as specified on the plans and shall conform to Section 12-3.12 "Portable Changeable Message Signs," of the Standard Specifications and “Maintaining Traffic” of these special provisions."

A portable changeable message sign shall be placed in advance of the first warning sign for each stationary lane closure.

A portable changeable message sign shall be placed before and during ramp and connector closures.

### 10-1.23 CHANNELIZER

Channelizers shall conform to the provisions in Section 12, "Construction Area Traffic Control Devices," of the Standard Specifications and these special provisions.

Channelizers shall conform to the provisions in "Prequalified and Tested Signing and Delineation Materials" of these special provisions.

When no longer required for the work as determined by the Engineer, channelizers and underlying adhesive used to cement the channelizer bases to the pavement shall be removed. Removed channelizers and adhesive shall become the property of the Contractor and shall be removed from the site of work.

### 10-1.24 TEMPORARY CRASH CUSHION MODULE

This work shall consist of furnishing, installing, and maintaining sand filled temporary crash cushion modules in groupings or arrays at each location shown on the plans, as specified in these special provisions or where designated by the Engineer. The grouping or array of sand filled modules shall form a complete sand filled temporary crash cushion in conformance with the details shown on the plans and these special provisions.

Attention is directed to "Public Safety" of these special provisions.

Whenever the work or the Contractor's operations establishes a fixed obstacle, the exposed fixed obstacle shall be protected with a sand filled temporary crash cushion. The sand filled temporary crash cushion shall be in place prior to opening the lanes adjacent to the fixed obstacle to public traffic.

Sand filled temporary crash cushions shall be maintained in place at each location, including times when work is not actively in progress. Sand filled temporary crash cushions may be removed during a work period for access to the work provided that the exposed fixed obstacle is 15 feet or more from a lane carrying public traffic and the temporary crash cushion is reset to protect the obstacle prior to the end of the work period in which the fixed obstacle was exposed. When no longer required, as determined by the Engineer, sand filled temporary crash cushions shall be removed from the site of the work.

At the Contractor's option, the modules for use in sand filled temporary crash cushions shall be either Energite III Inertial Modules, Fitch Inertial Modules or TrafFix Sand Barrels manufactured after March 31, 1997, or equal:

1. Energite III and Fitch Inertial Modules, manufactured by Energy Absorption Systems, Inc., 35 East Wacker Drive, Suite 1100, Chicago, IL 60601:

   1.1. Northern California: Traffic Control Service, Inc., 8585 Thys Court, Sacramento, CA 95828, telephone (800) 884-8274, FAX (916) 387-9734
   1.2. Southern California: Traffic Control Service, Inc., 1818 E. Orangethorpe, Fullerton, CA 92831-5324, telephone (800) 222-8274, FAX (714) 526-9501

2. TrafFix Sand Barrels, manufactured by TrafFix Devices, Inc., 220 Calle Pintoresco, San Clemente, CA 92672, telephone (949) 361-5663, FAX (949) 361-9205

   2.1. Northern California: United Rentals, Inc., 1533 Berger Drive, San Jose, CA 95112, telephone (408) 287-4303, FAX (408) 287-1929
   2.2. Southern California: Statewide Safety & Sign, Inc., P.O. Box 1440, Pismo Beach, CA 93448, telephone (800) 559-7080, FAX (805) 929-5786

Modules contained in each temporary crash cushion shall be of the same type at each location. The color of the modules shall be the standard yellow color, as furnished by the vendor, with black lids. The modules shall exhibit good workmanship free from structural flaws and objectionable surface defects. The modules need not be new. Good used undamaged modules conforming to color and quality of the types specified herein may be utilized. If used Fitch modules requiring a seal are furnished, the top edge of the seal shall be securely fastened to the wall of the module by a continuous strip of heavy duty tape.

Modules shall be filled with sand in conformance with the manufacturer's directions, and to the sand capacity in pounds for each module shown on the plans. Sand for filling the modules shall be clean washed concrete sand of commercial quality. At the time of placing in the modules, the sand shall contain not more than 7 percent water as determined by California Test 226.

Modules damaged due to the Contractor's operations shall be repaired immediately by the Contractor at the Contractor's expense. Modules damaged beyond repair, as determined by the Engineer, due to the Contractor's operations shall be removed and replaced by the Contractor at the Contractor's expense.

Temporary crash cushion modules shall be placed on movable pallets or frames conforming to the dimensions shown on the plans. The pallets or frames shall provide a full bearing base beneath the modules. The modules and supporting pallets or frames shall not be moved by sliding or skidding along the pavement or bridge deck.

A Type R or P marker panel shall be attached to the front of the crash cushion as shown on the plans, when the closest point of the crash cushion array is within 12 feet of the traveled way. The marker panel, when required, shall be firmly fastened to the crash cushion with commercial quality hardware or by other methods determined by the Engineer.

At the completion of the project, temporary crash cushion modules, sand filling, pallets or frames, and marker panels shall become the property of the Contractor and shall be removed from the site of the work. Temporary crash cushion modules shall not be installed in the permanent work.

Temporary crash cushion modules placed in conformance with the provisions in "Public Safety" of these special provisions will not be measured nor paid for.

### 10-1.25 EXISTING HIGHWAY FACILITIES

The work performed in connection with various existing highway facilities shall conform to the provisions in Section 15, "Existing Highway Facilities," of the Standard Specifications and these special provisions.

Except as otherwise provided for damaged materials in Section 15-2.04, "Salvage," of the Standard Specifications, the materials to be salvaged shall remain the property of the State, and shall be cleaned, packaged, bundled, tagged, and hauled to the District Landscape Maintenance Station located at Sawyer Camp Trail and Hillcrest Boulevard, Millbrae, CA, 94030, and stockpiled.

Items as shown on the plans to be salvaged include:

14. Half-barrel, 55-gallon steel drum planters.
15. Clay pot (25” diameter) planters.
16. Sewer manhole frame and cover.
17. Memorial and commorative plaques.

The Contractor shall notify the Engineer and the District 4 Maintenance Area Superintendent (San Francisco), telephone (415) 330-6536, a minimum of 48 hours prior to hauling salvaged material to the designated location. Existing plants in planters shall be watered and maintained in accordance with "Maintain Existing Planted Areas" of these special provisions, until delivery to the designated location.

Full compensation for maintaining existing plants shall be considered as included in the contract lump sum price paid for maintain existing planted areas and no additional compensation will be allowed therefor.

**ABANDON SEWER AND WATER PIPE LINE**

Existing sewer and water utility pipelines, where shown on the plans to be abandoned, shall be abandoned in place or, at the option of the Contractor, the pipelines shall be removed and disposed of. Resulting openings into existing structures that are to remain in place shall be plugged with concrete conforming to the provisions in Section 90-10 "Minor Concrete," of the Standard Specifications. The concrete shall contain not less than 505 pounds of cementitious material per cubic yard.

Abandoning sewer and water pipelines in place shall conform to the following:

1. Pipelines that intersect the side slopes shall be removed to a depth of not less than 3 feet measured normal to the plane of the finished side slope, before being abandoned.
2. Pipelines 12 inches in diameter and larger, shall, at the Contractor's option, be backfilled with either sand, controlled low strength material or slurry cement backfill conforming to the provisions in Section 19-3.062, "Slurry Cement Backfill," of the Standard Specifications by any method acceptable to the Engineer that completely fills the pipe. Sand backfill material shall be clean, free draining, and free from roots and other deleterious substances.
3. The ends of sewer and water pipelines shall be securely closed by a 0.5-foot thick tight fitting plug or wall of commercial quality concrete.

Sewer and water pipelines shall not be abandoned until their use is no longer required. The Contractor shall notify the Engineer in advance of any intended pipeline abandonment.

Full compensation for concrete plugs, pipe removal, structure excavation, and backfill (including sand, controlled low strength material or slurry cement backfill) shall be considered as included in the contract price paid per linear foot for abandon sewer and water pipeline and no additional compensation will be allowed therefor.

**REMOVE GATE AND FENCE**

Existing chain link gate and chain link fence, where shown on the plans, shall be removed and disposed of.

**REMOVE ROADSIDE SIGN AND ROADSIDE SIGN (STRAP AND SADDLE BRACKET)**

Existing roadside signs and roadside signs (strap and saddle bracket method), at those locations shown on the plans to be removed, shall be removed and disposed of.

Existing roadside signs and roadside signs (strap and saddle bracket method) shall not be removed until replacement signs have been installed or until the existing signs are no longer required for the direction of public traffic, unless otherwise directed by the Engineer.

Full compensation for salvaging sign panels shall be considered as included in the contract unit price paid for remove roadside sign and no separate payment will be made therefor.

**RELOCATE ROADSIDE SIGN**

Existing roadside signs shall be removed and relocated to the new locations shown on the plans.

Two holes shall be drilled in each existing post as required to provide the breakaway feature shown on the plans.

**RELOCATE BLUE STAR MEMORIAL**

Existing Blue Star Memorial shall be removed, stored and relocated to the new location as shown on the plans or as directed by the Engineer.

The contract lump sum price paid for relocate Blue Star Memorial shall include full compensation for furnishing all labor, materials, tools, equipment, and incidentals and for doing all work involved in relocate Blue Star Memorial, complete in place, including storage, as shown on the plans, as specified in the Standard Specification and these special provisions, and as directed by the Engineer.

**REMOVE MANHOLE**

Existing manhole, where shown on the plans to be removed, shall be completely removed and disposed of.

Remove manhole will be measured and paid for per unit in the same manner specified for remove manhole in Section 15, "Existing Highway Facilities," of the Standard Specifications

**COLD PLANE ASPHALT CONCRETE PAVEMENT**

Existing asphalt concrete pavement shall be cold planed at the locations and to the dimensions shown on the plans.

Planing asphalt concrete pavement shall be performed by the cold planing method. Planing of the asphalt concrete pavement shall not be done by the heater planing method.

Cold planing machines shall be equipped with a cutter head not less than 30 inches in width and shall be operated so that no fumes or smoke will be produced. The cold planing machine shall plane the pavement without requiring the use of a heating device to soften the pavement during or prior to the planing operation.

The depth, width, and shape of the cut shall be as shown on the plans or as designated by the Engineer. The final cut shall result in a uniform surface conforming to the plans. The outside lines of the planed area shall be neat and uniform. Planing asphalt concrete pavement operations shall be performed without damage to the surfacing to remain in place.

Planed widths of pavement shall be continuous except for intersections at cross streets where the planing shall be carried around the corners and through the conform lines. Following planing operations, a drop-off of more than 0.15-foot will not be allowed between adjacent lanes open to public traffic.

Where transverse joints are planed in the pavement at conform lines no drop-off shall remain between the existing pavement and the planed area when the pavement is opened to public traffic. If Hot Mix Asphalt (HMA) has not been placed to the level of existing pavement before the pavement is to be opened to public traffic a temporary HMA taper shall be constructed. HMA for temporary tapers shall be placed to the level of the existing pavement and tapered on a slope of 30:1 (Horizontal: Vertical) or flatter to the level of the planed area.

HMA for temporary tapers shall be the same quality as the HMA used elsewhere on the project or shall conform to the material requirements for minor HMA. HMA for tapers shall be compacted by any method that will produce a smooth riding surface. Temporary HMA tapers shall be completely removed, including the removal of loose material from the underlying surface, before placing the permanent surfacing. The removed material shall be disposed of outside the highway right of way in conformance with the provisions in Section 7-1.13, "Disposal of Material Outside the Highway Right of Way," of the Standard Specifications.

The material planed from the roadway surface, including material deposited in existing gutters or on the adjacent traveled way, shall be disposed of in conformance with the provisions in Section 7-1.13, "Disposal of Material Outside the Highway Right of Way," of the Standard Specifications. Removal operations of cold planed material shall be concurrent with planing operations and follow within 50 feet of the planer, unless otherwise directed by the Engineer.

Cold plane asphalt concrete pavement will be measured by the square yard. The quantity to be paid for will be the actual area of surface cold planed irrespective of the number of passes required to obtain the depth shown on the plans.

The contract price paid per square yard for cold plane asphalt concrete pavement shall include full compensation for furnishing all labor, materials, tools, equipment, and incidentals, and for doing all the work involved in cold planing asphalt concrete surfacing and disposing of planed material, including furnishing the HMA for and constructing, maintaining, removing, and disposing of temporary HMA tapers, as specified in the Standard Specifications and these special provisions and as directed by the Engineer.

**REMOVE CONCRETE**

Concrete, where shown on the plans to be removed, shall be removed.

The pay quantities of concrete to be removed will be measured by the cubic yard, measured before and during removal operations.

Concrete removed shall be disposed of outside the highway right of way in conformance with the provisions in Section 7-1.13, "Disposal of Material Outside the Highway Right of Way," of the Standard Specifications.

**REMOVE RETAINING WALL**

Retaining wall, where shown on the plans to be removed, shall be removed and disposed of.

Attention is directed to the requirements of "Asbestos Abatement" in Section 12-2, "Sitework," of these special provisions regarding the presence and removal of asbestos.

Retaining wall, or any portion thereof, to be removed shall not be removed until its use is no longer required.

Full compensation for retaining wall asbestos abatement work shall be considered as included in the contract price paid per linear foot for remove retaining wall and no additional compensation will be allowed therefor.

## 10-1.26 CLEARING AND GRUBBING

Clearing and grubbing shall conform to the provisions in Section 16, "Clearing and Grubbing," of the Standard Specifications and these special provisions.

Additional areas for clearing and grubbing include the following locations:

A. 12" x 12" timbers near existing coin-operated telephones, maximum 10 timbers
B. Black plastic on-grade pipe, maximum 25 linear feet
C. Decorative fire hydrant in pet area
D. Wooden bench formed from large log
E. Concrete sprinkler protectors, maximum 20 count
F. Two sets of 4-tread concrete steps
G. Miscellaneous concrete, maximum 3 cubic yards
H. Wooden "Crystal Springs Safety Rest Area" sign at off-ramp
I. Wooden log near drive-gate and emergency call box
J. Above ground tree stump near drive-gate
K. Miscellaneous trash receptacles, maximum 6 count
L. Miscellaneous site elements and debris not otherwise noted, maximum 4 cubic yards.

Vegetation shall be cleared and grubbed only within the excavation and embankment slope lines.

**10-1.27 EARTHWORK**

Earthwork shall conform to the provisions in Section 19, "Earthwork," of the Standard Specifications and these special provisions.

Where a portion of the existing surfacing is to be removed, the outline of the area to be removed shall be cut on a neat line with a power-driven saw to a minimum depth of 0.17-foot before removing the surfacing. Full compensation for cutting the existing surfacing shall be considered as included in the contract price paid per cubic yard for roadway excavation and no additional compensation will be allowed therefor.

The portion of imported borrow placed within 4 feet of the finished grade shall have a Resistance (R-Value) of not less than 15.

Reinforcement or metal attached to reinforced concrete rubble placed in embankments shall not protrude above the grading plane. Prior to placement within 2 feet below the grading plane of embankments, reinforcement or metal shall be trimmed to no greater than 3/4 inch from the face of reinforced concrete rubble. Full compensation for trimming reinforcement or metal shall be considered as included in the contract prices paid per cubic yard for the types of excavation shown in the Engineer's estimate, or the contract prices paid for furnishing and placing imported borrow or embankment material, as the case may be, and no additional compensation will be allowed therefor.

Imported borrow shall be mineral material including rock, sand, gravel, or earth. The Contractor shall not use man-made refuse in imported borrow including:

A. Portland cement concrete
B. Asphalt concrete
C. Hot mix asphalt
D. Material planed from roadway surfaces
E. Residue from grooving or grinding operations
F. Metal
G. Rubber
H. Mixed debris
I. Rubble

**10-1.28 CONTROLLED LOW STRENGTH MATERIAL**

Controlled low strength material shall consist of a workable mixture of aggregate, cementitious materials, and water and shall conform to the provisions for slurry cement backfill in Section 19-3.062, "Slurry Cement Backfill," of the Standard Specifications and these special provisions.

At the option of the Contractor, controlled low strength material may be used as structure backfill for pipe culverts, except that controlled low strength material shall not be used as structure backfill for culverts having a diameter or span greater than 20 feet.

When controlled low strength material is used for structure backfill, the width of the excavation shown on the plans may be reduced so that the clear distance between the outside of the pipe and the side of the excavation, on each side of the pipe, is a minimum of 12 inches. This minimum may be reduced to 6 inches when the height of cover is less than or equal to 20 feet or the pipe diameter or span is less than 42 inches.

Controlled low strength material in new construction shall not be permanently placed higher than the basement soil. For trenches in existing pavements, permanent placement shall be no higher than the bottom of the existing pavement permeable drainage layer. If a drainage layer does not exist, permanent placement in existing pavements shall be no higher than one inch below the bottom of the existing asphalt concrete surfacing or no higher than the top of base below the existing portland cement concrete pavement. The minimum height that controlled low strength material shall be placed, relative to the culvert invert, is 0.5 diameter or 0.5 height for rigid culverts and 0.7 diameter or 0.7 height for flexible culverts.

When controlled low strength material is proposed for use, the Contractor shall submit a mix design and test data to the Engineer for approval prior to excavating the trench for which controlled low strength material is proposed for use. The test data and mix design shall provide for the following:

A. A 28-day compressive strength between 50 pounds per square inch and 100 pounds per square inch for pipe culverts having a height of cover of 20 feet or less and a minimum 28-day compressive strength of 100 pounds per square inch for pipe culverts having a height of cover greater than 20 feet. Compressive strength shall be determined in conformance with the requirements in ASTM Designation: D 4832.
B. Cement shall be any type of portland cement conforming to the requirements in ASTM Designation: C 150; or any type of blended hydraulic cement conforming to the requirements in ASTM Designation: C 595M or the physical requirements in ASTM Designation: C 1157M. Testing of cement will not be required.
C. Admixtures may be used in conformance with the provisions in Section 90-4, "Admixtures," of the Standard Specifications. Chemical admixtures containing chlorides as Cl in excess of one percent by weight of admixture, as determined in conformance with the requirements of California Test 415, shall not be used. If an air-entraining admixture is used, the maximum air content shall be limited to 20 percent. Mineral admixtures shall be used at the Contractor's option.

Materials for controlled low strength material shall be thoroughly machine-mixed in a pugmill, rotary drum or other approved mixer. Mixing shall continue until the cementitious material and water are thoroughly dispersed throughout the material. Controlled low strength material shall be placed in the work within 3 hours after introduction of the cement to the aggregates.

When controlled low strength material is to be placed within the traveled way or otherwise to be covered by paving or embankment materials, the material shall achieve a maximum indentation diameter of 3 inches prior to covering and opening to public traffic. Penetration resistance shall be measured in conformance with the requirements in ASTM Designation: D 6024.

Controlled low strength material used as structure backfill for pipe culverts will be considered structure backfill for compensation purposes.

### 10-1.29 MATERIAL CONTAINING NATURALLY OCCURRING ASBESTOS

This work includes specifications for handling, stockpiling, transporting, and disposing of material containing naturally occurring asbestos (NOA). The State regulates material containing NOA and material from areas where serpentine or ultramafic rock is present. Material containing NOA is material containing 0.25 percent or greater concentration of asbestos. Naturally occurring asbestos (NOA) is present within the job site limits. The tested levels of NOA range from less than 0.25 to 6.00 percent asbestos, with an average of 1.78 percent as estimated by the 90 percent upper confidence limit (UCL) and as analyzed by California Air Resources Board (CARB) Test Method 435.

Perform earthwork in areas containing NOA under Section 19, "Earthwork," of the Standard Specifications and these special provisions. A copy of the asbestos testing report is available as specified in "Project Information" of these special provisions.

Notify the Air Pollution Control District (APCD) at least 15 days before starting work in areas containing NOA and comply with the California Air Resources Board (CARB), Asbestos Airborne Toxic Control Measure for Construction, Grading, Quarrying and Surface Mining Operations (ATCM) and California Code of Regulations (CCR), Title 17, Section 93105 (d)(1)(A).

Material containing NOA exists throughout the project site.

Surplus material containing NOA may be temporarily stockpiled until such time it is transported and disposed of in accordance with these specifications or used on site (for excavated material containing 0.25 percent NOA or greater). Limit stockpile locations to areas that contain NOA within the job site limits when not actively working with stockpile material. Cover temporary stockpiles with polyethylene sheeting of 10-mil minimum thickness or stabilize stockpiles by other methods permitted by the ATCM under CCR Title 17, Section 93105(d)(1)(3). Temporarily stockpiled surplus material containing NOA is not selected material under Section 19-2.07, "Selected Material," of the Standard Specifications.

Do not leave NOA surface areas exposed unless these areas are stabilized by being kept wetted or by being treated with a chemical dust palliative. Disturbed material containing NOA permanently placed during construction activities must be covered with a 3 inch minimum layer of asbestos-free material that has been certified by the Engineer. Survey the locations

where material containing NOA is placed using GPS, electronic theodolite, or other methods approved by the Engineer and submit the information to the Engineer.

Material with 1 percent or higher concentration of NOA is hazardous material and for removing, managing, hauling, and disposing of the material outside the right-of-way, comply with Federal, State, and local laws and ordinances.

Material with 0.25 percent or higher of NOA must not be left exposed on the surface if disturbed.

**SUBMITTALS**

Submit the asbestos compliance plan (ACP) signed by a Certified Industrial Hygienist (CIH) certified in Comprehensive Practice by the American Board of Industrial Hygiene to the Engineer for acceptance at least 15 days before starting work in areas containing NOA.

**ASBESTOS COMPLIANCE PLAN**

Prepare and implement a site specific asbestos compliance plan (ACP) to prevent or minimize worker exposure to asbestos. The ACP must comply with:

1. CCR, Title 8, Section 1529, (Asbestos) and Section 5192, (Hazardous Waste Operations and Emergency Response)
2. Occupational Safety and Health Guidance Manual published by the National Institute of Occupational Safety and Health (NIOSH)
3. Occupational Safety and Health Administration (OSHA), including addenda to it issued up to and including the date of advertisement of the contract

Include in the ACP:

1. Identification of personnel designated to be on site
2. Job hazard analysis for work assignments
3. Summary of potential risks
4. Worker exposure air monitoring plan
5. Description of personal protective equipment
6. Delineation of work zones on the job site
7. Decontamination procedures
8. General safe work practices
9. Site security measures
10. Emergency response plans
11. Description of worker training

Before performing work in areas with material containing NOA, personnel who have not had the worker training must complete a safety training program that meets the requirements of the ACP. The safety training program must meet the requirements of CCR, Title 8, Section 1529, (Asbestos), and Section 5192 (b)(4)(B), (Hazardous Waste Operations and Emergency Response). Provide the Engineer written certification of completion of safety training for each trainee before performing work in areas containing NOA.

Provide training, personal protective equipment, and washing facilities for 3 Department employees.

When required by local APCD, perform daily ambient air monitoring on this job site. If daily ambient monitoring is required, submit a written air monitoring report to the Engineer every month. The report must include:

1. Air monitoring results
2. An analysis of results from the prior month
3. The name and location of the laboratory where the analysis was performed
4. An assessment of exposures of workers or the public
5. Descriptions of the type of air monitoring equipment
6. Sampling frequency

**SAMPLING AND ANALYSIS PLAN**

**DUST CONTROL PLAN**

Prepare and implement a site specific dust control plan (DCP). Prevent visible dust emission during excavation, stockpiling, transportation, or placement of material containing NOA under Section 10, "Dust Control," of the Standard Specifications, these special provisions, and the requirements in the Asbestos ATCM CCR Title 17, Section 93105(d)(1)(B).

Control dust in areas with material containing NOA using measures that include the following:

1. Stabilize unpaved areas subject to vehicular traffic by keeping adequately wetted, treated with a chemical dust palliative, or covered with material that contains less than 0.25 percent asbestos
2. The speed of vehicles and equipment traveling across unpaved areas must not be more than 15 mph unless the road surface and surrounding area is sufficiently stabilized to prevent vehicles and equipment going faster from causing dust that is visible from crossing job site limits
3. Stockpiles and disturbed areas not subject to vehicular traffic must be located in the plan and stabilized by being kept adequately wetted, treated with a chemical dust palliative, or covered with material that contains less than 0.25 percent asbestos
4. Conduct activities so that no dirt or mud tracking is visible on any paved roadway open to the public

**MATERIAL TRANSPORTATION AND DISPOSAL**

Excess material containing 0.25 percent or more NOA must not be disposed of in a surfacing application as defined in CCR Title 17, Section 93106, "Asbestos Airborne Toxic Control Measure for Surfacing Applications."

Transport surplus material containing NOA to a landfill facility appropriately permitted to receive the NOA material. You are responsible for identifying the appropriately permitted landfill to receive the material. When handling and disposing of surplus material obtain written authorization from the owner of the disposal facility as provided in the ATCM CCR Title 17, Section 93105 and as required by Health and Safety Code Section 25249.6, stating that the surplus material contains NOA.

Dispose of surplus material containing asbestos with concentrations equal to or greater than 1 percent as hazardous waste at a landfill facility under permit issued by the California Environmental Protection Agency.

Material containing NOA excavated from outside the limits of payment for contract items is the property of the Contractor and must be disposed of in accordance with these special provisions.

Provide the Engineer copies of manifests, landfill receipts and certified weight tickets showing the amount of disposal material containing NOA and the concentration of asbestos that was sent to the facility. Provide the Engineer a copy of additional test results if required by the owner of the landfill facility.

The Engineer obtains the Environmental Protection Agency Generator Identification Number for any disposal of Department of Toxic Substance Control regulated hazardous material and will sign all manifests. Notify the Engineer 5 days before the manifests are to be signed. Ensure that the Engineer has full access to the disposal facility during construction.

**MEASUREMENT AND PAYMENT**

Roadway excavation (naturally occurring asbestos) will be measured and paid for by the cubic yard in the same manner specified for roadway excavation in Section 19, "Earthwork," of the Standard Specifications. Structure excavation (naturally occurring asbestos) will be measured and paid for by the cubic yard in the same manner as structure excavation specified for the construction of foundations for structures in Section 19-3, "Structure Excavation and Backfill."

Surveying locations where material containing NOA is placed as directed by the Engineer and reporting survey data to the Engineer will be paid for as extra work as provided in Section 4-1.03D, "Extra Work", of the Standard Specifications.

The contract lump sum price paid for asbestos compliance plan (naturally occurring asbestos) must include full compensation for preparing and implementing the ACP and no additional compensation will be allowed therefor.

The contract lump sum price paid for dust control plan (naturally occurring asbestos) includes full compensation for preparing and implementing the DCP and providing notification and payment of fees to the APCD and no additional compensation will be allowed therefor.

Transporting and disposing of surplus material containing greater than or equal to 0.25 percent of NOA to an appropriately permitted landfill facility, including providing copies of disposal documents to the Engineer will be paid for as extra work under Section 4-1.03D, "Extra Work," of the Standard Specifications.

Placing of NOA material and covering of NOA material within the project limits must be directed by the Engineer and will be paid for as extra work under Section 4-1.03D, "Extra Work," of the Standard Specifications.

Air monitoring and reporting results will be paid for as extra work under Section 4-1.03D, "Extra Work," of the Standard Specifications.

The Department does not pay for sampling, analyzing, transporting, and disposing of material containing NOA from outside the limits of payment for contract items.

## 10-1.30 EROSION CONTROL (TYPE D)

Erosion control (Type D) includes applying erosion control materials to embankment and excavation slopes and other areas disturbed by construction activities. Erosion control (Type D) must comply with Section 20-3, "Erosion Control," of the Standard Specifications and these special provisions.

If the slope on which the erosion control to be placed is finished during the rainy season as specified under "Water Pollution Control" of these special provisions, apply erosion control to the slope immediately.

Before applying erosion control materials, prepare soil surface under Section 19-2.05, "Slopes," of the Standard Specifications, except that rills and gullies exceeding 2 inches in depth or width must be leveled. Remove vegetative growth, temporary erosion control materials, and other debris from areas to receive erosion control.

Before applying erosion control materials, the Engineer designates the ground location of erosion control (Type D) in increments of one acre or smaller for smaller areas. Place stakes or other suitable markers at the locations designated by the Engineer. Furnish all tools, labor and materials required to adequately indicate the various locations.

## MATERIALS

Materials must comply with Section 20-2, "Materials," of the Standard Specifications and these special provisions.

### Seed

Seed must comply with Section 20-2.10, "Seed," of the Standard Specifications. Seed not required to be labeled under the California Food and Agricultural Code shall be tested for purity and germination by a seed laboratory certified by the Association of Official Seed Analysts or by a seed technologist certified by the Society of Commercial Seed Technologists. Measure and mix individual seed species in the presence of the Engineer.

Seed must contain at most 1.0 percent total weed seed by weight.

Deliver seed to the job site in unopened separate containers with the seed tag attached. Containers without a seed tag attached are not accepted. The Engineer takes a sample of approximately 1 ounce or 0.25 cup of seed for each seed lot greater than 2 pounds.

Seed must comply with the following:

Seed

| Botanical Name (Common Name) | Percent Germination (Minimum) | Pounds Pure Live Seed Per Acre (Slope Measurement) |
|---|---|---|
| Lupinus bicolor (Pygmy Leaf Lupine) | 40 | 4 |
| Lupinus nanus (Sky Lupine) | 40 | 4 |
| Lotus purshianus (Purshing's Lotus) | 40 | 3 |
| Elymus glaucus (Blue Wild Rye) | 40 | 9 |
| Festuca rubra var Molate (Red Fescue) | 40 | 6 |
| Hordeum vulgare var UC337/UC603 (Barley (UC337, UC603) | 60 | 62 |
| Festuca idahoensis (Idaho Festuca) | 35 | 6 |

### Seed Sampling Supplies

At the time of seed sampling, provide the Engineer a glassine lined bag and custody seal tag for each seed lot sample.

### Straw

Straw must comply with Section 20-2.06, "Straw," of the Standard Specifications and these special provisions.

Wheat and barley straw must be derived from irrigated crops.

Before delivery of wheat or barley straw to the job site, provide the name, address and telephone number of the grower.

Straw must be derived from wheat or barley.

Straw must be free of plastic, glass, metal, rocks, and refuse or other deleterious material.

### Compost

The compost producer must be fully permitted as specified under the California Integrated Waste Management Board, Local Enforcement Agencies and any other State and Local Agencies that regulate Solid Waste Facilities. If exempt from State permitting requirements, the composting facility must certify that it follows guidelines and procedures for production of

compost meeting the environmental health standards of Title 14, California Code of Regulations, Division 7, Chapter 3.1, Article 7.

The compost producer must be a participant in United States Composting Council's Seal of Testing Assurance program.

Compost may be derived from any single, or mixture of any of the following feedstock materials:

1. Green material consisting of chipped, shredded, or ground vegetation; or clean processed recycled wood products
2. Biosolids
3. Manure
4. Mixed food waste

Compost feedstock materials to reduce weed seeds, pathogens and deleterious materials as specified under Title 14, California Code of Regulations, Division 7, Chapter 3.1, Article 7, Section 17868.3

Compost must not be derived from mixed municipal solid waste and must be reasonably free of visible contaminates. Compost must not contain paint, petroleum products, pesticides or any other chemical residues harmful to animal life or plant growth. Compost must not possess objectionable odors.

Metal concentrations in compost must not exceed the maximum metal concentrations listed in Title 14, California Code of Regulations, Division 7, Chapter 3.1, Section 17868.2.

Compost must comply with the following:

Physical/Chemical Requirements

| Property | Test Method | Requirement |
|---|---|---|
| pH | *TMECC 04.11-A, Elastometric pH 1:5 Slurry Method, pH Units | 6.0–8.0 |
| Soluble Salts | TMECC 04.10-A, Electrical Conductivity 1:5 Slurry Method dS/m (mmhos/cm) | 0-10.0 |
| Moisture Content | TMECC 03.09-A, Total Solids & Moisture at 70+/- 5 deg C, % Wet Weight Basis | N/A |
| Organic Matter Content | TMECC 05.07-A, Loss-On-Ignition Organic Matter Method (LOI), % Dry Weight Basis | 30–65 |
| Maturity | TMECC 05.05-A, Germination and Vigor<br>Seed Emergence<br>Seedling Vigor<br>% Relative to Positive Control | <br>80 or Above<br>80 or Above |
| Stability | TMECC 05.08-B, Carbon Dioxide Evolution Rate mg $CO_2$-C/g OM per day | 8 or below |
| Particle Size | TMECC 02.02-B Sample Sieving for Aggregate Size Classification % Dry Weight Basis | 95% Passing 5/8 inch<br>70% Passing 3/8 inch |
| Pathogen | TMECC 07.01-B, Fecal Coliform Bacteria < 1000 MPN/gram dry wt. | Pass |
| Pathogen | TMECC 07.01-B, Salmonella < 3 MPN/4 grams dry wt. | Pass |
| Physical Contaminants | TMECC 02.02-C, Man Made Inert Removal and Classification:<br>Plastic, Glass and Metal, % > 4mm fraction | Combined Total: < 1.0 |
| Physical Contaminants | TMECC 02.02-C, Man Made Inert Removal and Classification:<br>Sharps (Sewing needles, straight pins and hypodermic needles), % > 4mm fraction | None Detected |

*TMECC refers to "Test Methods for the Examination of Composting and Compost," published by the United States Department of Agriculture and the United States Compost Council (USCC).

Before compost application, provide the Engineer with a copy of the compost producer's compost technical data sheet and a copy of the compost producers Seal of Testing Assurance certification. The compost technical data sheet includes:

1. Laboratory analytical test results
2. Directions for product use
3. List of product ingredients

Before compost application, provide the Engineer with a Certificate of Compliance under Section 6-1.07, "Certificates of Compliance," of the Standard Specifications.

**Stabilizing Emulsion**

Stabilizing emulsion must comply with Section 20-2.11, "Stabilizing Emulsion," of the Standard Specifications and these special provisions.

Stabilizing emulsion:

1. Must be in a dry powder form
2. Must be a processed organic adhesive used as a soil tackifier
3. May be reemulsifiable

**APPLICATION**

Apply erosion control materials in separate applications in the following sequence:

1. Apply the following mixture with hydroseeding equipment at the rates indicated within 60 minutes after the seed has been added to the mixture:

| Material | Pounds Per Acre (Slope Measurement) |
|---|---|
| Seed | 94 |
| Fiber | 285 |

| Material | Cubic Yards Per Acre (Slope Measurement) |
|---|---|
| Compost | 4 |

2. Compost may be dry applied at the total of the rates specified in the preceding table and the following table instead of including it as part of the hydro-seeding operations. In areas where the compost is dry applied, all compost for that area must be applied before the next operation.
3. Apply straw at the rate of 2 tons per acre based on slope measurements. Incorporation of straw will not be required. Distribute straw evenly without clumping or piling.
4. Apply the following mixture with hydro-seeding equipment at the corresponding rates:

| Material | Pounds Per Acre (Slope Measurement) |
|---|---|
| Fiber | 285 |
| Stabilizing Emulsion (Solids) | 125 |

| Material | Cubic Yards Per Acre (Slope Measurement) |
|---|---|
| Compost | 4 |

The ratio of total water to total stabilizing emulsion in the mixture must be as recommended by the manufacturer.

Once straw work is started in an area, complete stabilizing emulsion applications in that area on the same working day.

The Engineer may change the rates of erosion control materials to meet field conditions.

**MEASUREMENT AND PAYMENT**

Erosion control (Type D) will be measured by the square yard or by the acre, whichever is designated in the Engineer's Estimate. The area will be calculated on the basis of actual or computed slope measurements.

The contract price paid per square yard or acre for erosion control (Type D) includes full compensation for furnishing all labor, materials, tools, equipment, and incidentals, and for doing all the work involved in applying erosion control (Type D) complete in place, as shown on the plans, as specified in the Standard Specifications and these special provisions, and as directed by the Engineer.

### 10-1.31 IRRIGATION CROSSOVERS

Irrigation crossovers shall conform to the provisions in Section 20-5, "Irrigation Systems," of the Standard Specifications and these special provisions.

Conduits shall be placed in open trenches in conformance with the provisions in Section 20-5.03B, "Conduit for Irrigation Crossovers," of the Standard Specifications, except Type A pavement marker will not be required unless otherwise shown on the plans.

Conduits shall be corrugated high density polyethylene (CHDPE) pipe. Corrugated high density polyethylene pipe shall conform to the requirements in ASTM Designation: F 405 or F 667, or AASHTO Designation: M 252 or M 294 and shall be Type S. Couplings and fittings shall be as recommended by the pipe manufacturer.

Water line crossovers shall conform to the provisions in Section 20-5.03C, "Water Line Crossovers," of the Standard Specifications.

Sprinkler control crossovers shall conform to the provisions in Section 20-5.027D, "Sprinkler Control Crossovers," of the Standard Specifications.

Installation of pull boxes shall conform to the provisions in Section 20-5.027I, "Conductors, Electrical Conduit and Pull Boxes," of the Standard Specifications. When no conductors are installed in electrical conduits, pull boxes for irrigation crossovers shall be installed on a foundation of compacted soil.

### 10-1.32 IRRIGATION SLEEVE

Irrigation sleeves shall be polyvinyl chloride (PVC) plastic pipe and shall conform to the provisions in Section 20-2.15B(1), "Plastic Pipe Supply Line," of the Standard Specifications and these special provisions.

Irrigation sleeves less than 6 inches in diameter shall have a pressure rating (PR) 315.

Irrigation sleeves 6 inches or larger in diameter shall be Schedule 40.

Fittings shall be Schedule 40.

Irrigation sleeves shall be installed where shown on the plans.

Irrigation sleeves shall be installed not less than 1.5 feet below finished grade measured to the top of the sleeve. Sleeves shall extend 6 inches beyond paving. The ends of the sleeve shall be capped until use.

Quantities of irrigation sleeve to be paid will be determined from the slope length designated by the Engineer. Irrigation sleeve placed in excess of the lengths designated will not be paid for.

The contract price paid per linear foot for irrigation sleeve shall include full compensation for furnishing all labor, materials, tools, equipment, and incidentals, and for doing all the work involved in irrigation sleeve, complete in place, as shown on the plans, as specified in the Standard Specifications and these special provisions, and as directed by the Engineer.

### 10-1.33 IMPORTED TOPSOIL

Imported topsoil shall conform to the provisions in Section 20-2, "Materials," and Section 20-3, "Erosion Control," of the Standard Specifications.

### 10-1.34 AGGREGATE BASE

Aggregate base must comply with Section 26, "Aggregate Bases," of the Standard Specifications and these special provisions.

Aggregate base must be Class 3.

Do not store reclaimed asphalt concrete or aggregate base with reclaimed asphalt concrete within 100 feet measured horizontally of any culvert, watercourse, or bridge.

The spreading and compacting specifications of the Standard Specifications do not apply to Class 3 aggregate base.

Class 3 aggregate base must comply with:

Grading (Percentage Passing)

| Sieve Sizes | 3/4" Maximum | |
|---|---|---|
| | Operating Range | Contract Compliance |
| 1" | 100 | 100 |
| 3/4" | 90 - 100 | 87 - 100 |
| No. 4 | 35 - 60 | 30 - 65 |
| No. 30 | 10 - 30 | 5 - 35 |
| No. 200 | 2 - 9 | 0 - 12 |

Spread and compact aggregate base to produce a uniform base, firmly compacted, and free from pockets of coarse or fine material.

## 10-1.35 PARKING AREA SEAL COAT

Parking area seal coat shall consist of mixing asphaltic emulsion, aggregate, polymer and water and spreading the mixture on pavement surfaces. Parking area seal coat shall be applied as shown on the plans and in conformance these special provisions.

Attention is directed to "Replace Asphalt Concrete Surfacing" of these special provisions.

### MATERIALS

Asphaltic emulsion shall be either Grade SS1h or CSS1h and shall conform to the provisions in Section 94, "Asphaltic Emulsions," of the Standard Specifications, except that in Tables 1 and 2, the values for penetration at 25°C, in the tests on residue from distillation, shall be a minimum of 20 to a maximum of 60. Clay stabilized emulsion with a solids content of not less than 45 percent by weight may be used.

Mineral aggregate components shall be clean, hard, durable, uncoated particles that are free from decomposed materials, organic materials and other deleterious substances. The percentage composition, by weight, of the aggregate shall be 100 percent passing the No. 16 sieve.

At least 15 days prior to their intended use, the Contractor shall furnish samples of aggregates from the source the Contractor proposes to use for the project. The samples shall have been processed in a manner representative of that for the material to be used in the work.

Polymer additive shall be a commercial quality polymer formulated for the purpose intended. The Contractor shall submit the manufacturer's product data information for the proposed polymer at least 10 days prior to use.

Water shall be potable and of such quality that the water will not separate from the emulsion before the material is placed in the work.

Oil seal primer shall be a quick-drying emulsion with suitable admixtures manufactured specifically for the purpose of isolating the parking area seal coat from residual oils, petroleum grease, and gasoline stained pavements. The properties of the oil seal primer shall be compatible with the new parking area seal coat materials. The Contractor shall submit the manufacturer's product data information of the material proposed for use at least 10 days prior to use.

### MIX DESIGN AND CERTIFICATION

At least 10 days before parking area seal coat placement, the Contractor shall submit to the Engineer for approval a laboratory report of tests and proposed mix designs for the specific materials to be used on the project.

A laboratory capable of performing the applicable tests shall perform the tests and mix design. The proposed mixture shall conform to the following requirements of the following tests:

| Test Description | Test Method | Requirement | |
|---|---|---|---|
| | | Minimum | Maximum |
| Mass per Liter | ASTM Designation: D 244 | 1.1 kg | |
| Cone Penetration, mm | California Test 413 | 340 | 700 |
| % Non-Volatile<br>% Non-Volatile soluble in Tri-clorethylene | ASTM Designation: D 2042* | 50<br>10 | <br>35 |
| Wet Track Abrasion, $g/m^2$ | ASTM Designation: D 3910 | | 380 |
| Dried Film Color | | Black | |
| Viscosity | ASTM Designation: D 562 | 75KREB | |

* Weigh 10 grams of homogenous product into a previously tared, small ointment can. Place in constant temperature oven at 165°C ±5°C for 90 minutes ±3 minutes. Cool, reweigh and calculate non-volatile components as a percent of the original weight.

The laboratory that performs the tests and mix designs shall prepare a signed report that contains the following: results of the tests on individual materials, comparisons of the test results to the specifications, and the amount of water that is allowed to be added on site. Previous laboratory reports covering the same materials may be accepted, provided that the reports were prepared during the same calendar year.

No substitution of other mix designs for parking area seal coat material will be permitted unless the materials proposed for substitution are tested and a laboratory report is submitted for the substituted design as specified above.

The Contractor shall furnish a Certificate of Compliance to the Engineer in conformance with the provisions in Section 6-1.07, "Certificates of Compliance" of the Standard Specifications. The certificate shall certify that the parking area seal coat material, conforms to the these special provisions.

**PROPORTIONING**

Parking area seal coat mixture shall be produced by uniformly blending asphaltic emulsion, aggregate, water, and admixtures in a central plant capable of producing a finished product conforming to these special provisions. Components shall be measured by electronic or mechanical controls that consistently proportion the additives. Blending the admixtures with the base asphaltic emulsion shall be by mechanical means to provide a uniform mixture.

Parking area seal coat shall be stored in a tank equipped with power driven mixing or agitation equipment capable of keeping the stored material thoroughly and uniformly mixed. The stored material shall be protected from freezing in cold weather conditions.

Parking area seal coat shall contain a minimum of 2 percent polymer by volume of the undiluted asphaltic emulsion material. The polymer shall be added on site and verified by the Engineer.

Water may be added at the project site in conformance with the manufacturer's recommendations for consistency and spreadability, but shall not exceed 15 percent by volume.

**SURFACE PREPARATION**

Pavement surfaces to receive parking area seal coat shall be cleaned of oil and grease spots, dirt, clay, dust, and other deleterious materials that might adversely affect bonding of the seal coat. Cleaning shall be done by air blowing, vacuum, mechanical sweeper, washing, or other methods approved by the Engineer. Solvents shall not be used for cleaning pavement.

Tack coat shall be applied to weathered surfaces, areas previously coated with coal tar, and other areas as directed by the Engineer. The tack coat shall consist of one part Grade SS1h asphaltic emulsion conforming to the provisions in Section 94, "Asphaltic Emulsions," and 4 parts water applied at a rate of 0.63-gallon to 1.58 gallon per square yard. The tack coat color shall be completely black and the tack coat shall be cured prior to application of the parking area seal coat.

When detergents are used in the washing method for cleaning the pavement surface, the pavement shall be thoroughly rinsed with water before application of the parking area seal coat. Detergents shall not be used that will adversely affect the pavement surface or the seal coat, as determined by the Engineer. The surface shall not have standing water prior to the application of the seal coat.

After cleaning the existing pavement, remaining oil and grease spots shall be sealed with oil seal primer. The oil seal primer shall be applied in conformance with the manufacturer's recommendations.

Areas where oil or grease has penetrated the existing asphalt concrete, and cleaning, and applying oil seal primer or tack coat are insufficient to produce an acceptable surface to receive the seal coat shall be repaired as directed by the Engineer. Repairing these asphalt concrete areas will be paid for as extra work in conformance with the provisions in Section 4-1.03D, "Extra Work," of the Standard Specifications.

**APPLICATION**

Application of the parking area seal coat shall be performed by mechanical means using rubber faced squeegees, brooms, distributor bars, spray wands, any combination of these methods, or other techniques approved by the Engineer.

Parking area seal coat material sampled at the project site shall be sealed within 30 minutes of placement and shall be the finished, undiluted material.

Immediately prior to application of the parking area seal coat, the pavement surface shall be dampened, as directed by the Engineer. A distributor truck or other equipment approved by the Engineer shall be used to apply the water. The surface shall not have any standing water prior to application of the sealant.

The parking area seal coat shall be applied in one or more applications and shall be uniform and free flowing, free of lumps and other inconsistencies. If, after the addition of the maximum allowable water volume, the mixture does not produce a seal coat as specified, the seal coat will be rejected and shall be removed, at the Contractor's expense, from the site in conformance with the provisions in Section 7-1.13, "Disposal of Material Outside the Highway Right of Way" of the Standard Specifications. Replacement parking area seal coat, conforming to the special provisions, shall be furnished and applied.

The parking area seal coat shall be thoroughly dry prior to application of subsequent coats.

Parking area seal coat shall be applied uniformly in a continuous manner so that no ridges or uncoated areas shall exist. Parking area seal coat shall be applied at a total rate of 4.1 to 5.1 gallon per square yard, not including added water.

Parking area seal coat shall not be applied when the ambient temperature is less than 55° F or the surface temperature is less than 60° F. Parking area seal coat shall not be applied within 24 hours of rain or within 24 hours prior to forecasted rain, freezing temperatures, during rain, or when the surface contains standing water. The Contractor shall notify the Engineer to

inactivate the irrigation control system not less than 5 days prior to applying the seal coat. Irrigation watering will be kept off the area to be seal coated for at least 24 hours prior to and at least 24 hours after the application of the parking area seal coat.

Upon completion of the final application, the area shall be protected from traffic or equipment for a period of not less than 24 hours.

Striping shall be applied only after the parking area seal coat has thoroughly dried.

**MEASUREMENT AND PAYMENT**

Parking area seal coat will be measured by the ton. The quantity of parking area seal coat to be paid for will be the combined weight of the aggregate and asphaltic emulsion used in the seal coat mixture. The weight of added water in the seal coat mixture will not be included in the weight of the seal coat to be paid for. The weight of aggregate and asphaltic emulsion will be determined in conformance with the provisions in Section 9-1.01, "Measurement of Quantities," of the Standard Specifications, except that no deduction will be made for water in the aggregate and asphaltic emulsion.

The contract price paid per ton for parking area seal coat shall include full compensation for furnishing all labor, materials, tools, equipment, and incidentals, and for doing all work involved in constructing the parking area seal coat, complete in place, as shown on the plans, as specified in the Standard Specifications and these special provisions, and as directed by the Engineer.

Tack coat will be measured by the ton in conformance with the provisions in Section 94-1.07, "Measurement," of the Standard Specifications.

The contract price paid per ton for tack coat shall include full compensation for furnishing all labor, materials, tools, equipment, and incidentals, and for doing all the work involved in applying tack coat, complete in place, as shown on the plans, as specified in the Standard Specifications and these special provisions, and as directed by the Engineer.

## 10-1.36 HOT MIX ASPHALT

### GENERAL

#### Summary

This work includes producing and placing hot mix asphalt (HMA) Type A using the Method process.

Comply with Section 39, "Hot Mix Asphalt," of the Standard Specifications.

### MATERIALS

#### Asphalt Binder

The grade of asphalt binder mixed with aggregate for HMA Type A must be PG 64-10.

#### Aggregate

The aggregate for HMA Type A must comply with the 1/2 inch grading.

### CONSTRUCTION

#### Vertical Joints

Do not leave a vertical joint more than 0.15 foot high between adjacent lanes open to public traffic.

#### Widening

If widening existing pavement, construct new structural section on both sides of the existing pavement to match the elevation of the existing pavement's edge at each location before placing Parking Area Seal Coat over the existing pavement.

#### Conform Tapers

Place additional HMA along the pavement's edge to conform to road connections and private drives. Hand rake, if necessary, and compact the additional HMA to form a smooth conform taper.

## 10-1.37 MINOR HOT MIX ASPHALT

### GENERAL

#### Summary

This work includes producing hot mix asphalt (HMA) at a central mixing plant and placing it as specified.

**MATERIALS**

For minor HMA:

1. Do not submit a job mix formula.
2. Choose the 3/8-inch or 1/2-inch HMA Type A or Type B aggregate gradation under Section 39-1.02E, "Aggregate," of the Standard Specifications.
3. Minimum asphalt binder content must be 6.8 percent for 3/8-inch aggregate gradation and 6.0 percent for 1/2-inch aggregate gradation.
4. Choose asphalt binder Grade PG 64-10, PG 64-16, or PG 70-10 under Section 92, "Asphalts," of the Standard Specifications.

If you request and the Engineer authorizes, you may reduce the minimum asphalt binder content.

Tack coat must comply with Section 39, "Hot Mix Asphalt," of the Standard Specifications.

**CONSTRUCTION**

Using a self-propelled spreader, spread minor HMA ready for compacting without further shaping.

Compact minor HMA with a vibratory roller providing a minimum of 7,000 pounds centrifugal force. With the vibrator on, compact at least 3 complete coverages over each layer, overlapping to prevent displacement. The speed of the vibratory roller in miles per hour must not exceed the vibrations per minute divided by 1,000. If the HMA layer thickness is less than 0.08 foot, turn the vibrator off. Complete the first coverage before the mixture's temperature drops below 250 °F.

Minor HMA finished surface must be:

1. Textured uniformly
2. Compacted firmly
3. Without depressions, humps, and irregularities
4. Compliant with the 12-foot straightedge specifications in Section 39-1.12, "Smoothness," of the Standard Specifications

## 10-1.38 REPLACE ASPHALT CONCRETE SURFACING

**GENERAL**

**Summary**

This work includes removing existing asphalt concrete surfacing and underlying base and replacing with hot mix asphalt (HMA). The Engineer determines the exact limits of replaced asphalt concrete surfacing.

**MATERIALS**

HMA Type A and tack coat must comply with the specifications in Section 39-1.02, "Materials" of the Standard Specifications.

The grade of asphalt binder mixed with aggregate for HMA must be PG 64-10.

The aggregate for HMA must comply with the 1/2 inch grading.

**CONSTRUCTION**

Pave replacement HMA under Section 39-3, "Method," of the Standard Specifications.

Replace asphalt concrete in a lane before the lane is specified to be opened to public traffic under "Maintaining Traffic" of these special provisions.

Before removing asphalt concrete, outline the replacement area and cut neat lines with a saw or grind to full depth of the existing asphalt concrete. Do not damage asphalt concrete and base remaining in place.

Dispose of removed material under Section 7-1.13, "Disposal of Material Outside the Highway Right of Way," of the Standard Specifications.

If base is excavated beyond the specified plane, replace it with HMA at your expense.

**MEASUREMENT AND PAYMENT**

The Engineer measures replace asphalt concrete surfacing based on the specified dimensions and any adjustments ordered.

The contract price paid per cubic yard for replace asphalt concrete surfacing includes full compensation for furnishing all labor, materials, tools, equipment, and incidentals, and for doing all the work involved in replacing asphalt concrete surfacing

including tack coat, complete in place as shown on the plans, as specified in the Standard Specifications and the special provisions, and as directed by the Engineer.

You may request the Engineer's approval to leave rejected replacement HMA in place. If the Engineer approves, you must accept a reduction in the payment for the rejected replacement HMA.

## 10-1.39 CONCRETE STRUCTURES

Portland cement concrete structures shall conform to the provisions in Section 51, "Concrete Structures," of the Standard Specifications and these special provisions.

### STAIR NOSING INSERTS

Stair nosing inserts shall be furnished and installed as shown on the plans, in conformance with these special provisions.

Stair nosing inserts shall be heavy duty and designed for commercial or public installations and designed for installation in newly constructed concrete stairs.

Stair nosing inserts shall consist of abrasive skid resistant grit bars set within extruded aluminum bands and shall be held in place with and barbed anchors. Barbed anchors shall be continuous and shall extend a minimum of 1 inch below the upper surface of the stair nosing insert.

Grit bars shall be black.

The Contractor shall use stair nosing inserts from one of the following manufacturers, or equal:

A. Cast-in-Place stair nosing: Model No. N-B30
Arden Architectural Specialties, Inc.

B. Balco stair nosing: Model No. R-315P
Balco Inc.

C. Amstep stair nosing: Model No. 331A
Amstep Products

Stair nosing inserts shall be installed in conformance with the manufacturer's instructions.

### MEASUREMENT AND PAYMENT

Measurement and payment for concrete in structures shall conform to the provisions in Section 51-1.22, "Measurement," and Section 51-1.23, "Payment," of the Standard Specifications and these special provisions.

Full compensation for stair nosing inserts shall be considered as included in the contract price paid per cubic yard for minor concrete (minor structure) and no separate payment will be made therefor.

## 10-1.40 REINFORCEMENT

Reinforcement shall conform to the provisions in Section 52, "Reinforcement," of the Standard Specifications and these special provisions.

The Department's mechanical splices prequalified list can be found at:

http://www.dot.ca.gov/hq/esc/approved_products_list/

The provisions in "Welding Quality Control" of these special provisions shall not apply to resistance butt welding.

## 10-1.41 ROADSIDE SIGNS

Roadside signs shall be furnished and installed at the locations shown on the plans or where designated by the Engineer and in conformance with the provisions in Section 56-2, "Roadside Signs," of the Standard Specifications and these special provisions.

The Contractor shall furnish roadside sign panels in conformance with the provisions in "Furnish Sign" of these special provisions.

Wood posts shall be pressure treated after fabrication in conformance with the provisions in Section 58, "Preservative Treatment of Lumber, Timber and Piling," of the Standard Specifications and AWPA Use Category System: UC4A, Commodity Specification A or B.

**10-1.42 FURNISH SIGN**

Signs shall be fabricated and furnished in accordance with details shown on the plans, the Traffic Sign Specifications, and these special provisions.

Traffic Sign Specifications for California sign codes are available for review at:

http://www.dot.ca.gov/hq/traffops/signtech/signdel/specs.htm

Traffic Sign Specifications for signs referenced with Federal MUTCD sign codes can be found in Standard Highway Signs Book, administered by the Federal Highway Administration, which is available for review at:

http://mutcd.fhwa.dot.gov/ser-shs_millennium.htm

Information on cross-referencing California sign codes with the Federal MUTCD sign codes is available at:

http://www.dot.ca.gov/hq/traffops/signtech/signdel/specs.htm

Temporary or permanent signs shall be free from blemishes that may affect the serviceability and detract from the general sign color and appearance when viewing during daytime and nighttime from a distance of 25 feet. The face of each finished sign shall be uniform, flat, smooth, and free of defects, scratches, wrinkles, gel, hard spots, streaks, extrusion marks, and air bubbles. The front, back, and edges of the sign panels shall be free of router chatter marks, burns, sharp edges, loose rivets, delaminated skins, excessive adhesive over spray and aluminum marks.

**QUALITY CONTROL FOR SIGNS**

The requirements of "Quality Control for Signs" in this section shall not apply to construction area signs.

No later than 14 days before sign fabrication, the Contractor shall submit a written copy of the quality control plan for signs to the Engineer for review. The Engineer will have 10 days to review the quality control plan. Sign fabrication shall not begin until the Engineer approves the Contractor's quality control plan in writing. The Contractor shall submit to the Engineer at least 3 copies of the approved quality control plan. The quality control plan shall include, but not be limited to the following requirements:

A. Identification of the party responsible for quality control of signs,
B. Basis of acceptance for incoming raw materials at the fabrication facility,
C. Type, method and frequency of quality control testing at the fabrication facility,
D. List (by manufacturer and product name) of process colors, protective overlay film, retroreflective sheeting and black non-reflective film,
E. Recommended cleaning procedure for each product, and
F. Method of packaging, transport and storage for signs.

No legend shall be installed at the project site. Legend shall include letters, numerals, tildes, bars, arrows, route shields, symbols, logos, borders, artwork, and miscellaneous characters. The style, font, size, and spacing of the legend shall conform to the Standard Alphabets published in the FHWA Standard Highway Signs Book. The legend shall be oriented in the same direction in accordance with the manufacturer's orientation marks found on the retroreflective sheeting.

On multiple panel signs, legend shall be placed across joints without affecting the size, shape, spacing, and appearance of the legend. Background and legend shall be wrapped around interior edges of formed panel signs as shown on plans to prevent delamination.

The following notation shall be placed on the lower right side of the back of each sign where the notation will not be blocked by the sign post or frame:

A. PROPERTY OF STATE OF CALIFORNIA,
B. Name of the sign manufacturer,
C. Month and year of fabrication,
D. Type of retroreflective sheeting, and
E. Manufacturer's identification and lot number of retroreflective sheeting.

The above notation shall be applied directly to the aluminum sign panels in 1/4-inch upper case letters and numerals by die-stamp and applied by similar method to the fiberglass reinforced plastic signs. Painting, screening, or engraving the notation will not be allowed. The notation shall be applied without damaging the finish of the sign.

Signs with a protective overlay film shall be marked with a dot of 3/8 inch in diameter. The dot placed on white border shall be black, while the dot placed on black border shall be white. The dot shall be placed on the lower border of the sign before application of the protective overlay film and shall not be placed over the legend and bolt holes. The application method and exact location of the dot shall be determined by the manufacturer of the signs.

For sign panels that have a minor dimension of 48 inches or less, no splice will be allowed in the retroreflective sheet except for the splice produced during the manufacturing of the retroreflective sheeting. For sign panels that have a minor dimension greater than 48 inches, only one horizontal splice will be allowed in the retroreflective sheeting.

Unless specified by the manufacturer of the retroreflective sheeting, splices in retroreflective sheeting shall overlap by a minimum of one inch. Splices shall not be placed within 2 inches from edges of the panels. Except at the horizontal borders, the splices shall overlap in the direction from top to bottom of the sign to prevent moisture penetration. The retroreflective sheeting at the overlap shall not exhibit a color difference under the incident and reflected light.

Signs exhibiting a significant color difference between daytime and nighttime shall be replaced immediately.

Repairing sign panels will not be allowed except when approved by the Engineer.

The Department will inspect signs at the Contractor's facility and delivery location, and in accordance with Section 6, "Control of Materials," of the Standard Specifications. The Engineer will inspect signs for damage and defects before and after installation.

Regardless of kind, size, type, or whether delivered by the Contractor or by a common carrier, signs shall be protected by thorough wrapping, tarping, or other methods to ensure that signs are not damaged by weather conditions and during transit. Signs shall be dry during transit and shipped on palettes, in crates, or tier racks. Padding and protective materials shall be placed between signs as appropriate. Finished sign panels shall be transported and stored by method that protects the face of signs from damage. The Contractor shall replace wet, damaged, and defective signs.

Signs shall be stored in dry environment at all times. Signs shall not rest directly on the ground or become wet during storage. Signs, whether stored indoor or outdoor, shall be free standing. In areas of high heat and humidity signs shall be stored in enclosed climate-controlled trailers or containers. Signs shall be stored indoor if duration of the storage will exceed 30 days.

Screen processed signs shall be protected, transported and stored as recommended by the manufacturer of the retroreflective sheeting.

When requested, the Contractor shall provide the Engineer test samples of signs and materials used at various stages of production. Sign samples shall be 12" x 12" in size with applied background, letter or numeral, and border strip.

The Contractor shall assume the costs and responsibilities resulting from the use of patented materials, equipment, devices, and processes for the Contractor's work.

**SHEET ALUMINUM**

Alloy and temper designations for sheet aluminum shall be in accordance with ASTM Designation: B 209.

The Contractor shall furnish the Engineer a Certificate of Compliance in conformance with Section 6-1.07, "Certificates of Compliance," of the Standard Specifications for the sheet aluminum.

Sheet aluminum shall be pretreated in accordance to ASTM Designation: B 449. Surface of the sheet aluminum shall be cleaned, deoxidized, and coated with a light and tightly adherent chromate conversion coating free of powdery residue. The conversion coating shall be Class 2 with a weight between 10 milligrams per square foot and 35 milligrams per square foot, and an average weight of 25 milligrams per square foot. Following the cleaning and coating process, the sheet aluminum shall be protected from exposure to grease, oils, dust, and contaminants.

Sheet aluminum shall be free of buckles, warps, dents, cockles, burrs, and defects resulting from fabrication.

Base plate for standard route marker shall be die cut.

**RETROREFLECTIVE SHEETING**

The Contractor shall furnish retroreflective sheeting for sign background and legend in conformance with ASTM Designation: D 4956 and "Prequalified and Tested Signing and Delineation Materials" of these special provisions.

Retroreflective sheeting shall be applied to sign panels as recommended by the retroreflective sheeting manufacturer without stretching, tearing, and damage.

Class 1, 3, or 4 adhesive backing shall be used for Type II, III, IV, VII, VIII, and IX retroreflective sheeting. Class 2 adhesive backing may also be used for Type II retroreflective sheeting. The adhesive backing shall be pressure sensitive and fungus resistant.

When the color of the retroreflective sheeting determined from instrumental testing is in dispute, the Engineer's visual test will govern.

## PROCESS COLOR AND FILM

The Contractor shall furnish and apply screened process color, non-reflective opaque black film, and protective overlay film of the type, kind, and product that are approved by the manufacturer of the retroreflective sheeting.

The Contractor shall furnish the Engineer a Certificate of Compliance in accordance to Section 6-1.07, "Certificates of Compliance," of the Standard Specifications for the screened process color, non-reflective opaque black film, and protective overlay film.

The surface of the screened process color shall be flat and smooth. When the screened process colors determined from the instrumental testing in accordance to ASTM Designation: D 4956 are in dispute, the Engineer's visual test will govern.

The Contractor shall provide patterns, layouts, and set-ups necessary for the screened process.

The Contractor may use green, red, blue, and brown reverse-screened process colors for background and non-reflective opaque black film or black screened process color for legend. The coefficient of retroreflection for reverse-screened process colors on white retroreflective sheeting shall not be less than 70 percent of the coefficient of retroreflection specified in ASTM Designation: D 4956.

The screened process colors and non-reflective opaque black film shall have the same outdoor weatherability as that of the retroreflective sheeting.

After curing, screened process colors shall withstand removal when tested by applying 3M Company Scotch Brand Cellophane Tape No. 600 or equivalent tape over the color and removing with one quick motion at 90° angle.

## SINGLE SHEET ALUMINUM SIGN

Single sheet aluminum signs shall be fabricated and furnished with or without frame. The Contractor shall furnish the sheet aluminum in accordance to "Sheet Aluminum" of these special provisions. Single sheet aluminum signs shall be fabricated from sheet aluminum alloy 6061-T6 or 5052-H38.

Single sheet aluminum signs shall not have a vertical splice in the sheet aluminum. For signs with depth greater than 48 inches, one horizontal splice will be allowed in the sheet aluminum.

Framing for single sheet aluminum signs shall consist of aluminum channel or rectangular aluminum tubing. The framing shall have a length tolerance of ±1/8 inch. The face sheet shall be affixed to the frame with rivets of 3/16-inch diameter. Rivets shall be placed within the web of channels and shall not be placed less than 1/2 inch from edges of the sign panels. Rivets shall be made of aluminum alloy 5052 and shall be anodized or treated with conversion coating to prevent corrosion. The exposed portion of rivets on the face of signs shall be the same color as the background or legend where the rivets are placed.

Finished signs shall be flat within a tolerance of ±1/32 inch per linear foot when measured across the plane of the sign in all directions. The finished signs shall have an overall tolerance within ±1/8 inch of the detailed dimensions.

Aluminum channels or rectangular aluminum tubings shall be welded together with the inert gas shielded-arc welding process using E4043 aluminum electrode filler wires as shown on the plans. Width of the filler shall be equal to wall thickness of smallest welded channel or tubing.

## FIBERGLASS REINFORCED PLASTIC PANEL SIGN

The Contractor shall furnish fiberglass reinforced plastic panel sign in accordance with ASTM Designation: D 3841 and "Prequalified and Tested Signing and Delineation Materials" of these special provisions.

Fiberglass reinforced plastic shall be acrylic modified and ultraviolet stabilized for outdoor weatherability. The plastic shall contain additives designed to suppress fire ignition and flame propagation. When tested in accordance with the requirements in the ASTM Designation: D 635, the extent of burning shall not exceed one inch.

Fiberglass reinforced plastic shall be stabilized to prevent the release solvents and monomers. The front and back surfaces of the laminate shall be clean and free of constituents and releasing agents that can interfere with the bonding of retroreflective sheeting.

The fiberglass reinforced plastic panel sign shall be weather resistant Grade II thermoset polyester laminate.

The fiberglass reinforced plastic panels shall be minimum 0.135-inch thick. Finished fiberglass reinforced plastic panel signs shall be flat within a tolerance of ±1/32 inch per linear foot when measured across the plane of the sign in all directions. The finished signs shall have an overall tolerance within ±1/8 inch of the specified dimensions.

Color of fiberglass reinforced plastic panels shall be uniform gray within Munsel color range of N7.5 to N8.5.

Fiberglass reinforced plastic panels shall be cut from a single piece of laminate. Bolt holes shall be predrilled. The predrilled bolt holes, panel edges, and the front and back surfaces of the panels shall be true and smooth. The panel surfaces shall be free of visible cracks, pinholes, foreign inclusions, warping and wrinkles that can affect performance and serviceability.

**MEASUREMENT AND PAYMENT**

Furnishing signs (except for construction area signs) will be measured by the square foot and the quantity to be paid for will be the total area, in square feet, of the sign panel types installed in place.

The contract price paid per square foot for furnish sign of the types specified in the Engineer's estimate shall include full compensation for furnishing all labor, materials, tools, equipment, and incidentals, and for doing all the work involved in fabricating and furnishing the signs, including fastening hardware, as shown on the plans, as specified in the Standard Specifications and these special provisions, and as directed by the Engineer.

Full compensation for furnishing and installing protective overlay on signs shall be considered as included in the contract price paid per square foot for furnish sign of the various types and no separate payment will be made therefor.

### 10-1.43 PREPARING AND PAINTING CONCRETE CURB

The concrete curb as shown on the plans shall be prepared and painted in conformance with the details shown on the plans, the provisions in Section 59, "Painting," and Section 91, "Paint," of the Standard Specifications, and these special provisions.

The paint to be applied to concrete surfaces shall conform to the provisions in Section 91-4.05, "Paint; Acrylic Emulsion, Exterior White and Light and Medium Tints," of the Standard Specifications. The color of the paint shall be red or green as shown on the plans.

### 10-1.44 PLASTIC PIPE

Polyvinyl chloride pipe (planter drain) and shall conform to the provisions in Section 64, "Plastic Pipe," of the Standard Specifications.

### 10-1.45 PLANTER DRAIN

Planter drains shall consist of furnishing and installing planter drains as shown on the plans and shall conform to these special provisions, and as directed by the Engineer.

The Contractor shall furnish planter drains from one of the following manufacturers or equal:

A. 12" Plastic Atrium Grate, Baughman Tile Co.
B. 12" Atrium Grate with Catch Basin and 12" Square 2-Hole Basin Kit, Hancor, Inc.
C. Cast Iron Planter Drain Model 3220PA with basin, Wade Drains
D. Atrium Grate with Basin, Advanced Drainage Systems
E. 6" Atrium Grate and Catch Basin, NDS Pro.

Planter drains shall be installed in conformance with the manufacturer's instructions.

The contract unit price paid for planter drain shall include full compensation for furnishing all labor, materials, tools, equipment, and incidentals, and for doing all the work involved in installing planter drain, complete in place, as shown on the plans, as specified in and these special provisions, and as directed by the Engineer.

### 10-1.46 UNDERDRAIN

Perforated plastic pipe underdrains shall conform to the provisions in Section 68-1, "Underdrains," of the Standard Specifications and these special provisions.

All underdrain pipe shall have a smooth wall interior surface.

### 10-1.47 WELDED STEEL PIPE

Welded steel pipe shall conform to the provisions in Section 70, "Miscellaneous Facilities," of the Standard Specifications and these special provisions.

Coating and wrapping will not be required.

Coating the interior surface of the pipe will not be required.

Full compensation for furnishing all labor, materials, tools, equipment and incidentals, and for doing all the work involved in installing the different sizes, or types of welded steel pipe, complete in place, including structure excavation and structure backfill and connecting new pipe to existing or new facilities shall be considered as included in the contract price paid per linear foot for welded steel pipe and no additional compensation will be allowed therefor.

### 10-1.48 SEWER MANHOLE

Sewer manholes shall consist of furnishing and installing manhole, frame and cover and shall conform to the plans and these special provisions.

Ten (10) working days prior to the start of work, Contractor shall furnish a complete list of materials with manufacturer and model number, and shop drawings for the Engineer approval and shall also furnish certificates of compliance where applicable. No work shall begin until such list and certificates have been approved in writing by the Engineer.

All sanitary sewage work shall conform to the applicable portions of the California Plumbing Code (CPC).

Material Submittal is required for the following materials:

A. Sewer Manholes, including but not limited to precast riser, concentric or eccentric cone, adjustment ring, frame and cover.
B. Steel reinforcement, including rebar and welded wire reinforcement.
C. Bituminous coating

Certificate of Compliance is required for the following materials:

A. Precast Sanitary Sewer Manhole frame and cover.

**MATERIALS**

Base rock material shall be clean 1-1/2-inch minus gravel or crushed rock well graded from coarse to fine. Base rock shall be of such nature that it can be readily compacted.

Sewer manholes sections shall conform to the requirements of ASTM Designation: C 478, or precast reinforced concrete pipe conforming to ASTM Designation: C 76.

Cones shall be manufactured of the same materials, strength and quality requirements as the straight sections. The cones shall be concentric or eccentric, as shown on the plans, and shall have a maximum height of 3 feet .

Mortar shall be standard premixed mortar conforming to ASTM C-387 or proportion 1 part portland cement to 2 parts clean, well-graded sand which will pass a 1/8-inch screen. Admixtures may be used not exceeding the following percentages of weight of cement: hydrated lime, 10 percent; diatomaceous earth or other inert materials, 5 percent.

Epoxy mortar shall be a commercial quality, trowelable, 3-component epoxy mortar consisting of 2 pourable epoxy components and a chemically resistant aggregate filler of silica quartz sand with a maximum water absorption of 0.1 percent. Epoxy shall have a pull-off strength of not less than 1,000 psi and a 90 percent cure in 24 hours. Epoxy mortar shall be the type that requires no primer as a bonding agent.

Manhole frames and covers shall conform to the details as shown on the plans and these special provisions.

Manhole frame and cover shall be gray cast iron, conforming to ASTM Designation: A 48, Class 30 or greater (traffic type). Cover shall be no bolt, closed pick hole and shall be marked "SS," "SEWER," or "SANITARY SEWER". The side or bottom of the cover shall be machined grooved for an integral O-ring gasket. The frame seat for the bottom O-ring gasket shall be a minimum of 7/8 inch in width. O-rings shall be neoprene and conform to ASTM Designation: C-443 for rubber gasket material.

Bituminous coating shall conform to ASTM Designations: D 41and D 449.

**INSTALLATION**

Manholes shall be installed in accordance with their manufacturer's recommendations.

Manholes shall be constructed plumb with sections level.

Earthwork backfill compaction shall conform to Section 19-5, "Compaction," of the Standard Specifications.

The interior and exterior surfaces of manholes, except the bottom, shall be completely coated with 2 applications of bituminous coating, applied at a rate of 100 square feet per gallon.

Backfill around manholes shall be of the quality of new trench backfill immediately adjacent.

Carefully inspect precast manhole sections to be joined. Sections with chips or cracks in the tongue shall not be used. Preformed plastic gaskets shall be installed in strict conformance with the manufacturer's recommendations. Only pipe primer furnished by the gasket manufacturer will be approved.

All joints and pipe inlets of manholes shall be sealed watertight, inside and outside, with epoxy mortar.

Construct sewer manhole inverts in conformance with details shown on the plans, and with smooth transitions to ensure an unobstructed flow through manhole. Remove all sharp edges or rough sections which tend to obstruct flow. Where a full section of pipe is laid through a manhole, break out the top section as indicated and cover exposed edge of pipe completely with mortar. Trowel all mortar surfaces smooth.

Install frames and covers on top of manholes in conformance to the detail as shown on the plans. Frames shall be set in a bed of mortar with the mortar carried over the flange of the ring. Set frames so tops of covers are flush with surface of adjoining pavement or ground surface, unless otherwise shown or directed.

The edge and bottom of manhole cover seat areas shall be coated with a uniform application of heavy duty, waterproof automotive or industrial grease.

### TESTING SEWER MANHOLES

The test shall consist of plugging all inlets and outlets and filling the sewer manhole with water to the top of the cone section. Leakage in each sewer manhole shall not exceed 0.1 gallon per hour per foot of head above the invert. A sewer manhole may be filled 24 hours prior to time of testing, if desired, to permit normal absorption into the walls to take place. Minimum time for a test shall be 1 hour.

The Contractor, at no additional cost to the State, shall repair sewer manholes that do not meet the leakage test, or are unsatisfactory from visual inspection. Sewer manholes shall be watertight to infiltration, and any leakage of groundwater shall be eliminated by permanent repairs.

### MEASUREMENT AND PAYMENT

Sewer manhole will be measured by the actual number of sewer manholes constructed.

The contract unit price paid for sewer manhole shall include full compensation for furnishing all labor, materials, tools, equipment, and incidentals, and for doing all the work involved in constructing sewer manhole, complete in place, including excavation, leakage testing, reconnection of side street sewer pipe, adjustment of manholes to final grade, furnishing and placing minor concrete, base rock and backfill, as shown on the plans, as specified in the Standard Specifications and these special provisions, and as directed by the Engineer.

## 10-1.49 DIRECTIONAL HORIZONTAL BORING

### GENERAL

#### Summary

Scope--This work shall consist of materials and installation of HDPE utility pipes and sewer pipe, utilizing directional boring trench-less excavation methods in accordance with the details shown on the plans and these special provisions.

Related Sections--Trenching, backfilling, and compaction shall conform to the requirements specified under "Earthwork" of the special provisions.

#### Safety

Applicable occupational safety and health standards, rules, regulations and orders established by the State of California shall be adhered to during the work. Attention is directed to "Public Safety" of the special provisions when work is conducted in the roadway right of way.

#### Submittals

Preconstruction Submittals--The equipment system to be used including manufacturer's literature, describing in detail, the boring equipment to be used and manufacturer's instructions shall be submitted for approval. Submittal shall include detailed descriptions of projects on which this system has been successfully used, giving total pipe length, project duration, and number of restarts.

Spoil Removal Plan--Method of spoil removal shall be submitted for approval.

Drilling Fluid Collection And Disposal Practices--Drilling fluids, additives and their Material Safety Data Sheets (MSDS) shall be identified within the contractor’s submittal package.

A. Excess drilling fluids shall be contained within a lined pit or containment pound, until removed from the site.
B. When an area of contaminated ground is encountered, the slurry shall be tested for contamination and disposed of in a manner, which meets Local, State and/or Federal requirements.
C. Precautions shall be taken to keep drilling fluids out of the streets, manholes, sanitary and storm sewers, and other drainage systems, including streams and rivers.
D. The Contractor shall make all diligent efforts to minimize the amount of drilling fluids and cuttings spilled during the drilling operation, and shall provide complete clean-up of all drilling mud overflows or spills.

Product Data: Manufacturer’s descriptive data for pipe and accessories shall be submitted for approval. Products include but are not limited to piping casing, joints, fittings, valves, couplings and, and slurry system.

Working Drawings: Complete working drawings and design calculations for the pipe shall be submitted for approval in accordance with the provisions in Section 5-1.02, "Plans and Working Drawings," of the Standard Specifications and the Special Provisions.

The Contractor shall identify in the construction plan:

A. Location of entry and exit pits.
B. Working areas and their approximate size.
C. Proposed pipe fabrication and layout areas.
D. State right-of-way lines, property lines.
E. Other utility right-of way and easement lines.
F. Pipe material and wall thickness.
G. Location of test pits or boreholes undertaken during the soil investigation.
H. Identify the proposed drilling alignment (both plan & profile view. from entry to exit.
I. Identity all grades and curvature radii.
J. All utilities (both horizontal and vertical).
K. Structures with their clearances from the proposed drill alignment.
L. Confirm the minimum clearance requirements of affected utilities and structures.
M. Required minimum clearances from existing utilities and structures.
N. Diameter of pilot hole, number and size of prereams/backreams.
O. Access requirements to site (if required).
P. Crew experience.
Q. Type of tracking equipment. Locating and tracking of the reamer during the back-reaming process is required**.**

Drawings shall indicate the proposed method of construction including location of receiving and sending pits and plan and profile view of proposed crossing. Design calculations shall indicate the suitability of the selected pipe considering the geological setting, and the drilling materials and equipment being used. Drawings and calculations shall be stamped and signed by an engineer who is registered as a Civil or Structural Engineer in the State of California. The expiration date of the registration shall be shown. Engineer's original signature shall be submitted; copies will not be accepted.

### Delivery, Storage and Handling

The Contractor shall inspect materials delivered to site for damage and unload and store materials with a minimum handling. Materials shall be stored on site in enclosures or under protective covering. Plastic piping, jointing materials and rubber components shall be covered out of direct sunlight. Materials shall not be stored directly on the ground and insides of pipes, fittings, and valves maintained free of dirt and debris.

Special coatings and linings on pipe and fittings shall be protected from damage and if damaged, the material shall be repaired or replaced at the Contractor's expense.

## MATERIALS

### Piping Materials

A HDPE Utility Pipe--HDPE utility pipe shall conform to ASTM D 3350, Standard Dimension Ratio (SDR) 17.
B. Joints and Fittings--The connection of adjacent pieces of HDPE pipe shall be accomplished by field heat fusion butt welding with fusion polyethylene (PE) fittings conforming to ASTM D3261.

### Concrete

Concrete shall be 3000 psi. Concrete and reinforcement shall conform to the requirements specified under "Cast-in-Place Concrete" in Section 12-3, "Concrete" of these special provisions.

### Bentonite

Bentonite shall conform to API Spec 13A and have the capacity of mixing with water to form a stable and homogeneous suspension.

**CONSTRUCTION**

**Preparation**

A. Access Pits

1. Construction methods for directional boring access pits shall be subject to approval of the Engineer. Acceptable construction methods may include the use of interlocked steel sheet piling or precast circular concrete segments lowered in place during excavation.

2. Pits shall be of a size commensurate with safe working practices and located as shown on plans. With the approval of the Engineer, the Contractor may relocate pits to better suit the capabilities of the horizontal boring method proposed. Where no locations are given, the Contractor shall determine such locations with the approval of the Engineer.

3. Pit locations shall, where possible, be kept clear of road intersections and within a single traffic lane, in order to minimize disruption to the flow of traffic. Support equipment, spoil piles, and materials shall also be located such as to minimize disruption to traffic and are subject to the approval of the Engineer.

4. The Contractor shall properly support all excavations and prevent movement of the soil, pavement, utilities or structures outside of the excavation. Sheeting, bracing, and lining shall be furnished, placed and maintained as required to support the sides and floor of all pits and to provide adequate protection of the work, personnel, and the general public. Design loads on the sides of the sending and receiving pit walls are dependent on the construction method and flexibility of the wall systems.

5. A starter pit shall be constructed to accommodate the installation of directional boring components.

6. A receiver pit shall be constructed to accommodate the installation of pipe.

7. The Contractor shall furnish, install, and maintain equipment to keep the sending pit free of excess water. Surface protection shall be provided during the period of construction to ensure that surface runoff does not enter driving shaft(s). Groundwater dewatering shall comply with the approved dewatering plan and shall not affect surrounding soils or structures beyond the tolerances stated in paragraph entitled "Settlement, Alignment and Tolerances."

8. The Contractor shall provide security fence around all access pit areas and provide pit cover(s) when the pit area is kept open over night and is not in use.

9. Design of the sending and receiving pit supports shall also take into account the loading from drilling or pipe pulling operations, where appropriate.

10. Where a thrust block is required to transfer boring loads into the soil, it shall be properly designed and constructed by the Contractor. The backstop shall be normal (square) with the proposed pipe alignment and shall be designed to withstand the maximum boring pressure to be used with a factor of safety of at least 2.0. It shall also be designed to minimize excessive deflections in such a manner as to avoid disturbance of adjacent structures or utilities or excessive ground movement. If a concrete thrust block or treated soil zone is utilized to transfer boring loads into the soil, the boring is not to be commenced until the concrete or other materials have attained the required strength.

B. Pit Backfill and Compaction

1. Upon completion of the pipe pull and approval of the installed pipeline by the Engineer, all equipment, debris, and unacceptable materials shall be removed from the pits and backfilling and compaction operations completed.

**Installation**

Installation of Tracer Wire--A continuous length of tracer wire shall be installed for the full length of each run of nonmetallic pipe. Attach wire to top of pipe in such a manner that will not be displaced during construction operations.

Settlement, Alignment and Tolerances--Settlement or heave of ground surface along centerline of directional boring alignments during and after installation of the pipe shall not exceed 5 inches. No more than 5 inch lateral and 2.5 inch vertical deviation shall be permitted in the position of the completed pipes. [Water shall be free draining between any two points at the pipe invert. No reverse grades will be allowed.] [Overcut shall not exceed one inch on the radius of the pipe being installed. The annular space created by the overcut [must] be filled with the lubrication material that is used to reduce soil friction drag on the pipe.] Should pavement heaving or settlement occur, saw cutting and replacement of the asphalt shall be the responsibility of the Contractor. To prevent future settlement should the drilling operation be unsuccessful the contractor shall ensure the backfill of any void(s) with grout or backfilled by other means. The Contractor shall submit, to the Engineer, the daily monitoring and plotting of the ground surface along the directional boring alignments at the end of the work shift.

Horizontal Directional Drilling (HDD)

A. HDD equipment selected for the project shall be compatible with the geotechnical conditions of the work and capable of tunneling through mixed face conditions without exceeding the settlement tolerances specified in paragraph "Settlement, Alignment and Tolerances." During construction continuous monitoring and plotting of pilot drill and also back reaming progress shall be undertaken to ensure compliance with the proposed installation alignment and allow for appropriate course corrections to be undertaken should the bore start to deviate from the intended bore path. The Contractor shall submit, to the Engineer, the daily monitoring and plotting of drilling at the end of the work shift.

B. Any pipe which has been damaged during installation shall be replaced by the Contractor at no additional cost. If a new replacement pipe is required extending from the sending to the receiver pit, it shall be installed in conformance with the contract drawings and this section. All excavated material from tunnel and pit construction shall be disposed of away from the construction site. Stockpiling shall be permitted on the construction site and material shall be removed at regular intervals not exceeding 24 hours. Ground movements shall be monitored during the work and suitable changes made in the construction methods that control ground movements and prevent damage or detrimental movement to the work and adjacent structures and pavements.

Ventilation--Adequate ventilation shall be provided for all cased pits. Follow confined space entry procedures. The design of ventilating system shall include such factors as the volume required to furnish fresh air in the pits.

Lighting--Adequate lighting shall be provided for the nature of the activity being conducted by workers for the directional boring. Both power and lighting circuits shall be separated and thoroughly insulated with ground fault interrupters are required. Lights shall comply with requirements with regards to shatter resistance and illumination requirements.

Spoil Transportation--The spoil transportation system shall match the excavation rate with rate of spoil removal. The system must also be capable of balancing groundwater pressures and adjustment to maintain face stability for he particular soil conditions of this project.

**Field Quality Control And Site Restoration**

Sewer Pipe Test--

A. Sewer pipes shall be tested for obstructions before covering the pipes by balling and flushing the pipes with an approved commercial sewer cleaning ball. The ball shall be moved slowly through the sewer with a tag line. Obstructions or irregularities shall be removed or repaired.

B. Sewer pipes shall be tested for leakage for a minimum period of 4 hours by filling with water to an elevation of 4 feet above the average invert of sewer pipe, or to the top of the manholes where less than 4 feet deep. The system shall show no visible leaks, and the leakage rate shall not exceed the rate allowed by the local agency. In the absence of such requirements, leakage shall not exceed one pint per 24 hours, per millimeter diameter, per 100 feet of pipe. Sewer pipes may be tested in sections with the test water progressively passed down the sewers if feasible. Water shall be released at a rate which will not create water hammer or surge in the plugged section of sewer.

C. In lieu of hydrostatic test with water, the air test method, "Air Test," as outlined in the CPC, may be used.

Field Tests and Inspections--The Contractor shall perform field tests, and provide labor, equipment, and incidentals required for testing. The Contractor shall produce evidence, when required, that any item of work has been constructed in accordance with drawings and specifications:

A. All surfaces affected by the work shall be restored to their pre-existing conditions.

B. The Contractor shall provide a set of as-built drawings to include both alignment and profile. Drawings should be constructed from actual field readings. Raw data shall be submitted as part of the "As-Built" document. The Contractor shall stipulate the tracking method used to ensure the data was captured.

**MEASUREMENT AND PAYMENT**

**Measurement**

The directional horizontal boring pipe work to be performed under these specifications will be listed in the contract items by size, or size and class, and whatever other information is necessary for identification.

The length of pipe to be paid for will be the slope length designated by the Engineer. Pipe placed in excess of the length designated will not be paid for, unless pipes are cut to fit a structure or slope. When pipes are cut to fit a structure or slope, the quantity to be paid for will be the length of pipe necessary to be placed before cutting, measured in 2-foot increments.

**Payment**

The contract price paid per linear foot for HDD of the types of pipe listed in the Engineer's Estimate shall include full compensation for furnishing the pipe, excavating, boring, furnishing and placing backfill material, constructing boring pits and backfilling pits after the installation of pipe, and all incidentals necessary to install pipe, complete in place, as specified.

The above prices and payments shall include full compensation for furnishing all labor, materials, tools, equipment, and incidentals, and for doing all the work involved in installing pipe, complete in place, including structure excavation and structure backfill, and connecting new pipe to existing or new facilities, including adapters and fittings, as shown on the plans, and as specified in these special provisions, and as directed by the Engineer.

## 10-1.50 SLOPE PROTECTION

Concrete (ditch lining) shall be placed or constructed in conformance with the provisions in Section 72, "Slope Protection," of the Standard Specifications.

## 10-1.51 MISCELLANEOUS CONCRETE CONSTRUCTION

Minor concrete (textured paving), minor concrete (miscellaneous construction) and portland cement concrete splash pads shall conform to the provisions in Section 73, "Concrete Curbs and Sidewalks," of the Standard Specifications and these special provisions.

Curb ramp detectable warning surface shall consist of raised truncated domes constructed or installed on curb ramps in conformance with the details shown on the plans and these special provisions. At the option of the Contractor, the detectable warning surface shall be prefabricated, cast-in-place, or stamped into the surface of the curb ramp. The color of the detectable warning surface shall be yellow conforming to Federal Standard 595B, Color No. 33538.

Prefabricated detectable warning surface shall be in conformance with the requirements established by the Department of General Services, Division of State Architect and be attached in conformance with the manufacturer's recommendations.

Cast-in-place and stamped detectable warning surfaces shall be painted in conformance with the provisions in Section 59-6, "Painting Concrete," of the Standard Specifications.

The finished surfaces of the detectable warning surface shall be free from blemishes.

Prior to constructing the cast-in-place or stamping the detectable warning surface, the Contractor shall demonstrate the ability to produce a detectable warning surface conforming to the details shown on the plans and these special provisions by constructing a 24" x 24" test panel.

The manufacturer shall provide a written 5-year warranty for prefabricated detectable warning surfaces, guaranteeing replacement when there is defect in the dome shape, color fastness, sound-on-cane acoustic quality, resilience, or attachment. The warranty period shall begin upon acceptance of the contract.

Full compensation for constructing or furnishing and installing curb ramp detectable warning surfaces shall be considered as included in the contract price paid per cubic yard for minor concrete miscellaneous construction and no separate payment will be made therefor.

Aggregate for minor concrete (textured paving) shall conform to the grading specified for fine aggregate in Section 90-3.03, "Fine Aggregate Grading," of the Standard Specifications. Aggregate for grout shall conform to the following grading:

| Sieve Sizes | Percentage Passing |
|---|---|
| No. 4 | 100 |
| No. 8 | 90 - 100 |
| No. 16 | 60 - 100 |
| No. 30 | 35 - 70 |
| No. 50 | 15 - 35 |
| No. 100 | 2 - 15 |

Samples of the colors specified for textured paving ("Ashlar Slate" English Slate Texture") and stone pavers band are available for review by prospective bidders at the office of the Department of Transportation, 111 Grand Ave, Oakland CA 94612 (510-286-5955). Portland cement concrete closely conforming to the colors specified for textured paving are available through commercial concrete sources.

A sample of sufficient size (minimum 1 square yard), of each type and color of the textured paving, to demonstrate the textured paving, including stone pavers band, color hardener, curing and finishing compounds, for both grouted and ungrouted finishes, shall be submitted to the Engineer for written approval.

Textured paving shall not be placed on the project prior to approval by the Engineer of the samples prepared and submitted by the Contractor. In the event more than one sample of each type and color of textured paving to be placed is required by the Engineer, each additional sample will be paid for as extra work as provided in Section 4-1.03D of the Standard Specifications.

Bar reinforcing steel, of the size and type shown on the plans and conforming to the provisions in Section 52, "Reinforcement," of the Standard Specifications, shall be placed in the textured paving or other miscellaneous construction areas, as shown on the plans.

Aggregate base shall be Class 2 and shall conform to the provisions in Section 26, "Aggregate Bases," of the Standard Specifications.

The respective pattern types and colors of concrete for textured paving shall be placed at the locations shown on the plans, struck off and compacted until a layer of mortar is brought to the surface. The concrete shall be screeded to the required grade and cross section and floated to a uniform surface.

The forming tools for the textured paving shall be applied to form the patterned surfaces while the concrete is still in the plastic stage of set.

Textured paving areas shall be cured by the curing compound method. The curing compound shall be curing compound (6) conforming to the provisions in Section 90-7.01B, "Curing Compound Method," of the Standard Specifications.

For payment purposes, the area in square feet of minor concrete (textured paving) will be determined from horizontal measurements of the finished textured paving.

The contract price paid per square foot for minor concrete (textured paving) shall include full compensation for furnishing all labor, materials (including reinforcing steel, where required, and aggregate base), tools, equipment, and incidentals, and for doing all the work involved in constructing textured paving, including grouted areas, complete in place, as shown on the plans, as specified in the Standard Specifications and these special provisions, and as directed by the Engineer.

## 10-1.52 STONE PAVER BAND

Stone paver band shall be furnished and placed as shown on the plans and in conformance with these special provisions.

### MATERIALS

#### Granite

Granite for the stone paver band shall be clean, smooth rock obtained from a single source.

Granite shall be exterior architectural grade, 3/4 inch thick, black color, and flame textured top finish. A sample of the granite shall be submitted to the Engineer for approval prior to delivery of the granite to the project site.

Granite shall be secured in place on mortar over concrete substrate, with grout joints.

#### Mortar

Portland cement mortar shall conform to Section 90-2.01, "Portland Cement," of the Standard Specifications. Hydrated lime shall conform to ASTM Designation" C 207, Type S. Mortar sand shall be commercial quality.

Mortar for binding granite to concrete substrate shall consist by volume, one part Portland cement, 1/4 to 1/2 part hydrated lime, and 2-1/4 to 3 parts mortar sand. Sufficient water shall be added to make a workable mortar. Each batch of mortar shall not be retempered more than one hour after mixing.

**Grout**

Grout, for binding granite pieces/joints, shall be exterior grade latex-portland cement grout mix ANSI standard A118.6 incorporating a dry acrylic resin. Water is added to make a workable grout. Each batch of grout shall not be retempered more than one hour after mixing.

**PREPARATION**

The concrete substrate surfaces to receive the mortar bed and stone pavers band shall not vary more than 3/16 inch from plane and shall be true, plumb, and square.

Prior to beginning stone pavers band work, concrete substrate surfaces shall be cleared of any debris, dirt, oils, sand, dust, and other laitance materials.

The concrete substrate surface shall be washed off with water immediately prior to applying the mortar bed.

**PLACEMENT**

Granite stone pavers shall be placed while mortar is still plastic, and uniformly spaced a maximum of 1/2 inch apart. The Contractor shall remove any mortar and grout adhering to the exposed surfaces of the granite. Loose granite, or joint gaps greater than 1/2 inch, or uneven grout joints in excess of 1/8 inch from plane, shall be reset at the Contractor's expense by methods determined by the Engineer.

Grout shall be placed in the granite joints after 48 hours of the granite/mortar installation. Finished grout shall be uniform in flat smoothness and color, without any voids or low spots. Any grout residue on the exposed granite surface shall be removed such that there is no indication of grout haziness and the true color of the granite is evident, as compared to a non-grouted granite piece.

**MEASUREMENT AND PAYMENT**

Stone paver band will be measured by the square foot as determined from actual measurements made parallel to the ground slope.

The contract price paid per square foot for stone paver band shall include full compensation for furnishing all labor, materials, tools, equipment, and incidentals, and for doing all the work involved in placing stone paver band, complete in place, as shown on the plans, as specified in the Standard Specifications and these special provisions, and as directed by the Engineer.

## 10-1.53 MISCELLANEOUS IRON AND STEEL

Miscellaneous iron and steel shall conform to the provisions in Section 75, "Miscellaneous Metal," of the Standard Specifications.

## 10-1.54 CHAIN LINK FENCE

Chain link fence and drive gate shall be Type (CL-1.6 vinyl-clad) and shall conform to the provisions in Section 80, "Fences," of the Standard Specifications and these special provisions.

Chain link fabric shall be vinyl coated as specified in Section 83-1.02I, "Chain Link Railing," of the Standard Specification. The color shall be black.

All posts, braces, fittings, tension wires, tie wires, post clips and appurtenances shall be vinyl coated as specified for fabric

Where necessary to conform to curvature, either horizontal or vertical, the fabric shall be reworked and fitted so as to present a smooth, neat, and workmanlike appearance.

## 10-1.55 DECORATIVE METAL GATE AND FENCE

Decorative metal fence and gates shall conform to the provisions in Section 80, "Fences," Section 75, "Miscellaneous Metal," Section 55, "Steel Structures," and Section 59, "Painting," of the Standard Specifications and these special provisions. Fence and gates shall be fabricated in accordance with the details shown on the plans and as directed by the Engineer.

Decorative metal fence and gates shall be furnished and installed at the locations shown on the plans.

**MATERIALS**

Decorative metal fence and gates shall be finished with a fused coating of electrostatically applied polyester powder paint. The color of the polyester powder paint shall be black. The minimum thickness of the polyester powder coating shall be not less than 2 mils.

Fence posts shall be installed in pre-set sleeves in accordance with the manufacturer's instructions.

Hinges, hasps, locks, and closing and locking hardware shall be preapproved by the Engineer and installed per manufacturer's instructions.

The gate latch shall meet accessibility requirements of the Americans with Disabilities Act.

The cane bolts shall be stainless steel.

All metal fabrications shall be provided with smooth, flat surfaces without blemishes. Do not use materials with exposed pitting, seam marks, roller marks, rolled trade names or roughness.

All bolts and nuts shall be hot-dipped galvanized or stainless steel.

Grout shall be erosion control anchoring cement, factory packaged, non-shrink, non-staining, hydraulic-controlled expansion cement formulation for mixing with water at a project site to create pourable anchoring, patching and grouting compound. Provide formulation that is resistant to erosion from water exposure without needing protection by a sealer or waterproof coating and that is recommended for exterior use.

Concrete footings shall conform to the provisions in Section 80-4, "Chain Link Fence," of the Standard Specifications and these special provisions.

**INSTALLATION**

Contractor shall verify metal work dimensions by field measurements before fabrication.

The fencing shall be erected as shown on the plans with fence posts in holes formed by sleeves provided in the concrete footings to receive the fence posts.

The fencing shall be carefully erected, true to line and grade. Posts shall be vertical with the deviation from the vertical not exceeding 1/8 inch at the top.

All exposed welds shall be finished and surfaces smoothed and blended such that surfaces match those of adjacent surfaces.

After erecting all metal work, any abrasions of the galvanized or exposed steel shall be repaired in accordance to the provisions in Section 83-1, "Railings," of the Standard Specifications.

**PAYMENT**

The contract price or prices paid per linear foot for the different sizes or sizes and types of decorative metal gate and fence, shall include full compensation for furnishing all labor, materials, tools, equipment, and incidentals, and for doing all the work involved in installing decorative metal fencing, gate, cane bolts and latch complete in place, including polyester powder paint, as shown on the plans, as specified in the Standard Specifications and these special provisions, and as directed by the Engineer.

## 10-1.56 THERMOPLASTIC TRAFFIC STRIPE AND PAVEMENT MARKING

Thermoplastic traffic stripes (traffic lines) and pavement markings shall be applied in conformance with the provisions in Section 84, "Traffic Stripes and Pavement Markings," of the Standard Specifications and these special provisions.

Thermoplastic material shall be free of lead and chromium, and shall conform to the requirements in State Specification PTH-02ALKYD.

Retroreflectivity of the thermoplastic traffic stripes and pavement markings shall conform to the requirements in ASTM Designation: D 6359-99. White thermoplastic traffic stripes and pavement markings shall have a minimum initial retroreflectivity of 250 mcd $m^{-2}$ $lx^{-1}$. Yellow thermoplastic traffic stripes and pavement markings shall have a minimum initial retroreflectivity of 150 mcd $m^{-2}$ $lx^{-1}$.

Where striping joins existing striping, as shown on the plans, the Contractor shall begin and end the transition from the existing striping pattern into or from the new striping pattern a sufficient distance to ensure continuity of the striping pattern.

Thermoplastic traffic stripes shall be applied at the minimum thickness and application rate as specified below. The minimum application rate is based on a solid stripe of 4 inches in width.

| Minimum Stripe Thickness (inch) | Minimum Application Rate (lb/ft) |
|---|---|
| 0.079 | 0.27 |

Thermoplastic traffic stripes and pavement markings shall be free of runs, bubbles, craters, drag marks, stretch marks, and debris.

At the option of the Contractor, permanent traffic striping and pavement marking tape conforming to the provisions in "Prequalified and Tested Signing and Delineation Materials" of these special provisions may be placed instead of the thermoplastic traffic stripes and pavement markings specified herein. Permanent tape, if used, shall be installed in conformance with the manufacturer's specifications.

If permanent tape is placed instead of thermoplastic traffic stripes and pavement markings, the tape will be measured and paid for by the linear foot as thermoplastic traffic stripe and by the square foot as thermoplastic pavement marking.

**10-1.57 PARKING BUMPER**

Parking bumpers shall be furnished and installed at the locations and in the manner shown on the plans.

Parking bumpers shall be precast with concrete and reinforcing steel as shown on the plans. Concrete shall be minor concrete conforming to the provisions in Section 90-10, "Minor Concrete," of the Standard Specifications. Concrete shall contain not less than 472 pounds of cementitious material per cubic yard. Parking bumpers may be commercially available precast concrete bumpers conforming to the details shown on the plans. Minor variations in cross section dimensions will be acceptable in commercially available units.

Dowels shall be commercial quality reinforcing steel or mild steel rods.

Parking bumpers will be measured by the unit as determined from actual count in place.

The contract unit price paid for parking bumper (precast concrete) shall include full compensation for furnishing all labor, materials, tools, equipment, and incidentals, and for doing all the work involved in installing precast concrete parking bumpers, complete in place, as shown on the plans, as specified in the Standard Specifications and these special provisions and as directed by the Engineer.

**10-1.58 SITE FURNISHINGS**

Site furnishings shall consist of placing concrete picnic table, trash receptacles, and installing water posts at locations as shown on the plans and in conformance with these special provisions. The size of the individual pieces of site furnishing shall be as shown on the plans.

Site furnishings will be State-furnished in accordance with "State-furnished Materials" of these special provisions and will be furnished to the Contractor at the site of the work.

Concrete for the concrete pads and foundations shall conform to Section 90-10, "Minor Concrete," of the Standard Specifications.

Drain rock for water post shall consist of gravel or crushed rock conforming to the following requirements:

Grading Requirements

| Sieve Size | Operating Range |
|---|---|
| 1” | 100 |
| 3/4" | 90-100 |
| No. 4 | 35-60 |
| No. 30 | 10-30 |
| No. 200 | 2-9 |

The color of drain rock shall be gray.

Edging shall be pressure-treated construction grade lumber, including stakes,. and shall conform to Sections 20-2.12, "Lumber," and 20-4.04, "Header Boards," of the Standard Specifications.

Edging shall be a minimum 2x4 nominal dimension. Stakes shall be 1” by 1-1/4” and 12 inches in length.

Precast concrete site furnishings shall be placed at the locations as shown on the plans and arranged in an even uniform manner within the designated area of work.

Areas to receive drain rock for the water post shall be cleared of trash and debris. Vegetation shall be removed to the ground. Cleared trash, debris and removed vegetation shall be disposed outside the highway right of way in conformance with Section 7-1.13, "Disposal of Material Outside the Highway Right of Way," of the Standard Specifications.

The splash area for water post shall be filled with drain rock to 1/2" below the top of the wood edging.

The contract lump sum price paid for install site furnishing shall include full compensation for furnishing all labor, materials, tools, equipment, and incidentals, and for doing all the work involved in placing concrete picnic table, trash receptacles, and installing edging, concrete pedestals and other components required for water post, and for all transportation of items to be salvaged, complete in place, as shown on the plans, as specified in the Standard Specifications and these special provisions, and as directed by the Engineer.

**10-1.59 PET WASTE BAG DISPENSER**

Pet waste bag dispenser shall be furnished and installed as shown on the plans and in conformance with these special provisions.

Pet waste bag dispenser shall be obtained from one of the following manufacturers, or equal:

A. Dogipot – Junior Dispenser: Model No. 1002-2 aluminum
Dogipot, Inc.
B. Gladiator – Pet Waste Dispenser: Model JJB008-SK
JJB Solutions, Inc.
C. Baggit – Aluminum Dispenser: Model No. 2001-A
RWE Distributing – BAGIT, Inc.

Pet waste bag dispenser shall be installed in conformance with the manufacturer's instructions.

The contract price paid per unit for pet waste bag dispenser shall include full compensation for furnishing all labor, materials, tools, equipment, and incidentals, and for doing all the work involved in installation, complete in place, including post, footing, and sign, as shown on the plans, as specified in the Standard Specifications and these special provisions, and as directed by the Engineer.

### 10-1.60 FLAGPOLE

Flagpole shall conform to the provisions in Section 52, "Reinforcement," and Section 68-1.025, "Permeable Material," of the Standard Specifications and these special provisions. This work shall consist of furnishing, and installing a ground set flagpole and foundation in accordance with the details shown on the plans and these special provisions. Manufacturer's descriptive data and installation instructions shall be submitted for approval.

Flagpole shall be tapered, 35 feet exposed height, 6063-T6 aluminum alloy pole with 6 inch diameter aluminum ball, ball bearing non-fouling truck with aluminum body and 4 inch diameter aluminum sleeves, 9 inch cast aluminum cleat and 0.3 inch polypropylene rope halyards with flag clasps. Aluminum shall be clear anodized after fabrication.

Metal sleeve, sand, wedges and sealant for flagpole foundation shall be as recommended by the flagpole manufacturer. Metal sleeve shall be capped and shall have a ground spike with support plate.

Concrete for flagpole base shall be constructed of Minor Concrete, conforming to Section 90, "Portland Cement Concrete," of the Standard Specifications.

The flagpole shall be erected plumb and rigid in accordance with the manufacturer's recommendations. Sand shall be consolidated before placing sealant.

The contract unit price paid for flag pole shall include full compensation for furnishing all labor, materials, tools, equipment, and incidentals, and for doing all the work involved in furnishing and installing flag pole, complete in place, including earthwork, as shown on the plans, as specified in the Standard Specifications and these special provisions, and as directed by the Engineer.

## SECTION 10-2 HIGHWAY PLANTING AND IRRIGATION SYSTEMS

### 10-2.01 GENERAL

The work performed in connection with highway planting and irrigation systems shall conform to the provisions in Section 20, "Erosion Control and Highway Planting," of the Standard Specifications and these special provisions.

When fluctuations of water pressure and water supply are encountered during normal working hours, plants shall be watered at other times, as often, and in sufficient amounts as conditions may require to keep the soil and plant roots moist during the life of the contract.

Full compensation for watering plants outside normal working hours shall be considered as included in the contract lump sum prices paid for highway planting and plant establishment work and no additional compensation will be allowed therefor.

#### PROGRESS INSPECTIONS

Progress inspections will be performed by the Engineer for completed highway planting and irrigation system work at designated stages during the life of the contract.

Progress inspections will not relieve the Contractor of responsibility for installation in conformance with the special provisions, plans and Standard Specifications. Work within an area shall not progress beyond each stage until the inspection has been completed, corrective work has been performed, and the work is approved, unless otherwise permitted by the Engineer.

The requirements for progress inspections will not preclude additional inspections of work by the Engineer at other times during the life of the contract.

The Contractor shall notify the Engineer, in writing, at least 4 working days prior to completion of the work for each stage of an area and shall allow a minimum of 3 working days for the inspection.

Progress inspections will be performed at the following stages of work:

A. During pressure testing of the pipelines on the supply side of control valves.
B. During testing of low voltage conductors.
C. Before planting begins and after completion of the work specified for planting in Section 20-4.03, "Preparing Planting Areas," of the Standard Specifications.
D. Before plant establishment work begins and after completion of the work specified for planting in Section 20-4.05, "Planting," of the Standard Specifications.
E. At intervals of one month during the plant establishment period.

**COST BREAK-DOWN**

The Contractor shall furnish the Engineer a cost break-down for the contract lump sum items of highway planting and irrigation system. Cost break-down tables shall be submitted to the Engineer for approval within 15 working days after the contract has been approved. Cost break-down tables will be approved, in writing, by the Engineer before any partial payment will be made for the applicable items of highway planting and irrigation system involved.

Cost break-downs shall be completed and furnished in the format shown in the samples of the cost break-downs included in this section. Line item descriptions of work shown in the samples are the minimum to be submitted. Additional line item descriptions of work may be designated by the Contractor. If the Contractor elects to designate additional line item descriptions of work, the quantity, value and amount for those line items shall be completed in the same manner as for the unit descriptions shown in the samples. The line items and quantities given in the samples are to show the manner of preparing the cost break-downs to be furnished by the Contractor.

The Contractor shall determine the quantities required to complete the work shown on the plans. The quantities and their values shall be included in the cost break-downs submitted to the Engineer for approval. The Contractor shall be responsible for the accuracy of the quantities and values used in the cost break-downs submitted for approval.

The sum of the amounts for the line items of work listed in each cost break-down table for highway planting and for irrigation system work shall be equal to the contract lump sum price bid for Highway Planting and Irrigation System, respectively. Overhead and profit shall be included in each individual line item of work listed in a cost break-down table.

No adjustment in compensation will be made in the contract lump sum prices paid for highway planting and irrigation system due to differences between the quantities shown in the cost break-downs furnished by the Contractor and the quantities required to complete the work as shown on the plans and as specified in these special provisions.

Individual line item values in the approved cost break-down tables will be used to determine partial payments during the progress of the work and as the basis for calculating an adjustment in compensation for the contract lump sum items of highway planting and irrigation system due to changes in line items of work ordered by the Engineer. When the total of ordered changes to line items of work increases or decreases the lump sum price bid for either Highway Planting or Irrigation System by more than 25 percent, the adjustment in compensation for the applicable lump sum item will be determined in the same manner specified for increases and decreases in the total pay quantity of an item of work in Section 4-1.03B, "Increased or Decreased Quantities," of the Standard Specifications.

**HIGHWAY PLANTING COST BREAK-DOWN**

**Contract No. 04-0A9204**

| UNIT DESCRIPTION | UNIT | APPROXIMATE QUANTITY | VALUE | AMOUNT |
|---|---|---|---|---|
| ROADSIDE CLEARING | LS | LUMP SUM | | |
| REMOVE EXISTING PLANTS FOR TRENCHING | LS | LUMP SUM | | |
| PREPARE HOLE | EA | 1950 | | |
| SOIL AMENDMENT | CY | 1400 | | |
| CULTIVATE | SQYD | 470 | | |
| MULCH | CY | 150 | | |
| COMMERCIAL FERTILIZER (GRANULAR) | LB | 140 | | |
| PLANT (GROUP A) | EA | 780 | | |
| PLANT (GROUP B) | EA | 280 | | |
| PLANT (GROUP E) | EA | 150 | | |
| PLANT (GROUP I) | EA | 810 | | |
| PLANT (GROUP P) | EA | 7 | | |
| PLANT (GROUP U) | EA | 47 | | |
| PLACE BOULDERS | TON | 89 | | |
| | | | | |
| | | | | |
| | | | | |

**TOTAL** _____

**IRRIGATION SYSTEM COST BREAK-DOWN**

**Contract No. 04-0A9204**

| UNIT DESCRIPTION | UNIT | APPROXIMATE QUANTITY | VALUE | AMOUNT |
|---|---|---|---|---|
| CHECK AND TEST AND REMOVEEXISTING IRRIGATION FACILITIES | LS | LUMP SUM | | |
| CONTROL AND NEUTRAL CONDUCTORS (ARMOR CLAD) | LS | LUMP SUM | | |
| 1" ELECTRIC REMOTE CONTROL VALVE (PRESSURE REGULATING) | EA | 9 | | |
| 1-1/4" ELECTRIC REMOTE CONTROL VALVE (PRESSURE REGULATING) | EA | 1 | | |
| 2" ELECTRICL REMOTE CONTROL VALVE (PRESSURE REGULATING) | EA | 1 | | |
| 24 - STATION IRRIGATION CONTROLLER (WALL MOUNTED) | EA | 1 | | |
| GPRS CELLULAR PHONE PACKAGE | EA | 1 | | |
| 2" FLOW SENSOR | EA | 1 | | |
| FLOW MONITORING PACKAGE | EA | 1 | | |
| FLOW SENSOR SIGNAL WIRE | LS | LUMP SUM | | |
| 3/4" PLASTIC PIPE (SCH 40) (SUPPLY LINE) | LF | 1440 | | |
| 1" PLASTIC PIPE (SCH 40) (SUPPLY LINE) | LF | 500 | | |
| 1-1/4" PLASTIC PIPE (SCH 40) (SUPPLY LINE) | LF | 40 | | |
| 2" PLASTIC PIPE (PR 315) (SUPPLY LINE)(MAIN) | LF | 350 | | |
| 3/4" PLASTIC PIPE (IRRIGATION LINE) | LF | 3700 | | |
| 2" BACKFLOW PREVENTER ASSEMBLY | EA | 1 | | |
| BACKFLOW PREVENTER ASSEMBLY ENCLOSURE | EA | 1 | | |
| BACKFLOW PREVENTER INSULATION BLANKET | EA | 1 | | |
| SPRINKLER (TYPE B-2) | EA | 170 | | |
| SPRINKLER (TYPE D-1) | EA | 980 | | |

**IRRIGATION SYSTEM COST BREAK-DOWN**

**Contract No. 04-0A9204**

| | | | | |
|---|---|---|---|---|
| 2" GATE VALVE | EA | 3 | | |
| 3/4" QUICK COUPLING VALVE | EA | 5 | | |
| FLUSH VALVE | EA | 6 | | |
| 1” WYE STRAINER | EA | 1 | | |
| | | | | |
| | | | | |
| | | | | |

**TOTAL _____**

## 10-2.02 EXISTING HIGHWAY PLANTING

In addition to the provisions in Section 20, "Erosion Control and Highway Planting," of the Standard Specifications, work performed in connection with existing highway planting shall conform to the provisions in "Existing Highway Facilities," of these special provisions.

Replacement planting shall conform to the provisions in "Preservation of Property" of these special provisions.

### MAINTAIN EXISTING PLANTED AREAS

Existing planted areas, designated on the plans to be maintained, shall be maintained throughout the life of the contract in conformance with these special provisions.

Attention is directed to "Preservation of Property" of these special provisions.

Existing plants shall be watered in conformance with the provisions in Section 20-4.06, "Watering," of the Standard Specifications.

Existing planted areas to be maintained shall be inspected for deficiencies by the Contractor in the presence of the Engineer. Deficiencies requiring corrective action shall include weeds; dead, diseased, or unhealthy plants; missing plant stakes and tree ties; inadequate plant basins; and other deficiencies needing corrective action to promote healthy plant life. The inspection shall be completed within 15 days after the start of work.

Deficiencies found during the inspection shall be corrected within 15 days after the inspection ends. Correction of deficiencies, as directed by the Engineer, will be paid for as extra work in conformance with the provisions in Section 4-1.03D, "Extra Work," of the Standard Specifications.

After deficiencies have been corrected, the Contractor shall perform work to maintain existing planted areas in a neat appearance and to promote healthy plant growth. The work shall include the following:

A. Weeds shall be killed before the weeds reach the seed stage of growth or exceed 6 inches in length.
B. Trash, debris and weeds shall be removed from existing planted areas. Weeds shall be killed prior to removal. Trash, debris and weed removal in ground cover areas shall extend beyond the outer limits of ground cover areas to the adjacent edges of paving, fences and proposed plants and planting areas, and a 6-foot diameter area centered at each existing tree and shrub outside of existing ground cover areas.
C. Existing plant basins shall be kept well-formed and free of silt. If existing plant basins require repairs, and the plant basins contain mulch, the mulch shall be replaced after the plant basins have been repaired.
D. When a portion of a new automatic irrigation system is completed, the existing plants to be watered by that portion of the irrigation system shall be watered automatically.
E. Pesticides for maintaining existing planted areas shall conform to the provisions in "Pesticides" of these special provisions.

The contract lump sum price paid for maintain existing planted areas shall include full compensation for furnishing all labor, materials, tools, equipment, and incidentals, and for doing all the work involved in maintain existing planted areas, complete in place, as shown on the plans, as specified in the standard specifications and these special provisions, and as directed by the Engineer.

### REMOVE EXISTING PLANTS FOR TRENCHING

Removing existing plants for trenching shall conform to the provisions in Section 20-5.026, "Remove Existing Plants for Trenching," of the Standard Specifications and these special provisions.

Removing existing plants for trenching work shall consist of removing and replacing ground cover, pruning trees and shrubs within trench locations, and disposing of removed ground cover and prunings.

Replacement of removed ground cover within the maximum 6-foot width, as specified in Section 20-5.026, "Remove Existing Plants for Trenching," of the Standard Specifications, will be required, except for trenches within 6-foot of fences, curbs, dikes or shoulders.

Trees and shrubs adjacent to dikes, walks, fences, guard railing, and pavement edges may be pruned back 10 feet from these facilities to facilitate trenching work. When trenching is to be performed adjacent to other trees and shrubs that cannot be avoided, the trees and shrubs may be pruned upon receipt of prior written approval of the Engineer.

Pruning shall include removal of deadwood, suckers, and broken or bruised branches one inch or larger in diameter. Pruning shall conform to the provisions in Section 20-4.055, "Pruning," of the Standard Specifications.

Removed ground cover and pruned materials shall be disposed of in conformance with the provisions in Section 7-l.13, "Disposal of Material Outside the Highway Right of Way," of the Standard Specifications. At the Contractor's option,

removed ground cover and prunings may be reduced to chips. Chipped materials shall be spread within the highway right of way where designated by the Engineer.

Shrubs adjacent to dikes, fences, guard railing, and the edge of pavement within the 10-foot pruned area designated above, that in the opinion of the Engineer should be removed after pruning, shall be removed and disposed of. Removing and disposing of the shrubs not otherwise provided for will be paid for as extra work as provided in Section 4-1.03D,"Extra Work," of the Standard Specifications.

## 10-2.03 EXISTING HIGHWAY IRRIGATION FACILITIES

The work performed in connection with the various existing highway irrigation system facilities shall conform to the provisions in "Existing Highway Facilities," of these special provisions.

Water shall be maintained in conformance with the provisions in Section 20-5.025, "Maintain Existing Water Supply," of the Standard Specifications.

### CHECK AND TEST EXISTING IRRIGATION FACILITIES

Existing irrigation facilities that are to remain and that are within those areas where clearing and grubbing or earthwork operations are to be performed, shall be checked for missing or damaged components and proper operation prior to performing clearing and grubbing or earthwork operations. Existing irrigation facilities outside of work areas that are affected by the construction work shall also be checked for proper operation.

A written list of existing irrigation system deficiencies shall be submitted to the Engineer within 5 working days after checking the existing facilities.

Deficiencies found during checking of the existing facilities shall be corrected as directed by the Engineer. Corrective work ordered by the Engineer will be paid for as extra work as provided in Section 4-1.03D, "Extra Work," of the Standard Specifications.

Length of watering cycles for use of potable water from water meters for checking or testing existing irrigation facilities shall be as determined by the Engineer.

Additional repairs required for the existing irrigation system as ordered by the Engineer, except as otherwise provided for in "Maintain Existing Irrigation Facilities" of these special provisions, will be paid for as extra work as provided in Section 4-1.03D, "Extra Work," of the Standard Specifications.

### MAINTAIN EXISTING IRRIGATION FACILITIES

Existing irrigation facilities shall be maintained throughout the life of the contract. Prior to the start of maintaining existing irrigation facilities work, the facilities shall be checked for proper operation, and repaired in conformance with the provisions in "Check and Test Existing Irrigation Facilities" of these special provisions.

After the existing facilities have been checked and repaired, the Contractor shall be responsible for the routine maintenance of existing irrigation systems. The work shall include, but not limited to, checking irrigation systems for proper operation and adjusting, repairing or replacing valves, valve boxes, sprinklers, risers, swing joints, wye strainers, valve assembly units, and filter assembly units.

The Contractor will not be responsible for maintaining existing water meters, underground pipe supply lines, control and neutral conductors, and electrical conduits. Except as otherwise specified in "Existing Highway Irrigation Facilities" of these special provisions, repair work to these facilities ordered by the Engineer will be paid for as extra work as provided in Section 4-l.03D, "Extra Work," of the Standard Specifications.

Existing automatic irrigation systems shall be operated automatically during the life of the contract, except manual operation will be allowed for the work during plant replacement, fertilization, weed germination, and the repair of irrigation facilities.

Irrigation controllers shall be programmed by the Contractor for seasonal water requirements. During winter seasons irrigation systems shall be operated automatically a minimum of 2 minutes every 2 weeks.

Irrigation systems and facilities shall be checked for proper operation at least once every 30 days. When required, as determined by the Engineer, adjusting, repairing or replacing irrigation facilities shall be completed within 5 working days after checking the irrigation systems. Except as provided in these special provisions, repair and replacement of irrigation facilities shall conform to the provisions in "Existing Highway Irrigation Facilities" of these special provisions.

Except as provided in these special provisions, the contract lump sum price paid for maintain existing irrigation facilities shall include full compensation for furnishing all labor, materials, tools, equipment, and incidentals, and for doing all the work involved in maintaining existing irrigation facilities, complete in place, including checking irrigation facilities, as shown on the plans, as specified in the Standard Specifications and these special provisions, and as directed by the Engineer.

**REMOVE EXISTING IRRIGATION FACILITIES**

Existing irrigation facilities where shown on the plans to be removed, shall be removed. Facilities that are more than 6 inches below finished grade may be abandoned in place.

Immediately after disconnecting an existing irrigation facility to be removed or abandoned from an existing facility to remain, the remaining facility shall be capped or plugged, or shall be connected to a new or existing irrigation facility.

Facilities to be removed shall be disposed of in conformance with the provisions in Section 7-1.13, "Disposal of Material Outside the Highway Right of Way," of the Standard Specifications.

## 10-2.04 HIGHWAY PLANTING

The work performed in connection with highway planting shall conform to the provisions in Section 20-4, "Highway Planting," of the Standard Specifications and these special provisions.

**HIGHWAY PLANTING MATERIALS**

**Mulch**

Mulch must be wood chips.

**Commercial Fertilizer (Granular)**

Commercial fertilizer (granular) shall be a pelleted or granular form and shall fall within 20 percent of the following guaranteed chemical analysis:

| Ingredient | Percentage |
|---|---|
| Nitrogen | 19 |
| Phosphoric Acid | 6 |
| Water Soluble Potash | 12 |

**Commercial Fertilizer (Slow Release)**

Commercial fertilizer (slow release) shall be a pelleted or granular form, shall be slow or controlled release with a nutrient release over an 8-month to 12-month period, and shall fall within the following guaranteed chemical analysis range:

| Ingredient | Percentage |
|---|---|
| Nitrogen | 16-21 |
| Phosphoric Acid | 6-8 |
| Water Soluble Potash | 4-10 |

**ROADSIDE CLEARING**

Prior to preparing planting areas, mulch areas, relocating the Worker Memorial Boulder and placing boulders, or commencing irrigation trenching operations for planting areas, trash and debris shall be removed from the entire highway right of way within the project limits, excluding paved areas, medians and existing planted areas where existing plants are to remain.

A. Weeds shall be killed and removed within the entire highway right of way, within the project limits, except for existing planting areas to be maintained, and including median areas, new and existing pavement, curb, sidewalk and other surfaced areas.
B. Existing ground cover shall be killed and removed from within an area 6 -foot in diameter centered at each proposed plant location within existing ground cover areas.

After the initial roadside clearing is complete, additional roadside clearing work shall be performed as necessary to maintain the areas, as specified above, in a neat appearance until the start of the plant establishment period. This work shall include the following:

A. Trash and debris shall be removed.
B. Rodents shall be controlled.
C. Weed growth shall be killed before the weeds reach the seed stage of growth or exceed 6 inches in length, whichever occurs first, except for weeds in wild flower seeding areas to be mowed.

D. Existing ground cover shall be killed and removed from within the 6-foot diameter areas specified for each proposed plant location within the existing ground cover areas.
E. Weeds in plant basins, including basin walls, shall be removed by hand pulling, after the plants have been planted.

**Weed Control**

Weed control shall also conform to the following:

A. Stolon type weeds shall be killed with glyphosate.
B. Removed weeds and ground cover shall be disposed of outside the highway right of way in conformance with the provisions in Section 7-1.13, "Disposal of Material Outside the Highway Right of Way," of the Standard Specifications.

Roadside clearing work shall not include work required to be performed as clearing and grubbing as specified in Section 16, "Clearing and Grubbing," of the Standard Specifications.

**PESTICIDES**

Pesticides used to control weeds shall conform to the provisions in Section 20-4.026, "Pesticides," of the Standard Specifications. Except as otherwise provided in these special provisions, pesticide use shall be limited to the following materials:

Fluazifop-butyl
Glyphosate
Oryzalin (Preemergent)

Granular preemergents may be used when applied to areas that will be covered with mulch, excluding plant basins. Granular preemergents shall be limited to the following materials:

Oxadiazon (Preemergent)

Granular preemergents shall be applied prior to the application of mulch. Mulch applications shall be completed in these areas on the same working day. Photosensitive dye will not be required.

Glyphosate shall be used to kill stolon type weeds.

Oxadiazon shall be of the emulsifiable concentration or wettable powder type, except when Oxadiazon is used under mulch in conformance with these special provisions.

Prior to the application of preemergents, ground cover plants shall have been planted a minimum of 3 days and shall have been thoroughly watered.

A minimum of 100 days shall elapse between applications of preemergents.

Except for ground cover plants, preemergents shall not be applied within 18 inches of plants.

If the Contractor elects to request the use of other pesticides on this project, the request shall be submitted, in writing, to the Engineer not less than 15 days prior to the intended use of the other pesticides. Except for the pesticides listed in these special provisions, no pesticides shall be used or applied without prior written approval of the Engineer.

Pesticides shall not be applied within the limits of the plant basins. Pesticides shall not be applied in a manner that allows the pesticides to come in contact with the foliage and woody parts of the plants.

**PLACE BOULDERS**

Place boulders shall consist of furnishing and installing "Sonoma Fieldstone" landscape boulders in the sizes and quantities as shown on the plans and in conformance with Section 72-2, "Rock Slope Protection," and these special provisions.

A sample of the boulder shall be submitted to the Engineer for approval prior to delivery of the landscape boulders to the project site.

Landscape boulders shall be completely smooth and weathered on all surfaces and without cracks, breaks, or fissures.

Landscape boulders shall be placed as follows:

A. Landscape boulders shall be placed so that one third of the boulders mass is below finish grade with rock stratification, if present, for all boulders pointing in a single direction, unless otherwise shown on the plans or directed by the Engineer.
B. Final location for boulder placement will be approved by the Engineer prior to excavation.

Boulders shall be protected from cracking, splitting or spalling by the Contractor's operations during handling and placement of the boulders. Damaged boulders shall be replaced at the Contractor's expense.

Full compensation for placing boulders shall be considered as included in the contract lump sum price paid for highway planting and no separate payment will be made therefor.

**PREPARING PLANTING AREAS**

Plants adjacent to drainage ditches shall be located so that after construction of the basins, no portion of the basin walls shall be less than the minimum distance shown on the plans for each plant involved.

**CULTIVATE**

Areas shown on the plans to be cultivated shall be cultivated.

Immediately prior to cultivation, soil amendment and commercial fertilizer shall be added to the areas to be cultivated. Soil amendment shall be added at the rate of 3 cubic feet per square yard and commercial fertilizer (granular) shall be applied at the rate of 10.5 pounds per 1,000 square feet. Soil amendment and fertilizer shall be thoroughly mixed with the soil.

After cultivation is complete and the irrigation systems have been installed and the plant holes have been excavated and backfilled, no further planting work shall be done in the cultivated areas for a period of 15 days, except the soil shall be kept sufficiently moist to germinate weeds. Weeds that germinate shall be killed.

**PLANTING**

Backfill material for plant holes shall be a mixture of soil and soil amendment. The quantity of soil amendment shall be as shown on the Plant List. Soil amendment shall conform to the provisions in Section 20-2.03, "Soil Amendment," of the Standard Specifications. Backfill material shall be thoroughly mixed and uniformly distributed throughout the entire depth of the plant hole without clods and lumps.

Commercial fertilizer (pelleted and granular) shall be applied or placed at the time of planting and at the rates shown on the Plant List and in conformance with the provisions in Section 20-4.05, "Planting," of the Standard Specifications and these special provisions.

Mulch will not be required in the plant basins when mulch is not indicated on the Plant List for the plants involved.

A granular preemergent shall be applied to areas to be covered with mulch outside of plant basins in conformance with the provisions in "Pesticides" of these special provisions.

Mulch placed in areas outside of plant basins shall be spread to a uniform depth of 2 inches, unless otherwise shown on the plans.

Mulch shall be spread from the outside of the proposed plant basin to the adjacent edges of shoulders, dikes, curbs, sidewalks, walls, fences, and existing plantings. If the proposed plant material is 12 feet or more from the adjacent edges of shoulders, dikes, curbs, sidewalks, walls, fences, and other existing plantings, the mulch shall be spread 6 feet beyond the outside edge of the proposed plant basins.

Mulch shall not be placed within 3 feet of the centerline of earthen drainage ditches, within 3 feet of the edge of paved ditches, and within 3 feet of the centerline of drainage flow lines.

Attention is directed to "Irrigation Systems Functional Test" of these special provisions regarding functional tests of the irrigation systems. Planting shall not be performed in an area until the functional test has been completed for the irrigation system serving that area.

**PLANT ESTABLISHMENT WORK**

The plant establishment period shall be Type 2 and shall not be less than 250 working days.

Attention is directed to "Relief From Maintenance and Responsibility" in these special provisions regarding relief from maintenance and protection.

Commercial fertilizer (slow release) shall be applied to trees, shrubs, vines and ground cover during the first week of April and October of each year. Commercial fertilizer shall be applied at the rates shown on the plans and shall be spread with a mechanical spreader wherever possible.

The center to center spacing of replacement plants for unsuitable ground cover plants shall be determined by the number of completed plant establishment working days at the time of replacement and the original spacing in conformance with the following:

| ORIGINAL SPACING (Inches) | SPACING OF REPLACEMENT GROUND COVER PLANTS (Inches) | | |
|---|---|---|---|
| | Number of Completed Plant Establishment Working Days | | |
| | 1-125 | 126-190 | 191-End of Plant Establishment |
| 9 | 9 | 6 | 6 |
| 12 | 12 | 9 | 6 |
| 48 | 48 | 36 | 24 |

During the plant establishment period, the plants shall be watered utilizing the Remote Irrigation Control System (RICS) software program. A watering schedule shall be submitted to the Engineer for use during the plant establishment period.

Weeds within plant basins, including basin walls and ground cover, shall be controlled by hand pulling.

Weeds within mulched and ground cover areas and outside of plant basins shall be controlled by killing.

Weeds within median areas, pavement, curbs, sidewalk, and other surfaced areas shall be controlled by killing.

At the option of the Contractor, plants of a larger container size than those originally specified may be used for replacement plants during the first 125 working days of the plant establishment period.

After 125 working days of the plant establishment period have been completed, replacement of plants, except for plant (Group I), plants, shall be 5-gallon size for one-gallon size plants; 15-gallon size for 5-gallon size plants; and other plant replacement plants shall be the same size as originally specified. Replacement bulbs (plant Group E) will not be required.

When ordered by the Engineer, one application of a preemergent pesticide conforming to the provisions in "Pesticides" of these special provisions, shall be applied between 40 working days and 50 working days prior to completion of the plant establishment period. This work will be paid for as extra work as provided in Section 4-1.03D,"Extra Work," of the Standard Specifications.

During the plant establishment period, if plants become restricted by foliage protectors, the tops of foliage protectors shall be removed. Foliage protectors shall be completely removed, including the support stakes, within 15 working days prior to completion of the plant establishment period.

Wye strainers shall be cleaned at least 15 days prior to the completion of the plant establishment period.

The final inspection shall be performed in conformance with the provisions in Section 5-1.13, "Final Inspection," of the Standard Specifications and shall be completed a minimum of 20 working days before the estimated completion of the contract.

## 10-2.05 IRRIGATION SYSTEMS

Irrigation systems shall be furnished and installed in conformance with the provisions in Section 20-5, "Irrigation Systems," of the Standard Specifications, except materials containing asbestos fibers shall not be used.

Attention is directed to the provisions in "Obstructions" of these special provisions, regarding work over or adjacent to existing underground facilities. Excavation for proposed irrigation facilities shall not be started until the existing underground facilities have been located.

Method A pressure testing shall conform to the provisions in Section 20-5.03H(1), "Method A", of the Standard Specifications, except leaks that develop in the tested portion of the system shall be located and repaired after each test period when a drop of more than 5 pounds per square inch is indicated by the pressure gage. After the leaks have been repaired, the one hour pressure test shall be repeated and additional repairs made until the drop in pressure is 5 pounds per square inch or less.

### VALVE BOXES

Valve boxes shall conform to the provisions in Section 20-2.24, "Valve Boxes," of the Standard Specifications, except as otherwise provided herein.

Valve boxes shall be precast portland cement concrete.

Covers for concrete valve boxes shall be glass fiber reinforced plastic

Valve boxes shall be identified on the top surface of the covers by stenciling with paint the appropriate abbreviations for the irrigation facilities contained in the valve boxes as shown on the plans. Valve boxes that contain remote control valves shall be identified by the appropriate letters and numbers (controller and station numbers). The letters and numbers shall be 2 inches in height. The stenciling paint shall be a commercial quality, epoxy resin base paint of a color which contrasts with the valve box covers.

**GATE VALVES**

Gate valves shall be as shown on the plans and in conformance with the provisions in Section 20-2.28, "Gate Valves," of the Standard Specifications and these special provisions.

Gate valves, 3 inches and larger in size, shall be furnished with a square nut and 3 long shank keys that will operate the valve.

Gate valves shall have a solid bronze or brass wedge.

**ELECTRIC AUTOMATIC IRRIGATION COMPONENTS**

**Irrigation Controllers**

Irrigation controllers shall be compatible with the Rainbird - Maxicom2® Central Control system and shall include a central control interface, flow monitor, cellular phone communication package, mounted on a stainless steel wall mounting backboard.

Irrigation controller and shall conform to the following:

| MODEL NO. | UNIT DESCRIPTION | UNIT | QUOTED UNIT COST |
|---|---|---|---|
| ESP-24SITE-W | 24 - STATAION ESP-SITE SATELLITE SERIES CONTROLLER (INCLUDES WALL MOUNT BACKBORAD) | EA | $4,445 |
| GPRS CELLPKG | GPRS CELL PHONE PACKAGE | EA | $1,700 |
| PT1502-PKG | FLOW MONITORING PACKAGE * | EA | $2,850 |
| **TOTAL** | | | **$8,995** |
| NOTE: The quoted prices do not include sales tax or shipping costs. | | | |

Arrangements have been made to insure that any successful bidder can obtain the specified equipment listed above from Horizon Irrigation, 1521 South Fresno Ave., Stockton, CA 95206 (209) 992-2313.

Prices are guaranteed by Horizon Irrigation until 12/31/08.

Irrigation controller equipment shall be programmed by the irrigation controller manufacturer's authorized representative or distributor.

The Contractor shall be responsible for establishing communication and programming interface between the irrigation controller and the existing remote irrigation control system (RICS) base station, and demonstrating that controllers and base station are in operating condition and performs the functions specified.

The irrigation controllers shall communicate with the base station at the Department of Transportation's District Maintenance Station, located at Sawyer Camp Trail and Hillcrest Boulevard, Millbrae, CA, 94030.

The irrigation controller shall be programmed to perform the following minimum activities in association with the existing base station:

A. Monitor the main line flows when operating with, or independently of, the base station.
B. Monitor flow rate to allow selection of:

    1. Percent-high flow
    2. Percent-low flow
    3. Provisions for supply line fill time
    4. Leak detection in excess of 19 liters per minute.

C. Closing of remote control valve (master), shutting off pumps and remote control valves when flow rates are exceeded on main lines or through remote control valve (as determined by operator-entered parameters). When an excess high flow is determined by the irrigation controller, the irrigation program shall conduct a series of test steps to determine one of the following and take the corresponding action:

    1. For a mainline break or stuck open remote control valve: The entire irrigation system shall be shut down.
    2. For a lateral line break or missing sprinklers: The current operating remote control valve shall be shut down and the irrigation program shall go on to the next scheduled remote control valve.

D. A time delay feature shall prevent an instantaneous response to a temporary surge at start-up or momentary system condition.
E. The following irrigation controller activities (alarms) shall be logged at the field unit and uploaded to the base station upon request of the base station in real-time and scheduled unattended time:

1. A low flow alarm when the actual flow is less than the percent-low and the supply line fill time has passed.
2. A high flow alarm when the actual flow is greater than the percent-high and the supply line fill time has passed.
3. There is no actual flow detected and the supply line fill time has passed.

The Contractor shall make application and arrangements for cellular service and assign the services to the State upon the date of acceptance of the contract. Fees for the applications, licenses and leases will be reimbursed by the State.

Inputs and outputs of the irrigation controller, flow monitoring and communication system shall be lightning, transient and surge protected, including the power, antenna and control connections.

Irrigation controllers shall include auxiliary items such as gutters, terminal strips, cables, antennas compatible with GPRS cellular phone package, and other additional equipment necessary for functional operation with the existing base station.

Full compensation for furnishing, installing and programming communication equipment and cellular phone package shall be considered as included in the contract lump sum price paid for irrigation systems and no additional compensation will be allowed therefor.

Full compensation for furnishing, installing and programming flow monitoring package shall be considered as included in the contract lump sum price paid for irrigation systems and no additional compensation will be allowed therefor.

**Electric Remote Control Valves**

Electric remote control valves shall conform to the provisions in Section 20-2.23, "Control Valves," of the Standard Specifications and the following:

A. Valves shall be brass-construction.
B. Valves shall be straight pattern (side inlet) as shown on the plans.
C. Electric remote control valves shall be outfitted with adjustable pressure regulators as shown on the plans. Pressure regulators shall be compatible for use with the electric remote control valves and shall be of the same manufacturer as the electric remote control valves. Pressure regulators shall regulate and maintain the outlet pressure regardless of the incoming pressure. Pressure regulators shall withstand a cold water working pressure of 200 psi. The Contractor shall adjust the pressure regulators to provide proper operation of the irrigation system downstream of the electric remote control valves.

**Flow Sensor**

Flow sensors shall be Rainbird Model FS200P or equal.

Flow sensors conform to the following:

| MODEL NO. | UNIT DESCRIPTION | UNIT | QUOTED UNIT COST |
|---|---|---|---|
| FS200P | RAIN BIRD 2'' FLOW SENSOR | EA | $700.00 |
| NOTE: The quoted prices do not include sales tax or shipping costs. | | | |

Arrangements have been made to insure that any successful bidder can obtain the specified equipment listed above from Horizon Irrigation, 1521 South Fresno Ave., Stockton, CA 95206 (209) 992-2313.

Prices are guaranteed by Horizon Irrigation until 12/31/08.

The flow sensor shall be installed in a valve box a minimum of 10 pipe diameters upstream and 5 pipe diameters downstream from the nearest fitting or other device, as shown on the plans.

The flow sensor shall be connected to flow monitoring equipment and irrigation controller with 2-conductor shielded 20 AWG or larger stranded copper signal wire.

### Pull Boxes

Pull box installations shall conform to the provisions in Section 20-5.027I, "Conductors, Electrical Conduits and Pull Boxes," of the Standard Specifications.

### Conductors

Low voltage, as used in this section "Conductors," shall mean 36 V or less.

Low voltage control and neutral conductors in pull boxes and valve boxes, at irrigation controller terminals, and at splices shall be marked as follows:

A. Conductor terminations and splices shall be marked with adhesive backed paper markers or adhesive cloth wrap-around markers, with clear, heat-shrinkable sleeves sealed over the markers.
B. Non-spliced conductors in pull boxes and valve boxes shall be marked with clip-on, "C" shaped, white extruded polyvinyl chloride sleeves. Marker sleeves shall have black, indented legends of uniform depth with transparent overlays over the legends and "chevron" cuts for alignment of 2 or more sleeves.

Markers for the control conductors shall be identified with the appropriate number or letter designations of irrigation controllers and station numbers. Markers for neutral conductors shall be identified with the appropriate number or letter designations of the irrigation controllers.

The color of low voltage neutral and control conductor insulation, except for the striped portions, shall be homogeneous throughout the entire thickness of the insulation.

Insulation for conductors may be UL listed polyethylene conforming to UL44 test standards with a minimum insulation thickness of 41 mils for wire sizes 10AWG and smaller.

## ARMOR-CLAD CONDUCTORS

Armor-clad conductors shall be used in direct burial applications from pull boxes adjacent to irrigation controller to remote control valves and other irrigation facilities in conformance with the details shown on the plans and these special provisions.

Armor-clad conductors shall conform to the following:

A. Conductors shall be the proper size for the application, and shall be solid, uncoated copper with a conductor size not less than 90 percent of the AWG diameter required.
B. At the Contractor's option, conductor insulation coverings shall be either of the following:

    1. Polyvinyl chloride (PVC) conforming to UL style, Type UF 60°C, 600 V. Average thickness of insulation shall be not less than 60 mils, with a minimum thickness of 54 mils, or
    2. UL listed polyethylene conforming to UL44 test standards with a minimum insulation thickness of 41 mils for wire sizes 10AWG and smaller.

C. Armor shall be a minimum 0.005-inch thick by 0.50-inch wide Type 304 stainless steel tape that is helically wrapped over each conductor with a 33 percent minimum overlap.
D. Outer jacket for conductors shall be sunlight resistant PVC and shall conform to the Insulated Power Cable Engineer's Association (ICEA) S-61-402, NEMA Standard WC5, and UL Listing 1263. Nominal thickness of the outer jacket shall be 30 mils with a minimum thickness of 24 mils.

## IRRIGATION SYSTEMS FUNCTIONAL TEST

Functional tests for the remote irrigation controller system (RICS) and associated automatic irrigation systems shall conform to the provisions in Section 20-5.027J, "Testing," of the Standard Specifications and these special provisions.

Two functional tests shall be performed, one without and one with connection to the remote irrigation controller system base station. Both tests shall consist of demonstrating to the Engineer, through one complete cycle of the irrigation controllers in the automatic mode, that the associated automatic components of the irrigation systems operate properly.

The Contractor shall notify the Engineer not less than 2 weeks prior to starting the functional tests for the remote irrigation control system.

The existing remote irrigation controller system base station is located at the Department of Transportation's District Maintenance Station at Sawyer Camp Trail and Hillcrest Boulevard, Millbrae, CA, 94030.

Associated automatic components for both tests shall include, but not limited to, new and existing remote control valve actuator systems, irrigation controllers, remote control valves, conductors, and flow sensors. Associated automatic

components for the second test shall include, but not be limited to, new and existing irrigation software programs, cellular phone, and flow alarms for high, low, zero, and maximum mainline flows.

The first test shall be performed prior to planting the plants and shall consist of testing the irrigation controllers and associated automatic irrigation systems without connection to the remote irrigation controller system base station. Upon completion of a satisfactory functional test, and correction of the deficiencies, the plants to be planted in the areas watered by the irrigation system may be planted, provided the planting areas have been prepared as specified in these special provisions.

The second test shall be performed prior to the start of plant establishment and shall consist of testing the irrigation controllers (field units) and associated automatic irrigation systems with connection to the remote irrigation controller system base station. As part of the second test, a remote irrigation controller system watering schedule shall be submitted for each irrigation controller (field unit) to the Engineer. The Engineer will enter the watering schedule into the irrigation software program, and a computer printout will be made available to the Contractor for verification. If the Engineer determines the submitted watering schedule is unacceptable, a revised watering schedule shall be submitted to the Engineer for approval within 5 working days. Also as part of the second test, the Contractor shall demonstrate to the Engineer that the remote irrigation controller system base station detects and reports the high, low, zero, and maximum mainline flow alarms. Upon completion of a satisfactory test, including correction of deficiencies, the plant establishment period may begin, provided planting work as specified in these special provisions has been completed except for plant establishment work.

If existing and new automatic components of the irrigation systems, including remote irrigation controller system base station components, fail a functional test, the components shall be repaired. Repairs shall be at the Contractor's expense, except for repairs to an existing base station (personal computer, printer, mouse, keyboard, cables, and software) which will be paid for as extra work as provided in Section 4-1.03D of the Standard Specifications. Testing shall be repeated until satisfactory operation is obtained.

Repair or replacement of existing irrigation facilities due to unsatisfactory performance shall conform to the provisions in Section 20-5.025, "Maintain Existing Water Supply," of the Standard Specifications and "Existing Highway Irrigation Facilities" of these special provisions.

## PIPE

### Steel Pipe

Galvanized steel pipe supply lines installed between water meters and backflow preventer assemblies shall be installed not less than 30 inches below finished grade, measured to the top of the pipe.

### Plastic Pipe

Plastic pipe supply lines shall be polyvinyl chloride (PVC) 1120 or 1220 pressure rated pipe with the minimum pressure rating (PR) shown on the plans.

Plastic pipe supply lines less than 4 inches in diameter shall have solvent cemented type joints. Primers shall be used on the solvent cemented type joints.

Plastic pipe supply lines (main) shall have a minimum cover of 2 feet.

Plastic pipe (irrigation lines) shall be installed on grade as shown on the plans.

A nonhardening joint compound shall be used in place of the pipe thread sealant tape conforming to the provisions in Section 20-5.03E, "Pipe," of the Standard Specifications. Joint compounds shall be applied in conformance with the manufacturer's recommendations.

Fittings for plastic pipe supply lines with a pressure rating (PR) of 315 shall be Schedule 80.

## THRUST BLOCK

Thrust blocks shall be installed in accordance with the these special provisions. Thrust blocks shall be installed on the main supply line at all changes in direction and terminus run.

Concrete shall conform to the special provision in Section 20-2.26, "Concrete," of the Standard Specifications.

## BACKFLOW PREVENTER ASSEMBLIES

Backflow preventers shall conform to the provisions in Section 20-2.25, "Backflow Preventers," of the Standard Specifications and these special provisions.

Backflow preventers shall have current approval from the University of Southern California Foundation for Cross-Connection Control and Hydraulic Research (USC Foundation).

Before backflow preventer assembly installation, the Contractor shall provide the Engineer with the portion of the USC Foundation "List of Approved Backflow Prevention Assemblies" showing type of assembly, manufacturer's name, model number, edition of the manual under which the assembly was approved, approval date and the last renewal date.

The "List of Approved Backflow Prevention Assemblies" is available to Foundation Members. Membership information to join the USC Foundation is available at:

http://www.usc.edu/dept/fccchr/membership.html

Questions concerning the USC Foundation "List of Approved Backflow Prevention Assemblies" can be answered by calling the Foundation at toll free (866) 545-6340.

Pressure loss through the backflow preventers shall not exceed the following:

| BACKFLOW PREVENTER SIZE (inches) | FLOW RATE (Gallons per minute) | PRESSURE LOSS (psi) |
|---|---|---|
| 2 | 80 | 12 |

Backflow preventer assemblies shall be painted with a minimum of 2 applications of a commercial quality enamel paint. The color of the paint shall be light brown.

When backflow preventer assembly enclosures are specified, the portland cement concrete pads for the enclosures will be paid for in conformance to the provisions in "Backflow Preventer Assembly Enclosures" of these special provisions.

**BACKFLOW PREVENTER ASSEMBLY ENCLOSURE**

Enclosures shall be fabricated of structural steel angles and flattened expanded metal and shall be installed over backflow preventer assemblies on a portland cement concrete pad as shown on the plans and in conformance with these special provisions.

Expanded metal for sides, ends and top panels shall be fabricated from 14-gage minimum thickness, sheet steel. The flattened expanded metal openings shall be approximately 3/4" x 1-3/4" in size.

Expanded metal panels shall be attached to the steel frames by a series of welds, not less than 1/4 inch in length and spaced not more than 4 inches on centers, along the edges of the enclosure.

Padlocks will be State-furnished in accordance with "State-furnished Materials" of these special provisions.

Enclosures shall be galvanized, after fabrication, in conformance with the provisions in Section 75-1.05, "Galvanizing," of the Standard Specifications.

Concrete for the concrete pad shall conform to Section 90-10, "Minor Concrete," of the Standard Specifications.

Hold down bolt assemblies shall be galvanized and shall be installed when the portland cement concrete pad is still plastic. Nuts shall be hexagonal and washers shall be the lock type.

Enclosures shall be painted with one application of a commercial quality pre-treatment, vinyl wash primer and a minimum of one application of a commercial quality, exterior enamel for metal. The finish color shall be light brown.

All parts of the backflow preventer assembly enclosure, including hold down assemblies, may be constructed of stainless steel instead of standard steel materials specified above. Stainless steel enclosures shall conform to the provisions herein except galvanizing, priming and painting shall not be required. Stainless steel enclosures shall be powder coated a light brown color by the manufacturer.

The minimum clearance between the backflow preventer assembly and the backflow preventer assembly enclosure shall be 2 inches.

**TESTING NEW BACKFLOW PREVENTERS**

New backflow preventers shall be tested for proper operation in conformance with the provisions in Section 20-5.03J, "Check and Test Backflow Preventers," of the Standard Specifications and these special provisions.

Tests for new backflow preventers shall be satisfactorily completed after installation and before operation of the irrigation systems.

New backflow preventers shall be retested one year after the satisfactory completion of the previous test, and each year thereafter until the plant establishment period is completed. An additional test shall be provided not more than 10 days prior to acceptance of the contract.

**BACKFLOW PREVENTER ASSEMBLY BLANKET**

Backflow preventer assembly blankets on new backflow preventer assemblies shall be furnished and installed in conformance with these special provisions.

At the Contractor's option, blankets shall be vinyl coated or polymeric resin coated polyester fabric. Blanket insulation shall have a minimum R-value of 30. The outer fabric of the blankets shall be green and UV, water, mildew and flame resistant.

Blankets installed on backflow preventer assemblies with an enclosure shall have a securing mechanism using zippers, Velcro, grommets, snaps or buttons or a combination thereof.

Blankets shall be sized and installed in conformance with the manufacturer's instructions. One copy of the manufacturer's instructions shall be furnished to the Engineer.

**SPRINKLERS**

Sprinklers shall conform to the type, pattern, material, and operating characteristics listed in the "Sprinkler Schedule" shown on the plans.

**SPRINKLER (TYPE D)**

Type D sprinklers shall be plastic, nonadjustable, pressure compensating emitters with automatic flushing action. Emitter shall be regulated by dual silicone diaphragms. Emitters shall have the flow rate and operating pressure range shown on the plans.

Emitters shall be installed as shown on the plans and in conformance with the manufacturer's written instructions. Two copies of the written instructions shall be furnished to the Engineer prior to installation.

Emitters shall be equipped with a single barb which shall be inserted into a shrub nut. Shrub nuts shall be installed on a threaded polyvinyl chloride (PVC) riser as shown on the plans.

Flexible tubing for the emitters shall be virgin polyethylene plastic containing 2 percent to 3 percent carbon black. The size of the tubing shall be as recommended by the manufacturer of the emitter.

Discharge ends of tubing shall be held in place, within the basin and approximately 2 inches above grade, by plastic or metal stakes. Stakes shall be as recommended by the manufacturer of the emitter.

**WYE STRAINERS**

Wye strainers shall be installed on the upstream side of the electric remote control valves as shown on the plans.

When garden valves are opened, discharge shall be up and out of the valve box.

**FLUSH VALVES**

Flush valves shall consist of a garden valve, riser and a plastic pipe (locator). Flush valves shall be installed at the ends of supply lines for Type D sprinklers as shown on the plans.

A total of 3 loose keys for the garden valves, as specified herein, shall be furnished to the Engineer prior to completion of the project.

Pipe supply line (locator) shall conform to the provisions in Section 20-2.20, "Plastic Pipe (Locator)," of the Standard Specifications.

**FINAL IRRIGATION SYSTEM CHECK**

A final check of existing and new irrigation facilities shall be performed not more than 40 working days and not less than 30 working days prior to acceptance of the contract.

The length of watering cycles using potable water measured by water meters for the final check of irrigation facilities will be determined by the Engineer.

Remote control valves connected to existing and new irrigation controllers shall be checked for automatic performance when the controllers are in automatic mode.

Unsatisfactory performance of irrigation facilities installed or modified by the Contractor shall be repaired and rechecked at the Contractor's expense until satisfactory performance is obtained, as determined by the Engineer.

Repair or replacement of existing irrigation facilities due to unsatisfactory performance shall conform to the provisions in "Existing Highway Irrigation Facilities" of these special provisions.

Nothing in this section "Final Irrigation System Check" shall relieve the Contractor of full responsibility for making good or repairing defective work or materials found before the formal written acceptance of the entire contract by the Director.

Full compensation for checking the irrigation systems prior to the acceptance of the contract shall be considered as included in the contract lump sum price paid for plant establishment work and no additional compensation will be allowed therefor.

## SECTION 10-3. (BLANK)

## SECTION 11. (BLANK)

## SECTION 12. BUILDING WORK

## SECTION 12-1. GENERAL REQUIREMENTS

### 12-1.01 SCOPE

Building work described herein and as shown on the plans shall conform to the requirements of these special provisions and Sections 1 through 9 of the Standard Specifications. Sections 10 through 95 of the Standard Specifications shall not apply to the work in this Section 12 except when specific reference is made thereto.

The building work to be done consists, in general, of removing the existing comfort station and display kiosk, and construction of a men's and women's comfort station, CHP office, vending structure, display canopy and retaining wall and such other items or details, not mentioned above, that are required by the plans, Standard Specifications, or these special provisions shall be performed, placed, constructed or installed.

### 12-1.02 ABBREVIATIONS

Section 1-1.02, "Abbreviations," of the Standard Specifications is amended by adding the following:

| | |
|---|---|
| AAMA | American Architectural Manufacturers' Association |
| ACI | American Concrete Institute |
| AGA | American Gas Association |
| AITC | American Institute of Timber Construction |
| AMCA | Air Movement and Control Association |
| APA | American Plywood Association |
| ARI | American Refrigeration Institute |
| ASHRAE | American Society of Heating, Refrigeration and Air Conditioning Engineers |
| CBC | California Building Code (2001 Edition) |
| CEC | California Electrical Code (2001 Edition) |
| CMC | California Mechanical Code (2001 Edition) |
| CPC | California Plumbing Code (2001 Edition) |
| CS | Commercial Standards (US Department of Commerce) |
| ESO | Electrical Safety Orders |
| FGMA | Flat Glass Marketing Association |
| FM | Factory Mutual |
| FS | Federal Specification |
| ICBO | International Conference of Building Officials |
| NAAMM | National Association of Architectural Metal Manufacturers |
| NBFU | National Board Fire Underwriters |
| NEC | National Electrical Code |
| NFPA | National Fire Protection Association or National Forests Products Association |
| PEI | Porcelain Enamel Institute |
| PS | Product Standard (US Department of Commerce) |
| RIS | Redwood Inspection Service |
| SCPI | Structural Clay Products Institute |
| SMACNA | Sheet Metal and Air Conditioning Contractors' National Association |
| SSPC | Steel Structures Paint Council |
| TCA | Tile Council of America |
| TPI | Truss Plate Institute |
| UBC | Uniform Building Code (1997 Edition) |
| WCLIB | West Coast Lumber Inspection Bureau (stamped WCLB) |
| WCLB | Grade stamp for WCLIB |

| | |
|---|---|
| WI | Woodwork Institute |
| WWPA | Western Wood Products' Association |

**12-1.03 GUARANTEE**

The Contractor hereby unconditionally guarantees that the building work will be done in accordance with the requirements of the contract, and further guarantees the building work of the contract to be and remain free of defects in workmanship and materials for a period of one year from the date of acceptance of the contract, unless a longer guarantee period is required elsewhere in these special provisions. The Contractor hereby agrees to repair or replace any and all building work, together with any other adjacent work which may be displaced in so doing, that may prove to be not in accordance with the requirements of the contract or that may be defective in its workmanship or material within the guarantee period specified, without any expense whatsoever to the Department, ordinary wear and tear and unusual abuse or neglect excepted.

The performance bond for contract price of the building work, shall remain in full force and effect during the guarantee period.

The Contractor further agrees, that within 10 calendar days after being notified in writing by the Department of any building work not in accordance with the requirements of the contract or any defects in the building work, he shall commence and prosecute with due diligence all work necessary to fulfill the terms of this guarantee, and shall complete the work within a reasonable period of time, and, in the event he fails to comply, he does hereby authorize the Department to proceed to have such work done at the Contractor's expense and he shall honor and pay the cost and charges therefor upon demand. The Department shall be entitled to all costs and expenses, including reasonable attorney's fees, necessarily incurred upon the Contractor's refusal to honor and pay the above costs and charges.

**12-1.04 AREAS FOR CONTRACTOR'S USE**

No area is available within the contract limits for the exclusive use of the Contractor. The Contractor shall arrange with the Engineer for areas to store equipment and materials within the work area.

**12-1.05 COOPERATION**

Attention is directed to Sections 7-1.14, "Cooperation," and 8-1.10, "Utility and Non-Highway Facilities," of the Standard Specifications and these special provisions.

The Contractor shall plan his work to minimize interference with State forces and the public. Interruptions to any services for the purpose of making or breaking a connection shall be made only after consultation with and for such time periods as directed by the Engineer.

**12-1.06 SUBMITTALS**

Working drawings, material lists, descriptive data, samples and other submittals specified in these special provisions shall be submitted for approval in accordance with the provisions in Section 5-1.02, "Plans and Working Drawings," of the Standard Specifications and these special provisions.

Unless otherwise permitted in writing by the Engineer, all submittals required by these special provisions shall be submitted within 35 days after the contract has been approved.

Attention is directed to the provisions in Section 5-1.01, "Authority of Engineer," of the Standard Specifications. The Engineer may request submittals for materials or products where submittals have not been specified in these special provisions, or may request that additional information be included in specified submittals, as necessary to determine the quality or acceptability of such materials or products.

Attention is directed to Section 6-1.05, "Trade Names and Alternatives," of the Standard Specifications. The second indented paragraph of the first paragraph of said Section 6-1.05 is amended to read:

Whenever the specifications permit the substitution of a similar or equivalent material or article, no test or action relating to the approval of such substituted material will be made until the request for substitution is made in writing by the Contractor accompanied by complete data as to the equality of the material or article proposed. Such request shall be made within 35 days after the date the contract has been approved and in ample time to permit approval without delaying the work, but need not be made in less than 35 days after award of the contract.

Work requiring the submittal of working drawings, material lists, descriptive data, samples, or other submittals shall not begin prior to approval of said submittal by the Engineer. Fifteen working days shall be allowed for approval or return for correction of each submittal or resubmittal. Should the Engineer fail to complete his review within the time specified and if, in the opinion of the Engineer, the Contractor's controlling operation is delayed or interfered with by reason of the delay in review, an extension of time commensurate with the delay in completion of the work thus caused will be granted as provided in Section 8-1.07, "Liquidated Damages," of the Standard Specifications.

Submittals shall be delivered to the locations indicated in these special provisions. If a specific location is not indicated, the submittal shall be delivered to the Division of Structure Design, Documents Unit, Fourth Floor, Mail Station 9-4/4I, 1801 30th Street, Sacramento, California 95816, telephone (916) 227-8252, or the submittals shall be mailed to the Division of Structure Design, Documents Unit, Mail Station 9-4/4I, P. O. Box 942874, Sacramento, California 94274-0001.

Each submission of drawings, material lists and descriptive data shall consist of at least 5 copies. Two copies will be returned to the Contractor either approved for use or returned for correction and resubmittal.

Each separate item submitted shall bear a descriptive title, the name of the project, district, county, and contract number. Plans and detailed drawings shall be not larger than 22" x 36".

The material list shall be complete as to name of manufacturer, catalog number, size, capacity, finish, all pertinent ratings, and identification symbols used on the plans and in the special provisions for each unit.

Parts lists and service instructions packaged with or accompanying the equipment installed in the work shall be delivered to the Engineer at the jobsite. Required operating and maintenance instructions shall be submitted in triplicate.

Manufacturer's warranties for products installed in the work shall be delivered to the Engineer at the jobsite.

Unapproved samples and samples not incorporated in the work shall be removed from State property, when directed by the Engineer.

**12-1.07 SCHEDULE OF VALUES**

The Contractor shall prepare and submit to the Engineer for approval 2 copies of a Schedule of Values within 15 working days of approval of the contract covering each lump sum item for building work. Fifteen working days shall be allowed for approval or return for correction of each submittal or resubmittal. Should the Engineer fail to complete his review within the time specified and if, in the opinion of the Engineer, the Contractor's controlling operation is delayed or interfered with by reason of the delay in review, an extension of time commensurate with the delay in completion of the work thus caused will be granted as provided in Section 8-1.07, "Liquidated Damages," of the Standard Specifications.

The Schedule of Values must be accurately divided into sections representing the cost of each separate building or structure. All work that is not part of a separate building or structure, such as excavation, grading, curbs, gutters, sidewalks, paving, sewer and storm drainage and utility distribution lines are to be included under a specific section as General Work and not included in the building or structure cost. Indirect costs and general condition items are to be listed as a separate line item of work. The sections representing each building or structure must be identified as to the building or structure they represent and be broken down to show the corresponding value of each craft, trade or other significant portion of the work. A sub-total for each section shall be provided.

The Schedule of Values shall be approved by the Engineer before any partial payment estimate is prepared.

The sum of the items listed in the Schedule of Values shall equal the contract lump sum price for building work. Overhead, profit and bond premium are to be proportionally distributed across all line items of cost.

## 12-1.08 INSPECTION

All items covered or all stages of work that are not to remain observable must be inspected and approved before progress of work conceals portions to be inspected. The Contractor shall notify the Engineer not less than 72 hours in advance of when such inspection is needed.

## 12-1.09 OBSTRUCTIONS

Attention is directed to Sections 7-1.11, "Preservation of Property," 7-1.12, "Responsibility for Damage," 7-1.16, "Contractor's Responsibility for the Work and Materials," and 8-1.10, "Utility and Non-Highway Facilities," of the Standard Specifications.
The Contractor shall notify the Engineer and the appropriate regional notification center for operators of subsurface installations at least 5 working days prior to performing any excavation or other work close to any underground pipeline, conduit, duct, wire or other structure. Regional notification centers include but are not limited to the following:

Underground Service Alert
Northern California (USA)
Telephone: 1(800)642-2444

Underground Service Alert
Southern California (USA)
Telephone: 1(800)422-4133

South Shore Utility
Coordinating Council (DIGS)
Telephone: 1(800)541-3447

Western Utilities
Underground Alert, Inc.
Telephone: 1(800)424-3447

## 12-1.10 PRESERVATION OF PROPERTY

Attention is directed to Sections 7-1.11, "Preservation of Property," 7-1.12, "Responsibility for Damage," 7-1.16, "Contractor's Responsibility for the Work and Materials," and 8-1.10, "Utility and Non-Highway Facilities," of the Standard Specifications.

Operations shall be conducted in such a manner that existing facilities, surfacing, installations, and utilities which are to remain in place will not be damaged. Temporary surfacing, facilities, utilities and installations shall also be protected until they are no longer required. The Contractor, at his expense shall furnish and install piling, sheet piling, cribbing, bulkheads, shores, or whatever means may be necessary to adequately support material carrying such facilities, or to support the facilities themselves and shall maintain such support until they are no longer needed.

## 12-1.11 UTILITY CONNECTION

The Contractor shall make all arrangements, and obtain all permits and licenses required for the extension of and connection to each utility service applicable to this project, shall furnish all labor and materials necessary for such extensions which are not performed or provided by the utility, and shall furnish and install any intermediate equipment required by the serving utilities.

Upon written request by the Contractor, the State will pay all utility permits, licenses, connection charges, and excess length charges directly to the utility. Such request shall be submitted not less than 45 days before service connections are required.

The costs incurred by the Contractor for the extensions of utilities beyond the limits shown on the plans, and in furnishing and installing any intermediate equipment required by the serving utilities, will be paid for as extra work as provided in Section 4-1.03D of the Standard Specifications.

Full compensation for any costs incurred by the Contractor to obtain the permits and licenses shall be considered as included in the contract lump sum price paid for building work and no additional compensation will be allowed therefor.

### 12-1.12 TEMPORARY UTILITIES

The Contractor may obtain electrical power and water from existing State electrical power and water outlets within the contract limits free of charge for contract operations where such utilities exist, provided that such utility services are in service and are not required by the State for other purposes and subject to the provisions in the section "Cooperation" of these special provisions.

The Contractor shall make his own arrangements to obtain any additional electrical power and water or other utilities required for his operations and shall make and maintain the necessary service connections at his own expense.

When existing utility systems are being modified, periods of shutdown will be determined by the Engineer.

The Contractor shall provide adequate temporary lighting to perform the work and allow the Engineer to inspect the project as each portion is completed.

The Contractor shall provide and pay for telephone service he may require. State telephone facilities shall not be used.

### 12-1.13 SANITARY FACILITIES

Tools shall not be cleaned nor shall cleaning liquids be disposed of in State sanitary facilities or sewers.

Separate toilet facilities shall be provided for Contractor's personnel. Facilities shall include the periodic flushing, waste removal and cleaning of such facilities. Units shall to be maintained in a clean and sanitary condition, including a supply of toilet tissue, toilet seat covers, paper towels and paper cups. Waste material shall be disposed of off site in a lawful manner. Temporary toilet units shall be single occupant units of the chemical type, properly vented and fully enclosed with a glass fiber reinforced polyester shell or similar nonabsorbent material.

### 12-1.14 MEASUREMENT AND PAYMENT

The contract lump sum price paid for building work shall include full compensation for furnishing all labor, materials, tools, equipment, and incidentals, and for doing all the work involved in constructing the building work, complete in place, as shown on the plans, as specified in the Standard Specifications and these special provisions, and as directed by the Engineer.

Full compensation for any incidental materials and labor, not shown on the plans or specified, which are necessary to complete the buildings and appurtenances shall be considered as included in the contract lump sum price paid for building work and no additional compensation will be allowed therefor.

### 12-1.15 PROJECT RECORD DRAWINGS

The Contractor shall prepare and maintain one set of project record drawings, using an unaltered set of original project plans, to clearly show all as-constructed information for the project. As a minimum, the information to be shown shall include 1) any plan clarifications or change orders, 2) locations of any underground utilities, or 3) the location, size, type, and manufacturer of all major products or components selected by the Contractor for use in the work.

All markings shall be placed on the project record drawings using red ink or red pencil. Original figures shall not be eradicated nor written over and superseded material shall be neatly lined out. Additional drawings shall be submitted if the required information cannot be clearly shown on the original set of project plans. The additional drawings shall be not less than 11" x 17" in size and shall have the contract number on each sheet. The Contractor shall sign and date each sheet of the project record drawings to verify that all as-constructed information shown on the drawings is correct.

The Contractor shall periodically review the set of project record drawings with the Engineer during the progress of the work to assure that all changes and other required information are being recorded.

Before completion of the work, the Contractor shall request a review of the project record drawings to determine the completeness and adequacy of them. If the project record drawings are unacceptable, the Contractor shall inspect, measure, and survey the project as necessary to record the required additional information.

The set of completed project record drawings shall be delivered to the Engineer prior to acceptance of the contract.

**12-1.16 FIELD ENGINEERING**

This section specifies administrative and procedural requirements for field engineering services to be performed by the Contractor.

Lines and Grades:

Attention is directed to Section 5-1.07, "Lines and Grades," of the Standard Specifications.

Such stakes or marks will be set by the Engineer as he determines to be necessary to establish the lines and grades required for the completion of the work shown on the plans and as specified in these special provisions. In general, these will consist of the primary vertical and horizontal control points.

Stakes and marks set by the Engineer shall be carefully preserved by the Contractor. In case such stakes and marks are destroyed or damaged they will be replaced at the Engineer's earliest convenience. The Contractor will be charged for the cost of necessary replacement or restoration of such stakes and marks which in the judgment of the Engineer were carelessly or willfully destroyed or damaged by the Contractor's operations. This charge will be deducted from any moneys due or to become due the Contractor.

All other stakes or marks required to establish the lines and grades required for the completion of the work shall be the responsibility of the Contractor.

Existing utilities and equipment:

The existence and location of underground and other utilities and construction indicated as existing are not guaranteed. Before beginning sitework, the Contractor shall investigate and verify the existence and location of underground utilities and other construction.

Prior to construction, the Contractor shall verify the location and invert elevation at points of connection of sanitary and septic sewers, storm sewer, and water or fire service piping.

Surveys for layout and performance:

The Contractor shall perform all surveys for layout and performance, reduce field notes, and make all necessary calculations and drawings necessary to carry out the work.

The Contractor shall locate and layout site improvements, and other work requiring field engineering services, including pavements, stakes for grading, fill and topsoil placement, utility slopes and invert elevations by instrumentation and similar appropriate means.

Batter boards shall be located and laid out for structures, building foundations, column grids and locations, floor levels and, control lines and levels required for mechanical and electrical work.

Survey accuracy and tolerances:

The tolerances generally applicable in setting survey stakes for foundations, slabs, and underground work shall not exceed the following:

| Survey Stakes or Markers | Tolerance |
|---|---|
| Rough grading or excavation | 0.10-foot |
| Trimming or preparation of subgrade for roadways | 0.05-foot |
| Roadway surfacing, steel or concrete pipe | 0.02-foot |
| Structures or building construction | 0.01-foot |

Such tolerance shall not supersede stricter tolerances required by the plans or special provisions, and shall not otherwise relieve the Contractor of responsibility for measurements in compliance therein.

## SECTION 12-2. SITEWORK

### 12-2.01 BUILDING DEMOLITION AND REMOVAL OF MISCELLANEOUS FACILITIES

**SCOPE.—**This work consists of the requirements for building demolition and removal work,-as part of new construction work.

**REFERENCES.--**

The publications listed below form a part of this specification to the extent referenced. The publications are referred to in the text by the basic designation only.

**AMERICAN NATIONAL STANDARDS INSTITUTE (ANSI)**
ANSI A10.6 (1990) Safety Requirements for Demolition Operations

**AIR CONDITIONING AND REFRIGERATION INSTITUTE (ARI)**
ARI Guideline K (1997) Containers for Recovered Fluorocarbon Refrigerants

**GENERAL.--**Contractor shall not begin demolition until authorization is received from the Engineer. The work includes demolition, and removal of resulting rubbish and debris. Rubbish and debris shall be removed from State property daily, unless otherwise directed, to avoid accumulation at the demolition site. Materials that cannot be removed daily shall be stored in areas specified by the Engineer. In the interest of occupational safety and health, the work shall be performed in accordance with applicable sections of State safety ordinances for demolition work.

**SUBMITTALS.--**

**Work Plan.—**Contractor shall submit the procedures proposed for the accomplishment of the work. The procedures shall provide for safe conduct of the work, including procedures and methods to provide necessary supports, lateral bracing and shoring when required protection of property which is to remain undisturbed, coordination with other work in progress, and timely disconnection of utility services. The procedures shall include a detailed description of the methods and equipment to be used for each operation, and the sequence of operations. Submit proposed demolition and removal procedures to the Engineer for approval before work is started.

**REGULATORY AND SAFETY REQUIREMENTS.--**

The Contractor shall comply with federal, state, and local hauling and disposal regulations. In addition to the requirements of the "Contract Clauses," safety requirements shall conform with ANSI A10.6.

**Notifications.--**Furnish timely notification to Federal, State, regional, and local authorities in accordance with 40 CFR 61-SUBPART M. Notify the State Environmental Protection Agency and the Engineer in writing 10 working days prior to the commencement of work.

**DUST AND DEBRIS CONTROL.--**

Prevent the spread of dust and debris on roadway pavements or building compound and avoid the creation of a nuisance or hazard in the surrounding area. Do not use water if it results in hazardous or objectionable conditions such as, but not limited to, ice, flooding, or pollution. Vacuum and dust the work area frequently. Sweep pavements as often as necessary to control the spread of debris that may result in foreign object damage potential to vehicles.

**PROTECTION.--**

**Existing Work.--**Before beginning any demolition work, the Contractor shall survey the site and examine the drawings and specifications to determine the extent of the work. The Contractor shall take necessary precautions to avoid damage to existing items to remain in place, to be reused, or to remain the property of the State; any damaged items shall be repaired or replaced as approved by the Engineer. The Contractor shall coordinate the work of this section with all other work and shall construct and maintain shoring, bracing, and supports as required. The Contractor shall ensure that structural elements are not overloaded and shall be responsible for increasing structural supports or adding new supports as may be required as a result of any cutting, removal, or demolition work performed under this contract.

**Trees.--**Trees within the project site which might be damaged during demolition, and which are indicated to be left in place, shall be protected by a 6 foot fence. The fence shall be securely erected a minimum of 5 feet from the trunk of individual trees or follow the outer perimeter of branches or clumps of trees. Any tree designated to remain that is damaged during the work under this contract shall be replaced in kind or as approved by the Engineer.

**Facilities.--**Protect electrical and mechanical services and utilities. Where removal of existing utilities and pavement is specified or indicated, provide approved barricades, temporary covering of exposed areas, and temporary services or connections for electrical and mechanical utilities.

**Protection of Personnel.--**During the demolition work the Contractor shall continuously evaluate the condition of the structure being demolished and take immediate action to protect all personnel working in and around the demolition site. No area, section, or component of floors, roofs, walls, columns, pilasters, or other structural element will be allowed to be left standing without sufficient bracing, shoring, or lateral support to prevent collapse or failure while workmen remove debris or perform other work in the immediate area.

**BURNING**.--The use of burning at the project site for the disposal of refuse and debris will not be permitted.

**USE OF EXPLOSIVES.--**Use of explosives will not be permitted.

**EXISTING FACILITIES TO BE REMOVED.--**

**Structures.--**Existing structures indicated shall be removed to bottom of slab and footings.

**Utilities and Related Equipment.--**Abandon existing utilities in place, except as indicated otherwise, and terminate in a manner conforming to the nationally recognized code covering the specific utility and approved by the Engineer. When utility lines are encountered that are not indicated on the drawings, the Engineer shall be notified prior to further work in that area. Remove meters and related equipment and deliver to a location in accordance with instructions of the Engineer. If utility lines are encountered that are not shown on drawings, contact the Engineer for further instructions.

**DISPOSITION OF MATERIAL.--**

**Title to Materials.--**Except where specified in other sections, all materials and equipment removed, and not reused, shall become the property of the Contractor and shall be removed from State property. Title to materials resulting from demolition, and materials and equipment to be removed, is vested in the Contractor upon approval by the Engineer of the Contractor's demolition and removal procedures, and authorization by the Engineer to begin demolition. The State will not be responsible for the condition or loss of, or damage to, such property after contract award. Materials and equipment shall not be viewed by prospective purchasers or sold on the site.

**Unsalvageable Material.--**Concrete, masonry, and other noncombustible material, except concrete permitted to remain in place, shall be disposed of in the disposal area located off site. Combustible material shall be disposed of in the sanitary fill area located off the site.

**CLEANUP.--**Debris and rubbish shall be removed from excavations. Debris shall be removed and transported in a manner that prevents spillage on streets or adjacent areas. Local regulations regarding hauling and disposal shall apply.

## 12-2.02 ASBESTOS ABATEMENT

## PART 1 - GENERAL

This work includes removal, clean up and disposal of the below listed asbestos containing material (ACM) and asbestos containing construction material (ACCM) to the extent necessary for the building and structure demolition work of this project. The Contractor shall review all demolition plans, survey reports and field verify location and extent of materials containing asbestos related work.

### REFERENCES

Codes, regulations and references applicable to asbestos abatement work include but are not limited to the following:

1. American National Standards Institute (ANSI) publications;

   Z9.2-79 Fundamentals Governing the Design and Operation of Local Exhaust Systems.

   A10.6-2006. Safety Requirements For Demolition Operations

2. American Society for Testing and Materials (ASTM) publications;

   D1331-89 (Re-approved 2001) Surface and Interfacial Tensions of Solutions of Surface Active Agents.

   E1494-92 (Re-approved 2002) Specifications for Encapsulants for Friable Asbestos-Containing Building Materials.

   E1368.90 Standard Practices For Visual Inspection of Asbestos Abatement Projects.

3. Code of Federal Regulations (CFR);

   29 CFR 1926.1101 "Asbestos."

   40 CFR 61 Subpart A and Subpart M, USEPA, "National Emission Standards for Hazardous Air Pollutants (NESHAPS)."

4 National Fire Protection Association (NFPA):

   No. 70.2005 National Electrical Code.

5. California Code of Regulations (CCR):

   Title 8, Division 1, Chapter 3.2, Subchapter 2, "Regulations of the Division of Occupational Safety and Health;" Article 2.5, Section 341.6 to 341.14; "Registration-Asbestos-Related Work."

   Title 8, Division 1, Chapter 4, Subchapter 7, "General Industry Safety Orders," Group 16, Article 110, Section 5203; "Carcinogen Report of Use Requirements."

   Title 8, Division 1, Chapter 4, Subchapter 4, "Construction Safety Orders," Article 4, Section 1529: "Asbestos"

   Title 22, Division 4.5, Chapter 10, "Hazardous Waste Management System: General."

6. Local Air Pollution Control District Regulations

**EXISTING SITE CONDITIONS**

A hazardous material survey report by:

1. Asbestos and Lead-based Paint/Material Demolition Survey, by CSC of Pleasanton, CA, March 31, 2005
2. Asbestos & Deteriorated Lead Paint Survey Report, by Geocon, March 2007
3. Retaining Wall Asbestos Report, by EMSL, April 27, 2007

is included as an information handout. Location of asbestos containing materials and presumed asbestos containing materials from survey reports where work is preformed include:

| Location | Description | Asbestos Concentration | Approximate Amount |
|---|---|---|---|
| Rock façade (Serpentine) | Exterior A side (West wall) | 3% - 5% Chrysotile | 190 sqft |
| Retaining wall (Serpentine) | Entire wall | .25% - 14.75% Chrysotile | 246 lf |

This work includes all plans, permits and the removal, transportation, storage, and disposal of all material containing asbestos as specified or shown on the plans.

Furniture and portable equipment will be removed from the area of work by the Department before any work begins.

**PRECONSTRUCTION MEETING**

At least 7 days before asbestos removal work commences, a preconstruction meeting shall be held at a location designated by the Engineer. Attendees shall include the Engineer, Department's Observation Service, Contractor's Competent Person; the Contractor's Project Superintendent, and others as necessary. The agenda shall include a review of project safety requirements, the Contractor's written asbestos compliance work plan, emergency contacts and notification plan, containment and work area design, facility requirements, submittals, and any other issues pertinent to the safe execution of the asbestos abatement work.

Work shall not commence until the Engineer has approved submittals and plans for asbestos abatement work.

**EQUIPMENT AND MEDICAL SURVEILLANCE**

Personnel protective equipment, training, and medical surveillance required by the Contractor's Health and Safety Plan shall be provided to State personnel by the Contractor. The number of State personnel will be 4. The Contractor shall comply with all Federal State and local requirements for safety which shall include providing employees with coveralls (preferably disposable plastic coated), rubber gloves (to be discarded after use), rubber boots (to be washed thoroughly after use) and appropriate respirators (to cover nose and mouth). The Contractor shall be responsible for verifying that all employees, who are involved in asbestos removal operations, wear the protective devices enumerated herein during removal operations.

**SUBMITTALS**

**Product data**

A list of manufacturer's product data, specifications, samples and application instructions and other pertinent information as necessary shall be submitted for approval.

**Abatement Procedure Plans**

The Contractor shall submit the following detailed plan of the work procedures for abatement of asbestos materials:

1. Federal, State and Local agencies that require notification.
2 Personal monitoring procedures.

3. Phasing of abatement work indicating daily roster of workers for each phase.
4. Security system warning signs locations.
5. Detailed plans for decontamination facilities, toilets, and systems providing intraroom and Work Area to outside communication showing connections to existing building.
6. Standard procedures for protecting workers, visitors, and employees and protection of spaces outside Work Area from contamination.
7. Engineering systems exposure control indicating number, location, and capacity of supply and exhaust systems, the expected direction of flow, and the range of expected differential pressure in each area.
8. Safety precautions such as lockout, tagout, fall protection, and confined space entry procedures and equipment and work procedures to be used in the encapsulation, removal and demolition of materials containing asbestos.

The plan shall be prepared, signed and stamped by a certified asbestos consultant.

**Waste Transportation:** Submit the method of transport of hazardous waste including name, address, EPA I.D. number and telephone number of transporter.

**Hazardous Waste Site:** Submit for approval the name, class, address, EPA I.D. number and telephone number of hazardous waste site(s) to be utilized for disposal.

**Waste Manifest:** For Waste Manifest purposes the Generator is the facility of the subject work. Obtain necessary information for this purpose from the Engineer. Give a copy of the Waste Manifest to the State's Observation Service for each shipment of material containing asbestos. The Contractor shall submit a non hazardous waste manifest or waste shipment record (WSR) for disposal of material containing asbestos that is not classified as a hazardous waste.

**Qualifications:** The following documents shall be submitted:

Registration: Submit copy of the registration for Asbestos-Related work from the Division of Occupational Safety and Health in accordance with Title 8, Article 2.5 of the California Code of Regulations.

Medical Examination: Submit proof that personnel who will be entering regulated asbestos areas have had medical examinations, and furnish the results of said exam to the Engineer and signed by the medical examiner.

Submit an employee roster to the Engineer for each Work Shift and confirm in writing within 24 hours of commencement of shift.

**Land Disposal Restrictions:** Submit a copy of the completed Notice and Certification with each Hazardous Waste Manifest for wastes intended for land disposal pursuant to Section 67740 of 22 CCR, Division 4.5, Chapter 45, to the Engineer and signed by the generator.

For HEPA-filtration systems exhausting externally within 15 meters of the building's air intake or entry, submit the results of on-site DOP or Portacount testing of required efficiency.

## NOTIFICATIONS, COMMUNICATIONS AND POSTINGS

The Contractor shall notify the Engineer 15 working days prior to the start of any abatement work.
Prior to performing operations involving the removal of material containing asbestos, the Contractor shall provide written notification to all Federal, State and local agencies that regulate the handling and disposal of material containing asbestos.
The Division of Occupational Safety and Health (CAL OSHA) shall be notified 24 hours prior to performing removal operations of materials containing asbestos.
Notification shall be in accordance with the NESHAP, 40 CFR, Part 61, Subpart M and Section 341.9 of Title 8 of California Code of Regulations.
In addition to detailed requirements of this Specification, comply with laws, ordinances, rules, and regulations of federal, state, regional, and local authorities regarding handling, storing, transporting, and disposing of material containing asbestos. Submit matters of interpretation of standards to the appropriate administrative agency for resolution before

starting work. Where requirements of this Specification and reference documents vary, the most stringent requirement shall apply.

**FIELD AIR SAMPLING**

Personnel monitoring and other monitoring which is required by law or considered necessary by the Contractor for worker protection shall be the responsibility of the Contractor and performed by the Contractor's Competent Person. The Contractor shall disclose any interest in the firm or laboratory performing the Field Air Sampling or analysis.

## PART 2 – PRODUCTS (Not applicable)

## PART 3 - EXECUTION

**PROJECT PROCEDURES**

**GENERAL**

Asbestos abatement work shall not commence until:

Arrangements have been made for disposal of material containing asbestos at an acceptable site.
Arrangements have been made for containing and disposal of waste water containing asbestos resulting from wet stripping.
Work areas and decontamination enclosure systems and parts of the building required to remain in use are effectively segregated.
Tools, equipment and material waste receptacles are on hand.
Arrangements have been made for building security.
Preparatory steps have been taken and applicable notices posted and permits obtained.
Differential pressure systems are installed and operating, where applicable.
The Contractor's submittal for the isolating of non-asbestos work areas has been reviewed and approved by the Engineer.

**WORK AREAS**

**WORK AREA REQUIREMENTS**

All asbestos abatement shall be preformed in regulated areas with access limited to the asbestos removal contractor's employees, regulating officials and Engineer until cleared.
All regulated areas require clearance testing by the Department's observation service using the Transmission Electron Microscopy (TEM) analysis method.
Mini-enclosure's shall have clearance testing in accordance with the TEM analysis method.
The department will pay for all laboratory tests necessary for clearance testing.
When performing removal work on wall or ceiling areas with unknown asbestos analysis reports, a full containment, negative pressure enclosure, 3 stage decontamination area will be required.
Shut down electric power. Provide temporary power and lighting and ensure safe installation of temporary power sources and equipment per applicable electrical code requirements and provide ground-fault interrupter circuits as power source for electrical equipment.
Shut down and isolate heating, cooling, and ventilation air systems to prevent contamination and fiber dispersal to other areas of the structure. Isolate and depressurize steam, compressed gas, hydraulics, and other pressurized systems prior to work involving piping or components in such systems. During the work, vents within the work area shall be sealed with 2 layers of 6 mil fire rated plastic sheeting sealed with tape.
Do not begin work until area is free of loose equipment.
Pre-clean fixed objects within the proposed Work Areas, using HEPA filtered vacuum equipment or wet cleaning methods, as appropriate, and enclose with protective barriers of plywood covered with minimum 6 mil fire rated plastic sheeting sealed with tape.
All stationary equipment will be pre-cleaned with a HEPA filtered vacuum and protected with a water-tight double 6 mil fire rated plastic sheeting.

Clean the proposed Work Areas using HEPA filtered vacuum equipment or wet cleaning methods as necessary to maintain fiber levels at or below 0.01 f/cc. Methods that raise dust, such as dry sweeping or vacuuming with equipment not equipped with HEPA filters shall not be used.
Seal off openings, including but not limited to corridors, doorways, ducts, grills, diffusers, and any other penetrations of the Work Areas, with 2 layers of 6 mil fire rated plastic sheeting sealed with tape. Doorways and corridors which will not be used for passage during work shall be sealed with barriers.
Cover floor and wall surfaces with plastic sheeting sealed with tape. Use a minimum of two layers of 6 mil fire rated plastic on floors. Cover floors first so that plastic extends at least 305 mm up on walls, then cover walls with a minimum of 6 mil fire rated plastic sheeting to the floor level, thus overlapping the floor material by a minimum of 305 mm. The Contractor may use additional layers to assist in protection during the replacement of materials.
Install Decontamination Enclosure System or equivalent prefabricated portable decontamination units as approved.
Maintain emergency and fire exits from work areas.

**MAINTENANCE OF CONTAINMENT/NEGATIVE PRESSURE ENCLOSURE SYSTEMS**

Ensure that barriers and plastic linings are effectively sealed and taped. Repair damaged barriers and remedy defects immediately upon discovery.
Visually inspect enclosures at the beginning of each work period.
Use smoke methods to test effectiveness of barriers prior to implementing asbestos removal and when directed by the Engineer. Ensure that the integrity of the enclosure system is not breached during the duration of its use.

**DISPOSAL**

Containers to be loaded for transportation from the holding area shall be removed by workers who have entered from unregulated areas, dressed in clean overalls. Workers shall not enter from the holding area into the wash room or the work area.
The sealed asbestos containers shall be delivered to the Contractor's pre-designated approved Hazardous Waste Site for burial; in accordance with Title 22, CCR, EPA guidelines and 40 CFR 61.156 and local Air Pollution Control District Regulations.
Notify the Engineer 48 hours in advance of the time when materials containing asbestos are to be removed from the site.
The Contractor shall be responsible for safe handling and transportation of hazardous waste generated by this Contract to the designated Hazardous Waste Site.
The Contractor shall hold the State harmless for claims, damages, losses, and expenses against the State, including attorney's fees arising out of or resulting from asbestos spills on the site or spills enroute to the disposal site.

**DECONTAMINATION OF WORK AREA (GROSS REMOVAL TECHNIQUE)**

After visual inspection and written notification to proceed from the State's Observation Service and after visual inspection by the State's observation Service, encapsulate surfaces where asbestos material has been removed.

Surfaces from which asbestos have been removed shall be sealed with a clear encapsulant after the surface is clean and dry. Post abatement lockdown encapsulant shall be applied using airless spray equipment.

Prepare and apply encapsulant according to the manufacturer's specifications.

Upon completion of encapsulation work, notify the Engineer in writing that encapsulation surfaces are ready for review.
The State's Observation Service shall determine that a clearance fiber count is at or below 70 s/mm$^2$ by TEM analysis following Asbestos Hazard Emergency Response Act (AHERA) protocol.
Upon proper notification, the Engineer and the State's Observation Service will review encapsulated surfaces for conformance with Specifications. Non-conformance of work shall be remedied until work is in compliance.
Upon successful compliance with review of the Engineer, and after written notification from the State's Observation Service, remove outer layer of plastic floors. Inner plastic layer and isolation barriers, vents, grilles, diffuser, etc. shall remain in place.
Wet clean or clean with HEPA vacuum equipment, surfaces within the work area. Equipment used in the work area shall be included in the clean-up and shall be removed from the work area. Decontamination enclosure system(s) shall remain during the cleaning sequence until after final air clearance.

After final cleaning operation or removal procedure notify the Engineer that the work area is ready for review and "Clearance Testing". If "Clearance Testing" shows the work area has not been decontaminated, repeat cleaning or application of encapsulant, or both, until the work area is in compliance.
After written notification from the Engineer accepting decontamination of the work area, remove inner plastic layer isolation barriers and proceed with any remaining repairs or refinish work and reestablishment of objects and systems as specified.

**AIR MONITORING**

**PERIMETER AREA AIR MONITORING**

Throughout the abatement process perimeter area air monitoring may be conducted by the State's Observation Service to ensure work is done in conformance with fiber concentration limits of these Specifications.
If perimeter area air monitoring outside the work area is in excess of 0.01 fibers/cc the Contractor shall make modifications in work procedures to assure compliance with minimum standards. Unsatisfactory results are fiber counts in excess of 0.01 fibers/cc by Phase Contract Microscopy (PCM) NIOSH 7400 method measured outside the work area as Perimeter Area Air Monitoring.
The State's Observation Service will report perimeter area air monitoring results collected outside the work area to the Engineer on the following day prior to start of work.
The Contractor shall submit the laboratory analysis report and chain of custody (COC) to the State's Observation Service of the Contractor's personal monitoring results within 48 hours following completion of that work shift. Personal air monitoring results shall not exceed the maximum use level (MUL) of the respiratory protection factor (PF) in use for asbestos.

**CLEARANCE TESTING**

The State's Observation Service upon completion of the visual inspection and encapsulation review form (Form A) will conduct final air clearance sampling for each work area. For the purpose of this work, clearance shall be defined as an air sample showing fiber counts at or below 70s/mm$^2$ by Transmission Electron Microscopy (TEM) analysis following the Asbestos Hazard Emergency Response Act (AHERA) 40 CFR Part 763 Appendix A to Subpart E (Transmission Electron Microscopy Analytical Method). The Contractor will be given a Clearance Testing and Asbestos Air Monitoring Notification (Form B) by the State's Observation Service.

**RE-ESTABLISHMENT OF SYSTEMS**

When clean-up is complete:

1. Re-establish HVAC including installation of new filters and disposal of used filters, and insure mechanical and electrical systems are in proper working order.

**REPAIR AND PAINTING**

Damage to finishes and other items, not scheduled for demolition or removal, as a result of work under this section shall be repaired or replaced, painted, or cleaned to match existing adjacent surfaces to satisfaction of the Engineer. Painting shall comply with the requirements under "Painting" in Division 9, "Finishes," of these special provisions.

**VISUAL INSPECTION AND ENCAPSULATION REVIEWS** **FORM A**

PROJECT: WORK ORDER NO.:
LOCATION: BUILDING NAME:
WORK AREA (if applicable):
CONTRACTOR:

## VISUAL INSPECTION REVIEW

In accordance with the Contract Specifications, for the referenced project, Contractor hereby certifies that all surfaces in the referenced building work area are free from all visible material and residue, and notifies the Engineer or Observation Service that the referenced area is ready for visual inspection review.

By: Date:
(Signature)

Title:
(Print Name)

Observation Service hereby certifies that Observation Service has performed the visual inspection review of the referenced work area, and verifies that this inspection has been thorough and that all surfaces in the work area are free from all visible material and residue. Observation Service hereby notifies Contractor to proceed with the encapsulation of the abated surfaces and decontamination of the work area.

By: Date:
(Signature)

Title:
(Print Name)

## ENCAPSULATION REVIEW

Contractor hereby notifies the Engineer or Observation Service that the work area encapsulated surfaces are ready for review.

By: Date:
(Signature)

Title:
(Print Name)

Observation Service certifies the review of the work area encapsulated surfaces was acceptable and found them to be in conformance with the Specifications.

By: Date:
(Signature)

Title:
(Print Name)

**CLEARANCE TESTING & ASBESTOS AIR MONITORING NOTIF1CATION FORM B**

PROJECT: WORK ORDER NO.:
LOCATION: BUILDING NAME:
WORK AREA (if applicable):
CONTRACTOR:

**CLEARANCE TESTING CERTIFICATION**

Observation Service hereby certifies that Observation Service has taken an air sample "Clearance Test" upon completion of each Work Area. Observation Service further certifies that the decontamination of the Work Area has complied with the Specifications and the air samples indicated a fiber count of at or below 70 s/mm$^2$ by TEM analysis as per AHERA protocol.

By: Date:
(Signature)

Title:

(Print Name)

**ASBESTOS AIR MONITORING NOTIFICATION**

To: (Name of Facility CPO)

(Name & Location of Facility)

(Department)

In accordance with Asbestos Notification Law, health and Safety Code Section 25915, and for the above referenced project Building (Work Area, if applicable), the Real Estate Services Division (RESD) is transmitting the information herein above related to the air monitoring results conducted pursuant to Section 1529 of Title 8 of the California Code of Regulations. RESD has logged this transmittal as a part of Asbestos Program records.

If you have any questions regarding this information, contact the Project Manager.

From: Date:

Signature of RESD Construction Supervisor

(Print Name)

## 12-2.03 LEAD RELATED CONSTRUCTION WORK

### PART 1 - GENERAL

#### SUMMARY

The work shall consist of procedures for removal, repair, and disposal of lead based materials which are designated on the plans or specified in these special provisions to be removed and disposed of.

The Contractor shall take special precautions for that part of the work which involves the demolition and handling of materials which may contain lead, either during demolition or construction.

#### SITE CONDITIONS

The building areas to be removed are known to contain lead containing materials. A hazardous material survey report by

1. Asbestos and Lead-based Paint/Material Demolition Survey, by CSC of Pleasanton, CA, March 31, 2005
2. Asbestos & Deteriorated Lead Paint Survey Report, by Geocon, March 2007

is included as an Information Handout. The following items tested positive for Lead Based Paint material:

| **Lead based paint** | | | |
|---|---|---|---|
| **Location** | **Description** | **Lead Concentration** | **Approximate Amount** |
| Walls and Partitions | Ceramic tile system | 0.93 – 4.0 mg/sqcm | 2,500 sqft |
| Everywhere | Existing paint systems | | |

Where existing lead based materials are to be removed during demolition, construction or alterations, such material may need to be treated as hazardous waste, and shall be removed, hauled and disposed of in accordance with all applicable Federal, State and local laws and ordinances.

**SUBMITTALS**

The Contractor shall submit to the Engineer a lead compliance plan, abatement procedure plan and debris containment and collection plan. No work shall be done on any portion of the work which contains, or may contain, lead based materials until the Engineer has review and approved the submittals. The Contractor shall allow 15 days for the review of the submittals.

These plans shall be submitted as specified in Section 5-1.02, "Plans and Working Drawings," of the Standard Specifications.

**Lead Compliance Plan**

The Contractor shall prepare a project specific lead compliance plan to prevent or minimize worker exposure to lead.
The lead compliance plan shall contain the elements listed in Title 8, California Code of Regulations, Section 1532.1(e)(2)(B). The lead compliance plan shall be prepared, signed and stamped by an Industrial Hygienist certified in Comprehensive Practice by the American Board of Industrial Hygiene.

**Abatement Procedure Plans**

The abatement procedure plan prepared, signed and stamped by a lead project monitor or lead project designer currently certified by the California Department of Health Services. The plan shall address but not be limited to the following abatement procedures:

1. Personal monitoring procedures.
2. Phasing of abatement work indicating daily roster of workers for each phase.
3. Security system warning signs locations.
4. Detailed plans for decontamination facilities, toilets, and systems providing anteroom and work area to outside communication showing connections to the existing building.
5. Standard procedures for protecting workers, visitors, and employees and protection of spaces outside work area from contamination.
6. Engineering systems exposure control indicating number, location, and capacity of supply and exhaust systems, the expected direction of flow, and the range of expected differential pressure in each area.
7. Safety precautions such as lockout, tagout, fall protection, confined space entry procedures and equipment and work procedures to be used in the encapsulation, removal and disposal of lead based paint..
8. Final clearance inspection criteria.

**Debris Containment and Collection Plan**

The debris containment and collection plan shall be prepared, signed and stamped by a lead project monitor or lead project designer currently certified by the California Department of Health Services. The program shall identify

materials, equipment, and methods to be used when the existing paint system is disturbed and shall include working drawings of containment systems, and provisions for ventilation and air movement for visibility and worker safety.

**REFERENCES**

Codes which govern removal and disposal of materials containing lead include, but are not limited to the following:

1. California Health and Safety Code, Division 20, Chapter 6.5, "Hazardous Waste Control."
2. California Code of Regulations, Title 17, Division 1, Chapter 11, "Occupational Lead Poisoning Prevention Program."
3. California Code of Regulations, Title 22, Division 4.5, Chapter 10, "Hazardous Waste Management System: General."
4. California Code of Regulations, Title 8, Division 1, Chapter 4, Subchapter 4, Article 4, "Lead."
5. Occupational Safety and Health Administration (OSHA), 29 Code of Federal Regulation (CFR) Part 1926.62, "Lead."

**NOTIFICATION**

The Contractor shall notify the Engineer 3 business days in advance of the start of removal operations of lead based material.

Prior to performing operations involving the removal of lead based material, the Contractor shall provide written notification to all Federal, State and local agencies that regulate the removal, handling, transporting and disposal of lead in construction.

The Contractor shall notify the Division of Occupational Safety and Health (CAL OSHA) 24 hours prior to performing removal operations of materials containing lead or lead based materials.

**QUALITY ASSURANCE**

The lead related construction work shall be supervised by a California Department of Health Services Certified Lead Supervisor. The supervisor shall be on-site during abatement work preparation and post-abatement clean-up and be readily available as required by Title 17 California Code of Regulations 36100 (A1). Personnel for lead related construction work shall be California Department of Health Services Lead Worker Certified.

**REGULATORY REQUIREMENTS**

If measures being taken by the Contractor are inadequate to provide for worker safety and the containment and collection of residue from existing paint systems, the Engineer will direct the Contractor to revise his operations and the compliance plans. Such directions will be in writing and will specify the items of work for which the Contractor's compliance plans are inadequate. No further work shall be performed on said items until the compliance plans are adequate and, if required, a revised compliance plan has been approved.

If inadequate measures are taken to provide for the containment and collection of debris produced when the existing paint system is disturbed, the Engineer will direct the Contractor to revise the operations and the debris containment and collection plan. The directions will be in writing and will specify the items of work for which the debris containment and collection plan is inadequate. No further work shall be performed on the items until the debris containment and collection plan is adequate and, if required, a revised plan has been approved for the containment and collection of debris produced when the existing paint system is disturbed.

The State will not be liable to the Contractor for failure to approve all or any portion of an originally submitted or revised compliance program for worker safety and the containment and collection of residue from existing paint systems, nor for any delays to the work due to the Contractor's failure to submit an acceptable compliance program.

**SAFETY**

Construction activities (including demolition) that disturb materials or paints containing any amount of lead are subject to certain requirements of the in Title 8, California Code of Regulations Section 1532.1.

Any work that disturbs the existing paint system will expose workers to health hazards and will:

1. Produce debris containing heavy metal in amounts that may exceed the thresholds established in Titles 8 and 22 of the California Code of Regulations.
2. Produce toxic fumes when heated.

The Contractor shall be responsible for verifying that all employees, who are involved in removal operations, wear the required protective devices during removal operations.

Personal protective equipment, training, and washing facilities, required by the Contractor's health and safety plan shall be supplied to State personnel by the Contractor. The number of State personnel will be 4.

**TRAINING**

State personnel shall complete a safety training program provided by the Contractor, that meets the requirements of Title 8, California Code of Regulations, Section 1532.1, "Lead," and the Contractor's lead compliance program.

**PART 2 – PRODUCTS (Not applicable)**

**PART 3 - EXECUTION**

**REMOVAL**

Painted materials shall be removed using the wet process, vacuum blasting process or other acceptable processes that contain paint debris. Use removal equipment as necessary to remove all paint and provide clean substrate suitable for a new finish.

Removed material and water used for removal shall be collected. Removed material shall be separated from water using approved filters.

**HANDLING**

The Contractor shall comply with all Federal, State, and local regulations for the removal of material containing lead prior to demolition, shall place such removed material in approved plastic containers (double ply, 0.15 mm minimum thickness, plastic bags) with caution labels affixed to said bags. Such caution labels shall have conspicuous, legible lettering which spells out the following, or equivalent warning:

**CAUTION**

**CONTAINS LEAD**

Temporary storage on the ground of material and residue produced when the existing paint system is disturbed will not be permitted. Material and residue shall be stored in leak proof containers and shall be handled in such a manner that no spillage will occur.

At the option of the Contractor, the removed lead based materials may be placed directly into a roll off or drop box which shall have the same caution label affixed on all sides.

### TRANSPORTING

The debris shall be hauled by a transporter currently registered with the California Department of Toxic Substances Control using correct manifesting procedures and vehicles displaying current certification of compliance. The Contractor shall make all arrangements with the operator of the disposal facility and perform any testing of the debris required by the operator. All vehicles used to transport hazardous waste material shall have affixed to the vehicle a valid Certificate of Compliance issued by United States Department of Transportation. If a roll off or drop box is utilized, both the drop box and the transporting vehicle shall have a valid Certificate of Compliance issued by the United States Department of Transportation.

### DISPOSAL

The Engineer will obtain the required EPA generator identification numbers, and will sign the hazardous waste manifests.

All material and residue produced during removal operations shall be tested and profiled to determine hazardous waste characteristics. Dispose of residue and waste at an approved disposal facility in accordance with the requirements of the disposal facility operator.

The Contractor shall notify the proper authorities at the disposal site in advance of delivery of hazardous waste containing lead to the disposal site.

### FINAL CLEARANCE INSPECTION

Final clearance inspection wipe testing will be performed after clean-up activities are completed following Department of Health Services criteria in the California Code of Regulations Title 17.

## 12-2.04 EARTHWORK FOR BUILDING WORK

## PART 1 - GENERAL

### SUMMARY

Scope: This work shall consist of performing earthwork for building work in accordance with the details shown on the plans and these special provisions.

Earthwork for building work shall consist of structure excavation and structure backfill. Structure excavation shall include excavation for footings, foundations, walls, and trenches. Structure backfill shall include backfilling under slabs; backfilling under and around footings; backfilling for walls, backfilling for pipes and conduits; backfilling holes resulting from removal of existing facilities. In addition to structure excavation and structure backfill, earthwork for building work shall include any other earthwork, not mentioned, but necessary to complete the building work.

Attention is directed to the Information Handout for information regarding foundation recommendations and reports that were prepared for use during the design of this project.

Attention is directed to the requirements of "Field Engineering" in Section 12-1, "General Requirements," of these special provisions.

### QUALITY ASSURANCE

Samples: Samples of sand, pea gravel, or crushed stone, weighing not less than 25 pounds, shall be submitted to the Engineer at the jobsite for approval.

## SITE CONDITIONS

Existing Underground Piping and Conduit: The location of existing underground piping and conduit is based on the best records available. Before beginning work, the Contractor shall accurately locate the piping and conduit involved in the work. If the location of the existing piping or conduit deviates from the location shown on the plans by more than 5 feet, or, if no elevations are indicated and the piping or conduit is more than 3 feet below grade, the cost of the additional excavation, backfill, piping or conduit, and removal and replacement of concrete, if any, will be paid for as extra work as provided in Section 4-1.03D of the Standard Specifications.

Existing Surfaced or Planted Areas:

Existing surfaced or planted areas that are removed, broken or damaged by the Contractor's operations shall be restored to their original condition except as otherwise shown on the plans or specified herein.

Restoration materials shall be equal to or better than the original materials. Surfacing shall be replaced to match the material thickness, grades, and finish of the adjacent surrounding surfaces.

# PART 2 - PRODUCTS

## BACKFILL MATERIALS

Structure Backfill: Structure and trench backfill shall be free of organic and other deleterious material and shall be suitable for the required compaction. Gravel without sand matrix shall not be used except as free draining granular material beneath slabs and footings.

Sand: Sand shall be clean, washed sand, free from clay or organic material graded such that 100 percent passes the 1/4-inch sieve, 90 percent to 100 percent passes the No. 4 sieve and not more than 5 percent passes the No. 200 sieve size.

Pea Gravel (Naturally Rounded):

Pea gravel (naturally rounded) shall be clean, washed, dry density of not less than 95 pounds per cubic foot, free from clay or organic material and shall conform to the following grading as determined by California Test 202:

| Sieve or Screen Size | Percentage Passing |
|---|---|
| 3/4" | 100 |
| 1/2" | 90-100 |
| 3/8" | 40-70 |
| No. 4 | 0-15 |
| No. 8 | 0-3 |

Pea gravel shall conform to the following requirements:

| Test | California Test No. | Test Requirements |
|---|---|---|
| Durability Index | 229 | 35 Min. |

Crushed Stone:

Crushed stone shall be clean, washed, dry density of not less than 95 pounds per cubic foot, crushed stone or crushed gravel with an angular particle size not less than 1/8 inch or more than 1/2 inch.

| Sieve or Screen Size | Percentage Passing |
|---|---|
| 1/2" | 100 |
| 3/8" | 85-100 |
| No. 4 | 10-30 |
| No. 8 | 0-3 |

Crushed stone shall conform to the following requirements:

| Test | California Test No. | Test Requirements |
|---|---|---|
| Durability Index | 229 | 35 Min. |

## PART 3 - EXECUTION

### PREPARATION AND RESTORATION

Sawcutting: Prior to excavation or trenching, existing surfacing shall be removed to saw cut lines, or to existing wood dividers or expansion joints, if any. The saw cut shall be to a neat line and have a depth not less than one inch.

Restoration: Surfacing shall be replaced to match the thickness, grades and finish of the adjacent surrounding surfaces.

### STRUCTURE EXCAVATION

Unless otherwise noted, all excavation for building work shall be classified as structure excavation.

Footing Excavation:

The bottom of excavation shall not be disturbed. The Contractor shall excavate by hand to the final grade. The bottom of concrete footings shall be poured against undisturbed material. Unless otherwise noted, compaction of the bottom of footing excavation is not required unless the material is disturbed. The footing depths shown on the plans shall be changed to suit field conditions when directed by the Engineer. Solid rock at or near required depths shall not be disturbed. Unsuitable material shall be excavated down to firm bearing as directed by the Engineer. Work and materials required because of excavation in excess of the depths shown on the plans, when such excavation has been ordered by the Engineer, will be paid for as extra work as provided in Section 4-1.03D of the Standard Specifications.

Excavate to the elevations and dimensions within a tolerance of ±1/2 inch. Limits of the excavation shall allow for adequate working space for installing materials and as required for safety of personnel. Such working space excavation shall be replaced in kind and compacted at the Contractor's expense.

Overdepth excavation for footings shall be backfilled with concrete or such other material recommended by the Contractor and approved by the Engineer. Relative compaction shall be not less than 95 percent.

Excavation for Pipes and Conduits:

Pipes or conduits in the same trench shall have a minimum clear distance between pipes or conduits of 6 inches. Pipes or conduits shall have not less than 2½ feet of cover from top of pipes or conduits to finished grade unless otherwise shown on the plans or specified.

Trenching shall be of sufficient depth to permit placing a minimum depth of 4 inches of compacted sand under all pipes and conduits.

Excavation adjacent to trees shall be performed by hand methods where necessary to avoid injury to trees and roots. Roots 2 inches in diameter and larger shall be protected with heavy burlap. Roots smaller than 2 inches in diameter adjacent to trees shall be hand trimmed. Cuts through roots 1/2 inch in diameter and larger shall be sealed with tree trimmers' asphaltic emulsion. If trenches remain open more than 24 hours, the side of the trench adjacent to the tree shall be shaded with burlap and kept damp. Materials shall not be stockpiled within the drip line of trees.

Dewatering: Excavations shall be kept clear of standing water. Water shall be removed by pumping if necessary. Water removed from excavation shall be carried away from the building site and disposed of in a manner that will not harm State or adjacent property.

**STRUCTURE BACKFILLING**

Unless otherwise noted, all backfill for building work shall be classified as structure backfill. Backfill shall be placed and compacted in horizontal layers, not more than 6 inches thick prior to compaction, and to the lines and grades shown on the plans or to original ground.

Structure Backfill: After structures are in place and forms are removed, wood and other debris shall be removed from excavations before placing structure backfill.

Backfilling Pipes and Conduits:

Backfill placed under pipe and conduits shall be compacted sand, 4 inches minimum depth. Backfill material placed to a level 6 inches above tops of pipes and conduits shall be sand or fine earth and particles shall not exceed 1/2 inch in greatest dimension. For wrapped, coated, or plastic pipe or conduits, sand shall be used for backfill. Backfill material placed higher than 6 inches above tops of pipes or conduits shall consist of material free of stones or lumps exceeding 4 inches in greatest dimension except:

1. The top 12 inches of backfill under roads, walks or paving shall consist of aggregate base material.
2. The top 6 inches of backfill in planted areas shall consist of topsoil.

Unless otherwise shown on the plans, pipe under roads, with less than 2½ feet of cover over the top of pipe, shall be backfilled with concrete to a level 4 inches above the top of pipe. Concrete for backfill shall be commercial quality concrete containing not less than 564 pounds of cement per cubic yard.

**COMPACTION**

Relative compaction shall be determined in accordance with California Test 216 or 231.

Unless otherwise noted below, all backfill shall be compacted to a minimum relative compaction of 90 percent.

Unless approved in writing by the Engineer, compaction by jetting or ponding will not be permitted.

Compact Original Ground: Original ground surface under fill with surfacing of concrete and asphalt concrete shall be compacted to a relative compaction of not less than 95 percent for a minimum depth of 6 inches.

Subgrade Preparation:

Preparation of subgrade material for placing aggregate base, surfacing, or slabs thereon shall include fine grading, compaction, reworking as necessary. The upper 6 inches of the subgrade shall have the same compaction as the fill to be placed over it.

The prism of backfill directly underneath the building foundation and sloping downward at 1:1 shall be compacted to 95 percent.

Structure Backfill: Structure backfill shall be compacted to not less than 95 percent relative compaction.

Trench Backfill: Trench backfill placed beneath slabs or paved areas shall be compacted to a relative compaction of not less than 95 percent.

**DISPOSAL**

Surplus Material: Surplus material from the excavation shall be disposed of at the site of the work as directed by the Engineer.

**FIELD QUALITY CONTROL**

Inspection: When the excavation is substantially completed to grade, the Contractor shall notify the Engineer. No concrete shall be placed until the foundation has been approved by the Engineer.

Testing: The State will conduct compaction tests during the backfilling and compacting operations.

## 12-2.05 AGGREGATE BASE

## PART 1 - GENERAL

**SUMMARY**

Scope: This work shall consist of furnishing, spreading and compacting aggregate base in accordance with the details shown on the plans and these special provisions.

## PART 2 - PRODUCTS

Aggregate base:

Aggregate base shall be commercial quality aggregates consisting of broken stone; crushed gravel; natural, clean, rough-surfaced gravel and sand; or a combination thereof.

Aggregate base shall conform to the following grading as determined by California Test 202:

| Sieve or Screen Size | Percentage Passing |
|---|---|
| 1" | 100 |
| 3/4" | 90 - 100 |
| No. 4 | 35 - 60 |
| No. 30 | 10 - 30 |
| No. 200 | 2 - 9 |

Aggregate base shall also conform to the following quality requirements:

| Tests | California Test No. | Test Requirements |
|---|---|---|
| Durability Index | 229 | 35 Min. |
| Resistance (R-Value) | 301 | 78 Min. |
| Sand Equivalent | 217 | 22 Min. |

**PART 3 - EXECUTION**

**SPREADING AND COMPACTING**

Spreading:

Aggregate base shall be placed and compacted to the lines and grades shown on the plans.

Spreading and compacting shall be performed by methods that will produce a uniform base, free from pockets of coarse or fine material.

Compaction: Relative compaction of each layer of compacted base material shall be not less than 95 percent, as determined by California Test 216 or 231.

**12-2.06 FREE DRAINING GRANULAR MATERIAL**

**PART 1 - GENERAL**

**SUMMARY**

Scope: This work shall consist of furnishing and placing free draining granular material beneath slabs in accordance with the details shown on the plans and these special provisions.

**PART 2 - PRODUCTS**

Free Draining Franular Material: Free draining granular material shall be clean, hard, durable, free-draining rock. The material gradation shall be such that all passes the one-inch screen, and not more than 10 percent passes the No. 4 sieve as determined by California Test 202. Granular material shall be free from organic material, clay balls or other deleterious substances.

**PART 3 - EXECUTION**

**SPREADING AND CONSOLIDATING**

Free draining granular material shall be placed, spread, and consolidated by tamping or vibrating.

**12-2.07 TERMITE CONTROL**

**PART 1 - GENERAL**

**SUMMARY**

Scope: This work shall consist of furnishing and applying soil treatment for termite control in accordance with these special provisions.

## SUBMITTALS

Product Data: Product labels for the soil treatment material showing descriptive information on the active chemical ingredients, mixing instructions for concentration levels, directions for use, application rates, and precautionary information shall be submitted for approval. Labels shall include an EPA product registration number.

## QUALITY ASSURANCE

Codes and Standards:

Attention is directed to Section 7-1.01H, "Use of Pesticides," of the Standard Specifications.

Soil treatment operations for control of termites shall be performed by a pest control operator who is licensed by the State of California.

Insecticides used in termite control work shall be approved and registered by the United States Environmental Protection Agency (EPA) and the State of California.

## DELIVERY, HANDLING AND STORAGE

The storage, mixing and application of chemicals; the cleaning of equipment; and the disposal of product containers shall be in accordance with federal, state and local regulations.

# PART 2 - PRODUCTS

Soil Treatment Material:

Soil treatment materials for termite control shall be commercial quality and shall be water emulsifiable.

The active chemical ingredient of the termiticide shall be any EPA approved chemical or combinations of chemicals intended for the eradication and control of subterranean termites.

All product containers shall bear the manufacturer's EPA approved label with EPA registration number.

# PART 3 - EXECUTION

## PREPARATION

The Engineer shall be notified not less than 3 working days in advance of the planned termite control work. Similar notice shall be given to any state or local agency which requires that their representative be present during the termite control work.

Soil Preparation:

Excavation, embankment construction, backfilling and grading operations shall be completed prior to the application of the soil treatment solution. Deleterious matter that will decrease the effectiveness of the treatment shall be removed from all areas to be treated.

Soil to be treated, except under slabs and foundations and vertical surfaces of trenches, shall be cultivated a minimum of 2 inches in depth, and shall be graded as shown on the plans.

Termite control work shall be performed in the presence of the Engineer unless the Contractor has received written approval from the Engineer to proceed.

**MIXING**

The soil treatment emulsion shall be mixed in accordance with the manufacturer's instructions to achieve the chemical concentration level shown on the EPA approved product label for the type of soil and the area to be treated.

**APPLICATION**

The soil treatment emulsion shall be applied to all soil within the area of the building including floor slab areas, under foundations and footings, to the horizontal and vertical surfaces of excavations and to such other areas or surfaces, not mentioned, but which are required for the complete and total protection of the building. The application shall be in accordance with the instructions shown on the EPA approved product label.

Where free draining material has previously been placed, sufficient amount of dilution shall be added to reach the soil beneath the free draining material.

Treated areas that are subsequently excavated, graded, trenched or filled shall be given an additional application.

**PROTECTION**

Treated areas shall be protected in accordance with the instructions shown on the EPA approved product label until the treated surface is covered by subsequent construction.

If concrete slab cannot be placed over the soil the same day it has been treated, a vapor barrier shall be placed over the treated area to prevent disturbance of the treated soil.

## SECTION 12-3. CONCRETE AND REINFORCEMENT

### 12-3.01 CAST-IN-PLACE CONCRETE

### PART 1 - GENERAL

**SUMMARY**

Scope: This work shall consist of constructing cast-in-place concrete facilities in accordance with the details shown on the plans and these special provisions.

Whenever the 28-day compressive strength shown on the plans is 3,500 psi or greater, the concrete shall be considered to be designated by compressive strength. The 28-day compressive strengths shown on the plans which are less than 3,500 psi , are shown for design information and are not to be considered a requirement for acceptance of the concrete.

Related Work: Compressive strength concrete shall conform to the requirements in Section 90-9, "Compressive Strength," of the Standard Specifications.

**SUBMITTALS**

Product Data:

Manufacturer's descriptive data for admixtures, expansion joint material, vapor barrier, hardener, and sealer shall be submitted for approval.

Descriptive data shall be delivered to the Engineer at the jobsite.

## QUALITY ASSURANCE

Certificates of Compliance:

Certificates of Compliance shall be furnished for cement, reinforcement, epoxy products, and admixtures in accordance with the requirements specified in Section 6-1.07, "Certificates of Compliance," of the Standard Specifications.

# PART 2 - PRODUCTS

## CONCRETE MIXES

Concrete (Structural Work):

Commercial quality concrete shall be proportioned to provide a workable mix suitable for the intended use; shall have not less than 564 pounds of cement per cubic yard; 0 to 2-inch penetration, inclusive, as determined by California Test 533.

Concrete (Minor Work):

Commercial quality concrete for concrete curbs, sidewalks, driveways, gutter depressions, new door openings, and collars shall be proportioned to provide a workable mix suitable for the intended use; shall have not less than 470 pounds of cement per cubic yard; 0 to 2-inch penetration, inclusive, as determined by California Test 533.

## CONCRETE MATERIALS

Cement: Cement shall conform to ASTM Designation: C 150, Types II, or III portland cement; or Type IP (MS) Modified cement. Type IP (MS) Modified shall conform to ASTM Designation: C 595 and shall be comprised of an intimate mixture of Type II Modified cement and not more than 20 percent of a pozzolanic material.

Aggregates:

Aggregates shall be free from deleterious coatings, clay balls and other extraneous materials.

Admixtures: Admixtures used in portland cement concrete shall be included on the Department's current list of approved admixtures, and shall conform to ASTM Designation: C 494, Types A, B, D, F or G for chemical admixtures; ASTM Designation: C 260 for air-entraining admixtures; and ASTM Designation: C 618 for mineral admixtures, except loss on ignition shall not exceed 4 percent. Properties of admixtures shall be uniform in each lot.

Coloring for Concrete: Coloring for portland cement concrete shall be chemically inert, fade resistant mineral oxide or synthetic type.

## FORM MATERIALS

Forms for Exposed Finish Concrete:

Forms for exposed surfaces shall be plywood, metal or other panel type materials. Plywood shall be not less than 5/8 inch thick and without scars, dents, and delaminations. Forms shall be furnished in largest practical pieces to minimize number of joints.

Plywood shall conform to the requirements of U. S. Product Standard PS-1 for Exterior B-B (Concrete Form) Class I.

Forms for edges of slabs shall be nominal 2-inch solid stock lumber, plywood, or metal forms.

Forms for Unexposed Finish Concrete: Forms for unexposed finish concrete surfaces shall be plywood, lumber, metal or other acceptable material.

Forms for Cylindrical Columns or Supports: Forms for cylindrical columns shall be metal, fiberglass reinforced plastic, paper or fiber tubes. Paper or fiber tubes shall be constructed of laminated plies using water-resistant adhesive with wax-impregnated exterior for protection against weather or moisture.

Form Ties: Form ties shall be factory fabricated, removable or snapoff metal ties for use as necessary to prevent spreading of forms during concrete placement.

Form Oil: Form oil shall be commercial quality form oil which will permit the ready release of the forms and will not discolor the concrete.

**REINFORCING MATERIALS**

Bar Reinforcement: Bar reinforcement shall conform to ASTM Designation: A 615/A 615M, Grade 60 [420], or ASTM Designation: A 706/A 706M.

Welded Wire Fabric: Welded wire fabric shall conform to ASTM Designation: A 185.

Bar Supports: Bar supports for reinforcement shall be precast mortar blocks or ferrous metal chairs, spacers, metal hangers, supporting wires, and other approved devices of sufficient strength to resist crushing under applied loads.

**EPOXY**

Epoxy shall be furnished as 2 components which shall be mixed together at the site of the work.

Epoxy Resin Adhesive: Epoxy resin adhesive shall conform to State of California Specification No. 8040-21M-08 or other epoxy suitable for bonding new concrete to old.

Epoxy Mortars: Epoxy mortar and epoxy mortar surface treatment shall consist of a commercial quality, trowelable mixture consisting of epoxy and sand. Epoxy shall have a pull-off strength of not less than 1,000 psi and a 90-percent cure in 24 hours. Epoxy shall be of the type that requires no primer as a bonding agent.

Sand:

Sand for use in epoxy mortars shall be clean and shall have a moisture content of not more than 0.50-percent when tested in accordance with California Test 226.

Sand for epoxy mortar surface treatment shall be graded such that 100-percent passes the No. 100 sieve.

**RELATED MATERIALS**

Anchor Bolts, Nuts, and Washers:

Nonheaded anchor bolts shall conform to ASTM Designation: A 36/A 36M, with a minimum hook length of 6.2 diameters.

Headed anchor bolts shall conform to ASTM Designation: A 307.

Threaded rods shall conform to ASTM Designation: A 572.

Nuts shall conform to ASTM Designation: A 563, Grade A.

Washers for anchor bolts shall be commercial quality.

Exposed anchor bolts, nuts, and washers shall be hot dipped galvanized.

Expansion Joint Material: Expansion joint material shall be commercial quality asphalt impregnated pressed fiber sheets, ½-inch thickness at pedestrian walk ramps.

Vapor Barrier: Vapor barrier shall be commercial quality polyethylene sheets not less than 6 mils thick.

Bond Breaker: Bond breaker shall be Type I asphalt saturated organic felt or such other material approved by the Engineer.

Nonskid Abrasive Aggregate: Nonskid abrasive aggregate shall be commercial quality aluminum oxide, silicon carbide, or almandite garnet grit particles; screen size 12-30 or 14-36.

Type A Control Joints: Type A control joints shall be commercial quality, preformed, T-shaped plastic strips with detachable top flange.

Keyed Construction Joint Forms: Keyed construction joint forms shall be commercial quality, galvanized metal or plastic, factory fabricated construction joint forms. Forms shall produce a rabbeted key type joint.

Divider and Edger Strips: Divider and edger strips shall be foundation grade redwood.

Mortar: Mortar shall consist of one part cement to 2 parts clean sand and only enough water to permit placing and packing.

Curing Compound: Curing compound shall be a non-pigmented curing compound with fugitive dye conforming to the requirements of ASTM Designation: C 309, Type 1-D, Class A.

Concrete Hardener: Concrete hardener shall be commercial quality water borne penetrating type magnesium fluosilicate, zinc fluosilicate or combination thereof.

Splash Block: Splash blocks shall be precast concrete splash blocks with depressed runoff trough. Splash blocks shall be 12" x 24" x 3½" in size unless otherwise shown on the plans.

**ADMIXTURES**

Admixtures shall be used when specified or ordered by the Engineer and may be used at the Contractor's option to conserve cement or to facilitate any construction operation.

Calcium chloride shall not be used in any concrete.

Admixtures shall be combined with concrete materials by methods that produce uniform properties throughout the concrete.

If more than one admixture is used, said admixtures shall be compatible with each other so that the desirable effects of all admixtures will be realized.

Mineral admixtures may be used to replace up to 15 percent of Type II portland cement provided the weight of mineral admixture used is not less than the weight of cement replaced. Mineral admixtures shall not be used to replace Type IP (MS) Modified or Type III cements. Chemical admixtures may be used to reduce up to 5 percent of the portland cement except that the cement content shall not be less than 470 pounds per cubic yard. When both chemical and mineral admixtures are used with Type II cement, the weight of cement replaced by mineral admixture may be considered as cement in determining the resulting cement content.

Mineral admixtures will be required in the manufacture of concrete containing aggregates that are determined to be "deleterious" or "potentially deleterious" when tested in accordance with ASTM Designation: C 289. The use of mineral admixture in such concrete shall conform to the requirements in this section except that the use of set retarding admixtures will not be permitted.

When the use of a chemical admixture is specified or is ordered by the Engineer, the admixture shall be used at the rate specified or ordered. If no rate is specified or ordered, or if the Contractor uses a chemical admixture for his own convenience, the admixture shall be used at the dosage normally recommended by the admixture manufacturer.

When air-entrainment is specified or is ordered by the Engineer, the air-entraining admixture shall be used in amounts to produce concrete having the specified or ordered air content as determined by California Test 504. If the Contractor uses air-entrainment for his own convenience, the average air content shall not exceed 4 percent and no single test shall exceed 5½ percent.

Chemical admixtures and air-entraining admixtures shall be dispensed in liquid form. Dispensers shall have sufficient capacity to measure at one time the total quantity required for each batch. If more than one liquid admixture is used in the concrete, a separate measuring unit shall be provided for each liquid admixture and dispensing shall be such that the admixtures are not mixed at high concentrations. When air-entraining admixtures are used with other liquid admixtures, the air-entraining admixtures shall be the first to be incorporated into the mix. Unless liquid admixtures are added to premeasured water for the batch, they shall be discharged to flow into the stream of water so that the admixtures are well dispersed throughout the batch.

**BAR REINFORCING STEEL**

Bending:

Reinforcing steel bars shall accurately conform to the dimensions shown on the plans.

Bars shall be bent or straightened in a manner that will not crack or break the material. Bars with kinks or improper bends shall not be used.

Hooks, bends and splices shall conform to the provisions of the Building Code Requirements for Reinforced Concrete of the American Concrete Institute.

**MIXING AND TRANSPORTING CONCRETE**

When a truck mixer or agitator is used for transporting concrete to the delivery point, discharge shall be complete within 1½ hours, or before 250 revolutions of the drum or blades, whichever comes first, after the introduction of cement to the aggregates.

The temperature of mixed concrete, immediately before placing, shall be not less than 50°F nor more than 90°F.

Truck mixers or agitator shall be equipped with electrically or mechanically actuated revolution counters by which the number of revolutions of the drum or blades may readily be verified. The counters shall be of the continuous-registering type, which accurately register the number of revolutions and shall be mounted on the truck so that the Engineer may safely and conveniently inspect them from alongside the truck. Under conditions contributing to quick stiffening of the concrete, or when the temperature of the concrete is 86°F or above, a time less than 1½ hours may be required.

When non-agitating hauling equipment is used for transporting concrete to the delivery point, discharge shall be complete within one hour after the introduction of cement to the aggregates. Under conditions contributing to quick stiffening of the concrete, or when the temperature of the concrete is 86°F, or above, the time between the introduction of cement to the aggregates and discharge shall not exceed 45 minutes.

Each load of concrete for the work shall be accompanied by a trip ticket, a copy of which shall be delivered to the Engineer at the jobsite. The trip ticket shall show volume of concrete, weight of cement and aggregates, quantity of each admixture, quantity of water including water added at the jobsite, time of day the concrete is batched, and revolution counter readings on transit mix trucks at the times the truck is charged and unloaded.

## PART 3 - EXECUTION

### PREPARATION

Existing Concrete Construction:

Where fresh concrete joins existing or previously placed concrete or masonry, the contact surfaces of the existing or previously placed material shall be roughened, cleaned, flushed with water and allowed to dry to a surface dry condition immediately prior to placing the fresh concrete. The roughened surface shall be no smoother than a wood trowelled surface. Cleaning of the contact surfaces shall remove laitance, curing compounds, debris, dirt and such other substances or materials which would prevent bonding of the fresh concrete.

Abrasive blast methods shall be used to clean horizontal construction joints to the extent that clean aggregate is exposed.

Exposed reinforcing steel located at the contact surfaces which is to be encased in the fresh concrete shall be cleaned to remove any substance or material that would prevent bonding of the fresh concrete.

Forms:

Forms shall be mortar tight, true to the dimensions, lines, and grades shown on the plans, securely fastened and supported, and of adequate rigidity to prevent distortion during placing of concrete.

Forms for exposed surfaces shall be constructed with triangular fillets not less than 3/4" x 3/4" attached so as to prevent mortar runs and to produce smooth straight chamfers at all sharp edges of the concrete.

Form fasteners shall be removable without chipping, spalling, heating or otherwise damaging the concrete surface. Form ties shall be removed to a depth of at least one inch below the surface of the concrete.

The inside surfaces of forms shall be cleaned of all dirt, mortar and foreign material. Forms shall be thoroughly coated with form oil prior to use.

Forms shall not be stripped until at least 40 hours after placing concrete, except soffit forms and supports shall not be released or removed until at least 10 days after placing concrete.

Anchorages and embedded items shall be placed and rigidly secured at their planned locations prior to placing concrete.

Reglets or embedded flashing shall be installed on concrete forms before the concrete is placed.

Redwood dividers shall have 16d galvanized nails partially driven into both vertical faces at 18 inches on center.

Vapor Barrier:

Vapor barrier shall be lapped 6 inches and securely taped at splices. Vapor barrier shall be protected with a 3-inch layer of clean uncompacted sand cover.

Unless otherwise shown on the plans, vapor barrier shall be placed under portions of the floor slab scheduled to receive finish flooring.

Placing Reinforcing Steel:

Reinforcing steel bars shall be accurately placed to the dimensions shown on the plans.

Bar reinforcement conforming to ASTM Designation: A 615/A 615M, Grade 60 [420], or A 706/A 706M shall be lapped at least 45 diameters.

Bars shall be firmly and securely held in position by means of wiring and approved bar supports. The spacing of supports and ties shall prevent displacement of the reinforcing or crushing of supports.

Tie wire shall be clear of concrete formwork and concrete surfaces.

All reinforcing steel shall be in place and inspected before concrete placement begins. Placing of bars on fresh layers of concrete will not be permitted.

Ground Bar: A continuous reinforcing steel bar shall be installed in the building foundation at the location indicated on the plans for the electrical ground bar. The use of epoxy coated reinforcing bar is not permitted. The end of the ground bar shall extend beyond the concrete surface and shall be protected from damage by construction operations.

**PLACING CONCRETE**

Concrete shall be placed and consolidated by means of internal vibrators to form dense, homogeneous concrete free of voids and rock pockets.

Forms and subgrade shall be thoroughly moistened with water immediately before placing concrete.

Concrete shall be placed as nearly as possible to its final location and the use of vibrators for extensive shifting of the concrete will not be permitted.

Concrete shall be deposited and consolidated in a continuous operation within limits of construction joints, until the placing of the panel or section is completed.

When concrete is to be placed in large areas requiring more than two pours, concrete shall be placed in alternate long strips between construction joints and the final slab infilled.

Vibrators used to consolidate concrete containing epoxy-coated bar reinforcement shall have a resilient covering to prevent damage to such reinforcement.

**FINISHING CONCRETE SURFACES**

Finishing Unformed Surfaces:

Slabs shall be placed full thickness to finish elevation and leveled to screeds by use of long straightedges. The screeds shall be set to grade at approximately 6-foot centers. After leveling, screeds shall be removed and the surface shall be floated with wooden floats.

Type A control joint strips shall be inserted into the floated concrete so that the bottom of the top flange is flush with the finish elevation. Strips shall be standard manufactured lengths and shall be placed on an approximate straight line. The top flange of the strips shall be removed after the concrete has set and cured.

The floated surface shall be trowelled with steel trowels. Troweling shall form a dense, smooth and true finish. Walkways, pedestrian ramps, stairs and outdoor slabs for pedestrian traffic shall be given a non-slip broom finish unless a different finish is called for on the plans or in these special provisions.

The application of cement dust coat will not be permitted.

Steel trowel finish and broom finish will not be required for slabs to receive exposed aggregate finish nor for slabs to be covered with ceramic tile.

Concrete floor surfaces to receive ceramic tile shall be floated to grade and then, before final set of the concrete, the floated surfaces shall be roughened with stiff bristled brushes or rakes.

Finished surfaces of floor slabs shall not deviate more than 1/8 inch from the lower edge of a 10-foot long straight edge.

Finishing Formed Surfaces:

Formed concrete surfaces shall be finished by filling holes or depressions in the surface, repairing all rock pockets, and removing fins. All surfaces of formed concrete exposed to view shall have stains and discolorations removed, unsightly bulges removed, and all areas which do not exhibit the required smooth, even surface of uniform texture and appearance shall be sanded with power sanders or other approved abrasive means until smooth, even surfaces of uniform texture and appearance are obtained.

Cement mortar, patching and finishing materials used to finish exposed surfaces of concrete shall closely match the color of surrounding surfaces.

Nonskid Abrasive Aggregate Finish: Where shown on the plans, walkways shall receive a nonskid abrasive aggregate (grit) finish. The grit shall be applied uniformly at the rate of not less than 0.3 pound per square foot and tamped into the floated concrete surface while the concrete is plastic. The grit shall be buried about 0.7 diameter of each particle into the concrete.

**CURING CONCRETE**

Freshly placed concrete shall be protected from premature drying and excessive cold or hot temperatures.

Initial curing of floor slabs shall start as soon as free water has disappeared from the concrete surface. The concrete shall be kept continuously wet by application of water for not less than 7 days after the concrete has been placed.

Cotton mats, rugs, carpets, or sand blankets may be used as a curing medium to retain the moisture during the curing period. Curing materials that will stain or discolor concrete shall not be used on surfaces exposed to view.

Prior to placing the curing medium, the entire surface of the concrete shall be kept damp by applying water with a nozzle that so atomizes the flow that a mist and not a spray is formed, until the surface of the concrete is covered with the curing medium. At the expiration of the curing period, the concrete surfaces shall be cleared of all curing mediums.

Concrete surfaces, other than floor slabs, shall be kept moist for a period of at least 5 days by leaving the forms in place or by covering the exposed surfaces using moist rugs, cotton mats or other curing materials approved by the Engineer.

Concrete curbs, sidewalks, collars, and gutter depressions may be cured with a curing compound.

**PROTECTING CONCRETE**

Concrete shall not be placed on frozen or frost covered surfaces.

Concrete shall be protected from damage due to rain, freezing or inclement weather, and shall be maintained at a temperature of not less than 40°F for 72 hours. When required by the Engineer, the Contractor shall provide a written outline of his proposed methods of protecting concrete.

Vehicles, equipment, or concentrated loads weighing more than 300 pounds individually and material stockpiles weighing more than 50 pounds per square foot will not be permitted on the concrete within 10 calendar days after placing.

**SPECIAL TREATMENTS**

Concrete Hardener:

Chemical concrete hardener shall be applied to the floor surfaces shown on the plans, prior to the application of concrete sealer. Surfaces shall be clean and dry before the application of hardener.

The solution shall be applied in accordance with the manufacturer's instructions.

After the hardener has dried, the surface shall be mopped with water to remove encrusted salts.

Concrete Sealer: Concrete sealer shall be applied to the concrete surfaces designated on the plans in accordance with the manufacturer's instructions for heavy duty use. The sealer shall be applied to dry concrete surfaces.

Epoxy Resin Adhesive: Epoxy resin adhesive shall be applied to concrete surfaces shown on the plans. Epoxy resin adhesive shall be mixed and applied in accordance with the manufacturer's recommendations.

Epoxy Mortars:

Epoxy for use as a binder in epoxy mortars shall be thoroughly mixed together before the aggregate is added, and unless otherwise specified, the mix proportions shall consist of one part binder to approximately 4 parts of aggregate, by volume.

All surfaces against which epoxy mortars are to be applied shall be free of rust, paint, grease, asphalt, and loose or deleterious material.

## SECTION 12-4. MASONRY

### 12-4.01 CONCRETE MASONRY UNITS

### PART 1 - GENERAL

#### SUMMARY

Scope: This work shall consist of constructing reinforced hollow concrete masonry units in accordance with the details shown on the plans and these special provisions.

Related Work:

Water repellent coating shall be applied in accordance with the requirements specified under "Water Repellent Coating" in Section 12-7, "Thermal and Moisture Protection," of these special provisions.

Prefaced masonry units shall conform to the requirements specified under "Prefaced Masonry Units," elsewhere in this Section 12-4.

#### PERFORMANCE REQUIREMENTS

Unit Strength: Provide masonry units that develop the following installed compressive strengths (f'm) at 28 days:

Based on net area f'm = 1,500 psi

#### SUBMITTALS

Product Data: Manufacturer’s descriptive data for each type of masonry unit, accessory, and other manufactured products shall be submitted for approval.

Samples: Two samples of masonry units of each color and architectural finish shall be submitted for approval.

#### QUALITY ASSURANCE

Single Source Responsibility:

Exposed masonry units of uniform color and texture shall be obtained from one manufacturer for each different product required for each continuous surface or visually related surfaces.

Mortar ingredients of uniform quality, including color for exposed masonry, shall be obtained from one manufacturer for each cementitious component and from one source and producer for each aggregate.

Certificates of Compliance: Certificate of Compliance shall be furnished for masonry units, aggregate for grout and transit mixed grout in accordance with the requirements specified in Section 6-1.07, "Certificates of Compliance," of the Standard Specifications.

**DELIVERY, HANDLING AND STORAGE**

Delivery: Masonry materials shall be delivered to the project in an undamaged condition.

Storage and Handling: Masonry units shall be stored and handled in order to prevent deterioration or damage due to moisture, temperature changes, contamination, corrosion or other causes.

## PART 2 - PRODUCTS

**CONCRETE MASONRY UNITS**

Concrete Masonry Units:

Concrete masonry units shall be nominal size, color and architectural finish as shown on plans; hollow load bearing, light weight or medium weight, Grade N, Type II, conforming to ASTM Designation: C 90; standard or open ended masonry units.

Special shapes shall be provided where required for lintels, corners, jambs, sash, control joints, headers, bonding and other special conditions.

**MORTAR AND GROUT MATERIALS**

Cement:

Cement for mortar shall be Type II, low alkali portland cement conforming to ASTM Designation: C 150; or masonry cement conforming to ASTM Designation: C 91.

Cement for grout shall be Type II portland cement conforming to ASTM Designation: C 150 with maximum 15 percent Class N, F, or C mineral admixture conforming to ASTM Designation: C 618 except that the loss on ignition shall not exceed 4 percent; or Type IP(MS) blended hydraulic cement conforming to ASTM Designation: C 595.

Aggregate:

Aggregate for mortar shall conform to ASTM Designation: C 144, except not more than 10 percent shall pass the No. 100 sieve.

Aggregate for grout shall conform to ASTM Designation: C 404, except 100 percent of the coarse aggregate shall pass the 3/8-inch sieve. Soundness loss shall not exceed 10 percent as determined by California Test 214.

Coloring for Mortar: Coloring for mortar shall be chemically inert, fade resistant mineral oxide or synthetic type.

Lime: Lime shall conform to ASTM Designation: C 207, Type S.

Premixed Mortar or Grout: A premixed packaged blend of cement, lime, and sand, with or without color, that requires only water to prepare for use as masonry mortar or grout may be furnished. Packages of premix shall bear the manufacturer's name, brand, contents, weight, and color identification.

Transit Mixed Grout: Transit mixed grout shall conform to ASTM Designation: C 94, except aggregate shall be as specified herein for aggregate for grout. The minimum compressive strength shall be 2,500 psi at 28 days when tested

in accordance with ASTM Designation: C 39. Admixtures, if used, shall conform to ASTM Designation: C 494, Types A, E or F and shall not contain chlorides.

**REINFORCEMENT, TIES AND ANCHORING DEVICES**

Bar Reinforcement: Bar reinforcement shall conform to ASTM Designation: A 615/A 615 M, Grade 60, or ASTM Designation: A 706/A 706 M.

Anchor Bolts: Anchor bolts shall conform to ASTM Designation: A 36/A 6M with a minimum hook length of 6.2 diameters, and shall be 1/2-inch diameter unless otherwise shown on the plans.

Anchors, Ties, Angles, and Metal Lath: Anchors, ties, angles, and metal lath shall be commercial quality, and shall be galvanized.

Dry Pack: Dry pack to set items into masonry shall be one part portland cement to not over 3 parts of clean sand and with a minimum amount of water for hydration and packing.

**PROPORTIONING MORTAR AND GROUT**

Mortar shall be proportioned by loose volume and shall have one part cement, one quarter part of hydrated lime and 2¼ to 3 parts aggregate. Mortar shall be tinted with coloring to match the masonry units.

Grout, except transit mixed and packaged premix grout, shall be proportioned by loose volume and shall have one part cement, not more than 1/10 part hydrated lime, 2¼ to 3 parts sand aggregate, and not more than 2 parts gravel aggregate.

Aggregate shall be measured in a damp loose condition.

Grout shall be mixed with sufficient water to produce a mix consistency suitable for pumping without segregation. Slump shall not exceed 9 inches.

**PART 3 - EXECUTION**

**CONSTRUCTION**

Masonry units shall be laid in running bond, except as otherwise shown on the plans.

Surfaces of metal, glass, wood, completed masonry, and other such materials exposed to view shall be protected from spillage, splatters and other deposits of cementitious materials from masonry construction. All such deposits shall be removed without damage to the materials or exposed surfaces.

Construction will comply with Section 2104, “Construction,” of the CBC. Tolerances specified in Section 2104 shall be in affect unless otherwise shown on the plans.

Where fresh masonry joins concrete or masonry, the contact surfaces of existing material shall be roughened, cleaned and lightly wetted. The roughened surface shall be no smoother than a wood troweled surface. Cleaning shall remove laitance, curing compounds, debris, dirt and any substance which decreases bond to the fresh masonry.

Masonry shall not be erected when the ambient air temperature is below 40°F.

Surfaces of masonry erected when the ambient air temperature exceeds 100°F. shall be kept moist with water for a period of not less than 24 hours. Water shall be uniformly applied with a fog spray at the intervals required to keep the surfaces moist but not to exceed 3 hours unless otherwise approved by the Engineer.

All anchors, bolts, dowels, reglets and other miscellaneous items to be cast into the wall, shall be firmly secured in place before grout is poured.

Shoring for concrete masonry lintels shall remain in place a minimum of 15 days after the wall has been completed.

Laying Masonry Units:

Concrete masonry units shall be laid dry.

During laying of units all cells shall be kept dry in inclement weather by suitably covering incomplete walls. Wooden boards and planks shall not be used as covering materials. The covering shall extend down each side of masonry walls approximately 2 feet.

Chases shall be kept free from debris and mortar.

Bond beam units with an opening at each cross web shall be used at all horizontal reinforcing bars.

Where masonry unit cutting is necessary, all cuts shall be made with a masonry saw to neat and true lines. Blocks with excessive cracking or chipping of the finished surfaces exposed to view will not be acceptable.

Lintels: Masonry lintels shall be as shown on the plans. Lintels shall be formed using U-shaped lintel units with reinforcing bars placed as shown on the plans. Formed-in-place lintels shall be temporarily supported.

Bar Reinforcement:

Bar reinforcement shall be accurately positioned in the center of the cell and securely held in position with either wire ties or spacing devices near the ends of bars and at intervals not exceeding 192 bar diameters. Wire shall be 16-gage or heavier. Wooden, aluminum, or plastic spacing devices shall not be used. Tolerances for the placement of vertical reinforcement in walls and flexural elements shall be ± ½ inch. Tolerance for longitudinal reinforcement in walls shall be ± 2 inches.

The minimum spacing for splices in vertical reinforcement for masonry walls shall be 4 feet plus lap.

Bar reinforcement shall not be placed in the plane of mortar joints.

Mortar:

Mortar joints shall be approximately 3/8 inch wide. Units shall be laid with all head and bed joints filled solidly with mortar for the full width of masonry unit shell. Head joints shall be shoved tight. Exposed joints shall be concave, tooled smooth, unless otherwise shown on the plans.

Mortar that has been mixed more than one hour shall not be retempered.

Mortar placed in joints shall preserve the unobstructed vertical continuity of the concrete filling. Any overhanging mortar projecting more than ½ inch, or other obstruction or debris shall be removed from the inside of such cells.

**GROUTING**

All cells shall be filled solidly with grout. All grout in the cells shall be consolidated at the time of placement by vibrating and reconsolidated after excess moisture has been absorbed but before plasticity is lost. Slicing with a trowel is not acceptable.

Masonry units may be placed full height of the masonry work before grouting, or they may be placed in increments for individual grout pours.

Cleanouts shall be provided for all grout pours over 5 feet in height. Such cleanouts shall be provided in the bottom course at every cell containing vertical reinforcement. After cell inspection, the cleanouts shall be sealed before filling with grout.

Masonry units shall be placed full height of the grout pour. Grout shall be placed in a continuous pour in grout lifts not exceeding 6 feet. The interruption between placing successive lifts of grout shall be not more than one hour.

Between grout pours, a horizontal construction joint shall be formed by stopping the grout a minimum of 1½ inches below the top of the last course, except if the joint is at a bond beam, it shall be ½ inch below the top of the bond beam unit, or at the top of the wall.

**CLEANING AND PROTECTING MASONRY**

Splashes, stains or spots on the faces of the masonry exposed to view shall be removed.

Completed masonry shall be protected from freezing for a period of at least 5 days.

In addition:

Mortar shall be tested in accordance with UBC Standard: 21-16.

Any work not meeting the requirements of section 2105 shall be redone and retested. Sampling, inspecting, reworking and retesting of material will be done at the contractor's expense.

## SECTION 12-5. METALS

### 12-5.01 STRUCTURAL STEEL FOR BUILDINGS

### PART 1 - GENERAL

**SUMMARY**

Scope: This work shall consist of fabricating, assembling, furnishing and erecting structural steel in accordance with the details shown on the plans and these special provisions.

Structural steel consists of:

HSS Tubes
Base Plates

Source Quality Control: Materials and fabrication procedures are subject to inspection and tests in mill, shop and field, conducted by the Engineer or a qualified inspection agency. The Contractor or fabricator shall provide access to the Engineer or testing agency to places where the structural steel work is being fabricated or produced so that the required inspection and testing can be accomplished. Such inspections and tests will not relieve the Contractor of responsibility for providing materials and fabrication procedures in compliance with specified requirements. The testing agency may inspect the structural steel at the plant before shipment; however, the Engineer reserves the right, at any time before final acceptance to reject the material that does not conform to the contract requirements.

**REFERENCES**

Structural steel shall be fabricated, assembled and erected in accordance with American Institute of Steel Construction (AISC), "Specifications for the Design, Fabrication and Erection of Structural Steel for Buildings."

Welding shall be in accordance with American Welding Society (AWS) D1.1, "Structural Welding Code - Steel."

**SUBMITTALS**

Product Data: Product data for items to be incorporated into the work, including structural steel, high strength bolts, nuts and washers and alternative connectors, shall be submitted for approval.

Working Drawings:

Working drawings and calculations shall be submitted for approval.

Working drawings shall show any changes proposed in the work, details of connections and joints exposed to the weather, details for connections not dimensioned on the plans, the sequence of shop and field assembly and erection, welding sequences and procedures. If required, the location of butt welded splices on a layout drawing of the entire structure, and the location and details of any temporary supports that are to be used.

Calculations and working drawings for falsework to be used for the erection of structural steel shall be submitted for approval. The falsework shall be designed and constructed to provide the necessary rigidity and to support loads which will be applied. Working drawings and design calculations shall be stamped and signed by an engineer who is registered as a Civil or Structural Engineer in the State of California. The expiration date of the registration shall be shown.

**CLOSEOUT SUBMITTALS**

Final Drawings:

At the completion of each building on the contract, one set of reduced prints on 60-pound (minimum) bond paper, 11 inches x 17 inches in size, of the corrected original tracings of all approved drawings for each building shall be furnished to the Engineer. An index prepared specifically for the drawings for each building containing sheet numbers and titles shall be included on the first reduced print in the set for each building. Reduced prints for each building shall be arranged in the order of drawing numbers shown in the index.

The edge of the corrected original tracing image shall be clearly visible and visually parallel with the edges of the page. A clear, legible symbol shall be provided on the upper left side of each page to show the amount of reduction and a horizontal and vertical scale shall be provided on each reduced print to facilitate enlargement to original scale.

**QUALITY ASSURANCE**

Qualifications for Welding: A certified copy of qualification test record for welders shall be submitted to the Engineer at the jobsite. Descriptive data for equipment for field welding structural steel, including type and electric power requirements, shall be submitted for approval.

Certificates of Compliance: Certificate of Compliance shall be furnished for structural steel products in accordance with the requirements specified in Section 6-1.07, "Certificates of Compliance," of the Standard Specifications. Certificate of Compliance shall include mill test certificates for each heat number used in the work.

**DELIVERY, HANDLING AND STORAGE**

Structural materials shall be loaded, transported, unloaded and stored so that it is kept clean and undamaged. Material shall be stored above ground on platforms, skids, or other supports. Covers and protection shall be provided to protect the materials from corrosion.

Anchorages and anchor bolts, which are to be embedded in concrete or masonry, shall be delivered in ample time to not delay the work.

## PART 2 - PRODUCTS

**MATERIALS**

Steel Bars, Plates and Shapes: Steel bars, plates and shapes shall conform to ASTM Designation: A 36/A 36M or A 572/A 572M, Grade 50 [345].

Pipe: Pipe shall conform to ASTM Designation: A 53, standard weight, unless otherwise shown on the plans.

Steel Tubing: Steel tubing shall conform to ASTM Designation: A 500, Grade B.

Stud Connectors: Stud connectors shall conform to ASTM Designation: A 108, Grades 1018 through 1020, cold drawn, either semi- or fully killed.

Anchor Bolts, Nuts and Washers:

Nonheaded anchor bolts shall conform to ASTM Designation: A 36/A 36M, with a minimum hook length of 6.2 diameters.

Headed anchor bolts shall conform to ASTM Designation: A 307.

Nuts shall conform to ASTM Designation: A 563, Grade A.

Washers for anchor bolts shall be commercial quality.

Machine Bolts, Nuts and Washers:

Machine bolts and nuts shall conform to ASTM Designation: A 307.

Washers for machine bolts shall be commercial quality.

Inorganic Zinc Primer: Inorganic zinc primer shall be a waterborne inorganic zinc primer conforming to the requirements of AASHTO Designation: M 300-92 I, Type II. Inorganic zinc primer shall be listed on the qualified products list which may be obtained from the Transportation Laboratory, (916) 227-7000.

Mortar: Mortar shall consist of one part cement, measured by volume, to 2 parts clean sand and only enough water to permit placing and packing.

**FABRICATION**

Shop Fabrication and Assembly:

Workmanship and finish shall be equal to the best general practice in modern shops.

Cuts shall not deviate more than 1/16 inch from the intended line. Roughness, notches or gouges shall be removed.

Bearing stiffeners at points of loading shall be square with the web and shall have at least 75 percent of the stiffener in contact with the flanges.

Finished members shall be true to line, shall have square corners and smooth bends and shall be free from twists, kinks, warps, dents and open joints.

Exposed edges and ends of metal shall be dressed smooth, with no sharp edges and with corners slightly rounded.

Stud Connectors: Steel surfaces shall be prepared as recommended by the manufacturer of the stud connectors. Stud connectors shall be welded to the flanges of beams or girders as shown on the plans. Automatic end welding of headed stud connectors shall be in accordance with the manufacturer's instructions.

Connections:

Abutting surfaces at connections shall be clean.

Cutting and welding at the jobsite will not be allowed except as shown on the approved drawings or specifically approved by the Engineer.

Finished holes for bolts shall be cylindrical and perpendicular to the plane of the connection. Subpunched and subdrilled holes shall be ¼ inch smaller in diameter than the diameter specified for the finished hole.

Bolted Connections:

Bolts for connecting steel to steel shall be machine bolts conforming to ASTM Designation: A 307.

Holes for Other Work:

Holes for securing other work to structural steel and passage of other work through steel framing members shall be as shown on the approved drawings.

Threaded nuts or specialty items for securing other work to steel members shall be as shown on the approved drawings.

Holes shall be cut, drilled or punched perpendicular to metal surfaces. Holes shall not be flame cut or enlarged by burning. Holes are to be drilled in bearing plates.

**SHOP PAINTING**

Structural steel members, except those to receive sprayed-fireproofing, shall be painted.

Surface Preparation: Surfaces of structural steel to receive inorganic zinc primer shall be blast cleaned in accordance with Steel Structures Painting Council, SSPC-SP 10, "Near-White Blast Cleaning."

Bolted Connections: Contact surfaces of high strength bolted connections and ungalvanized anchor bolt assemblies shall be blast cleaned and coated with waterborne inorganic zinc primer before assembly. The total thickness of primer on each surface shall be between 1 mil to 3 mils and may be applied in one application.

Painting:

Immediately after surface preparation, surfaces of structural steel shall receive an undercoat of waterborne inorganic zinc primer. Color shall essentially match Federal Standard 595B, No. 36373.

The manufacturer's published mixing and application instructions for inorganic zinc primer shall be followed.

**PART 3 - EXECUTION**

**ERECTION AND ASSEMBLY**

Field Splices:

Field splices shall be made only at the locations shown on approved working drawings.

The parts shall be accurately assembled in their final position as shown on the plans and in true alignment with related and adjoining work before final fastening.

All parts shall be supported adequately and at locations to provide a vibration free, rigid, and secure installation.

Bolted Connections:

All high strength bolted connections shall be made with high strength bolts installed with direct tension indicator washers or tension control fasteners.

When used, one mechanically galvanized direct tension washer shall be installed with each high strength bolt. Bolts shall be tightened until a direct tension indicator washer gap is 0.005 inch or less. A zero gap will not be cause for rejection.

During installation of tension control bolts, the torque required to turn the nut on the tension control bolt shall be counterbalanced by the torsion shear resistance of the splined end of the bolt.

The bolt head type and head location shall be consistent within a joint.

Nuts shall be on side of member least exposed to view.

Setting Bases and Bearing Plates:

Concrete and masonry surfaces shall be cleaned and roughened to improve bond. Bottom of base and bearing plates shall be clean.

Base plates and bearing plates for structural members shall be set on wedges or other adjusting devices.

Anchor bolts shall be wrench tightened after supported members have been positioned and plumbed.

Mortar shall be solidly packed between bearing surfaces and base or bearing plates to ensure that no voids remain. Exposed surfaces shall be finished and allowed to cure.

**FIELD PAINTING**

Touch-up Painting: After erection, the Contractor shall clean field welds, bolted connections, and abraded areas of shop paint and apply the same materials as applied for shop painting.

Surfaces that are scheduled to receive finish coats shall be painted with an additional prime coat and finish coats in accordance with the requirements specified for shop primed steel under "Painting" in Section 12-9.

**QUALITY CONTROL**

Testing and inspection:

Ultrasonic examination shall be performed by the Contractor on at least 50 percent of all full penetration butt-welded splices in accordance with the requirements of AWS D1.1 and these special provisions.

Welding procedures and methods shall be subject to inspection for conformance with AWS D1.1.

Butt welds shall be tested in accordance with AWS D1.1, Chapter 6, Part C, Ultrasonic Testing of Groove Welds.

Examination, reporting and disposition of tests shall be in accordance with the provisions of 6.12, AWS D1.1.

In addition to ultrasonic examinations by the Contractor, welds may be subject to inspection or non-destructive testing by the Engineer.

When additional inspection or non-destructive testing is required by the Engineer, the Contractor shall provide sufficient access facilities in the shop and at the jobsite to permit the Engineer or his agent to perform such inspection and testing.

The Contractor shall correct all deficiencies in the structural steel work which inspections and laboratory test reports have indicated to be not in compliance with these special provisions. Additional tests shall be performed by the Contractor at his expense to reconfirm any non-compliance of original work, and to show compliance of the corrected work.

## 12-5.02 METAL DECK

## PART 1 - GENERAL

### SUMMARY

Scope: This work shall consist of furnishing and installing metal deck in accordance with the details shown on the plans and these special provisions.

Metal deck includes ribbed sheet steel decking units, bent plates, accessories, fasteners and such other components, not mentioned, but required for a rigid, secure and complete installation.

### REFERENCES

The design, fabrication and erection of metal deck shall conform to the applicable requirements of the American Iron and Steel Institute (AISI) publication, "Specifications for the Design of Light Gauge Cold Formed Steel Structural Members," and the applicable Steel Deck Institute Design Manual and these special provisions.

Welding shall be in accordance with American Welding Society (AWS) D1.3, "Structural Welding Code - Sheet Steel."

### SUBMITTALS

Product Data: Manufacturer's descriptive data for each type of deck and accessories shall be submitted for approval.

Working Drawings: Working drawings showing complete erection layouts, details, dimensions, deck section properties shall be submitted for approval. Drawings shall show types and gages, fastening methods, including the location, type and sequence of connections, sump pans, cut openings, surface finishes and temporary supports or bracing.

The metal deck supplier shall submit a fastening schedule and calculations stamped by an engineer who is registered as a Civil or Structural Engineer in the State of California showing that the metal roof panels, clips, and fasteners conform to the span and design loads shown on the plans and the wind uplift requirements of the CBC.

### QUALITY ASSURANCE

Qualification of Field Welding:

Welding processes and welding operators shall be qualified in accordance with "Welder Qualification," procedures in American Welding Society (AWS) D1.1, and D1.3 "Structural Welding Code - Steel."

Welding decking in place is subject to inspection and testing. Defective work shall be removed and replaced with acceptable work.

Certificates of Compliance: Certificates of Compliance shall be furnished for the metal decking in accordance with the requirements specified in Section 6-1.07, "Certificates of Compliance," of the Standard Specifications.

### DELIVERY, HANDLING AND STORAGE

Metal deck units and accessories shall be transported, stored and erected in a manner that will prevent corrosion, distortion or other damage.

Deck units shall be stored off the ground with one end elevated to provide drainage.

## PART 2 - PRODUCTS

Manufacturers: Acceptable manufacturers shall be; Verco Manufacturing Co.; BHP Co.; or equal.

## MATERIALS

Deck Units:

Deck units, closures and plates shall be fabricated from galvanized sheet steel conforming to ASTM Designation: A 653/A 653M, Grade 33 [230].

Galvanizing shall conform to the requirements of ASTM Designation: A 924/A 924M, G60 [Z180].

Miscellaneous Steel Shapes: Miscellaneous steel shapes shall conform to ASTM Designation: A 36/A 36M.

Anchor Clips, Vent Clips, Flashing, Saddle Plates, Flexible Closure Strips and Other Accessories: Anchor clips, vent clips, flashing, saddle plates, flexible closure strips and other accessories shall be as recommended by the decking manufacturer.

## FABRICATION

Deck units shall be formed to span 3 or more supports, with flush, telescoped or nested 2-inch laps at ends and interlocking or nested side laps unless otherwise shown on the plans.

Deck units shall conform to the configurations, metal thickness, depth and width and section properties shown on the plans.

End bearing shall be not less than 1½ inches.

Metal Closure Strips: Metal closure strips for opening between deck units and other construction shall be fabricated from the same gage and material as the adjacent deck units. Strips shall be formed to provide tight-fitting closures at end of cells or flutes and sides of decking.

Roof Sump Pans: Sump pans shall be fabricated from single piece of galvanized sheet steel with level bottoms and sloping sides to direct water flow to drain. Sump pans shall be of adequate size to receive roof drains and with bearing flanges not less than 3 inches wide. Pans shall be recessed not less than 1½ inches below roof deck surface unless otherwise shown or required by deck configuration. Holes for drains shall be cut in the field.

Cleaning: When spray-on fireproofing is specified, the decking manufacturer shall supply decking free of amounts of oil or lubricants which would significantly impair the adhesion of the spray-on fireproofing.

# PART 3 - EXECUTION

## INSTALLATION

Deck units and accessories shall be installed in accordance with the manufacturer's recommendations and approved drawings and these special provisions.

Units shall be placed on supporting steel framework, adjusted in place and properly aligned before being permanently fastened. Ends of units shall have positive bearing over structural supports.

Cutting and fitting shall present a neat and true appearance with exposed burrs removed. Openings through the decking shall be cut square and shall be reinforced as recommended by the decking manufacturer.

The metal deck shall not be used as a working platform before deck units are fastened in place. Supplies, equipment or other loads shall not be stored on the deck. Mechanical equipment or other loads shall not be hung from metal roof decking.

Welding:

Welding shall conform to AWS requirements (D1.1 and D1.3) and procedures for manual shielded metal arc welding, appearance and quality of welds, and methods used in correcting welding work.

Welding washers shall be used where recommended by the manufacturer.

Fastening Roof Deck Units: Roof deck units shall be fastened to supporting steel members as shown on the structural plans.

Fastening Side Laps: Side laps of adjacent deck units shall be fastened as shown on the plans.

Roof Sump Pans: Roof sump pans shall be placed over openings provided in roof and welded to top decking surface. Welds are to be spaced at not more than 12 inches with at least one weld in each corner. Cut opening in sump bottom to accommodate drain size indicated.

Field Painting:

Immediately following erection, field welds, bolted connections and abraded areas shall be cleaned with a wire brush.

Galvanized surfaces shall be touched-up with galvanizing repair paint recommended by the manufacturer.

## 12-5.03 COLD FORMED METAL FRAMING

## PART 1 - GENERAL

### SUMMARY

Scope: This work shall consist of furnishing and installing cold formed metal framing, including load-bearing and non-bearing steel studs, and "C"-shaped steel joists and rafters, in accordance with the details shown on the plans and these special provisions.

### SYSTEM DESCRIPTION

Loadings:

Components shall be sized to withstand the design loads shown on the plans.

Wall system shall be designed to provide for movement of components without damage, failure of joint seals, undue stress on fasteners, or other detrimental effects when subject to seasonal or cyclical day/night temperature range.

Wall system design shall accommodate construction tolerance, deflection of building structural members, and clearances of intended openings.

### REFERENCES

Component Design: Structural properties of studs and joists shall be computed in accordance with American Iron and Steel Institute (AISI), "Specification for Designing of Cold-Formed Steel Structural Members."

Welding:

Welding shall be in accordance with American Welding Society (AWS) D1.3, "Structural Welding Code - Sheet Steel."

Welders shall be qualified in accordance with "Welder Qualification," procedures of AWS D1.1, "Structural Welding Code-Steel."

## SUBMITTALS

Product Data:

Manufacturer's descriptive data and installation instructions for each item of cold-formed metal framing and accessories shall be submitted for approval.

Installation instructions shall include instructions for securing studs to tracks and other framing connections.

Working Drawings:

Working drawings and calculations for cold formed metal framing components not fully dimensioned in manufacturer's descriptive data shall be submitted for approval.

Working drawings shall include framing members showing size and gage designations, number, type, location and spacing. Working drawings shall include supplemental strapping, bracing, splices, bridging, accessories, and details required for proper installation.

The cold formed metal framing supplier shall submit drawings and calculations stamped by an Engineer who is registered as a Civil or Structural Engineer in the State of California showing that the metal framing and fasteners comply with seismic and wind uplift requirements of the CBC.

## QUALITY ASSURANCE

Fire-rated Assemblies: Where cold formed metal framing units are components of assemblies indicated to be fire-rated, provide units which have been approved for the rating indicated on the plans.

## DELIVERY, STORAGE AND HANDLING

Cold formed metal framing components shall be protected from rusting and damage. Components shall be delivered to the jobsite in manufacturer's unopened containers or bundles, fully identified with name, brand, type and grade. Components shall be stored off ground in a dry ventilated space.

# PART 2 - PRODUCTS

## COLD FORMED METAL FRAMING

Steel Studs, Joists Blocking and Rafters:

Load-bearing studs shall be formed to channel shape, punched web, and knurled faces, conforming to ASTM Designation: A 653/A 653M, Grade33 [230]. Studs shall be 18-gage minimum thickness and size as shown on the drawings.

Joists, rafters, and other framing components, 18-gage minimum thickness, shall be fabricated of commercial quality galvanized steel sheets; conforming to ASTM Designation: A 653/A 653M, Grade 33 [230] minimum thickness and as shown on the drawings.

Steel Track: Track shall be formed steel, channel shape, and same width as studs; solid web; not less than 18-gage thickness.

## ACCESSORIES

Fasteners: Fasteners shall be hot-dipped galvanized, self-drilling, self-tapping screws, or bolts, nuts and washers.

Anchorages: Anchorages shall be ICBO approved for the purpose intended, integral stud type, powder driven or drilled expansion bolts.

**FINISHES**

Studs, Track and Headers: Studs, tracks and headers shall be hot-dipped galvanized to conform to ASTM Designation: A 653M, G60.

Miscellaneous Metal Parts: Miscellaneous parts, including, bracing, furring, plates, gussets, and bridging, shall be hot dipped galvanized to not less than 1¼ ounces per square foot.

**FABRICATION**

Cold formed metal framing components shall be fabricated in place or prefabricated into panels to the maximum extent possible prior to erection. Panels shall be fabricated plumb, square, true to line and braced against racking with joints welded. Lifting of prefabricated panels shall be performed in a manner to prevent damage or distortion.

Panels shall be fabricated in jig or templates to hold members in proper alignment and position to assure accurate placement.

Fastenings: Components shall be fastened by shop welding, bolting or screw fasteners as shown on the approved drawings.

## PART 3 - EXECUTION

**INSTALLATION**

Studs:

Studs shall be erected plumb, except as needed for diagonal bracing or similar requirements. Channel tracks shall be aligned accurately to the wall layout at both floor and ceiling. Tracks shall be secured to floor and ceiling with fasteners spaced at not more than 16-inch intervals. Fasteners shall be provided at corners and ends of track.

Studs shall extend from floor to underside of ceiling except at wall openings. Each stud shall be secured to tracks at both top and bottom by bolting or screw fastening at both inside and outside flanges. Field welding shall not be permitted. A ½-inch clearance shall be provided at the top shoes. Door openings shall have double studs continuous across head and from floor to ceiling on each jamb.

Studs at openings shall be fastened solidly and securely to floor clips. Floor clips shall be fastened to the floor with 2 anchors unless otherwise shown on the plans.

Supplemental framing, blocking and bracing shall be installed in steel stud system wherever walls or partitions are to support fixtures, equipment, services, casework, heavy trim and furnishings, and similar work requiring attachment to the wall or partition.

One continuous, horizontal ¾-inch channel reinforcement shall be placed approximately 6 inches above all wall openings. The reinforcement shall pass through the web openings in the studs and shall extend through the first stud located beyond the double studs at either side of the opening and shall be saddle tied to each stud it passes through.

Joists and Rafters:

Joists and rafters shall be installed directly over bearing studs or a load distribution member shall be installed at the top track.

Web stiffeners shall be provided at reaction points where shown on the plans.

Ends of joists shall be reinforced with end clips, steel hangers, steel angle clips, steel stud section, or as otherwise recommended by the manufacturer.

Joists shall be secured to interior support systems to prevent lateral movement of bottom flanges.

## 12-5.04 BUILDING MISCELLANEOUS METAL

## PART 1 - GENERAL

Scope: This work shall consist of fabricating, furnishing and installing building miscellaneous metal in accordance with the details shown on the plans and these special provisions.

Building miscellaneous metal shall consist of the following:

Bracket for wall mounted water heater.
Perforated metal vision screen with tube steel frame
Handrailing

Including all anchors, fastenings, hardware, accessories and other supplementary parts necessary to complete the work.

### REFERENCES

Codes and Standards: Welding of steel shall be in accordance with American Welding Society (AWS) D 1.1, "Structural Welding Code-Steel" and D 1.3, “Structural Welding Code-Sheet Steel.”

### SUBMITTALS

Product Data: Submit manufacturer's specifications, anchor details and installation instructions for products used in miscellaneous metal fabrications.

Working Drawings: Working drawings of fabricated items shall be submitted for approval.

### QUALITY ASSURANCE

Shop Assembly: Preassemble items in shop to the greatest extent possible to minimize field splicing and assembly. Disassemble units only as necessary for shipping and handling limitations. Clearly mark all units for reassembly and installation.

Inspection and Tests: Materials and fabrication procedures shall be subject to inspection and tests by the Engineer, in mill, shop and field. Such tests will not relieve the Contractor of responsibility of providing materials and fabrication procedures in compliance with specified requirements.

## PART 2 - PRODUCTS

### MATERIALS

Steel Bars, Plates and Hot-rolled Shapes: Steel bars, plates and hot-rolled shapes shall conform to ASTM Designation: A 36/A 36M.

Galvanized Sheet Steel: Galvanized sheet steel shall conform to ASTM Designation: A 653/A 653M, Grade 33 [230]. Galvanizing shall be G60 [Z180].

Pipe: Pipe shall be commercial quality standard steel pipe.

Steel Tubing: Steel tubing shall conform to ASTM Designation: A 500, Grade B, or A 501.

Bolts, Studs, Threaded Rods, Nuts and Washers:

Bolts, studs, threaded rods, and nuts for general application shall conform to ASTM Designation: A 307.

Washers shall be commercial quality.

Fittings: Brackets, bolt, threaded studs, nuts, washers, and other fittings for railings and handrailings shall be commercial quality pipe and fittings.

Expansion Anchors: Expansion anchors shall be ICBO approved for the purpose intended, integral stud type anchor or internally threaded type with independent stud, hex nut and washer.

Powder Driven Anchors: Powder driven anchors shall be plated, spring steel alloy drive pin or threaded stud type anchors for use in concrete or steel. Spring steel shall conform to ASTM Designation: A 227, Class 1. The diameter, length and type of shank and the number and type of washer shall be as recommended by the manufacturer for the types and thickness of material being anchored or fastened.

Mortar: Mortar shall consist of one part cement, measured by volume, to 2 parts clean sand and only enough water to permit placing and packing.

**FABRICATION**

Workmanship and Finish:

Workmanship and finish shall be equal to the best general practice in modern shops.

Miscellaneous metal shall be clean and free from loose mill scale, flake rust and rust pitting, and shall be well formed and finished to shape and size with sharp lines and angles. Bends from shearing or punching shall be straightened.

The thickness of metal and details of assembly and support shall give ample strength and stiffness.

Built-up parts shall be true to line and without sharp bends, twists and kinks. Exposed ends and edges of metal shall be milled or ground smooth, with corners slightly rounded.

Joints exposed to the weather shall be made up to exclude water.

Galvanizing: Items indicated on the plans to be galvanized shall be hot-dip galvanized after fabrication. The weight of galvanized coating shall be at least 1½ ounces per square foot of surface area, except drainage grates shall have at least 2 ounces per square foot of surface area.

Painting: Building miscellaneous metal items not galvanized shall be cleaned and prime painted prior to erection in accordance with the requirements specified for steel and other ferrous metals under "Painting" in Section 12-9, "Finishes," of these special provisions.

Loose Bearing and Leveling Plates: Loose bearing and leveling plates shall be furnished for steel items bearing on masonry or concrete construction, made flat, free from warps or twists, and of required thickness and bearing area. Plates shall be drilled to receive anchor bolts. Galvanize after fabrication.

Steel Pipe Railings and Handrailings:

Pipe handrailing shall consist of handrailing elements supported by metal brackets (wall type) or handrailing elements supported by tubular steel posts (post type).

Ends of railing pipe shall be closed, except for a 1/8-inch diameter weep hole at the low point.

All corners on railings shall be rounded. Simple and compound curves shall be formed by bending pipe in jigs to produce uniform curvature; maintain cylindrical cross-section of pipe throughout the bend without buckling, twisting or otherwise deforming exposed surfaces of the pipe.

Wall brackets, end closures, flanges, miscellaneous fitting and anchors shall be provided for interconnections of pipe and attachment of railings and handrails to other work. Inserts and other anchorage devices shall be furnished for connecting railings and handrails to concrete or masonry.

## PART 3 - EXECUTION

### GENERAL

Anchorages:

Anchorage devices and fasteners shall be provided for securing miscellaneous metal in-place construction; including threaded fasteners for concrete and masonry inserts, toggle bolts, through bolts, lag bolts, wood screws and other connectors.

Cutting, drilling and fitting shall be performed as required for installation of miscellaneous metal fabrications. Work is to set accurately in location, alignment and elevation, plumb, level, true and free of rack, measured from established lines and levels.

Loose Leveling and Bearing Plates: Plates shall be set on wedges or other adjustable devices. Anchor bolts shall be wrench tightened after the plates have been positioned and plumbed. Mortar shall be packed solidly between bearing surfaces and plates to ensure that no voids remain.

Steel Pipe Railings and Handrailings:

Railings shall be adjusted prior to anchoring to ensure matching alignment at abutting joints. Secure posts and railing ends to building construction as shown on the plans.

Powder Driven Anchors: Powder driven anchors shall be installed with low velocity powder actuated equipment in accordance with the manufacturer's instructions and State and Federal OSHA regulations.

### DAMAGED SURFACES

Galvanized surfaces that are abraded or damaged at any time after the application of the zinc coating shall be repaired by thoroughly wire brushing the damaged areas and removing all loose and cracked coating, after which the clean areas shall be painted with 2 applications of unthinned zinc-rich primer (organic vehicle type). Aerosol cans shall not be used.

# SECTION 12-6. WOOD AND PLASTICS

## 12-6.01 ROUGH CARPENTRY

## PART 1 - GENERAL

### SUMMARY

Scope: This work shall consist of furnishing and installing materials and performing rough carpentry work including wood framing, furring, and sheathing in accordance with the details shown on the plans and these special provisions.

Rough carpentry includes carpentry work not specified as part of other sections and which is generally not exposed.

## SUBMITTALS

Product Data: Manufacturer's material data and installation instructions shall be submitted for gypsum sheathing, framing hardware and underlayments.

Wood Treatment Data:

Chemical treatment manufacturer's instructions shall be submitted for the handling, sorting, installation, and finishing of treated materials.

For each type of preservative treatment used, certification by treating plant shall include type of preservative solution and pressure process used, net amount of preservative retained and conformance with the applicable standards of the American Wood Preservers Association.

For each type of fire-retardant treatment, include certification by treating plant that the treated material complies with the applicable standards and other requirements.

## DELIVERY, HANDLING AND STORAGE

Delivery and Storage: Materials shall be kept under cover and dry. All materials shall be protected from exposure to weather and contact with damp or wet surfaces with blocking and stickers. All lumber, plywood and other panels shall be stacked in such a manner to provide air circulation within and around the stacks.

# PART 2 - PRODUCTS

## PLYWOOD PANELS

Plywood panels shall comply with Voluntary Product Standard PS1, "U. S. Product Standard for Construction and Industrial Plywood."

Plywood panels shall be Group 1 unless otherwise noted.

Each plywood panel shall be factory marked with APA or other trademark evidencing compliance with grade requirements.

Structural Plywood Wall Sheathing: Structural plywood wall sheathing for walls shall be APA RATED SHEATHING, Exposure 1. Thickness and grade shall be as shown on the plans.

Structural Plywood Roof Sheathing:

Structure plywood roof sheathing shall be APA RATED SHEATHING, Exposure 1. Span rating, thickness and grade shall be as shown on the plans.

Structure plywood roof sheathing in exposed overhangs shall be APA RATED SHEATHING, A-C, Exterior, Group 1. Thickness shall be the same as the remainder of the sheathing.

## MISCELLANEOUS MATERIALS

Rough Carpentry Hardware:

Steel plates and rolled sections shall be mild, weldable steel, conforming to AISI grades 1016 through 1030 except 1017.

Nails, screws, bolts, nuts, washers shall be commercial quality. Exposed fasteners shall be hot dipped galvanized or stainless steel.

Joist hangers, clips and other standard framing hardware shall be ICBO approved, commercial quality, galvanized sheet steel or hot dipped galvanized, of the size shown on the plans.

Expansion anchors and powder driven anchors shall be as specified under "Building Miscellaneous Metal," in Section 12-5, "Metals," of these special provisions.

Building Paper: Building paper shall be kraft type waterproofing building paper, Type I (No. 15) asphalt saturated roofing felt or high density, bonded polyethylene fiber building paper.

Adhesive: Adhesive for plywood glue-nailed systems shall conform to APA Specification: AFG-01.

**PART 3 - EXECUTION**

**INSTALLATION**

Plywood Panels:

Plywood panels shall be attached to the framing as shown on the plans and these special provisions. All structural plywood sheathing (both roof and wall) shall be nailed with "Common" nails.

Plywood decking shall be glued and nailed to the framing system.

Plywood sheathing shall be nailed to the framing system and shall be continuous over 2 or more supports. Roof and floor panels shall be installed with the long dimension across the supports, with end joints staggered 4 feet. Wall sheathing shall have all edges blocked. Spacing between panels shall be 1/8 inch.

**12-6.02 FINISH CARPENTRY**

**PART 1 - GENERAL**

**SUMMARY**

Scope: This work consists of furnishing and installing materials and performing finish carpentry, including interior trim, panels and plywood and softwood paneling, as shown on the plans and these special provisions.

Finish carpentry includes carpentry work not specified as part of other sections and which is generally exposed to view.

**SUBMITTALS**

Product Data: Manufacturer's specifications and installation instructions for each item of factory-fabricated siding and paneling.

Samples: One sample shall be submitted to the Engineer at the jobsite for each species and cut or pattern of finish carpentry as shown below:

Exterior standing and running trim: 2 feet long x full board or molding width, finished on one side and one edge.

Interior standing and running trim: 2 feet long by full board or molding width, finished on one side and one edge.

Siding: 2 feet long, finished on one side and one edge.

Exterior plywood for transparent finish: 2 feet long x panel width, finish shall be applied to upper half of each piece.

Plywood paneling: 2 feet long x full panel width, finished on one side.

## QUALITY ASSURANCE

Factory Marks: Each piece of lumber and plywood shall be marked with type, grade, mill and grading agency identification. Marks shall be omitted from surfaces to receive transparent finish. A mill certificate stating that material has been inspected and graded in accordance with requirements shall be furnished if marks cannot be placed on concealed surfaces.

## PRODUCT DELIVERY, STORAGE AND HANDLING

Delivery: Carpentry materials shall be delivered after painting, wet work and similar operations have been completed.

Protection: Finish carpentry materials shall be protected during transit, delivery, storage and handling to prevent damage, soiling and deterioration.

# PART 2 - PRODUCTS

## WOOD PRODUCT QUALITY STANDARDS

Plywood: Plywood shall conform to the requirements of Voluntary Products Standard PS-1, "U. S. Product Standard for Construction and Industrial Plywood."

Woodworking: Woodworking shall conform to the requirements of Woodwork Institute of California (WI), "Manual of Millwork."

## MATERIALS

Plywood Paneling and Wainscotting: Plywood paneling and wainscotting shall be APA Interior Grade A-C, Group 1, Exposure 1 plywood. Thickness shall be as shown on the plans.

Miscellaneous Materials:

Nails, screws and other anchoring devices of the type, size, material and finish required shall be provided for secure attachment, concealed where possible.

Fasteners and anchorages for exterior use shall be hot dip galvanized.

Screens for soffit vents shall be 4 x 4 or 8 x 8 mesh, galvanized screen. Open area shall be not less than 50 percent.

# PART 3 - EXECUTION

## INSTALLATION

All work shall be installed plumb, level and true with no distortions.

Anchor Finish Carpentry:

Finish carpentry shall be anchored to framing or blocking built in or attached directly to the substrate.

Interior carpentry shall be attached to grounds, stripping and blocking with countersunk, concealed fasteners and blind nailing where required for complete installation. Fine finish nails shall be used for exposed nailing, countersunk and filled flush with finished surface and matching final finish where transparent finish is indicated.

## ADJUSTMENT, CLEANING, FINISHING AND PROTECTION

Damaged and defective finish carpentry work shall be repaired or replaced.

All exposed or semi-exposed surfaces shall be cleaned.

Finish carpentry shall be finished in accordance with the requirements specified under "Painting" in Section 12-9, "Finishes," of these special provisions.

## 12-6.03 CABINETS

### PART 1 - GENERAL

#### SUMMARY

Scope: This work shall consist of furnishing and installing wood cabinets and plastic laminate tops, splashes and returns as shown on the plans and in these special provisions.

#### SUBMITTALS

Product Data: Manufacturer's product data for plastic laminates and cabinet hardware shall be submitted for approval.

Samples: Three samples shall be submitted for each of the items shown below:

Plastic laminate, 8" x 10" for each type, color, pattern and surface finish.

Working Drawings: Working drawings for cabinets showing location of cabinets, dimensioned plans and elevations, attachment devices and other components shall be submitted for approval. Working drawings shall bear the "WI Certified Compliance Label" on the first sheet of the drawings.

#### QUALITY ASSURANCE

Codes and Standards: Cabinets and swinging gate shall be manufactured and installed in accordance with the Manual of Millwork of the Woodwork Institute (WI) requirements for the custom grade architectural millwork.

Certificates of Compliance:

Prior to delivery to the jobsite, the cabinet manufacturer shall issue a WI Certified Compliance Certificate indicating that the products he will furnish for this job and certifying that they will fully meet all the requirements of the grade or grades specified.

WI Certified Compliance Label shall be stamped on all cabinet work and swinging gate.

Each plastic laminate top shall bear the WI Certified Compliance Label.

Prior to completion of the contract, a WI Certified Compliance Certificate for Installation shall be delivered to the Engineer.

#### DELIVERY, STORAGE AND HANDLING

Protection: Cabinets shall be protected during transit, delivery, storage and handling to prevent damage, soiling and deterioration.

### PART 2 - PRODUCTS

#### ACCEPTABLE MANUFACTURERS

Manufacturers: Subject to compliance with these specifications, high pressure decorative laminates shall be Consoweld Corp.; Formica Corp.; Nevamar Corp.; or equal.

**MANUFACTURED UNITS**

Cabinets shall be fabricated to the dimensions, profiles, and details shown on the plans with openings and mortises precut, where possible to receive hardware and other items and work.

Fabrication, assembly, finishing, hardware application, and other work shall be completed to the maximum extent possible prior to shipment to the jobsite.

Laminate Clad Cabinets:

Laminate clad cabinets shall be custom grade, flush overlay construction.

Laminate cladding shall be high pressure decorative laminate complying with NEMA LD 3. Color, pattern and finish shall be as shown on the plans. Laminate surface and grade shall be as follows:

Horizontal and vertical surfaces other than tops shall conform to GP-50 (50-mil nominal thickness).

Postformed surfaces shall conform to PF-42 (42-mil nominal thickness).

Laminated Counter Tops and Splashes:

Laminated counter tops and splashes shall be WI custom grade.

Surface material shall be high pressure laminated plastic conforming to NEMA LD-3, 50-mil thickness.

Unless otherwise shown on the plans, splashes shall be 4 inches high from the surface of the deck. Back splashes shall be continuous formed and coved. Side splashes shall be top set.

Laminated counter tops self edged, counter tops to receive sinks or plumbing fixtures shall have a bullnose.

The underside of tops and backsides of splashes shall be covered with an approved backing sheet.

**CABINET HARDWARE AND ACCESSORY MATERIALS**

Cabinet hardware and accessory materials shall be provided for cabinets.

Hardware shall be provided with standard US 26D metal plated finish.

Drawer Slides: Drawer slides shall be side mounting full extension with fully enclosed rolling balls and rollers. Concealed slides and bearings, and positive stop. Capacity shall be not less than 75 pounds, except capacity shall be not less than 100 pounds for heavy duty drawers.

Door Guides: Sliding door guides shall be continuous, dual channel, metal guides, top and bottom. Bottom guide shall have crowned track.

Shelf Supports: Shelf supports shall be adjustable, semi-recessed, chrome finished pressed metal, heavy duty standards and support clip, with one inch adjustment increments.

Cabinet Hinges:

Cabinet hinges shall be steel. Length of jamb leaf shall be 2½ inches. The type of hinge shall be as shown on the plans.

Cabinet hinge manufacturers shall be Stanley, Hager, McKinney, or equal.

Cabinet Catches:

Cabinet catches shall be self aligning magnetic type in aluminum case with zinc plated steel strike.

Cabinet catch manufacturers shall be Stanley, Hager, McKinney, or equal.

Cabinet Pulls:

Cabinet pulls shall be "U" shaped 5/16-inch diameter rod, with 1 5/16-inch projection and 3-inch center to center fastening.

Cabinet pull manufacturers shall be Stanley, Hager, McKinney, or equal.

Wall bumper shall be not less than 2½ inches in diameter with a one-inch projection.

**FABRICATION**

Shop Assembly:

Nails shall be countersunk and the holes filled, molds shall be neatly mitered and all joints shall be tight and true.

As far as practicable, work shall be assembled at the mill and delivered to the building ready to be set in place. Parts shall be smoothly dressed and interior work shall be belt sanded at the mill and hand sanded at the building. After assembly, work shall be cleaned and made ready for the specified finish.

Veneer sequence matching shall be maintained of cabinets with transparent finish.

All work shall be prepared to receive finish hardware. Finish hardware shall be accurately fitted and securely fastened as recommended by the manufacturer. Finish hardware shall not be fastened with adhesives.

Drawers shall be fitted with dust covers of ¼-inch plywood or hardboard above compartments and drawers except where located directly under tops.

Precut Openings: Openings for hardware, appliances, plumbing fixtures, and similar items shall be precut where possible. Openings shall be accurately located and templates used for proper size and shape. Edges of cutouts shall be smoothed and edges sealed with a water-resistant coating.

**PART 3 - EXECUTION**

**INSTALLATION**

Cabinets: Cabinets shall be installed without distortion so that doors and drawers fit openings properly and are accurately aligned. Hardware shall be adjusted to center doors and drawers in openings and to provide unencumbered operation. Installation of hardware and accessory items shall be completed as indicated on the approved drawings.

Laminate Tops: Laminate tops shall be securely fastened to base units and other support systems as indicated on the approved drawings.

Cabinet Hardware:

Doors for cabinets shall be equipped with one pair of hinges and one catch per leaf, unless otherwise shown on the plans. Each door leaf shall be equipped with one pull.

Drawers up to 24 inches wide shall have one pull and drawers over 24 inches wide shall have two pulls.

## SECTION 12-7. THERMAL AND MOISTURE PROTECTION

### 12-7.01 WATER REPELLENT SEALANT

### PART 1 - GENERAL

#### SUMMARY

Scope: The work shall consist of cleaning and placing a silane sealant on exterior concrete surfaces and on those interior concrete surfaces that will not be covered by insulation, framing, paneling or other construction.

#### SUBMITTALS

Product Data: Manufacturer's descriptive data and application instructions shall be submitted for approval.

#### QUALITY ASSURANCE

Certificates of Compliance: Certificates of Compliance shall be furnished with each shipment of water repellent sealant in accordance with Section 6-1.07, "Certificates of Compliance," of the Standard Specifications, and a Materials Safety Data Sheet.

### PART 2 - PRODUCTS

Manufacturers: Water repellent sealer shall be Hydrozo Inc., Enviroseal 40; Tamms Industries, Baracade Silane 40; Sonneborne, Penetrating Sealer 40; or equal.

Water Repellent Sealant:

Water repellent sealant shall be a 40 percent minimum, organosilane solution, diluted in a suitable solvent, and shall consist of alkyltrimethoxy silanes with alkyl groups of i-butyl, i-octyl, n-octyl, singularly or in combination.

The water repellent sealant shall be tinted with a fugitive dye which will cause the concrete sealant to be distinguishable on the concrete surface for at least four hours after application, but shall disappear within seven days after application.

### PART 3 - EXECUTION

#### PREPARATION

Protection: Surfaces of other materials surrounding or near the surfaces to receive the water repellent sealant shall be protected from overspray or spillage from the waterproofing operation. Water repellent sealant applied to surfaces not intended to be waterproofed shall be removed and the surfaces restored to their original condition.

Surface Preparation:

All surfaces to receive water repellent sealant shall be cleaned with light abrasive blasting.

Blasting shall remove all dirt, debris and other deleterious materials, including removal of existing cement matrix.

After cleaning, the concrete surfaces shall be air blown to dry and remove loose surface material prior to sealing.

#### APPLICATION

The water repellent solution shall be applied in accordance with manufacturer's application instructions.

Water repellent sealant shall be applied only during periods of weather as recommended by the manufacturer, when the atmospheric temperature is between 40°F and 100°F and for exterior application when wind speed is less than 5 miles per hour.

Subject to written approval by the Engineer, the Contractor may provide suitable enclosures to permit concrete sealing during inclement weather.

**FIELD QUALITY CONTROL**

Tests:

Approximately 24 hours after placement of the water repellent sealant, the Contractor shall uniformly dampen the treated concrete surface using a fine water spray. Spray shall completely wet the surface without causing runoff.

After 5 days following sealant application, if required by the Engineer, the Contractor shall spray designated sealed concrete surfaces with a fresh water spray to verify sealant coverage. The water spray shall not penetrate the concrete surfaces, and surfaces determined to lack sufficient sealant coverage shall be resealed.

## 12-7.02 CORRUGATED ALUMINUM SIDING

## PART 1 - GENERAL

**SUMMARY**

Scope: This work shall consist of furnishing and installing manufactured corrugated aluminum siding panels, in accordance with the details shown on the plans and these special provisions.

Corrugated aluminum siding system shall consist of prefinished metal siding panels, fasteners, and accessories and components, not mentioned, which are required for a complete, securely fastened and weathertight installation.

**SUBMITTALS**

Product Data:

Manufacturer's technical product data, installation instructions, and recommendations for each type of sheathing material shall be submitted for approval.

Product data shall include the manufacturer's name and a complete material description of all components of the corrugated aluminum sheathing system.

Samples:

Material samples shall include a 12" x 12" sample of the corrugated aluminum siding panels to be installed and a sample of each fastening device.

Working Drawings:

Working drawings showing the layout and details of the corrugated aluminum siding system shall be submitted for approval.

Working drawings shall include the shape, size, thickness, and method of attachment for each component used in the work; the layout and spacing of fasteners and details of connections and closures.

Design calculations for the fastening system of the wall panels with the substrate shown on the plans shall be submitted to verify compliance with the design requirements.

## QUALITY ASSURANCE

Certificates of Compliance: Certificates of compliance shall be furnished for the metal sheathing system in accordance with the requirements specified in Section 6-1.07, "Certificates of Compliance," of the Standard Specifications.

## DELIVERY, HANDLING AND STORAGE

Delivery and Handling: Corrugated aluminum panels shall be protected against damage and discoloration.

Storage: Corrugated aluminum panels shall be stored above ground, with one end elevated for drainage and protected against standing water and condensation between adjacent surfaces.

# PART 2 - PRODUCTS

## MATERIALS

## SHEET MATERIALS

Base Metal: Base metal shall be cold formed aluminum-zinc alloy-coated, commercial quality, sheet steel conforming to ASTM Designation: A 792/A 792M, Grade 40 [275] with G90 [Z275] coating, extra smooth.

Metal siding system shall be a corrugated system with corrugations spaced approximately 2.67 inches on center. The depth of the corrugations shall be approximately ½ inch.

## METAL FINISHES

Coatings shall be applied before or after forming and fabricating panels, as required for maximum coating performance capability.

## MISCELLANEOUS METAL SHAPES

Flashings: Flashings shall be formed from the same material, gage and in the same finish as the metal corrugated aluminum siding panels.

Perforated Soffit: Perforated soffit shall be formed from the same material, gage and in the same finish as the corrugated aluminum sheathing panels.

## MISCELLANEOUS MATERIALS

Fasteners: Fasteners shall be as recommended by the corrugated aluminum panel system manufacturer. Corrugated aluminum sheet metal screws shall not be used except to fasten trim and flashings.

Closures: Closures shall be rubber, neoprene, closed cell plastic or prefinished metal.

## FABRICATION

Unless otherwise shown on the plans, or specified herein, corrugated aluminum siding panels shall be fabricated in continuous lengths for the height of the structure, from eaves to sill, except such length shall not exceed the manufacturer’s maximum production length.

Flashings shall be fabricated in the longest practical lengths.

Corrugated aluminum siding panels shall be factory formed. Field formed panels are not acceptable.

## PART 3 - EXECUTION

### INSTALLATION

Corrugated Aluminum Siding Panels:

The corrugated aluminum siding shall be installed and fastened in accordance with the details shown on the plans and the approved working drawings. Cutting and fitting shall present a neat and true appearance with exposed burrs removed.

Corrugated aluminum panels shall be adjusted in place and properly aligned for the detailed conditions before fastening. Panels shall not be warped, bowed or twisted. The surface finish on the panels shall not be cracked, blemished or otherwise damaged.

Miscellaneous Metal Shapes:

Trim, flashings, and other prefinished corrugated aluminum work shall be positioned to the correct alignment for each detailed condition. Corrugated aluminum work shall be securely attached to backing construction using fasteners at the spacing shown on approved working drawings.

Corrugated aluminum panels, trim, and other prefinished metal that are marred, punctured, incorrectly bent, or incorrectly installed will be considered damaged and shall be replaced with undamaged units.

### CLEAN UP AND CLOSE OUT

Clean up:

Adjacent surfaces shall be protected during the system installation.

Corrugated aluminum anels, trim, and other prefinished metal surfaces shall be cleaned after installation as recommended by the manufacturer.

Damaged Units: Panels and other components of the work which have been damaged or have deteriorated beyond successful repair shall be removed and replaced.

## 12-7.03 METAL ROOFING

## PART 1 - GENERAL

### SUMMARY

Scope: This work shall consist of furnishing and installing preformed metal roofing in accordance with the details shown on the plans and these special provisions.

Metal roofing system shall consist of underlayment, prefinished metal roof panels, gutters, downspouts, concealed fasteners, sealants, snow guards, and other accessories and components, not mentioned, which are required for a complete, securely fastened and weathertight installation.

### SYSTEM DESCRIPTION

Design Requirements: The roofing system shall conform to the wind design requirements for uplift in Chapter 16 of the CBC for the wind speed and exposure shown on the plans.

## SUBMITTALS

Product Data:

Manufacturer's technical product data, installation instructions, and recommendations for each type of roofing material shall be submitted for approval.

Product data shall include the manufacturer's name and a complete material description of all components of the metal roofing system.

Samples:

Material samples shall include a 12" x 12" sample of the roofing panel for each color to be installed and a sample of each anchor clip and fastening device.

Working Drawings:

Working drawings showing the layout and details of the metal roofing shall be submitted for approval.

Working drawings shall show the shape, size, thickness, and method of attachment for each component used in the work; the layout and spacing of fasteners; details of connections and closures; and details for expansion joints and weathertight joints.

Design calculations for the fastening system with the substrate shown on the plans shall be submitted to verify compliance with the design requirements.

Working drawings and design calculations shall be stamped and signed by an engineer who is registered as a Civil or Structural Engineer in the State of California. The expiration date of the registration shall be shown. The Engineer's signature shall be original.

## QUALITY ASSURANCE

Certificates of Compliance: Certificates of compliance shall be furnished for the metal roofing system in accordance with the requirements specified in Section 6-1.07, "Certificates of Compliance," of the Standard Specifications.

## DELIVERY, HANDLING AND STORAGE

Delivery and Handling: Panels shall be protected against damage and discoloration.

Storage: Panels shall be stored above ground, with one end elevated for drainage and protected against standing water and condensation between adjacent surfaces.

# PART 2 - PRODUCTS

## MATERIALS

## SHEET MATERIAL

Base Metal: Base metal shall be cold formed, 24-gage, galvanized sheet steel conforming to ASTM Designation: A 653/A 653M, Grade 33 [230] with G90 [Z275] coating, except where a higher strength is required for performance, extra smooth; or cold formed aluminum-zinc alloy-coated, commercial quality, sheet steel conforming to ASTM Designation: A 792/A 792M, Grade 40 [275] with AZ55 [AZM 165], coating extra smooth.

Configuration: Metal roofing system shall have primary vertical ribs spaced at not less than 8 inches nor more than 12 inches, with 2 intermediate ribs located between the primary ribs. The depth of the primary ribs shall be between ¾ inch and 1 5/8 inches in depth.

## METAL FINISHES

Coatings shall be applied before or after forming and fabricating panels, as required for maximum coating performance capability.

Colors or color matches shall be as shown on the plans or, if not otherwise shown, shall be as selected by the Architect from the manufacturer's standard color palette.

Fluoropolymer Coating:

Finish shall be the manufacturer's standard Kynar coating with a baked on primer (0.2-mil) and a finish coat of 0.8-mil nominal for a total dry film thickness of approximately 1.0-mil nominal.

Interior finish shall consist of a 0.15-mil epoxy primer and a backer coat.

## MISCELLANEOUS METAL SHAPES

Flashings, Gutters, and Downspouts: Flashings, gutters, and downspouts shall be formed from the same material, gage and in the same finish as the roofing panels.

Perforated Soffit: Perforated soffit shall be formed from the same material, gage and in the same finish as the roof panels.

## MISCELLANEOUS MATERIALS

Fastener Clips: Fastener clips shall be noncorrosive ferrous metal fasteners as recommended by the metal roofing system manufacturer to resist the design loads.

Fasteners: Fasteners shall be as recommended by the metal roofing system manufacturer. Sheet metal screws shall not be used except to fasten trim and flashings.

Underlayment: Underlayment shall be as recommended by the metal roofing system manufacturer, but not less than 30-pound minimum asphalt impregnated fiber glass mat roofing felt.

Sealant and Sealant Tape: Sealant and sealant tape shall be as recommended by the roofing manufacturer.

Closures: Closures shall be rubber, neoprene, closed cell plastic or prefinished metal.

## FABRICATION

Unless otherwise shown on the plans, or specified herein, roof panels shall be fabricated in continuous lengths for the length of the roof, from ridge or peak to eave, except such length shall not exceed the manufacturer's maximum production length. Flashings shall be fabricated in the longest practical lengths.

Roofing panels shall be factory formed. Field formed panels are not acceptable.

# PART 3 - EXECUTION

## INSTALLATION

Underlayment: The roof and fascia panels shall be installed over underlayment. Underlayment shall be laid parallel to the eaves, shingle fashion with 6-inch edge laps and 12-inch end laps and shall be fastened as recommended by the metal roofing system manufacturer.

Roof Panels:

The roof system shall be installed and fastened in accordance with the details shown on the plans and the approved working drawings. Cutting and fitting shall present a neat and true appearance with exposed burrs removed. Openings through roof panels shall be cut square and shall be reinforced as recommended by the metal roofing system manufacturer.

Roof panels shall be adjusted in place and properly aligned for the detailed conditions before fastening. Panels shall not be warped, bowed or twisted. The surface finish on the panels shall not be cracked, blemished or otherwise damaged.

Gaskets, joint fillers, sealants and sealing tape shall be installed where indicated on the approved drawings or as required for weatherproof performance of panel systems.

Fasteners shall not be driven through roof panels or batten covers.

Miscellaneous Metal Shapes:

Trim, fascia, flashings, gutters, downspouts, scuppers, caps, and other prefinished metal work shall be positioned to the correct alignment for each detailed condition. Metal work shall be securely attached to backing using fasteners at the spacing shown on approved working drawings. Prefinished metal to be installed over concrete, masonry or plaster shall be back-coated with asphaltic paint as recommended by the metal roofing system manufacturer.

Roof panels, trim, gutters, and other prefinished metal that are marred, punctured, incorrectly bent, or incorrectly installed will be considered damaged and shall be replaced with undamaged units.

Gutters shall be fabricated by the metal roofing system manufacturer to the shape and lengths shown on the plans. Expansion joints shall conform to the manufacturer's recommendations and to SMACNA "Architectural Sheet Metal Manual."

The metal roofing system shall be installed weathertight. Closures shall be tight fitting and shall be provided at the ends of panels, at the boundary of the roof, and as indicated on the approved working drawings.

**CLEAN UP AND CLOSE OUT**

Clean up:

Adjacent surfaces shall be protected during the roofing system installation and sealant work. Excess sealant shall be removed as the installation progresses.

Roof panels, molding, trim, and other prefinished metal surfaces shall be cleaned after installation as recommended by the manufacturer. Exposed cuts shall be touched-up with a matching durable primer and paint as recommended by the metal roofing system manufacturer.

Touch up: Damaged paint surfaces shall be touched up by using an air dry touch up paint supplied by the metal roofing system manufacturer. Only a small brush shall be used for touching up. No spraying of touch up paint is to be performed.

Damaged Units: Panels and other components of the work which have been damaged or have deteriorated beyond successful repair shall be removed and replaced.

## 12-7.04 SHEET METAL FLASHING

## PART 1 - GENERAL

### SUMMARY

Scope: This work shall consist of fabricating, furnishing and installing sheet metal flashing in accordance with the details shown on the plans and these special provisions.

Sheet metal shall include metal flashings, counterflashings, straps, gutters, downspouts, roof jacks, reglets, copings, scuppers, conductor heads, and screen type vents.

Alternatives: Premolded roof flashings may be used in lieu of sheet metal flashings where shown on the plans.

### QUALITY ASSURANCE

Codes and Standards: Sheet metal work shall in accordance with the requirements in the latest edition of the Sheet Metal and Air Conditioning Contractors National Association (SMACNA) "Standard Practice in Architectural Sheet Metal Work."

## PART 2 - PRODUCTS

### MATERIALS

Galvanized Sheet Steel: Galvanized sheet steel shall conform to ASTM Designation: A 653/A 653M with G 90 [Z275] coating, not less than 24-gage, unless otherwise shown on the plans. Surfaces to be painted shall not have factory coatings on galvanizing that cannot be removed by paint thinner.

Premolded Roof Flashing: Premolded flashing shall be premolded neoprene or ethylene propylene diene monomer (EPDM) flashing, resistant to ozone and ultraviolet. Units shall have overlapping tab to flash the seam.

Hardware and Fastenings: Hardware and fastening for premolded roof flashings shall be stainless steel.

Solder: Solder shall conform to ASTM Designation: B 32, Alloy Grade Sn50.

Soldering Flux: Soldering flux shall be acid type, conforming to Federal Specification: O-F-506C, Type I, Form A.

Insect Screen: Insect screen shall be industrial wire cloth and screen, medium grade, 18 mesh, 0.017-inch diameter, 0.039-inch openings, plain weave, galvanized steel conforming to ASTM Designation: E 437.

Lap Joint Sealant: Lap joint sealant for concealed locations shall be a non-drying butyl.

Flashing Cement: Flashing cement shall be a bituminous plastic cement, asbestos free, conforming to ASTM Designation: D 4586, Type II.

Sealant: Sealant for exposed locations shall be a silicone sealant conforming to ASTM Designation: C 920.

Primer: Primer shall be as recommended by the sealant manufacturer.

### FABRICATION

Sheet metal shall be assembled to Sheet Metal and Air Conditioning Contractors National Association Standards.

Sheet metal shall be formed to the sizes, shapes and dimensions shown on the plans or as specified herein with angles and lines straight, sharp and in true alignment. The number of joints shall be kept to a minimum.

Angle bends and folds for interlocking the metal shall be made with full regard for expansion and contraction to avoid buckling or fullness in the metal after it is installed.

Joints in sheet metal work shall be closed watertight unless slip joints are specifically required. Watertight joints shall be mechanically interlocked and then thoroughly soldered for metals other than aluminum. Watertight joints in aluminum or between aluminum and other metals shall be sealed with acrylic sealant.

Sheet metal joints to be soldered shall be cleaned with steel wool or other means, pre-tinned and soldered watertight.

All joints shall be wiped clean of flux after soldering. Acid flux shall be neutralized by washing the joints with sodium bicarbonate.

Flashings shall have a 45 degree drip return at bottom edges. Unless otherwise shown on the plans, counterflashing shall extend not less than 4 inches over roofing or other materials protected by the counterflashing and shall be arranged so that roofing or materials can be repaired without damage to the counterflashing. Where reglets are indicated, counterflashing shall be fastened by lead wedges or snap-in flashing.

## PART 3 - EXECUTION

Preparation: Surfaces to receive sheet metal shall be clean, smooth and free from defects.

Protection: Aluminum surfaces to be in contact with concrete, mortar, or dissimilar metals shall be given a heavy coat of coal tar paint.

### INSTALLATION

Roof Penetration Flashings:

All pipes, ducts, vents and flues passing through roofs shall be made waterproof with flashings of storm collars or counterflashings.

Roof penetration flashings shall be fabricated from galvanized sheet steel, not less than 24-gage. Size and shape shall be as shown on the plans.

The lower flashing shall be galvanized sheet metal, 24-gage, and extend 6 inches minimum from outside of the pipe in all directions and 1½ inches above the top of the roofing.

The top flashing shall be galvanized sheet steel or sheet lead as shown on the plans.

Hung Gutters:

Hung gutters shall be fabricated from galvanized sheet steel, not less than 24-gage. Gutters shall be size and shape as shown on the plans.

Gutters shall be fabricated in sections not less than 10 feet in length. Use sections as long as practicable for lengths over 10 feet.

Joints shall be lapped at least 1½ inches, rivet and solder watertight. Butt type expansion joints, ¾ inch wide, shall be provided at midpoint between down spouts and where expansion joints occur in the structure.

Downspouts:

Downspouts shall be fabricated from galvanized sheet steel, not less than 24-gage. Size and shape shall be as shown on the plans.

Downspouts shall be installed as shown on the plans, secured to the wall with straps near top, bottom and at intermediate points not more than 8 feet apart. Straps shall extend 2 inches out on wall and be secured with suitable anchors.

Unless otherwise shown on the plans, the lower end of downspout shall terminate with mitered 45 degree elbow.

Premolded Roof Flashings: Premolded roof flashings shall be installed in accordance with the manufacturer's instructions.

## 12-7.05 ROOF SPECIALTIES

## PART 1 - GENERAL

### SUMMARY

Scope: This work shall consist of furnishing and installing roof specialties in accordance with details shown on the plans and these special provisions.

Roof specialties shall include vent through roof flashing.

### SUBMITTALS

Product Data: Manufacturer's descriptive data, rough-in diagrams, installation instructions and general product recommendations shall be submitted for approval.

Samples: Two samples, minimum 8 inches square, of each exposed metal and plastic sheet materials, and 2 samples, minimum 24 inches long, of formed or extruded metal member each color and finish specified shall be submitted for approval.

Coordination Drawings: Coordination drawings for items interfacing with or supporting mechanical or electrical equipment, ductwork, piping or conduit, shall be submitted for approval. Drawings shall indicate dimensions and locations of items provided in this special provision, together with relationship and methods of attachment to adjacent construction and to mechanical and electrical items.

### QUALITY ASSURANCE

Labels: Units shall be provided which have been tested, listed, and bear the label of UL, FM or other recognized testing agency.

Codes and Standards: Prefabricated units shall conform to the requirements of SMACNA, "Architectural Sheet Metal Manual," details for fabrication of units, including flanges and cap flashing to coordinate with types of roofing involved.

## PART 2 - PRODUCTS

Manufacturer's standard units, modified as necessary, shall be provided to comply with the contract requirements. Each unit shall be shop fabricated to the greatest extent possible.

### MATERIALS

Sheet Steel: Sheet steel shall be structural quality conforming to the requirements of ASTM Designation: A 570.

Fasteners: Fasteners shall be the same metal as the metal to be fastened, or other non-corrosive metal as recommended by the unit manufacturer. Finish of the fastener shall be the same finish as the metal being fastened.

Bituminous Coating: Bituminous coating shall be as recommended by the unit manufacturer for the use specified.

Gaskets: Gaskets shall be tubular or fingered design of neoprene or polyvinyl chloride as recommended by the unit manufacturer.

## PART 3 - EXECUTION

### INSTALLATION

Prefabricated units shall be installed in accordance with the manufacturer's instructions and approved coordination drawings.

Installation of the units shall be coordinated with installation of the roof decking and other substrates to receive accessory units, vapor barriers, insulation, roof and flashing materials.

Units shall be securely fastened to supporting members, adequate to withstand all lateral, inward or outward loading pressures.

Where metal surfaces are to be installed in contact with non-compatible metals or other corrosive substrates, including wood decking, bituminous coatings shall be applied to metal surfaces.

Except as noted above, roof flanges shall be set in a thick bed of roofing cement to form a watertight seal.

Operational Testing: Units with operational components shall be fully tested. Joints and hardware shall be cleaned and lubricated. All units shall be adjusted for proper operation.

### CLEANING AND PROTECTION

All exposed metal and plastic surfaces shall be cleaned in accordance with the manufacturer's instructions. Damaged metal coatings shall be repaired.

# 12-7.06 JOINT SEALANT

## PART 1 - GENERAL

### SUMMARY

Scope: This work shall consist of preparing and placing a joint sealant in accordance with the details shown on the plans and these special provisions.

The sealed joint shall consist of tempered hardboard, expanded polystyrene and a pourable joint seal.

### SUBMITTALS

Product Data: Manufacturer's descriptive data, specifications and installation instructions shall be submitted to the Engineer at the jobsite for approval.

## PART 2 - PRODUCTS

Tempered Hardboard: Tempered hardboard shall be 1/8-inch minimum thickness, commercial quality suitable for the use intended. Other facing materials may be used provided they furnish equivalent protection.

Expanded Polystyrene: Expanded polystyrene shall be commercially available polystyrene board.

Polyethylene Foam: Polyethylene foam shall be commercial quality, with a continuous, impervious, glazed top surface, suitable for retaining the liquid sealant in the joint while hardening.

Primer: Primer shall be as recommended by the sealant manufacturer.

Joint Sealant: Joint sealant shall be a commercial quality, 2 component polyurethane sealant, which shall be self-levelling and withstand up to 25 percent movement.

## PART 3 - EXECUTION

### PREPARATION

Forming:

Groove for joint seal shall be formed to a uniform width and depth and to the alignment shown on the plans or as ordered by the Engineer. The completed groove shall have a top width within 1/8 inch of the width shown on the plans and the bottom width shall not vary from the top width by more than 1/16 inch.

At least 24 hours prior to installing the joint seal, the Contractor shall repair all spalls, fractures, breaks, or voids in the concrete surfaces of the joint groove.

The lip of the joint shall be beveled by grinding as shown on the plans.

Cleaning:

Prior to sealing joints, expanded polystyrene, hardboard, concrete spillage and all foreign material shall be removed from the deck to the bottom of the formed joint.

Prior to placing the joint seal, the joint shall be cleaned by a method which shall include abrasive blast cleaning and then be cleaned with a high pressure air jets to remove all residue and foreign material.

### INSTALLATION

Materials:

No material shall be used which has skinned over or which has settled in the container to the extent that it cannot be easily redispersed by hand stirring to form a smooth uniform product.

Each container of material shall be clearly labeled or each delivery of material in the tanks of 2-component equipment shall be accompanied with a ticket showing designation (Component A or B), the manufacturer's name, lot or batch number, date of manufacture, date of packaging, and date, if any, beyond which the sealant shall not be used.

Primer: A primer shall be applied to the sides of the groove and all exposed vertical surfaces in the joint prior to placing the sealant. Primer shall be dry at the time of placing the sealant. Contaminated primer shall be removed and replaced.

Joint Sealant: The 2-component sealant shall be mixed and placed in the groove in accordance with manufacturer's instructions. Unmixed liquid components which have been exposed to the atmosphere for more than 24 hours, shall not be used.

## 12-7.07 SEALANTS AND CAULKING

## PART 1 - GENERAL

### SUMMARY

Scope: This work shall consist of furnishing and applying sealants and caulking which are required for this project, but not specified elsewhere, in accordance with the details shown on the plans and these special provisions.

Related Work: Pourable polyurethane joint sealant shall conform to the requirements under "Joint Sealant" elsewhere in this Section 12-7.

### QUALITY ASSURANCE

Certificates of Compliance: Certificates of compliance shall be furnished for the sealants and caulking in accordance with the requirements specified in Section 6-1.07, "Certificates of Compliance," of the Standard Specifications.

### SUBMITTALS

Product Data: Manufacturer's descriptive data and installation instructions for all sealants shall be submitted for approval.

Samples: Color samples of all sealants shall be submitted for approval. Unless otherwise shown on the plans, colors will be selected by the Engineer from the manufacturer's standard colors.

## PART 2 - PRODUCTS

### MATERIALS

All sealants, primers and accessories shall be non-staining to adjacent exposed surfaces. Products having similar applications and usage shall be of the same type and same manufacturer. Gun consistency compound shall be used unless otherwise required by the job conditions.

Acrylic Sealant: Acrylic sealant shall be one compound, solvent release acrylic sealant.

Butyl Sealant: Butyl sealant shall be one component, skinning type.

Silicone Sealant: Silicone sealant shall be one component, low modulus building sealant. Sealant shall be tack-free in one hour, shall not sag or flow, shall be ozone resistant and capable of 100 percent extension without failure.

Joint Sealant: Joint sealant shall be a two-part, non sag polysulfide base, synthetic rubber sealant formulated from liquid polysulfide polymer.

Backer Rod: Backer rod shall be round, open or closed cell polyurethane. Backer rod shall be sized such that it must be compressed between 25 percent and 75 percent of its uncompressed diameter during installation in the joint.

Neoprene: Neoprene shall conform to the requirements of ASTM Designation: C 542.

## PART 3 - EXECUTION

### APPLICATION

Unless otherwise shown on the plans, sealants shall be applied in accordance with the manufacturer's instructions.

Silicone sealants shall not be used in locations where painting is required.

Butyl sealants shall not be used in exterior applications, and acrylic sealants shall not be used in interior applications.

Sealants shall be applied in a continuous operation for the full length of the joint. Immediately following the application of the sealant, the sealant shall be tooled smooth using a tool similar to that used to produce concave masonry joints. Following tooling, the sealant shall remain undisturbed for not less than 48 hours.

## SECTION 12-8. DOORS AND WINDOWS

### 12-8.01 HINGED DOORS

### PART 1 – GENERAL

Scope: This work shall consist of furnishing and installing hinged doors and frames in accordance with the details shown on the plans and these special provisions.

**SUBMITTALS**

Manufacturer's descriptive data, installation instructions for fire rated assemblies and a door schedule shall be submitted for approval. The door schedule shall include a description of the type, location and size of each door and frame.

### PART 2 - PRODUCTS

Metal Door:

Metal door shall be flush, seamless steel door factory prepared and reinforced to receive hardware and having cold rolled stretcher leveled sheet steel face sheets not less than 0.048 inch thick (18-gage). Face sheets shall be bonded with thermosetting adhesive to rigid board honeycomb or precured foam core; or face sheets shall be welded to all parts of an assembled grid of cold formed pressed metal stiffeners and framing members located around edges, ends, openings and at all locations necessary to prevent buckling of face sheets. Seams shall be tack welded, filled and ground smooth. Bottom edge and internal stiffeners of grid type core shall have moisture vents. Welds on exposed surfaces shall be ground smooth. Louvered or glazed openings shall be provided where shown on the plans.

Where fire rated doors are required, doors shall be listed and labeled for the fire rating shown on the plans.

Active leaf of double door shall have a full height astragal of 1/8-inch flat bar or folded sheet strip, not less than 0.060 inch thick (16-gage), welded on the outside of the active leaf.

Door shall be cleaned and treated by the bonderized process or approved phosphatizing process and then given one factory application of metal protective rust inhibitive primer. Primer shall not contain lead type pigments.

Glazing for Doors: Glazing for doors shall be safety glass as specified under "Glazing" in Section 12-8, "Doors and Windows," of these special provisions. Glazing shall be not less than 3/16 inch thick.

Pressed Metal Frame:

Pressed metal frame shall be not less than 0.060-inch thick (16-gage) sheet steel with integral stop, mitered corners, face welded and ground smooth corners. Frames shall be reinforced for all hardware and shall be cleaned and treated by the bonderized process or an approved phosphatizing process and then given one factory application of metal protective rust inhibitive primer. Primer shall not contain lead type pigments.

Frames for fire rated doors shall be listed for the same rating shown on the plans for fire rated doors.

Sealants: Sealants shall be ultraviolet and ozone resistant, gun grade polysulfide or polyurethane, multicomponent, Federal Specification: TT-S-227.

### PART 3 - EXECUTION

**INSTALLATION**

Doors and frames shall be installed rigidly, securely, plumb and true and in such a manner that the doors operate freely without rubbing or binding. Clearance between frame and door shall be not more than 1/8 inch. The exterior frame shall be sealed weathertight.

Pressed metal frames shall be secured with clips and anchors as shown on the plans.

Painting: Except for the primer application specified herein, doors and frames shall be cleaned, prepared and painted in accordance with the requirements specified under "Painting" in Section 12-9, "Finishes," of these special provisions.

## 12-8.02 PRESSED METAL FRAMED WINDOWS

### PART 1 - GENERAL

Scope: This work shall consist of furnishing and installing pressed metal framed windows in accordance with the details shown on the plans and these special provisions.

Submittals: Manufacturer's descriptive data, working drawings and installation instructions shall be submitted for approval.

### PART 2 - PRODUCTS

Framing: Framing shall be pressed metal, not less than 0.060 inch thick (16-gage) with all members square and true, full mitered frame corners and continuous welds at all joints and cover plates. Welds at frame faces shall be ground smooth and flush with surrounding surfaces. All metal surfaces shall be cleaned and factory primed with one coat of metal protective rust inhibitive primer. Primer shall not contain lead type pigments.

Anchors: Anchors shall be manufacturer's standard.

Glazing: Glazing shall conform to the requirements specified under "Glazing," in Section 12-8, "Doors and Windows," of these special provisions.

Backer Rod: Backer rod shall be close cell, non-absorbent, non-staining foam rod compatible with sealant.

Sealant: Sealant shall be ultraviolet and ozone resistant, gun grade polysulfide or polyurethane, single component. Sealant shall conform to Federal Specification: TT-S-227.

### PART 3 - EXECUTION

Installation: Frames shall be installed rigidly, securely, plumb and true. Installations shall be sealed watertight and weathertight.

Painting: Except for the primer application specified herein, exposed frame surfaces shall be cleaned, prepared and painted in accordance with the requirements specified under "Painting" in Section 12-9, "Finishes," of these special provisions.

## 12-8.03 FINISH HARDWARE

### PART 1 - GENERAL

#### SUMMARY

Scope: This work shall consist of furnishing and installing hardware items for doors in accordance with the details shown on the plans and these special provisions.

Hardware for special doors and frames, if required, shall be as specified under "Hinged Doors" in Section 12-8 "Doors and Windows," of these special provisions.

Hardware assemblies shall comply with the fire code and the disabled accessibility requirements indicated on the plans and specified in these special provisions.

## SUBMITTALS

Manufacturer's technical information and catalog cuts for each item of door hardware and a door hardware schedule shall be submitted for approval prior to installation.

Manufacturer's catalog cuts shall include catalog numbers, material, grade, type, size, function, design, quality and finish of hardware.

The door hardware schedule shall indicate the location and size of door opening, the door and frame material, and the size, style, finish and quantity of the hardware components required.

## FINISHES

Hardware shall be provided with standard US 26D metal plated finish or sprayed finish where indicated.

## KEYING INSTRUCTIONS

New facilities shall have a building master key system established.

Locks shall have cylinders with figure eight interchangeable cores with six pin barrels. Permanent cores and keys shall be delivered to the Engineer for final installation at completion of project.

The Contractor shall also provide figure eight interchangeable cores for use during construction which shall remain the property of the State.

Key bows shall be stamped "State of California" and "Do Not Duplicate."

# PART 2 - PRODUCTS

## GENERAL

Door hardware equal in material, grade, type, size, function, design, quality and manufacture to that specified herein may be submitted for approval.

Butt Hinges:

Butt hinges shall be steel, 1 1/2-pair per door unless otherwise specified or shown on the plans. Nonremovable pins shall be provided at outswing exterior doors. Hinge size shall be 4½" x 4½" unless otherwise noted.

Standard weight hinges shall be:

| | |
|---|---|
| Hager | BB 1279 |
| McKinney | TB 2714 |
| Stanley | BB 179 |
| or equal. | |

Heavy weight hinges shall be:

| | |
|---|---|
| Hager | BB 1168 |
| McKinney | T4B 37869 |
| Stanley | BB 168 |
| or equal. | |

Mortise Locksets, Latchsets and Privacy Sets:

Mortise locksets, latchsets and privacy sets shall be steel case with 1¼" x 8" face plate and 2¾-inch backset. Door and frame preparation for mortise locksets, latchset and privacy sets shall conform to ANSI A115.1.

Lever operated lockset shall be:

| | |
|---|---|
| Best | 35H 6FW 15H |
| Falcon | LM521 DG |
| Schlage | L9453R x 06 |
| or equal. | |

Lever operated latchset:

| | |
|---|---|
| Best | 35H 0N 15H |
| Falcon | LM101 DG |
| Schlage | L9010 x 06 |
| or equal. | |

Lever operated privacy set:

| | |
|---|---|
| Best | 35H 0L 15H |
| Falcon | LM311 DG |
| Schlage | L9040 x 06 |
| or equal. | |

Cylindrical Locksets, Latchsets and Privacy Sets:

Cylindrical locksets, latchsets and privacy sets shall be steel chassis, 2 1/8-inch diameter, 2¾-inchbackset. Door and frame preparation for cylindrical lockset, latchsets and privacy sets shall conform to ANSI A115.1.

Lever operated lockset shall be:

| | |
|---|---|
| Best | 93K6 AB 9C |
| Schlage | D53RD RHO |
| Falcon | LY501 DG |
| or equal. | |

Lever operated latchset shall be:

| | |
|---|---|
| Best | 93K ON 9C |
| Falcon | LY101 DG |
| Schlage | D10S RHO |
| or equal. | |

Lever operated privacy set shall be:

| | |
|---|---|
| Best | 93K OL 9C |
| Falcon | LY301 DG |
| Schlage | D40S RHO |
| or equal. | |

Cylindrical Dead Locks:

Cylindrical dead locks shall have one-inch throw bolt with concealed hardened steel inserts and one-inch diameter bolt housing, 2¾-inch backset.

Single cylinder dead lock with inside lever turn shall be:

| | |
|---|---|
| Best | 83T 7K |
| Falcon | D441 |
| Schlage | B460R |
| or equal. | |

Flush Bolts:

Flush bolts shall be installed at the top and bottom of the inactive leaf of pairs of doors. Provide automatic bolts on UL rated pairs of doors.

Flush bolts for manual operation shall be:

| | |
|---|---|
| Trimco | 3915 |
| Glynn Johnson | FB6 |
| H.B. Ives | 457 |
| or equal. | |

Flush bolts for automatic operation shall be:

| | |
|---|---|
| Door Control | 840 |
| Glynn Johnson | FB7 |
| H.B. Ives | 559 |
| or equal. | |

Coordinators:

Coordinators shall be installed at pairs of UL rated doors and at pairs of doors having panic devices.

Coordinators shall be:

| | |
|---|---|
| Door Control | 600 |
| Glynn Johnson | GJCOR |
| H.B. Ives | 936 |
| or equal. | |

Door Closers:

Parallel arms for closers shall be installed at outswing exterior doors. Closers shall have sprayed finish to match other hardware on door.

Door closers shall be:

| | |
|---|---|
| LCN | 4040 |
| Norton | 3501-BF |
| Dorma | 7800 |
| or equal. | |

Floor Mounted Stops:

Floor mounted stops shall be dome type. The height of the stop shall be determined by the clearance required when a threshold is used or not used. Floor stops shall be installed within 4" of the adjacent wall.

Stops for openings without thresholds shall be:

| | |
|---|---|
| Builders Brass | 8061 |
| Quality | 331 |
| Trimco | 1210 |
| or equal. | |

Stops for openings with thresholds shall be:

| | |
|---|---|
| Builders Brass | 8063 |
| Quality | 431 |
| Trimco | 1213 |
| or equal. | |

Wall Bumpers:

Wall bumpers base diameter shall be 2½ inches with a one-inch projection.

Bumpers shall be:

| | |
|---|---|
| Builders Brass | WC9 |
| Quality | 302 |
| Trimco | 1270CV |
| or equal. | |

Thresholds, Rain Drips, Door Sweeps and Door Shoes:

Thresholds, rain drips, door sweeps and door shoes shall conform to the sizes and configurations shown on plans. Thresholds at door openings with accessibility requirements shall not exceed ½ inch in height, with a beveled edge.

Threshold, rain drip, door sweep and door shoe manufacturers shall be Pemko, Reese, Zero, or equal.

Threshold Bedding Sealant: Threshold bedding sealant shall conform to Federal Specification: SS-C-153.

Weatherstrip and Draft Stop:

Weatherstrip and draft stop shall conform to the sizes and shapes shown on plans. Assemblies shall be UL listed and shall be provided where shown on the plans or as specified in these special provisions.

Weatherstrip and draft stop manufacturers shall be Pemko, Reese, Zero, or equal.

Door Signs and Name Plates: Door signs and name plates shall be as specified under "Signs" in Section 12-10, "Specialties," of these special provisions.

## PART 3 - EXECUTION

Doors and Frames: Doors and frames shall be set square and plumb and be properly prepared before the installation of hardware.

### INSTALLATION

Hardware items shall be accurately fitted, securely applied, and adjusted and lubricated in accordance with the manufacturer's instructions. Installation shall provide proper operation without bind or excessive play.

Thresholds shall be set in a continuous bed of sealant material.

Door controls shall be set so that the effort required to operate doors with closers shall not exceed 5 pounds maximum for exterior doors and interior doors. The effort required to operate fire doors may be increased above the values shown for exterior and interior doors, by the authority having jurisdiction but shall not exceed 15 pounds maximum.

Door stops located on concrete surfaces shall be fastened rigidly and securely in place with expansion anchoring devices. Door stops mounted elsewhere shall be securely attached with wood screws or expansion devices as required.

Backing shall be provided in wall framing at wall bumper locations.

The location and inscriptions for door signs and name plates shall be as shown on the plans.

Hardware, except hinges, shall be removed from surfaces to be painted before painting.

Upon completion of installation and adjustment, the Contractor shall deliver to the Engineer all dogging keys, closer valve keys, lock spanner wrenches, and other factory furnished installation aids, instructions and maintenance guides.

**DOOR HARDWARE GROUPS AND SCHEDULE**

Hardware groups specified herein shall correspond to those shown on the plans:

**GROUP 1 COMFORT STATION ENTRY DOOR (Single door)**

| | |
|---|---|
| (3) ½ -Pair | Door hinges |
| 1-set | Door Closer |
| 1-set | Mortised Latchset |
| 1-set | Dead Bolt |
| 1-set | Threshold, Door Sweep and Drip Rail |
| 1-set | Door mounted Hold Open |
| 1-set | Floor mounted Door Stop |
| 1-set | Silencer |
| 1-set | Door Weatherstripping |

**GROUP 2 COMFORT STATION ENTRY DOOR (Single door)**

| | |
|---|---|
| (3) ½ -Pair | Door hinges |
| 1-set | Door Closer |
| 1-set | Mortised Privacy set |
| 1-set | Deadbolt |
| 1-set | Threshold, Door Sweep and Drip Rail |
| 1-set | Door mounted Hold Open |
| 1-set | Floor mounted Door Stop |
| 1-set | Silencer |
| 1-set | Door Weatherstripping |

**GROUP 3 UTILITY/STORAGE/ DOORS (Pair of Doors)**

| | |
|---|---|
| (3) ½ -Pair | Door hinges (each door) |
| 1-set | Lever activated Mortised Lock Set |
| 1-set | Mortised Dead bolt |
| 1-set | Astragal |
| 1-set | Door Coordinator |
| 1-set | Top & Bottom locks |
| 1-set | Floor mounted Door Stop |
| 1-set | Threshold, Door Sweep and Drip Rail |

**GROUP 4 CREW ROOM (Single Door, Office)**

| | |
|---|---|
| (3) ½ -Pair | Door hinges |
| 1-set | Door Closer |
| 1-set | Mortised Lockset |
| 1-set | Dead Bolt |
| 1-set | Threshold, Door Sweep and Drip Rail |
| 1-set | Door mounted Hold Open |
| 1-set | Floor mounted Door Stop |
| 1-set | Silencer |
| 1-set | Door Weatherstripping |

**GROUP 5 RESTROOM DOOR**

| | |
|---|---|
| (3) ½ -Pair | Door hinges |
| 1-set | Mortised Privacy set |
| 1-set | Door Closer |

## 12-8.04 GLAZING

## PART 1 - GENERAL

### SUMMARY

Scope: This work shall consist of furnishing and installing glazing in accordance with the details shown on the plans and these special provisions.

Glazing shall consist of glass and acrylic sheets for windows, doors and other glazed openings.

All glass shall conform to ASTM Designation: C 1036 and the classifications specified herein and shall be clear glass except as noted.

All acrylic sheets shall conform to ASTM Designation: D 702, Type III, Grade 3.

Safety glass shall be furnished and installed at all locations designated in Consumer Product Safety Commission's Safety Standard For Architectural Glazing Materials 16 CFR 1201.

### SUBMITTALS

A detailed list of glazing materials including glass, sheet, sealants, tapes, setting blocks, shims, compression seals, and glazing channels shall be submitted for approval. The list shall include a schedule of the materials to be used at each location.

### LABELS

Each individual pane of heat strengthened or fully tempered glass shall bear an identification label in accordance with ASTM Designation: C 1048.

## PART 2 - PRODUCTS

Safety Glass: Safety glass shall conform to Consumer Product Safety Commission Safety Standard For Architectural Glazing Materials: 16 CFR 1201, and ANSI Standard Z97.1 and shall be one of the following:

Wire Glass: Wire glass shall be Type II, Class 1, Form 1, Mesh m1; ¼-inch thick clear polished wire glass with diamond mesh.

Bullet Resistant Acrylic Plastic Sheet: Bullet resistant acrylic plastic sheet shall be 1¼-inch thick, cast acrylic substrate with modified, silica filled, polysiloxane surface coating; UL rated for medium power small arms; 94 percent luminous transmission and one percent haze as determined by ASTM Designation: D 1003-16.

Seals, Caulks, Putties, Setting Blocks, Shims, Tapes, Compression Seals, Felt, Spacers, and Channels: Seals, caulks, putties, setting blocks, shims, tapes, compression seals, felt, spacers, and channels shall be top grade, commercial quality, as recommended by the glass or sheet manufacturer and shall conform to the requirements in the publications of the Flat Glass Marketing Association.

## PART 3 - EXECUTION

### INSTALLATION

Glazing shall conform to the general conditions and applicable details in the publications of the Flat Glass Marketing Association.

Panes shall be bedded fully and evenly, set straight and square within panels in such a manner that the pane is entirely free of any contact with metal edges and surfaces.

For all panes on the exterior of the building, the glazing on both sides of window panes shall provide a watertight seal and watershed. Seals shall extend not more than 1/16 inch beyond the holding members. A void shall be left between the vertical edges of the panes and the glazing channel. Weep systems shall be provided to drain condensation to the outside.

Panes in assemblies using extruded gasket glazing shall be set in accordance with the assembly manufacturer's instructions using gaskets and stops supplied by the manufacturer.

Whenever welding or burning of metal is in progress within 15 feet of glazing materials, a protective cover shall be provided over exposed surfaces.

### REPLACEMENT AND CLEANING

All broken or cracked glass and glass with scratches which reduce the strength shall be replaced before completion of the project.

Panes shall be kept clean of cement and plaster products, cleansers, sealants, tapes and all other foreign material that may cause discoloration, etching, staining, or surface blemishes to the materials.

Excess sealant left on the surface of the glass or surrounding materials shall be removed during the work life of the sealant.

Solvents and cleaning compounds shall be chemically compatible with materials, coatings and glazing compounds to remain. Cleaners shall not have abrasives that scratch or mar the surfaces.

The protective covering on acrylic sheet surfaces shall be left until construction is completed or 2 weeks after glazing, whichever is shorter. The covering shall be removed before adhesives dry sufficiently to adhere to the sheet during removal rather than the protective membrane.

Acrylic sheets shall be protected against scuffs, scratches and marring of the surface during construction and any such damaged sheet shall be replaced or restored to like new condition. Restoration work shall conform to the manufacturer's recommendations.

All panes shall be cleaned just before the final inspection. All stains and defects shall be removed. Paint, dirt, stains, labels (except etched labels), and surplus glazing compound shall be removed without scratching or marring the surface of the panes or metal work.

## SECTION 12-9. FINISHES

### 12-9.01 PORTLAND CEMENT PLASTER

### PART 1 – GENERAL

Scope: This work shall consist of installing lath and applying portland cement plaster in accordance with the details shown on the plans and these special provisions.

Plaster shall be 3 coat work. The total thickness of plaster shall be ¾ inch unless otherwise shown on the plans. The color and the surface finish shall be as shown on the plans.

### PART 2 - PRODUCTS

Sand: Sand shall be lean commercial quality plaster sand.

Cement: Cement shall be portland cement, blended hydraulic cement, or portland cement with a maximum of 15 percent mineral admixture. Portland cement shall be Type II, conforming to ASTM Designation: C 150. Blended hydraulic cement shall be Type IP, conforming to ASTM Designation: C 595. Mineral admixture shall be Class N, Class F or Class C, conforming to ASTM Designation: C 618, except loss on ignition shall not exceed 4 percent.

Lime: Lime shall conform to ASTM Designation: C 206.

Color for Plaster: Color for plaster shall be non-fading, sunproof, and limeproof fine ground synthetic mineral oxide.

Premixed Portland Cement Plaster: Premixed portland cement plaster shall be a premixed packaged blend of cement, lime and sand, with or without color, that requires only water to prepare for use as portland cement plaster, may be furnished. Premixed plaster shall be proportioned as specified herein. Packages of premix shall bear the manufacturer's name, brand, weight and color identification.

Metal Lath: Metal lath shall be self-furring expanded metal diamond mesh with rust inhibitive coating and waterproof vapor barrier backing. Mesh shall weigh not less than 3.4 pounds per square yard.

Metal Lath Fasteners: Metal lath fasteners shall be galvanized or corrosion resistant nails, screws or staples.

Beads, Screeds, Control Joints and Accessories: Beads, screeds, control joints and accessories shall be galvanized steel, not less than 0.022 inch thick.

Vent Screen: Vent screen shall be galvanized sheet steel combination screen and vent with corrosion resistant metal insect screen on the inside.

Water: Water shall be potable.

### PART 3 - EXECUTION

#### INSTALLATION

Metal lath, beads, screeds, control joints, vent screens and other metal accessories shall be installed rigidly and securely in place in accordance with the manufacturer's recommendations.

The type, size and spacing of fasteners for fastening the metal lath and accessories shall be as recommended by the metal lath manufacturer for the type of substrate and the location of the lath and accessories.

**PROPORTIONING AND MIXING**

Materials shall be accurately proportioned and measured for each batch. All batches for a given coat shall be proportioned the same. Plaster shall be proportioned one part cement to between 3 and 5 parts sand by volume, only sufficient water to obtain a workable mix, and a lime plasticizing agent. Not more than 20 pounds of dry hydrated lime or lime putty per sack of cement shall be used in the first and second plaster coat. Plaster for finish coat shall contain not more than 94 pounds of dry hydrated lime or lime putty per sack of cement. Lime shall not be used if mineral admixture or blended hydraulic cement is used.

Frozen materials shall not be used in the mix.

All plaster mixing ingredients shall be mixed in a mechanical mixer. After all ingredients are in the mixer, the plaster shall be mixed for a minimum of 2 minutes. The mixture shall be uniform in color after mixing. Hand mixing of plaster will be allowed only with the written approval of the Engineer.

Plaster to be colored shall be colored by mixing the coloring ingredient uniformly and homogeneously into the plaster. Color, if used, will be required only in materials for the finish coat.

**APPLICATION**

Plaster shall not be applied if the ambient temperature is 40°F or less. Plaster shall not be applied to frost covered or frozen surfaces. Surfaces to receive plaster shall be clean.

The coats of plaster shall be applied continuously in one general direction without allowing mortar to dry at the edges.

The first coat shall be applied with sufficient material and pressure to form full keys and good bond and to cover surfaces. Before setting, the first coat shall be cross-scratched to receive the second coat. The first coat shall be moisture cured, without soaking, for not less than 48 hours after application or until covered by the second coat.

The second coat of plaster shall not be placed until the first coat of plaster has set thoroughly or until at least 12 hours after the first coat of plaster has been placed. The second coat shall be brought out to grounds, straightened to a true, even surface, roughened to assure a bond with the finish coat, and made free of imperfections which would reflect in the finish coat. The second coat shall be moisture cured, without soaking, for not less than 48 hours after application.

The third coat of plaster shall not be placed until at least 7 days after the second coat of plaster has been placed. Troweling of the third coat of plaster shall leave the surface smooth and free from rough areas, trowel marks, checks, or other blemishes. The finished surface shall be true and even and shall not vary more than 1/8 inch in 5 feet from the required plane. Plaster with cracks, blisters, pits, stains, efflorescence, shadowing, dryouts, or checks will not be accepted. Surfaces shall be clean and sound.

The third coat shall have the type of finish shown on the plans.

After all other related work has been completed, pointing around trim and set work and repairing of damaged portions of plaster shall be done. Repairs and patching shall match surrounding work in texture and appearance.

Plaster coats shall be protected against freezing for a period of 24 hours after application.

## 12-9.02 GYPSUM WALLBOARD

### PART 1 – GENERAL

Scope: This work shall consist of furnishing, installing and finishing gypsum wallboard in accordance with the details shown on the plans and these special provisions.

Where assembly fire ratings are indicated on the plans, construction shall provide the fire resistance in accordance with the applicable standards in the Fire Resistance Design Manual published by the Gypsum Association.

Wallboard backing for use in restroom and shower areas shall be water-resistant gypsum backing board.

## PART 2 - PRODUCTS

Gypsum Wallboard**:** Gypsum wallboard shall conform to ASTM Designation: C 36/C 36M.

Gypsum Backing Board**:** Gypsum backing board shall conform to ASTM Designation: C 442/C 442M.

Water-resistant Gypsum Backing Board**:** Water-resistant gypsum backing board shall conform to ASTM Designation: C 630/C C 630M.

Gypsum Sheathing Board**:** Gypsum sheathing board shall conform to ASTM Designation: C 79/C 79M.

Exterior Gypsum Soffit Board**:** Exterior gypsum soffit board shall conform to ASTM Designation: C 931/C 931M.

Joint Tape and Joint and Finishing Compound**:** Joint tape and joint and finishing compound shall conform to ASTM Designation: C 475.

Corner Beads, Metal Trim and Control Joints**:** Corner beads, metal trim and control joints shall be galvanized steel of standard manufacture.

Resilient Metal Channel**:** Resilient metal channel shall be galvanized sheet steel channels of standard manufacture for reducing sound transmission in wood frame partitions.

Fasteners**:** Fasteners shall be gypsum wallboard nails conforming to ASTM Designation: C 514 or steel drill screws conforming to ASTM Designation: C 1002.

## PART 3 - EXECUTION

### DELIVERY AND STORAGE

Materials shall be delivered in original packages, containers or bundles bearing brand name, applicable standard of manufacture, and name of manufacturer or supplier and shall be kept dry and fully protected from weather and direct sunlight exposure. Gypsum wallboard shall be stacked flat with adequate support to prevent sagging or damage to edges, ends and surfaces.

### INSTALLATION

Wallboard panels to be installed on ceilings and soffits shall be installed with the long dimension of the panels perpendicular to the framing members. Wallboard panels to be installed on walls may be installed with the long dimension of the panels either parallel or perpendicular to the framing members. The direction of placing the panels shall be the same on any one wall or partition assembly.

Edges of wallboard panels shall be butted loosely together. All cut edges and ends shall be smoothed as needed for neat fitting joints.

All edges and ends of gypsum wallboard panels shall coincide with the framing members, except those edges and ends which are perpendicular to the framing members. End joints on ceiling and on the opposite sides of a partition assembly shall be staggered.

Except where closer spacings are shown on the plans, the spacing of fasteners shall not exceed the following:

| | |
|---|---|
| Nails | 7 inches |
| Screws | 12 inches |
| Screws at perimeter of panels for fire resistive assemblies having metal framing | 8 inches |

Type S steel drill screws shall be used to fasten wallboard to metal framing. Nails or Type W steel drill screws shall be used to fasten wallboard to wood framing. Except as shown on the plans, screws shall not be used in fire resistive assemblies.

Adhesives shall not be used for securing wallboard to framing.

Gypsum wallboard panels shown on the plans for shear wall sheathing or for fire resistive assemblies shall be fastened to all framing members. Gypsum wallboard panels at other locations and gypsum wallboard finish over plywood sheathed shear walls shall be fastened to all framing members except at the following locations:

At internal angles formed by ceiling and walls; ceiling panels shall be installed first with the fasteners terminating at a row 7 inches from the walls, except for walls parallel to ceiling framing. Wall panels shall butt the ceiling panels. The top row of wall panel fasteners shall terminate 8 inches from the ceiling.

At internal vertical angles formed by the walls; fasteners shall not be installed along the edge or end of the panel that is installed first. Fasteners shall be installed only along the edge or end of the panel that butts and overlaps the panel installed first.

Fasteners shall be located at least 3/8 inch from wallboard panel edges and ends. Nails shall penetrate into wood framing at least 1 1/8 inches. Screws shall penetrate into wood framing at least 5/8 inch. All metal fasteners shall be driven slightly below surface level without breaking the paper or fracturing the core.

Metal trim shall be installed at all free edges of panels, at locations where wallboard panels abut dissimilar materials and at locations shown on the plans. Corner beads shall be installed at external corners. Control joints shall be installed at the locations shown on the plans.

Joints between face panels, the internal angles formed by ceiling and walls and the internal vertical angles formed by walls shall be filled and finished with joint tape and at least 3 coats of joint compound. Tape in the corners shall be folded to conform to the angle of the corner. Tape at joints and corners shall be embedded in joint compound.

Dimples at nail and screw heads, dents, and voids or surface irregularities shall be patched with joint compound. Each patch shall consist of at least 3 coats and each coat shall be applied in a different direction.

Flanges of corner beads, control joints and trim shall be finished with a least 3 coats of joint compound.

Each coat of joint compound shall be feathered out onto the panel surface and shall be dry and lightly sanded before applying the next coat. The finished surfaces of joint compound at the panel joints, internal angles, patches and at the flanges of trim, corner beads and control joints shall be flat and true to the plane of the surrounding surfaces and shall be lightly sanded.

Good lighting of the work area shall be provided during the final application and sanding of the joint compound.

Gypsum wallboard used as backing boards for tile or rigid sheet wall covering or wainscotting shall be water resistant. Joints in backing board shall not be taped or filled and dimples at the fastener heads shall not be patched. Edges of cuts and holes in backing board shall be sealed with a primer or sealer that is compatible with the wall covering or wainscotting adhesive to be used.

Surfaces of wallboard to be textured shall receive an orange peel texture, unless otherwise shown on the plans.

## 12-9.03 CERAMIC TILE

## PART 1 - GENERAL

### SUMMARY

Scope**:** This work shall consist of furnishing and installing ceramic tile in accordance with the details shown on the plans and these special provisions.

Ceramic tile shall include matte porcelain tile, trim tile, setting materials, grouts and such other materials as maybe required for a complete installation.

**SUBMITTALS**

Product Data**:**

Manufacturer's descriptive data, a list of materials to be used, and installation instructions for all materials required for the work shall be submitted for approval.

Manufacturer’s descriptive data shall be submitted for each type of tile, mortar bed materials, bond coat materials and additives, and grout materials and additives.

Materials list and installation instructions shall include all products and materials to be incorporated into the work.

Samples**:** Samples shall include 2 individual samples of each type and color of tile and trim to be installed and shall be of the same size, shape, pattern and finish as the tile and trim to be installed.

**QUALITY ASSURANCE**

Single Source Responsibility**:** Each type and color of tile, grout and setting materials shall be obtained from a single source.

Master Grade Certificates**:** Each shipment of tile to the project site shall be accompanied by a Master Grade Certificate issued by the tile manufacturer.

Certificates of Compliance**:** Certificates of compliance shall be furnished for bond coat materials, setting bed materials and grout in accordance with the requirements specified in Section 6-1.07, "Certificates of Compliance," of the Standard Specifications.

**DELIVERY, STORAGE AND HANDLING**

Delivery**:** Tile and packaged materials shall be delivered to the job site in sealed, unbroken, unopened containers with the labels intact. Tile containers shall bear the Standard Grade label.

Storage and Handling**:** Materials shall be stored and handled in such a manner as to prevent damage or contamination by water, freezing or foreign matter.

**PROJECT CONDITIONS**

Protection**:** Tile work shall be protected and environmental conditions maintained during and after installation to comply with the reference standards and manufacturer's printed instructions.

Temperatures**:**

Unless otherwise specified in the manufacturer’s installation instructions, the ambient temperature shall be maintained at not less than 50°F nor more than 100°F in tiled areas during installation and for 7 days after completion. Exterior work areas shall be shaded from direct sunlight during installation.

Tile shall not be installed when the temperature of the substrate is greater than 90°F or is frost covered.

Illumination**:** Interior work areas shall be illuminated to provide the same level and angle of illumination as will be available during final inspection.

## PART 2 - PRODUCTS

### MANUFACTURERS

Available Manufacturers**:** Subject to compliance with the specifications, tile shall be American Olean Tile Co., Inc.; Summitville Tiles, Inc.; United States Ceramic Tile Co.; or equal.

### GENERAL

Tile Color and Size**:** Tile color shall be as shown on the plans; tile size shall be as indicated in the Schedule elsewhere in this special provision.

### TILE PRODUCTS

Matte Porcelain Tile:

Matte porcelain tile shall be machine made, unpolished, dust pressed natural porcelain clay and shall have a plain face. Tile shall have a nominal thickness of 5/16 inch. Matte porcelain tile shall be slip resistant.

Matte porcelain trim tile shall include cove type base at walls and single piece intersecting cove base at corners.

### SETTING MATERIALS

Portland Cement Mortar Installation Materials: Materials for portland cement mortar installation shall conform to the requirements in ANSI Standard: A108.1 as required for installation method designated, unless otherwise indicated.

Membrane: Membrane shall be asphalt impregnated felt conforming to ASTM Designation: D 226, Type I, or polyethylene film conforming to ASTM Designation: C 171, Type 1.1.2. Polyethylene film shall not be less than 4 mils thick.

Reinforcement: Reinforcement shall be galvanized welded wire fabric with 2" x 2"-W0.3 x W0.3 conforming to ASTM Designations: A 82 and A 185 except for minimum wire size. Reinforcement shall be provided in flat sheets.

Metal Lath: Metal lath shall be self furring, galvanized, conforming to ASTM Designation: C 847, flat expanded type weighing not less than 2.5 pounds per square yard. Factory assembled metal lath and paper backing may be used where reinforcement over paper is shown on the plans.

Tile Bond Coat:

Tile bond coat shall be latex-portland cement bond coat.

Latex-portland cement mortar bond coat shall be a prepackaged mortar mix, conforming to ANSI Standard: A118.4, incorporating a dry acrylic resin, and to which only water is added at the job site. Mortar shall be suitable for exterior use and be labeled for the type of tile to be installed.

### GROUTING MATERIALS

Tile Grout:

Tile grout shall be latex-portland cement grout.

Latex-portland cement grout shall be a prepackaged grout mix, conforming to ANSI Standard: A118.6, incorporating a dry acrylic resin, and to which only water is added at the jobsite. Grout shall be suitable for exterior use and labeled for the type of tile to be installed.

Grout Pigment: Grout pigment shall be chemically inert, fade resistant mineral oxide or synthetic type. Color shall be as shown on the plans.

**SEALANTS**

Sealant:

Sealant for vertical expansion joints shall be a medium modulus silicone or polyurethane. Sealant for horizontal joints shall be a 2-part polyurethane type material with a Shore Hardness of 35 to 45.

**MORTAR BEDS**

Cement Mortar Bed:

Cement mortar bed for walls shall be proportioned of one part cement, ½ part hydrated lime, 6 parts damp sand by volume and only enough water to provide the necessary workability. Ingredients shall be dry mixed, water added, and materials blended to produce a stiff mix. Mortar bed shall be not less than ¾ inch in thickness.

Cement mortar bed for floors shall be proportioned of one part cement, 1/10 parts hydrated lime, 5 parts damp sand by volume and only enough water added to provide the necessary workability. Ingredients shall be dry mixed, water added, and materials blended to produce a stiff mix. Mortar bed shall be not less than 1¼ inches in thickness.

**MISCELLANEOUS MATERIALS**

Sand: Sand shall be a natural or manufactured sand conforming to ASTM Designation: C 144, except that no more than 10 percent shall pass the No. 100 sieve.

Sealers:

Sealer for unglazed quarry tile shall be water repellent, clear solution of ammonium cementitious compound, silicone base material, or other commercially manufactured sealer.

Sealer for grout shall be a penetrating proprietary compound designed for sealing grout. Silicone sealers shall not be used.

Cement: Cement shall conform to ASTM Designation: C 150, Type I.

Hydrated Lime: Hydrated lime shall conform to ASTM Designation: C 206, Type S, or ASTM Designation: C 207, Type S.

Water: Water shall be clean and potable.

Metal Edge Strips: Metal edge strips shall be stainless steel terrazzo strips, 1/8 inch wide at top edge with integral provision for anchorage to mortar bed or substrate.

**MIXING MORTAR AND GROUT**

Mixing: Mortar and grout shall be mixed to comply with the requirements of referenced standards and manufacturers for accurately proportioning of materials, water or additive content, mixing equipment and mixer speeds, mixing containers, mixing time, and other procedures need to produce mortars and grout of uniform quality with optimum performance characteristics for application intended.

## PART 3 - EXECUTION

### PREPARATION

Concrete, mortar, or masonry substrate surfaces which are to receive a mortar bed shall not vary more than ¼ inch in 8 feet from the required plane and shall be true, plumb at vertical surfaces, and square at intersection edges.

Surfaces to receive a mortar setting bed or a bond coat shall be cleaned adequately to assure a tight bond to the applied material. Such cleaning shall leave the surface thoroughly roughened and free from laitance, coatings, oil, sand, dust and loose particles.

The cleaned surfaces which are to receive a mortar bed shall be saturated with water just prior to placing mortar or the cleaned surfaces shall be coated with fresh neat cement slurry. If the surface is saturated with water, excess water shall be removed and the wetted surfaces uniformly dusted with portland cement. The slurry or wetted cement dust shall be broomed to completely coat the surface with a thin and uniform coating just prior to placing the mortar.

Substrates shall be inspected to insure that grounds, anchors, plugs, recessed frames, bucks, drains, electrical work, mechanical work, and similar items in or behind the tile have been installed before proceeding with installation of the tiles.

### INSTALLATION

Tile installation shall conform to applicable parts of ANSI 108 Series of the tile installation standards included under "American National Standard Specifications for the Installation of Ceramic Tile" and Tile Council of American, "Handbook for Ceramic Tile Installation."

All tile shall be installed on a bond coat over a setting bed. The setting bed shall be a cured cement mortar bed or a prepared, dimensionally stable substrate of concrete, masonry, cementitious backer board, or other cementitious material.

The back face of the tile shall be free of paper, adhesives, fiber mesh, resins, or other materials affecting the bond of the tile to the bedding material.

Tile sheets shall have permanent edge bonding or temporary mounting materials on the exposed face. Water soluble or absorbent adhesives shall not be used for edge bonding. Temporary mounting materials shall allow observation during tile setting operations.

Tile work shall extend into recesses and under or behind equipment and fixtures, to form a complete covering without interruptions, except as shown on the plans. Work shall be terminated neatly at obstructions, edges and corners without disrupting pattern or joint alignments.

Intersections and returns shall be accurately formed. Cutting and drilling of tile shall be performed without marring visible surfaces. Cut edges of tile abutting trim, finish or built-in items shall be carefully ground to produce straight aligned joints. Tile shall be closely fit to electrical outlets, piping, fixtures and other penetrations such that plates, collars, or covers overlap the tile.

Mortar Bed Placement:

The mortar bed, with or without reinforcement as shown on the plans, shall be placed, consolidated, and finished to the required thickness.

The surface of the mortar bed shall be true and pitched as shown on the plans, without high or low spots. The mortar bed surface shall not vary more than 1/8 inch in 8 feet from a plane parallel to the finished tile surface when tile is installed on a cured mortar bed.

In no case shall the allowed tolerances result in offsets between adjoining tiles, low spots on finished tile surfaces than can pond water, or finished tile surfaces that are not plumb or not true.

Pea gravel mortar shall be tightly compacted so as to fill all voids in the aggregate. Compaction shall be obtained using a stand-up wooden tamper weighing not less than 35 pounds or using a motor driven tamper and leveler.

Cement mortar beds to receive a tile bond coat shall be damp cured under cover for a minimum of 48 hours at a temperature of not less than 70°F.

Tile Bond Coat:

The tile bond coat mortar shall be mixed according to the manufacturer's recommendations. The consistency of the mixture shall be such that ridges formed with the recommended notched trowel shall not flow or slump. Reworking will be allowed provided no water or materials are added. The setting bed surfaces shall be dampened before placing the bond coat as necessary tile installation, but the setting bed shall not be soaked. The setting bed surfaces for epoxy bond coat shall be dry.

The bond coat shall be floated onto the cured mortar bed surface with sufficient pressure to cover the surface evenly with no bare spots. The surface area to be covered with the bond coat shall be no greater than the area that can be tiled while the bond coat is still plastic. The bond coat shall be combed with a notched trowel as recommended by the manufacturer within 10 minutes before installing tile. Tile shall not be installed on a skinned over bond coat.

Installing Tiles:

Tile shall be installed in accordance with the manufacturer's instructions and shall be set solid and shall be well bonded to the substrate.

Tile set on a tile bond coat shall be installed in accordance with ANSI Standard: A108.5, and tile set on an epoxy mortar shall be installed in accordance with ANSI Standard: A108.6.

If tiles are cut, the cuts shall be made with saws. Cut edges shall be rubbed with an abrasive stone to bring the edge of the glaze slightly back from the body of the tile. Cuts shall be accurately made to neatly fit the tile in place. Cut edges shall not be butted against other tile. Cut tile shall be at least half the size of a full size tile.

Tile shall completely cover wall areas behind mirrors and fixtures.

Tile shall be installed so that the finished tile surface does not vary more than 1/8 inch in 8 feet from the finished tile surface shown on the plans. In no case shall there be offsets in adjoining tiles, low spots on finished tile surfaces that can pond water, or finished tile surfaces that are not plumb or true in the completed tile work.

Tiles shall be firmly pressed into the freshly notched bond coat. Tile on interior surfaces shall be tapped and beat into a true surface and to obtain at least 80 percent coverage by the mortar on the back of each tile. Tile on exterior surfaces shall have 100 percent coverage and shall be back-buttered immediately prior to setting the tile.

If tile is face mounted, the paper and glue shall be removed within one hour after tile is installed and all tiles that do not meet the requirements for joints and surface tolerance shall be adjusted or replaced.

Mortar that exudes into the grout spaces between tiles shall be removed to the bottom of tile.

Joints: Joints between tile shall be continuous both vertically and horizontally. Joints shall be straight and of uniform and equal width. Where tiles on adjoining surface are the same size, the joints shall align, one with the other. Joint width shall be as recommended by the tile manufacturer.

Grouting Tile:

Grout shall be mixed, applied and cured in accordance with the manufacturer's recommendations and ANSI Standard: A108.10 for cement grout and ANSI Standard: A108.9 for epoxy grout.

Spacers, strings, ropes, pegs, glue, paper, and face mounting material shall be removed before grouting. Joints between glazed wall tile shall be wetted if they have become dry. Joints for epoxy mortar shall be dry.

Grouting shall not begin until at least 48 hours after installing tile.

A maximum amount of grout shall be forced into the joints between tiles in accordance with the manufacturer's recommendations. The grout shall be finished to the depth of the cushion for cushion edge tile and finished flush with the surface for square edge tile. All gaps and skips in the grout spaces shall be filled.

Mortar or mounting mesh shall not show through the grouted joints.

The finished grout shall have a uniform color and shall be smooth without voids, pinholes or low spots.

Expansion joints shall be kept free of grout or mortar.

Grout shall be protected from freezing or frost for a least 5 days after installation.

Expansion Joints:

Expansion joints shall be installed at the perimeter of all tile floors and at all substrate control joints and changes in the substrate material. Exterior expansion joint spacing shall not exceed 16 feet in any direction.

All expansion joints shall be made with sealant over backer rods. The thickness of sealant at the center of expansion joints shall not exceed the width of the joint. Joint edges shall be primed as recommended by the sealant manufacturer.

Edge Strips: Edge strips shall be installed at openings where the threshold has not been shown on the plans, but where tile floor abuts other flooring materials at the same level. Edge strips shall be installed centered under the closed door, or where there is no door, centered in the opening.

Sounding Tile: Tiled surfaces shall be sounded with a metal bar or chain for improperly bonded tile or setting bed. Tile or setting bed that emits a hollow sound shall be replaced.

Replacement: Cracked, chipped, broken, or otherwise defective tiles shall be removed and replaced. All tiles which differ more than 1/16 inch in elevation from adjacent tile edges shall be removed and replaced.

Curing:

After the installation of tile and the grouting of joints, the tile and grout shall be cured by keeping the surface continuously damp for at least 72 hours after grouting. Curing materials shall not stain the tile or grouted joints. Curing methods shall not erode away the grout.

After grouting, horizontal tiled surfaces shall be closed to traffic, and all tiled surfaces shall be kept free from impact, vibration or shock, for at least 72 hours.

**CLEANING AND PROTECTION**

Cleaning Tile Surfaces:

All exposed tile surfaces shall be cleaned of all grout haze upon completion of grouting. Acids and chemicals used to clean tile shall conform to the tile manufacturer's recommendations. Cleaners shall not be harmful to materials on surfaces of abutting floors, walls, and ceilings. Tile work shall be rinsed thoroughly with clean water before and after using acid or chemical cleaners. After cleaning and rinsing, tile surfaces shall be polished using a soft cloth.

Tile work shall be cleaned and polished again immediately prior to completion of the contract. All dirt, grime, stains, paints, grease, and other discoloring agents or foreign materials shall be removed.

Protection:

After grouting, horizontal tiled surfaces shall be closed to traffic, and all tiled surfaces shall be kept free from impact, vibration or shock, for at least 72 hours after.

Tile surfaces damaged by construction operations shall be retiled.

**SCHEDULES**

Wall Tile:

Wall tile shall be nominal 4" x 4" glazed wall tile.

Installation on mortar bed, using a tile bond coat and grout, shall conform to the requirements of Method W 222, "Handbook for Ceramic Tile Installation."

Installation on concrete and masonry shall be on a mortar bed using tile bond coat and grout, and shall conform to the requirements of Method W 211, "Handbook for Ceramic Tile Installation.

## 12-9.04 RESILIENT BASE

### PART 1 - GENERAL

Scope: This work shall consist of furnishing and installing resilient base in accordance with the details shown on the plans and these special provisions.

**SUBMITTALS**

Manufacturer's descriptive data, installation instructions, color palette, and samples of resilient base shall be submitted for approval. Samples shall be not less than 2 inches in length.

### PART 2 - PRODUCTS

Resilient Base: Resilient base shall be manufacturer's best grade, rubber or vinyl base, with premolded internal and external corner pieces. The height and color shall be as shown on the plans.

Adhesive: Adhesive shall be as recommended by base manufacturer.

### PART 3 - EXECUTION

**INSTALLATION**

Bases shall be firmly and totally attached to walls with adhesive and shall be accurately scribed to trim, molding and cabinets. All joints shall be tight fitting. Bases between premolded corners or other termini may be installed continuous or installed using 4-foot minimum standard manufactured lengths. Filler pieces shall be not less than 18 inches.

## 12-9.05 VINYL COMPOSITION TILE

### PART 1 - GENERAL

Scope: This work shall consist of furnishing and installing vinyl composition tile in accordance with the details shown on the plans and these special provisions.

Vinyl composition tile shall consist of vinyl composition tile, edger strips, floor wax and tile manufacturer's recommended primers and adhesives.

### SUBMITTALS

Manufacturer's descriptive data, installation instructions, color and pattern samples shall be submitted for approval. Samples of tile shall be 12" x 12" in size.

## PART 2 - PRODUCTS

Vinyl Composition Tile: Vinyl composition tile shall be semi-flexible, 3/32-inch minimum thickness, 12" x 12" tile conforming to Federal Specification: SS-T-312, Type IV. Color and pattern shall be as shown on the plans.
Primer, Leveling Compound Crack Filler and Adhesives: Primer, leveling compound crack filler and adhesives shall be waterproof types as recommended by the tile manufacturer.

Wax: Wax shall be water emulsion, self-polishing type containing not less than 16 percent wax solids, wetting agents, and a nonslip agent. The wax shall meet UL antislip standards.

Edger Strips: Edger strips shall be commercial quality, stainless steel or aluminum.

## PART 3 - EXECUTION

### PREPARATION

Before placing adhesives, all surfaces to receive vinyl composition tile shall be made free of localized depressions or bumps. Bumps shall be ground flat. Holes, depressions and cracks shall be filled with crack filler or leveling compound.

Immediately prior to application of the tile flooring, the surface to be covered shall be thoroughly dry, free of paint, oil, grease, mortar, plaster droppings, scaly surfaces or other irregularities and shall be broom clean. Primer, when recommended, shall be thoroughly brushed on the surface at the rate recommended by the adhesive manufacturer and shall be completely dry before the application of adhesives.

The rooms where tile is to be installed shall be maintained at a temperature of at least 70°F for not less than 72 hours before installation, during installation and for 5 days after installation.

### APPLICATION

Tile shall be laid to a true, straight, smooth and even finished surface in accordance with the manufacturer's instructions. Joints shall be tight fitting. Floor covering shall be placed before floor mounted fixtures are installed. After tile has been set, the finished surface shall be rolled and crossrolled with a roller weighing 100 pounds or more.

Edger strips shall be installed at free edges.

Where tile patterns between rooms differ, the pattern break at openings shall occur at the centerline of the common wall.

Upon completion of the tile application, all stains, surplus adhesive, dirt and debris resulting from the work shall be removed and the floor left broom clean. Tile shall be protected from damage at all times during construction. As a last order of work, tile shall be washed with soap and warm water, rinsed, and then waxed in accordance with the tile manufacturer's printed instructions. Not less than 2 applications of wax shall be placed on the tile flooring.

# 12-9.06 RESILIENT SHEET FLOORING

## PART 1 - GENERAL

Scope: This work shall consist of furnishing and installing resilient sheet flooring in accordance with the details shown on the plans and these special provisions.

Resilient sheet flooring shall also include cove molding, metal caps, edger strips, floor wax and flooring manufacturer's recommended primers and adhesives.

**SUBMITTALS**

Manufacturer's descriptive data, installation instructions, color and pattern samples shall be submitted for approval. Samples of sheet flooring shall be 12" x 12" in size.

## PART 2 - PRODUCTS

Resilient Sheet Flooring: Resilient sheet flooring shall be flexible vinyl sheet not less than 0.085 inch thick. Color and pattern shall be as shown on the plans.

Primer, Leveling Compound Crack Filler and Adhesives: Primer, leveling compound crack filler and adhesives shall be waterproof types as recommended by the flooring manufacturer.

Wax: Wax shall be water emulsion, self-polishing type containing not less than 16 percent wax solids, wetting agents, and a nonslip agent. The wax shall meet UL antislip standards.

Cove Molding: Cove molding shall be commercial quality wood, rubber or plastic.

Edger Strips: Edger strips shall be commercial quality, stainless steel or aluminum.

Metal Caps: Metal caps shall be commercial quality, noncorrosive metal.

## PART 3 - EXECUTION

**PREPARATION**

Before placing adhesives, all surfaces to receive resilient sheet flooring shall be made free of localized depressions or bumps. Bumps shall be ground flat. Holes, depressions and cracks shall be filled with crack filler or leveling compound.

Immediately prior to installation of the resilient sheet flooring, the surface to be covered shall be thoroughly dry, free of paint, oil, grease, mortar, plaster droppings, scaly surfaces or other irregularities and shall be broom clean. Primer, when recommended, shall be thoroughly brushed on the surface at the rate recommended by the adhesive manufacturer and shall be completely dry before application of adhesives.

The rooms where resilient sheet flooring is to be installed shall be maintained at a temperature of at least 70°F for not less than 72 hours before installation, during installation and for 5 days after installation.

**INSTALLATION**

Resilient sheet flooring shall be laid to a true, straight, smooth and even finish surface in accordance with the manufacturer's instructions. Resilient sheet flooring shall be laid parallel to building lines with the minimum of seams using manufacturer's standard widths. Seams shall be tight fitting, fully bonded along their length and present a continuous pattern.

Resilient sheet flooring shall be placed before floor mounted fixtures are installed.

After resilient sheet flooring has been installed, the finished surface shall be rolled and crossrolled with a roller weighing 100 pounds or more.

Edger strips shall be installed at free edges.

Upon completion of the flooring installation, all stains, surplus adhesive, dirt and debris resulting from the work shall be removed and the floor left broom clean. Resilient sheet flooring shall be protected from damage at all times during

construction. As a last order of work, floor covering shall be washed with soap and warm water, rinsed, and then waxed in accordance with the floor covering and wax manufacturers' printed instructions. Not less than 2 applications of wax shall be placed on the floor covering.

## 12-9.07 PAINTING

### PART 1 - GENERAL

Scope: This work shall consist of preparing surfaces to receive coatings, and furnishing and applying coatings, in conformance with the schedules and details shown on the plans and these special provisions.

The coatings specified in this section are in addition to any factory finishes, shop priming, or surface treatment specified elsewhere in these special provisions.

#### DEFINITIONS

Detergent Wash: Removal of dirt and water-soluble chemicals by scrubbing with a solution of detergent and water, and removal of all solution and residues with clean water.

Hand Cleaning: Removal of dirt, loose rust, mill scale, excess base material, filler, aluminum oxide, chalking paint, peeling paint, or paint that is not firmly bonded to the surfaces by using hand or powered wire brushes, hand scraping tools, power grinders, or sandpaper and removal of all loose particles and dust prior to coating.

Mildew Wash: Removal of mildew by scrubbing with a solution of detergent, hypochlorite-type household bleach, and warm water, and removal of all solution and residues with clean water.

Abrasive Blasting:

Removal of loosely adhering paint, dirt, rust, mill scale, efflorescence, weak concrete, or laitance, shall be by the use of airborne abrasives. Loose particles, dust, and abrasives shall be removed by blasting with clean, oil-free air.

Abrasives shall be limited to mineral grit, steel grit, or steel shot, and shall be graded to produce the surface profile recommended in the manufacturer's data sheet.

Steam Cleaning: Removal of oil, grease, dirt, or other foreign matter by using steam generated by commercial steam cleaning equipment, from a solution of water and steam cleaning compounds, and removal of all residues and cleaning compounds with clean water.

TSP Wash: Removal of oil, grease, dirt, paint gloss, and other foreign matter by scrubbing with a solution of trisodium phosphate and warm water, and removal of all solution and residues with clean water.

Water Blasting: Removal of dirt, loose scale, chalking, or peeling paint by low-pressure water cleaning. Water blasting shall be performed in conformance with the requirements in SSPC-SP12 and shall produce a surface cleanliness meeting the requirements of SSPC-SP12-WJ4. Equipment used shall have a minimum flow rate of 1.5 GPM. If a detergent solution is used, it shall be biodegradable and shall be removed from all surfaces with clean water.

Protection:

The Contractor shall provide protective devices, such as tarps, screens or covers, as necessary to prevent damage to the work and to other property or persons from all cleaning and painting operations.

Paint or paint stains on surfaces not designated to be painted shall be removed by the Contractor at the Contractor's expense and the original surface shall be restored.

#### SUBMITTALS

Manufacturer's descriptive data, a materials list, and color samples shall be submitted for approval.

Product descriptive data shall include product description, manufacturer's recommendations for product mixing, thinning, tinting, handling, site environmental requirements, product application, and drying time.

Materials list shall include manufacturer's name, trade name, and product numbers for each type coating to be applied.

Color samples shall be manufacturer's color cards, approximately 2" x 3", for each color of coating shown on the plans. Color samples for stains shall be submitted on wood of the same species, color, and texture as the wood to receive the stain.

**QUALITY ASSURANCE**

Certificates of Compliance: Certificates of Compliance shall be furnished when products are required to conform with the requirements of The Society for Protective Coatings (SSPC) in conformance with the requirements specified in Section 6-1.07, "Certificates of Compliance," of the Standard Specifications.

**REGULATORY REQUIREMENTS**

Coatings and applications shall conform to the rules for control of Volatile Organic Compound (VOC) emissions adopted by the air quality control district in the air basin in which the coatings are applied.

**SITE ENVIRONMENTAL REQUIREMENTS**

Coatings shall be applied in conformance with the environmental constraints specified in the manufacturer's printed instructions. These conditions shall be maintained until the coating has cured and is ready for recoat.

Continuous ventilation shall be provided during application of the coatings.

Adequate lighting, as determined by the Engineer, shall be provided while surfaces are being prepared for coatings and during coating applications.

**DELIVERY, STORAGE, AND HANDLING**

Products shall be delivered to the site in sealed, labeled containers and stored in a well-ventilated area at an ambient air temperature of not less than 45°F. Container labeling shall include manufacturer's name, type of coating, trade name, color designation, drying time, and instructions for tinting, mixing, and thinning.

**MAINTENANCE STOCK**

Upon completion of coating work, a full one-gallon container of each type and color of finish coat and stain used shall be delivered to the location at the project site designated by the Engineer. Containers shall be tightly sealed and labeled with color, texture, and room locations where used, in addition to the manufacturer's standard product label.

## PART 2 - PRODUCTS

Products for each coating system shall be from a single manufacturer and shall conform to the requirements in the Detailed Performance Standards of the Master Painters Institute (MPI). Each product shall be shown on the MPI Approved Products List unless otherwise specified in these special provisions.

## PART 3 - EXECUTION

**INSPECTION**

Coatings shall not be applied until surface preparation has been approved by the Engineer. The Contractor shall notify the Engineer at least 3 working days prior to the application of coatings.

## SURFACE PREPARATION

Surfaces scheduled to be coated shall be prepared in conformance with the coating manufacturer's printed instructions unless otherwise specified in these special provisions.

Hardware, cover plates, light fixture trim, and similar items shall be removed prior to preparing surfaces for coating. Following the application of the finish coating, the removed items shall be reinstalled in their original locations.

Galvanized Metal:

New surfaces shall be roughened by hand sanding or light abrasive blasting. Galvanizing shall not be removed during cleaning or roughening.

Damaged or corroded areas shall be cleaned and given 2 spot applications of a coating that conforms to the requirements in the Detailed Performance Standards of the MPI, and listed on MPI List "Number 18, Primer, Zinc Rich, Organic."

Steel and Other Ferrous Metals: Surface shall be cleaned in conformance with the requirements in SSPC-SP 1. Surface profile shall be as required for the coating system specified.

Aluminum and Other Non-ferrous Metals: Surface shall be cleaned in conformance with the requirements in SSPC-SP 1.

Gypsum Board: Holes, cracks, and other surface imperfections shall be filled with joint compound or suitable filler prior to application of coatings. Taped joints and filled areas shall be hand sanded to remove excess joint compound and filler.

Cement Plaster: New plaster shall be cured a minimum of 14 days before coating. Cracks, holes, and surface imperfections shall be filled with patching plaster and hand textured to match adjacent surfaces.

Concrete and Concrete Masonry Unit: New material shall be cleaned and prepared in conformance with the requirements in SSPC-SP 13. Cracks and voids shall be filled with cement mortar patching material. Concrete shall be cured until the surface moisture is below the level specified in the coating manufacturer's printed instructions.

Previously Coated Surfaces:

Dirt, oil, grease, or other surface contaminants shall be removed by water blasting, steam cleaning, or TSP wash. Minor surface imperfections shall be filled as required for new work. Mildew shall be removed by mildew wash. Chalking paint shall be removed by hand cleaning. The surfaces of existing hard or glossy coatings shall be abraded to dull the finish by hand cleaning or light abrasive blasting. Abrasive blasting shall not be used on wood or non-ferrous metal surfaces.

Chipped, peeling, blistered, or loose coatings shall be removed by hand cleaning, water blasting, or abrasive blasting. Bare areas shall be pretreated and primed as required for new work.

## APPLICATION

Coatings shall be applied in conformance with the printed instructions and at the application rates recommended by the manufacturer to achieve the dry film thickness stated in the coating technical data sheet.

Mixing, thinning and tinting shall conform to the manufacturer's printed instructions. After thinning, the coating shall conform to the regulatory requirements in these special provisions.

Coatings shall be applied only when surfaces are dry and properly prepared.

Cleaning and painting shall be scheduled so that dust and other contaminants from the cleaning process will not fall on wet, newly coated surfaces.

Materials required to be coated shall have coatings applied to all exposed surfaces, including the tops and bottoms of wood and metal doors, the insides of cabinets, and other surfaces not normally visible from eye level.

Surface Finish Application:

Each coat shall be applied to a uniform finish. Finished surfaces shall be free of surface deviations and imperfections such as skips, cloudiness, spotting, holidays, laps, brush marks, runs, sags, curtains, ropiness, improper cutting in, overspray, drips, ridges, waves, and variations in color and texture.

Each application of a multiple application finish system shall closely resemble the final color coat, except each application shall provide enough contrast in shade to distinguish the separate applications.

Work Required Between Applications:

Each application of material shall be cured in conformance with the coating manufacturer's printed instructions before applying the succeeding coating.

Stain blocking primer shall be spot applied whenever bleeding substances are visible through the previous application of a coating.

Timing of Applications: The first application of the coating system shall be during the same work shift that the final surface preparation was performed. Additional coats shall be applied as soon as the required drying time of the preceding coat, specified in the coating manufacturer's printed instructions, has been met.

Application Methods:

Coatings shall be applied by brush, roller or spray. Rollers shall be of a type which do not leave a stippled texture in the paint film. Extension handles for rollers shall not be greater than 6 feet in length.

If spray methods are used, surface deviations and imperfections such as overspray, thickness deviations, lap marks, and orange peel shall be considered as evidence the work is unsatisfactory and the Contractor shall apply the remainder of the coating by brush or roller, as approved by the Engineer.

Back Priming:

The first application of the coating system shall be applied to all wood surfaces (face, back, edges, and ends) of wood materials that are not factory coated, immediately upon delivery to the project site. Surfaces of interior finish woodwork that adjoin concrete or masonry shall be coated with one application of exterior wood primer before installation.

Patches in Previously Coated Surfaces: Where patches are made on surfaces of previously coated walls or ceilings, the entire surface to corners on every side of the patch shall be coated with a minimum of one application of the finish coat.

Finishing Mechanical and Electrical Components:

Shop primed mechanical and electrical components shall be finish coated in conformance with the coating system specified for the substrate material. Louvers, grilles, covers, and access panels on mechanical and electrical components shall be removed and coated separately.

Interior surfaces of air ducts which are visible through grilles or louvers shall be coated with one application of flat black enamel, to limit of the sight line.

Exposed conduit, piping, and other mechanical and electrical components shall be painted.

Both sides and all surfaces, including edges and back of wood mounting panels for electrical and telephone equipment shall be finish coated before installing equipment.

**CLEANING**

Upon completion of all operations, the coated surfaces shall be thoroughly cleaned of dust, dirt, grease, or other unsightly materials or substances.

Surfaces marred or damaged as a result of the Contractor's operations shall be repaired, at his expense, to match the condition of the surfaces prior to the beginning of the Contractor's operations.

**COATING SYSTEM**

The surfaces to be coated shall be as shown on the plans and as specified in these special provisions. When a coating system is not shown or specified for a surface to be finish coated, the coating system to be used shall be as specified for the substrate material. The number of applications specified for each coating system listed herein is a minimum. Additional coats shall be applied if necessary to obtain a uniform color, texture, appearance, or required dry film thickness.

**SYSTEM 1- CEMENT PLASTER AND CONCRETE**:

2 Finish Coats:

Flat: Latex, Exterior, MPI Gloss Level 1, MPI List Number 10
Semi-Gloss: Latex, Exterior, MPI Gloss Level 5, MPI List Number 11

**SYSTEM 2 - GYPSUM BOARD**:

One Prime Coat:

Primer Sealer: Latex, Interior, MPI List Number 50

2 Finish Coats:

Flat: Latex, Interior, MPI Gloss Level 1, MPI List Number 53
Velvet-like: Latex, Interior, MPI Gloss Level 2, MPI List Number 44
Semi-Gloss: Latex, Interior, MPI Gloss Level 5, MPI List Number 54
Gloss: Latex, Interior, MPI Gloss Level 6, MPI List Number 114

**SYSTEM 3- STEEL AND OTHER FERROUS METALS, INTERIOR EXPOSURE**

One Prime Coat:

Coating meeting the requirements of SSPC-Paint 15

2 Finish Coats:

Flat: Latex, Exterior, MPI Gloss Level 1, MPI List Number 10
Eggshell-like: Light Industrial coating, Water Based, Exterior, MPI Gloss Level 3, MPI List Number 161
Semi-Gloss: Light Industrial coating, Water Based, Exterior, MPI Gloss Level 5, MPI List Number 163
Gloss: Light Industrial coating, Water Based, Exterior, MPI Gloss Level 6, MPI List Number 164

**SYSTEM 4- STEEL AND OTHER FERROUS METALS, EXTERIOR EXPOSURE**

2 Prime Coats:

Primer: Rust Inhibitive, Water Based, MPI List Number 107

2 Finish Coats:

Flat: Latex, Exterior, MPI Gloss Level 1, MPI List Number 10
Eggshell-like: Light Industrial coating, Water Based, Exterior, MPI Gloss Level 3, MPI List Number 161
Semi-Gloss: Light Industrial coating, Water Based, Exterior, MPI Gloss Level 5, MPI List Number 163
Gloss: Light Industrial coating, Water Based, Exterior, MPI Gloss Level 6, MPI List Number 164

**COLOR SCHEDULE**

Colors shall be as shown on the plans.

## 12-9.08 FIBERGLASS REINFORCED PLASTIC PANELS

### PART 1 - GENERAL

Scope: This work shall consist of furnishing and installing fiberglass reinforced plastic (FRP) panels and trim molding in accordance with details shown on the plans and these special provisions.

**SUBMITTALS**

Manufacturer's descriptive data, installation instructions, and finish options shall be submitted for approval.

Product descriptive data shall show the manufacturer's name and shall indicate conformance to these special provisions.

Installation instructions shall show the FRP panel manufacturer's recommended method of installation.

Finish options shall show the manufacturer's standard color palette for FRP panels and trim molding. Color shall be as shown on the plans.

### PART 2 - PRODUCTS

FRP Panel: FRP panel shall be Class I flame-spread, minimum nominal thickness of 0.090 inch; Marlite, Class A/I FRP; Kemlite, Fire-X Glasbord; or equal.

Trim Molding: Trim molding shall be manufacturer's standard vinyl molding with nailing flanges and a 3/8-inch deep channel of sufficient width to receive panels and sealant.

Adhesive and Sealant: Adhesive and sealant shall be as recommended by the FRP panel manufacturer.

### PART 3 - EXECUTION

**INSTALLATION**

The FRP panels and trim molding shall be installed in accordance with the manufacturer's installation instructions.

Trim molding shall be nailed through the flange into solid wood backing. All nails shall be concealed by FRP panels in the completed installation. Trim shall be one continuous piece along each wall unless the wall length exceeds the manufacturer's standard trim length. If more than one piece is used on one wall, the pieces shall be approximately equal length, with no piece less than 4 feet in length. All FRP panel edges shall be covered by a trim molding.

Panels shall be one continuous piece along each wall unless the wall length exceeds the manufacturer's standard panel length. If more than one panel piece is used on one wall, the pieces shall be approximately equal length, with no piece less than 4 feet in length.

**CLEAN-UP**

Adjacent surfaces shall be protected from adhesive or sealant. Excess adhesive and sealant shall be removed as the installation progresses using a solvent or cleaning agent recommended by the FRP panel manufacturer.

## SECTION 12-10. SPECIALTIES

### 12-10.01 TACKBOARDS

### PART 1 - GENERAL

Scope: This work shall consist of furnishing and installing tackboards in accordance with the details shown on the plans and these special provisions.

**SUBMITTALS**

Manufacturer's descriptive data, color and texture samples and installation instructions shall be submitted for approval. Color and texture will be selected by the Engineer after the award of the contract.

### PART 2 - PRODUCTS

Tackboards: Tackboards shall be textured plastic coating on cotton-fabric, pressure laminated to ¼-inch thick cork underlayment. Cork underlayment shall be bonded to a ¼-inch thick hardboard backing. Tackboard dimensions shall be as shown on the plans.

Border Moldings: Border moldings shall be factory applied, extruded clear anodized aluminum trim.

### PART 3 - EXECUTION

**INSTALLATION**

Tackboards shall be installed rigidly, securely, plumb and true, and in accordance with the manufacturer's recommendations.

### 12-10.02 MARKER BOARDS

### PART 1 – GENERAL

Scope: This work shall consist of furnishing and installing a marker boards in accordance with the details shown on the plans and these special provisions.

One felt eraser and 12 felt tipped liquid chalk markers of assorted colors shall be furnished for each marker board installed.

**SUBMITTALS**

Manufacturer's descriptive data and installation instructions shall be submitted for approval.

## PART 2 - PRODUCTS

Marker Board:

Marker board shall conform to Porcelain Enamel Institute Standard PEI-S-104, and shall be porcelain enamel surface on 0.024-inch thick (24-gage) sheet steel pressure laminated to ¼-inch thick tempered hardboard. Hardboard shall have a backing of 0.015-inch nominal thickness aluminum sheet. Enamel surface shall be suitable for marking with felt tipped liquid chalk markers and erasing with a felt eraser or dry cloth. The enamel surface shall be white in color.

Marker board dimensions shall be as shown on the plans.

Trim and marker tray: Trim and marker tray shall be factory installed, satin finish, clear anodized aluminum extrusions.

## PART 3 - EXECUTION

### INSTALLATION

Marker boards shall be installed rigidly, securely, plumb and true in accordance with the manufacturer's instructions.

## 12-10.03 METAL TOILET PARTITIONS

## PART 1 - GENERAL

Scope: This work shall consist of furnishing and installing metal toilet partitions in accordance with the details shown on the plans and these special provisions.

Metal toilet partitions shall consist of doors, pilasters, fasteners, anchorages and hardware. Internal reinforcement shall be provided at all fasteners, anchorages, hardware and accessories.

Doors, panels and pilasters shall have a factory applied, baked on enamel finish consisting of not less than one prime coat over a chemically pretreated base followed by at least one baked on enamel finish coat.

### SUBMITTALS

Manufacturer's descriptive data, standard color palette, installation instructions and working drawings shall be submitted for approval.

Working drawings shall show the plan layout, door and panel elevations and all details required for the complete installation and anchorage of the partition system.

## PART 2 - PRODUCTS

Doors and Panels:

Doors and panels shall be flush, one-inch minimum thickness, formed of two 0.034-inch (22-gage) minimum thickness, galvanized steel sheets over a honeycomb core. Doors and panels shall have formed edges sealed with a continuous oval crown locking strip, and shall be mitered, welded and finished at the corners.

Doors shall have controlled action hinges, with vertical pintle and ball bearing roller operating on adjustable cams, or moving parts of nylon and stainless steel. Top pivots shall be recessed into edges of doors.

Doors shall be provided with slide bar latch and a combination coat-hat hook and door stop, except as otherwise specified.

Doors on stalls designed for use by the disabled shall be provided with a slide latch, combination coat-hat hook and door stop, and U-shaped door pulls immediately below the latch on the inside and outside of the door.

Pilasters: Pilasters shall be 1¼-inch thick, of the same construction as the doors and panels, except the galvanized face sheets shall be 0.040-inch (20-gage) minimum thickness, and shall have an adjustable, leveling base.

Fasteners and Anchorages: Fasteners and anchorages shall be stainless steel with vandal resistant heads.

Hardware: Hardware shall be highly polished chromium plated, cast alloy, or heavy duty anodized aluminum.

Pilasters Anchors: Pilasters anchors shall be integral stud anchor type or internally threaded expansion sleeve type with single cone expander. Self-drilling type anchorage shall not be used.

**PART 3 - EXECUTION**

**INSTALLATION**

Metal toilet partitions shall be installed rigidly, securely, plumb, and true and in accordance with the manufacturer's recommendations. Tops and bottoms of doors shall align with tops and bottoms of panels, and all horizontal lines shall be level.

Rigid backing shall be provided in walls to receive anchorages.

Panels shall be anchored with at least 3 brackets at each wall and pilaster. Two anchors shall be used to fasten each pilaster base to the floor.

Doors shall not bind during opening and closing. The clearance between the door edges and pilasters shall be uniform, equidistant, and shall not exceed 3/16 inch. Hinges shall be adjusted to hold doors ajar when unlatched. Doors on stalls designed for use by the disabled shall return to the closed position.

Drilling, cutting and fitting of wall and floor finishes shall be concealed by the completed installation.

**CLEAN-UP**

Toilet partitions shall be cleaned, polished and free of all defects. Chipped, dented, scratched, or otherwise damaged work shall be replaced at the Contractor's expense.

**12-10.04 LOUVERS**

**PART 1 - GENERAL**

Scope: This work consists of furnishing and installing louvers in accordance with the details shown on the plans and these special provisions.

**SUBMITTALS**

Manufacturer's descriptive data and installation instructions shall be submitted for approval.

**PART 2 - PRODUCTS**

Louvers:

Louvers shall be factory fabricated units of extruded aluminum alloy not less than 0.081 inch thick (12-gage) or galvanized steel sheet not less than 0.064 inch thick (16-gage) with standard "Z" type blades, and removable bronze 16 x 16 mesh insect screens mounted on the inside of the units.

Louvers shall have integral caulking strips and retaining beads.

## PART 3 - EXECUTION

### INSTALLATION

Louvers shall be installed in accordance with the manufacturer's instructions. The completed louver installation shall be weather tight.

### PAINTING

Louvers shall be cleaned, prepared and painted in accordance with the requirements specified under "Painting" in Section 12-9, "Finishes," of these special provisions.

## 12-10.05 INFORMATION DISPLAY CASES

## PART 1 - GENERAL

### SUMMARY

Scope: This work shall consist of fabricating, furnishing and installing information display cases in accordance with the details shown on the plans and these special provisions.

Information display cases shall be completely factory assembled, illuminated units with tackboard and glazed aluminum door and frame and mounted in redwood framing.

### SUBMITTALS

Product Data: Manufacturer's descriptive data for the component parts of the display cases shall be submitted for approval.

### QUALITY ASSURANCE

## PART 2 - PRODUCTS

### MATERIALS

Aluminum Door and Frame: Aluminum door and frame shall be heavy, Type 6063-T5 extruded aluminum. Unit shall be complete with lock, full length piano hinge, glazing and weatherstripping.

Tackboard: Tackboard shall be bulletin board grade, self- sealing, ¼-inch thick corkboard glued to the plywood core. Glue shall be for exterior use and shall be compatible with the materials being adhered.

Plywood Core: Plywood core shall be exterior grade plywood as recommended by the display case manufacturer.

Lighting: Lighting shall be as shown on the plans.

### FABRICATION

Shop Assembly: Nails shall be countersunk and the holes filled. Joints shall be neatly mitered and fitted tight and true.

Shop Finishing:

Wood surfaces shall be coated with stain unless indicated otherwise on the plans. Coating, if required, shall be completed prior to the installation of the aluminum door and frame.

The final finish shall be in accordance with the requirements specified under "Painting" in Section 12-9, "Finishes," of these special provisions.

**PART 3 - EXECUTION**

**INSTALLATION**

Information display cases shall be installed in accordance with the manufacturer's recommendations.

Door and lock shall be adjusted, as necessary, after installation for smooth and easy operation.

**12-10.06 SIGNS**

**PART 1 - GENERAL**

**SUMMARY**

Scope: This work shall consist of furnishing and installing signs in accordance with the details shown on the plans and these special provisions.

**SUBMITTALS**

Product Data: Manufacturer's descriptive data for sign materials, colors and graphics, and for fastening hardware and material shall be submitted for approval.

**PART 2 - PRODUCTS**

Plastic Signs (Permanent Room Identification):

Plastic signs for permanent room identification for other than restrooms shall be scratch resistant, non-static, fire retardent, washable melamine laminate with a non-glare surface, not less than 1/8 inch thick. Letters and numbers shall be upper case Helvetica, one inch in height, 1/32 inch above and integral with sign material, accompanied by Grade 2 Braille.

Grade 2 Braille dots shall be 1/10 inch on center in each cell with 2/10-inch space between cells. Dots shall be raised a minimum of 1/40 inch above the background.

Plastic Sign (Restroom):

Plastic sign for restroom shall be not less than ¼-inch acrylic plastic. Sign background shall be blue and shall conform to Federal Standard 595B, Color No. 15090. Male/female symbol and lettering shall be white and shall conform to Federal Standard 595B, Color No. 17886.

Male restroom identification shall be a male symbol on an equilateral triangle with edges 12 inches long and a vertex pointing upward.

Female restroom identification shall be a female symbol on a 12-inch diameter circle.

Unisex restroom identification shall be a male and female symbol on a 12-inch equilateral triangle superimposed on a 12-inch diameter circle.

Accessible Building Entrance Sign:

Accessible building entrance sign shall be not less than 1/8-inch acrylic plastic, not less than 4" x 4" with the international symbol of accessibility.

Sign background shall be blue and shall conform to Federal Standard 595B, Color No. 15090. Symbol and border shall be white and shall conform to Federal Standard 595B, Color No. 17886.

Fastening hardware and material: Fastening hardware and material shall be as recommended by the sign manufacturer. Fasteners shall be noncorrosive.

**PART 3 - EXECUTION**

Inscription: sign messages shall be as shown on the plans.

**INSTALLATION**

Plastic signs for room identification and restrooms shall be fastened or secured to clean, finished surfaces in accordance with the sign manufacturer's instructions. Signs shall be installed at a location and height as shown on the plans.

Fastening hardware and material shall be installed within the sign as shown on the plans.

**12-10.07 WARDROBE LOCKERS**

**PART 1 - GENERAL**

**SUMMARY**

Scope: This work shall consist of furnishing and installing wardrobe lockers in accordance with the details shown on the plans and these special provisions.

**SUBMITTALS**

Product Data:

Manufacturer's descriptive data, installation instructions, and standard color palette shall be submitted for approval.

Unless otherwise shown on the plans, the color will be selected by the Engineer from the standard color palette after the award of the contract.

**PART 2 - PRODUCTS**

**ACCEPTABLE MANUFACTURERS**

Available Manufacturers: Subject to conformance with the contract provisions, metal lockers shall be Art Metal Products; Lyon Metal Products; Republic Storage Systems; or equal.

Lockers:

Lockers shall be standard, factory fabricated steel units. Framing shall be 0.060 inch thick (16-gage) and face sheets shall be 0.024 inch (24-gage), except door face sheets shall be 0.060 inch (16-gage).

Lockers shall be equipped with the following: hat shelf located approximately 10 inches below the top of the wardrobe locker, side to side coat rod, coat hook, louver vents at top and bottom of door, handleslide latch, provisions for a padlock, lockbar with 3-point latching contact with door frame and 1 1/2 pair full looped leaf hinges.

The approximate dimensions of the wardrobe lockers shall be 15 inches wide, 18 inches deep and 72 inches high.

Closed Base: Closed base shall be the manufacturer's standard continuous 6-inch base, fabricated of the same material and designed for use with the lockers provided. Bottoms shall be flanged inward for stiffening. Bases shall have the same finish as the locker units.

Top: Top shall be the manufacturer's standard continuous sloping top with end closure as needed, fabricated of the same material and designed for use with the lockers provided. Tops shall have the same finish as the locker units.

**FABRICATION**

Shop Assembly:

Lockers shall be fabricated square, rigid, and without warp, with metal faces flat and free of dents or distortion.

Frame joints and seams shall be welded. Exposed welds shall be ground smooth. Hinge and latch connections shall be welded or riveted.

Bolts shall be used for assembly and mounting lockers components. Bolt or rivet heads on fronts of locker doors or frame shall not be exposed.

Factory Finish: Lockers shall be chemically pretreated with degreasing and phosphatizing process. Wardrobe lockers shall have a baked enamel finish on all surfaces, exposed and concealed.

**PART 3 - EXECUTION**

**INSTALLATION**

Lockers shall be mounted on closed bases at locations shown in accordance with the manufacturer's instructions for plumb, level, rigid, and flush installation.

Wardrobe lockers shall be bolted together at tops and bottoms. The backs of the end lockers shall be bolted to wall anchors with ¼-inch bolts installed near the tops of the wardrobe lockers as recommended by the locker manufacturer.

Trim, sloping tops, and metal filler panels, if required, shall be installed using concealed fasteners to provide flush, hairline joints against adjacent surfaces.

The number of lockers shall be as shown on the plans.

**12-10.08 FIRE EXTINGUISHERS**

**PART 1 - GENERAL**

**SUMMARY**

Scope: This work shall consist of furnishing and installing fire extinguishers with mounting brackets in accordance with the details shown on the plans and these special provisions.

**REFERENCES**

Fire Extinguishers shall conform to the requirements in California Code of Regulations, Title 19 Division 1, Chapter 3, "Portable Fire Extinguishers."

**SUBMITTALS**

Product Data: Manufacturer's descriptive data and installation instructions shall be submitted for approval.

### QUALITY ASSURANCE

Codes and Standards: Fire extinguishers shall be Underwriters Laboratories or Factory Mutual Laboratories approved for the type, rating and classification of extinguisher specified.

## PART 2 - PRODUCTS

### MANUFACTURER'S

Acceptable Manufacturers: Subject to contract compliance, manufacturers shall be J. L. Industries; Larsen's Manufacturing; Potter-Roemer; or equal.

### COMPONENTS

Fire Extinguisher: Fire extinguisher shall be fully charged, multi-purpose dry chemical type, with charge indicator, hose and nozzle, and attached service record tag. Fire extinguisher shall be of the capacity and type rating shown on the plans.

Mounting Bracket: Mounting bracket shall be the manufacturer's standard painted, surface mounted type.

## PART 3 - EXECUTION

### INSTALLATION

Fire extinguishers shall be installed in locations and at mounting heights shown on the plans, or if not shown, at a height of 48 inches from the finished floor to the top of the fire extinguisher.

Fire extinguisher mounting brackets and cabinets shall be attached to structure, square and plumb, in accordance with the manufacturer's recommendations.

### IDENTIFICATION

Bracket-mounted: Extinguishers shall be identified with red letter decals spelling "FIRE EXTINGUISHER" applied to wall surface. Letter size, style and location as selected by the Engineer.

### SERVICING

Fire extinguishers shall be serviced, charged, and tagged not more than 5 days prior to contract acceptance.

# 12-10.09 FREE STANDING STEEL SHELVING

## PART 1 - GENERAL

Scope: This work shall consist of furnishing and installing free standing steel shelving in accordance with the details shown on the plans and these special provisions.

### SUBMITTALS

Manufacturer's descriptive data, installation instructions and standard color palette shall be submitted for approval. The color will be selected by the Engineer after the award of the contract.

## PART 2 - PRODUCTS

Shelving: Shelving shall be factory fabricated steel shelves and supports capable of supporting loads of 25 pounds per square foot of shelf area. Shelves shall not deflect more than 5/16 inch when subjected to the loads specified herein and

shall show no permanent deflection after removal of such loads. Shelves shall be supported and attached by means of clips. Studs or bolts shall not be used. Shelves shall be adjustable in vertical increments of 3 inches or less. Shelving shall be of the approximate dimensions and number shown on the plans and shall have a baked enamel finish.

**PART 3 - EXECUTION**

Free standing steel shelving shall be installed in accordance with the manufacturer's instructions.

**12-10.10 TELEPHONE ENCLOSURES**

**PART 1 - GENERAL**

Scope: This work shall consist of furnishing and installing telephone enclosures in accordance with the details shown on the plans and these special provisions.

**SUBMITTALS**

Manufacturer's descriptive data and installation instructions shall be submitted for approval.

**PART 2 - PRODUCTS**

Telephone Enclosure:

Telephone enclosure shall be standard factory fabricated, wall mounted unit with integral stainless steel writing and directory shelves, concealed theft and vandal resistant steel mounting bracket, steel frame with acoustical blanket behind perforated stainless steel back panel and ½-inch thick clear acrylic side panels. The telephone enclosure shall be not less than 34 inches high by 19 inches wide by and 12 inches deep.

The size of the telephone apparatus box shall be verified with the telephone company prior to ordering or fabricating the enclosure.

Electrical Service and Telephone Service Conduit and Conductors: Electrical service and telephone service conduit and conductors shall be as specified in Section 12-16, "Electrical" of these special provisions.

**PART 3 - EXECUTION**

**INSTALLATION**

The telephone enclosures shall be installed and fastened rigidly and securely in accordance with the manufacturer's instructions.

Electrical Service: Electrical service conduits and conductors shall be installed as shown on the plans.

Telephone Service:

Conduits for the telephone service conductors shall be installed as shown on the plans. A pull wire shall be installed in the telephone conduit, and shall be doubled back into the conduit at both ends.

The telephone company shall furnish and install the telephone set, apparatus box and telephone service conductors in accordance with the provisions specified under "Utility Connection" in Section 12-1, "General Requirements," of these special provisions.

## 12-10.11 TOILET ROOM ACCESSORIES

## PART 1 - GENERAL

Scope: This work shall consist of furnishing and installing toilet room accessories in accordance with the details shown on the plans and these special provisions.

### SUBMITTALS

Manufacturer's descriptive data and installation instructions and details shall be submitted for approval.

## PART 2 - PRODUCTS

Toilet Tissue Dispenser: Toilet tissue dispenser shall be dual roll, surface mounted, stainless steel with satin finish, approximately 8½" x 5" x 3" deep. Dispenser shall utilize standard toilet tissue rolls. The top roll shall automatically drop into place after the bottom roll is depleted. One dispenser per toilet stall.

Waste Receptacle: Waste receptacle shall be stainless steel waste receptacle with satin finish, all welded construction and seamless corners. Approximate width: 15 inches. Waste container capacity shall be not less than 30 gallons. Waste container shall have a removable receptacle equipped with liner hooks, reusable vinyl liner, and tumbler lock. One waste receptacle per lavatory.

Soap Dispenser System: Soap dispenser system shall be wall-mounted and shall have gravity feed, plunger type spouts, and a remote stainless steel liquid soap reservoir equipped with soap level indicator, outlet valves, and brass tubing and fittings. Brass tubing and fittings shall be as recommended by the dispenser manufacturer. The stainless steel and chrome plated brass construction soap dispensing mechanisms shall be capable of delivering fixed amounts of liquid soap in lather form. The vandal resistant valves shall project not more than 3½ inches from the wall and shall not be removable from within the restroom.

Toilet Seat Cover Dispenser: Toilet seat cover dispenser shall be stainless steel, lockable dispenser. Approximate dimensions: 15" x 11½" x 2 3/8" deep. One dispenser per toilet stall.

Napkin Receptacle: Napkin receptacle shall be wall hung, stainless steel napkin receptacle with piano hinges top and bottom and disposable liner. Approximate capacity: one gallon. One receptacle per women's toilet stall.

Mirror, Wall Hung: Mirror, wall hung shall be Number 1 quality, ¼ inch thick, electrolytically copper plated float or plate glass mirror with nonmoisture-absorbing filler. Mirror shall have a heavy gage galvanized steel back and stainless steel frame. The frame shall have a satin finish and shall be mitered and welded and the corners shall be ground smooth. Fasteners shall not penetrate surfaces of the frame exposed to view. Mirror shall conform to Federal Specification: DD-M-411b and shall be guaranteed against silver spoilage for not less than 10 years.

Mirror, Wall Hung with Shelf: Mirror, wall hung with shelf shall conform to the requirements specified for the wall hung mirror except the frame shall have an integral 5-inch wide stainless steel shelf.

Grab Bars: Grab bars shall be stainless steel, 1½-inch diameter bars with integral mounting flanges concealed under integral escutcheons.

Electric Hand Dryer: Electric hand dryer shall be a surface-mounted, 120-volt, 16-ampere unit with a maximum lockout timer of 35 seconds. Hand dryer shall be mounted on a heavy duty backing plate with 2 chrome plated tamper resistant bolts. The backing plate shall have two 7/8-inch diameter holes for electrical access and shall be bolted to the wall with four thru-wall concealed mounting bolts. Hand dryer cover plate shall be a one piece, heavy duty, rib-reinforced, die-cast zinc alloy, cover plate, painted with an electrostatically applied white epoxy and chip-proof finish paint. Nozzle shall be fixed in the downward air position.

Electric Hand Dryer Motor: The motor shall be 460 watts minimum, series commutated, 20,000 RPM, through-flow discharge blower motor. The fan and motor combination shall produce an air velocity of 4,850 linear meters per minute

at the air outlet, and 14,000 linear feet per minute at a distance of 4 inches away from the air outlet. Fan and motor assembly shall be insulated from the housing by a resilient rubber mounting.

Heater: A 900-watt, nichrome wire heating element protected by an automatic resetting high temperature limit control switch that opens when air flow stops, and automatically re-closes when air flow resumes. The heating element shall produce an air temperature of up to 135°F at a distance of 4 inches away from the air outlet, at a 72°F ambient room temperature.

Controls: Hand dryer shall be activated by an infrared optical sensor located adjacent to the air outlet. The hand dryer shall operate as long as hands are under the air outlet for the maximum lockout time of 35 seconds. Under normal conditions of atmospheric temperature, hand dryer shall be able to dry the hands within 15 seconds.

**PART 3 - EXECUTION**

Toilet room accessories shall be installed in accordance with the manufacturer's recommendations. Fasteners for mounting toilet room accessories shall be concealed and vandal resistant.

Expansion anchors shall be used for mounting accessories on masonry or concrete walls.

Toilet room accessories shall be mounted after painting work has been completed.

All toilet room accessories shall be mounted plumb, secure and rigid. Grab bars shall be supported adequately so the bars will withstand an applied load of 250 pounds at any point.

## SECTION 12-11. (BLANK)

## SECTION 12-12. FURNISHINGS

### 12-12.01 HORIZONTAL BLINDS

**PART 1 - GENERAL**

**SUMMARY**

Scope: This work shall consist of furnishing and installing horizontal blinds in accordance with the details shown on the plans and these special provisions.

Horizontal blinds shall be standard, factory manufactured assemblies suitable for use on exterior wall windows.

**SUBMITTALS**

Product Data: Manufacturer's descriptive data, color chips, and installation instructions shall be submitted for approval.

**PART 2 - PRODUCTS**

Horizontal Blinds:

Horizontal blinds shall be nominal one inch wide, spring tempered virgin aluminum alloy horizontal slats supported by braided polyester ladders. Braided ladders shall hold slats at equal spaces, parallel, straight, and shall provide tilt control and adequate overlap of slats. The distance between ladders shall not exceed 23 inches. Slat tilt shall be adjustable by a transparent wand. Blinds shall be adjustable to any height using lift cords.

Hardware shall be enclosed in a metal head and the opening hardware shall be clinched to the head. All metal parts shall have a corrosion resistant coating.

## PART 3 - EXECUTION

### INSTALLATION

Horizontal blinds shall be installed in accordance with the manufacturer's instructions.

## SECTION 12-13. (BLANK)

## SECTION 12-14. (BLANK)

## SECTION 12-15. MECHANICAL

### 12-15.01 MECHANICAL WORK

### PART 1 - GENERAL

Scope: This work shall consist of performing mechanical work in accordance with the details shown on the plans and these special provisions.

Mechanical work shall include furnishing all labor, materials, equipment and services required for providing heating, ventilating, air conditioning, plumbing, and fire protection systems.

Earthwork, foundations, sheet metal, painting, electrical, and such other work incidental and necessary to the proper installation and operation of the mechanical work shall be in accordance with the requirements specified for similar type work elsewhere in these special provisions.

System layouts are generally diagrammatic and location of equipment is approximate. Exact routing of pipes, ducts, etc., and location of equipment is to be governed by structural conditions and obstructions. Equipment requiring maintenance and inspection is to be readily accessible.

Roof penetrations shall be flashed and sealed watertight in accordance with the requirements specified under "Sheet Metal Flashing" in Section 12-7, "Thermal and Moisture Protection," of these special provisions.

### SUBMITTALS

Product Data:

A list of materials and equipment to be installed, manufacturer's descriptive data, and such other data as may be requested by the Engineer shall be submitted for approval.

Manufacturer's descriptive data shall include complete description, performance data and installation instructions for the materials and equipment specified herein. Control and wiring diagrams, rough-in dimensions for plumbing fixtures, and component layout shall be included where applicable.

Manufacturer's descriptive data shall be submitted for the following:

Plumbing fixtures and accessories
Electronic flush valves
Water hammer arrestors
Infrared sensorElectric water heater
Automatic trap primer
Hose faucet
Service sink and faucets
Drinking fountain and water chiller
Piping, fittings and appurtenances
Emergency eyewash

Electronic faucets
Valves and appurtenances
Heat pumps
Heat-Vent-Light
Backflow preventer
Y-Strainer
Fire Protection Underground Water Storage Tank
Dry Hydrant
Tank Vent and Water Sight Gage Assembly
Deadmen
Anchor Strap and Connector

**CLOSEOUT SUBMITTALS**

Operation and Maintenance Manuals:

Prior to the completion of the contract, 3 identified copies of the operation and maintenance instructions with parts lists for the equipment specified herein shall be delivered to the Engineer at the jobsite. The instructions and parts lists shall be indexed and bound in a manual form and shall be complete and adequate for the equipment installed. Inadequate or incomplete material shall be returned. The Contractor shall resubmit adequate and complete manuals at no expense to the State.

Operation and maintenance manuals shall be submitted for the following equipment:

Electronic Flush valves
Infrared sensor
Electric water heater
Valves
Electronic faucets
Heat pump
Heat-Vent-Light
Water chiller
Backflow preventer
Fire Protection Underground Water Storage Tank
Dry Hydrant
Tank Vent and Water Sight Gage Assembly

**QUALITY ASSURANCE**

Codes and Standards: Mechanical work, including equipment, materials and installation, shall conform to the CBC,CMC, and to the California Code of Regulations, Title 8, Chapter 4, Division of Industrial Safety (DIS).

**WARRANTY**

Warranties and Guarantees: Manufacturer's warranties and guarantees for materials or equipment used in the work shall be delivered to the Engineer at the jobsite prior to acceptance of the contract.

## 12-15.02 PIPE, FITTINGS, VALVES AND FIRE PROTECTION SYSTEM

## PART 1 - GENERAL

**SUMMARY**

Scope: This work shall consist of furnishing and installing pipes, fittings, valves and a complete fire protection system in accordance with the details shown on the plans and these special provisions.

Pipe, fittings and valves shall include such plumbing and piping accessories and appurtenances, not mentioned, that are required for the proper installation and operation of the plumbing and piping systems.

The fire protection system shall include an underground water storage tank, dry hydrant, accessories and appurtenances necessary for the complete installation and operation of said system.

All piping insulation and wrapping material shall be in accordance with the requirements specified under "Mechanical Insulation," in this Section 12-15.

The pipe sizes shown on the plans are nominal inside diameter. No change in the pipe size shown on the plans shall be permitted without written permission from the Engineer.

The pipe and fitting classes and material descriptions shall be as specified herein. No change in class or description shall be permitted without written permission from the Engineer.

**QUALITY ASSURANCE**

Codes and Standards: Pipe, fittings, valves and fire protection system shall be installed in accordance with the requirements in the CPC, NFPA the manufacturer's recommendations and the requirements specified herein.

## PART 2 - PRODUCTS

**MATERIALS**

**PIPE AND FITTINGS (Class and Description)**

A1: Schedule 40 galvanized steel pipe conforming to ASTM Designation: A 53, with 150 psi galvanized malleable iron banded screwed fittings and galvanized steel couplings. The weight of the zinc coating shall be not less than 90 percent of that specified in ASTM Designation: A 53.

A2: Schedule 40 galvanized steel pipe conforming to ASTM Designation: A 53, with black cast iron recessed drainage fittings. For rainwater leaders, neoprene-gasket compression couplings, Smith Blair, Dresser, or equal, may be used. The weight of the zinc coating shall be not less than 90 percent of that specified in ASTM Designation: A 53.

C1: Hub and plain end cast iron soil pipe with neoprene gaskets conforming to Cast Iron Soil Pipe Institute's Standard 301. Pipe, fittings and gaskets shall be of one manufacturer.

C2: Hubless cast iron soil pipe with neoprene gaskets, corrugated stainless steel shields and stainless steel clamps conforming to Cast Iron Soil Pipe Institute's Standard 301. Joint materials shall be furnished by pipe manufacturer.

H1: Type DWV hard copper tubing conforming to ASTM Designation: B 306, with DWV drainage fittings, stop type couplings and threaded adapters.

H2: Type K hard copper tubing conforming to ASTM Designation: B 88, with wrought copper or cast bronze solder joint pressure fittings, stop type couplings and threaded adapters. Solder shall be lead-free.

H3: Type L hard copper tubing conforming to ASTM Designation: B 88, with wrought copper or cast bronze solder joint pressure fittings, stop type couplings and threaded adapters. Solder shall be lead-free.

P1: Polyvinyl chloride (PVC) gravity sewer plastic pipe and fittings conforming to ASTM Designation: D 3034, Standard Dimension Ratio (SDR) 35, with integral bell and bell and spigot rubber gasketed joints or conforming to ASTM Designation: D2665 with solvent welded fittings. Rubber gaskets shall conform to ASTM Designation: F 477. Stainless steel clamps with rubber boots shall not be used.

P2: Polyvinyl chloride (PVC) plastic pipe and fittings conforming to ASTM Designation: D 2241, Type I, Grade 1, Standard Dimension Ratio (SDR) 21, rated for 200 psi working pressure at 73°F, National Sanitation Foundation approved. Pipe shall have bell ends conforming to ASTM Designation: D 3139 with triple edge rubber sealing ring.

For pipe sizes 2-inch diameter and smaller, plain end pipe with solvent welded fittings ASTM Designation: D 2241, Type I, Grade 1, Standard Dimension Ratio (SDR) 21, rated for 200 psi may be used.

P3: Polyvinyl chloride (PVC) standard weight pipe and fittings, Schedule 40, conforming to ASTM Designation: D 1785. Pipe shall meet or exceed requirements of National Sanitation Foundation Standard No. 14. Pipe shall have bell ends conforming to ASTM Designation: D 2672. For pipe sizes 3 inches and smaller, plain end pipe with solvent welded fittings conforming to ASTM Designation: D 2241, may be used.

P4: Polyvinyl chloride (PVC) plastic pipe and fittings shall conform to AWWA Designation: C900, Class 150, Standard Dimension Ratio (SDR) 18. Pipe shall have bell end with a solid cross section elastomeric ring conforming to ASTM Designation: D 1869.

Unions (for Steel Pipe): Unions (for steel pipe) shall be 250 psi, threaded malleable iron, ground joint, brass to iron seat, galvanized or black to match piping.

Unions (for Copper or Brass Pipe): Unions (for copper or brass pipe) shall be 150 psi cast bronze, ground joint, bronze to bronze seat with silver brazing threadless ends or 125 psi cast brass, ground joint, brass to brass seat with threaded ends.

Unions (for Brass Waste and Flush Pipes): Unions (for brass waste and flush pipes) shall be slip or flange joint unions with soft rubber or leather gaskets. Unions shall be placed on the fixture side of the traps.

Dielectric Waterway: Dielectric waterway shall be a premanufactured unit that incorporates an insulated interior lining at least 3 inches in length between the 2 pipes being connected while maintaining metal to metal contact on the exterior surface. Dielectric water way shall be listed by IAPMO (International Association of Plumbing and Mechanical Officials).

Insulating Union: Insulating union or flange as applicable shall be suitable for the service on which used. Connections shall be constructed such that the 2 pipes being connected are completely insulated from each other with no metal to metal contact. Insulating couplings shall not be used. Insulating union shall be F. H. Maloney; Central Plastics; EPCO; or equal.

Insulating Connection (to Hot Water Tanks): Insulating connection (to hot water tanks) shall be 6-inch minimum, flexible copper tubing with dielectric union at each end and designed to withstand a pressure of 150 psi and a temperature of 200°F.

**VALVES**

Gate Valve (2½-inch and smaller):

Gate valve (2½-inch and smaller) shall be bronze body and trim, removable bonnet and non rising stem, Class 125 and same size as pipe in which installed. Gate valve shall be Crane, 438; Nibco Scott, T-113; Jenkins, 370; or equal.

Gate valve in nonferrous water piping systems may be solder joint type with bronze body and trim. Valve shall be Kitz, 59; Nibco Scott, S-113; Jenkins, 1240; or equal.

Gate Valve (3-inch and larger, above ground): Gate valve (3-inch and larger, above ground) shall be iron body with bronze trim, removable bonnet and non-rising stem, Class 125 and same size as pipe in which installed. Gate valve shall be Crane, 461; Nibco Scott, F-619; Jenkins, 326; or equal.

Gate Valve (3-inch and larger, below ground): Gate valve (3-inch and larger, below ground) shall be AWWA double disc, hub or rubber ring type, removable bonnet and non-rising stem, equipped with operating nuts, 200 psi working pressure, and Tee handle wrench for each valve. Valve shall be Mueller, A-2380; American Valve, Model 28; or equal.

Ball Valve: Ball valve shall be two piece, minimum 400 psi WOG, bronze body and chrome plated or brass ball with full size port. Valve shall be Nibco Scott, T-580; Watts, B-6000; Kitz, 56; or equal.

Check Valve (1½-inch and smaller): Check valve (1½-inch and smaller) shall be silent spring loaded type, threaded bronze body, nylon or teflon disc, beryllium or stainless steel helical spring and shaft, Class 125 and same size as pipe in which installed. Check valve shall be Nibco/Scott, T-480; CPV, 36; Kitz, 26; or equal.

Check Valve (2-inch and larger): Check valve (2-inch and larger) shall be silent wafer type, full faced for installation between 125 psi flanges, iron body with bronze trim, nylon or teflon disc, stainless steel helical spring and shaft, Class 125 and same size as pipe in which installed. Check valve shall be APCO, Series 300; CPV, 10D; Metraflex, Series 900; or equal.

Automatic trap primer.

Automatic trap primer shall be all bronze body with integral vacuum breaker, non limiting internal operating assembly with gasketed bronze cover. Automatic trap primer shall be as manufactured by Zurn, Z-1022; Wade, W-2400; or equal.

**FAUCET AND HYDRANTS**

Hose Faucet: Hose faucet shall be compression type, angle pattern, wall flange at exterior locations, tee handle, ¾-inch female thread with hose end, rough chrome or nickel plated finish for locations inside building, rough brass finish for others. Hose faucet shall be supplied with an integral or nonremovable threaded outlet vacuum breaker which meets the requirements of the American Society of Sanitary Engineering (ASSE) Standard: 1011. Hose faucet shall be Nibco, No. 63VB; Chicago, No. 13T; or equal.

Box Hydrant:

Box hydrant shall be ¾-inch, nickel bronze box with hinged, locking cover, bronze casing and hydrant, integral vacuum breaker and minimum ¼-inch drain port. Operating key shall be provided. Box hydrant shall be J. R. Smith, Model 5709 QTSAP; Josam, Model 71020; Zurn, Model 1330; or equal.

**CLEANOUTS**

Cleanout Through Wall: Cleanout through wall shall be cast iron cleanout tee type with polished stainless access plates. Plug shall be countersunk brass or bronze with tapered threads. Cleanout shall be Wade, No. W-8460; Smith, No. 4532; Zurn, No. 1445; or equal.

Cleanout Through Floor:

Cleanout through floor shall have nonslip scoriated nickel bronze access plate and adjustable frame with square pattern top for ceramic tile and round pattern top for other finishes. Where floors are constructed with a membrane, access frame shall be provided with membrane clamping flange. Plug shall be countersunk brass or bronze with tapered threads. Cleanout shall be Wade, W-7000 Series; Smith, 4023 Series; Zurn, No. 1400; or equal.

Cleanout through floors in exterior locations shall be heavy duty, floating pipe type with cast iron cover. Cleanouts shall be Wade, No. W-8300-HF; Smith, No. 4253; Zurn, No. 1474; or equal.

Cleanout to Grade: Cleanout to grade shall be cast iron ferrule type. Plug shall be countersunk brass or bronze with tapered threads. Cleanout to grade shall be Wade, No. W-8450; Smith, 4420; Zurn, No 1440; or equal.

**FIRE PROTECTION SYSTEM**

Fire Protection Underground Water Storage Tank: The fire storage tank shall be factory-manufactured single-walled fiberglass cylindrical tank meeting AWWA Standard D120 standards. The manufacturer shall include these appurtenances with the storage tank: a tank vent and water sight gage assembly, manway, a dry hydrant, pre-fabricated deadmen or forms, anchor straps, and connectors. The appurtenances shall meet NFPA 1142 standards. The tank capacity and location of appurtenances shall be as shown on the plans. All construction or appurtenance joint(s) shall be above the tank waterline. Adhesives and sealants shall be waterproof, corrosion resistant, and approved for the intended application.

Dry Hydrant: The dry hydrant pipe shall be 6-inch threaded Schedule 40 galvanized steel and PVC pipe with an anodized black aluminum National Hose Thread (NHT) 4½-inch male fire connection fitting with a bright yellow colored lockable cap. The pipes shall be connected using a 6-inch Schedule 80 PVC full coupling. Threaded fittings shall withstand at least 300 foot pounds of torque.

Tank Vent and Water Sight Gage Assembly: The tank vent and water sight gage shall be an integrated assembly. The sight gage shall be capable of indicating if water level in the tank is full or in need of replenishment. The pipe diameter of the assembly shall be 8 inches with a 10-inch diameter adapter flange. Suitable gasket shall be provided with adapter flange. The pipe material of the assembly shall be Schedule 40 PVC.

Deadmen: The deadmen shall be either pre-fabricated or cast-in-place. The deadmen shall be part of the tank package and pursuant with the tank manufacturer's instructions. Installation shall be in accordance with the tank manufacturer's instructions and approved by the Engineer. The deadmen shall be sized to prevent tank floatation.

Anchor Strap and Connector: The anchor strap shall be fiberglass compatible material and supplied by tank manufacturer. The number and location of straps shall be as specified by tank manufacturer. The connector shall be as recommended by tank manufacturer.

Backfill and Bedding:

Pea Gravel: Pea gravel shall be a mix of rounded particles, sizes between 1/8 inch and 3/4 inch. The pea gravel shall conform to the specifications of ASTM C-33, paragraph 9.1, sizes 6, 67, or 7. No more than 5% by weight of the backfill shall pass through a #8 sieve. The material shall be washed, free-flowing, and free of ice, snow, and debris.

Crushed Stone: Crushed stone shall be a mix of angular particles, sizes between 1/8 inch and 1/2 inch. The crushed stone shall conform to the specifications of ASTM C-33, paragraph 9.1, sizes 7 or 8. No more than 5% by weight of the backfill shall pass through a #8 sieve. The material shall be washed, free-flowing, and free of ice, snow, and debris.

**MISCELLANEOUS ITEMS**

Water Hammer Arrestor: Water hammer arrestor shall be stainless steel body with bellows or piston. Arrestor compression chambers shall be pneumatically charged. Water hammer arrestors shall be tested and certified in accordance with the Plumbing and Drainage Institute Standard: PDI-WH201 and sized as shown on the plans.

Access Door: Access door shall be 16-gage prime coated steel, face mounting square frame, minimum 12” x 12” door with concealed hinge and screwdriver latch.

Compression Stop (Exposed): Compression stop (exposed) shall be metal full free waterway, angle type, ground joint union, non-rising stem, molded rubber seat and wheel handle.

Compression Stop (Concealed): Compression stop (concealed) shall be long neck, built-in compression stops for required wall thickness, loose key and exposed parts polished chromium plated. Supplies shall be Chicago, 1771; California Brass, No. 172; or equal.

Wye Strainer: Wye strainer shall be wye pattern, cast iron body and Type 304 stainless steel or monel strainer screen. The strainer screen shall have an open area equal to at least 3 times the cross sectional area of the pipe in which it is installed and shall be woven wire fabric with 20 mesh or perforated sheet with 0.032-inch maximum diameter holes.

Backflow Preventer: Backflow preventer shall be factory assembled with 2 check valves, one pressure differential relief valve, 2 ball valves and 4 test cocks. Backflow preventers shall be of the approved type reduced pressure principle devices listed by the County of Los Angeles Department of Health Services, Cross-Connection and Water Pollution Control Section, 2525 Corporate Place, Monterey Park, California 91754, Telephone (213) 881-4140.

Underground Tracer Tape: Under tracer tape shall provided for all buried piping having permanent, bright colored, continuous printed plastic tape with copper wire or aluminum foil intended for direct burial service; not less than 50 mm wide x 0.1 mm thick; lettering shall read "CAUTION WATER PIPE BURIED BELOW," "CAUTION FIRE PIPE BURIED BELOW," or "CAUTION SEWER PIPE BURIED BELOW".

Pipe Hanger (for piping supported from overhead): Pipe hanger (for piping supported from overhead) shall be Grinnell, Model 269; Super Struct, C711; or equal.

Pipe Wrapping Tape and Primer:

Pipe wrapping tape shall be pressure sensitive polyvinyl chloride or pressure sensitive polyethylene tape having nominal thickness of 20 mils. Wrapping tape shall be Polyken, 922; Manville, Trantex VID-20; Scotchrap, 51; or equal.

Pipe wrapping primer shall be compatible with the pipe wrapping tape used.

Floor, Wall, and Ceiling Plates: Floor, wall, and ceiling plates shall be chromium plated steel or plastic plates having screw or spring clamping devices and concealed hinges. Plates shall be sized to completely cover the hole.

Valve Box: Valve box shall be precast high density concrete with polyethylene face and cast iron traffic rated cover marked "WATER," or "CO-SS" as applicable. Extension shall be provided as required. Valve box shall be Christy, B3; Brooks Products Company, 3TL; Frazer, 3; or equal.

Floor Drain: Floor drain shall be cast iron body and flashing collar, adjustable nickel bronze 6-inch strainer head with seepage openings and caulk or no-hub outlet. Floor drain shall be round or square as shown on the Architectural plans. Floor drain shall be J. R. Smith, 2005/2010; Wade, W-1100; Zurn, Z-415; or equal.

## PART 3 - EXECUTION

### INSTALLATION

### INSTALLATION OF PIPES AND FITTINGS

Pipe and Fittings: Pipe and fittings shall be installed in accordance with the following designated uses:

| Designated Use | Pipe and Fitting Class |
|---|---|
| Domestic water (CW and HW) in buildings | H3 or A1 |
| Domestic water underground within 5 feet of the building | A1 or H2 |
| Domestic water underground 5 feet beyond the building | P2, P3, P4, A1 or H2 |
| Fire protection water, underground | B1,D1 or P4 |
| Fire protection water riser | B1, D1 or H3 |
| Sanitary drain piping above ground in building | H1, C1, or C2 |
| Sanitary drain and vent piping underground within 5 feet of the building | C1 or C2 |
| Sanitary vent piping above ground in building | A2, H1, C1, or C2 |
| Sanitary drain pipe, 5 feet beyond the building | C1, C2, or P1 |
| Equipment drains and relief valve discharge | H3 or A1 |
| Soap lines | H3 |

Installing Piping:

Water piping shall be installed generally level, free of traps and bends, and arranged to conform to the building requirements.

Piping installed underground shall be tested as specified elsewhere in these special provisions before backfilling.

Public use areas, offices, rest rooms, locker rooms, crew rooms, training rooms, storage rooms in office areas, hallway type rooms, and similar type use areas shall have concealed piping.

Warehouse rooms, equipment bays, and loft areas shall have exposed piping.

Piping shall not be run in floor fill, except as shown on the plans.

Piping shall be installed parallel to walls. All obstructions shall be cleared, headroom preserved and openings and passageways kept clear whether shown or not. Piping shall not interfere with other work.

Where pipes pass through exterior walls, a clear space around pipe shall be provided. Space shall be caulked water tight with silicone caulk.

Underground copper pipe shall have brazed joints. Underground plastic pipe shall be buried with No. 14 solid bare copper wire. Wire ends at pipe ends shall be brought up 8 inches and looped around pipe.

Exposed supply and drain piping in rest rooms shall be chrome finished.

Forty-five degree bends shall be used where offsets are required in venting. Vent pipe headers shall be sloped to eliminate any water or condensation.

Vent piping shall extend a minimum of 8 inches above the roof.

Horizontal sanitary sewer pipe inside buildings shall be installed on a uniform grade of not less than ¼ inch per foot unless shown otherwise on the plans.

Drainage pipe shall be run as straight as possible and shall have easy bends with long turns.

Wye fittings and 1/8 or 1/16 bends shall be used where possible. Long sweep bends and combination Wye and 1/8 bends may be used only for the connection of branch pipes to fixtures and on vertical runs of pipe.

Water pipe near sewers:

Water pipe shall not be installed below sewer pipe in the same trench or at any crossing, or below sewer pipe in parallel trenches less than 10 feet apart.

When a water pipe crosses above a sewer pipe, a vertical separation of at least 12 inches between the top of the sewer and the bottom of the water pipe shall be maintained.

When water and sewer pipe is installed in the same trench, the water pipe shall be on a solid shelf at least 12 inches above the top of the sewer pipe and 12 inches to one side.

Pipe Sleeves:

The Contractor shall provide sleeves, inserts and openings necessary for the installation of pipe, fittings and valves. Damage to surrounding surfaces shall be patched to match existing.

PVC pipe sleeves shall be provided where each pipe passes through concrete floors, footings, walls or ceilings. Inside diameter of sleeves shall be at least ¾ inch larger than outside diameter of pipe. Sleeves shall be installed to provide at least 3/8-inch space all around pipe the full depth of concrete. Space between pipes and pipe sleeves shall be caulked watertight.

Cutting Pipe: Pipe shall be cut straight and true and the ends shall be reamed to the full inside diameter of the pipe after cutting.

Damaged Pipe: Pipe that is cracked, bent or otherwise damaged shall be removed from the work.

Pipe Joints and Connections:

Joints in threaded steel pipe shall be made with teflon tape or a pipe joint compound that is nonhardening and noncorrosive, placed on the pipe and not in the fittings.

The use of thread cement or caulking on threaded joints will not be permitted. Threaded joints shall be made tight. Long screw or other packed joints will not be permitted. Any leaky joints shall be remade with new material.

Exposed polished or enameled connections to fixtures or equipment shall be made with special care, showing no tool marks or threads.

Cleaning and Closing Pipe: The interior of all pipe shall be cleaned before installation. All openings shall be capped or plugged as soon as the pipe is installed to prevent the entrance of any materials. The caps or plugs shall remain in place until their removal is necessary for completion of the installation.

Securing Pipe: Pipe in the buildings shall be held in place by iron hangers, supports, pipe rests, anchors, sway braces, guides or other special hangers. Material for hangers and supports shall be compatible with the piping or neoprene isolators shall be used. Allowances shall be made for expansion and contraction. Steel pipe shall have hangers or supports every 10 feet. Copper pipe one inch or less in diameter smaller shall have hangers or supports every 6 feet and sizes larger than one inch shall have hangers or supports every 10 feet. Plastic pipe shall have hangers or supports every 3 feet. Cast iron soil pipe with neoprene gaskets shall be supported at each joint. Vertical pipes shall be supported with clamps or straps. Horizontal and vertical piping shall be securely supported and braced to prevent swaying, sagging or flexing of joints.

Hangers and Supports:

Hangers and supports shall be selected to withstand all conditions of loading to which the piping and associated equipment may be subjected and within the manufacturer's load ratings. Hangers and supports shall be spaced and distributed so as to avoid load concentrations and to minimize the loading effect on the building structure.

Hangers and supports shall be sized to fit the outside diameter of pipe or pipe insulation. Hangers shall be removable from around pipe and shall have provisions for vertical adjustment after erection. Turnbuckles may be used.

Materials for holding pipe in place shall be compatible with piping material.

Hanger rods shall be provided with locknuts at all threaded connections. Hanger rods shall be sized as follows:

| Pipe Size | Minimum Hanger Rod Diameter |
|---|---|
| ½” to 2” | 3/8” |
| 2½” to 3½” | 1/2" |
| 4” to 5” | 5/8” |
| 6” | 3/4" |

Wrapping and Coating Steel Pipe:

Steel pipe buried in the ground shall be wrapped or shall be plastic coated as specified herein:

1. Wrapped steel pipe shall be thoroughly cleaned and primed as recommended by the tape manufacturer.
2. Tapes shall be tightly applied with 1/2 uniform lap, free from wrinkles and voids with approved wrapping machines and experienced operators to provide not less than 40-mil thickness.
3. Plastic coating on steel pipe shall be factory applied. Coating imperfections and damage shall be repaired to the satisfaction of the Engineer.

4. Field joints, fittings and valves for wrapped and plastic coated steel pipe shall be covered to provide continuous protection by puttying and double wrapping with 20-mil thick tape. Wrapping at joints shall extend a minimum of 6 inches over the adjacent pipe covering. Width of tape for wrapping fittings shall not exceed 2 inches. Adequate tension shall be applied so tape will conform closely to contours of fittings. Putty tape insulation compounds approved by the Engineer shall be used to fill voids and provide a smooth even surface for the application of the tape wrap.

Wrapped or coated pipe, fittings, and filed joints shall be approved by the Engineer after assembly. Piping shall be placed on temporary blocks to allow for inspection. Deficiencies shall be repaired to the satisfaction of the Engineer before backfilling or closing in.

Thrust Blocks:

Thrust blocks shall be formed by pouring concrete between pipe and trench wall. Thrust blocks shall be sized and so placed as to take all thrusts created by maximum internal water pressure.

Plastic pipe underground shall be provided with thrust blocks and clamps at changes in direction of piping, connections or branches from mains 2 inches and larger, and all capped connections.

Union: Unions shall be installed where shown and at each threaded or soldered connection to equipment and tanks. Unions shall be located so piping can be easily disconnected for removal of equipment or tanks. Unions shall be omitted at compression stops.

Dielectric Waterway: Dielectric waterway shall be provided between metal pipes of different material, and between brass or bronze valves and steel piping.

Insulating Union and Insulating Connection:

Insulating union and insulating connection shall be provided where shown and at the following locations:

1. In metallic water service connections into each. Insulating connections shall be installed on the exterior of the building, above ground and after shut-off valve.
2. In water service connections in ground at point where new metallic pipes connect to existing metallic pipes. Install valve box above insulating connection.
3. At points of connections of copper or steel water pipes to steel domestic water heaters and tanks.

Bonding at Insulating Connections: Interior water piping and other interior piping that may be electrically energized and are connected with insulating connections shall be bonded in accordance with the CEC. Bonding shall all be coordinated with electrical work.

Compression Stop: Each fixture, including hose faucets, shall be equipped with a compression stop installed on water supply pipes to permit repairs without shutting off water mains. Ball valves may be installed where shown on the plans or otherwise permitted by the Engineer.

**INSTALLATION OF VALVES**

Exterior Valves: Exterior valves located underground shall be installed in a valve box marked "Water." Extensions shall be provided as required.

**INSTALLATION OF FAUCETS AND HYDRANTS**

Hose Faucet and Hydrants: Faucets and hydrants shall be installed with outlets 18 inches above finished grade.

**INSTALLATION OF CLEANOUTS**

Cleanouts:

A concrete pad 18 inches long and 4 inches thick shall be placed across the full width of trench under cleanout Wye or 1/8 bend. Cast iron soil pipe (C1 or C2) and fittings shall be used from Wye to surface. Required clearance around cleanouts shall be maintained.

Cleanout risers outside of a building installed in a surface other than concrete shall terminate in a cleanout to grade. Cleanout to grade shall terminate in a valve box with cover marked "CO-SS". Top of box shall be set flush with finished grade. Cleanout plug shall be 4 inches below grade and shall be located in the box to provide sufficient room for rodding.

Cleanout risers installed in tile and concrete floors, including building aprons and sidewalks, shall terminate in a cleanout through floor.

**INSTALLATION OF FIRE PROTECTION SYSTEM**

Fire Protection Water Storage Tank:

Underground fire protection water storage tank, deadmen, and other appurtenances shall be installed in accordance with the plans, these specifications, codes and standards and strict accordance with the manufacturer's installation instructions and as approved by the Engineer.

Water storage tank shall be filled to operating level with clean, fresh water upon completion of construction and testing.

The flanged manway cover shall be bolted securely and adhered with tracer tape along the circular edges of the cover.

**INSTALLATION OF MISCELLANEOUS ITEMS**

Water Hammer Arrestor: Water hammer arrestor shall be installed so that they are vertical and accessible for replacement. Water hammer arrestor shall be installed with access door when in walls or there is no access to ceiling crawl spaces. Access door location shall be where shown on the plans or as approved by the Engineer.

Backflow Preventer:

Backflow preventer shall be installed a minimum of 12 inches above ground. Backflow preventer assembly shall include a wye strainer, backflow preventer, fittings and pipe. Assembly components shall be the same size as the pipe in which they are installed unless otherwise shown on the plans.

Flushing Completed Systems: All completed systems shall be flushed and blown out.

Chlorination:

The Contractor shall flush and chlorinate all domestic water piping and fixtures.

Calcium hypochlorite granules or tablets, if used, shall not be applied in the dry form, but shall first be dissolved into a solution before application.

The Contractor shall take adequate precautions in handling chlorine so as not to endanger workmen or damage materials. All pipes and fittings shall be completely filled with water containing a minimum of 50 ppm available chlorine. Each outlet in the system shall be opened and water run to waste until a strong chlorine test is obtained. The line shall then be closed and the chlorine solution allowed to remain in the system for a minimum of 24 hours so that the line shall contain no less than 25 ppm chlorine throughout. After the retention period, the system shall be drained, flushed and refilled with fresh water.

**FIELD QUALITY CONTROL**

Testing:

The Contractor shall test piping at completion of roughing in, before backfilling, and at other times as directed by the Engineer.

The system shall be tested as a single unit, or in sections as approved by the Engineer. The Contractor shall furnish necessary materials, test pumps, instruments and labor and notify the Engineer at least 3 working days in advance of testing. After testing, the Contractor shall repair all leaks and retest to determine that leaks have been stopped. Surplus water shall be disposed of after testing as directed by the Engineer.

The Contractor shall take precautions to prevent joints from drawing while pipes and appurtenances are being tested. The Contractor shall repair damage to pipes and appurtenances or to other structures resulting from or caused by tests.

General Tests:

All piping shall be tested after assembly and prior to backfill, pipe wrapping, connecting fixtures, wrapping joints and covering the pipe. Systems shall show no loss in pressure or visible leaks.

The Contractor shall test systems according to the following schedule for a period of not less than 4 hours:

| Test Schedule | | |
|---|---|---|
| Piping System | Test Pressure | Test Media |
| Sanitary sewer and vent | 10-foot head | Water |
| Water | 125 psig | Water |
| Firewater | 5 psig | Air |

During testing of water systems, valves shall be closed and pipeline filled with water. Provisions shall be made for release of air.

Sanitary sewers shall be cleared of obstructions before testing for leakage. The pipe shall be proved clear of obstructions by pulling an appropriate size inflatable plug through the pipe. The plug shall be moved slowly through the pipe with a tag line. The Contractor shall remove or repair any obstructions or irregularities.

Sanitary sewer pipes beyond 5 feet perpendicular to the building shall be tested for leakage for a period of not less than 4 hours by filling with water to an elevation of 4 feet above average invert of sewer or to top of manholes where less than 4 feet deep. The system shall show no visible leaks The sewer may be tested in sections with testing water progressively passed down the sewer as feasible. Water shall be released at a rate that will not create water hammer or surge in plugged sections of sewer.

Testing Backflow Preventers:

Backflow preventers installed by the Contractor shall be tested at the completion of the supply system installation for proper operation by a certified Backflow Preventer Tester.

The tester shall hold a valid certificate as a Backflow Preventer Tester from the county in which the device to be tested is located or, if the county does not have a certification program for Backflow Preventer Testers, the tester shall have a certificate from one of the following:

1. The American Water Works Association.
2. A county which has a certification program for Backflow Preventer Testers. The certification under which the tester has been certified shall be acceptable to the water purveyor and the local agency having jurisdiction.

Testing for proper operation shall conform to the procedures of the county in which the testing is being performed, or, if such procedures are not available in the county, such tests shall conform to the provisions in the latest edition of the Guidance Manual For Cross Connection Control Program, which is available from the California Department of Health Services, Division of Drinking Water and Environmental Management, 601 N 7th Street, P.O. Box 942732, Sacramento, CA 94234.

The Contractor shall notify the Engineer at least 5 days prior to testing backflow preventers. Such tests shall be satisfactorily completed after installation of the backflow preventer assemblies and before operation of the systems.

One copy of all test results for each backflow preventer shall be furnished to the Engineer.

Full compensation for providing the certified Backflow Preventer Tester and for testing the backflow preventers shall be considered as included in the lump sum price paid for building work and no additional compensation will be allowed therefore.

Testing Fire Protection Underground Water Storage Tank:

Before installing the tank, a visual air and soap test shall be conducted in strict accordance with AWWA D120-02 standards, section 5.2.3.2. The maximum test pressure for 10-foot diameter tanks and smaller shall be 5 psi. The maximum test pressure for 12-foot diameter tanks and larger shall be 3 psi.

After installation is completed and before completion of backfilling, the tank shall be filled with water through the dry hydrant (with the 90° fitting removed) to the top of the pipe. Cover the top of pipe to minimize evaporation. Remove cover and measure the water loss after a twenty-four (24) hour period. No tank will be accepted if the water level falls more than 0.5 inches. Repairs or replacements, if necessary, shall be made at the Contractor's expense. The Engineer shall be notified at least 48 hours in advance of starting the testing.

After backfilling and after all tank appurtenances are installed, verify the performance of the tank by having the local fire department pump either 10% of the tank volume or after 2 minutes of pumping, whichever comes first. Refill the tank with water to proper level after this performance test.

The fire protection system shall then be checked by the Contractor to demonstrate the satisfactory overall operation of the fire protection system as a completed unit. The test shall be conducted in the presence of the Engineer. During the test period, final adjustments shall be made to the equipment and components as required to place the system in satisfactory operating condition.

Any equipment or work found deficient during the test shall be replaced or repaired and retested. The Engineer shall be notified a least 72 hours in advance of starting the retest.

## 12-15.03 MECHANICAL INSULATION

## PART 1 - GENERAL

### SUMMARY

Scope: This work shall consist of furnishing and installing mechanical insulation in accordance with the details shown on the plans and these special provisions.

Piping insulation shall be installed on all domestic hot water piping, above grade, in non-conditioned spaces.

P-trap, hot water supply pipes and angle valves for lavatories and sinks, except in janitor closets or similar enclosed spaces, shall be insulated.

### QUALITY ASSURANCE

Codes and Standards:

Mechanical insulation shall conform to California State Energy Commission regulations and, where applicable, shall meet American Society of Testing and Materials (ASTM) standards.

All materials shall bear the label of the Underwriters Laboratory (UL) or other approved testing laboratory indicating that the materials proposed for use conform to the required fire hazard ratings.

Pipe safety insulation shall conform to Section 1504(b) of the CPC.

## PART 2 - PRODUCTS

### MATERIAL

All pipe insulation and wrapping material, including adhesives and jackets, located within buildings shall be certified to have a composite flame spread rating of not more than 25 and smoke development rating of not more than 450 when tested in accordance with ASTM Designation: E 84.

Domestic Water Insulation: Piping insulation shall be glass fiber molded pipe insulation with factory applied jacket suitable for service temperatures up to 350°F. Covering jacket shall have pressure sealing lap adhesive joints. Pipe insulation shall have a minimum thermal resistance of R-3. Insulation and jackets shall be Owens-Corning, Fiberglass 25 with ASJ/SSL All Service Jacket; Manville, Micro-Lok 650ML with AP-T All Purpose Jacket; or equal.

Piping Insulation Cement: Insulation cement shall be Fenco, All Purpose Cement; Manville, JM375; or equal.

PVC Jacket: PCV jacket shall be rated for a service temperature of 175°F. PVC jacket shall include covers specifically designed to cover pipe fittings.

Alternative Pipe Insulation: Alternative pipe insulation shall be closed cell, elastomeric material in a flexible tubular form. Insulation shall have a service temperature range between -40°F and 200°F, a minimum vapor transmission rating of 0.20 perm-inch, and a minimum thermal resistance of R-3.

Pipe Safety Insulation: Pipe safety insulation for P-traps, hot water supply pipes and angle valves shall be molded closed cell vinyl or closed cell foam with exterior vinyl surface. Pipe safety insulation shall be configured to protect against contact. Pipe safety insulation shall be Truebro Inc., Handi Lav-guard; Plumberex Specialty Products, Handy Shield; or equal.

Adhesive: Adhesive shall be non-flammable type: Benjamin Foster Company, No. 85-20 Spark Safe; Goodloe E. Moore Company, Tuff Bond No. 6; Permacel, No. PA-3l0; 3M, No. 38 Insulation Adhesive; Swift's, No. 7228 brush type or No. 7336 spray type; Chicago Mastic, 17-461; or equal.

Studs: Studs shall be cement-in-place type, pneumatic driven type or percussive welding type, and shall have one-inch minimum diameter washers.

Insulation Inserts: Insulation inserts at pipe hangers supports for pipes 2 inches or larger shall be calcium silicate, cellular glass, or other acceptable material of the same thickness as the adjacent insulation and not less than 13-pound density.

## PART 3 - EXECUTION

### INSTALLATION

Insulation materials shall be neatly installed with smooth and even surfaces, jackets drawn tight and smoothly cemented down.

Insulation material shall not be installed until all pipes or surfaces to be covered are tested for leaks, cleaned and dried, and foreign materials, such as rust, have been removed.

Piping Insulation:

Piping insulation shall be in accordance with the following, except that unions, unless integral with valves, and flexible connections shall not be insulated:

1. Where insulation butts against flanges or is discontinued, insulation shall be tapered to pipe to allow for covering jacket to completely seal off end of insulation.

   Insulation shall be extended on the valve bodies up to the valve bonnet.

   Extend insulation continuous through pipe hangers and pipe sleeves. At hangers where pipe is supported, provide an insulated protection shield.

   Insulating cement shall be applied to fittings, valves, and strainers and troweled smooth to thickness of adjacent covering. Strainer cleanout plugs shall remain accessible. Covers fabricated from molded pipe covering may be used in lieu of cement, provided covers are neat and well secured.

2. Jacket flap shall be sealed down with factory applied self-sealing lap. Seams shall be lapped not less than 1½ inches. Jacket shall be secured with aluminum bands installed at 12-inch centers.

3. Exposed outdoor insulation shall have an additional 0.016-inch minimum thickness aluminum jacket applied over the completed insulation. The jacket shall have a factory applied moisture barrier and shall be Childers; Smith; or equal.

   End joints shall be lapped with aluminum holding traps located directly over the lap. Additional aluminum holding straps shall be placed at 8-inch centers. Jacket at ells and tees shall be mitered, or premanufactured fitting jackets shall be provided, with additional aluminum holding bands, as required. All joints shall be sealed watertight using silicon type, heat resistant sealant.

4. In-ground insulation shall have an additional PVC jacket applied over the completed insulation and vapor barrier. PVC jacket shall be made watertight with adhesive or sealant as recommended by the PVC jacket manufacturer.

Alternate pipe insulation, where used, shall be installed on hot water piping before connections are made or the insulation may be slit lengthwise, applied to pipe and sealed with adhesive.

Pipe Safety Insulation: Pipe safety insulation shall be installed in accordance with the manufacturer's recommendations.

## 12-15.04 PLUMBING FIXTURES

## PART 1 - GENERAL

### SUMMARY

Scope: This work shall consist of the furnishing and installing plumbing fixtures in accordance with the details shown on the plans and these special provisions.

## PART 2 - PRODUCTS

Plumbing fixtures shall be white in color and shall meet the following requirements:

Water Closet: Water closet shall be wall hung, vitreous china, blow out type, elongated bowl, 1½-inch back spud; with solid plastic, open front elongated seat with check hinges of the following types or equal:

| | American Standard | Crane | Kohler |
|---|---|---|---|
| Closet | "Instanto" 2511.012 | "Rapidway" 3-462 | "Sifton" K-4460-ER |
| Seat | Church 5321.070 | Olsonite 95 | "Lustra" K-4670-C |
| Electronic Flush valve | 1.5 Gallon per flush, Diaphragm or piston typeconcealed behind wall with integral control stop and through the wall infrared "hands free" sensor and manual flushing button. Flush valve shall have vacuum breaker suitable for use with 1 1/2-inch spud water closets | | |
| | TOTO, Model No. TET2ARS31. Transformer Model No. TEF61RSV17 | | SLOAN, Model No. 152-ES-S. Transformer Model No. EL-208-100VA or EL-154-50VA |
| Carrier | Concealed closet chair carrier with 4-inch outlet connection; Zurn, J.R. Smith, Josam, Wade, or equal. | | |

Water closet (1.5 Gallon per flush, floor mounted with tank for CHP Office.)—

Water closet shall be 1.5 gallon per flush maximum, vitreous china, siphon jet, elongated bowl, close coupled tank, floor mounted, with solid plastic open front elongated seat with check hinges. Tank shall be water pressurized air reservoir type. Water closet shall meet or exceed ANSI Standard: A112.19.2. Closet and accessories shall be the following types or equal:

| | American Standard | Crane | Kohler |
|---|---|---|---|
| Closet | "Cadel EL 1.6/PA" 2292.100 | "Economiser" 3-604 | "Wellworth" K-3458 |
| Seat | Olsonite 95 | Church 5321.070 | "Lustra" K-4670-C |

Urinal: Urinal shall be wall hung, vitreous china, blowout type, 1¼-inch back spud, integral shields, spreader, and trap of following types or equal:

| | American Standard | Crane | Eljer |
|---|---|---|---|
| Urinal | "Lynbrook" 6538.010 | "Delrio" 7-182 | "Correcto Watersaver" 161-1075 |
| Electronic Flush valve | 1 Gallon per flush, Diaphragm or piston type concealed behind wall with integral control stop and through the wall infrared "hand free" sensor. Flush valve shall have vacuum breaker suitable for use with 1¼-inch spud urinals. | | |
| | TOTO, Model No. TET2ARS & VB13RB-11. Transformer Model TEF61RSV 17. | SLOAN, Model No. 195-ES-S. Transformer Model No. EL-208-100VA or EL-154-50VA. | |
| Carrier | Concealed carrier with top and bottom bearing plates and 3-inch outlet connection; for CMU wall; Zurn, J.R. Smith, Josam, Wade, or equal. | | |

Urinal (Disabled Accessible): Urinal shall be disabled accessible, vitreous china, washout type, ¾-inch back spud, wall hung, integral shields, spreader, and trap of following types or equal:

| | American Standard | Crane | Eljer |
|---|---|---|---|
| Urinal | | | "Savon Watersaver" 161-1095 |
| Electronic Flush valve | 1Gallon per flush, Diaphragm or piston type concealed behind wall with integral control stop and through the wall infrared "hand free" sensor. Flush valve shall have vacuum breaker suitable for use with ¾-inch spud urinals. | | |
| Carrier | Concealed carrier with top and bottom bearing plates and 3-inch outlet connection; Zurn, J.R. Smith, Josam, Wade, or equal. | | |

Lavatory: Lavatory shall be vitreous china, with back, integral perforated grid drain, drilled for 4-inch centers, size 20” x 18”, with faucet and concealed chair carrier, of the following types, or equal:

| | Eljer | Crane | Kohler |
|---|---|---|---|
| Lavatory | "Delwyn" 051-1644 | "Norwich" 1-194-V | "Greenwich " K-2032 |
| Drain | 803-0552 | 8-5230 | K-7715 |
| Electronic Faucet | Electronic faucet shall be AC power source with 12 volt DC transformer included, ADA compliance with mounting plates | | |
| | TOTO, TEL3AAC-10 & TN71V1 | SLOAN, ETF-600A | Kohler, K-13662-2E |
| Carrier | Concealed arm wall mounted carrier with leveling screws and locking devices; Zurn, J.R. Smith, Josam, Wade, or equal. | | |

Lavatory (wall-mounted in CHP Office).--

Lavatory shall be vitreous china, integral perforated grid drain, drilled for 4 inch centers, size 20 inch x 18 inch, with single extra long lever mixing faucet and chair carrier with concealed arms. Lavatory faucet shall be equipped with a flow limiting device that limits the flow rate of water to no more than 1/2 Gallon per minute. Lavatory and accessories shall be of the following types or equal:

| | Eljer | Crane | Kohler |
|---|---|---|---|
| Lavatory | "Lucerne" "Blair" 0355.012 051-1308 | "Norwich" 1-194-V , 1165V | "Chesapeak" K-1729 |
| Drain | -- | C-1065-G or Moen 52659 | K-7715 |
| Supplies | Brass Craft FR1711C | C-1151 or Moen 52664 | K-7605 |
| Faucet | 2385.130, 2175.200 | Moen Chateau 8400 L4635 | K-15592-5 |
| Trap | 1 ¼ inch chromium plated brass exposed bent tube adjustable 17-gage minimum thickness. | | |
| Carrier | Concealed wall mounted carrier with leveling screws and locking devices; Zurn, J.R. Smith, Josam, Wade, Jonespec, or equal. | | |

Kitchen sink: Kitchen sink shall be constructed of 18-gage minimum stainless steel with full undercoating. Sink shall be single compartment, self-rimmed with ledge for faucet. Normal bowl size shall be 21 inch x 15 inch with an outside depth of 7 inch or less. Sink shall be supplied with stainless steel strainer and chrome P-trap. Kitchen sink faucet shall be metal body, chrome plated, single lever mixing type with 8 inch long swing spout aerator and replaceable ceramic cartridge.

Service Sink: Service sink shall be acid resisting enameled cast iron, plain undrilled back, stainless steel or chrome plated sheet brass rim guard on three sides, stainless steel strainer, size approximately 22” x 18”, with 3-inch floor stand trap with integral cleanout, of the following types, or equal:

| | American Standard | Eljer | Kohler |
|---|---|---|---|
| Service sink | "Lakewell" 7692.023 | 242-0150 | "Bannon" K-6718 |
| Strainer | 8301.061 | ----- | ----- |
| Trap | 7798.176 | 804-1060 w/strainer | K-6673 w/strainer |
| Faucet | Bucket hook, vacuum breaker, integral stops, top brace, long spout with hose threads: | | |
| | 8344.111 or 8343.105 | 749-1200 | K8907 |

Water Heater (electric): Water heater shall be minimum capacity as shown on plans, designed for minimum 125 psig, interlocking (nonsimultaneous) or single element, glass lined, magnesium anodes, cold water drop tube, high temperature energy shut-off device, valved drain, high density R-8 minimum foam insulation and finished with a steel jacket with baked enamel finish. Water heater shall meet the requirements of the California Energy Commission.
Water heater shall be equipped with an ASME labeled, tank mounted, pressure and temperature relief valve sized for maximum input.

Under Sink Water Heater: Under sink water heater shall be tankless, electric water heater, flow activated, suitable for 20 Psi to 45 Psi water pressure, and shall provide a 95º F water temperature rise at 0.5 gallon per minute water flow. Heater shall be wall mounted and equipped with metal housing, stainless steel heating coils and over-temperature protection. Capacity and electrical service shall be as shown on the plans.

Water Chiller: Water chiller shall be a standard commercially manufactured remote type, 115 volts AC, air-cooled with an adjustable temperature control dial, and shall produce a minimum of 8 gallons of 50°F water per hour based on an inlet water temperature of 80°F and an ambient room temperature of 90°F.
Water chiller compressor shall be hermetically sealed and insulated.
Water chiller shall be Haws, HCR8; Elkay, ER-14; Sunroc, RP-14-4; or equal.

Emergency Eyewash: Emergency eyewash shall be 1 ¼-inch minimum, galvanized steel pipe stand with 9 inch floor mounting flange and equipped with 8.5 inch x 11 inch pictorial and worded emergency identification sign.
Eyewash shall have a 10 inch diameter stainless steel bowl, anti-surge heads and circular chrome plated spray ring to bathe the entire face, dust cover assembly, and a stay-open ball valve operated by a flag handle. Eyewash unit shall be mounted on the pipe stand.
Emergency eyewash shall be Haws, Speakman, Western, or equal.

Drinking Fountain: Drinking fountain shall be a "Hi-Lo" mounted unit with 14 gauge, Type 304 Stainless Steel satin finish. Drinking fountain shall be equipped with front push button valves, 1¼-inch NPT traps, polish chrome-plated brass bubbler heads and waste strainers, matching stainless steel back panel and vandal-resistant bottom plate. Bowls feature a one-piece 14 gauge stamping with rounded design and integral ¼" stainless steel mounting plates. Drinking fountain shall be completed with mounting plate and support carrier.
Drinking fountain shall be Haws, Model 1119.14; Elkay, Model EHWM217C; Sunroc, Model DRF-3801 or equal.

## PART 3 - EXECUTION

### INSTALLATION

All finish for exposed metal on any fixture, including wall flanges, bolts, nuts and washers, shall be polished chrome plated.

Fixtures shall be sealed to wall with silicone caulk bead.

All exposed metal surfaces on fixture supports shall be enameled to harmonize with fixtures.

Wall mounted fixtures shall be installed on concealed carriers designed to support weight of fixture from the floor. Carriers shall be made for the specific fixture to be supported and for the particular installation conditions.

All fixtures shall be provided with accessible compression stops.

Fixture mounting heights: Unless otherwise noted, all fixtures shall be mounted at the heights shown on plans.

Water closet: Water closet designated as disabled accessible on the plans shall be installed with disabled accessible flush valve and shall be installed at 17 inches from the top of seat to the finished floor.

Lavatory: Faucet shall be mounted in right-side hole. Unused faucet holes shall be closed with chrome plated covers. Traps shall be installed behind wall in plumbing gallery.

Service sink: Service sink double faucet shall be mounted on wall above sink back with spout outlet face 16 inches above service sink rim.

Water heater: Water heater shall be installed with seismic restraints, inlet ball valve, insulating connections and ¾-inch temperature and pressure relief drain pipe as shown on plans. Under sink water heater shall be installed in accordance with the manufacturer's recommendations.

Water chiller: Water chiller shall be installed in the plumbing gallery near the drinking fountains on a galvanized steel wall shelf with brackets, adequately sized and bolted to the wall. Headroom and walking spaces in the plumbing gallery shall be preserved.

Insulation: All hot water supply, and water pipe between the water chiller and drinking fountains shall be wrapped with insulating material.

Emergency eyewash: Emergency eyewash shall be installed in accordance with the manufacturer's recommendations.

**FIELD QUALITY CONTROL**

Testing:

The Contractor shall test piping as specified elsewhere in these special provisions.

The Engineer will inspect all installed fixtures for proper installation and test for proper operation after all plumbing work is complete.

## 12-15.05 HEATING, VENTILATING AND AIR CONDITIONING EQUIPMENT AND SYSTEMS

### PART 1 - GENERAL

Scope: This work shall consist of furnishing, installing and testing heating, ventilating and air conditioning (HVAC) equipment in accordance with the details shown on the plans and these special provisions.
The performance rating and electric service of the HVAC equipment shall be as shown on the plans.

Temperature Controls: Thermostats, microprocessor controllers, relays, timer switches, and other sensor type control devices required for this work shall be furnished and installed by the supplier of the heating, ventilating and air conditioning equipment. All temperature control wiring shall be furnished and installed in accordance with the requirements specified in Section 12-16, "Electrical," of these special provisions.

Codes and Standards:

Equipment and systems shall conform to California State Energy Commission Regulations and, where applicable, shall be American Refrigeration Institute (ARI), American Gas Association (AGA), Sheet Metal and Air Conditioning Contractors National Association, Inc. (SMACNA), and Air Movement and Control Association (AMCA) approved for performance ratings and application shown on the plans.

Any appliance for which there is a California standard established in the Appliance Efficiency Standards may be installed only if the manufacturer has certified to the Commission, as specified in those regulations, that the appliance complies with the applicable standards for that appliance. Space conditioning equipment may be installed only if the manufacturer has certified that the equipment meets or exceeds all applicable efficiency requirements listed in the Energy Efficiency Standards.

## PART 2 - PRODUCTS

### HEATING AND COOLING UNITS

Heat Pump (Wall Mounted): Heat pump shall be wall mounted, through-the-wall type with backup electrical resistance heating, rotary type compressor, and shall include slide-out chassis design, thermostat, adjustable discharge grilles, multi-speed fan, and integral thermal overload protection.

Heat Pump (Ductless): Heat pump shall consist of an outdoor condenser unit with an indoor fan/coil unit. The condenser unit shall consist of a rotary type compressor, condensing coil, fan and all controls, tubing and appurtenances required for a complete operating system. The indoor fan coil units shall consist of an evaporating coil, expansion control device, propeller fan, auxiliary electric heat strips and thermostat. In addition, the indoor unit shall come with a plug or local disconnect. The system shall provide heating or cooling as required by the thermostat. Units shall be Sanyo, Mitsubishi Electric, Toshiba, or equal.

### FANS AND VENTILATORS

**Combination Heat-Light-Exhaust fan.--**

Combination Heat-Light-Exhaust fan shall be ceiling mounted, recessed type unit with metal housing, grille and backdraft damper. Ducting size shall be as required by the manufacturer. Combination heat-light-exhaust fan shall be Panasonic, No. FV11VHL1; Broan, No. QTXE110HLor equal.

### HVAC CONTROLS

**Remote thermostat (ductless heat pump)**.--
Remote thermostat shall be a microprocessor control with LCD readouts wall mounted unit. Remote thermostat for the ductless heat pump shall be furnished by the HVAC equipment manufacturer to be fully integrated with the equipment furnished.

### AUXILIARY HVAC COMPONENTS

Unless specified herein, all components shall be sized and have the characteristics as shown on the plans.

Duct Supports: Duct supports shall be hot-dip galvanized steel.

Refrigerant and Condensate Drain Piping: Refrigerant and condensate drain piping shall be rigid, Type L copper tubing with brazed solder fittings. The suction line shall be insulated, with vapor barrier and shall be weatherproofed for exterior installation. Factory sealed tubing shall not be used.

## PART 3 - EXECUTION

### INSTALLATION

Ventilator:

Exhaust duct connected to the combination heat-vent-light fan shall be routed to the roof and shall terminate in a weatherproof cap. Duct sizes shall be as recommended by the manufacturer.

Condensate Drains: Heat pumps shall be provided with condensate drain trap and piping. Outdoor piping shall extend to the nearest gutter or as shown on the plans. Air gap shall be installed where required by code. Interior condensate drain piping shall be insulated with foam insulation.

Mounting Heights: Thermostats shall be installed as shown on the plans.

Vents: Vents shall be securely fastened to the building construction, shall be provided with a collar at all ceiling penetrations and shall terminate with a weather cap fabricated of the same material.

**FIELD QUALITY CONTROL**

Pre-test Requirements:

Before starting or operating ,equipment shall be cleaned and checked for proper installation, lubrication and servicing.

The Contractor shall replace or revise any equipment or work found deficient during tests.

Project Completion Tests:

The Engineer shall be notified at least 3 working days in advance of starting project completion tests.

Upon completion of mechanical work and pre-test requirements, or at such time prior to completion as determined by the Engineer, the Contractor shall operate and test installed mechanical equipment for at least 4-hours to demonstrate satisfactory overall operation.

## SECTION 12-16. ELECTRICAL

### 12-16.01 ELECTRICAL WORK

### PART 1 - GENERAL

**SUMMARY**

Scope: This work shall consist of performing electrical work in accordance with the details shown on the plans and these special provisions.

Electrical work shall include furnishing all labor, materials, equipment and services required to construct and install the complete electrical system shown on the plans and the work of installing electrical connections for the thermostats, motors, and controls specified elsewhere in these special provisions.

System layouts are generally diagrammatic and location of equipment is approximate. Exact routing of conduits and other facilities and location of equipment is to be governed by structural conditions and other obstructions, and shall be coordinated with the work of other trades. Equipment requiring maintenance and inspection shall be located where it is readily accessible for the performance of such maintenance and inspection.

Related Work: Earthwork, foundations, sheet metal, painting, mechanical and such other work incidental to and necessary for the proper installation and operation of the electrical work shall be done in accordance with the requirements specified for similar work elsewhere in these special provisions.

**CLOSEOUT SUBMITTALS**

Operation and Maintenance Manuals:

Prior to the completion of the contract, 3 identified copies of the operation and maintenance instructions with parts lists for the equipment specified herein shall be delivered to the Engineer at the jobsite. The instructions and parts

lists shall be in a bound manual form and shall be complete and adequate for the equipment installed. Inadequate or incomplete material will be returned. The Contractor shall resubmit adequate and complete manuals at no expense to the State.

**QUALITY ASSURANCE**

Codes and Standards: All work performed and materials installed shall be in accordance with the CEC and the California Code of Regulations, Title 8, Chapter 4, "Electrical Safety Orders."

Warranties and Guarantees: Manufacturer's warranties and guarantees for materials or equipment used in the work shall be delivered to the Engineer at the jobsite prior to acceptance of the contract.

**PART 2 - PRODUCTS (Not applicable)**

**PART 3 - EXECUTION**

**TESTING**

After the electrical system installation work has been completed, the electrical system shall be tested in the presence of the Engineer to demonstrate that the electrical system functions properly. The Contractor shall make necessary repairs, replacements, adjustments and retests at his expense.

**12-16.02 BASIC MATERIALS AND METHODS**

**PART 1 - GENERAL**

**SUMMARY**

Scope: This work shall consist of furnishing and installing conduits, conductors, fittings, and wiring devices in accordance with the details shown on the plans and these special provisions.

Conduits, conductors, fittings, and wiring devices shall include those accessories and appurtenances, not mentioned, that are required for the proper installation and operation of the electrical system.

Related Work:

Roof penetrations shall be flashed and sealed watertight conforming to the requirements specified under "Sheet Metal Flashing" in Section 12-7, "Thermal and Moisture Protection," of these special provisions.

**SUBMITTALS**

Product Data:

A list of materials and equipment to be installed and the manufacturer's descriptive data shall be submitted for approval. Any other data as requested by the Engineer shall also be submitted for approval.

Manufacturer's descriptive data shall include complete description, performance data and installation instructions for the materials and equipment specified herein. Control and wiring diagrams, rough-in dimensions for recessed junction and pull boxes, and component layout shall be included where applicable. All control and power conductors on the shop drawings shall be identified with wire numbers.

## PART 2 - PRODUCTS

### CONDUITS AND FITTINGS

Rigid Steel Conduit and Fittings:

Rigid steel conduit shall be threaded, full weight rigid steel, hot-dip galvanized inside and outside with steel or malleable iron fittings. Fittings shall be threaded unless otherwise specified or shown on the plans.

Split or three-piece couplings shall be electroplated, malleable cast iron couplings.

Insulated grounding bushings shall be threaded malleable cast iron body with plastic insulated throat and steel, lay-in ground lug with compression screw.

Insulated metallic bushings shall be threaded malleable cast iron body with plastic insulated throat.

Electrical Metallic Tubing (EMT) and Fittings:

Electrical metallic tubing shall be formed of cold rolled strip steel, electrical resistance welded continuously along the longitudinal seam with zinc coating outside and enamel or lacquer coating inside.

Couplings shall be electroplated, rain and concrete tight, gland compression type, steel body couplings with malleable iron nuts.

Connectors shall be electroplated, rain and concrete tight, gland compression type, steel body connectors with male hub, malleable iron nut and insulated plastic throat.

Flexible Metallic Conduit and Fittings:

Flexible metallic conduit shall be fabricated in continuous lengths from galvanized steel strip, spirally wound and formed to provide an interlocking design.

Fittings shall be electroplated screw-in type with malleable cast iron body and threaded male hub with insulated throat.

Liquid Tight Flexible Metallic Conduit and Fittings:

Liquid tight flexible metallic conduit shall be fabricated in continuous length from galvanized sheet steel, spirally wound and formed to provide an interlocking design with an extruded polyvinyl chloride cover.

Fittings shall be electroplated, malleable cast iron body, with cap nut, grounding ferrule, and connector body with insulated throat.

Rigid Non-metallic Conduit and Fittings:

Rigid non-metallic conduit shall be Schedule 40, high impact, nonconducting, self-extinguishing polyvinyl chloride (PVC) rigid non-metallic conduit for direct underground burial.

Couplings shall be PVC, socket type or thread on one end and socket type on the other end as required for the particular application.

Terminal adapters for adapting PVC conduit to boxes, threaded fittings, or metallic conduit system shall be PVC adapters with threads on one end and socket type on the other end.

## CABLES AND CONDUCTORS

Cables: Cables used for closed circuit television system (CCTV) are specified under closed circuit television system in these special provisions.

Telephone Cables: Telephone cables from telephone terminal board in womens' comfort station to mens' comfort station and to public telephone units shall be twisted unshielded 4-pair (UTP) category 5e with #24 AWG solid copper conductors.

Telephone cable from utility telephone pole to telephone terminal board in Women's comfort station and from telephone terminal board to CHP building shall be twisted unshielded 6-pair (UTP) communications cable with #18 AWG stranded, tinned copper, rated 300-volt with polyvinyl chloride jacket.

Conductors:

Conductors shall be stranded copper wire.

Conductor insulation types unless otherwise shown or specified, shall be as follows:

1. Conductors across hinges of control panel enclosures shall be Type MTW.
2. Conductors shall be type XHHW-2 in wet, underground, and outdoor locations.
3. Conductors shall be type THHN in dry locations.

Wire Connections and Devices: Wire connections and devices shall be pressure or compression type, except that connectors for No. 10 AWG and smaller conductors in dry locations may be preinsulated spring-pressure type.

## ELECTRICAL BOXES

Outlet, Device and Junction Boxes:

Unless otherwise shown or specified, boxes shall be galvanized steel boxes with knock-outs and shall be the size and configuration best suited to the application indicated on the plans. Minimum size of outlet, receptacle, switch or junction boxes shall be 4 inches square by 1½ inches deep, except that switch boxes for the installation of single switches and outlet boxes for flush-mounted light fixtures shall be 2” x 3” x 1½” deep.

Multiple switches shall be installed in standard gang boxes, unless otherwise specified or shown on the plans.

Cast metal boxes shall be cast iron boxes with threaded hubs and shall be of the size and configuration best suited to the application shown on the plans.

Flush-mounted boxes shall have stainless steel covers, 0.04 inch thick. Cover screws shall be metal with finish to match cover finish.

Unless otherwise shown or specified, surface-mounted boxes shall have galvanized steel covers with metal screws.

Weatherproof junction boxes shall have cast metal covers with gaskets.

Weatherproof switch and receptacle boxes shall have gasketed covers with gasketed hinged flaps to cover switches and receptacles.

All PVC switch and receptacle boxes shall have gasketed covers with gasketed hinged flaps to cover switches and receptacles.

Sectional device plates will not be permitted.

Underground Pull Boxes:

Pull boxes shall be high density reinforced concrete box with ultraviolet inhibitor polyethylene etched face anchored in concrete and fiberglass cover with hold down bolts. The polyethylene and fiberglass material shall be fire resistant and show no appreciable change in physical properties with exposure to the weather. No. 3 1/2 pull box shall be Brooks Products, No. 3 1/2; Christy Concrete Products, N9; or equal. No. 5 pull box shall be Brooks Products No. 5; Christy Concrete Products, N30; or equal.

Traffic rated pull boxes shall be high density reinforced concrete box with steel cover with hold down bolts and bonding strap. Pull box and cover shall be designed for H20 loading. No. 3 1/2 pull box shall have inside dimensions of 19¼ inches by 13¼ inches and No. 5 pull box shall have inside dimensions of 27 1/8 inches by 16 1/8 inches.

**RECEPTACLES AND SWITCHES**

Ground Fault Circuit Interrupter Receptacles, (GFCI): Ground fault circuit interrupter receptacles shall be NEMA Type 5-20R, feed-through type, ivory color, 3-wire, 20-ampere, 125-volt AC, grounding type, specification grade, duplex receptacle with ground fault interruption. Receptacle shall detect and trip at current leakage of 5 milliamperes and shall have front mounted test and reset buttons.

Duplex Receptacles: Duplex receptacles shall be NEMA Type 5-20R, 3-wire, 20-ampere, 125-volt AC, safety grounding, ivory color, specification grade receptacle suitable for wiring with stranded conductors.

Heat pump Receptacle: Heat pump receptacle shall be NEMA Type 6-20R, 3-wire, 20-ampere, 250-volt AC, safety grounding, specification grade receptacle suitable for wiring with stranded conductors.

Snap Switches: Snap switches shall be 20-ampere, 120/277-volt AC, quiet type, specification grade, ivory color switch with silver cadmium alloy contacts. Switch shall be suitable for wiring with stranded conductors.

**Wall switch occupancy sensor, type 1.--**

Wall switch occupancy, Type 1, shall be wall-mounted, passive infrared (PIR) sensor switch with adjustable photocell override and time delay. Switch shall be rated at 800 W (minimum) incandescent or 1200 VA (minimum) fluorescent at 120 V (ac) and operate on 120/277 V (ac). The switch shall be capable of manual-on/automatic off mode. The sensor switch shall cover a minimum of 850 square feet of floor area, be suitable for installation in a single gang box, and shall have a field of view of not less than 180 degrees. The time delay off setting shall be adjustable from 30 seconds to 30 minutes, initially set at 10 minutes. Light level adjustment shall be adjustable from 30 lux to 2000 lux, initially set at 800 lux.

**Wall switch occupancy sensor, type 2.--**

Wall switch occupancy sensor, type 2, shall be wall-mounted, passive infrared dual relay sensor switch with adjustable photocell override and time delay. Primary relay shall be rated at 800 W (minimum) incandescent or 1200 VA (minimum) fluorescent at 120 V (ac). Secondary relay shall be rated at 800 W (minimum) incandescent or 800 VA (minimum) fluorescent at 120 V. Switch shall operate on 120/277 V (ac). The relays in the sensor shall be capable of simultaneously controlling 2 different lighting loads or circuits. The second relay shall be independent allowing for two circuit control. The unit shall have dual manual override switches that can be used to toggle manual-on/automatic off mode for each lighting load. Sensor shall have audible alert to indicate impending light shut off. The sensor switch shall cover a minimum of 1,000 square feet of floor area, be suitable for installation in a single gang box, and shall have a field of view of not less than 180 degrees. The time delay off setting shall be adjustable from 30 seconds to 30 minutes, initially set at 10 minutes. Light level adjustment shall be adjustable from 30 lux to 2000 lux, initially set at 800 lux.

**Ceiling mounted occupancy sensor.--**

Ceiling mounted occupancy sensor, type 1 shall be a low voltage, passive infrared (PIR) sensor switch. Switch shall have an adjustable photocell override or built-in light level sensor and time delay. Switch shall operate on 24 V (dc) and shall be provided with a power pack unit. The sensor switch shall cover a minimum of 1200 square feet of floor area. Switch shall have a field of view of not less than 360 degrees, conical pattern. The time delay off setting shall be adjustable from 30 seconds to 30 minutes, initially set at 10 minutes. Light level adjustment shall be adjustable

from 30 lux to 2000 lux, initially set at 800 lux. The sensor shall have LED indicator that remains active at all times in order to verify detection within the area to be controlled.

**MISCELLANEOUS MATERIALS**

Warning Tape: Warning tape shall be 4-inch wide and contain the printed warning "CAUTION ELECTRICAL CONDUIT" in bold ¾-inch black letters at 30-inch intervals on bright orange or yellow background. The printed warning shall be non-erasable when submerged under water and resistant to insects, acids, alkali, and other corrosive elements in the soil. The tape shall have a tensile strength of not less than 155 pounds per 4-inch wide strip and shall have a minimum elongation of 700 percent before breaking.

Pull Ropes: Pull ropes shall be nylon or polypropylene with a minimum tensile strength of 500 pound-force.

Watertight Conduit Plugs: Watertight conduit plugs shall be a hollow or solid stem expansion plugs complete with inner and outer white polypropylene compression plates and red thermoplastic rubber seal. Seal material shall be non-stick type rubber resistant to oils, salt, and alkaline substances normally available at the construction sites.

Anchorage Devices: Anchorage devices shall be corrosion resistant, toggle bolts, wood screws, bolts, machine screws, studs, expansion shields, and expansion anchors and inserts.

Electrical Supporting Devices:

Electrical supporting devices shall be one hole conduit clamps with clamp backs, hot-dipped galvanized, malleable cast iron.

Construction channel shall be 1 5/8 inches by 1 5/8 inches, 12-gage galvanized steel channel with 17/32-inch diameter bolt holes, 1½ inches on center in the base of the channel.

Ground rod(s): Ground rod(s) shall be a ¾-inch (minimum) galvanized or copper clad steel rod, 10 feet long.

Telephone Outlet Boxes:

Telephone outlet boxes shall be 4-inch square boxes and plates with modular type telephone outlet. Boxes on stud walls shall have plaster ring.

Plates for flush mounting outlets in finished room shall be Type 430 stainless steel, 0.04 inch thick with satin finish.

## PART 3 - EXECUTION

**INSTALLATION**

Conduit:

Rigid steel conduit shall be used unless otherwise shown on the plans or specified in these special provisions.

Electrical metallic tubing may be used in furred spaces and for exposed work indoors above the switch height.

Unless otherwise specified or shown on the plans, flexible metal conduit shall be used to connect suspended lighting fixtures, motors, HVAC equipment, and other equipment subject to vibration in dry locations.

Unless otherwise specified or shown on the plans, liquid-tight flexible metal conduit shall be used to connect motors, HVAC equipment, and other equipment subject to vibration in wet locations.

Rigid non-metallic conduit shall be used at the locations shown on the plans for direct underground burial 30 inches below grade. All risers and elbows through building floors shall be rigid steel.

Conduit Installation:

Conduit trade sizes are shown on the plans. No deviation from the conduit size shown on the plans will be permitted without written permission from the Engineer.

Conduit shall be concealed unless otherwise shown on the plans.

Conduits shall be tightly covered and well protected during construction using metallic bushings and bushing "pennies" to seal open ends.

Rigid non-metallic conduit bends of 30 degrees or greater shall be factory-made long radius sweeps. Bends less than 30 degrees shall be made using an approved heat box.

A pull rope shall be installed in all empty conduits. At least 3 feet of pull rope shall be doubled back into the conduit at each termination.

Locations of conduit runs shall be planned in advance of the installation and coordinated with the ductwork, plumbing, ceiling and wall construction in the same areas and shall not unnecessarily cross other conduits or pipe, nor prevent removal of ceiling tiles or panels, nor block access to mechanical or electrical equipment.

Where practical, conduits shall be installed in groups in parallel, vertical or horizontal runs and at elevations that avoid unnecessary offsets.

Exposed conduit shall be installed parallel and at right angles to the building lines.

Conduits shall not be placed closer than 12 inches from a parallel hot water or 3 inches from such lines crossing perpendicular to the runs.

All raceway systems shall be secured to the building structures using specified fasteners, clamps and hangers.

All metal conduits, metal conduit risers, and metal conduit elbows in contact with soil or concrete shall be wrapped with a double layer of 20-mil thick pipe wrapping tape. Each individual layer shall be overlapped a minimum of 50%.

Single conduit runs shall be supported by using one hole pipe clamps. Where run horizontally on walls in damp or wet locations, conduit shall be installed with "clamp backs" to space conduit off the surface.

Multiple conduit runs shall be supported with construction channel secured to the building structure. Conduits shall be fastened to construction channel with channel compatible pipe clamps.

Raceways of different types shall be joined using approved couplings or transition fittings.

Expansion couplings shall be installed where conduit crosses a building separation or expansion joint.

All floor and wall penetrations shall be sealed water-tight.

Existing underground conduit to be incorporated into a new system shall be cleaned with a mandrel or cylindrical wire brush and blown out with compressed air.

Conduit Terminations:

Rigid steel conduits shall be securely fastened to cabinets, boxes and gutters using 2 locknuts and specified insulating metallic bushing. Electrical metallic tubing shall be securely fastened to cabinets, boxes and gutters using specified connectors. Conduit terminations at exposed weatherproof enclosures and cast outlet boxes shall be made watertight using specified hubs.

Grounding bushings with bonding jumpers shall be installed on all type of conduits terminating at concentric knockouts and on all conduits containing service conductors, grounding electrode conductor, and conductors feeding separate buildings.

Conductor and Cable Installation:

Conductors shall not be installed in conduit until all work of any nature that may cause injury is completed. Care shall be taken in pulling conductors that insulation is not damaged. An approved non-petroleum base and insulating type pulling compound shall be used as needed.

All cables shall be installed and tested in accordance with manufacturer's recommendations.

Splices and joints shall be insulated with insulation equivalent to that of the conductor.

Provide 6 inches of slack at each outlet and device connection. If the outlet or device is not at the end of a run of wire, connection shall be made with correctly colored pigtails tapped to the runs with splices as specified herein.

Branch circuit conductors in panelboards and load centers shall be neatly trained along a path from the breaker terminals to their exit point. The conductors shall have ample length to transverse the path without strain, but shall not be so long as to require coiling, doubling back, or cramming. The path shall transverse the panelboard gutter spaces without entering a gutter containing service conductors and, unless otherwise shown on the plans, without entering the gutter space of any panelboard feeder.

All pressure type connectors and lugs shall be retightened after the initial set.

Splices in underground pull boxes and similar locations shall be made watertight.

Junction boxes in furred or accessible ceiling spaces shall be identified with felt-tip pen denoting the circuits contained in the box.

Conductor Identification:

The neutral and equipment grounding conductors shall be identified as follows:

Neutral conductor shall have a white or natural gray insulation except that conductors No. 4 and larger may be identified by distinctive white marker such as paint or white tape at each termination.

Equipment grounding conductor shall be bare or insulated. If insulated, equipment grounding conductors shall have green or green with one or more yellow stripes insulation over its entire length except that conductors No. 4 and larger may be permanently identified by distinctive green markers such as paint or green tape over its entire exposed insulation.

Ungrounded feeder and branch circuit conductors shall be color coded by continuously colored insulation, except conductors No. 6 AWG or larger may be color coded by colored tape at each connection and where accessible. Ungrounded conductor color coding shall be as follows:

| SYSTEM | COLOR CODE |
|---|---|
| 120/240V-Single phase | Black, blue |

Once an insulated circuit conductor, including grounded and ungrounded conductors, is identified with a specific color code, that color code shall be used for the entire length of the circuit.

Where more than one branch circuit enters or leaves a conduit, panel, gutter, or junction box, each conductor shall be identified by its panelboard and circuit number. All control conductors including control conductors of manufacturer supplied and field wired control devices shall be identified at each termination with the wire numbers

shown on the plans, approved working drawings, and as directed by the Engineer where deemed necessary. Identification shall be made with one of the following:

1. Adhesive backed paper or cloth wrap-around markers with clear, heat shrinkable tubing sealed over either type of marker.
2. Self-laminating wrap around type, printable, transparent, permanent heat bonding type thermoplastic film markers.
3. Pre-printed, white, heat-shrinkable tubing.

Each terminal block shall have a molded marking strip attached with screws. The identifying numbers of the terminating conductors, as shown on the plans or on the submittal drawings, shall be engraved in the marking strip.

Outlet, Device and Junction Box Installation:

Where exposed threaded steel conduits are connected to an outlet, device, or junction box below switch height, the box shall be a cast metal box. Unless otherwise shown on the plans or specified in these special provisions, all other boxes shall be sheet steel boxes. Weatherproof outlet, device and junction boxes shall have cast metal covers with gaskets. Unless otherwise shown on the plans or specified in these special provisions, all other boxes shall have standard galvanized covers.

All boxes shall finish flush with building walls, ceiling and floors except where exposed work is called for.

Raised device covers (plaster rings) shall be installed on all boxes concealed in concrete, masonry or stud walls.

No unused openings shall be left in any box. Knockout seals shall be installed as required to close openings.

Outlet, device, and junction boxes shall be installed at the locations and elevations shown on the plans or specified herein. Adjustments to locations may be made as required by structural conditions and to suit coordination requirements of other trades.

Boxes in stud walls and partitions shall not be mounted back to back. Through-wall boxes shall not be used.

Boxes installed in metal stud walls shall be equipped with brackets designed for attaching directly to the studs or shall be mounted on heavy gauge galvanized steel, snap-in box supports.

Fixture outlet boxes installed in suspended ceilings of gypsum board or lath and plaster construction shall be mounted on 16-gage metal channel bars attached to main ceiling runners.

Fixture outlet boxes for pendant-mounted fixtures installed in suspended ceilings supporting acoustical tiles or panels shall be supported directly from the structures above.

Underground Pull Box Installation:

Electrical pull box covers or lids shall be marked "ELECTRICAL." Telephone service pull box covers or lids shall have plain, unmarked covers.

The bottom of pull boxes shall be bedded in 6 inches of clean, crushed rock or gravel and shall be grouted with 1½-inch thick grout prior to installation of conductors. Grout shall be sloped to a one-inch PVC pipe drain hole. Conduit shall be sealed in place with grout.

Top of pull boxes shall be flush with surrounding grade or top of curb. In unpaved areas where pull box is not immediately adjacent to and protected by a concrete foundation, pole or other protective construction, the top of pull box shall be set at plus one inch above surrounding grade. Pull boxes shown on the plans in the vicinity of curbs shall be placed adjacent to the back of curb. Pull boxes shown on the plans adjacent to lighting standards shall be placed on the side of foundation facing away from traffic.

Ground Rod(s) Installation: The ground rod(s) shall be driven vertically until the top is 6 inches above the surrounding surface. When vertical penetration of the ground rod cannot be obtained, an equivalent horizontal grounding system, approved by the Engineer, shall be installed.

Anchorages:

Hangers, brackets, conduit straps, supports, and electrical equipment shall be rigidly and securely fastened to surfaces by means of toggle bolts on hollow masonry; expansion shields and machine screws, or expansion anchors and studs or standard preset inserts on concrete or solid masonry; machine screws or bolts on metal surfaces; and wood or lag screws on wood construction.

Anchorage devices shall be installed in accordance with the anchorage manufacturer's recommendations.

Mounting heights: Electrical system components shall be mounted at the following mounting heights, unless otherwise shown on the plans. The mounting height dimensions shall be measured above the finished floor to the bottom of the device or component.

| | |
|---|---|
| Thermostats | 3’-4” |
| Wall switches | 3’-4” maximum |
| Convenience outlets | 3’-4” in utility area |
| Telephone outlets | 2’-0” minimum in CHP building<br>3'4" in utility area. |

## 12-16.03 SERVICE AND DISTRIBUTION

## PART 1 - GENERAL

### SUMMARY

Scope: This work shall consist of furnishing and installing service and distribution equipment in accordance with the requirements of the serving utilities, the details shown on the plans and these special provisions.

Attention is directed to "Utility Connection" in Section 12-1, "General Requirements," of these special provisions regarding arrangements, permits, licenses, charges, fees and costs for utility connections and extensions.

Related Work: Concrete and reinforcement for service pedestal shall conform to the requirements specified for minor work under "Cast-in-Place Concrete," in Section 12-3, "Concrete and Reinforcement," of these special provisions.

### SUBMITTALS

Installation Details: The Contractor shall submit complete service installation details to the serving utilities for approval. Prior to submitting installation details to the serving utility, the Contractor shall have said drawings reviewed and stamped "APPROVED" by the Engineer. Submittals shall be approved by the serving utility prior to commencing work.

Product Data:

A list of materials and equipment to be installed and the manufacturer's descriptive data shall be submitted for approval. Any other data as requested by the Engineer shall also be submitted for approval.

Manufacturer's descriptive data shall include complete description, performance data and installation instructions for the materials and equipment specified herein. Control and wiring diagrams, rough-in dimensions, and component layout shall be included where applicable. All control and power conductors on the shop drawings shall be identified with wire numbers.

## PART 2 - PRODUCTS

Service Equipment: Service equipment, pedestal mounted, shall contain a pull section, metering compartment, service disconnect switch for 120/240-volt, 200-ampere, single-phase, 3-wire service and a distribution compartment with circuit breakers feeding various panels, as shown on the plans.

Enclosure: Enclosure shall be NEMA 3R enclosure. Exterior shall be 12-gage and interior shall be 14-gage sheet steel. All screws, latches, hinge pins and similar hardware shall be stainless steel. Circuit breaker shall be operable with the exterior door open. Exterior door shall be lockable with a padlock. Enclosure finish shall be baked enamel or baked thermosetting polyester finish.

Service Disconnect Switch: Service disconnect switch shall be 2-pole, 240-volt, 250-ampere frame, 200-ampere trip, molded case circuit breaker with AC magnetic trip adjusted to 1200 amperes. The interrupting capacity of the circuit breaker shall be 42000 amperes (symmetrical) at 240-volt. Breaker shall be Square D, Type KA; or equal.

The circuit breakers in the distribution compartment feeding various panels as shown on the plan shall be 2-pole, 240-volt molded case circuit breakers with trip rating as shown on the plans. The interrupting capacity of the circuit breakers shall be 42000 amperes (symmetrical) at 240-volt.

**PART 3 - EXECUTION**

Foundation for service pedestal shall be as shown on the plans.

Installation of service and distribution equipment shall be in accordance with the requirements of the serving utilities as shown on the approved installation details.

## 12-16.04 ELECTRICAL EQUIPMENT

**PART 1 - GENERAL**

**SUMMARY**

Scope: This work shall consist of furnishing and installing panelboards, disconnect switches, transformers, and related accessories in conformance with the details shown on the plans and these special provisions.

Related Work: Anchorage devices shall be as specified under "Basic Materials and Methods" elsewhere in Section 12-16.

**SUBMITTALS**

Product Data:

A list of materials and equipment to be installed and the manufacturer's descriptive data shall be submitted for approval. Any other data as requested by the Engineer shall also be submitted for approval.

Manufacturer's descriptive data shall include complete description, performance data and installation instructions for the materials and equipment specified herein. Control and wiring diagrams, rough-in dimensions, and component layout shall be included where applicable. All control and power conductors on the shop drawings shall be identified with wire numbers.

**PART 2 - PRODUCTS**

**PANELBOARDS**

Panelboard A: Panelboard A shall be indoor type, surface-mounted, factory assembled, 1-phase, 3-wire, 120/240-volt, AC panelboard at least 20 inches wide with 100-ampere main circuit breaker, elecrolytically tin plated copper bus bars, insulated groundable neutral, hinged door and molded case branch circuit breakers as shown on the plans. Panel shall be Square D Company, NQOD; General Electric, AL; or equal.

Panelboard B: Panelboard B shall be similar to panelboard A.

Panelboard C: Panelboard C shall be indoor type, flush-mounted, factory assembled, 1-phase, 3-wire, 120/240-volt, AC panelboard at least 14.25 inches wide with 60-ampere main circuit breaker, electrolytically tin plated copper bus bars, insulated groundable neutral, hinged door and molded case branch circuit breakers as shown on the plans. Panels shall be Square D Company, QO; General Electric, AL; or equal.

Panelboard D: Panelboard D shall be indoor type, surface-mounted, factory assembled, 1-phase, 3-wire, 120/240-volt, AC panelboard, 125-ampere rated main lugs, electrolytically tin plated copper bus bars, insulated groundable neutral, hinged door and molded case branch circuit breakers as shown on the plans. Panels shall be Square D Company, QO; General Electric, AL; or equal.

**MISCELLANEOUS MATERIALS**

Nameplates: Nameplates shall be laminated phenolic plastic with white core and black front and back. Nameplate inscription shall be in capitals letters etched through the outer layer of the nameplate material.

Plywood Backing Board: Plywood backing board for mounting electrical or telephone equipment shall be ¾-inch, APA plywood panels, C-D PLUGGED and touch-sanded, Exposure 1.

## PART 3 - EXECUTION

**INSTALLATION**

Plywood Backing Board:

Plywood backing board shall be securely fastened to walls or other vertical framing.

Surface to be coated shall be cleaned of all dirt, excess materials, and filler by hand cleaning.

Exposed surfaces of plywood backing board shall be coated in conformance with the provisions in "Wood, Painted" specified under Section 12-9 "Painting," of these special provisions. The color shall match surrounding surfaces, or shall be as directed by the Engineer.

Coatings shall be applied in conformance with the manufacturer′s instructions. Each coat shall be applied to a uniform finish, free of skips, brush marks, laps or other imperfections.

Panelboard Installation:

Set cabinets plumb and symmetrical with building lines. Train interior wiring as specified under "Conductor and Cable Installation" in "Basic Materials and Methods" of these special provisions. Touch-up paint any marks, blemishes, or other finish damage suffered during installation. Replace cabinets, doors or trim exhibiting dents, bends, warps or poor fit that may impede ready access, security or integrity.

Mounting height shall be 5½ feet to the highest circuit breaker handle, measured above the finished floor.

Provide one ¾-inch empty conduit from flush panelboard enclosure to a point above furred ceiling for each 16 circuits or fraction thereof in each panelboard.

Where "Future" or "Space" is indicated on the plans, branch connectors, mounting brackets, and other hardware shall be furnished and installed for future breaker.

A typewritten directory under transparent protective cover shall be provided and set in metal frame inside each cabinet door. Directory panel designation for each circuit breaker shall include complete information concerning equipment controlled, including room number or area designated on the plans.

Transformer Installation: Connect primary to minimum value taps during construction period and prior to initial building start-up. Make voltage readings and adjust tap connections to nominal voltage during final construction review and prior to building occupancy. Install conduit connections that will prevent transmission of the transformer vibrations to the conduit system. Transformers shall be bolted to floor when floor mounted and bolted to wall with support brackets when wall mounted. Pad mounted transformers (unit substation) shall be installed as shown on the plans.

Equipment Identification:

Equipment shall be identified with nameplates fastened with self-tapping, cadmium-plated screws or nickel-plated bolts.

Nameplate inscriptions shall read as follows:

| Item | Letter height, inches | Inscription |
|---|---|---|
| Panel A | ¼” | Panel A 120/240 V, 1PH, 3W |
| Panel B | ¼” | Panel B 120/240 V, 1PH, 3W |
| Panel C | ¼” | Panel C 120/240 V, 1PH, 3W |
| Panel D | ¼” | Panel D 120/240 V, 1PH, 3W |
| Main Service Pedestal | 3/8” | Main Service and Distribution |
| Main Service Disconnect | ¼” | Main Service Disconnect |
| Water Heater Timer | ¼” | Water Heater Timer |

## 12-16.05 LIGHTING

## PART 1 – GENERAL

Scope: This work shall consist of furnishing, installing and connecting all lighting equipment in accordance with the details shown on the plans and these special provisions.

### SUBMITTALS

Manufacturer's descriptive information, photometric curves, catalog cuts, and installation instructions shall be submitted for approval. Any other data as requested by the Engineer shall also be submitted for approval.

## PART 2 - PRODUCTS

Lighting Fixture Lamps: Lighting fixture lamps shall be type and size as shown on the plans. Lamps shall be General Electric, Phillips, Sylvania, or equal. Fluorescent lamps, unless otherwise noted, shall be 4100K tri-phosphor with a CRI of 70 or greater.

Ballasts: All fixtures shall be equipped with high power factor ballasts suitable for the line voltage and for the type, size and number of lamps required by the fixture. Fluorescent ballasts shall be UL Listed, Class P and ETL Certified ballasts with sound rating A. Fluorescent ballasts shall be high-frequency electronic ballasts with power factor greater then 0.95, nominal ballast factor of 0.88 unless specified otherwise, total harmonic distortion less than 20 percent, crest factor less than or equal to 1.7, complying with ANSI C 62.41 Category A for surge protection, and FCC Part 18 for interference. Dimming ballasts shall be high frequency ballasts as specified above and shall be capable of dimming the light output from 100 percent to 20 percent of the rated light output.

Lighting Fixtures: Lighting fixtures shall be as shown on the plans and as specified herein. Outdoor luminaires shall be listed and labeled "Fixture Suitable For Wet Locations."

F1: Surface-mounted fluorescent fixture with two 32-watt T8 lamps, electronic ballast and heavy duty one-piece housing with high-impact clear acrylic, wrap-around diffuser, suitable for damp location. The fixture shall be Lithonia, Catalog No. VDS; Luminaire Lighting Corporation, LVP 751 Series, or equal.

F2: Stem-mounted fluorescent fixture with two 32-watt T8 lamps, electronic ballast and baked enamel ribbed 10% uplight reflector, complete with end plates. The fixture shall be Lithonia, Catalog No. AF10; Day Brite, Catalog No. 1FD2; or equal.

F3: Surface-mounted fluorescent fixture with two 32-watt T8 lamps, electronic ballast and one-piece, clear acrylic, wrap-around diffuser. The fixture shall be Lithonia, Catalog No. LB; or equal.

F4: Recessed fluorescent fixture with one 13-watt 120-volt lamp, electronic ballast and with polycarbonate flush prismatic lens. The fixture shall be Lithonia, Catalog No. LU6F; or equal.

MH1:

Pole mounted, 175-watt, 240-volt, metal halide, cutoff luminaire with integral ballast, cast aluminum housing, minimum 18" wide with 6" fluted arm (or architectural arm) and flat glass lens The luminaire shall be U.S. Architectural Lighting, Catalog No. AEROLUME AER; Holophane, Series Mongoose G; or equal.

Pole for luminaire shall be as shown on the plans. Pole shall have hand hole with cover plate, base plate and all necessary hardware.

MH2: Outdoor sign light, tenon base or knuckle mounted or yoke mounted, 175-watt, 120-volt metal halide architectural flood lighting fixture with solid one-piece aluminum, dark bronze, housing with integral ballast. The light fixture shall be suitable for use outdoor in wet location. The mounting shall be as shown on the plans and as recommended by the light fixture manufacturer. The luminaire shall be Holophane, Catalog No. Compact flood H710 Series; Lithonia, Catalog No. KFL Series; or equal.

MH3: Outdoor light, wall-mounted, 70-watt, 120-volt metal halide, rugged, corrosion resistant die-cast aluminum housing with integral ballast. The luminaire shall be Day-Brite, Catalog No WLM; Lithonia, Catalog No. Wall-Paks TWH; or equal.

MH4: Outdoor flag light shall be similar to Sign light MH2.

Fused Splices: Fused splices shall be Buss, Type HEX; Elastimold, Style D65; or equal; with standard midget, ferrule, 5-ampere, 250-volt, slow blowing fuses.

Photoelectric Unit, PEU: Photoelectric unit shall be cadmium sulfide photoelectric control with capacity of 1000-watt incandescent or 1800-watt inductive or fluorescent load, mounting adapter, and EEI-NEMA twist lock receptacle; Fisher-Pierce, Ripley, or equal.

Lighting Control Station, LCS: Lighting control station shall consist of a lighting contactor timer switch and pilot light in a surface mounted NEMA-12 enclosure with a hinged door.

Lighting Contactor, LC: Lighting contactor shall be electrically held, 4-pole combination lighting contactor with 120-volt AC coil and 30-ampere, double-break, silver alloy contacts; Square D Company, I.T.E., Westinghouse, or equal.

Pilot Light, PL: Pilot light shall be panel mounted, heavy duty, oil tight indicating light with 120-volt, AC, LED lamp with red domed cap.

Timer switch.-- Timer switch shall 120 volts, 0- 2 hours time range without hold, mechanical spring wound timer switch with single-pole single-throw contacts rated 20-ampere at 120 volts.

**FABRICATION**

Component Mounting:

The following electrical components shall be mounted on the back panel of the light control station enclosure:

Terminal Block, TB
Lighting contactors, LC

The following electrical components shall be mounted on the hinged door of the light control station enclosure:

Timer switch, TS
Pilot lights, PL

**PART 3 - EXECUTION**

Lighting Fixtures:

Lighting fixtures shall be mounted securely in accordance with the manufacturer's recommendations. Mounting methods shall be suitable for the particular type of ceiling or support at each location.

The Contractor shall provide all supports, hangers, spacers, channels, fasteners and other hardware necessary to support the fixtures.

Fixtures shall be set at the mounting heights shown on the plans, except heights shown shall be adjusted to meet conditions.

Ballasts:

All fluorescent fixtures shall be equipped with high power factor ballasts suitable for the line voltage and for the type, size and number of lamps required by fixture. The Contractor has the option to install low voltage dimming control provided that the Contractor submit plans and specifications with appropriate revisions for the low voltage dimming control to the Engineers for approval prior to installation.

All ballasts used in unheated areas inside the building shall be 0°F ballasts or less.

Pole Mounted Luminaires:

In the pull box adjacent to each pole for luminaire, MH1, and luminaire MH2 a fused splice connector shall be installed in each ungrounded conductor between the line and the ballast. The connector shall be readily accessible in the pull box and shall be insulated and made waterproof in accordance with the splice connector manufacturer's recommendations.

Concrete foundations shall be as shown on the plans. Anchor bolts or devices shall be accurately located and positioned to match the holes in the pole base plates. Pole and luminaire orientation shall be as indicated on the plans.

The poles for pole mounted type fixtures shall be mounted rigidly and securely on the foundations as recommended by the fixture and pole manufacturer.

**12-16.06 CLOSED CIRCUIT TELEVISION SYSTEM (CCTV)**

**GENERAL.--** Closed circuit television system (CCTV) shall be color type system consisting of fixed camera with camera enclosure, pole mount and adaptor, LCD monitor, video cable, power cables (AC/DC), connectors, CCTV Control Panel, and such other equipment required by the CCTV manufacturer to install a complete system as show on the plans. The number of closed circuit television cameras and components shall be as shown on the plans and as required by the manufacturer for the complete operation of the CCTV system.

**CAMERA.--**

Camera system shall be environmental pendant high performance integrated dome type system with build-in power surge and lightning protection. Camera system shall be auto focus, high-resolution integrated lowlight color camera/optics package that meet or exceed the following specifications:

a. Signal format shall be compatible with all applicable National Television Standards Committee (NTSC) .
b. Imager shall be ¼" color, progressive scan, interline transfer CCD (Charge Coupled Device).
c. Effective pixels shall be 768 (H) x 494 (V).
d. Horizontal resolution shall be 470 TV lines.
e. Focus shall be automatic with manual override.
f. Day (Color)/Night (Mono) switchover: manual or auto
g. Iris control shall be automatic with override.
h. Zoom: 23X optical with 10X digital
i. Maximum sensitivity @ 35 IRE shall be 0.05 lux at ½ second.
j. Video signal to noise ratio shall be >50 db.
k. Input voltage shall be 18-30 VAC with 24 VAC nominal.
l. Input power shall be less than 70 VA.
m. Operating temperature shall be -40° F ~ 140° F.

The cameras shall be Pelco Spectra III SE series or Cohu 3920 series, or equal.

**CAMERA ENCLOSURE.--**

The camera and lens shall be contained in a pole mounted enclosure. The enclosure shall consist of a standard pendant, backbox of light gray color finish and smoke lower dome. The complete camera assembly shall be supplied with all accessories and mounting hardware for mounting securely on round poles.

a. The back box shall have outside dimension of approximately 8.5" (Diameter) x 10.9" (Height including dome)
b. The enclosure shall be fabricated from seam welded 0.075" (14-gauge) steel and finished in a gray polyester powder coat.
c. The housing shall be environment al pendant type with built-in memory for storing camera and dome setting.
d. The enclosure shall have two tamper-resistant.
e. The enclosure shall have four diameter holes on protected rear area surface for mounting.
f. The enclosure shall have plunger type door tamper switch with "pull to cheat" feature and N.O./N.C. contacts clearly marked on body of the switch.
g. The enclosure shall contain sun shield, fan and heater with a heater kit rated at 24 VAC, 30 W and shall be thermostatically controlled ON at 4.44 °C and OFF at 15.56 °C.

**DIGTAL VIDEO RECORDER**.--

Digital video recorder shall be a personal computer (PC) based system and shall have the following components:

A. Intel Core 2 Duo Processor with minimum 1.8 GHz (Central Processing Unit) CPU or higher,
B. 40 total lanes PCI-Express with 2 independent 16 lane slots main board,C. Minimum of 4 GB DDR3 Random Access Memory (RAM),
D. 500 GB hard drive,
E. Dual layer DVD±R/RW,
F. Universal Serial Bus (USB) keyboard/USB scroll mouse,
G. Eight video inputs, Video capture card.

**MONITOR**.--

The LCD monitor shall be minimum 19 inches with multimode functionality and shall meet or exceed the following specifications:

LCD panel pixel array shall be 1280 x 1024.
Panel aspect ratio shall be 4:3.
Brightness shall be 35.3 cd/ft^2.
Contrast ratio shall be 500:1, and panel lamp life shall be minimum 40,000 hours.
Response time shall be 8 millisecond maximum.
Speakers shall be integrated, 2 x 1.0 watt.
Input voltage shall be 100-240 VAC, 50/60 Hz, with internal power supply.
Power consumption shall be <50 W (on), <5W (standby.)
Vertical frequency shall be 56 Hz to 75 Hz.
Operating humidity shall be 20% to 85%, non-condensing.
Operating temperature shall be 32° F ~ 104° F.

**CONNECTORS**.--

All external connections shall be made by means of connectors. The connectors shall be keyed to preclude improper hockups. All wires to and from connectors shall be color coded or appropriately marked.

INSTALLATION: CCTV system shall be installed as shown on the plans and as recommended by the CCTV system manufacturer. The Contractor shall provide all supports, fasteners and other hardware necessary for the installation of the CCTV system.

TRAINING: The Contractor shall provide two hours of on-site training on the use, operation, and maintenance of the system for not more than 4 designated State employees. The Contractor shall notify the Engineer in writing not less than 10 days in advance of proposed training class.

CCTV System final test.--The Contractor shall have a representative present during the testing and training, who is capable of troubleshooting Contractor installed equipment. The representative shall troubleshoot Contractor installed equipment as the need arises.

In the presence of the Engineer, the Contractor shall conduct a final test of the CCTV system to verify the system is complete and fully operational. The Contractor shall conduct end to end performance tests on the CCTV system. These tests shall confirm the functional operation of all elements of the system and shall include measurements of the system performance.

# AMENDMENTS TO THE STANDARD SPECIFICATIONS

## DATED MAY 2006

# AMENDMENTS ISSUE DATE: 05-01-09

## SECTION 0 GLOBAL REVISIONS
**(Issued 05-01-09)**

Global revisions are changes to contract documents not specific to a section of the Standard Specifications.
In each contract document at each occurrence, interpret the following terms as shown:

| Term | Interpretation | Conditions |
|---|---|---|
| AC | HMA | 1. Where AC means asphalt concrete<br>2. Except where existing AC is described |
| Asphalt concrete | Hot mix asphalt | Except where existing asphalt concrete is described |
| Controlling operation | Controlling activity | -- |
| Engineer's Estimate | Verified Bid Item List | -- |
| Engineering fabrics | Geosynthetics | -- |
| Notice to Contractors | Notice to Bidders | -- |
| Project information | Supplemental project information | Except in "Contract Project Information Signs" |
| Clause referring to a delay as a right-of-way delay | Delay under Section 8-1.09, "Delays" | -- |
| Reference to a working day or non–working day under Section 8-1.06, "Time of Completion" | Working day as defined in Section 1-4.02, "Glossary" | -- |
| Time extension due to an unanticipated event not caused by either party or an issue involving a third party under Section 8-1.07, "Liquidated Damages" | Non–working day | -- |
| Time extension due to an act of the Engineer or of the Department not contemplated by the contract | Time adjustment under Section 8-1.09B, "Time Adjustments" | -- |

^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^

## SECTION 1 DEFINITIONS AND TERMS
**(Issued 05-01-09)**

**Replace Section 1 with:**

## SECTION 1 GENERAL
### 1-1 GENERAL
#### 1-1.01 GENERAL

Section 1 includes general rules of interpretation.

The Department is gradually standardizing the style and language of the specifications. The new style and language includes:

1. Use of:

    1.1. Imperative mood
    1.2. Introductory modifiers

1.3. Conditional clauses

2. Elimination of:

2.1. Language variations
2.2. Definitions for industry-standard terms
2.3. Redundant specifications
2.4. Needless cross-references

The use of this new style does not change the meaning of a specification not yet using this style.

Sections 1 through 9 include general specifications applicable to every contract unless specified as applicable under certain conditions.

The specifications are written to the Bidder before award and the Contractor after. Before award, interpret sentences written in the imperative mood as starting with "The Bidder must" and interpret "you" as "the Bidder" and "your" as "the Bidder's." After award, interpret sentences written in the imperative mood as starting with "The Contractor must" and interpret "you" as "the Contractor" and "your" as "the Contractor's."

Omission of "a," "an," and "the" is intentional. These articles have been omitted in some specifications for streamlining purposes.

Unless an object or activity is specified to be less than the total, the quantity or amount is all of the object or activity.

A plural term includes the singular.

All items in a list apply unless the items are specified as choices.

Headings are included for the purposes of organization and referencing. Inclusion of a heading with no related content, "Reserved," or "Not Used" does not indicate that no specification exists for that subject; applicable specifications may be covered in a general or referenced specification.

## 1-2 REFERENCES

### 1-2.01 REFERENCES

Where Standard Specifications refer to the special provisions to describe the work, interpret the reference as a reference to the Bid Item List, the special provisions, or both.

Interpret a reference to a section of the Standard Specifications as a reference to the Standard Specifications as revised by any amendment, special provision, or both.

A reference within parentheses to a law or regulation is included in the contract for convenience only and is not a comprehensive listing of related laws and regulations. Lack of a reference does not indicate no related laws or regulations exist.

Where the version of a referenced document is not specified, use the current version in effect on the date of Notice to Bidders.

A reference to a subsection includes the section's general specifications of which the subsection is a part.

A code not specified as a Federal code is a California code.

## 1-3 ABBREVIATIONS AND MEASUREMENT UNITS

### 1-3.01 ABBREVIATIONS

**Abbreviations**

| Abbreviation | Meaning |
|---|---|
| AAN | American Association of Nurserymen |
| AASHTO | American Association of State Highway and Transportation Officials |
| AISC | American Institute of Steel Construction |
| AISI | American Iron and Steel Institute |
| AMA | archaeological monitoring area |
| ANSI | American National Standards Institute |
| APHA | American Public Health Association |
| API | American Petroleum Institute |
| AREMA | American Railway Engineering and Maintenance-of-Way Association |
| ASME | American Society of Mechanical Engineers |

| | |
|---|---|
| ASTM | American Society for Testing and Materials |
| AWG | American Wire Gage |
| AWPA | American Wood-Preservers' Association |
| AWS | American Welding Society |
| AWWA | American Water Works Association |
| CIH | Certified Industrial Hygienist |
| DBE | Disadvantaged Business Enterprise |
| DVBE | Disabled Veteran Business Enterprise |
| EIA | Electronic Industries Alliance |
| ESA | environmentally sensitive area |
| ETL | Electrical Testing Laboratories |
| FHWA | Federal Highway Administration |
| IEEE | Institute of Electrical and Electronics Engineers |
| NETA | National Electrical Testing Association, Inc. |
| NEMA | National Electrical Manufacturers Association |
| PLAC | permit, license, agreement, certification, or any combination of these |
| SSPC | The Society for Protective Coatings |
| UL | Underwriters' Laboratories Inc. |

## 1-3.02 MEASUREMENT UNITS

**Measurement Units**

| Symbols as used in the specifications | Symbols as used in the Bid Item List | Meaning |
|---|---|---|
| A | — | amperes |
| | ACRE | acre |
| | CF | cubic foot |
| | CY | cubic yard |
| -- | EA | each |
| g | -- | gram |
| ksi | -- | kips per square inch |
| | GAL | gallon |
| h | H | hour |
| | LB | pound |
| -- | LS | lump sum |
| | LF | linear foot |
| | LNMI | lane mile |
| | MFBM | thousand foot board measure |
| | MI | mile |
| | MSYD | thousand station yard |
| Ω | -- | ohm |
| pcf | -- | pounds per cubic foot |
| s | -- | second |
| | STA | 100 feet |
| | SQFT | square foot |
| | SQYD | square yard |
| | TAB | tablet |
| ton | TON | 2,000 pounds |
| V | -- | volt |
| W | -- | watt |
| -- | WDAY | working day |

## 1-4 DEFINITIONS

### 1-4.01 GENERAL

Interpret terms as defined in the contract documents. A construction-industry term not defined in the contract documents has the meaning defined in Means Illustrated Construction Dictionary, Condensed Version, Second Edition.

### 1-4.02 GLOSSARY

**aerially deposited lead:** Lead primarily from vehicle emissions deposited within unpaved areas or formerly unpaved areas.

**archaeological monitoring area:** Area within, near, or straddling the project limits where access is allowed, but work is subject to archaeological monitoring.

**archaeological resources:** Remains of past human activity, including historic and prehistoric material (e.g., tools and tool fragments, hearth and food remains, structural remains, and human remains).

**acceptance:** Formal written acceptance by the Director of an entire contract that has been completed in all respects in accordance with the plans and specifications and any modifications to them previously approved.

**base:** Layer of specified material of planned thickness placed immediately below the pavement or surfacing.

**basement material:** Material in excavation or embankments underlying the lowest layer of subbase, base, pavement, surfacing, or other specified layer to be placed.

**bid item:** Specific work unit for which the bidder provides a price.

**Bid Item List:** List of bid items and the associated quantities.

**Bid Item List, verified:** Bid Item List with verified prices. The Contract Proposal of Low Bidder at the Department's Web site is the verified Bid Item List.

**bridge:** Structure, with a bridge number, that carries a utility facility, or railroad, highway, pedestrian or other traffic, over a water course or over or under or around any obstruction.

**building-construction contract:** Contract that has "building construction" on the cover of the Notice to Bidders and Special Provisions.

**business day:** Day on the calendar except Saturday or holiday.

**California Manual on Uniform Traffic Control Devices:** The California Manual on Uniform Traffic Control Devices for Streets and Highways (California MUTCD) is issued by the Department of Transportation and is the Federal Highway Administration's MUTCD 2003 Edition, as amended for use in California.

**Certified Industrial Hygienist:** Industrial hygienist certified in comprehensive practice by the American Board of Industrial Hygiene.

**conduit:** Pipe or tube in which smaller pipes, tubes, or electrical conductors are inserted or are to be inserted.

**contract:** Written and executed contract between the Department and the Contractor.

**contract bonds:** Security for the payment of workers and suppliers furnishing materials, labor, and services and for guaranteeing the Contractor's work performance.

**contract item:** Bid item.

**Contractor:** Person or business or its legal representative entering into a contract with the Department for performance of the work.

**culvert:** Structure, other than a bridge, that provides an opening under a roadway for drainage or other purposes.

**day:** 24 consecutive hours running from midnight to midnight; calendar day.

**deduction:** Amount of money permanently taken from progress payment and final payment. Deductions are not retentions under Pub Cont Code § 7107.

**Department:** Department of Transportation as defined in St & Hwy Code § 20 and authorized in St & Hwy Code § 90; its authorized representatives.

**detour:** Temporary route for traffic around a closed road part. A passageway through a job site is not a detour.

**Director:** Department's Director.

**Disabled Veteran Business Enterprise:** Business certified as a DVBE by the Office of Small Business and DVBE Services, Department of General Services.

**divided highway:** Highway with separated traveled ways for traffic, generally in opposite directions.

**Engineer:** Department's Chief Engineer acting either directly or through properly authorized agents; the agents acting within the scope of the particular duties delegated to them.

**environmentally sensitive area:** Area within, near, or straddling the project limits where access is prohibited or limited to protect environmental resources.

**Federal-aid contract:** Contract that has a Federal-aid project number on the cover of the Notice to Bidders and Special Provisions.

**fixed costs:** Labor, material, or equipment cost directly incurred by the Contractor as a result of performing or supplying a particular bid item that remains constant regardless of the item's quantity.

**frontage road:** Local street or road auxiliary to and located generally on the side of an arterial highway for service to abutting property and adjacent areas and for control of access.

**grading plane:** Basement material surface on which the lowest layer of subbase, base, pavement, surfacing, or other specified layer is placed.

**highway:** Whole right of way or area that is reserved for and secured for use in constructing the roadway and its appurtenances.

**holiday:**

1. Every Sunday
2. January 1st, New Year's Day
3. 3rd Monday in January, Birthday of Martin Luther King, Jr.
4. February 12th, Lincoln's Birthday
5. 3rd Monday in February, Washington's Birthday
6. March 31st, Cesar Chavez Day
7. Last Monday in May, Memorial Day
8. July 4th, Independence Day
9. 1st Monday in September, Labor Day
10. 2nd Monday in October, Columbus Day
11. November 11th, Veterans Day
12. 4th Thursday in November, Thanksgiving Day
13. Day after Thanksgiving Day
14. December 25th, Christmas Day

If January 1st, February 12th, March 31st, July 4th, November 11th, or December 25th falls on a Sunday, the Monday following is a holiday. If November 11th falls on a Saturday, the preceding Friday is a holiday. Interpret "legal holiday" as "holiday."

**informal-bid contract:** Contract that has "Informal Bid Authorized by Pub Cont Code §10122" on the cover of the Notice to Bidders and Special Provisions.

**Information Handout:** Supplemental project information furnished to bidders as a handout.

**laboratory:** Laboratory authorized by the Department to test materials.

**liquidated damages:** Amount prescribed in the specifications, pursuant to the authority of Pub Cont Code § 10226, to be paid to the State or to be deducted for each day's delay in completing the whole or any specified portion of the work beyond the time allowed in the specifications.

**material shortage:** Shortage of raw or produced material that is area-wide and caused by an unusual market condition, except if any of the following occurs:

1. Shortage relates to a produced, nonstandard material
2. Supplier's and the Contractor's priority for filling an order differs
3. Event outside the U.S. for a material produced outside the U.S.

**median:** Portion of a divided highway separating the traveled ways for traffic in opposite directions including inside shoulders.

**Notice to Bidders:** Document that provides a general work description, bidder and bid specifications, and the time and location the Department receives bids.

**paleontological resources:** Fossils and the deposits they are found in. Fossils are evidence of ancient life preserved in sediments and rock. Examples of paleontological resources are remains of (1) animals, (2) animal tracks, (3) plants, and (4) other organisms. Archaeological resources are not paleontological and fossils found within an archaeological resource are generally considered archaeological resources, not paleontological resources.

**pavement:** Uppermost layer of material placed on the traveled way or shoulders. This term is used interchangeably with surfacing.

**plans:** Official project plans and Standard Plans, profiles, typical cross sections, working drawings and supplemental drawings, or reproductions thereof, approved by the Engineer, which show the location, character, dimensions and details of the work to be performed. These documents are to be considered as a part of the plans.

In the above definition, the following terms are defined as follows:

**Standard Plans:** Standard Plans issued by the Department.

**project plans:** Specific details and dimensions peculiar to the work supplemented by the Standard Plans insofar as the same may apply.

**roadbed:** Area between the intersection of the upper surface of the roadway and the side slopes or curb lines. The roadbed rises in elevation as each increment or layer of subbase, base, surfacing or pavement is placed. Where the

medians are so wide as to include areas of undisturbed land, a divided highway is considered as including 2 separate roadbeds.

**roadway:** Highway portion included between the outside lines of sidewalks, or curbs, slopes, ditches, channels, waterways, and including all the appertaining structures, and other features necessary to proper drainage and protection.

**shoulder:** Roadway portion contiguous with the traveled way for accommodation of stopped vehicles, for emergency use, and for lateral support of base and surface courses.

**special provisions:** Specific clauses setting forth conditions or requirements peculiar to the work and supplementary to these Standard Specifications. The Department's publication titled "Labor Surcharge And Equipment Rental Rates" is part of the special provisions.

**specifications:** Directions, provisions, and requirements contained in these Standard Specifications, Amendments to the Standard Specifications, and the special provisions. Where the term "these specifications" or "these Standard Specifications" is used in this book, it means the provisions set forth in this book.

**State:** State of California, including its agencies, departments, or divisions, whose conduct or action is related to the work.

**Structure Design:** Offices of Structure Design of the Department.

**subbase:** Layer of specified material of planned thickness between a base and the basement material.

**subgrade:** Roadbed portion on which pavement, surfacing, base, subbase, or a layer of any other material is placed.

**substructure:** Bridge portions below the bridge seats, tops of piers, haunches of rigid frames, or below the spring lines of arches. Backwalls and parapets of abutments and wingwalls of bridges are portions of the substructure.

**superstructure:** Bridge portion except the bridge substructure.

**supplemental project information:** Information relevant to the project, specified as supplemental project information, and made available to bidders.

**surfacing:** Uppermost layer of material placed on the traveled way, or shoulders. This term is used interchangeably with pavement.

**traffic lane:** Portion of a traveled way for the movement of a single line of vehicles.

**traveled way:** Portion of the roadway for the movement of vehicles, exclusive of shoulders.

**total bid:** Sum of the item totals as verified by the Department; original contract price.

**withhold:** Money temporarily or permanently taken from progress payment. Withholds are not retentions under Pub Cont Code § 7107.

**work:** All the work specified, indicated, shown or contemplated in the contract to construct the improvement, including all alterations, amendments, or extensions to it made by contract change order or other written orders of the Engineer.

**working day:** Time measure unit for work progress. A working day is any day except:

1. Saturdays and holidays
2. A day when you cannot perform work on the controlling activity for at least 50 percent of the day with at least 50 percent of the normal labor and equipment due to any of the following:

    2.1. Adverse weather-related conditions that cause you to dismiss the crew
    2.2. Maintaining traffic under the contract
    2.3. The Engineer's direction to suspend the controlling activities for reasons unrelated to your performance
    2.4. An unanticipated event not caused by either party such as:

        2.4.1. Act of God (Pub Cont Code § 7105)
        2.4.2. Act of a public enemy
        2.4.3. Epidemic
        2.4.4. Fire
        2.4.5. Flood
        2.4.6. Governor-declared state of emergency
        2.4.7. Landslide
        2.4.8. Quarantine restriction

    2.5. An issue involving a third-party, including:

        2.5.1. Industry or area-wide labor strike
        2.5.2. Material shortage
        2.5.3. Freight embargo

2.5.4. Jurisdictional requirement of a law enforcement agency

2.5.5. Workforce labor dispute of a utility or non-highway facility owner resulting in a utility or non-highway facility reconstruction not described and not solely for the Contractor's convenience

## 1-5 DISTRICTS

**District Composition and Office Addresses**

| District | Counties | Location Address | Mailing Address |
|---|---|---|---|
| 1 | Del Norte (DN), Humboldt (Hum), Lake (Lak), Mendocino (Men) | 1656 UNION ST<br>EUREKA, CA | PO BOX 3700<br>EUREKA CA 95502 |
| 2 | Lassen (Las), Modoc (Mod), Plumas (Plu), Shasta (Sha), Siskiyou (Sis), Tehama (Teh), Trinity (Tri) | 1657 RIVERSIDE DR<br>REDDING, CA | PO BOX 496073<br>REDDING CA 96049-6073 |
| 3 | Butte (But), Colusa (Col), El Dorado (ED), Glenn (Gle), Nevada (Nev), Placer (Pla), Sacramento (Sac), Sierra (Sie), Sutter (Sut), Yolo (Yol), Yuba (Yub) | 703 B ST<br>MARYSVILLE, CA | PO BOX 911<br>MARYSVILLE CA 95901 |
| 4 | Alameda (Ala), Contra Costa (CC), Marin (Mrn), Napa (Nap), San Francisco (SF), San Mateo (SM), Santa Clara (SCl), Solano (Sol), Sonoma (Son) | 111 GRAND AVE<br>OAKLAND, CA | PO BOX 23660<br>OAKLAND CA 94623-0660 |
| 5 | Monterey (Mon), San Benito (SBt), San Luis Obispo (SLO), Santa Barbara (SB), Santa Cruz (SCr) | 50 HIGUERA ST<br>SAN LUIS OBISPO, CA | 50 HIGUERA ST<br>SAN LUIS OBISPO CA 93401-5415 |
| 6 | Fresno (Fre), Kern (Ker), Kings (Kin), Madera (Mad), Tulare (Tul) | 1352 W. OLIVE AVE<br>FRESNO, CA | PO BOX 12616<br>FRESNO CA 93728-2616 |
| 7 | Los Angeles (LA), Ventura (Ven) | 100 S. MAIN ST<br>LOS ANGELES | 100 S MAIN ST<br>LOS ANGELES CA 90012 |
| 8 | Riverside (Riv), San Bernardino (SBd) | 464 W 4TH ST<br>SAN BERNARDINO, CA | 464 W 4TH ST<br>SAN BERNARDINO CA 92401-1400 |
| 9 | Inyo (Iny), Mono (Mno) | 500 S MAIN ST<br>BISHOP, CA | 500 S MAIN ST<br>BISHOP CA 93514-3423 |
| 10 | Alpine (Alp), Amador (Ama), Calaveras (Cal), Mariposa (Mpa), Merced (Mer), San Joaquin (SJ), Stanislaus (Sta), Tuolumne (Tuo) | 1976 E CHARTER WAY<br>STOCKTON, CA | PO BOX 2048<br>STOCKTON CA 95201 |
| 11 | Imperial (Imp), San Diego (SD) | 4050 TAYLOR ST<br>SAN DIEGO, CA | 4050 TAYLOR ST<br>SAN DIEGO CA 92110-2737 |
| 12 | Orange (Ora) | 3347 MICHELSON DR<br>STE 100<br>IRVINE, CA | 3347 MICHELSON DR STE 100<br>IRVINE CA 92612-0661 |

A project with work in District 1, 2, or 3 is a North Region project. For Districts 1, 2, and 3, interpret each reference to the district office as the North Region office. The North Region office address is the District 3 address.

## 1-6 WEB SITES, ADDRESSES, AND TELEPHONE NUMBERS

**Web Sites, Addresses, and Telephone Numbers**

| Agency, Department Unit, or Reference | Web Site | Address | Telephone No. |
|---|---|---|---|
| Bid Document Unit | | MSC 26<br>BID DOCUMENT UNIT<br>DEPARTMENT OF TRANSPORTATION<br>1120 N ST RM 200<br>SACRAMENTO CA 95814-5605 | |
| Department | www.dot.ca.gov | | |
| Department of General Services, Office of Small Business and DVBE Services | www.pd.dgs.ca.gov/smbus/default.htm | OFFICE OF SMALL BUSINESS AND DVBE SERVICES<br>DEPARTMENT OF GENERAL SERVICES<br>707 3RD ST<br>WEST SACRAMENTO CA 95605-2811 | (800) 559-5529<br>(916) 375-4940 |
| Department of Industrial Relations | www.dir.ca.gov | | |
| Department of Industrial Relations, Division of Apprenticeship Standards | | 455 GOLDEN GATE AVENUE<br>SAN FRANCISCO, CA 94102 | |
| Office Engineer | | MSC 43<br>OFFICE ENGINEER<br>DEPARTMENT OF TRANSPORTATION<br>1727 30TH ST<br>SACRAMENTO CA 95816-7005 | |
| Office Engineer–Verified Bid Results | http://www.dot.ca.gov/hq/esc/oe/awards/bidsum_html/6week_list.html. | | |
| Offices of Structure Design, Documents Unit | | MSC 9-4/4I<br>DOCUMENTS UNIT OFFICES OF STRUCTURE DESIGN<br>DEPARTMENT OF TRANSPORTATION<br>1801 30TH ST<br>SACRAMENTO CA 95816-7006 | (916) 227-0716 |
| Publication Distribution Unit | | PUBLICATION UNIT<br>DEPARTMENT OF TRANSPORTATION<br>1900 ROYAL OAKS DRIVE<br>SACRAMENTO CA 95815-3800 | |
| Transportation Laboratory | | MATERIALS AND ENGINEERING TESTING SERVICES AND GEOTECHNICAL SERVICES<br>DEPARTMENT OF TRANSPORTATION<br>5900 FOLSOM BLVD<br>SACRAMENTO CA 95819-4612 | (916) 227-7000 |
| Department's Pre-Qualified Products List | http://www.dot.ca.gov/hq/esc/approved_products_list | | |

^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^

## SECTION 2 PROPOSAL REQUIREMENTS AND CONDITIONS
**(Issued 03-13-09)**

**Replace Section 2 with:**

## SECTION 2 BIDDING

### 2-1.01 GENERAL

Section 2, "Bidding," includes specifications related to bid eligibility and the bidding process.

### 2-1.02 BID INELIGIBILITY

A firm that has provided architectural or engineering services to the Department for this contract before bid submittal for this contract is prohibited from any of the following:

1. Submit a bid
2. Subcontract for a part of the work
3. Supply materials

### 2-1.03 BID DOCUMENTS

#### 2-1.03A General

Standard Specifications and Standard Plans may be viewed at the Department's Web site and may be purchased at the Publication Distribution Unit.

Special provisions, Amendments to the Standard Specifications, and project plans may be viewed at:

1. Department's Web site
2. District office of the district in which the work is located
3. Districts 4 and 12 offices
4. Bid Document Unit

For an informal-bid contract, special provisions, Amendments to the Standard Specifications, and project plans may be viewed at:

1. Department's Web site
2. Bid Document Unit

Bid books, special provisions, Amendments to the Standard Specifications, and project plans may be obtained at the Bid Document Unit. To expedite orders, you may obtain these documents by faxing an order to (916) 654-7028. Fax orders must include credit card charge number, card expiration date, and authorizing signature.

#### 2-1.03B Supplemental Project Information

Logs of test borings attached to the project plans are supplemental project information. The Department makes other supplemental information available as specified in the special provisions.

The Information Handout may be viewed and obtained at the Bid Document Unit.

If rock cores are available, you may view them by sending a request to Coreroom@dot.ca.gov.

Make your request at least 7 days before viewing. Include in your request:

1. District-County-Route
2. Bridge number
3. Contract number
4. Viewing date
5. Contact information, including telephone number.

If bridge as-built drawings are available:

1. For a project in District 1 through 6 or 10, you may request them from the Office of Structure Maintenance and Investigations, fax (916) 227-8357
2. For a project in District 7, 8, 9, 11, or 12, you may request them from the Office of Structure Maintenance and Investigations, fax (916) 227-8357, and are available at the Office of Structure Maintenance and Investigations, Los Angeles, CA, telephone (213) 897-0877

As-built drawings may not show existing dimensions and conditions. Where new construction dimensions are dependent on existing bridge dimensions, verify the field dimensions and adjust dimensions of the work to fit existing conditions.

## 2-1.04 SMALL BUSINESS ENTERPRISE GOAL

The Department has established an overall 25 percent small business participation goal. To determine if the goal is achieved, the Department is tracking small business participation on all contracts.

Contractors, subcontractors, suppliers, and service providers who qualify as small business are encouraged to apply for certification as a small business by submitting their application to the Department of General Services, Office of Small Business and DVBE Services.

## 2-1.05 DISADVANTAGED BUSINESS ENTERPRISES

Section 2-1.05, "Disadvantaged Business Enterprises," applies to a Federal-aid contract.

Under 49 CFR 26.13(b):

> The contractor, sub recipient or subcontractor shall not discriminate on the basis of race, color, national origin, or sex in the performance of this contract. The contractor shall carry out applicable requirements of 49 CFR part 26 in the award and administration of DOT-assisted contracts. Failure by the contractor to carry out these requirements is a material breach of this contract, which may result in the termination of this contract or such other remedy as the recipient deems appropriate.

In order to ensure the Department achieves its federally mandated statewide overall DBE goal, the Department encourages the participation of DBEs as defined in 49 CFR 26.

## 2-1.06 DISABLED VETERAN BUSINESS ENTERPRISES

### 2-1.06A General

Section 2-1.06, "Disabled Veteran Business Enterprises," applies to a non-Federal-aid contract.

Take necessary and reasonable steps to ensure that DVBEs have opportunity to participate in the contract.

Comply with Mil & Vet Code § 999 et seq.

### 2-1.06B No Goal

Section 2-1.06B, "No Goal," applies if no DVBE goal is shown in the Notice to Bidders.

The Department encourages bidders to obtain DVBE participation in order to ensure the Department achieves its State-mandated overall DVBE goal.

### 2-1.06C Goal

Section 2-1.06C, "Goal," applies if a DVBE goal is shown in the Notice to Bidders.

Make work available to DVBEs and select work parts consistent with available DVBE subcontractors and suppliers.

Meet the goal shown or demonstrate that you made good faith efforts to meet this goal.

## 2-1.07 SMALL BUSINESS AND NON–SMALL BUSINESS SUBCONTRACTOR PREFERENCES

### 2-1.07A General

Section 2-1.07, "Small Business and Non–Small Business Subcontractor Preferences (Govt Code § 14835 et seq. and 2 CA Code of Regs § 1896 et seq.)," applies to a non-Federal-aid contract.

### 2-1.07B Small Business Preference

The Department allows a bidder certified as a small business by the Office of Small Business and DVBE Services, Department of General Services, a preference if:

1. You completed a Request for Small Business Preference or Non–Small Business Preference form
2. You attached a copy of your Office of Small Business and DVBE Services small business certification to the form
3. The low bidder is not certified as a small business

The bidder's signature on the Request for Small Business Preference or Non–Small Business Preference form certifies that the bidder is certified as a small business at the time and day of bid or has submitted a complete application to the Department of General Services. The complete application and any required substantiating documentation must be received by the Department of General Services by 5:00 p.m. on bid opening date.

The Department of General Services determines if a bidder was certified on bid opening date. The Department confirms the bidder's status as a small business before applying the small business preference.

The small business preference is a reduction for bid comparison in the total bid submitted by the small business subcontractor by the lesser of:

1. 5 percent of the verified total bid of the low bidder
2. $50,000

If this reduction results in the small business contractor becoming the low bidder, the contract award is based on the total bid, not the reduced bid.

**2-1.07C Non–Small Business Subcontractor Preference**

The Department allows a bidder not certified as a small business by the Office of Small Business and DVBE Services, Department of General Services, a preference if:

1. You completed a Request for Small Business Preference or Non–Small Business Preference form
2. The low bidder is not certified as a small business and has not requested preference
3. The Certified Small Business Listing for the Non–Small Business Preference form shows that you are subcontracting at least 25 percent to certified small businesses.

The non–small business subcontractor preference is a reduction for bid comparison in the total bid submitted by the non–small business contractor requesting the preference by the lesser of:

1. 5 percent of the verified total bid of the low bidder
2. $50,000

If this reduction results in the non–small business contractor becoming the low bidder or a tie with a non-small business low bidder not requesting the preference, the contract award is based on the total bid, not the reduced bid.

A non-small business bidder cannot displace a small business bidder.

**2-1.08 DVBE INCENTIVE EVALUATION**

Section 2-1.08, "DVBE Incentive Evaluation," applies to a non-Federal-aid contract.

The Department applies the Small Business and Non–Small Business preference during bid verification and proceeds with the following evaluation for DVBE incentive.

The Department grants a DVBE incentive to bidders who achieve a DVBE participation of 1 percent or greater of the value of their bid (Mil & Vet Code and Code of Regs § 1896.98 et seq).

The DVBE incentive is a reduction, for bid comparison only, in the total bid submitted by the lesser of:

1. Percentage of DVBE achievement, rounded to 2 decimal places, of the verified total bid of the low bidder
2. 5 percent of the verified total bid of the low bidder
3. $100,000

The Department applies DVBE incentive and determines if bid ranking changes.

A non-small business bidder cannot displace a small business bidder. However, a small business bidder with higher DVBE achievement can displace another small business bidder.

The Department proceeds with awarding the contract to the new low bidder and posts the new verified bid results at its Office Engineer Web site.

## 2-1.09 PREFERENCE HIERARCHY

Section 2-1.09, "Preference Hierarchy," applies to a non-Federal-aid contract.

If a small business bidder and a non–small business bidder request preferences and the reductions result in a tied bid, the Department awards the contract to the small business bidder.

If a DVBE bidder and a non-DVBE bidder request preferences and the reduction results in a tied bid, the Department awards the contract to the DVBE bidder.

## 2-1.10 CALIFORNIA COMPANIES

Section 2-1.10, "California Companies," applies to a non-Federal-aid contract.

Under Pub Cont Code § 6107, the Department gives preference to a "California company," as defined, for bid comparison purposes over a nonresident contractor from any state that gives or requires a preference to be given contractors from that state on its public entity construction contracts.

Complete a California Company Preference form.

The California company reciprocal preference amount is equal to the preference amount applied by the state of the nonresident contractor with the lowest responsive bid unless the California company is eligible for a small business preference or a non–small business subcontractor preference; in which case the preference amount is the greater of the two, but not both.

If the low bidder is not a California company and a California company's bid with reciprocal preference is equal to or less than the lowest bid, the Department awards the contract to the California company on the basis of its total bid, not the reduced bid used for comparison except as specified in Section 2-1.09, "Preference Hierarchy."

## 2-1.11 JOB SITE AND DOCUMENT EXAMINATION

Examine the job site and bid documents.

Bid submission is your acknowledgment that you have examined the job site and bid documents and are satisfied with:

1. General and local conditions to be encountered
2. Character, quality, and scope of work to be performed
3. Quantities of materials to be furnished
4. Character, quality, and quantity of surface and subsurface materials or obstacles
5. Requirements of the contract

## 2-1.12 BID DOCUMENT COMPLETION

### 2-1.12A General

Complete forms in the Bid book. Submit the forms with your bid except:

1. For the following 2 forms for non-federal-aid non-informal-bid contracts:

   1.1. Certified DVBE Summary and DVBE - Good Faith Efforts forms. You may submit these forms with your bid. If you do not and you are the low bidder or the 2nd or 3rd low bidder, submit them so that they are received at the Office Engineer no later than 4:00 p.m. on the 4th business day after bid opening. If a DVBE joint venture is used, submit the joint venture agreement with the Certified DVBE Summary form. Other bidders may be required to submit these forms if bid ranking changes.

   1.2. Certified Small Business Listing for the Non–Small Business Preference form. If you are applying for the non–small business subcontractor preference, you may submit this information with your bid. If you do not, submit it so that it is received at the Office Engineer no later than 4:00 p.m. on the 2nd business day after bid opening. The listed subcontractors and suppliers must be certified as a small business at the time and day of bid or must have submitted a complete application to the Department of General Services. The complete application and any required substantiating documentation must be received by the Department of General Services by 5:00 p.m. on bid opening date.

2. On the Subcontractor List you may either submit the percentage of each bid item subcontracted with your bid or fax the percentage to (916) 227-6282 within 24 hours after bid opening.

Except for the percentage of each bid item subcontracted, do not fax submittals.

The Department determines a bidder has made good faith efforts if it submits evidence that it:

1. Contacted the Office of Small Business and DVBE Services, Department of General Services

2. Advertised in trade media and media focusing on DVBEs unless time limits the Department imposes do not allow the advertising
3. Submitted invitations to bid to potential DVBE contractors
4. Considered available DVBEs

### 2-1.12B Bid Item List and Bid Comparison

Submit a bid based on the work item quantities the Department shows in the Bid Item List.

For a lump sum based bid, the Department compares bids based on the total price.

For a unit price based bid, the Department compares bids based on the sum of the item totals.

For a cost plus time based bid, the Department compares bids based on the sum of the item totals and the total bid for time.

### 2-1.12C Subcontractor List

In the Subcontractor List, list each subcontractor to perform work:

1. In an amount in excess of 1/2 of 1 percent of the total bid or $10,000, whichever is greater (Pub Cont Code § 4100 et seq.)
2. That is a 1st tier DVBE subcontractor regardless of percentage of the total bid

The Subcontractor List must show the name, address, and work portions to be performed by each subcontractor listed. Show work portion by bid item number, description, and percentage of each bid item subcontracted.

## 2-1.13 BIDDER'S SECURITY

Submit your bid with one of the following forms of bidder's security equal to at least 10 percent of the bid:

1. Cash
2. Cashier's check
3. Certified check
4. Bidder's bond signed by a surety insurer who is licensed in California

Make checks and bonds payable to the Department of Transportation.

If using a bidder's bond, you may use the form in the Bid book. If you do not use the form in the Bid book, use a form containing the same information.

## 2-1.14 BID SUBMITTAL

Submit your bid:

1. Under sealed cover
2. Marked as a bid
3. Identifying the contract number and the bid opening date

If an agent other than the authorized corporation officer or a partnership member signs the bid, file a Power of Attorney with the Department either before opening bids or with the bid. Otherwise, the bid may be nonresponsive.

## 2-1.15 BID WITHDRAWAL

An authorized agent may withdraw a bid before the bid opening date and time by submitting a written bid withdrawal request at the location where the bid was submitted. Withdrawing a bid does not prevent you from submitting a new bid.

After the bid opening time, you cannot withdraw a bid.

## 2-1.16 BID OPENING

The Department publicly opens and reads bids at the time and place described in the Notice to Bidders.

## 2-1.17 BID REJECTION

The Department may reject:

1. All bids

2. A nonresponsive bid

### 2-1.18 BID RELIEF

The Department may grant bid relief under Pub Cont Code § 5100 et seq. Submit any request for bid relief to the Office Engineer. For Relief of Bid Request form, go to:

http://www.dot.ca.gov/hq/esc/oe/contractor_info/relief.pdf

### 2-1.19 SUBMITTAL FAILURE HISTORY

The Department considers a bidder's past failure to submit documents required after bid opening in determining a bidder's responsibility.

### 2-1.20 BID RIGGING

Section 2-1.20, "Bid Rigging," applies to a Federal-aid contract.

The U.S. Department of Transportation (DOT) provides a toll-free hotline to report bid rigging activities. Use the hotline to report bid rigging, bidder collusion, and other fraudulent activities. The hotline number is (800) 424-9071. The service is available Monday through Friday between 11:00 a.m. and 8:00 p.m. and is confidential and anonymous. The hotline is part of the DOT's effort to identify and investigate highway construction contract fraud and abuse and is operated under the direction of the DOT Inspector General.

^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^

## SECTION 3 AWARD AND EXECUTION OF CONTRACT
**(Issued 11-07-08)**

**Replace Section 3 with:**

## SECTION 3 CONTRACT AWARD AND EXECUTION

### 3-1.01 SCOPE

Section 3, "Contract Award and Execution," includes specifications related to contract award and execution.

### 3-1.02 CONTRACT AWARD

Submit any bid protest to the Office Engineer.

If the Department awards the contract, the award is made to the lowest responsible bidder within the number of days shown in the following table:

**Contract Award Period**

| Days (after bid opening) | Project Estimated Cost shown in the Notice to Bidders |
|---|---|
| 30 | < $200 million |
| 60 | ≥ $200 million |

The Department may extend the specified award period if the bidder agrees.

### 3-1.03 CONTRACT BONDS (PUB CONT CODE §§ 10221 AND 10222)

The successful bidder must furnish 2 bonds:

1. Payment bond to secure the claim payments of laborers, workers, mechanics, or materialmen providing goods, labor, or services under the contract. This bond must be equal to at least 100 percent of the total bid.
2. Performance bond to guarantee the faithful performance of the contract. This bond must be equal to at least 50 percent of the total bid.

The Department furnishes the successful bidder with bond forms.

### 3-1.04 CONTRACTOR LICENSE

For a Federal-aid contract, the Contractor must be properly licensed as a contractor (Pub Cont Code § 10164) from contract award through contract acceptance.

For a non-Federal-aid contract:

1. The Contractor must be properly licensed as a contractor from bid opening through contract acceptance (Bus & Prof Code § 7028.15)
2. Joint venture bidders must obtain a joint venture license before contract award (Bus & Prof Code § 7029.1)

### 3-1.05 INSURANCE POLICIES

The successful bidder must submit:

1. Copy of its commercial general liability policy and its excess policy or binder until such time as a policy is available, including the declarations page, applicable endorsements, riders, and other modifications in effect at the time of contract execution. Standard ISO form No. CG 0001 or similar exclusions are allowed if not inconsistent with Section 7-1.12, "Indemnification and Insurance." Allowance of additional exclusions is at the discretion of the Department.
2. Certificate of insurance showing all other required coverages. Certificates of insurance, as evidence of required insurance for the auto liability and any other required policy, shall set forth deductible amounts applicable to each policy and all exclusions that are added by endorsement to each policy. The evidence of insurance shall provide that no cancellation, lapse, or reduction of coverage will occur without 10 days prior written notice to the Department.
3. A declaration under the penalty of perjury by a CPA certifying the accountant has applied GAAP guidelines confirming the successful bidder has sufficient funds and resources to cover any self-insured retentions if the self-insured retention is $50,000 or higher.

If the successful bidder uses any form of self-insurance for workers compensation in lieu of an insurance policy, it shall submit a certificate of consent to self-insure under Labor Code § 3700.

### 3-1.06 SMALL BUSINESS PARTICIPATION REPORT

Complete and sign the Small Business (SB) Participation Report form included in the contract documents even if no small business participation is reported.

### 3-1.07 PAYEE DATA RECORD

Complete and sign the Payee Data Record form included in the contract documents.

### 3-1.08 CALTRANS BIDDER - DBE INFORMATION FORM

Section 3-1.08, "Caltrans Bidder - DBE Information Form," applies to a Federal-aid contract.

Complete and sign the Caltrans Bidder - DBE Information form included in the contract documents even if no DBE participation is reported.

Provide written confirmation from each DBE that the DBE is participating in the contract. A copy of a DBE's quote serves as written confirmation. If a DBE is participating as a joint venture partner, the Department encourages you to submit a copy of the joint venture agreement.

### 3-1.09 CONTRACT EXECUTION

The successful bidder must sign the contract.

Deliver to the Office Engineer:

1. Signed Contract form
2. Contract bonds
3. Documents identified in Section 3-1.05, "Insurance Policies"
4. Small Business Participation Report
5. Payee data record
6. For a Federal-aid contract, Caltrans Bidder - DBE Information form

For an informal-bid contract, the Office Engineer must receive these documents before the 5th business day after the bidder receives the contract. For all other contracts, the Office Engineer must receive these documents before the 10th business day after the bidder receives the contract.

The bidder's security may be forfeited for failure to execute the contract within the time specified (Pub Cont Code §§ 10181, 10182, and 10183).

The following is a copy of the Contract form:

STATE OF CALIFORNIA • DEPARTMENT OF TRANSPORTATION

**CONTRACT**

DES-OE-0103A (NEW 3/2008)

# STATE OF CALIFORNIA
# DEPARTMENT OF TRANSPORTATION
# CONTRACT NO. _____

This contract is entered into between the State of California's Department of Transportation and the Contractor named below:

_____

CONTRACTOR'S NAME

The parties agree to comply with the terms of the following exhibits that are by this reference made a part of this contract.

Exhibit A - Bid book dated _____

Exhibit B - Notice to Bidders and Special Provisions dated _____

Exhibit C - Project Plans approved _____

Exhibit D - Standard Specifications dated _____

Exhibit E - Standard Plans dated _____

Exhibit F - Addenda

Exhibits A, B, C, and F are those exhibits identified with the same contract number as this contract.

**This contract has been executed by the following parties:**

## CONTRACTOR

CONTRACTOR'S NAME *(if other than an individual, state whether a corporation, partnership, etc.)*

| BY *(Authorized Signature)* | DATE SIGNED *(Do not type)* |
|---|---|

PRINTED NAME AND TITLE OF PERSON SIGNING

FEDERAL EMPLOYER IDENTIFICATION NUMBER

## DEPARTMENT OF TRANSPORTATION

| BY *(Authorized Signature)* | DATE SIGNED *(Do not type)* |
|---|---|

PRINTED NAME AND TITLE OF PERSON SIGNING

**ADA Notice** For individuals with sensory disabilities, this document is available in alternate formats. For information call (916) 654-6410 or TDD (916) 654-3880 or write Records and Forms Management, 1120 N Street, MS-89, Sacramento, CA 95814.

**3-1.10 BIDDERS' SECURITIES**

The Department keeps the securities of the 1st, 2nd, and 3rd low bidders until the contract has been executed. The other bidders' securities, other than bidders' bonds, are returned upon determination of the 1st, 2nd, and 3rd low bidders, and their bidders' bonds are of no further effect (Pub Cont Code § 10184).

^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^

## SECTION 4 SCOPE OF WORK
**(Issued 05-01-09)**

**Add to Section 4-1.01:**

Nothing in the specifications voids the Contractor's public safety responsibilities.

**Add:**

**4-1.015 PROJECT DESCRIPTION**

Construct the work described in the special provisions and on project plans and by the bid items. The special provisions, project plans, and bid item descriptions set forth the specifications that apply.

**In Section 4-1.03A replace the 3rd paragraph with:**

Where the protest concerning an approved contract change order relates to the adjustment of contract time for the completion of the work, the time to be allowed is determined as specified in Section 8-1.09, "Delays."

**Add:**

**4-1.035 VALUE ENGINEERING**

**4-1.035A General**

Reserved

**4-1.035B Value Engineering Change Proposal**

You may submit a VECP to reduce any of the following:

1. Total cost of construction
2. Construction activity duration
3. Traffic congestion

Before preparing a VECP, meet with the Engineer to discuss:

1. Proposal concept
2. Permit issues
3. Impact on other projects
4. Project impacts, including traffic, schedule, and later stages
5. Peer reviews
6. Overall proposal merits
7. Review times required by the Department and other agencies

The VECP must not impair the project's essential functions or characteristics, such as:

1. Service life
2. Operation economy
3. Maintenance ease
4. Desired appearance

5. Design and safety

The VECP must include:

1. Description of the contract specifications and drawing details for performing the work and the proposed changes.
2. Itemization of contract specifications and drawing details that would be changed.
3. Detailed cost estimate for performing the work under the existing contract and under the proposed change. Determine the estimates under Section 9-1.03, "Force Account Payment."
4. Deadline for the Engineer to decide on the changes.
5. Bid items affected and resulting quantity changes.

The Department is not required to consider a VECP. If a VECP is similar to a change in the plans or specifications being considered by the Department at the time the proposal is submitted or if the proposal is based on or similar to drawings or specifications adopted by the Department before Contract award, the Department does not accept the VECP and may make these changes without VECP payments.

Until the Department approves a change order incorporating the VECP or parts of it, continue to perform the work under the contract. If the Department does not approve a change order before the deadline stated in the VECP or other date you subsequently stated in writing, the VECP is rejected. The Department does not adjust time or payment for a rejected VECP.

The Department decides whether to accept a VECP and the estimated net construction-cost savings from adopting the VECP or parts of it.

The Department may require you to accept a share of the investigation cost as a condition of reviewing a VECP. After written acceptance, the Department considers the VECP and deducts the agreed cost.

If the Department accepts the VECP or parts of it, the Department issues a change order that:

1. Incorporates changes in the contract necessary to implement the VECP or the parts adopted
2. Includes the Department's acceptance conditions
3. States the estimated net construction-cost savings resulting from the VECP
4. Obligates the Department to pay you 50 percent of the estimated net savings

In determining the estimated net construction-cost savings, the Department excludes your VECP preparation cost and the Department's VECP investigation cost, including parts paid by you.

If a VECP providing for a reduction in working days is accepted by the Department, 50 percent of the reduction is deducted from contract time.

If a VECP providing for a reduction in traffic congestion or avoiding traffic congestion is accepted by the Department, the Department pays 60 percent of the estimated net savings in construction costs attributable to the VECP. Submit detailed traffic handling comparisons between the existing contract and the proposed change, including estimates of the traffic volumes and congestion.

The Department may apply an accepted VECP for general use on other contracts.

If an accepted VECP is adopted for general use, the Department pays only the contractor who first submitted the VECP and only to the contracts awarded to that contractor before the submission of the accepted VECP.

If the Department does not adopt a general-use VECP, an identical or similar submitted proposal is eligible for acceptance.

**4-1.035C Value Analysis Workshop**

Section 4-1.035C, "Value Analysis Workshop," applies to a non-building-work contract with a total bid of over $5 million.

You may request a value analysis workshop by submitting a request after contract approval.

The Department offers a value analysis workshop to:

1. Identify value enhancing opportunities
2. Consider changes to the contract that will reduce the total cost of construction, construction activity duration, or traffic congestion without impairing the essential functions specified for a VECP in Section 4-1.035B, "Value Engineering Change Proposal."

If the request is authorized, you and the Engineer:

1. Schedule a value analysis workshop
2. Select a facilitator and workshop site

3. Agree to other workshop administrative details

The workshop must be conducted under the methods described in the Department's Value Analysis Team Guide available at:

http://www.dot.ca.gov/hq/oppd/value/

The facilitator must be a certified value specialist as recognized by the Society of American Value Engineers.

The Department reimburses you for 1/2 of the workshop cost. The workshop cost is the sum of the workshop-facilitator cost and the workshop-site cost. The Department determines the workshop cost based on the facilitator and workshop-site invoice prices minus any available or offered discounts. The Department does not pay you for any other associated costs.

^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^

## SECTION 5 CONTROL OF WORK
**(Issued 12-19-08)**

**Add:**

### 5-1.005 GENERAL

Failure to comply with any specification part is a waiver of your right to an adjustment of time and payment related to that part.

After contract approval, submit documents and direct questions to the Engineer. Orders, approvals, authorizations, and requests to the Contractor are by the Engineer.

The Engineer furnishes the following in writing:

1. Approvals
2. Authorizations
3. Notifications
4. Orders

The Contractor must furnish the following in writing:

1. Assignments
2. Notifications
3. Proposals
4. Requests, sequentially numbered
5. Subcontracts
6. Test results

The Department rejects a form if it has any error or any omission.

Convert foreign language documents to English.

Use contract administration forms available at the Department's Web site.

If the last day for submitting a document falls on a Saturday or holiday, it may be submitted on the next business day with the same effect as if it had been submitted on the day specified.

**Add to 5-1.01:**

Failure to enforce a contract provision does not waive enforcement of any contract provision.

**Add:**

## 5-1.012 PARTNERING

### 5-1.012A General

The Department strives to work cooperatively with all contractors; partnering is our way of doing business. The Department encourages project partnering among the project team, made up of significant contributors from the Department and the Contractor, and their invited stakeholders.

For a project with a total bid greater than $1 million, professionally facilitated project partnering is encouraged.

For a project with a total bid greater than $10 million, professionally facilitated project partnering is required.

In implementing project partnering, you and the Engineer manage the contract by:

1. Using early and regular communication with involved parties
2. Establishing and maintaining a relationship of shared trust, equity, and commitment
3. Identifying, quantifying, and supporting attainment of mutual goals
4. Developing strategies for using risk management concepts
5. Implementing timely communication and decision making
6. Resolving potential problems at the lowest possible level to avoid negative impacts
7. Holding periodic partnering meetings and workshops as appropriate to maintain partnering relationships and benefits throughout the life of the project
8. Establishing periodic joint evaluations of the partnering process and attainment of mutual goals

Partnering does not void any contract part.

The Department's "Field Guide to Partnering on Caltrans Construction Projects" current at the time of bid is available to the project team as reference. This guide provides structure, context, and clarity to the partnering process requirements. This guide is available at the Department's Partnering Program website:

http://www.dot.ca.gov/hq/construc/partnering.html

In implementing project partnering, the project team must:

1. Create a partnering charter that includes:

    1.1. Mutual goals, including core project goals and may also include project-specific goals and mutually supported individual goals.
    1.2. Partnering maintenance and close-out plan.
    1.3. Dispute resolution plan that includes a dispute resolution ladder and may also include use of facilitated dispute resolution sessions.
    1.4. Team commitment statement and signatures.

2. Participate in monthly partnering evaluation surveys to measure progress on mutual goals and may also measure short-term key issues as they arise.
3. Evaluate the partnering facilitator on Forms CEM-5501 and CEM-5502. The Engineer provides the evaluation forms to the project team and collects the results. The Department makes evaluation results available upon request. Facilitator evaluations must be completed:

    3.1. At the end of the initial partnering workshop on Form CEM-5501.
    3.2. At the end of the project close-out partnering workshop on Form CEM-5502.

4. Conduct a project close-out partnering workshop.
5. Document lessons learned before contract acceptance.

### 5-1.012B Partnering Facilitator, Workshops, and Monthly Evaluation Surveys

The Engineer sends you a written invitation to enter into a partnering relationship after contract approval. Respond within 15 days to accept the invitation and request the initial and additional partnering workshops. After the Engineer receives the request, you and the Engineer cooperatively:

1. Select a partnering facilitator that offers the service of a monthly partnering evaluation survey with a 5-point rating and agrees to follow the Department's "Partnering Facilitator Standards and Expectations" available at the Department's Partnering Program website
2. Schedule initial partnering workshop
3. Determine initial workshop site and duration
4. Agree to other workshop administrative details

Additional partnering workshops and sessions are encouraged throughout the life of the project as determined necessary by you and the Engineer, recommended quarterly.

**5-1.012C Training in Partnering Skills Development**

For a project with a total bid of $25 million or greater, training in partnering skills development is required.

For a project with a total bid between $10 million and $25 million, training in partnering skills is optional.

You and the Engineer cooperatively schedule the training session and select a professional trainer, training site, and 1 to 4 topics from the following list to be covered in the training:

1. Active Listening
2. Building Teams
3. Change Management
4. Communication
5. Conflict Resolution
6. Cultural Diversity
7. Dealing with Difficult People
8. Decision Making
9. Effective Escalation Ladders
10. Emotional Intelligence
11. Empathy
12. Ethics
13. Facilitation Skills
14. Leadership
15. Partnering Process and Concepts
16. Project Management
17. Project Organization
18. Problem Solving
19. Running Effective Meetings
20. Time Management
21. Win-Win Negotiation

Before the initial partnering workshop, the trainer conducts a 1-day training session in partnering skills development for the Contractor's and the Engineer's representatives. This training session must be a separate session from the initial partnering workshop and must be conducted locally. The training session must be consistent with the partnering principles under the Department's "Field Guide to Partnering on Caltrans Construction Projects."

Send at least 2 representatives to the training session. One of these must be your assigned representative as specified in Section 5-1.06, "Superintendence," of the Standard Specifications.

**5-1.012D Payment**

The Department pays you for:

1. 1/2 of partnering workshops and sessions based on facilitator and workshop site cost
2. 1/2 of monthly partnering evaluation survey service cost
3. Partnering skills development trainer and training site cost

The Department determines the costs based on invoice prices minus any available or offered discounts. The Department does not pay markups on these costs.

The Department does not pay for wages, travel expenses, or other costs associated with the partnering workshops and sessions, monthly partnering evaluation surveys, and training in partnering skills development.

**Add:**

## 5-1.015 RECORDS

### 5-1.015A General

Reserved

### 5-1.015B Record Retention

Retain project records from bid preparation through:

1. Final payment
2. Resolution of claims, if any

For at least 3 years after the later of these, retain cost records, including records of:

1. Bid preparation
2. Overhead
3. Payrolls
4. Payments to suppliers and subcontractors
5. Cost accounting

Maintain the records in an organized way in the original format, electronic and hard copy, conducive to professional review and audit.

### 5-1.015C Record Inspection, Copying, and Auditing

Make your records available for inspection, copying, and auditing by State representatives for the same time frame specified under Section 5-1.015B, "Record Retention." The records of subcontractors and suppliers must be made available for inspection, copying, and auditing by State representatives for the same period. Before contract acceptance, the State representative notifies the Contractor, subcontractor, or supplier 5 business days before inspection, copying, or auditing.

If an audit is to start more than 30 days after contract acceptance, the State representative notifies the Contractor, subcontractor, or supplier when the audit is to start.

### 5-1.015D Cost Accounting Records

Maintain cost accounting records for the project distinguishing between the following work cost categories:

1. Contract item work
2. Work character changes
3. Force account work
4. Extra work
5. Work performed under protests and claim notifications
6. Overhead
7. Subcontractors, suppliers, owner-operators, and professional services

Cost accounting records must include:

1. Final cost code lists and definitions
2. Itemization of the materials used and corresponding vendor's invoice copies
3. Direct cost of labor
4. Equipment rental charges
5. Workers' certified payrolls
6. Equipment:

    6.1. Size
    6.2. Type
    6.3. Identification number
    6.4. Hours operated

### 5-1.015E Extra Work Bills

Maintain separate records for force account costs.

Submit extra work bills using the Department's Internet extra work billing system.

The Contractor submitting and the Engineer approving an extra work bill using the Internet force account work billing system is the same as each party signing the report.

The Department provides billing system:

1. Training within 30 days of your written request
2. Accounts and user identification to your assigned representatives after a representative has received training

Each representative must maintain a unique password.

**Replace Section 5-1.04 with:**

## 5-1.04 CONTRACT COMPONENTS

A component in one contract part applies as if appearing in each. The parts are complementary and describe and provide for a complete work.

If a discrepancy exists:

1. The governing ranking of contract parts in descending order is:

    1.1. Special provisions
    1.2. Project plans
    1.3. Revised Standard Plans
    1.4. Standard Plans
    1.5. Amendments to the Standard Specifications
    1.6. Standard Specifications
    1.7. Supplemental project information

2. Written numbers and notes on a drawing govern over graphics
3. A detail drawing governs over a general drawing
4. A detail specification governs over a general specification
5. A specification in a section governs over a specification referenced by that section

If a discrepancy is found or confusion arises, request correction or clarification.

**Add:**

## 5-1.055 SUBCONTRACTING

### 5-1.055A General

No subcontract releases you from the contract or relieves you of your responsibility for a subcontractor's work.

If you violate Pub Cont Code § 4100 et seq., the Department may exercise the remedies provided under Pub Cont Code § 4110. The Department may refer the violation to the Contractors State License Board as provided under Pub Cont Code § 4111.

Except for a building-construction non-federal-aid contract, perform work equaling at least 30 percent of the value of the original total bid with your employees and with equipment owned or rented by you, with or without operators.

Each subcontract must comply with the contract.

Each subcontractor must have an active and valid State contractor's license with a classification appropriate for the work to be performed (Bus & Prof Code, § 7000 et seq.).

Submit copies of subcontracts upon request.

Before subcontracted work starts, submit a Subcontracting Request form.

Do not use a debarred contractor; a current list of debarred contractors is available at the Department of Industrial Relations' Web site.

Upon request, immediately remove and not again use a subcontractor who fails to prosecute the work satisfactorily.

**5-1.055B Disadvantaged Business Enterprises**

Section 5-1.055B, "Disadvantaged Business Enterprises," applies to a Federal-aid contract.

Use each subcontractor as listed on the Subcontractor List form unless you receive authorization for a substitution.

The Department requests the Contractor to:

1. Notify the Engineer of any changes to its anticipated DBE participation
2. Provide this notification before starting the affected work

Maintain records including:

1. Name and business address of each 1st-tier subcontractor
2. Name and business address of each DBE subcontractor, DBE vendor, and DBE trucking company, regardless of tier
2. Date of payment and total amount paid to each business

If you are a DBE contractor, include the date of work performed by your own forces and the corresponding value of the work.

Before the 15th of each month, submit a Monthly DBE Trucking Verification form.

For a DBE that leases trucks from a non-DBE, count only the fee or commission the DBE receives as a result of the lease arrangement.

If a DBE subcontractor is decertified before completing subcontracted work, the subcontractor must notify you in writing of the decertification date. If a subcontractor becomes a certified DBE before completing subcontracted work, the subcontractor must notify you in writing of the certification date. Submit the notifications. On contract work completion, complete a Disadvantaged Business Enterprises (DBE) Certification Status Change form. Submit the form within 90 days of contract acceptance.

Upon contract work completion, complete a Final Report – Utilization of Disadvantaged Business Enterprises (DBE), First-Tier Subcontractors form. Submit it within 90 days of contract acceptance. The Department withholds $10,000 until the form is submitted. The Department releases the withhold upon submission of the completed form.

**5-1.055C Disabled Veteran Business Enterprises**

Section 5-1.055C, "Disabled Veteran Business Enterprises," applies to a non-Federal-aid contract.

If a DVBE goal is shown in the Notice to Bidders:

1. Use each DVBE as shown on the Certified DVBE Summary form unless you receive authorization for a substitution
2. The requirement that DVBEs be certified by the bid opening date does not apply to DVBE substitutions after contract award
3. Maintain records of subcontracts made with certified DVBEs. Include in the records:

    3.1. Name and business address of each business
    3.2. Total amount paid to each business

4. For the purpose of determining compliance with Pub Cont Code § 10115 et seq.:

    4.1. Provide the Department relevant information requested
    4.2. Upon reasonable notice and during normal business hours, permit access to its premises for the purpose of:

        4.2.1. Interviewing employees
        4.2.2. Inspecting and copying books, records, accounts and other material that may be relevant to a matter under investigation

If no DVBE goal is shown in the Notice to Bidders and if you obtain DVBE participation, submit the participating DVBE names and value of work or supplies supplied by each DVBE transaction upon contract completion.

**5-1.055D Non–Small Businesses**

Section 5-1.055D, "Non–Small Businesses," applies to a non-Federal-aid contract.

Use each subcontractor as shown on the Certified Small Business Listing for the Non–Small Business Preference form unless you receive authorization for a substitution.

The requirement that small businesses be certified by the bid opening date does not apply to small business substitutions after contract award.

Maintain records of subcontracts made with certified small business subcontractors and records of materials purchased from certified small business suppliers. Include in the records:

1. Name and business address of each business
2. Total amount paid to each business

For the purpose of determining compliance with 2 CA Code of Regs § 1896 et seq.:

1. Provide the Department relevant information requested.
2. Upon reasonable notice and during normal business hours, permit access to its premises for the purpose of:

    2.1. Interviewing employees
    2.2. Inspecting and copying books, records, accounts and other material that may be relevant to a matter under investigation

**Replace Section 5-1.07 with:**

**5-1.07 LINES AND GRADES**

The Engineer places stakes and marks under Chapter 12, "Construction Surveys," of the Department's Surveys Manual.

Submit your request for Department-furnished stakes:

1. On a Request for Construction Stakes form. Ensure:

    1.1. Requested staking area is ready for stakes
    1.2. You use the stakes in a reasonable time

2. A reasonable time before starting an activity using the stakes

Establish priorities for stakes and note priorities on the request.

Preserve stakes and marks placed by the Engineer. If the stakes or marks are destroyed, the Engineer replaces them at the Engineer's earliest convenience and deducts the cost.

**Replace Section 5-1.116 with:**

**5-1.116 DIFFERING SITE CONDITIONS (23 CFR 635.109)**

**5-1.116A Contractor's Notification**

Promptly notify the Engineer if you find either of the following:

1. Physical conditions differing materially from either of the following:

    1.1. Contract documents
    1.2. Job site examination

2. Physical conditions of an unusual nature, differing materially from those ordinarily encountered and generally recognized as inherent in the work provided for in the contract

Include details explaining the information you relied on and the material differences you discovered.

If you fail to notify the Engineer promptly, you waive the differing site condition claim for the period between your discovery of the differing site condition and your notification to the Engineer.

If you disturb the site after discovery and before the Engineer's investigation, you waive the differing site condition claim.

**5-1.116B Engineer's Investigation and Decision**

Upon your notification, the Engineer investigates job site conditions and:

1. Notifies you whether to resume affected work
2. Decides whether the condition differs materially and is cause for an adjustment of time, payment, or both

**5-1.116C Protests**

You may protest the Engineer's decision by:

1. Submitting an Initial Notice of Potential Claim within 5 business days after receipt of the Engineer's notification
2. Complying with claim procedures

The Initial Notice of Potential Claim must detail the differences in your position from the Engineer's determination and support your position with additional information, including additional geotechnical data. Attach to the Initial Notice of Potential Claim a certification stating that you complied with Section 2-1.11, "Job Site and Document Examination."

Promptly submit supplementary information when obtained.

**Replace Section 5-1.14 with:**

**5-1.14 COST REDUCTION INCENTIVE**

Comply with Section 4-1.035B, "Value Engineering Change Proposal."

**Add:**

**5-1.15 DISPUTE RESOLUTION**

**5-1.15A General**

Section 5-1.15, "Dispute Resolution," applies to a contract with 100 or more working days.

In the Dispute Resolution Advisor Agreement and in the Dispute Review Board Agreement, interpret a reference to the special provisions as a reference to the Amendments to the Standard Specifications. In the Dispute Review Board Agreement, replace "Proposal and Contract" with "Bid book." Where the section title does not match the section number for a reference, refer to the referenced title.

**5-1.15B Dispute Resolution Advisor**

Section 5-1.15B, "Dispute Resolution Advisor," applies to a contract from $3 million to $10 million.

A dispute resolution advisor, hereinafter referred to as "DRA", is chosen by the Department and the Contractor to assist in the resolution of disputes. The DRA is a part of the contract administrative claims process as specified in the provisions in Section 9-1.04, "Notice of Potential Claim," and Section 9-1.07B, "Final Payment and Claims," of the Standard Specifications. The DRA shall not serve as a substitute for filing a protest or a notice of potential claim.

The DRA shall be established by the Department and the Contractor within 30 days of contract approval.

The Department and the Contractor shall each propose 3 potential DRA candidates. Each potential candidate shall provide the Department and the Contractor with their disclosure statement. The disclosure statement shall include a resume of the potential candidate's experience and a declaration statement describing past, present, anticipated, and planned relationships with all parties involved in this contract.

The Department and the Contractor shall select one of the 6 nominees to be the DRA. If the Department and the Contractor cannot agree on one candidate, the Department and the Contractor shall each choose one of the 3 nominated by the other. The final selection of the DRA will be decided by a coin toss between the two candidates.

The Department and the Contractor shall complete and adhere to the Dispute Resolution Advisor Agreement. No DRA meeting shall take place until the Dispute Resolution Advisor Agreement has been signed by all parties, unless all parties agree to sign it at the first meeting.

If DRA needs outside technical services, technical services shall be preapproved by both the Department and the Contractor.

DRA recommendations are nonbinding.

The Contractor shall not use the DRA for disputes between subcontractors or suppliers that have no grounds for a lawsuit against the Department.

DRA replacement is selected in the same manner as the original selection. The appointment of a replacement DRA will begin promptly upon determination of the need for replacement. The Dispute Resolution Advisor Agreement shall be amended to reflect the change of the DRA.

Failure of the Contractor to participate in selecting DRA will result in the withhold of 25 percent of the estimated value of all work performed during each estimate period that the Contractor fails to comply. DRA withholds will be released for

payment on the next monthly progress payment following the date that the Contractor has provided assistance in choosing the DRA and no interest will be due the Contractor.

The State and the Contractor shall bear the costs and expenses of the DRA equally.

The DRA shall be compensated at an agreed rate of $1,500 per day for time spent per meeting either at the start of the project or for a dispute. A member serving on more than one State DRA or Dispute Review Board, regardless the number of meetings per day shall not be paid more than the agreed rate per day. The agreed rate shall be considered full compensation for on-site time, travel expenses, transportation, lodging, time for travel, and incidentals for each day or portion thereof that the DRA is at an authorized DRA meeting.

No additional compensation will be made for time spent by the DRA to review and research activities outside the official DRA meetings unless that time, such as time spent evaluating and preparing recommendations on specific issues presented to the DRA, has been specifically agreed to in advance by the State and Contractor. Time away from the project that has been specifically agreed to in advance by the Department and the Contractor will be compensated at an agreed rate of $150 per hour. The agreed amount of $150 per hour shall include all incidentals including expenses for telephone, fax, and computer services.

The State will provide conference facilities for DRA meetings at no cost to the Contractor.

The Contractor shall make direct payments to the DRA for participation in authorized meetings and approved hourly rate charges from invoices submitted.

The State will reimburse the Contractor for the State's share of the costs.

There will be no markups applied to expenses associated with the DRA, either by the DRA or by the Contractor when requesting payment of the State's share of DRA expenses. Regardless of the DRA recommendation, neither party will be entitled to reimbursement of DRA costs from the other party.

The Contractor shall submit extra work bills and include invoices with original supporting documents for reimbursement of the State's share.

The cost of technical services will be borne equally by the State and Contractor. There will be no markups for these costs.

A copy of the "Dispute Resolution Advisor Agreement" to be executed by the Contractor, State and the DRA is as follows:

Form CEM 6206 Rev (04-06-07)

**DISPUTE RESOLUTION ADVISOR AGREEMENT**

_____
(Contract Identification)

Contract No. _____

**THIS DISPUTE RESOLUTION ADVISOR AGREEMENT, hereinafter called "AGREEMENT"**, made and entered into this _____ day of _____, _____, between the State of California, acting through the California Department of Transportation and the Director of Transportation, hereinafter called the "STATE," _____ hereinafter called the "CONTRACTOR," and _____, the Dispute Resolution Advisor, hereinafter called the "DRA." .

WITNESSETH, that

WHEREAS, the STATE and the CONTRACTOR, hereinafter called the "parties," are now engaged in the construction on the State Highway project referenced above; and

WHEREAS, the special provisions for the above referenced contract provides for the establishment and operation of the DRA to assist in resolving disputes; and

WHEREAS, the DRA is composed of one person, chosen by the CONTRACTOR and the STATE;

NOW THEREFORE, in consideration of the terms, conditions, covenants, and performance contained herein, or attached and incorporated and made a part hereof, the STATE, the CONTRACTOR, and the DRA hereto agree as follows:

## SECTION I DESCRIPTION OF WORK

To assist in the timely resolution of disputes between the parties, the contract provides for the establishment and the operation of the DRA. The DRA is to fairly and impartially consider disputes placed before it and provide recommendations for resolution of these disputes to the parties. The DRA shall provide recommendations based on the facts related to the dispute, the contract and applicable laws and regulations. The DRA shall perform the services necessary to participate in the DRA's actions as designated in Section III, Scope of Work.

## SECTION II DRA QUALIFICATIONS

DRA shall be knowledgeable in the type of construction and contract documents anticipated by the contract and shall have completed training through the Dispute Review Board Foundation. In addition, it is desirable for the DRA to have served on several State Dispute Review Boards (DRB).

No DRA shall have prior direct involvement in this contract. No DRA shall have a financial interest in this contract or parties thereto, including but not limited to the CONTRACTOR, subcontractors, suppliers, consultants, and legal and business services, within a period 6 months prior to award and during this contract. Exceptions to above are compensation for services on this or other DRAs and DRBs or retirement payments or pensions received from a party that are not tied to, dependent on or affected by the net worth of the party.

DRA shall fully disclose all direct or indirect professional or personal relationships with all key members of the contract.

## SECTION III SCOPE OF WORK

The Scope of Work of the DRA includes, but is not limited to, the following:

### A. PROCEDURES

The DRA shall meet with the parties at the start of the project to establish procedures that will govern the conduct of its business and reporting procedures in conformance with the requirements of the contract and the terms of this AGREEMENT. The DRA established procedures shall only be implemented upon approval by the parties. Subsequent meetings shall be held only to hear disputes between the parties.

The DRA shall not meet with, or discuss contract issues with individual parties.

State shall provide the DRA with the contract and all written correspondence regarding the dispute between the parties and, if available, the Contractor's supplemental notice of potential claim, and the Engineer's response to the supplemental notice of potential claim.

The parties shall not call the DRA who served on this contract as a witness in arbitration proceedings, which may arise from this contract.

The DRA shall have no claim against the STATE or the CONTRACTOR, or both, from claimed harm arising out of the parties' evaluations of the DRA's opinions.

### B. DISPUTE MEETING

The term "dispute meeting" as used in this subsection shall refer to both the informal and traditional dispute meeting processes, unless otherwise noted.

If the CONTRACTOR requests a dispute meeting with the DRA, the Contractor must simultaneously notify the STATE. Upon being notified of the need for a dispute meeting, the DRA shall review and consider the dispute. The DRA shall determine the time and location of the dispute meeting with due consideration for the needs and preferences of the parties, while recognizing the importance of a speedy resolution to the dispute.

Dispute meetings shall be conducted at any location that would be convenient and provide required facilities and access to necessary documentation.

Only the STATE's Resident Engineer or Area Construction Engineer and the CONTRACTOR's or subcontractor's, if the dispute involves a subcontractor, Superintendent or Project Manager may present information at a dispute meeting. There shall be no participation of persons who are not directly involved in the contract or who do not have direct knowledge of the dispute. The exception to this is technical services, as described below:

> The DRA, with approval of the parties, may obtain technical services necessary to adequately review the disputes presented, including audit, geotechnical, schedule analysis and other services. The parties' technical staff may supply those services as appropriate. The cost of technical services, as agreed to by the parties, shall be borne equally by the two parties as specified in an approved contract change order. The CONTRACTOR shall not be entitled to markups for the payments made for these services.

At the dispute meeting the DRA may ask questions, seek clarification, and request further clarification of data presented by either of the parties as may be necessary to assist in making a fully informed recommendation. However, the DRA shall

refrain from expressing opinions on the merits of statements on matters under dispute during the parties' presentations. Each party will be given ample time to fully present its position, make rebuttals, provide relevant documents, and respond to DRA questions and requests.

There shall be no testimony under oath or cross-examination, during DRA dispute meetings. There shall be no reporting of the procedures by a shorthand reporter or by electronic means. Documents and verbal statements shall be received by the DRA in conformance with the rules and regulations established at the first meeting between the DRA and parties. These established rules and regulations need not comply with prescribed legal laws of evidence.

Failure to attend a dispute meeting by either of the parties shall be conclusively considered by the DRA as indication that the non-attending party considers all written documents and correspondence submitted as their entire and complete argument. The claimant shall discuss the dispute, followed by the other party. Each party shall then be allowed one or more rebuttals at the meeting until all aspects of the dispute are thoroughly covered.

**1. TRADITIONAL DISPUTE MEETING:**

The following procedure shall be used for the traditional dispute meeting:

a. Within 5 days, after receiving the STATE's written response to the CONTRACTOR's supplemental notice of potential claim, the CONTRACTOR shall refer the dispute to the DRA, if the CONTRACTOR wishes to further pursue the dispute. The CONTRACTOR shall make the referral in writing to the DRA, simultaneously copied to the STATE. The written dispute referral shall describe the disputed matter in individual discrete segments, so that it will be clear to both parties and the DRA what discrete elements of the dispute have been resolved, and which remain unresolved, and shall include an estimate of the cost of the affected work and impacts, if any, on project completion.

b. The parties shall each be afforded an opportunity to be present and to be heard by the DRA, and to offer evidence. Either party furnishing written evidence or documentation to the DRA must furnish copies of such information to the other party a minimum of 10 days prior to the date the DRA is scheduled to convene the meeting for the dispute. Either party shall produce such additional evidence as the DRA may deem necessary to reach an understanding and a determination of the dispute. The party furnishing additional evidence shall furnish copies of such additional evidence to the other party at the same time the evidence is provided to the DRA. The DRA shall not consider evidence not furnished in conformance with the terms specified herein.

c. Upon receipt by the DRA of a written referral of a dispute, the DRA shall convene to review and consider the dispute. The dispute meeting shall be held no later than 25 days after receipt of the written referral unless otherwise agreed to by all parties.

d. The DRA shall furnish a written report to both parties. The DRA may request clarifying information of either party within 5 days after the DRA dispute meeting. Requested information shall be submitted to the DRA within 5 days of the DRA request. The DRA shall complete its report and submit it to the parties within 10 days of the DRA dispute meeting, except that time extensions may be granted at the request of the DRA with the written concurrence of both parties. The report shall summarize the facts considered, the contract language, law or regulation viewed by the DRA as pertinent to the dispute, and the DRA's interpretation and philosophy in arriving at its conclusions and recommendations and, if appropriate, recommends guidelines for determining compensation. The DRA's written opinion shall stand on its own, without attachments or appendices.

e. Within 10 days after receiving the DRA's report, both parties shall respond to the DRA in writing signifying that the dispute is either resolved or remains unresolved. Failure to provide the written response within the time specified, or a written rejection of the DRA's recommendation or response to a request for reconsideration presented in the report by either party, shall conclusively indicate that the party(s) failing to respond accepts the DRA recommendation. Immediately after responses have been received from both parties, the DRA shall provide copies of both responses to the parties simultaneously. Either party may request clarification of elements of the DRA's report from the DRA prior to responding to the report. The DRA shall consider any clarification request only if submitted within 5 days of receipt of the DRA's report, and if submitted simultaneously in writing to both the DRA and the other party. Each party may submit only one request for clarification for any individual DRA report. The DRA shall respond, in writing, to requests for clarification within 5 days of receipt of such requests.

f. Either party may seek a reconsideration of the DRA's recommendation. The DRA shall only grant reconsideration based upon submission of new evidence and if the request is submitted within the 10 day time limit specified for response to the DRA's written report. Each party may submit only one request for reconsideration regarding an individual DRA recommendation.

g. If the parties are able to settle their dispute with the aid of the DRA's report, the STATE and CONTRACTOR shall promptly accept and implement the settlement of the parties. If the parties cannot agree on compensation

within 30 days of the acceptance by both parties of the settlement, either party may request the DRA to make a recommendation regarding compensation.

**2. INFORMAL DISPUTE MEETING**

An informal dispute meeting shall be convened, only if, the parties and the DRA agree that this dispute resolution process is appropriate to settle the dispute.
The following procedure shall be used for the informal dispute meeting:

a. The parties shall furnish the DRA with one copy of pertinent documents requested by the DRA that are or may become necessary for the DRA to perform its function. The party furnishing documents shall furnish such documents to the other party at the same time the document is provided to the DRA.
b. After the dispute meeting has concluded; the DRA shall deliberate in private the same day, until a response to the parties is reached or as otherwise agreed to by the parties.
c. The DRA then verbally delivers its recommendation with findings to the parties.
d. After the recommendation is presented, the parties may ask for clarifications.
e. Occasionally the DRA on complex issues may be unable to formulate a recommendation based on the information given at a dispute meeting. However, the DRA may provide the parties with advice on strengths and weaknesses of their prospective positions, in the hope of the parties reaching settlement.
f. If the parties are able to settle their dispute with the aid of the DRA's opinion, the STATE and CONTRACTOR shall promptly accept and implement the settlement of the parties.
g. The DRA will not be bound by its oral recommendation in the event that a dispute is later heard by the DRA in a traditional dispute meeting.

Unless the dispute is settled, use of the informal dispute meeting does not relive the parties of their responsibilities under Section 5-1.12, "Dispute Resolution Advisor," of the Special Provisions or Subsection, "Traditional Dispute Meeting," of this AGREEMENT. There will be no extension of time allowed for the process to permit the use of the informal dispute meeting, unless otherwise agreed to by the parties.

**SECTION IV TIME FOR BEGINNING AND COMPLETION**

Once established, the DRA shall be in operation until the day the Director accepts the contract. The DRA shall not begin work under the terms of this AGREEMENT until authorized in writing by the STATE or as agreed to by the parties.

**SECTION V PAYMENT**

DRA shall be compensated at an agreed rate of $1,500 per day for time spent per meeting, either at the start of the project or for a dispute. A member serving on more than one State DRA or DRB, regardless the number of meetings per day, shall not be paid more than the agreed rate per day. The agreed rate shall be considered full compensation for onsite time, travel expenses, transportation, lodging, time for travel and incidentals for each day, or portion thereof that the DRA is at an authorized DRA meeting. No additional compensation will be made for time spent by DRA to review and research activities outside the official DRA meetings unless that time, (such as time spent evaluating and preparing recommendations on specific issues presented to the DRA), has been specifically agreed to in advance by the parties. Time away from the project, which has been specifically agreed to in advance by the parties, will be compensated at an agreed rate of $150 per hour. The agreed amount of $150 per hour shall include all incidentals including expenses for telephone, fax, and computer services. The State will provide administrative services such as conference facilities to the DRA.

**A. PAYMENT PROCESSING**

CONTRACTOR shall make direct payments to DRA for their participation in authorized meetings and approved hourly rate charges, from invoices submitted by the DRA, and technical services.

DRA may submit invoices to the CONTRACTOR for partial payment for work performed and services rendered for their participation in authorized meetings not more often than once per month during the progress of the work. The invoices shall be in a format approved by the parties and accompanied by a general description of activities performed during that billing period. Payment for hourly fees, at the agreed rate, shall not be paid to a DRA until the amount and extent of those fees are approved by the STATE and CONTRACTOR.

**B. INSPECTION OF COSTS RECORDS**

DRA and the CONTRACTOR shall keep available for inspection by representatives of the STATE and the United States, for a period of 3 years after final payment, the cost records and accounts pertaining to this AGREEMENT. If any

litigation, claim, or audit arising out of, in connection with, or related to this contract is initiated before the expiration of the 3-year period, the cost records and accounts shall be retained until such litigation, claim, or audit involving the records is completed.

**SECTION VI ASSIGNMENT OF TASKS OF WORK**

DRA shall not assign the work of this AGREEMENT.

**SECTION VII TERMINATION OF A DRA MEMBER**

DRA may resign after providing not less than 15 days written notice of the resignation to the STATE and CONTRACTOR. The DRA may be terminated, by either party, for failing to fully comply at all times with all required employment or financial disclosure conditions of DRA membership in conformance with the terms of the contract and this AGREEMENT. Each party shall document the need for replacement and substantiate the replacement request in writing to the other party and the DRA.

**SECTION VIII LEGAL RELATIONS**

The parties hereto mutually understand and agree that the DRA in the performance of duties is acting in the capacity of an independent agent and not as an employee of either party.

No party to this AGREEMENT shall bear a greater responsibility for damages or personal injury than is normally provided by Federal or State of California Law.

Notwithstanding the provisions of this contract that require the CONTRACTOR to indemnify and hold harmless the STATE, the parties shall jointly indemnify and hold harmless the DRA from and against all claims, damages, losses, and expenses, including but not limited to attorney's fees, arising out of and resulting from the findings and recommendations of the DRA.

**SECTION IX CONFIDENTIALITY**

The parties hereto mutually understand and agree that all documents and records provided by the parties in reference to issues brought before the DRA, which documents and records are marked "Confidential - for use by the DRA only," shall be kept in confidence and used only for the purpose of resolution of subject disputes, and for assisting in development of DRA findings and recommendations; that such documents and records will not be utilized or revealed to others, except to officials of the parties who are authorized to act on the subject disputes, for any purposes, during the life of this AGREEMENT. Upon termination of this AGREEMENT, said confidential documents and records, and all copies thereof, shall be returned to the parties who furnished them to the DRA. However, the parties understand that such documents may be subsequently discoverable and admissible in court or arbitration proceedings unless a protective order has been obtained by the party seeking further confidentiality.

**SECTION X DISPUTES**

Disputes between the parties arising out of the work or other terms of this AGREEMENT that cannot be resolved by negotiation and mutual concurrence between the parties or through the administrative process provided in the contract shall be resolved by arbitration as provided in Section 9-1.10, "Arbitration," of the Standard Specifications. Disputes between the DRA and the parties that cannot be resolved by negotiation and mutual concurrence shall be resolved in the appropriate forum.

**SECTION XI VENUE, APPLICABLE LAW, AND PERSONAL JURISDICTION**

In the event that any party, including the DRA, deems it necessary to institute arbitration proceedings to enforce any right or obligation under this AGREEMENT, the parties hereto agree that such action shall be initiated in the Office of Administrative Hearings of the State of California. The parties hereto agree that all questions shall be resolved by arbitration by application of California law and that the parties to such arbitration shall have the right of appeal from such decisions to the Superior Court in conformance with the laws of the State of California. Venue for the arbitration shall be Sacramento or any other location as agreed to by the parties.

**SECTION XII FEDERAL REVIEW AND REQUIREMENTS**

On Federal-Aid contracts, the Federal Highway Administration shall have the right to review the work of the DRA in progress, except for private meetings or deliberations of the DRA.

Other Federal requirements in this agreement shall only apply to Federal-Aid contracts.

**SECTION XIII CERTIFICATION OF CONTRACTOR, DRA, AND STATE**

IN WITNESS WHEREOF, the parties hereto have executed this AGREEMENT as of the day and year first above written.

DRA

By: _____

Title: _____

| CONTRACTOR | CALIFORNIA STATE DEPARTMENT OF TRANSPORTATION |
|---|---|
| By: _____ | By: _____ |
| Title: _____ | Title: _____ |

**5-1.15C Dispute Review Board**

Section 5-1.15C, "Dispute Review Board," applies to a contract over $10 million.

**5-1.15C(1) General**

To assist in the resolution of disputes or potential claims arising out of the work of this project, a Dispute Review Board, hereinafter referred to as the "DRB," shall be established by the Engineer and Contractor cooperatively upon approval of the contract. The DRB is intended to assist the contract administrative claims resolution process as specified in the provisions in Section 9-1.04, "Notice of Potential Claim," and Section 9-1.07B, "Final Payment and Claims," of the Standard Specifications and these special provisions. The DRB shall not serve as a substitute for provisions in the specifications in regard to filing potential claims. The requirements and procedures established in this section shall be a prerequisite to filing a claim, filing for arbitration, or filing for litigation prior or subsequent to project completion.

The DRB shall be utilized when dispute or potential claim resolution at the project level is unsuccessful. The DRB shall function as specified herein until the day of acceptance of the contract, at which time the work of the DRB will cease except for completion of unfinished reports. No DRB dispute meetings shall take place later than 30 days prior to acceptance of contract. After acceptance of contract, disputes or potential claims which have followed the dispute resolution processes of the Standard Specifications and these special provisions, but have not been resolved, shall be stated or restated by the Contractor, in response to the Proposed Final Estimate within the time limits provided in Section 9-1.07B, "Final Payment and Claims," of the Standard Specifications. The State will review those claims in conformance with the provisions in Section 9-1.07B of the Standard Specifications. Following the adherence to and completion of the contractual administrative claims procedure, the Contractor may file for arbitration in conformance with the provisions in Section 9-1.10, "Arbitration," of the Standard Specifications and these special provisions.

Disputes, as used in this section, shall include differences of opinion, properly noticed as provided hereinafter, between the State and Contractor on matters related to the work and other subjects considered by the State or Contractor, or by both, to be of concern to the DRB on this project, except matters relating to Contractor, subcontractor or supplier potential claims not actionable against the Department as specified in these special provisions or quantification of disputes for overhead type expenses or costs. Disputes for overhead type expenses or costs shall conform to the requirements of Section 9-1.07B, "Final Payment and Claims," of the Standard Specifications. Whenever the term "dispute" or "disputes" is used herein, it shall be deemed to include potential claims as well as disputes.

The DRB shall serve as an advisory body to assist in the resolution of disputes between the State and the Contractor, hereinafter referred to as the "parties." The DRB shall consider disputes referred to it, and furnish written reports containing findings and recommendations pertaining to those disputes, to the parties to aid in resolution of the differences between them. DRB findings and recommendations are not binding on the parties.

**5-1.15C(2) Selection Process, Disclosure and Appointments**

The DRB shall consist of one member selected by the State and approved by the Contractor, one member selected by the Contractor and approved by the State, and a third member selected by the first 2 members and approved by both the State and the Contractor. The third member shall act as the DRB Chairperson.

DRB members shall be especially knowledgeable in the type of construction and contract documents potentially anticipated by the contract. DRB members shall discharge their responsibilities impartially as an independent body,

considering the facts and circumstances related to the matters under consideration, pertinent provisions of the contract and applicable laws and regulations.

The State and the Contractor shall nominate and approve DRB members in conformance with the terms and conditions of the Dispute Review Board Agreement and these special provisions, within 45 days of the approval of the contract. Each party shall provide written notification to the other of the name of their selected DRB nominee along with the prospective member's complete written disclosure statement.

Disclosure statements shall include a resume of the prospective member's experience and a declaration statement describing past, present, anticipated, and planned relationships, including indirect relationships through the prospective member's primary or full-time employer, to this project and with the parties involved in this construction contract, including but not limited to, relevant subcontractors or suppliers to the parties, parties' principals, or parties' counsel. DRB members shall also include a full disclosure of close professional or personal relationships with all key members of the contract. Objections to nominees must be based on a specific breach or violation of nominee responsibilities or on nominee qualifications under these provisions unless otherwise specified. The Contractor or the State may, on a one-time basis, object to the other's nominee without specifying a reason and this person will not be selected for the DRB. Another person shall then be nominated within 15 days.

The first duty of the State and Contractor selected members of the DRB shall be to select and recommend a prospective third DRB member to the parties for final selection and approval. The first 2 DRB members shall proceed with the selection of the third DRB member immediately upon receiving written notification from the State of their selection, and shall provide their recommendation simultaneously to the parties within 15 days of the notification.

The first 2 DRB members shall select a third DRB member subject to mutual approval of the parties or may mutually concur on a list of potentially acceptable third DRB members and submit the list to the parties for final selection and approval of the third member. The goal in the selection of the third member is to complement the professional experience of the first 2 members and to provide leadership for the DRB's activities.

The third prospective DRB member shall supply a full disclosure statement to the first 2 DRB members and to the parties prior to appointment.

An impasse shall be considered to have been reached if the parties are unable to approve a third member within 15 days of receipt of the recommendation of the first 2 DRB members, or if the first 2 DRB members are unable to agree upon a recommendation within their 15 day time limit. In the event of an impasse in selection of third DRB member the State and the Contractor shall each propose 3 candidates for the third DRB member position. The parties shall select the candidates proposed under this paragraph from the current list of arbitrators certified by the Public Works Contract Arbitration Committee created by Article 7.2 (commencing with Section 10245) of the State Contract Act. The first 2 DRB members shall then select one of the 6 proposed candidates in a blind draw.

No DRB member shall have prior direct involvement in this contract. No member shall have a financial interest in this contract or the parties thereto, within a period of 6 months prior to award of this contract or during the contract, except as follows:

A. Compensation for services on this DRB.
B. Ownership interest in a party or parties, documented by the prospective DRB member, that has been reviewed and determined in writing by the State to be sufficiently insignificant to render the prospective member acceptable to the State.
C. Service as a member of other Dispute Review Boards on other contracts.
D. Retirement payments or pensions received from a party that are not tied to, dependent on or affected by the net worth of the party.
E. The above provisions apply to parties having a financial interest in this contract, including but not limited to contractors, subcontractors, suppliers, consultants, and legal and business services.

The Contractor or the State may reject any of the 3 DRB members who fail to fully comply at all times with all required employment and financial disclosure conditions of DRB membership as described in the Dispute Review Board Agreement and as specified herein. A copy of the Dispute Review Board Agreement is included in this section.

The Contractor, the State, and the 3 members of the DRB shall complete and adhere to the Dispute Review Board Agreement in administration of this DRB within 15 days of the parties' concurrence in the selection of the third member. No DRB meeting shall take place until the Dispute Review Board Agreement has been signed by all parties. The State authorizes the Engineer to execute and administer the terms of the Agreement. The person(s) designated by the Contractor as authorized to execute contract change orders shall be authorized to execute and administer the terms of this agreement, or to delegate the authority in writing. The operation of the DRB shall be in conformance with the terms of the Dispute Review Board Agreement.

**5-1.15C(3) Compensation**

The State and the Contractor shall bear the costs and expenses of the DRB equally. Each DRB member shall be compensated at an agreed rate of $1,200 per day if time spent per meeting, including on-site time plus one hour of travel time, is greater than 4 hours. Each DRB member shall be compensated at an agreed rate of $700 per day if time spent per meeting, including on-site time plus one hour of travel time, is less than or equal to 4 hours. The agreed rates shall be considered full compensation for on-site time, travel expenses, transportation, lodging, time for travel and incidentals for each day, or portion thereof, that the DRB member is at an authorized DRB meeting. No additional compensation will be made for time spent by DRB members in review and research activities outside the official DRB meetings unless that time, (such as time spent evaluating and preparing recommendations on specific issues presented to the DRB), has been specifically agreed to in advance by the State and Contractor. Time away from the project, which has been specifically agreed to in advance by the parties, will be compensated at an agreed rate of $125 per hour. The agreed amount of $125 per hour shall include all incidentals including expenses for telephone, fax, and computer services. Members serving on more than one DRB involving the Department, regardless of the number of meetings per day, shall not be paid more than the all inclusive rate per day or rate per hour for an individual project. The State will provide, at no cost to the Contractor, administrative services such as conference facilities and secretarial services to the DRB. These special provisions and the Dispute Review Board Agreement state the provisions for compensation and expenses of the DRB. DRB members shall be compensated at the same daily and hourly rate. The Contractor shall make direct payments to each DRB member for their participation in authorized meetings and approved hourly rate charges from invoices submitted by each DRB member. The State will reimburse the Contractor for the State's share of the costs. There will be no markups applied to expenses connected with the DRB, either by the DRB members or by the Contractor when requesting payment of the State's share of DRB expenses. Regardless of the DRB recommendation, neither party shall be entitled to reimbursement of DRB costs from the other party.

**5-1.15C(4) Replacement of DRB Members**

Service of a DRB member may be terminated at any time with not less than 15 days notice as follows:

A. The State may terminate service of the State appointed member.
B. The Contractor may terminate service of the Contractor appointed member.
C. Upon the written recommendation of the State and Contractor appointed members for the removal of the third member.
D. Upon resignation of a member.
E. The State or Contractor may terminate the service of any member who fails to fully comply with all required employment and financial disclosure conditions of DRB membership.

When a member of the DRB is replaced, the replacement member shall be appointed in the same manner as the replaced member was appointed. The appointment of a replacement DRB member will begin promptly upon determination of the need for replacement and shall be completed within 15 days. Changes in either of the DRB members chosen by the 2 parties will not require re-selection of the third member, unless both parties agree to such re-selection in writing. The Dispute Review Board Agreement shall be amended to reflect the change of a DRB member.

**5-1.15C(5) Operation**

The following procedure shall be used for dispute resolution:

A. If the Contractor objects to any decision, act or order of the Engineer, the Contractor shall give written notice of potential claim in conformance with the provisions in Section 9-1.04, "Notice of Potential Claim," of the Standard Specifications and these special provisions, including the provision of applicable cost documentation; or file written protests or notices in conformance with the provisions in the Standard Specifications and these special provisions.
B. The Engineer will respond, in writing, to the Contractor's written supplemental notice of potential claim within 20 days of receipt of the notice.
C. Within 15 days after receipt of the Engineer's written response, the Contractor shall, if the Contractor still objects, file a written reply with the Engineer, stating clearly and in detail the basis of the objection.
D. Following an objection to the Engineer's written response, the Contractor shall refer the dispute to the DRB if the Contractor wishes to further pursue the objection to the Engineer's decision. The Contractor shall make the referral in writing to the DRB, simultaneously copied to the State, within 21 days after receipt of the written response from the Engineer. The written dispute referral shall describe the disputed matter in individual discrete segments so that it will be clear to both parties and the DRB what discrete elements of the dispute have been resolved, and which

remain unresolved, and shall include an estimate of the cost of the affected work and impacts, if any, on project completion.

E. By failing to submit the written notice of referral to the DRB, within 21 days after receipt of the Engineer's written response to the supplemental notice of potential claim, the Contractor waives future claims and arbitration on the matter in contention.

F. The Contractor and the State shall each be afforded an opportunity to be present and to be heard by the DRB, and to offer evidence. Either party furnishing written evidence or documentation to the DRB must furnish copies of such information to the other party a minimum of 15 days prior to the date the DRB is scheduled to convene the meeting for the dispute. Either party shall produce such additional evidence as the DRB may deem necessary to reach an understanding and a determination of the dispute. The party furnishing additional evidence shall furnish copies of such additional evidence to the other party at the same time the evidence is provided to the DRB. The DRB shall not consider evidence not furnished in conformance with the terms specified herein.

G. Upon receipt by the DRB of a written referral of a dispute, the DRB shall convene to review and consider the dispute. The dispute meeting shall be held no earlier than 30 days and no later than 60 days after receipt of the written referral unless otherwise agreed to by all parties. The DRB shall determine the time and location of the DRB dispute meeting, with due consideration for the needs and preferences of the parties while recognizing the paramount importance of a timely hearing of the dispute.

H. There shall be no participation of either party's attorneys at DRB dispute meetings.

I. There shall be no participation of persons who are not directly involved in the contract or who do not have direct knowledge of the dispute, including but not limited to consultants, except for expert testimony allowed at the discretion of the DRB and with approval prior to the dispute meeting by both parties.

J. The DRB shall furnish a report, containing findings and recommendations as described in the Dispute Review Board Agreement, in writing to both the State and the Contractor. The DRB may request clarifying information of either party within 10 days after the DRB dispute meeting. Requested information shall be submitted to the DRB within 10 days of the DRB request. The DRB shall complete its report, including minority opinion, if any, and submit it to the parties within 30 days of the DRB dispute meeting, except that time extensions may be granted at the request of the DRB with the written concurrence of both parties. The report shall include the facts and circumstances related to the matters under consideration, pertinent provisions of the contract, applicable laws and regulations, and actual costs and time incurred as shown on the Contractor's cost accounting records. The DRB shall make recommendations on the merit of the dispute and, if appropriate, recommend guidelines for determining compensation.

K. Within 30 days after receiving the DRB's report, both the State and the Contractor shall respond to the DRB in writing signifying that the dispute is either resolved or remains unresolved. Failure to provide the written response within the time specified, or a written rejection of the DRB's recommendation or response to a request for reconsideration presented in the report by either party, shall conclusively indicate that the party(s) failing to respond accepts the DRB recommendation. Immediately after responses have been received from both parties, the DRB shall provide copies of both responses to the parties simultaneously. Either party may request clarification of elements of the DRB's report from the DRB prior to responding to the report. The DRB shall consider any clarification request only if submitted within 10 days of receipt of the DRB's report, and if submitted simultaneously in writing to both the DRB and the other party. Each party may submit only one request for clarification for any individual DRB report. The DRB shall respond, in writing, to requests for clarification within 10 days of receipt of such requests.

L. The DRB's recommendations, stated in the DRB's reports, are not binding on either party. Either party may seek a reconsideration of a recommendation of the DRB. The DRB shall only grant a reconsideration based upon submission of new evidence and if the request is submitted within the 30-day time limit specified for response to the DRB's written report. Each party may submit only one request for reconsideration regarding an individual DRB recommendation.

M. If the State and the Contractor are able to resolve their dispute with the aid of the DRB's report, the State and Contractor shall promptly accept and implement the recommendations of the DRB. If the parties cannot agree on compensation within 60 days of the acceptance by both parties of the DRB's recommendation, either party may request the DRB to make a recommendation regarding compensation.

N. The State or the Contractor shall not call DRB members who served on the DRB for this contract as witnesses in arbitration proceedings which may arise from this contract, and all documents created by the DRB shall be inadmissible as evidence in subsequent arbitration proceedings, except the DRB's final written reports on each issue brought before it.

O. The State and Contractor shall jointly indemnify and hold harmless the DRB members from and against all claims, damages, losses, and expenses, including but not limited to attorney's fees, arising out of and resulting from the findings and recommendations of the DRB.

P. The DRB members shall have no claim against the State or the Contractor, or both, from claimed harm arising out of the parties' evaluations of the DRB's report.

**5-1.15C(6) Disputes Involving Subcontractor Potential Claims**

For purposes of this section, a "subcontractor potential claim" shall include any potential claim by a subcontractor (including also any pass through potential claims by a lower tier subcontractor or supplier) against the Contractor that is actionable by the Contractor against the Department which arises from the work, services, or materials provided or to be provided in connection with the contract. If the Contractor determines to pursue a dispute against the Department that includes a subcontractor potential claim, the dispute shall be processed and resolved in conformance with these special provisions and in conformance with the following:

A. The Contractor shall identify clearly in submissions pursuant to this section, that portion of the dispute that involves a subcontractor potential claim or potential claims.
B. The Contractor shall include, as part of its submission pursuant to Step D above, a certification (False Claims Act Certification) by the subcontractor's or supplier's officer, partner, or authorized representative with authority to bind the subcontractor and with direct knowledge of the facts underlying the subcontractor potential claim. The Contractor shall submit a certification that the subcontractor potential claim is acknowledged and forwarded by the Contractor. The form for these certifications is available from the Engineer.
C. At DRB dispute meetings involving one or more subcontractor potential claims, the Contractor shall require that each subcontractor involved in the dispute have present an authorized representative with actual knowledge of the facts underlying the subcontractor potential claim to assist in presenting the subcontractor potential claim and to answer questions raised by the DRB members or the Department's representatives.
D. Failure by the Contractor to declare a subcontractor potential claim on behalf of its subcontractor (including lower tier subcontractors' and suppliers' pass through potential claims) at the time of submission of the Contractor's potential claims, as provided hereunder, shall constitute a release of the State by the Contractor of such subcontractor potential claim.
E. The Contractor shall include in all subcontracts under this contract that subcontractors and suppliers of any tier (a) agree to submit subcontractor potential claims to the Contractor in a proper form and in sufficient time to allow processing by the Contractor in conformance with the Dispute Review Board resolution specifications; (b) agree to be bound by the terms of the Dispute Review Board provisions to the extent applicable to subcontractor potential claims; (c) agree that, to the extent a subcontractor potential claim is involved, completion of all steps required under these Dispute Review Board special provisions shall be a condition precedent to pursuit by the subcontractor of other remedies permitted by law, including without limitation of a lawsuit against the Contractor; and (d) agree that the existence of a dispute resolution process for disputes involving subcontractor potential claims shall not be deemed to create any claim, right, or cause of action by any subcontractor or supplier against the Department.

Notwithstanding the foregoing, this Dispute Review Board special provision shall not apply to, and the DRB shall not have the authority to consider, subcontractor potential claims between the subcontractor(s) or supplier(s) and the Contractor that are not actionable by the Contractor against the Department.

**5-1.15C(7) Dispute Review Board Agreement**

A copy of the "Dispute Review Board Agreement" to be executed by the Contractor, State and the 3 DRB members after approval of the contract follows:

Form 6202 Rev (09/01/02)

**DISPUTE REVIEW BOARD AGREEMENT**

_____
(Contract Identification)

Contract No. _____

**THIS DISPUTE REVIEW BOARD AGREEMENT, hereinafter called "AGREEMENT"**, made and entered into this _____ day of _____, _____, between the State of California, acting through the California Department of Transportation and the Director of Transportation, hereinafter called the "STATE," _____ _____ hereinafter called the "CONTRACTOR," and the Dispute Review Board, hereinafter called the "DRB" consisting of the following members:

_____ ,
(Contractor Appointee)

_____ ,
(State Appointee)

and _____
(Third Person)

WITNESSETH, that

WHEREAS, the STATE and the CONTRACTOR, hereinafter called the "parties," are now engaged in the construction on the State Highway project referenced above; and

WHEREAS, the special provisions for the above referenced contract provides for the establishment and operation of the DRB to assist in resolving disputes; and

WHEREAS, the DRB is composed of three members, one selected by the STATE, one selected by the CONTRACTOR, and the third member selected by the other two members and approved by the parties;

NOW THEREFORE, in consideration of the terms, conditions, covenants, and performance contained herein, or attached and incorporated and made a part hereof, the STATE, the CONTRACTOR, and the DRB members hereto agree as follows:

**SECTION I DESCRIPTION OF WORK**

To assist in the resolution of disputes between the parties, the contract provides for the establishment and the operation of the DRB. The intent of the DRB is to fairly and impartially consider disputes placed before it and provide written recommendations for resolution of these disputes to both parties. The members of this DRB shall perform the services necessary to participate in the DRB's actions as designated in Section II, Scope of Work.

**SECTION II SCOPE OF WORK**

The scope of work of the DRB includes, but is not limited to, the following:

**A. OBJECTIVE**

The principal objective of the DRB is to assist in the timely resolution of disputes between the parties arising from performance of this contract. It is not intended for either party to default on their normal responsibility to amicably and fairly settle their differences by indiscriminately assigning them to the DRB. It is intended that the mere existence of the DRB will encourage the parties to resolve disputes without resorting to this review procedure. But when a dispute that is serious enough to warrant the DRB's review does develop, the process for prompt and efficient action will be in place.

**B. PROCEDURES**

The DRB shall render written reports on disputes between the parties arising from the construction contract. Prior to consideration of a dispute, the DRB shall establish rules and regulations that will govern the conduct of its business and

reporting procedures in conformance with the requirements of the contract and the terms of this AGREEMENT. DRB recommendations, resulting from its consideration of a dispute, shall be furnished in writing to both parties. The recommendations shall be based on facts and circumstances involved in the dispute, pertinent contract provisions, applicable laws and regulations. The recommendations shall find one responsible party in a dispute; shared or "jury" determinations shall not be rendered. The DRB shall make recommendations on the merit of the dispute, and if appropriate, recommend guidelines for determining compensation. If the parties cannot agree on compensation within 60 days of the acceptance by both parties of the DRB's recommendation, either party may request the DRB to make a recommendation regarding compensation.

The DRB shall refrain from officially giving advice or consulting services to anyone involved in the contract. The individual members shall act in a completely independent manner and while serving as members of the DRB shall have no consulting business connections with either party or its principals or attorneys or other affiliates (subcontractors, suppliers, etc.) who have a beneficial interest in the contract.

During scheduled meetings of the DRB as well as during dispute meetings, DRB members shall refrain from expressing opinions on the merits of statements on matters under dispute or potential dispute. Opinions of DRB members expressed in private sessions shall be kept strictly confidential. Individual DRB members shall not meet with, or discuss contract issues with individual parties, except as directed by the DRB Chairperson. Such discussions or meetings shall be disclosed to both parties. Other discussions regarding the project between the DRB members and the parties shall be in the presence of all three members and both parties. Individual DRB members shall not undertake independent investigations of any kind pertaining to disputes or potential disputes, except with the knowledge of both parties and as expressly directed by the DRB Chairperson.

### C. CONSTRUCTION SITE VISITS, PROGRESS MEETINGS AND FIELD INSPECTIONS

The DRB members shall visit the project site and meet with representatives of the parties to keep abreast of construction activities and to develop familiarity with the work in progress. Scheduled progress meetings shall be held at or near the project site. The DRB shall meet at least once at the start of the project, and at least once every 4 months thereafter. The frequency, exact time, and duration of additional site visits and progress meetings shall be as recommended by the DRB and approved by the parties consistent with the construction activities or matters under consideration and dispute. Each meeting shall consist of a round table discussion and a field inspection of the work being performed on the contract, if necessary. Each meeting shall be attended by representatives of both parties. The agenda shall generally be as follows:

1. Meeting opened by the DRB Chairperson.
2. Remarks by the STATE's representative.
3. A description by the CONTRACTOR's representative of work accomplished since the last meeting; the current schedule status of the work; and a forecast for the coming period.
4. An outline by the CONTRACTOR's representative of potential problems and a description of proposed solutions.
5. An outline by the STATE's representative of the status of the work as the STATE views it.
6. A brief description by the CONTRACTOR's or STATE's representative of potential claims or disputes which have surfaced since the last meeting.
7. A summary by the STATE's representative, the CONTRACTOR's representative, or the DRB of the status of past disputes and potential claims.

The STATE's representative will prepare minutes of all progress meetings and circulate them for revision and approval by all concerned within 10 days of the meeting.

The field inspection shall cover all active segments of the work, the DRB being accompanied by both parties' representatives. The field inspection may be waived upon mutual agreement of the parties.

### D. DRB CONSIDERATION AND HANDLING OF DISPUTES

Upon receipt by the DRB of a written referral of a dispute, the DRB shall convene to review and consider the dispute. The dispute meeting shall be held no earlier than 30 days and no later than 60 days after receipt of the written referral, unless otherwise agreed to by all parties. The DRB shall determine the time and location of DRB dispute meetings, with due consideration for the needs and preferences of the parties while recognizing the paramount importance of speedy resolution of issues. No dispute meetings shall take place later than 30 days prior to acceptance of contract.

Normally, dispute meetings shall be conducted at or near the project site. However, any location that would be more convenient and still provide required facilities and access to necessary documentation shall be satisfactory.

Both parties shall be given the opportunity to present their evidence at these dispute meetings. It is expressly understood that the DRB members are to act impartially and independently in the consideration of the contract provisions, applicable

laws and regulations, and the facts and conditions surrounding any dispute presented by either party, and that the recommendations concerning any such dispute are advisory and nonbinding on the parties.

The DRB may request that written documentation and arguments from both parties be sent to each DRB member, through the DRB Chairperson, for review before the dispute meeting begins. A party furnishing written documentation to the DRB shall furnish copies of such information to the other party at the same time that such information is supplied to the DRB.

DRB dispute meetings shall be informal. There shall be no testimony under oath or cross-examination. There shall be no reporting of the procedures by a shorthand reporter or by electronic means. Documents and verbal statements shall be received by the DRB in conformance with acceptance standards established by the DRB. These standards need not comply with prescribed legal laws of evidence.

The third DRB member shall act as Chairperson for dispute meetings and all other DRB activities. The parties shall have a representative at all dispute meetings. Failure to attend a duly noticed dispute meeting by either of the parties shall be conclusively considered by the DRB as indication that the non-attending party considers written submittals as their entire and complete argument. The claimant shall discuss the dispute, followed by the other party. Each party shall then be allowed one or more rebuttals until all aspects of the dispute are thoroughly covered. DRB members shall ask questions, seek clarification, and request further data from either of the parties as may be necessary to assist in making a fully informed recommendation. The DRB may request from either party documents or information that would assist the DRB in making its findings and recommendations including, but not limited to, documents used by the CONTRACTOR in preparing the bid for the project. A refusal by a party to provide information requested by the DRB may be considered by the DRB as an indication that the requested material would tend to disprove that party's position. In large or complex cases, additional dispute meetings may be necessary in order to consider all the evidence presented by both parties. All involved parties shall maintain the confidentiality of all documents and information, as provided in this AGREEMENT.

During dispute meetings, no DRB member shall express an opinion concerning the merit of any facet of the case. DRB deliberations shall be conducted in private, with interim individual views kept strictly confidential.

After dispute meetings are concluded, the DRB shall meet in private and reach a conclusion supported by 2 or more members. Private sessions of the DRB may be held at a location other than the job site or by electronic conferencing as deemed appropriate, in order to expedite the process.

The DRB's findings and recommendations, along with discussion of reasons therefor, shall then be submitted as a written report to both parties. Recommendations shall be based on the pertinent contract provisions, applicable laws and regulations, and facts and circumstances related to the dispute. The report shall be thorough in discussing the facts considered, the contract language, law or regulation viewed by the DRB as pertinent to the issues, and the DRB's interpretation and philosophy in arriving at its conclusions and recommendations. The DRB's report shall stand on its own, without attachments or appendices. The DRB Chairperson shall furnish a copy of the written recommendation report to the DRB Coordinator, Division of Construction, MS 44, P.O. Box 942874, Sacramento, CA 94274.

With prior written approval of both parties, the DRB may obtain technical services necessary to adequately review the disputes presented, including audit, geotechnical, schedule analysis and other services. The parties' technical staff may supply those services as appropriate. The cost of technical services, as agreed to by the parties, shall be borne equally by the 2 parties as specified in an approved contract change order. The CONTRACTOR will not be entitled to markups for the payments made for these services.

The DRB shall resist submittal of incremental portions of information by either party, in the interest of making a fully informed decision and recommendation.

The DRB shall make every effort to reach a unanimous decision. If this proves impossible, the dissenting member shall prepare a minority opinion, which shall be included in the DRB's report.

Although both parties should place weight upon the DRB's recommendations, they are not binding. Either party may appeal a recommendation to the DRB for reconsideration. However, reconsideration shall only be allowed when there is new evidence to present, and the DRB shall accept only one appeal from each party pertaining to an individual DRB recommendation. The DRB shall hear appeals in conformance with the terms described in the Section entitled "Dispute Review Board" in the special provisions.

### E. DRB MEMBER REPLACEMENT

Should the need arise to appoint a replacement DRB member, the replacement DRB member shall be appointed in the same manner as the original DRB members were appointed. The selection of a replacement DRB member shall begin promptly upon notification of the necessity for a replacement and shall be completed within 15 days. This AGREEMENT shall be amended to indicate change in DRB membership.

**SECTION III CONTRACTOR RESPONSIBILITIES**

The CONTRACTOR shall furnish to each DRB member one copy of pertinent documents that are or may become necessary for the DRB to perform their function. Pertinent documents are written notices of potential claim, responses to those notices, drawings or sketches, calculations, procedures, schedules, estimates, or other documents which are used in the performance of the work or in justifying or substantiating the CONTRACTOR's position. The CONTRACTOR shall also furnish a copy of such pertinent documents to the STATE, in conformance with the terms outlined in the special provisions.

**SECTION IV STATE RESPONSIBILITIES**

The STATE will furnish the following services and items:

**A. CONTRACT RELATED DOCUMENTS**

The STATE will furnish to each DRB member one copy of Notice to Contractors and Special Provisions, Proposal and Contract, Plans, Standard Specifications, and Standard Plans, change orders, written instructions issued by the STATE to the CONTRACTOR, or other documents pertinent to any dispute that has been referred to the DRB and necessary for the DRB to perform its function.

**B. COORDINATION AND SERVICES**

The STATE, through the Engineer, will, in cooperation with the CONTRACTOR, coordinate the operations of the DRB. The Engineer will arrange or provide conference facilities at or near the project site and provide secretarial and copying services to the DRB without charge to the CONTRACTOR.

**SECTION V TIME FOR BEGINNING AND COMPLETION**

Once established, the DRB shall be in operation until the day of acceptance of the contract. The DRB members shall not begin work under the terms of this AGREEMENT until authorized in writing by the STATE.

**SECTION VI PAYMENT**

**A. ALL INCLUSIVE RATE PAYMENT**

The STATE and the CONTRACTOR shall bear the costs and expenses of the DRB equally. Each DRB member shall be compensated at an agreed rate of $1,200 per day if time spent per meeting, including on-site time plus one hour of travel time, is greater than 4 hours. Each DRB member shall be compensated at an agreed rate of $700 per day if time spent per meeting, including on-site time plus one hour of travel time, is less than or equal to 4 hours. The agreed rates shall be considered full compensation for on-site time, travel expenses, transportation, lodging, time for travel and incidentals for each day, or portion thereof, that the DRB member is at an authorized DRB meeting. No additional compensation will be made for time spent by DRB members in review and research activities outside the official DRB meetings unless that time has been specifically agreed to in advance by the STATE and CONTRACTOR. Time away from the project that has been specifically agreed to in advance by the parties will be compensated at an agreed rate of $125 per hour. The agreed amount of $125 per hour shall include all incidentals including expenses for telephone, fax, and computer services. Members serving on more than one DRB involving the State, regardless of the number of meetings per day, shall not be paid more than the all inclusive rate per day or rate per hour for an individual project. The STATE will provide, at no cost to the CONTRACTOR, administrative services such as conference facilities and secretarial services to the DRB.

**B. PAYMENTS**

DRB members shall be compensated at the same rate. The CONTRACTOR shall make direct payments to each DRB member for their participation in authorized meetings and approved hourly rate charges from invoices submitted by each DRB member. The STATE will reimburse the CONTRACTOR for its share of the costs of the DRB.

The DRB members may submit invoices to the CONTRACTOR for partial payment for work performed and services rendered for their participation in authorized meetings not more often than once per month during the progress of the work. The invoices shall be in a format approved by the parties and accompanied by a general description of activities performed during that billing period. Payment for hourly fees, at the agreed rate, shall not be paid to a DRB member until the amount and extent of those fees are approved by the STATE and CONTRACTOR.

Invoices shall be accompanied by original supporting documents, which the CONTRACTOR shall include with the extra work billing when submitting for reimbursement of the STATE's share of cost from the STATE. The CONTRACTOR will be reimbursed for one-half of approved costs of the DRB. No markups will be added to the CONTRACTOR's payment.

**C. INSPECTION OF COSTS RECORDS**

The DRB members and the CONTRACTOR shall keep available for inspection by representatives of the STATE and the United States, for a period of 3 years after final payment, the cost records and accounts pertaining to this AGREEMENT. If any litigation, claim, or audit arising out of, in connection with, or related to this contract is initiated before the expiration of the 3-year period, the cost records and accounts shall be retained until such litigation, claim, or audit involving the records is completed.

**SECTION VII ASSIGNMENT OF TASKS OF WORK**

The DRB members shall not assign the work of this AGREEMENT.

**SECTION VIII TERMINATION OF DRB MEMBERS**

DRB members may resign from the DRB by providing not less than 15 days written notice of the resignation to the STATE and CONTRACTOR. DRB members may be terminated by their original appointing power or by either party, for failing to fully comply at all times with all required employment and financial disclosure conditions of DRB membership in conformance with the terms of the contract.

**SECTION IX LEGAL RELATIONS**

The parties hereto mutually understand and agree that the DRB member in the performance of duties on the DRB, is acting in the capacity of an independent agent and not as an employee of either party.

No party to this AGREEMENT shall bear a greater responsibility for damages or personal injury than is normally provided by Federal or State of California Law.

Notwithstanding the provisions of this contract that require the CONTRACTOR to indemnify and hold harmless the STATE, the parties shall jointly indemnify and hold harmless the DRB members from and against all claims, damages, losses, and expenses, including but not limited to attorney's fees, arising out of and resulting from the findings and recommendations of the DRB.

**SECTION X CONFIDENTIALITY**

The parties hereto mutually understand and agree that all documents and records provided by the parties in reference to issues brought before the DRB, which documents and records are marked "Confidential - for use by the DRB only," shall be kept in confidence and used only for the purpose of resolution of subject disputes, and for assisting in development of DRB findings and recommendations; that such documents and records will not be utilized or revealed to others, except to officials of the parties who are authorized to act on the subject disputes, for any purposes, during the life of the DRB. Upon termination of this AGREEMENT, said confidential documents and records, and all copies thereof, shall be returned to the parties who furnished them to the DRB. However, the parties understand that such documents shall be subsequently discoverable and admissible in court or arbitration proceedings unless a protective order has been obtained by the party seeking further confidentiality.

**SECTION XI DISPUTES**

Disputes between the parties hereto, including disputes between the DRB members and either party or both parties, arising out of the work or other terms of this AGREEMENT, which cannot be resolved by negotiation and mutual concurrence between the parties, or through the administrative process provided in the contract, shall be resolved by arbitration as provided in Section 9-1.10, "Arbitration," of the Standard Specifications.

**SECTION XII VENUE, APPLICABLE LAW, AND PERSONAL JURISDICTION**

In the event that any party, including an individual member of the DRB, deems it necessary to institute arbitration proceedings to enforce any right or obligation under this AGREEMENT, the parties hereto agree that such action shall be initiated in the Office of Administrative Hearings of the State of California. The parties hereto agree that all questions shall be resolved by arbitration by application of California law and that the parties to such arbitration shall have the right of appeal from such decisions to the Superior Court in conformance with the laws of the State of California. Venue for the arbitration shall be Sacramento or any other location as agreed to by the parties.

**SECTION XIII FEDERAL REVIEW AND REQUIREMENTS**

On Federal-Aid contracts, the Federal Highway Administration shall have the right to review the work of the DRB in progress, except for private meetings or deliberations of the DRB.

Other Federal requirements in this agreement shall only apply to Federal-Aid contracts.

**SECTION XIV CERTIFICATION OF THE CONTRACTOR, THE DRB MEMBERS, AND THE STATE**

IN WITNESS WHEREOF, the parties hereto have executed this AGREEMENT as of the day and year first above written.

DRB MEMBER

By: _____

Title: _____

DRB MEMBER

By: _____

Title :_____

DRB MEMBER

By :_____

Title :_____

CONTRACTOR

By: _____

Title: _____

CALIFORNIA STATE DEPARTMENT
OF TRANSPORTATION

By: _____

Title: _____

**Add:**

**5-1.16–5-17 (BLANK)**

**Add:**

**5-1.18 PROPERTY AND FACILITY PRESERVATION**

**5-1.18A General**

Preserve property and facilities, including:

1. Adjacent property
2. Department's instrumentation
3. ESAs
4. Lands administered by other agencies
5. Railroads and railroad equipment
6. Roadside vegetation not to be removed
7. Utilities
8. Waterways

Immediately report damage to the Engineer.

If you cause damage, you are responsible.

Install sheet piling, cribbing, bulkheads, shores, or other supports necessary to support existing facilities or support material carrying the facilities.

Dispose of temporary facilities when they are no longer needed.

If you damage plants not to be removed:

1. Dispose of them outside the right of way unless the Engineer allows you to reduce them to chips and spread the chips within the highway at locations designated by the Engineer
2. Replace them

Replace plants with plants of the same species.

Replace trees with 24-inch-box trees.

Replace shrubs with No. 15 container shrubs.

Replace ground cover plants with plants from flats. Replace Carpobrutus ground cover plants with plants from cuttings. Plant ground cover plants 1 foot on center.

If a plant establishment period is specified, replace plants before the start of the plant establishment period; otherwise, replace plants at least 30 days before Contract acceptance.

Water each plant immediately after planting and saturate the backfill soil around and below the roots or ball of earth around the roots of each plant. Water as necessary to maintain plants in a healthy condition until Contract acceptance.

The Department may make a temporary repair to restore service to a damaged facility.

If working on or adjacent to railroad property, do not interfere with railroad operations.

For an excavation on or affecting railroad property, submit work plans showing the system to be used to protect railroad facilities. Allow 65 days for the Engineer's review of the plans. Do not perform work based on the plans until the Engineer notifies you they are accepted.

**5-1.18B Nonhighway Facilities (Including Utilities)**

The Department may rearrange a nonhighway facility during the Contract. Rearrangement of a nonhighway facility includes installation, relocation, alteration, or removal of the facility.The Department may authorize facility owners and their agents to enter the highway to perform rearrangement work for their facilities or to make connections or repairs to their property. Coordinate activities to avoid delays.

Notify the Engineer at least 3 business days before you contact the regional notification center under Govt Code § 4216 et seq. Failure to contact the notification center prohibits excavation.

Before starting work that could damage or interfere with underground infrastructure, locate the infrastructure described in the Contract, including laterals and other appurtenances, and determine the presence of other underground infrastructure inferred from visible facilities such as buildings, meters, or junction boxes.

Notify the Engineer if the infrastructure described in the Contract cannot be found. If after giving the notice, you find the infrastructure in a substantially different location than described, finding the infrastructure is paid for as extra work as specified in Section 4-1.03D, "Extra Work."

Underground infrastructure described in the Contract may be in different locations than described, and additional infrastructure may exist.

Upon discovering an underground main or trunk line not described in the Contract, immediately notify the Engineer and the infrastructure owner. The Engineer orders the locating and protecting of the infrastructure. The locating and protecting is paid for as extra work as specified in Section 4-1.03D, "Extra Work." If ordered, repair infrastructure damage. If the damage is not due to your negligence, the repair is paid for as extra work as specified in Section 4-1.03D, "Extra Work."

If necessary underground infrastructure rearrangement is not described in the Contract, the Engineer may order you to perform the work. The rearrangement is paid for as extra work as specified in Section 4-1.03D, "Extra Work."

If you want infrastructure rearrangement different from that described in the Contract:

1. Notify the Engineer
2. Make an arrangement with the infrastructure owner
3. Obtain authorization for the rearrangement
4. The Department does not adjust time or payment for rearrangement different from the Contract
5. Pay the infrastructure owner any additional cost

Immediately notify the Engineer of a delay due to the presence of main line underground infrastructure not described in the Contract or in a substantially different location or due to rearrangement different from the Contract. The Department pays for one of these delays in the same manner as specified for a right of way delay in Section 8-1.09, "Right of Way Delays."

^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^

## SECTION 6 CONTROL OF MATERIALS
**(Issued 05-01-09)**

**Replace Section 6-1.05 with:**

## 6-1.05 SPECIFIC BRAND OR TRADE NAME AND SUBSTITUTION

A reference to a specific brand or trade name establishes a quality standard and is not intended to limit competition. You may use a product that is equal to or better than the specified brand or trade name if approved.

Submit a substitution request within a time period that:

1. Follows Contract award
2. Allows 30 days for review
3. Causes no delay

Include substantiating data with the substitution request that proves the substitution:

1. Is of equal or better quality and suitability
2. Causes no delay in product delivery and installation

**Add:**

## 6-1.075 GUARANTEE

Guarantee the work remains free from substantial defects for 1 year after contract acceptance except for work parts for which you were relieved of maintenance and protection. Guarantee each of these relieved work parts for 1 year after the relief date.

The guarantee excludes damage or displacement caused by an event outside your control including:

1. Normal wear and tear
2. Improper operation
3. Insufficient maintenance
4. Abuse
5. Unauthorized change
6. Act of God

During the guarantee period, repair or replace each work portion having a substantial defect.

The Department does not pay for corrective work.

During corrective work activities, provide insurance coverage specified for coverage before contract acceptance.

The contract bonds must be in full force and effect until the later of:

1. Expiration of guarantee period
2. Completion of corrective work

If a warranty specification conflicts with Section 6-1.075, "Guarantee," comply with the warranty specification.

During the guarantee period, the Engineer monitors the completed work. If the Engineer finds work having a substantial defect, the Engineer lists work parts and furnishes you the list.

Within 10 days of receipt of the list, submit for authorization a detailed plan for correcting the work. Include a schedule that includes:

1. Start and completion dates
2. List of labor, equipment, materials, and any special services you plan to use
3. Work related to the corrective work, including traffic control and temporary and permanent pavement markings

The Engineer notifies you when the plan is authorized. Start corrective work and related work within 15 days of notice.

If the Engineer determines corrective work is urgently required to prevent injury or property damage:

1. The Engineer furnishes you a request to start emergency repair work and a list of parts requiring corrective work
2. Mobilize within 24 hours and start work
3. Submit a corrective work plan within 5 days of starting emergency repair work

If you fail to perform work as specified, the Department may perform the work and bill you.

**In Section 6-1.08 delete the 2nd paragraph.**

**Add:**

**6-1.085 BUY AMERICA (23 CFR 635.410)**

For a Federal-aid contract, furnish steel and iron materials to be incorporated into the work that are produced in the United States except:

1. Foreign pig iron and processed, pelletized, and reduced iron ore may be used in the domestic production of the steel and iron materials [60 Fed Reg 15478 (03/24/1995)]
2. If the total combined cost of the materials does not exceed the greater of 0.1 percent of the total bid or $2,500, material produced outside the United States may be used

Production includes:

1. Processing steel and iron materials, including smelting or other processes that alter the physical form or shape (such as rolling, extruding, machining, bending, grinding, and drilling) or chemical composition
2. Coating application, including epoxy coating, galvanizing, and painting, that protects or enhances the value of steel and iron materials

For steel and iron materials to be incorporated into the work, submit a Certificate of Compliance under Section 6-1.07, "Certificates of Compliance," of the Standard Specifications that certifies all production processes occurred in the United States except for the above exceptions.

**Add:**

**6-1.087 BUY AMERICA (PUB RES CODE § 42703(d))**

Furnish crumb rubber to be incorporated into the work that is produced in the United States and is derived from waste tires taken from vehicles owned and operated in the United States.

For crumb rubber to be incorporated into the work, submit a Certificate of Compliance under Section 6-1.07, "Certificates of Compliance," of the Standard Specifications that certifies only crumb rubber manufactured in the United States and derived from waste tires taken from vehicles owned and operated in the United States is used.

**In Section 6-2.01 delete the 4th paragraph.**

**In Section 6-2.01 replace the 7th paragraph with:**

Upon the Contractor's written request, the Department tests materials from an untested local source. If satisfactory material from that source is used in the work, the Department does not charge the Contractor for the tests; otherwise, the Department deducts the test cost.

**In Section 6-2.01 delete the 8th paragraph.**

**In Section 6-2.02 delete the 3rd paragraph.**

**In Section 6-2.02 in the 7th paragraph, replace the 2nd sentence with:**

The Department deducts the charges for the removed material.

**In Section 6-2.03 in the 3rd paragraph, replace the 5th sentence with:**

No allowance or additional compensation will be made for lost time or for delay in completing the work due to moving the Contractor's plant from the designated mandatory source to the alternative mandatory source, other than a time adjustment as specified in Section 8-1.09, "Delays."

**In Section 6-3.01 delete the 4th paragraph.**

**In Section 6-3.01 in the 6th paragraph, delete the 1st sentence.**

**In Section 6-3.01 add:**

As used in Section 6-3.01, "Testing," tests are tests to assure the quality and to determine the acceptability of the work. The Department deducts costs of testing work found to be noncompliant.

^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^

## SECTION 7 LEGAL RELATIONS AND RESPONSIBILITY
**(Issued 05-01-09)**

**Replace Section 7-1.01 with:**

### 7-1.01 LAWS TO BE OBSERVED

Comply with laws, regulations, orders, decrees, and PLACs applicable to the project. Indemnify and defend the State against any claim or liability arising from the violation of a law, regulation, order, decree, or PLAC by you or your employees. Immediately report to the Engineer in writing a discrepancy or inconsistency between the contract and a law, regulation, order, decree, or PLAC.

**In Section 7-1.01A replace the 1st clause with:**

Work on the job site must comply with Labor Code §§ 1727 and 1770-1815 and 8 CA Code of Regs § 16000 et seq. Work includes roadside production and processing of materials.

**In Section 7-1.01A(2) in the 1st paragraph, replace item 3 with:**

3. Upon becoming aware of the subcontractor's failure to pay the specified prevailing rate of wages to the subcontractor's workers, the Contractor must diligently take corrective action to stop or rectify the failure, including withholding sufficient funds due the subcontractor for work performed on the public works project.

**In Section 7-1.01A(2), replace the 2nd paragraph with:**

Pursuant to Section 1775 of the Labor Code, the Division of Labor Standards Enforcement must notify the Contractor on a public works project within 15 days of the receipt by the Division of Labor Standards Enforcement of a complaint of the failure of a subcontractor on that public works project to pay workers the general prevailing rate of per diem wages. If the Division of Labor Standards Enforcement determines that employees of a subcontractor were not paid the general prevailing rate of per diem wages and if the Department did not withhold sufficient money under the contract to pay those employees the balance of wages owed under the general prevailing rate of per diem wages, the Contractor must withhold an amount of moneys due the subcontractor sufficient to pay those employees the general prevailing rate of per diem wages if requested by the Division of Labor Standards Enforcement. The Contractor must pay any money withheld from and owed to a subcontractor upon receipt of notification by the Division of Labor Standards Enforcement that the wage complaint has been resolved. If notice of the resolution of the wage complaint has not been received by the Contractor within 180 days of the filing of a valid notice of completion or acceptance of the public works project, whichever occurs later, the Contractor must

pay all moneys withheld from the subcontractor to the Department. The Department withholds these moneys pending the final decision of an enforcement action.

**In Section 7-1.01A(2) replace 7th paragraph with:**

Changes in general prevailing wage determinations apply to the contract when the Director of Industrial Relations has issued them at least 10 days before advertisement (Labor Code § 1773.6 and 8 CA Code of Regs 16204).

**In Section 7-1.01A(3) replace the 2nd paragraph with:**

The Department withholds the penalties specified in subdivision (g) of Labor Code § 1776 for noncompliance with the requirements in Section 1776.

**In Section 7-1.01A(3) replace the 4th paragraph with:**

The Department withholds for delinquent or inadequate payroll records (Labor Code § 1771.5). If the Contractor has not submitted an adequate payroll record by the month's 15th day for the period ending on or before the 1st of that month, the Department withholds 10 percent of the monthly progress estimate, exclusive of mobilization. The Department does not withhold more than $10,000 or less than $1,000.

**In Section 7-1.01A(3) delete the 5th paragraph.**

**Replace Section 7-1.01A(6) with:**

**7-1.01A(6) (Blank)**

**Replace Section 7-1.01F with:**

**7-1.01F Environmental Stewardship**

Comply with Section 14.

**Replace Section 7-1.01I with:**

**7-1.01I (Blank)**

**In Section 7-1.02 in the 2nd paragraph, replace the 4th sentence with:**

Trucks used to haul treated base, portland cement concrete, or hot mix asphalt shall enter onto the base to dump at the nearest practical entry point ahead of spreading equipment.

**In Section 7-1.02 between the 4th and 5th paragraphs, add:**

Loads imposed on existing, new, or partially completed structures shall not exceed the load carrying capacity of the structure or any portion of the structure as determined by AASHTO LRFD with interims and California Amendments, Design Strength Limit State II. The compressive strength of concrete ($f'_c$) to be used in computing the load carrying capacity shall be the smaller of the following:

1. Actual compressive strength at the time of loading
2. Value of $f'_c$ shown on the plans for that portion of the structure or 2.5 times the value of $f_c$ (extreme fiber compressive stress in concrete at service loads) shown on the plans for portions of the structure where no $f'_c$ is shown

**In Section 7-1.06 in the 1st paragraph, add:**

The Contractor's Injury and Illness Prevention Program shall be submitted to the Engineer. The program shall address the use of personal and company issued electronic devices during work. The use of entertainment and personal communication devices in the work zone shall not be allowed. Workers may use a communication device for business purposes in the work area, at a location where their safety and the safety of other workers and the traveling public is not compromised.

**Replace Section 7-1.07 with:**

**7-1.07 Lead Compliance Plan**

Section 7-1.07 applies if a bid item for a lead compliance plan is included in the Contract.

Prepare a work plan to prevent or minimize worker exposure to lead while managing and handling earth materials, paint system debris, traffic stripe residue, and pavement marking residue containing lead. Regulations containing specific Cal/OSHA requirements when working with lead include 8 CA Code of Regs § 1532.1.

The plan must contain the items listed in 8 CA Code of Regs § 1532.1(e)(2)(B). Before submittal, a CIH must sign and seal the plan. Submit the plan at least 7 days before starting any activity that presents the potential for lead exposure. The Engineer notifies you of the acceptability of the plan within 4 business days of receipt.

Before starting any activity that presents the potential for lead exposure to employees who have no prior training, including State employees, provide a safety training program to these employees that complies with 8 CA Code of Regs § 1532.1 and your lead compliance program.

Submit copies of air monitoring or job site inspection reports made by or under the direction of the CIH under 8 CA Code of Regs § 1532.1 within 10 days after the date of monitoring or inspection.

Supply personal protective equipment, training, and washing facilities required by your lead compliance plan for 5 State employees.

The contract lump sum price paid for lead compliance plan includes full compensation for furnishing all labor, materials, tools, equipment, and incidentals, and for doing all the work involved in preparing and implementing the plan as specified in this section.

**Replace Section 7-1.08 with:**

**7-1.08 PUBLIC CONVENIENCE**

Compliance with the provisions of this section does not relieve you of your responsibility for public safety.

Construction activities must not inconvenience the public or abutting property owners. Schedule and conduct work to avoid unnecessary inconvenience to the public and abutting property owners. Avoid undue delay in construction activities to reduce the public's exposure to construction.

Where possible, route traffic on new or existing paved surfaces.

Maintain convenient access to driveways, houses, and buildings. When the abutting property owner's access across the right of way line is to be eliminated or replaced under the contract, the existing access must not be closed until the replacement access facilities are usable. Construct temporary approaches to crossings and intersecting highways.

Provide a reasonably smooth and even surface for use by traffic at all time during excavation of roadways and construction of embankments. Before other grading activities, place fill at culverts and bridges to allow traffic to cross. If ordered, excavate roadway cuts in layers and construct embankments in partial widths at a time alternating construction from one side to the other and routing traffic over the side opposite the one under construction. Install or construct culverts on only 1/2 the width of the traveled way at a time; keep the traveled way portion being used by traffic open and unobstructed until the opposite side of the traveled way is ready for use by traffic.

Upon completion of rough grading or placing any subsequent layer, bring the surface of the roadbed to a smooth and even condition, free of humps and depressions and satisfactory for the use of the public.

After subgrade preparation for a specified layer of material has been completed, repair any damage to the roadbed or completed subgrade, including damage due to use by the public.

While subgrade and paving activities are underway, allow the public to use the shoulders. If half-width paving methods are used, allow the public to use the side of the roadbed opposite the one under construction. If enough width is available, keep open a passageway wide enough to accommodate at least 2 lanes of traffic at locations where subgrade and paving activities are underway. Shape shoulders or reshape subgrade as necessary to accommodate traffic during subgrade preparation and paving activities.

Apply water or dust palliative for the prevention or alleviation of dust nuisance.

Install signs, lights, flares, temporary railing (Type K), barricades and other facilities to direct traffic. Furnish flaggers whenever necessary to direct the movement of the public through or around the work.

You will be required to pay the cost of replacing or repairing all facilities installed under extra work for the convenience or direction or warning of the public which are lost while in your custody, or are damaged by your operations to such an extent as to require replacement or repair.

The Engineer may order or consent to your request to open a completed section of surfacing, pavement, or structure roadway surface for public use. You will not be compensated for any delay to your construction activities caused by the public. This does not relieve you from any other contractual responsibility.

**Replace Section 7-1.09 with:**

**7-1.09 PUBLIC SAFETY**

You are responsible to provide for public safety.

Do not construct a temporary facility that interferes with the safe passage of traffic.

Control dust resulting from the work, inside and outside the right-of-way.

Move workers, equipment, and materials without endangering traffic.

Whenever your operations create a condition hazardous to the public, furnish, erect and maintain those fences, temporary railing, barricades, lights, signs, and other devices and take any other necessary protective measures to prevent damage or injury to the public.

Any fences, temporary railing, barricades, lights, signs, or other devices furnished, erected and maintained by you are in addition to those for which payment is provided elsewhere in the specifications.

Provide flaggers whenever necessary to ensure that the public is given safe guidance through the work zone. Except as ordered, at locations where traffic is being routed through construction under one-way controls, move your equipment in compliance with the one-way controls.

Use of signs, lights, flags, or other protective devices must conform with the California MUTCD and as ordered. Signs, lights, flags or other protective devices must not obscure the visibility of, nor conflict in intent, meaning and function of either existing signs, lights and traffic control devices or any construction area signs or traffic control devices.

Keep existing traffic signals and highway lighting in operation. Other entities perform routine maintenance of these facilities during the work.

Cover signs that direct traffic to a closed area. Providing, maintaining, and removing the covers on construction area signs is paid as extra work under Section 4-1.03, "Extra Work."

Install temporary illumination in a manner which the illumination and the illumination equipment does not interfere with public safety. The installation of general roadway illumination does not relieve you from furnishing and maintaining any protective devices.

Equipment must enter and leave the highway via existing ramps and crossovers and must move in the direction of public traffic. All movements of workmen and construction equipment on or across lanes open to public traffic must be performed in a manner that will not endanger the public. Your vehicles or other mobile equipment leaving an open traffic lane to enter the construction area, must slow down gradually in advance of the location of the turnoff to give traffic following an opportunity to slow down. When leaving a work area and entering a roadway carrying public traffic, your vehicles and equipment must yield to public traffic.

Immediately remove hauling spillage from roadway lanes or shoulders open to traffic. When hauling on roadways, trim loads and remove material from shelf areas to minimize spillage.

Notify the Engineer not less than 20 days and not more than 90 days before the anticipated start of an activity that will change the vertical or horizontal clearance available to public traffic, including shoulders.

If vertical clearance is temporarily reduced to 15.5 feet or less, place low clearance warning signs in accordance with the California MUTCD and as ordered. Signs must comply with the dimensions, color, and legend requirements of the California MUTCD and these specifications except that the signs must have black letters and numbers on an orange retroreflective background. W12-2P signs must be illuminated so that the signs are clearly visible.

Pave or provide full width continuous and cleared wood walks for pedestrian openings through falsework. Protect pedestrians from falling objects and curing water for concrete. Extend overhead protection for pedestrians not less than 4 feet beyond the edge of the bridge deck. Illuminate all pedestrian openings through falsework. Temporary pedestrian facilities must comply with the American with Disabilities Act of 1990 (ADA).

Do not store vehicles, material, or equipment in a way that:

1. Creates a hazard to the public
2. Obstructs traffic control devices

Do not install or place temporary facilities used to perform the work which interfere with the free and safe passage of public traffic.

If you appear to be neglectful or negligent in furnishing warning devices and taking protective measures, the Engineer may direct your attention to the existence of a hazard and the necessary warning devices must be furnished and installed and protective measures taken by you. If the Engineer points out the inadequacy of warning devices and protective measures, that action on the part of the Engineer does not relieve you from your responsibility for public safety or abrogate the obligation to furnish and pay for these devices and measures.

Install temporary railing (Type K) or other approved protection system under the following conditions:

1. Excavations: Where the near edge of the excavation is within 15 feet from the edge of an open traffic lane
2. Temporarily Unprotected Permanent Obstacles: When the work includes the installation of a fixed obstacle together with a protective system, such as a sign structure together with protective railing, and you elect to install the obstacle before installing the protective system; or you, for your convenience and as authorized, remove a portion of an existing protective railing at an obstacle and do not replace such railing completely the same day
3. Storage Areas: When material or equipment is stored within 15 feet of the edge of an open traffic lane and the storage is not otherwise prohibited by the provisions of these Standard Specifications and the special provisions
4. Height Differentials: When construction operations create a height differential greater than 0.15 feet within 15 feet of the edge of traffic lane

Temporary railing (Type K) does not need to be installed where excavations within 15 feet from edge of an open traffic lane are:

1. Covered with steel plates or concrete covers of adequate thickness to prevent accidental entry by traffic or the public
2. In side slopes, where the downhill slope is 4:1 (horizontal:vertical) or less unless a naturally occurring condition
3. Protected by existing barrier or railing

Offset the approach end of temporary railing (Type K) a minimum of 15 feet from the edge of an open traffic lane. Install the temporary railing on a skew toward the edge of the traffic lane of not more than one foot transversely to 10 feet longitudinally with respect to the edge of the traffic lane. If the 15-foot minimum offset cannot be achieved, the temporary railing must be installed on the 10 to 1 skew to obtain the maximum available offset between the approach end of the railing and the edge of the traffic lane, and an array of temporary crash cushion modules must be installed at the approach end of the temporary railing.

Secure in place temporary railing (Type K) before starting work for which the temporary railing is required.

Where 2 or more lanes in the same direction are adjacent to the area where the work is being performed, including shoulders, and unless a barrier is present, the adjacent lane must be closed under any of the following conditions:

1. Work is within 6 feet of the edge of traveled way and approach speed is greater than 45 miles per hour
2. Work is within 3 feet of the edge of traveled way and approach speed is less than 45 mile per hour

Do not reduce an open traffic lane width to less than 10 feet. When traffic cones or delineators are used for temporary edge delineation, the line of cones or delineators is considered the edge of the traveled way.

If a traffic lane is closed with channelizers for excavation work, move the devices to the adjacent edge of the traveled way when not excavating. Space the devices the same as specified for the lane closure.

Do not move or temporarily suspend anything over a traffic lane open to the public unless the public is protected.

**Replace Section 7-1.11 with:**

**7-1.11 PRESERVATION OF PROPERTY**

Comply with Section 5-1.18, "Property and Facility Preservation."

**Replace Section 7-1.12 with:**

**7-1.12 INDEMNIFICATION AND INSURANCE**

The Contractor's obligations regarding indemnification of the State of California and the requirements for insurance shall conform to the provisions in Section 3-1.05, "Insurance Policies," and Sections 7-1.12A, "Indemnification," and 7-1.12B, "Insurance," of this Section 7-1.12.

### 7-1.12A Indemnification

The Contractor shall defend, indemnify, and save harmless the State, including its officers, employees, and agents (excluding agents who are design professionals) from any and all claims, demands, causes of action, damages, costs, expenses, actual attorneys' fees, losses or liabilities, in law or in equity (Section 7-1.12A Claims) arising out of or in connection with the Contractor's performance of this contract for:

1. Bodily injury including, but not limited to, bodily injury, sickness or disease, emotional injury or death to persons, including, but not limited to, the public, any employees or agents of the Contractor, the State, or any other contractor; and
2. Damage to property of anyone including loss of use thereof; caused or alleged to be caused in whole or in part by any negligent or otherwise legally actionable act or omission of the Contractor or anyone directly or indirectly employed by the Contractor or anyone for whose acts the Contractor may be liable.

Except as otherwise provided by law, these requirements apply regardless of the existence or degree of fault of the State. The Contractor is not obligated to indemnify the State for Claims arising from conduct delineated in Civil Code Section 2782 and to Claims arising from any defective or substandard condition of the highway that existed at or before the start of work, unless this condition has been changed by the work or the scope of the work requires the Contractor to maintain existing highway facilities and the Claim arises from the Contractor's failure to maintain. The Contractor's defense and indemnity obligation shall extend to Claims arising after the work is completed and accepted if the Claims are directly related to alleged acts or omissions by the Contractor that occurred during the course of the work. State inspection is not a waiver of full compliance with these requirements.

The Contractor's obligation to defend and indemnify shall not be excused because of the Contractor's inability to evaluate liability or because the Contractor evaluates liability and determine that the Contractor is not liable. The Contractor shall respond within 30 days to the tender of any Claim for defense and indemnity by the State, unless this time has been extended by the State. If the Contractor fails to accept or reject a tender of defense and indemnity within 30 days, in addition to any other remedy authorized by law, the Department may withhold such funds the State reasonably considers necessary for its defense and indemnity until disposition has been made of the Claim or until the Contractor accepts or rejects the tender of defense, whichever occurs first.

With respect to third-party claims against the Contractor, the Contractor waives all rights of any type to express or implied indemnity against the State, its officers, employees, or agents (excluding agents who are design professionals).

Nothing in the Contract is intended to establish a standard of care owed to any member of the public or to extend to the public the status of a third-party beneficiary for any of these indemnification specifications.

### 7-1.12B Insurance

#### 7-1.12B(1) General

Nothing in the contract is intended to establish a standard of care owed to any member of the public or to extend to the public the status of a third-party beneficiary for any of these insurance specifications.

#### 7-1.12B(2) Casualty Insurance

The Contractor shall procure and maintain insurance on all of its operations with companies acceptable to the State as follows:

1. The Contractor shall keep all insurance in full force and effect from the beginning of the work through contract acceptance.
2. All insurance shall be with an insurance company with a rating from A.M. Best Financial Strength Rating of A- or better and a Financial Size Category of VII or better.
3. The Contractor shall maintain completed operations coverage with a carrier acceptable to the State through the expiration of the patent deficiency in construction statute of repose set forth in Code of Civil Procedure Section 337.1.

#### 7-1.12B(3) Workers' Compensation and Employer's Liability Insurance

In accordance with Labor Code Section 1860, the Contractor shall secure the payment of worker's compensation in accordance with Labor Code Section 3700.

In accordance with Labor Code Section 1861, the Contractor shall submit to the Department the following certification before performing the work:

I am aware of the provisions of Section 3700 of the Labor Code which require every employer to be insured against liability for workers' compensation or to undertake self-insurance in accordance with the provisions of that code, and I will comply with such provisions before commencing the performance of the work of this contract.

Contract execution constitutes certification submittal.
The Contractor shall provide Employer's Liability Insurance in amounts not less than:

1. $1,000,000 for each accident for bodily injury by accident
2. $1,000,000 policy limit for bodily injury by disease
3. $1,000,000 for each employee for bodily injury by disease

If there is an exposure of injury to the Contractor's employees under the U.S. Longshoremen's and Harbor Workers' Compensation Act, the Jones Act, or under laws, regulations, or statutes applicable to maritime employees, coverage shall be included for such injuries or claims.

**7-1.12B(4) Liability Insurance**

**7-1.12B(4)(a) General**

The Contractor shall carry General Liability and Umbrella or Excess Liability Insurance covering all operations by or on behalf of the Contractor providing insurance for bodily injury liability and property damage liability for the following limits and including coverage for:

1. Premises, operations, and mobile equipment
2. Products and completed operations
3. Broad form property damage (including completed operations)
4. Explosion, collapse, and underground hazards
5. Personal injury
6. Contractual liability

**7-1.12B(4)(b) Liability Limits/Additional Insureds**

The limits of liability shall be at least the amounts shown in the following table:

| Total Bid | For Each Occurrence[1] | Aggregate for Products/Completed Operation | General Aggregate[2] | Umbrella or Excess Liability[3] |
|---|---|---|---|---|
| ≤$1,000,000 | $1,000,000 | $2,000,000 | $2,000,000 | $5,000,000 |
| >$1,000,000 ≤$5,000,000 | $1,000,000 | $2,000,000 | $2,000,000 | $10,000,000 |
| >$5,000,000 ≤$25,000,000 | $2,000,000 | $2,000,000 | $4,000,000 | $15,000,000 |
| >$25,000,000 | $2,000,000 | $2,000,000 | $4,000,000 | $25,000,000 |

1. Combined single limit for bodily injury and property damage.
2. This limit shall apply separately to the Contractor's work under this contract.
3. The umbrella or excess policy shall contain a clause stating that it takes effect (drops down) in the event the primary limits are impaired or exhausted.

The Contractor shall not require certified Small Business subcontractors to carry Liability Insurance that exceeds the limits in the table above. Notwithstanding the limits specified herein, at the option of the Contractor, the liability insurance limits for certified Small Business subcontractors of any tier may be less than those limits specified in the table. For Small Business subcontracts, "Total Bid" shall be interpreted as the amount of subcontracted work to a certified Small Business.

The State, including its officers, directors, agents (excluding agents who are design professionals), and employees, shall be named as additional insureds under the General Liability and Umbrella Liability Policies with respect to liability arising out of or connected with work or operations performed by or on behalf of the Contractor under this contract. Coverage for such additional insureds does not extend to liability:

1. Arising from any defective or substandard condition of the roadway which existed at or before the time the Contractor started work, unless such condition has been changed by the work or the scope of the work requires the Contractor to maintain existing roadway facilities and the claim arises from the Contractor's failure to maintain;

2. For claims occurring after the work is completed and accepted unless these claims are directly related to alleged acts or omissions of the Contractor that occurred during the course of the work; or
3. To the extent prohibited by Insurance Code Section 11580.04

Additional insured coverage shall be provided by a policy provision or by an endorsement providing coverage at least as broad as Additional Insured (Form B) endorsement form CG 2010, as published by the Insurance Services Office (ISO), or other form designated by the Department.

**7-1.12B(4)(c) Contractor's Insurance Policy is Primary**

The policy shall stipulate that the insurance afforded the additional insureds applies as primary insurance. Any other insurance or self-insurance maintained by the State is excess only and shall not be called upon to contribute with this insurance.

**7-1.12B(5) Automobile Liability Insurance**

The Contractor shall carry automobile liability insurance, including coverage for all owned, hired, and nonowned automobiles. The primary limits of liability shall be not less than $1,000,000 combined single limit each accident for bodily injury and property damage. The umbrella or excess liability coverage required under Section 7-1.12B(4)(b) also applies to automobile liability.

**7-1.12B(6) Policy Forms, Endorsements, and Certificates**

The Contractor shall provide its General Liability Insurance under Commercial General Liability policy form No. CG0001 as published by the Insurance Services Office (ISO) or under a policy form at least as broad as policy form No. CG0001.

**7-1.12B(7) Deductibles**

The State may expressly allow deductible clauses, which it does not consider excessive, overly broad, or harmful to the interests of the State. Regardless of the allowance of exclusions or deductions by the State, the Contractor is responsible for any deductible amount and shall warrant that the coverage provided to the State is in accordance with Section 7-1.12B, "Insurance."

**7-1.12B(8) Enforcement**

The Department may assure the Contractor's compliance with its insurance obligations. Ten days before an insurance policy lapses or is canceled during the contract period, the Contractor shall submit to the Department evidence of renewal or replacement of the policy.

If the Contractor fails to maintain any required insurance coverage, the Department may maintain this coverage and withhold or charge the expense to the Contractor or terminate the Contractor's control of the work in accordance with Section 8-1.08, "Termination of Control."

The Contractor is not relieved of its duties and responsibilities to indemnify, defend, and hold harmless the State, its officers, agents, and employees by the Department's acceptance of insurance policies and certificates.

Minimum insurance coverage amounts do not relieve the Contractor for liability in excess of such coverage, nor do they preclude the State from taking other actions available to it, including the withholding of funds under this contract.

**7-1.12B(9) Self-Insurance**

Self-insurance programs and self-insured retentions in insurance policies are subject to separate annual review and approval by the State.

If the Contractor uses a self-insurance program or self-insured retention, the Contractor shall provide the State with the same protection from liability and defense of suits as would be afforded by first-dollar insurance. Execution of the contract is the Contractor's acknowledgement that the Contractor will be bound by all laws as if the Contractor were an insurer as defined under Insurance Code Section 23 and that the self-insurance program or self-insured retention shall operate as insurance as defined under Insurance Code Section 22.

**Replace Section 7-1.125 with:**

**7-1.125 Legal Actions Against the Department**

If legal action is brought against the Department over compliance with a State or Federal law, rule, or regulation applicable to highway work, then:

1. If the Department, in complying with a court order, prohibits you from performing work, the resulting delay is a suspension related to your performance, unless the Department terminates the contract.
2. If a court order other than an order to show cause or the final judgment in the action prohibits the Department from requiring you to perform work, the Department may delete the prohibited work or terminate the contract.

**In Section 7-1.13 delete the 5th and 6th paragraphs.**

**Add:**

## 7-1.50 FEDERAL LAWS FOR FEDERAL-AID CONTRACTS

### 7-1.50A General

Section 7-1.50, "Federal Laws for Federal-Aid Contracts," includes specifications required in a Federal-aid construction contract and applies to a Federal-aid contract.

Form FHWA-1273 is included in the contract in Section 7-1.50B, "FHWA-1273." Some contract terms on the form are different than those used in other contract parts as shown in the following table:

**FHWA-1273 Terms and Department Equivalencies**

| FHWA-1273 Term | Equivalent Term Used in Other Contract Parts |
|---|---|
| SHA | Department |
| SHA contracting officer | Engineer |
| SHA resident engineer | Engineer |

### 7-1.50B FHWA-1273

FHWA-1273 Electronic version -- March 10, 1994
with revised Section VI

**REQUIRED CONTRACT PROVISIONS FEDERAL-AID CONSTRUCTION CONTRACTS**

I. General
II. Nondiscrimination
III. Nonsegregated Facilities
IV. Payment of Predetermined Minimum Wage
V. Statements and Payrolls
VI. Record of Materials, Supplies, and Labor
VII. Subletting or Assigning the Contract
VIII. Safety: Accident Prevention
IX. False Statements Concerning Highway Projects
X. Implementation of Clean Air Act and Federal Water Pollution Control Act
XI. Certification Regarding Debarment, Suspension, Ineligibility, and Voluntary Exclusion
XII. Certification Regarding Use of Contract Funds for Lobbying

**ATTACHMENTS**

A. Employment Preference for Appalachian Contracts (included in Appalachian contracts only)

**I. GENERAL**

1. These contract provisions shall apply to all work performed on the contract by the contractor's own organization and with the assistance of workers under the contractor's immediate superintendence and to all work performed on the contract by piecework, station work, or by subcontract.
2. Except as otherwise provided for in each section, the contractor shall insert in each subcontract all of the stipulations contained in these Required Contract Provisions, and further require their inclusion in any lower tier subcontract or purchase order that may in turn be made. The Required Contract Provisions shall not be incorporated by reference in any case. The prime contractor shall be responsible for compliance by any subcontractor or lower tier subcontractor with these Required Contract Provisions.
3. A breach of any of the stipulations contained in these Required Contract Provisions shall be sufficient grounds for termination of the contract.

4. A breach of the following clauses of the Required Contract Provisions may also be grounds for debarment as provided in 29 CFR 5.12:

   Section I, paragraph 2;
   Section IV, paragraphs 1, 2, 3, 4, and 7;
   Section V, paragraphs 1 and 2a through 2g.

5. Disputes arising out of the labor standards provisions of Section IV (except paragraph 5) and Section V of these Required Contract Provisions shall not be subject to the general disputes clause of this contract. Such disputes shall be resolved in accordance with the procedures of the U.S. Department of Labor (DOL) as set forth in 29 CFR 5, 6, and 7. Disputes within the meaning of this clause include disputes between the contractor (or any of its subcontractors) and the contracting agency, the DOL, or the contractor's employees or their representatives.
6. **Selection of Labor:** During the performance of this contract, the contractor shall not:

   a. discriminate against labor from any other State, possession, or territory of the United States (except for employment preference for Appalachian contracts, when applicable, as specified in Attachment A), or
   b. employ convict labor for any purpose within the limits of the project unless it is labor performed by convicts who are on parole, supervised release, or probation.

## II. NONDISCRIMINATION

(Applicable to all Federal-aid construction contracts and to all related subcontracts of $10,000 or more.)

1. **Equal Employment Opportunity:** Equal employment opportunity (EEO) requirements not to discriminate and to take affirmative action to assure equal opportunity as set forth under laws, executive orders, rules, regulations (28 CFR 35, 29 CFR 1630 and 41 CFR 60) and orders of the Secretary of Labor as modified by the provisions prescribed herein, and imposed pursuant to 23 U.S.C. 140 shall constitute the EEO and specific affirmative action standards for the contractor's project activities under this contract. The Equal Opportunity Construction Contract Specifications set forth under 41 CFR 60-4.3 and the provisions of the American Disabilities Act of 1990 (42 U.S.C. 12101 *et seq*.) set forth under 28 CFR 35 and 29 CFR 1630 are incorporated by reference in this contract. In the execution of this contract, the contractor agrees to comply with the following minimum specific requirement activities of EEO:

   a. The contractor will work with the State highway agency (SHA) and the Federal Government in carrying out EEO obligations and in their review of his/her activities under the contract.
   b. The contractor will accept as his operating policy the following statement:

      "It is the policy of this Company to assure that applicants are employed, and that employees are treated during employment, without regard to their race, religion, sex, color, national origin, age or disability. Such action shall include: employment, upgrading, demotion, or transfer; recruitment or recruitment advertising; layoff or termination; rates of pay or other forms of compensation; and selection for training, including apprenticeship, preapprenticeship, and/or on-the-job training."

2. **EEO Officer:** The contractor will designate and make known to the SHA contracting officers an EEO Officer who will have the responsibility for and must be capable of effectively administering and promoting an active contractor program of EEO and who must be assigned adequate authority and responsibility to do so.
3. **Dissemination of Policy:** All members of the contractor's staff who are authorized to hire, supervise, promote, and discharge employees, or who recommend such action, or who are substantially involved in such action, will be made fully cognizant of, and will implement, the contractor's EEO policy and contractual responsibilities to provide EEO in each grade and classification of employment. To ensure that the above agreement will be met, the following actions will be taken as a minimum:

   a. Periodic meetings of supervisory and personnel office employees will be conducted before the start of work and then not less often than once every six months, at which time the contractor's EEO policy and its implementation will be reviewed and explained. The meetings will be conducted by the EEO Officer.
   b. All new supervisory or personnel office employees will be given a thorough indoctrination by the EEO Officer, covering all major aspects of the contractor's EEO obligations within thirty days following their reporting for duty with the contractor.
   c. All personnel who are engaged in direct recruitment for the project will be instructed by the EEO Officer in the contractor's procedures for locating and hiring minority group employees.

d. Notices and posters setting forth the contractor's EEO policy will be placed in areas readily accessible to employees, applicants for employment and potential employees.
e. The contractor's EEO policy and the procedures to implement such policy will be brought to the attention of employees by means of meetings, employee handbooks, or other appropriate means.

4. **Recruitment:** When advertising for employees, the contractor will include in all advertisements for employees the notation: "An Equal Opportunity Employer." All such advertisements will be placed in publications having a large circulation among minority groups in the area from which the project work force would normally be derived.

   a. The contractor will, unless precluded by a valid bargaining agreement, conduct systematic and direct recruitment through public and private employee referral sources likely to yield qualified minority group applicants. To meet this requirement, the contractor will identify sources of potential minority group employees, and establish with such identified sources procedures whereby minority group applicants may be referred to the contractor for employment consideration.
   b. In the event the contractor has a valid bargaining agreement providing for exclusive hiring hall referrals, he is expected to observe the provisions of that agreement to the extent that the system permits the contractor's compliance with EEO contract provisions. (The DOL has held that where implementation of such agreements have the effect of discriminating against minorities or women, or obligates the contractor to do the same, such implementation violates Executive Order 11246, as amended.)
   c. The contractor will encourage his present employees to refer minority group applicants for employment. Information and procedures with regard to referring minority group applicants will be discussed with employees.

5. **Personnel Actions:** Wages, working conditions, and employee benefits shall be established and administered, and personnel actions of every type, including hiring, upgrading, promotion, transfer, demotion, layoff, and termination, shall be taken without regard to race, color, religion, sex, national origin, age or disability. The following procedures shall be followed:

   a. The contractor will conduct periodic inspections of project sites to insure that working conditions and employee facilities do not indicate discriminatory treatment of project site personnel.
   b. The contractor will periodically evaluate the spread of wages paid within each classification to determine any evidence of discriminatory wage practices.
   c. The contractor will periodically review selected personnel actions in depth to determine whether there is evidence of discrimination. Where evidence is found, the contractor will promptly take corrective action. If the review indicates that the discrimination may extend beyond the actions reviewed, such corrective action shall include all affected persons.
   d. The contractor will promptly investigate all complaints of alleged discrimination made to the contractor in connection with his obligations under this contract, will attempt to resolve such complaints, and will take appropriate corrective action within a reasonable time. If the investigation indicates that the discrimination may affect persons other than the complainant, such corrective action shall include such other persons. Upon completion of each investigation, the contractor will inform every complainant of all of his avenues of appeal.

6. **Training and Promotion:**

   a. The contractor will assist in locating, qualifying, and increasing the skills of minority group and women employees, and applicants for employment.
   b. Consistent with the contractor's work force requirements and as permissible under Federal and State regulations, the contractor shall make full use of training programs, i.e., apprenticeship, and on-the-job training programs for the geographical area of contract performance. Where feasible, 25 percent of apprentices or trainees in each occupation shall be in their first year of apprenticeship or training. In the event a special provision for training is provided under this contract, this subparagraph will be superseded as indicated in the special provision.
   c. The contractor will advise employees and applicants for employment of available training programs and entrance requirements for each.
   d. The contractor will periodically review the training and promotion potential of minority group and women employees and will encourage eligible employees to apply for such training and promotion.

7. **Unions**: If the contractor relies in whole or in part upon unions as a source of employees, the contractor will use his/her best efforts to obtain the cooperation of such unions to increase opportunities for minority groups and women within the unions, and to effect referrals by such unions of minority and female employees. Actions by the contractor either directly or through a contractor's association acting as agent will include the procedures set forth below:

   a. The contractor will use best efforts to develop, in cooperation with the unions, joint training programs aimed toward qualifying more minority group members and women for membership in the unions and increasing the skills of minority group employees and women so that they may qualify for higher paying employment.
   b. The contractor will use best efforts to incorporate an EEO clause into each union agreement to the end that such union will be contractually bound to refer applicants without regard to their race, color, religion, sex, national origin, age or disability.
   c. The contractor is to obtain information as to the referral practices and policies of the labor union except that to the extent such information is within the exclusive possession of the labor union and such labor union refuses to furnish such information to the contractor, the contractor shall so certify to the SHA and shall set forth what efforts have been made to obtain such information.
   d. In the event the union is unable to provide the contractor with a reasonable flow of minority and women referrals within the time limit set forth in the collective bargaining agreement, the contractor will, through independent recruitment efforts, fill the employment vacancies without regard to race, color, religion, sex, national origin, age or disability; making full efforts to obtain qualified and/or qualifiable minority group persons and women. (The DOL has held that it shall be no excuse that the union with which the contractor has a collective bargaining agreement providing for exclusive referral failed to refer minority employees.) In the event the union referral practice prevents the contractor from meeting the obligations pursuant to Executive Order 11246, as amended, and these specifications, such contractor shall immediately notify the SHA.

8. **Selection of Subcontractors, Procurement of Materials and Leasing of Equipment:** The contractor shall not discriminate on the grounds of race, color, religion, sex, national origin, age or disability in the selection and retention of subcontractors, including procurement of materials and leases of equipment.

   a. The contractor shall notify all potential subcontractors and suppliers of his/her EEO obligations under this contract.
   b. Disadvantaged business enterprises (DBE), as defined in 49 CFR 23, shall have equal opportunity to compete for and perform subcontracts which the contractor enters into pursuant to this contract. The contractor will use his best efforts to solicit bids from and to utilize DBE subcontractors or subcontractors with meaningful minority group and female representation among their employees. Contractors shall obtain lists of DBE construction firms from SHA personnel.
   c. The contractor will use his best efforts to ensure subcontractor compliance with their EEO obligations.

9. **Records and Reports:** The contractor shall keep such records as necessary to document compliance with the EEO requirements. Such records shall be retained for a period of three years following completion of the contract work and shall be available at reasonable times and places for inspection by authorized representatives of the SHA and the FHWA.

   a. The records kept by the contractor shall document the following:

      1. The number of minority and non-minority group members and women employed in each work classification on the project;
      2. The progress and efforts being made in cooperation with unions, when applicable, to increase employment opportunities for minorities and women;
      3. The progress and efforts being made in locating, hiring, training, qualifying, and upgrading minority and female employees; and
      4. The progress and efforts being made in securing the services of DBE subcontractors or subcontractors with meaningful minority and female representation among their employees.

   b. The contractors will submit an annual report to the SHA each July for the duration of the project, indicating the number of minority, women, and non-minority group employees currently engaged in each work classification required by the contract work. This information is to be reported on Form FHWA-1391. If on-the-job training is being required by special provision, the contractor will be required to collect and report training data.

## III. NONSEGREGATED FACILITIES

(Applicable to all Federal-aid construction contracts and to all related subcontracts of $10,000 or more.)

a. By submission of this bid, the execution of this contract or subcontract, or the consummation of this material supply agreement or purchase order, as appropriate, the bidder, Federal-aid construction contractor, subcontractor, material supplier, or vendor, as appropriate, certifies that the firm does not maintain or provide for its employees any segregated facilities at any of its establishments, and that the firm does not permit its employees to perform their services at any location, under its control, where segregated facilities are maintained. The firm agrees that a breach of this certification is a violation of the EEO provisions of this contract. The firm further certifies that no employee will be denied access to adequate facilities on the basis of sex or disability.

b. As used in this certification, the term "segregated facilities" means any waiting rooms, work areas, restrooms and washrooms, restaurants and other eating areas, timeclocks, locker rooms, and other storage or dressing areas, parking lots, drinking fountains, recreation or entertainment areas, transportation, and housing facilities provided for employees which are segregated by explicit directive, or are, in fact, segregated on the basis of race, color, religion, national origin, age or disability, because of habit, local custom, or otherwise. The only exception will be for the disabled when the demands for accessibility override (e.g. disabled parking).

c. The contractor agrees that it has obtained or will obtain identical certification from proposed subcontractors or material suppliers prior to award of subcontracts or consummation of material supply agreements of $10,000 or more and that it will retain such certifications in its files.

## IV. PAYMENT OF PREDETERMINED MINIMUM WAGE

(Applicable to all Federal-aid construction contracts exceeding $2,000 and to all related subcontracts, except for projects located on roadways classified as local roads or rural minor collectors, which are exempt.)

1. **General:**

   a. All mechanics and laborers employed or working upon the site of the work will be paid unconditionally and not less often than once a week and without subsequent deduction or rebate on any account [except such payroll deductions as are permitted by regulations (29 CFR 3) issued by the Secretary of Labor under the Copeland Act (40 U.S.C. 276c)] the full amounts of wages and bona fide fringe benefits (or cash equivalents thereof) due at time of payment. The payment shall be computed at wage rates not less than those contained in the wage determination of the Secretary of Labor (hereinafter "the wage determination") which is attached hereto and made a part hereof, regardless of any contractual relationship which may be alleged to exist between the contractor or its subcontractors and such laborers and mechanics. The wage determination (including any additional classifications and wage rates conformed under paragraph 2 of this Section IV and the DOL poster (WH-1321) or Form FHWA-1495) shall be posted at all times by the contractor and its subcontractors at the site of the work in a prominent and accessible place where it can be easily seen by the workers. For the purpose of this Section, contributions made or costs reasonably anticipated for bona fide fringe benefits under Section 1(b)(2) of the Davis- Bacon Act (40 U.S.C. 276a) on behalf of laborers or mechanics are considered wages paid to such laborers or mechanics, subject to the provisions of Section IV, paragraph 3b, hereof. Also, for the purpose of this Section, regular contributions made or costs incurred for more than a weekly period (but not less often than quarterly) under plans, funds, or programs, which cover the particular weekly period, are deemed to be constructively made or incurred during such weekly period. Such laborers and mechanics shall be paid the appropriate wage rate and fringe benefits on the wage determination for the classification of work actually performed, without regard to skill, except as provided in paragraphs 4 and 5 of this Section IV.

   b. Laborers or mechanics performing work in more than one classification may be compensated at the rate specified for each classification for the time actually worked therein, provided, that the employer's payroll records accurately set forth the time spent in each classification in which work is performed.

   c. All rulings and interpretations of the Davis-Bacon Act and related acts contained in 29 CFR 1, 3, and 5 are herein incorporated by reference in this contract.

2. **Classification:**

   a. The SHA contracting officer shall require that any class of laborers or mechanics employed under the contract, which is not listed in the wage determination, shall be classified in conformance with the wage determination.

   b. The contracting officer shall approve an additional classification, wage rate and fringe benefits only when the following criteria have been met:

1. the work to be performed by the additional classification requested is not performed by a classification in the wage determination;
2. the additional classification is utilized in the area by the construction industry;
3. the proposed wage rate, including any bona fide fringe benefits, bears a reasonable relationship to the wage rates contained in the wage determination; and
4. with respect to helpers, when such a classification prevails in the area in which the work is performed.

c. If the contractor or subcontractors, as appropriate, the laborers and mechanics (if known) to be employed in the additional classification or their representatives, and the contracting officer agree on the classification and wage rate (including the amount designated for fringe benefits where appropriate), a report of the action taken shall be sent by the contracting officer to the DOL, Administrator of the Wage and Hour Division, Employment Standards Administration, Washington, D.C. 20210. The Wage and Hour Administrator, or an authorized representative, will approve, modify, or disapprove every additional classification action within 30 days of receipt and so advise the contracting officer or will notify the contracting officer within the 30-day period that additional time is necessary.
d. In the event the contractor or subcontractors, as appropriate, the laborers or mechanics to be employed in the additional classification or their representatives, and the contracting officer do not agree on the proposed classification and wage rate (including the amount designated for fringe benefits, where appropriate), the contracting officer shall refer the questions, including the views of all interested parties and the recommendation of the contracting officer, to the Wage and Hour Administrator for determination. Said Administrator, or an authorized representative, will issue a determination within 30 days of receipt and so advise the contracting officer or will notify the contracting officer within the 30-day period that additional time is necessary.
e. The wage rate (including fringe benefits where appropriate) determined pursuant to paragraph 2c or 2d of this Section IV shall be paid to all workers performing work in the additional classification from the first day on which work is performed in the classification.

3. **Payment of Fringe Benefits:**

a. Whenever the minimum wage rate prescribed in the contract for a class of laborers or mechanics includes a fringe benefit which is not expressed as an hourly rate, the contractor or subcontractors, as appropriate, shall either pay the benefit as stated in the wage determination or shall pay another bona fide fringe benefit or an hourly case equivalent thereof.
b. If the contractor or subcontractor, as appropriate, does not make payments to a trustee or other third person, he/she may consider as a part of the wages of any laborer or mechanic the amount of any costs reasonably anticipated in providing bona fide fringe benefits under a plan or program, provided, that the Secretary of Labor has found, upon the written request of the contractor, that the applicable standards of the Davis-Bacon Act have been met. The Secretary of Labor may require the contractor to set aside in a separate account assets for the meeting of obligations under the plan or program.

4. **Apprentices and Trainees (Programs of the U.S. DOL) and Helpers:**

a. Apprentices:

1. Apprentices will be permitted to work at less than the predetermined rate for the work they performed when they are employed pursuant to and individually registered in a bona fide apprenticeship program registered with the DOL, Employment and Training Administration, Bureau of Apprenticeship and Training, or with a State apprenticeship agency recognized by the Bureau, or if a person is employed in his/her first 90 days of probationary employment as an apprentice in such an apprenticeship program, who is not individually registered in the program, but who has been certified by the Bureau of Apprenticeship and Training or a State apprenticeship agency (where appropriate) to be eligible for probationary employment as an apprentice.
2. The allowable ratio of apprentices to journeyman-level employees on the job site in any craft classification shall not be greater than the ratio permitted to the contractor as to the entire work force under the registered program. Any employee listed on a payroll at an apprentice wage rate, who is not registered or otherwise employed as stated above, shall be paid not less than the applicable wage rate listed in the wage determination for the classification of work actually performed. In addition, any apprentice performing work on the job site in excess of the ratio permitted under the registered program shall be paid not less than the applicable wage rate on the

wage determination for the work actually performed. Where a contractor or subcontractor is performing construction on a project in a locality other than that in which its program is registered, the ratios and wage rates (expressed in percentages of the journeyman-level hourly rate) specified in the contractor's or subcontractor's registered program shall be observed.

3. Every apprentice must be paid at not less than the rate specified in the registered program for the apprentice's level of progress, expressed as a percentage of the journeyman-level hourly rate specified in the applicable wage determination. Apprentices shall be paid fringe benefits in accordance with the provisions of the apprenticeship program. If the apprenticeship program does not specify fringe benefits, apprentices must be paid the full amount of fringe benefits listed on the wage determination for the applicable classification. If the Administrator for the Wage and Hour Division determines that a different practice prevails for the applicable apprentice classification, fringes shall be paid in accordance with that determination.
4. In the event the Bureau of Apprenticeship and Training, or a State apprenticeship agency recognized by the Bureau, withdraws approval of an apprenticeship program, the contractor or subcontractor will no longer be permitted to utilize apprentices at less than the applicable predetermined rate for the comparable work performed by regular employees until an acceptable program is approved.

b. Trainees:

1. Except as provided in 29 CFR 5.16, trainees will not be permitted to work at less than the predetermined rate for the work performed unless they are employed pursuant to and individually registered in a program which has received prior approval, evidenced by formal certification by the DOL, Employment and Training Administration.
2. The ratio of trainees to journeyman-level employees on the job site shall not be greater than permitted under the plan approved by the Employment and Training Administration. Any employee listed on the payroll at a trainee rate who is not registered and participating in a training plan approved by the Employment and Training Administration shall be paid not less than the applicable wage rate on the wage determination for the classification of work actually performed. In addition, any trainee performing work on the job site in excess of the ratio permitted under the registered program shall be paid not less than the applicable wage rate on the wage determination for the work actually performed.
3. Every trainee must be paid at not less than the rate specified in the approved program for his/her level of progress, expressed as a percentage of the journeyman-level hourly rate specified in the applicable wage determination. Trainees shall be paid fringe benefits in accordance with the provisions of the trainee program. If the trainee program does not mention fringe benefits, trainees shall be paid the full amount of fringe benefits listed on the wage determination unless the Administrator of the Wage and Hour Division determines that there is an apprenticeship program associated with the corresponding journeyman-level wage rate on the wage determination which provides for less than full fringe benefits for apprentices, in which case such trainees shall receive the same fringe benefits as apprentices.
4. In the event the Employment and Training Administration withdraws approval of a training program, the contractor or subcontractor will no longer be permitted to utilize trainees at less than the applicable predetermined rate for the work performed until an acceptable program is approved.

c. Helpers:

Helpers will be permitted to work on a project if the helper classification is specified and defined on the applicable wage determination or is approved pursuant to the conformance procedure set forth in Section IV.2. Any worker listed on a payroll at a helper wage rate, who is not a helper under an approved definition, shall be paid not less than the applicable wage rate on the wage determination for the classification of work actually performed.

5. **Apprentices and Trainees (Programs of the U.S. DOT):**

Apprentices and trainees working under apprenticeship and skill training programs which have been certified by the Secretary of Transportation as promoting EEO in connection with Federal-aid highway construction programs are not subject to the requirements of paragraph 4 of this Section IV. The straight time hourly wage rates for apprentices and trainees under such programs will be established by the particular programs. The ratio of apprentices and trainees to journeymen shall not be greater than permitted by the terms of the particular program.

6. **Withholding:**

The SHA shall upon its own action or upon written request of an authorized representative of the DOL withhold, or cause to be withheld, from the contractor or subcontractor under this contract or any other Federal contract with the same prime contractor, or any other Federally-assisted contract subject to Davis-Bacon prevailing wage requirements which is held by the same prime contractor, as much of the accrued payments or advances as may be considered necessary to pay laborers and mechanics, including apprentices, trainees, and helpers, employed by the contractor or any subcontractor the full amount of wages required by the contract. In the event of failure to pay any laborer or mechanic, including any apprentice, trainee, or helper, employed or working on the site of the work, all or part of the wages required by the contract, the SHA contracting officer may, after written notice to the contractor, take such action as may be necessary to cause the suspension of any further payment, advance, or guarantee of funds until such violations have ceased.

7. **Overtime Requirements:**

No contractor or subcontractor contracting for any part of the contract work which may require or involve the employment of laborers, mechanics, watchmen, or guards (including apprentices, trainees, and helpers described in paragraphs 4 and 5 above) shall require or permit any laborer, mechanic, watchman, or guard in any workweek in which he/she is employed on such work, to work in excess of 40 hours in such workweek unless such laborer, mechanic, watchman, or guard receives compensation at a rate not less than one-and-one-half times his/her basic rate of pay for all hours worked in excess of 40 hours in such workweek.

8. **Violation:**

Liability for Unpaid Wages; Liquidated Damages: In the event of any violation of the clause set forth in paragraph 7 above, the contractor and any subcontractor responsible thereof shall be liable to the affected employee for his/her unpaid wages. In addition, such contractor and subcontractor shall be liable to the United States (in the case of work done under contract for the District of Columbia or a territory, to such District or to such territory) for liquidated damages. Such liquidated damages shall be computed with respect to each individual laborer, mechanic, watchman, or guard employed in violation of the clause set forth in paragraph 7, in the sum of $10 for each calendar day on which such employee was required or permitted to work in excess of the standard work week of 40 hours without payment of the overtime wages required by the clause set forth in paragraph 7.

9. **Withholding for Unpaid Wages and Liquidated Damages:**

The SHA shall upon its own action or upon written request of any authorized representative of the DOL withhold, or cause to be withheld, from any monies payable on account of work performed by the contractor or subcontractor under any such contract or any other Federal contract with the same prime contractor, or any other Federally-assisted contract subject to the contract Work Hours and Safety Standards Act, which is held by the same prime contractor, such sums as may be determined to be necessary to satisfy any liabilities of such contractor or subcontractor for unpaid wages and liquidated damages as provided in the clause set forth in paragraph 8 above.

## V. STATEMENTS AND PAYROLLS

(Applicable to all Federal-aid construction contracts exceeding $2,000 and to all related subcontracts, except for projects located on roadways classified as local roads or rural collectors, which are exempt.)

1. **Compliance with Copeland Regulations (29 CFR 3):**

The contractor shall comply with the Copeland Regulations of the Secretary of Labor which are herein incorporated by reference.

2. **Payrolls and Payroll Records:**

a. Payrolls and basic records relating thereto shall be maintained by the contractor and each subcontractor during the course of the work and preserved for a period of 3 years from the date of completion of the contract for all laborers, mechanics, apprentices, trainees, watchmen, helpers, and guards working at the site of the work.

b. The payroll records shall contain the name, social security number, and address of each such employee; his or her correct classification; hourly rates of wages paid (including rates of contributions or costs anticipated for bona fide fringe benefits or cash equivalent thereof the types described in Section 1(b)(2)(B) of the Davis Bacon Act); daily and weekly number of hours worked; deductions made; and actual wages paid. In addition, for Appalachian contracts, the payroll records shall contain a notation indicating whether the employee does, or does not, normally reside in the labor area as defined in Attachment A, paragraph 1. Whenever the Secretary of Labor, pursuant to Section IV, paragraph 3b, has found that the wages of any laborer or mechanic include the amount of any costs reasonably anticipated in providing benefits under a plan or program described in Section 1(b)(2)(B) of the Davis Bacon Act, the contractor and each subcontractor shall maintain records which show that the commitment to provide such benefits is enforceable, that the plan or program is financially responsible,

that the plan or program has been communicated in writing to the laborers or mechanics affected, and show the cost anticipated or the actual cost incurred in providing benefits. Contractors or subcontractors employing apprentices or trainees under approved programs shall maintain written evidence of the registration of apprentices and trainees, and ratios and wage rates prescribed in the applicable programs.

c. Each contractor and subcontractor shall furnish, each week in which any contract work is performed, to the SHA resident engineer a payroll of wages paid each of its employees (including apprentices, trainees, and helpers, described in Section IV, paragraphs 4 and 5, and watchmen and guards engaged on work during the preceding weekly payroll period). The payroll submitted shall set out accurately and completely all of the information required to be maintained under paragraph 2b of this Section V. This information may be submitted in any form desired. Optional Form WH-347 is available for this purpose and may be purchased from the Superintendent of Documents (Federal stock number 029- 005-0014-1), U.S. Government Printing Office, Washington, D.C. 20402. The prime contractor is responsible for the submission of copies of payrolls by all subcontractors.

d. Each payroll submitted shall be accompanied by a "Statement of Compliance," signed by the contractor or subcontractor or his/her agent who pays or supervises the payment of the persons employed under the contract and shall certify the following:

    1. that the payroll for the payroll period contains the information required to be maintained under paragraph 2b of this Section V and that such information is correct and complete;
    2. that such laborer or mechanic (including each helper, apprentice, and trainee) employed on the contract during the payroll period has been paid the full weekly wages earned, without rebate, either directly or indirectly, and that no deductions have been made either directly or indirectly from the full wages earned, other than permissible deductions as set forth in the Regulations, 29 CFR 3;
    3. that each laborer or mechanic has been paid not less that the applicable wage rate and fringe benefits or cash equivalent for the classification of worked performed, as specified in the applicable wage determination incorporated into the contract.

e. The weekly submission of a properly executed certification set forth on the reverse side of Optional Form WH-347 shall satisfy the requirement for submission of the "Statement of Compliance" required by paragraph 2d of this Section V.

f. The falsification of any of the above certifications may subject the contractor to civil or criminal prosecution under 18 U.S.C. 1001 and 31 U.S.C. 231.

g. The contractor or subcontractor shall make the records required under paragraph 2b of this Section V available for inspection, copying, or transcription by authorized representatives of the SHA, the FHWA, or the DOL, and shall permit such representatives to interview employees during working hours on the job. If the contractor or subcontractor fails to submit the required records or to make them available, the SHA, the FHWA, the DOL, or all may, after written notice to the contractor, sponsor, applicant, or owner, take such actions as may be necessary to cause the suspension of any further payment, advance, or guarantee of funds. Furthermore, failure to submit the required records upon request or to make such records available may be grounds for debarment action pursuant to 29 CFR 5.12.

## VI. RECORD OF MATERIALS, SUPPLIES, AND LABOR

(As of May 22, 2007, Form FHWA-47 is no longer required.)

## VII. SUBLETTING OR ASSIGNING THE CONTRACT

1. The contractor shall perform with its own organization contract work amounting to not less than 30 percent (or a greater percentage if specified elsewhere in the contract) of the total original contract price, excluding any specialty items designated by the State. Specialty items may be performed by subcontract and the amount of any such specialty items performed may be deducted from the total original contract price before computing the amount of work required to be performed by the contractor's own organization (23 CFR 635).

    a. "Its own organization" shall be construed to include only workers employed and paid directly by the prime contractor and equipment owned or rented by the prime contractor, with or without operators. Such term does not include employees or equipment of a subcontractor, assignee, or agent of the prime contractor.

    b. "Specialty Items" shall be construed to be limited to work that requires highly specialized knowledge, abilities, or equipment not ordinarily available in the type of contracting organizations qualified and expected to bid on the contract as a whole and in general are to be limited to minor components of the overall contract.

2. The contract amount upon which the requirements set forth in paragraph 1 of Section VII is computed includes the cost of material and manufactured products which are to be purchased or produced by the contractor under the contract provisions.
3. The contractor shall furnish (a) a competent superintendent or supervisor who is employed by the firm, has full authority to direct performance of the work in accordance with the contract requirements, and is in charge of all construction operations (regardless of who performs the work) and (b) such other of its own organizational resources (supervision, management, and engineering services) as the SHA contracting officer determines is necessary to assure the performance of the contract.
4. No portion of the contract shall be sublet, assigned or otherwise disposed of except with the written consent of the SHA contracting officer, or authorized representative, and such consent when given shall not be construed to relieve the contractor of any responsibility for the fulfillment of the contract. Written consent will be given only after the SHA has assured that each subcontract is evidenced in writing and that it contains all pertinent provisions and requirements of the prime contract.

## VIII. SAFETY: ACCIDENT PREVENTION

1. In the performance of this contract the contractor shall comply with all applicable Federal, State, and local laws governing safety, health, and sanitation (23 CFR 635). The contractor shall provide all safeguards, safety devices and protective equipment and take any other needed actions as it determines, or as the SHA contracting officer may determine, to be reasonably necessary to protect the life and health of employees on the job and the safety of the public and to protect property in connection with the performance of the work covered by the contract.
2. It is a condition of this contract, and shall be made a condition of each subcontract, which the contractor enters into pursuant to this contract, that the contractor and any subcontractor shall not permit any employee, in performance of the contract, to work in surroundings or under conditions which are unsanitary, hazardous or dangerous to his/her health or safety, as determined under construction safety and health standards (29 CFR 1926) promulgated by the Secretary of Labor, in accordance with Section 107 of the Contract Work Hours and Safety Standards Act (40 U.S.C. 333).
3. Pursuant to 29 CFR 1926.3, it is a condition of this contract that the Secretary of Labor or authorized representative thereof, shall have right of entry to any site of contract performance to inspect or investigate the matter of compliance with the construction safety and health standards and to carry out the duties of the Secretary under Section 107 of the Contract Work Hours and Safety Standards Act (40 U.S.C. 333).

## IX. FALSE STATEMENTS CONCERNING HIGHWAY PROJECTS

In order to assure high quality and durable construction in conformity with approved plans and specifications and a high degree of reliability on statements and representations made by Engineers, contractors, suppliers, and workers on Federal-aid highway projects, it is essential that all persons concerned with the project perform their functions as carefully, thoroughly, and honestly as possible. Willful falsification, distortion, or misrepresentation with respect to any facts related to the project is a violation of Federal law. To prevent any misunderstanding regarding the seriousness of these and similar acts, the following notice shall be posted on each Federal-aid highway project (23 CFR 635) in one or more places where it is readily available to all persons concerned with the project:

### NOTICE TO ALL PERSONNEL ENGAGED ON FEDERAL-AID HIGHWAY PROJECTS

18 U.S.C. 1020 reads as follows:

"Whoever, being an officer, agent, or employee of the United States, or of any State or Territory, or whoever, whether a person, association, firm, or corporation, knowingly makes any false statement, false representation, or false report as to the character, quality, quantity, or cost of the material used or to be used, or the quantity or quality of the work performed or to be performed, or the cost thereof in connection with the submission of plans, maps, specifications, contracts, or costs of construction on any highway or related project submitted for approval to the Secretary of Transportation; or

Whoever knowingly makes any false statement, false representation, false report or false claim with respect to the character, quality, quantity, or cost of any work performed or to be performed, or materials furnished or to be furnished, in connection with the construction of any highway or related project approved by the Secretary of Transportation; or

Whoever knowingly makes any false statement or false representation as to material fact in any statement, certificate, or report submitted pursuant to provisions of the Federal-aid Roads Act approved July 1, 1916, (39 Stat. 355), as amended and supplemented;

Shall be fined not more that $10,000 or imprisoned not more than 5 years or both."

## X. IMPLEMENTATION OF CLEAN AIR ACT AND FEDERAL WATER POLLUTION CONTROL ACT

(Applicable to all Federal-aid construction contracts and to all related subcontracts of $100,000 or more.)

By submission of this bid or the execution of this contract, or subcontract, as appropriate, the bidder, Federal-aid construction contractor, or subcontractor, as appropriate, will be deemed to have stipulated as follows:

1. That any facility that is or will be utilized in the performance of this contract, unless such contract is exempt under the Clean Air Act, as amended (42 U.S.C. 1857 *et seq*., as amended by Pub.L. 91-604), and under the Federal Water Pollution Control Act, as amended (33 U.S.C. 1251 *et seq*., as amended by Pub.L. 92-500), Executive Order 11738, and regulations in implementation thereof (40 CFR 15) is not listed, on the date of contract award, on the U.S. Environmental Protection Agency (EPA) List of Violating Facilities pursuant to 40 CFR 15.20.
2. That the firm agrees to comply and remain in compliance with all the requirements of Section 114 of the Clean Air Act and Section 308 of the Federal Water Pollution Control Act and all regulations and guidelines listed thereunder.
3. That the firm shall promptly notify the SHA of the receipt of any communication from the Director, Office of Federal Activities, EPA, indicating that a facility that is or will be utilized for the contract is under consideration to be listed on the EPA List of Violating Facilities.
4. That the firm agrees to include or cause to be included the requirements of paragraph 1 through 4 of this Section X in every nonexempt subcontract, and further agrees to take such action as the government may direct as a means of enforcing such requirements.

## XI. CERTIFICATION REGARDING DEBARMENT, SUSPENSION, INELIGIBILITY AND VOLUNTARY EXCLUSION

1. **Instructions for Certification - Primary Covered Transactions:**

(Applicable to all Federal-aid contracts - 49 CFR 29)

a. By signing and submitting this proposal, the prospective primary participant is providing the certification set out below.
b. The inability of a person to provide the certification set out below will not necessarily result in denial of participation in this covered transaction. The prospective participant shall submit an explanation of why it cannot provide the certification set out below. The certification or explanation will be considered in connection with the department or agency's determination whether to enter into this transaction. However, failure of the prospective primary participant to furnish a certification or an explanation shall disqualify such a person from participation in this transaction.
c. The certification in this clause is a material representation of fact upon which reliance was placed when the department or agency determined to enter into this transaction. If it is later determined that the prospective primary participant knowingly rendered an erroneous certification, in addition to other remedies available to the Federal Government, the department or agency may terminate this transaction for cause of default.
d. The prospective primary participant shall provide immediate written notice to the department or agency to whom this proposal is submitted if any time the prospective primary participant learns that its certification was erroneous when submitted or has become erroneous by reason of changed circumstances.
e. The terms "covered transaction," "debarred," "suspended," "ineligible," "lower tier covered transaction," "participant," "person," "primary covered transaction," "principal," "proposal," and "voluntarily excluded," as used in this clause, have the meanings set out in the Definitions and Coverage sections of rules implementing Executive Order 12549. You may contact the department or agency to which this proposal is submitted for assistance in obtaining a copy of those regulations.
f. The prospective primary participant agrees by submitting this proposal that, should the proposed covered transaction be entered into, it shall not knowingly enter into any lower tier covered transaction with a person who is debarred, suspended, declared ineligible, or voluntarily excluded from participation in this covered transaction, unless authorized by the department or agency entering into this transaction.
g. The prospective primary participant further agrees by submitting this proposal that it will include the clause titled "Certification Regarding Debarment, Suspension, Ineligibility and Voluntary Exclusion-Lower Tier Covered Transaction," provided by the department or agency entering into this covered transaction, without modification, in all lower tier covered transactions and in all solicitations for lower tier covered transactions.
h. A participant in a covered transaction may rely upon a certification of a prospective participant in a lower tier covered transaction that is not debarred, suspended, ineligible, or voluntarily excluded from the covered transaction, unless it knows that the certification is erroneous. A participant may decide the method and

frequency by which it determines the eligibility of its principals. Each participant may, but is not required to, check the nonprocurement portion of the "Lists of Parties Excluded From Federal Procurement or Nonprocurement Programs" (Nonprocurement List) which is compiled by the General Services Administration.

i. Nothing contained in the foregoing shall be construed to require establishment of a system of records in order to render in good faith the certification required by this clause. The knowledge and information of participant is not required to exceed that which is normally possessed by a prudent person in the ordinary course of business dealings.

j. Except for transactions authorized under paragraph f of these instructions, if a participant in a covered transaction knowingly enters into a lower tier covered transaction with a person who is suspended, debarred, ineligible, or voluntarily excluded from participation in this transaction, in addition to other remedies available to the Federal Government, the department or agency may terminate this transaction for cause or default.

*** * * * ***

**Certification Regarding Debarment, Suspension, Ineligibility and Voluntary Exclusion--Primary Covered Transactions**

1. The prospective primary participant certifies to the best of its knowledge and belief, that it and its principals:

   a. Are not presently debarred, suspended, proposed for debarment, declared ineligible, or voluntarily excluded from covered transactions by any Federal department or agency;
   b. Have not within a 3-year period preceding this proposal been convicted of or had a civil judgement rendered against them for commission of fraud or a criminal offense in connection with obtaining, attempting to obtain, or performing a public (Federal, State or local) transaction or contract under a public transaction; violation of Federal or State antitrust statutes or commission of embezzlement, theft, forgery, bribery, falsification or destruction of records, making false statements, or receiving stolen property;
   c. Are not presently indicted for or otherwise criminally or civilly charged by a governmental entity (Federal, State or local) with commission of any of the offenses enumerated in paragraph 1b of this certification; and
   d. Have not within a 3-year period preceding this application/proposal had one or more public transactions (Federal, State or local) terminated for cause or default.

2. Where the prospective primary participant is unable to certify to any of the statements in this certification, such prospective participant shall attach an explanation to this proposal.

*** * * * ***

2. **Instructions for Certification - Lower Tier Covered Transactions:**

   (Applicable to all subcontracts, purchase orders and other lower tier transactions of $25,000 or more - 49 CFR 29)

   a. By signing and submitting this proposal, the prospective lower tier is providing the certification set out below.
   b. The certification in this clause is a material representation of fact upon which reliance was placed when this transaction was entered into. If it is later determined that the prospective lower tier participant knowingly rendered an erroneous certification, in addition to other remedies available to the Federal Government, the department, or agency with which this transaction originated may pursue available remedies, including suspension and/or debarment.
   c. The prospective lower tier participant shall provide immediate written notice to the person to which this proposal is submitted if at any time the prospective lower tier participant learns that its certification was erroneous by reason of changed circumstances.
   d. The terms "covered transaction," "debarred," "suspended," "ineligible," "primary covered transaction," "participant," "person," "principal," "proposal," and "voluntarily excluded," as used in this clause, have the meanings set out in the Definitions and Coverage sections of rules implementing Executive Order 12549. You may contact the person to which this proposal is submitted for assistance in obtaining a copy of those regulations.
   e. The prospective lower tier participant agrees by submitting this proposal that, should the proposed covered transaction be entered into, it shall not knowingly enter into any lower tier covered transaction with a person

who is debarred, suspended, declared ineligible, or voluntarily excluded from participation in this covered transaction, unless authorized by the department or agency with which this transaction originated.

f. The prospective lower tier participant further agrees by submitting this proposal that it will include this clause titled "Certification Regarding Debarment, Suspension, Ineligibility and Voluntary Exclusion-Lower Tier Covered Transaction," without modification, in all lower tier covered transactions and in all solicitations for lower tier covered transactions.

g. A participant in a covered transaction may rely upon a certification of a prospective participant in a lower tier covered transaction that is not debarred, suspended, ineligible, or voluntarily excluded from the covered transaction, unless it knows that the certification is erroneous. A participant may decide the method and frequency by which it determines the eligibility of its principals. Each participant may, but is not required to, check the Nonprocurement List.

h. Nothing contained in the foregoing shall be construed to require establishment of a system of records in order to render in good faith the certification required by this clause. The knowledge and information of participant is not required to exceed that which is normally possessed by a prudent person in the ordinary course of business dealings.

i. Except for transactions authorized under paragraph e of these instructions, if a participant in a covered transaction knowingly enters into a lower tier covered transaction with a person who is suspended, debarred, ineligible, or voluntarily excluded from participation in this transaction, in addition to other remedies available to the Federal Government, the department or agency with which this transaction originated may pursue available remedies, including suspension and/or debarment.

*** * * * ***

**Certification Regarding Debarment, Suspension, Ineligibility and Voluntary Exclusion--Lower Tier Covered Transactions:**

1. The prospective lower tier participant certifies, by submission of this proposal, that neither it nor its principals is presently debarred, suspended, proposed for debarment, declared ineligible, or voluntarily excluded from participation in this transaction by any Federal department or agency.
2. Where the prospective lower tier participant is unable to certify to any of the statements in this certification, such prospective participant shall attach an explanation to this proposal.

*** * * * ***

## XII. CERTIFICATION REGARDING USE OF CONTRACT FUNDS FOR LOBBYING

(Applicable to all Federal-aid construction contracts and to all related subcontracts which exceed $100,000 - 49 CFR 20)

1. The prospective participant certifies, by signing and submitting this bid or proposal, to the best of his or her knowledge and belief, that:

   a. No Federal appropriated funds have been paid or will be paid, by or on behalf of the undersigned, to any person for influencing or attempting to influence an officer or employee of any Federal agency, a Member of Congress, an officer or employee of Congress, or an employee of a Member of Congress in connection with the awarding of any Federal contract, the making of any Federal grant, the making of any Federal loan, the entering into of any cooperative agreement, and the extension, continuation, renewal, amendment, or modification of any Federal contract, grant, loan, or cooperative agreement.

   b. If any funds other than Federal appropriated funds have been paid or will be paid to any person for influencing or attempting to influence an officer or employee of any Federal agency, a Member of Congress, an officer or employee of Congress, or an employee of a Member of Congress in connection with this Federal contract, grant, loan, or cooperative agreement, the undersigned shall complete and submit Standard Form-LLL, "Disclosure Form to Report Lobbying," in accordance with its instructions.

2. This certification is a material representation of fact upon which reliance was placed when this transaction was made or entered into. Submission of this certification is a prerequisite for making or entering into this transaction imposed by 31 U.S.C. 1352. Any person who fails to file the required certification shall be subject to a civil penalty of not less than $10,000 and not more than $100,000 for each such failure.

3. The prospective participant also agrees by submitting his or her bid or proposal that he or she shall require that the language of this certification be included in all lower tier subcontracts, which exceed $100,000 and that all such recipients shall certify and disclose accordingly.

**7-1.50C Female and Minority Goals**

To comply with Section II, "Nondiscrimination," of "Required Contract Provisions Federal-Aid Construction Contracts," the Department is including in Section 7-1.50C, "Female and Minority Goals," female and minority utilization goals for Federal-aid construction contracts and subcontracts that exceed $10,000.

The nationwide goal for female utilization is 6.9 percent.

The goals for minority utilization [45 Fed Reg 65984 (10/3/1980)] are as follows:

**Minority Utilization Goals**

| | Economic Area | Goal (Percent) |
|---|---|---|
| 174 | Redding CA:<br>Non-SMSA Counties:<br>CA Lassen; CA Modoc; CA Plumas; CA Shasta; CA Siskiyou; CA Tehema | 6.8 |
| 175 | Eureka, CA<br>Non-SMSA Counties:<br>CA Del Norte; CA Humboldt; CA Trinity | 6.6 |
| 176 | San Francisco-Oakland-San Jose, CA:<br>SMSA Counties:<br>7120 Salinas-Seaside-Monterey, CA<br>CA Monterey<br>7360 San Francisco-Oakland<br>CA Alameda; CA Contra Costa; CA Marin; CA San Francisco; CA San Mateo<br>7400 San Jose, CA<br>CA Santa Clara, CA<br>7485 Santa Cruz, CA<br>CA Santa Cruz<br>7500 Santa Rosa<br>CA Sonoma<br>8720 Vallejo-Fairfield-Napa, CA<br>CA Napa; CA Solano<br>Non-SMSA Counties:<br>CA Lake; CA Mendocino; CA San Benito | <br><br>28.9<br><br>25.6<br><br><br>19.6<br><br>14.9<br><br>9.1<br><br>17.1<br><br>23.2 |
| 177 | Sacramento, CA:<br>SMSA Counties:<br>6920 Sacramento, CA<br>CA Placer; CA Sacramento; CA Yolo<br>Non-SMSA Counties<br>CA Butte; CA Colusa; CA El Dorado; CA Glenn; CA Nevada; CA Sierra; CA Sutter; CA Yuba | <br><br>16.1<br><br>14.3 |
| 178 | Stockton-Modesto, CA:<br>SMSA Counties:<br>5170 Modesto, CA<br>CA Stanislaus<br>8120 Stockton, CA<br>CA San Joaquin<br>Non-SMSA Counties<br>CA Alpine; CA Amador; CA Calaveras; CA Mariposa; CA Merced; CA Toulumne | <br><br>12.3<br><br>24.3<br><br>19.8 |
| 179 | Fresno-Bakersfield, CA<br>SMSA Counties:<br>0680 Bakersfield, CA<br>CA Kern<br>2840 Fresno, CA<br>CA Fresno<br>Non-SMSA Counties:<br>CA Kings; CA Madera; CA Tulare | <br><br>19.1<br><br>26.1<br><br>23.6 |
| 180 | Los Angeles, CA:<br>SMSA Counties:<br>0360 Anaheim-Santa Ana-Garden Grove, CA<br>CA Orange<br>4480 Los Angeles-Long Beach, CA<br>CA Los Angeles<br>6000 Oxnard-Simi Valley-Ventura, CA<br>CA Ventura | <br><br>11.9<br><br>28.3<br><br>21.5 |

| | | |
|---|---|---|
| | 6780 Riverside-San Bernardino-Ontario, CA<br>CA Riverside; CA San Bernardino<br>7480 Santa Barbara-Santa Maria-Lompoc, CA<br>CA Santa Barbara<br>Non-SMSA Counties<br>CA Inyo; CA Mono; CA San Luis Obispo | 19.0<br><br>19.7<br><br>24.6 |
| 181 | San Diego, CA:<br>SMSA Counties<br>7320 San Diego, CA<br>CA San Diego<br>Non-SMSA Counties<br>CA Imperial | <br><br>16.9<br><br>18.2 |

For each July during which work is performed under the contract, you and each non-material-supplier subcontractor with a subcontract of $10,000 or more must complete Form FHWA PR-1391 (Appendix C to 23 CFR 230). Submit the forms by August 15.

**7-1.50D Training**

Section 7-1.50D, "Training," applies if a number of trainees or apprentices is specified in the special provisions.

As part of your equal opportunity affirmative action program, provide on-the-job training to develop full journeymen in the types of trades or job classifications involved.

You have primary responsibility for meeting this training requirement.

If you subcontract a contract part, determine how many trainees or apprentices are to be trained by the subcontractor.

Include these training requirements in your subcontract.

Where feasible, 25 percent of apprentices or trainees in each occupation must be in their 1st year of apprenticeship or training.

Distribute the number of apprentices or trainees among the work classifications on the basis of your needs and the availability of journeymen in the various classifications within a reasonable recruitment area.

Before starting work, submit to the Department:

1. Number of apprentices or trainees to be trained for each classification
2. Training program to be used
3. Training starting date for each classification

Obtain the Department's approval for this submitted information before you start work. The Department credits you for each apprentice or trainee you employ on the work who is currently enrolled or becomes enrolled in an approved program.

The primary objective of Section 7-1.50D, "Training," is to train and upgrade minorities and women toward journeymen status. Make every effort to enroll minority and women apprentices or trainees, such as conducting systematic and direct recruitment through public and private sources likely to yield minority and women apprentices or trainees, to the extent they are available within a reasonable recruitment area. Show that you have made the efforts. In making these efforts, do not discriminate against any applicant for training.

Do not employ as an apprentice or trainee an employee:

1. In any classification in which the employee has successfully completed a training course leading to journeyman status or in which the employee has been employed as a journeyman
2. Who is not registered in a program approved by the US Department of Labor, Bureau of Apprenticeship and Training

Ask the employee if the employee has successfully completed a training course leading to journeyman status or has been employed as a journeyman. Your records must show the employee's answers to the questions.

In your training program, establish the minimum length and training type for each classification. The Department and FHWA approves a program if one of the following is met:

1. It is calculated to:

    1.1. Meet the your equal employment opportunity responsibilities

1.2. Qualify the average apprentice or trainee for journeyman status in the classification involved by the end of the training period

2. It is registered with the U.S. Department of Labor, Bureau of Apprenticeship and Training and it is administered in a way consistent with the equal employment responsibilities of federal-aid highway construction contracts

Obtain the State's approval for your training program before you start work involving the classification covered by the program.

Provide training in the construction crafts, not in clerk-typist or secretarial-type positions. Training is allowed in lower level management positions such as office engineers, estimators, and timekeepers if the training is oriented toward construction applications. Training is allowed in the laborer classification if significant and meaningful training is provided and approved by the division office. Off-site training is allowed if the training is an integral part of an approved training program and does not make up a significant part of the overall training.

The Department reimburses you 80 cents per hour of training given an employee on this contract under an approved training program:

1. For on-site training
2. For off-site training if the apprentice or trainee is currently employed on a federal-aid project and you do at least one of the following:

   2.1. Contribute to the cost of the training
   2.2. Provide the instruction to the apprentice or trainee
   2.3. Pay the apprentice's or trainee's wages during the off-site training period

3. If you comply with Section 7-1.50D, "Training"

Each apprentice or trainee must:

1. Begin training on the project as soon as feasible after the start of work involving the apprentice's or trainee's skill
2. Remain on the project as long as training opportunities exist in the apprentice's or trainee's work classification or until the apprentice or trainee has completed the training program

Furnish the apprentice or trainee:

1. Copy of the program you will comply with in providing the training
2. Certification showing the type and length of training satisfactorily completed

Maintain records and submit reports documenting your performance under Section 7-1.50D, "Training."

^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^

## SECTION 8 PROSECUTION AND PROGRESS
**(Issued 05-01-09)**

**Replace Section 8 with:**

## SECTION 8 PROSECUTION AND PROGRESS

### 8-1.01 (BLANK)

### 8-1.02 ASSIGNMENT

No third-party agreement relieves you or your surety of your responsibility to complete the work. Do not sell, transfer, or otherwise dispose of any contract part without prior written consent from the Department.

If you assign the right to receive contract payments, the Department accepts the assignment upon the Engineer's receipt of a notice. Assigned payments remain subject to deductions and withholds described in the contract. The Department may use withheld payments for work completion whether payments are assigned or not.

**8-1.025 PRECONSTRUCTION CONFERENCE**

Attend a preconstruction conference with key personnel, including your assigned representative, at a time and location determined by the Engineer. Submit documents as required before the preconstruction conference. You may begin work before the preconstruction conference.

Be prepared to discuss the following topics and documents:

| Topics | Document |
|---|---|
| Claim resolution | Notice of Potential Claims |
| Contractor's representation | Assignment of Contractor's representative |
| DBE and DVBE | Final utilization reports |
| Equipment | Equipment list |
| Labor compliance and equal employment opportunity | Job site posters and benefit and payroll reports |
| Material inspection | Notice of Materials to be Used |
| Materials on hand | Request for Payment for Materials on Hand |
| Measurements | -- |
| Partnering | Field Guide to Partnering on Caltrans Construction Projects |
| Quality control | QC plans |
| Safety | Injury and Illness Prevention Program and job site posters |
| Schedule | Baseline schedule and Weekly Statement of Working Days |
| Subcontracting | Subcontracting Request |
| Surveying | Survey Request |
| Traffic control | Traffic contingency plan and traffic control plans |
| Utility work | -- |
| Weight limitations | -- |
| Water Pollution Control | SWPPP or WPCP |
| Work restrictions | PLACs |
| Working drawings | -- |

**8-1.03 BEGINNING OF WORK**

Begin work within 15 days after receiving notice that the contract has been approved by the Attorney General or the attorney appointed and authorized to represent the Department. Submit a written notice 72 hours before beginning work. If the project has more than one location of work, submit a separate notice for each location.

You may begin work before receiving the notice of contract approval if you:

1. Deliver the signed contract, bonds, and evidence of insurance to the Department
2. Submit 72-hour notice
3. Obtain an encroachment permit from the Department
4. Are authorized by the Department to begin
5. Perform work at your own risk
6. Perform work under the contract

The Engineer does not count working days for days worked before contract approval.

If the contract is approved, work already performed that complies with the contract is authorized.

If the contract does not get approved, leave the job site in a neat condition. If a facility has been changed, restore it to its former or equivalent condition at your expense.

The Department does not adjust time for beginning before the approval date.

## 8-1.04 PROGRESS SCHEDULE

### 8-1.04A General

Reserved

### 8-1.04B Critical Path Method Schedule

The following definitions apply to critical path method schedules:

**activity**: Task, event, or other project element on a schedule that contributes to completing the project. Activities have a description, start date, finish date, duration, and one or more logic ties.
**baseline schedule**: The initial schedule showing the original work plan beginning on the date of contract approval. This schedule shows no completed work to date and no negative float or negative lag to any activity.
**controlling activity**: Construction activity that extends the scheduled completion date if delayed.
**critical path**: Longest continuous chain of activities for the project that has the least amount of total float of all chains. In general, a delay on the critical path extends the scheduled completion date.
**critical path method (CPM)**: Network based planning technique using activity durations and relationships between activities to calculate a schedule for the entire project.
**revised schedule**: Schedule that incorporates a proposed or past change to logic or activity durations.
**scheduled completion date**: Planned project completion date shown on the current schedule.
**updated schedule**: Current schedule developed from the accepted baseline and any subsequent accepted updated or revised schedules through regular monthly review to incorporate actual past progress.

Before or at the preconstruction conference, submit a CPM baseline schedule.

Submit a monthly updated schedule that includes the status of work completed to date and the work yet to be performed as planned.

On each schedule, show:

1. Planned and actual start and completion date of each work activity, including applicable:

    1.1. Submittal development
    1.2. Submittal review and approval
    1.3. Material procurement
    1.4. Contract milestones and constraints
    1.5. Equipment and plant setup
    1.6. Interfaces with outside entities
    1.7. Erection and removal of falsework and shoring
    1.8. Test periods
    1.9. Major traffic stage change
    1.10. Final cleanup

2. Order that you propose to prosecute the work
3. Logical links between the time-scaled work activities
4. All controlling activities
5. Legible description of each activity
6. At least one predecessor and one successor to each activity, except for project start and project end milestones
7. Duration of not less than one working day for each activity
8. Start milestone date as the contract approval date

You may include changes on updated schedules that do not alter the critical path or extend the schedule completion date compared to the current schedule. Changes may include:

1. Adding or deleting activities
2. Changing activity constraints
3. Changing durations
4. Changing logic

If any proposed change in planned work results in altering the critical path or extending the scheduled completion date, submit a revised schedule within 15 days of the proposed change.

For each schedule submittal:

1. Submit a plotted original, time-scaled network diagram on a sheet of at least 8.5" x 11" with a title block and timeline
2. If a computer program is used to make the schedule, submit a read-only compact disc or diskette containing the schedule data. Label the compact disc or diskette with:

    2.1. Contract number
    2.2. CPM schedule number and date produced
    2.3. File name

If there is no contract item for progress schedule (critical path method), full compensation for this work is included in the contract prices paid for the items of work involved, and no additional compensation will be allowed therefor.

## 8-1.05 TEMPORARY SUSPENSION OF WORK

### 8-1.05A General

The Engineer may suspend work wholly or in part due to any of the following:

1. Conditions are unsuitable for work progress.
2. You fail to do any of the following:

    2.1. Fulfill the Engineer's orders.
    2.2. Fulfill a contract part.
    2.3. Perform weather-dependent work when conditions are favorable so that weather-related unsuitable conditions are avoided or do not occur.

Upon the Engineer's written order of suspension, suspend work immediately. Provide for public safety and a smooth and unobstructed passageway through the work zone during the suspension as specified in Sections 7-1.08, "Public Convenience," and 7-1.09, "Public Safety." Resume work when ordered.

### 8-1.05B Suspensions Unrelated to Contractor Performance

For a suspension unrelated to your performance, providing for a smooth and unobstructed passageway through the work during the suspension will be paid for as extra work as specified in Section 4-1.03D, "Extra Work."

The days during a suspension unrelated to your performance are non-working days.

### 8-1.05C Suspensions Related to Contractor Performance

For a suspension related to your performance, the Department may provide for a smooth and unobstructed passageway through the work during the suspension and deduct the cost from payments.

The days during a suspension related to your performance are working days.

## 8-1.06 TIME OF COMPLETION

The time to complete the work is specified in the special provisions.

The Engineer issues a Weekly Statement of Working Days by the end of the following week unless the contract is suspended for reasons unrelated to your performance.

The Weekly Statement of Working Days shows:

1. Working days and non-working days during the reporting week
2. Time adjustments
3. Work completion date computations, including working days remaining
4. Controlling activities

You may protest a Weekly Statement of Working Days by:

1. Submitting a Notice of Potential Claim within 5 days of receipt of the Weekly Statement of Working Days
2. Following the dispute and claim procedures specified in Sections 9-1.04, "Notice of Potential Claim," and 9-1.07B, "Final Payment and Claims."

## 8-1.07 LIQUIDATED DAMAGES

### 8-1.07A General

The Department specifies liquidated damages (Pub Cont Code § 10226). Liquidated damages, if any, accrue starting on the 1st day after the expiration of the working days through the day of contract acceptance except as specified in Sections 8-1.07B, "Failure to Complete Work Parts within Specified Times," and 8-1.07C, "Failure to Complete Work Parts by Specified Dates."

The Department withholds liquidated damages before the accrual date if the anticipated liquidated damages may exceed the value of the remaining work.

Liquidated damages for all work, except plant establishment, are:

| Liquidated Damages | | |
|---|---|---|
| Total Bid | | Liquidated Damages per Day |
| From over | To | |
| $0 | $50,000 | $1,200 |
| $50,000 | $120,000 | $1,500 |
| $120,000 | $1,000,000 | $1,900 |
| $1,000,000 | $5,000,000 | $3,000 |
| $5,000,000 | $10,000,000 | $5,400 |
| $10,000,000 | $30,000,000 | $8,300 |
| $30,000,000 | $100,000,000 | $10,500 |
| $100,000,000 | $250,000,000 | $28,500 |

If all work, except plant establishment, is complete and the total number of working days has expired, liquidated damages are $950 per day.

### 8-1.07B Failure to Complete Work Parts within Specified Times

The Department may deduct specified damages from payments for each day in completing a work part beyond the time specified for completing the work part.

Damages for untimely completion of work parts may not be equal to the daily amount specified as liquidated damages for the project as a whole, but the Department does not simultaneously assess damages for untimely completion of work parts and for the whole work.

Damages accrue starting the 1st day after a work part exceeds the specified time through the day the specified work part is complete.

### 8-1.07C Failure to Complete Work Parts by Specified Dates

The Department may deduct specified damages from payments for each day in completing a work part beyond the specified completion date for the work part.

Damages for untimely work part completion may not be equal to the daily amount specified as liquidated damages for the project as a whole, but the Department does not simultaneously assess damages for untimely work part completion and the whole work.

Damages accrue starting the 1st day after an unmet completion date through the day the work part is complete.

### 8-1.07D Director Days

If the work is not completed within the working days, the Director may grant director days if it serves the State's best interest.

By granting director days, the Director adds working days to the contract. The Director may either grant enough days to eliminate the liquidated damages or fewer. In the latter case, the Department deducts liquidated damages for the remaining overrun in contract time. The Director may deduct the Department's engineering, inspection, and overhead costs incurred during the period of extension granted as director days.

## 8-1.08 TERMINATION OF CONTROL

The Department may terminate your control of the work for failure to do any of the following (Pub Cont Code § 10253):

1. Supply an adequate workforce
2. Supply material as described
3. Pay subcontractors (Pub Cont Code §10262)

4. Prosecute the work as described in the contract

The Department may also terminate your control for failure to maintain insurance coverage.

For a Federal-aid contract, the Department may terminate your control of the work for failure to include "Required Contract Provisions, Federal-Aid Construction Contracts" in subcontracts.

The Department gives you and your surety notice at least 5 days before terminating control. The notice describes the failures and the time allowed to remedy the failures. If failures are not remedied within the time provided, the Department takes control of the work.

The Department may complete the work if the Department terminates your control or you abandon the project (Pub Cont Code § 10255). The Department determines the unpaid balance under Pub Cont Code § 10258 and the contract.

At any time before final payment of all claims, the Department may convert a termination of control to a termination of contract.

## 8-1.09 DELAYS

### 8-1.09A General

An excusable delay is a delay of a controlling activity beyond your control, not foreseeable when the work began such as:

1. Change in the work
2. Department action that is not part of the contract
3. Presence of an underground utility main not described in the contract or in a location different from that specified
4. Described facility reconstruction not reconstructed as described, by the utility owner by the date specified, unless the reconstruction is solely for your convenience
5. Department's failure to obtain timely access to the right-of-way
6. Department's failure to perform an action in the time specified

A critical delay is a delay that extends the schedule completion date.

If requesting a delay-related time or payment adjustment, follow the dispute and claim procedures specified in Sections 9-1.04, "Notice of Potential Claim," and 9-1.07B, "Final Payment and Claims."

Minimize and mitigate impacts of delays.

### 8-1.09B Time Adjustments

For an excusable critical delay, the Department may make a time adjustment. The Engineer uses information from the schedule to evaluate requests for time adjustments.

If requesting an adjustment, submit a revised schedule showing the delay's effect on the controlling activity. If the delay has:

1. Occurred, submit records of dates and what work was performed during the delayed activity
2. Not occurred, submit the expected dates or duration of the delayed activity

If the Engineer requests, update the schedule to the last working day before the start of the delay.

### 8-1.09C Payment Adjustments

The Department may make a payment adjustment for an excusable delay that affects your costs.

Only losses for idle equipment, idle workers, and equipment moving or transporting are eligible for delay-related payment adjustments.

The Engineer determines payment for idle time of equipment in the same manner as determinations are made for equipment used in the performance of extra work paid for on a force account basis as specified in Section 9-1.03A(3), "Equipment Rental," with the following exceptions:

1. Delay factor in the Labor Surcharge and Equipment Rental Rates applies to each equipment rental rate
2. Daily number of payable hours equals the normal working hours during the delay, not to exceed 8 hours per day
3. Delay days exclude non-working days
4. Markups are not added

The Engineer determines payment adjustment for idle workers under Section 9-1.03A(1), "Labor," but does not add markups.

The Engineer includes costs due to necessary extra equipment moving or transporting.

**8-1.10 (BLANK)**

**8-1.11 TERMINATION OF CONTRACT**

**8-1.10A General**

The Director may terminate the contract if it serves the State's best interest. The Department issues you a written notice, implements the termination, and pays you.

**8-1.10B Relief from Responsibility for Work**

On receiving a termination notice:

1. Stop work
2. Notify subcontractors and suppliers of the contract termination and stop contract-related work
3. Perform the Engineer-ordered work to secure the job site for termination
4. Remove equipment
5. If authorized, settle termination-related claims and liabilities involving subcontractors and suppliers; assign to the Department the rights, titles, or interests held by you with respect to these parties

**8-1.10C Responsibility for Materials**

On receiving a termination notice, protect unused material until:

1. You submit an inventory of materials already produced, purchased, or ordered but not yet used; include the location of the material.
2. The Engineer identifies materials that will be retained by the Department. Submit bills of sales or other records of material title.
3. The Engineer confirms that unused materials paid by progress payment and materials furnished by the State have been delivered and stored as ordered.
4. Titles are transferred for materials purchased by the Department.

Dispose of materials that will not be retained by the Department.

**8-1.10D Contract Acceptance after Termination**

The Engineer recommends contract acceptance after determining completion of:

1. Contract work ordered to be completed before termination
2. Other work ordered to secure the project before termination
3. Material delivery and title transfer

Payment is made as specified in Section 9-1.07B, "Final Payment and Claims."

**8-1.10E Payment Adjustment for Termination**

If the Department issues a termination notice, the Engineer determines payment for termination based on the following:

1. Direct cost for the work:

    1.1. Including mobilization, demobilization, securing the job site for termination, and losses from the sale of materials
    1.2. Not including the cost of materials you keep, profit realized from the sale of materials, the cost of material damaged by an occurrence as defined in Section 7-1.165, "Damage by Storm, Flood, Tsunami or Earthquake," and other credits.

2. Cost of remedial work, as estimated by the Engineer, is not reimbursed.
3. Allowance for profit not to exceed 4 percent of the cost of the work. Prove a likelihood of having made a profit had the contract not been terminated.
4. Material handling costs for material returned to the vendor or disposed of as ordered.

5. Costs in determining the payment adjustment due to the termination, excluding attorney fees and litigation costs.

Termination of the contract does not relieve the surety of its obligation for any just claims arising out of the work performed.

^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^

## SECTION 9 MEASUREMENT AND PAYMENT
**(Issued 05-01-09)**

**In Section 9-1.02 in the 1st paragraph, replace last sentence with:**

Neither the payment of any estimate nor of any retained percentage or withhold relieves the Contractor of any obligation to make good any defective work or material.

**Add to Section 9-1.02:**

The Department pays 10 percent per year interest for unpaid and undisputed:

1. Progress payments
2. After-acceptance payment except for claims

For these payments, interest starts to accrue 30 days after the 1st working day following the 20th day of the month payment is due.

The Department pays 6 percent per year interest for accepted claims. Interest starts to accrue 61 days after the Department accepts a Final Claim Statement.

The Department pays 6 percent per year interest for awards in arbitration (Civ Code § 3289).

If the amount of a deduction or withhold exceeds final payment, the Department invoices you for the difference, to be paid upon receipt.

**In Section 9-1.03A replace the 2nd paragraph with:**

To the total of the direct costs computed as provided in Sections 9-1.03A(1), "Labor," 9-1.03A(2), "Materials," and 9-1.03A(3), "Equipment Rental," there will be added a markup of 35 percent to the cost of labor, 15 percent to the cost of materials, and 15 percent to the cost of equipment rental.

**In Section 9-1.03A replace the 4th paragraph with:**

If a subcontractor performs work at force account, accept an additional 10 percent markup to the total cost of that work paid at force account, including markups specified in Section 9-1.03, "Force Account Payment," as reimbursement for additional administrative costs.

**Replace Section 9-1.03B with:**

The Contractor, and all subcontractors obtained before or after contract execution, shall itemize the labor, material, and equipment rental costs, and shall not be deemed specialists unless the selected Contractor or available subcontractors on site are not capable of performing the specialty work and it is not the special service industry's established practice to provide cost itemization. In addition, the Engineer may approve work required to be performed at an off-site manufacturing plant or machine shop to be paid as a non-itemized specialist billing. To obtain approval as a specialist, the Contractor shall submit on behalf of the subcontractor a request to the Engineer prior to the start of the proposed specialist work.

If approval is granted, the Engineer will accept the non-itemized invoices for specialty work performed, provided the invoices are at current market rates. Markup percentages of Section 9-1.03A, "Work Performed by Contractor," will not apply. A markup of 10 percent will be added to the total cost of the extra work. The 10 percent markup shall reimburse the Contractor for additional administrative costs, and no other payment will be made by reason of performance of the extra work by a specialist.

If approval is not granted prior to the start of the proposed specialty work, the Contractor or subcontractor shall itemize labor, material, and equipment rental costs and apply percentage markups as required by Section 9-1.03A, "Work Performed by Contractor."

**In Section 9-1.03C delete the 6th paragraph.**

**In Section 9-1.04 replace the 2nd paragraph with:**

Disputes will not be considered unless you have first complied with specified notice or protest requirements, including Section 4-1.03, "Changes," Section 5-1.116, "Differing Site Conditions (23 CFR 635.109)," Section 5-1.18B "Nonhighway Facilities (Including Utilities)," and Section 8-1.06, "Time of Completion."

**In Section 9-1.04 in the 10th paragraph, replace item C with:**

C. When additional monetary compensation is requested, the exact amount requested calculated in conformance with Section 9-1.03, "Force Account Payment," or Section 8-1.09B, "Time Adjustments," including an itemized breakdown of individual costs. These costs shall be segregated into the following cost categories:

**In Section 9-1.04 in the 14th paragraph, replace the 2nd sentence with:**

Administrative disputes are disputes of administrative deductions or withholds, contract item quantities, contract item adjustments, interest payments, protests of contract change orders as provided in Section 4-1.03A, "Procedure and Protest," and protests of the Weekly Statement of Working Days as provided in Section 8-1.06, "Time of Completion."

**Replace Section 9-1.05 with:**

**9-1.05 STOP NOTICE WITHHOLDS**

The Department may withhold payments to cover claims filed under Civ Code § 3179 et seq.

**Add:**

**9-1.053 PERFORMANCE FAILURE WITHHOLDS**

During each estimate period you fail to comply with a contract part, including submittal of a document as specified, the Department withholds a part of the progress payment. The documents include quality control plans, schedules, traffic control plans, and water pollution control submittals.

For 1 performance failure, the Department withholds 25 percent of the progress payment but does not withhold more than 10 percent of the total bid.

For multiple performance failures, the Department withholds 100 percent of the progress payment but does not withhold more than 10 percent of the total bid.

The Department returns performance-failure withholds in the progress payment following the correction of noncompliance.

**Add:**

**9-1.055 PENALTY WITHHOLDS**

Penalties include fines and damages that are proposed, assessed, or levied against you or the Department by a governmental agency or citizen lawsuit. Penalties are also payments made or costs incurred in settling alleged permit violations of Federal, State, or local laws, regulations, or requirements. The cost incurred may include the amount spent for mitigation or correcting a violation.

If you or the Department is assessed a penalty, the Department may withhold the penalty amount until the penalty disposition has been resolved. The Department may withhold penalty funds and notify you within 15 days of the withhold. If the penalty amount is less than the amount being withheld from progress payments for retentions, the Department will not withhold the penalty amount.

If the penalty is resolved for less than the amount withheld, the Department pays interest at a rate of 6 percent per year on the excess withhold. If the penalty is not resolved, the withhold becomes a deduction.

Instead of the withhold, you may provide a bond payable to the Department of Transportation equal to the highest estimated liability for any disputed penalties proposed.

**Add:**

**9-1.057 PROGRESS WITHHOLDS**

The Department withholds 10 percent of a partial payment for noncompliant progress. Noncompliant progress occurs when:

1. Total days to date exceed 75 percent of the revised contract working days
2. Percent of working days elapsed exceeds the percent of value of work completed by more than 15 percent

The Engineer determines the percent of working days elapsed by dividing the total days to date by the revised contract working days and converting the quotient to a percentage.

The Engineer determines the percent of value of work completed by summing payments made to date and the amount due on the current progress estimate, dividing this sum by the current total estimated value of the work, and converting the quotient to a percentage. These amounts are shown on the Progress Payment Voucher.

When the percent of working days elapsed minus the percent of value of work completed is less than or equal to 15 percent, the Department returns the withhold in the next progress payment.

**In Section 9-1.06 in the 4th paragraph, replace the 1st sentence with:**

The Department shall pay monthly to the Contractor, while carrying on the work, the balance not retained, as aforesaid, after deducting therefrom all previous payments and all sums to be deducted or withheld under the provisions of the contract.

**In Section 9-1.065 replace the title and the 1st and 2nd paragraphs with:**

**9-1.065 RELEASE OF RETAINED FUNDS**

The Department releases retained funds if you:

1. Request release of the retention (Pub Cont Code § 10263) in writing
2. Deposit securities equivalent to the funds you want released into escrow with the State Treasurer or with a bank acceptable to the Department
3. Are the beneficial owner of and receive interest on the deposited securities substituted for the retained funds

**In Section 9-1.07A, replace the 2nd sentence with:**

The Department pays the balance due less previous payments, deductions, withholds, and retentions under the provisions of the contract and those further amounts that the Engineer determines to be necessary pending issuance of the proposed final estimate and payment thereon.

**In Section 9-1.07B, replace the 1st paragraph with:**

After acceptance by the Director, the Engineer makes a proposed final estimate of the total amount payable to the Contractor, including an itemization of the total amount, segregated by contract item quantities, extra work, and other basis for payment, and shows each deduction made or to be made for prior payments and amounts to be deducted, withheld, or retained under the provisions of the contract. Prior estimates and payments are subject to correction in the proposed final estimate. The Contractor must submit written approval of the proposed final estimate or a written statement of claims arising under or by virtue of the contract so that the Engineer receives the written approval or statement of claims no later than close of business of the 30th day after receiving the proposed final estimate. The Contractor's receipt of the proposed final estimate must be evidenced by postal receipt. The Engineer's receipt of the Contractor's written approval or statement of claims must be evidenced by postal receipt or the Engineer's written receipt if delivered by hand.

^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^

## SECTION 10 DUST CONTROL
**(Issued 02-06-09)**

**Replace Section 10 with:**
**SECTION 10 (BLANK)**

^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^

## SECTION 12 CONSTRUCTION AREA TRAFFIC CONTROL DEVICES
**(Issued 11-07-08)**

**In Section 12-1.01 in the 2nd paragraph, replace the 1st sentence with:**

Attention is directed to Part 6 of the California MUTCD.

**Replace Section 12-2.01 with:**

### 12-2.01 FLAGGERS

Flaggers while on duty and assigned to traffic control or to give warning to the public that the highway is under construction and of any dangerous conditions to be encountered as a result thereof, shall perform their duties and shall be provided with the necessary equipment in conformance with Part 6 of the California MUTCD. The equipment shall be furnished and kept clean and in good repair by the Contractor at the Contractor's expense.

All flaggers shall wear safety apparel meeting the requirements of ANSI/ISEA 107-2004 for Class 2 or 3 garment and complying with 71 Fed Reg 67792.

**In Section 12-3.01 replace the 1st paragraph with:**

In addition to the requirements in Part 6 of the California MUTCD, all devices used by the Contractor in the performance of the work shall conform to the provisions in this Section 12-3.

**In Section 12-3.06 in the 1st paragraph, replace the 2nd sentence with:**

Construction area signs are shown in or referred to in Part 6 of the California MUTCD.

**In Section 12-3.06 in the 4th paragraph, replace the 1st sentence with:**

All construction area signs shall conform to the dimensions, color and legend requirements of the plans, Part 6 of the California MUTCD and these specifications.

**In Section 12-3.06 in the 8th paragraph, replace the 1st sentence with:**

Used signs with the specified sheeting material will be considered satisfactory if they conform to the requirements for visibility and legibility and the colors conform to the requirements in Part 6 of the California MUTCD.

^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^

## SECTION 14 (BLANK)
**(Issued 03-13-09)**

**Replace Section 14 with:**

# SECTION 14 ENVIRONMENTAL STEWARDSHIP

## 14-1 GENERAL

### 14-1.01 GENERAL

Environmental stewardship includes both environmental compliance and environmental resource management.

If an ESA is shown on the plans:

1. The boundaries shown are approximate; the Department marks the exact boundaries on the ground
2. Do not enter the ESA unless authorized
3. If the ESA is breached, immediately:
   3.1. Secure the area and stop all operations within 60 feet of the ESA boundary
   3.2. Notify the Engineer
4. If the ESA is damaged, the Department determines what efforts are necessary to remedy the damage and who performs the remedy; you are responsible for remedies and charges.

## 14-2 CULTURAL RESOURCES

### 14-2.01 GENERAL

Reserved

### 14-2.02 ARCHAEOLOGICAL RESOURCES

If archaeological resources are discovered at the job site, do not disturb the resources and immediately:

1. Stop all work within a 60-foot radius of the discovery
2. Protect the discovery area
3. Notify the Engineer

The Department investigates. Do not take archaeological resources from the job site. Do not resume work within the discovery area until authorized.

If, in the opinion of the Engineer, completion of the work is delayed or interfered with by reason of an archaeological find, or investigation or recovery of archeological materials, you will be compensated for resulting losses, and an extension of time will be granted, in the same manner as provided for in Section 8-1.09, "Right of Way Delays."

If ordered, furnish resources to assist in the investigation or recovery of archaeological resources. This work will be paid for as extra work as specified in Section 4-1.03D, "Extra Work."

### 14-2.03 ARCHAEOLOGICAL MONITORING AREA

Section 14-2.03 applies if an AMA is described in the Contract.

The Department assigns an archaeological monitor to monitor job site activities within the AMA. Do not work within the AMA unless the archeological monitor is present.

The Engineer and the Department archaeological monitor conduct an AMA location field review with you at least 5 business days before start of work. The Department marks the exact boundaries of the AMA on the ground.

If temporary fence (Type ESA) for an AMA is described in the Contract, install temporary fence (Type ESA) to define the boundaries of the AMA during the AMA location field review.

At least 5 business days before starting work within an AMA, submit a schedule of days and hours to be worked for the Engineer's approval. If you require changes in the schedule, submit an update for the Engineer's approval at least 5 business days before any changed work day.

If archaeological resources are discovered within an AMA, comply with Section 14-2.02, "Archaeological Resources."

### 14-2.04 HISTORIC STRUCTURES

Reserved

## 14-3 COMMUNITY IMPACTS AND ENVIRONMENTAL JUSTICE

Reserved

## 14-4 NATIVE AMERICAN CONCERNS

Reserved

## 14-5 AESTHETICS

Reserved

## 14-6 BIOLOGICAL RESOURCES

### 14-6.01 GENERAL

Reserved

### 14-6.02 BIRD PROTECTION

Protect migratory and nongame birds, their occupied nests, and their eggs.

The Department anticipates nesting or attempted nesting from February 15 to September 1.

The federal Migratory Bird Treaty Act, 16 USC § 703–711, and 50 CFR Pt 10 and Fish & Game Code §§ 3503, 3513, and 3800 protect migratory and nongame birds, their occupied nests, and their eggs.

The federal Endangered Species Act of 1973, 16 USC §§ 1531 and 1543, and the California Endangered Species Act, Fish & Game Code §§ 2050–2115.5, prohibit the take of listed species and protect occupied and unoccupied nests of threatened and endangered bird species.

The Bald and Golden Eagle Protection Act, 16 USC § 668, prohibits the destruction of bald and golden eagles and their occupied and unoccupied nests.

If migratory or nongame bird nests are discovered that may be adversely affected by construction activities or an injured or killed bird is found, immediately:

1. Stop all work within a 100-foot radius of the discovery.
2. Notify the Engineer.

The Department investigates. Do not resume work within the specified radius of the discovery until authorized.

When ordered, use exclusion devices, take nesting prevention measures, remove and dispose of partially constructed and unoccupied nests of migratory or nongame birds on a regular basis to prevent their occupation, or perform any combination of these. This work will be paid for as extra work as specified in Section 4-1.03D, "Extra Work."

Prevent nest materials from falling into waterways.

Bird protection that causes a delay to the controlling activity is a condition unfavorable to the suitable prosecution of work as specified in Section 8-1.05, "Temporary Suspension of Work."

## 14-7 PALEONTOLOGICAL RESOURCES

If paleontological resources are discovered at the job site, do not disturb the material and immediately:

1. Stop all work within a 60-foot radius of the discovery
2. Protect the area
3. Notify the Engineer

The Department investigates and modifies the dimensions of the protected area if necessary. Do not take paleontological resources from the job site. Do not resume work within the specified radius of the discovery until authorized.

## 14-8 NOISE AND VIBRATION

### 14-8.01 GENERAL

Reserved

### 14-8.02 NOISE CONTROL

Do not exceed 86 dBa at 50 feet from the job site activities from 9 p.m. to 6 a.m. Use an alternative warning method instead of a sound signal unless required by safety laws.

Equip an internal combustion engine with the manufacturer-recommended muffler. Do not operate an internal combustion engine on the job site without the appropriate muffler.

## 14-9 AIR QUALITY

### 14-9.01 AIR POLLUTION CONTROL

Comply with air pollution control rules, regulations, ordinances, and statutes that apply to work performed under the Contract, including air pollution control rules, regulations, ordinances, and statutes provided in Govt Code § 11017 (Pub Cont Code § 10231).

Do not burn material to be disposed of.

### 14-9.02 DUST CONTROL

Prevent and alleviate dust by applying water, dust palliative, or both under Section 14-9.01.

Apply water under Section 17, "Watering."

Apply dust palliative under Section 18,"Dust Palliative."

If ordered, apply water, dust palliative, or both to control dust caused by public traffic. This work will be paid for as extra work as specified in Section 4-1.03D, "Extra Work."

## 14-10 SOLID WASTE DISPOSAL AND RECYCLING

### 14-10.01 SOLID WASTE DISPOSAL AND RECYCLING

Submit an annual Solid Waste Disposal and Recycling Report between January 1 and 15 for each year work is performed under the Contract at any time during the previous calendar year. Show the types and amounts of project-generated solid waste taken to or diverted from landfills or reused on the project from January 1 through December 31 of the previous calendar year.

Submit a final annual Solid Waste Disposal and Recycling Report within 5 business days after Contract acceptance. Show the types and amounts of project-generated solid waste taken to or diverted from landfills or reused on the project from January 1 to Contract acceptance.

For each failure to submit a completed form, the Department withholds $10,000.

## 14-11 HAZARDOUS WASTE AND CONTAMINATION

### 14-11.01 GENERAL

Reserved

### 14-11.02 ASBESTOS AND HAZARDOUS SUBSTANCES

Upon discovery, immediately stop working in and notify the Engineer of areas where asbestos or a hazardous substance is present if the:

1. Contractor reasonably believes the substance is asbestos as defined in Labor Code § 6501.7 or a hazardous substance as defined in Health & Safety Code §§ 25316 and 25317
2. Presence is not described in the Contract
3. Substance has not been made harmless

## 14-12 OTHER INTERAGENCY RELATIONS

Reserved

## 14-13 PAYMENT

Payment for work specified in Section 14 is included in the payment for the bid items involved unless:

1. Bid item for the work is shown in the verified Bid Item List
2. Work is specified as paid for as extra work

^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^

# SECTION 15 EXISTING HIGHWAY FACILITIES

**(Issued 05-01-09)**

**In Section 15-1.02 replace the 1st paragraph with:**

Existing facilities which are to remain in place shall be protected in conformance with the provisions in Sections 5-1.18, "Property and Facility Preservation," and 7-1.12, "Indemnification and Insurance."

^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^

## SECTION 19 EARTHWORK

**(Issued 11-21-08)**

**Replace Section 19-1.02 with:**

**19-1.02 (BLANK)**

**Replace Section 19-1.03 with:**

**19-1.03 GRADE TOLERANCE**

Immediately prior to placing subsequent layers of material thereon, the grading plane shall conform to one of the following:

A. When hot mix asphalt is to be placed on the grading plane, the grading plane at any point shall not vary more than 0.05 foot above or below the grade established by the Engineer.
B. When subbase or base material to be placed on the grading plane is to be paid for by the ton, the grading plane at any point shall not vary more than 0.10 foot above or below the grade established by the Engineer.
C. When the material to be placed on the grading plane is to be paid for by the cubic yard, the grading plane at any point shall be not more than 0.05 foot above the grade established by the Engineer.

**In Section 19-3.025C replace the 1st paragraph with:**

Cementitious material used in soil cement bedding shall conform to the provisions in Section 90-2.01, "Cementitious Materials." Supplementary cementitious material will not be required.

**In Section 19-3.025C replace the 4th paragraph with:**

The aggregate, cementitious material, and water shall be proportioned either by weight or by volume. Soil cement bedding shall contain not less than 282 pounds of cementitious material per cubic yard. The water content shall be sufficient to produce a fluid, workable mix that will flow and can be pumped without segregation of the aggregate while being placed.

**In Section 19-3.062 replace the 1st paragraph with:**

Slurry cement backfill shall consist of a fluid, workable mixture of aggregate, cementitious material, and water.

**In Section 19-3.062 replace the 5th paragraph with:**

Cementitious material shall conform to the provisions in Section 90-2.01, "Cementitious Materials." Supplementary cementitious material will not be required.

**In Section 19-3.062 replace the 8th paragraph with:**

The aggregate, cementitious material, and water shall be proportioned either by weight or by volume. Slurry cement backfill shall contain not less than 188 pounds of cementitious material per cubic yard. The water content shall be sufficient to produce a fluid, workable mix that will flow and can be pumped without segregation of the aggregate while being placed.

^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^

## SECTION 20 EROSION CONTROL AND HIGHWAY PLANTING
**(Issued 08-17-07)**

**Replace Section 20-2.03 with:**

### 20-2.03 SOIL AMENDMENT

Soil amendment shall comply with the requirements in the California Food and Agricultural Code.

Soil amendment producers shall comply with the following:

1. Be fully permitted to produce compost as specified under the California Integrated Waste Management Board, Local Enforcement Agencies and any other State and Local Agencies that regulate Solid Waste Facilities. If exempt from State permitting requirements, the composting facility must certify that it follows guidelines and procedures for production of compost meeting the environmental health standards of Title 14, California Code of Regulations, Division 7, Chapter 3.1, Article 7.
2. Be a participant in United States Composting Council's Seal of Testing Assurance program.

Soil amendment shall be composted and may be derived from any single, or mixture of any of the following feedstock materials:

1. Green material consisting of chipped, shredded, or ground vegetation; or clean processed recycled wood products
2. Biosolids
3. Manure
4. Mixed food waste

Soil amendment feedstock materials shall be composted to reduce weed seeds, pathogens and deleterious materials as specified under Title 14, California Code of Regulations, Division 7, Chapter 3.1, Article 7, Section 17868.3.

Soil amendment shall not be derived from mixed municipal solid waste and must be reasonably free of visible contaminates. Soil amendment must not contain paint, petroleum products, pesticides or any other chemical residues harmful to animal life or plant growth. Soil amendment must not possess objectionable odors.

Metal concentrations in soil amendment must not exceed the maximum metal concentrations listed in Title 14, California Code of Regulations, Division 7, Chapter 3.1, Section 17868.2.

Soil amendment must comply with the following:

Physical/Chemical Requirements

| Property | Test Method | Requirement |
|---|---|---|
| pH | *TMECC 04.11-A, Elastometric pH 1:5 Slurry Method, pH Units | 6.0–8.0 |
| Soluble Salts | TMECC 04.10-A, Electrical Conductivity 1:5 Slurry Method dS/m (mmhos/cm) | 0-10.0 |
| Moisture Content | TMECC 03.09-A, Total Solids & Moisture at 70+/- 5 deg C, % Wet Weight Basis | 30–60 |
| Organic Matter Content | TMECC 05.07-A, Loss-On-Ignition Organic Matter Method (LOI), % Dry Weight Basis | 30–65 |
| Maturity | TMECC 05.05-A, Germination and Vigor<br>Seed Emergence<br>Seedling Vigor<br>% Relative to Positive Control | <br>80 or Above<br>80 or Above |
| Stability | TMECC 05.08-B, Carbon Dioxide Evolution Rate mg $CO_2$-C/g OM per day | 8 or below |
| Particle Size | TMECC 02.02-B Sample Sieving for Aggregate Size Classification % Dry Weight Basis | 95% Passing 5/8 inch<br>70% Passing 3/8 inch |
| Pathogen | TMECC 07.01-B, Fecal Coliform Bacteria < 1000 MPN/gram dry wt. | Pass |
| Pathogen | TMECC 07.01-B, Salmonella < 3 MPN/4 grams dry wt. | Pass |
| Physical Contaminants | TMECC 02.02-C, Man Made Inert Removal and Classification:<br>Plastic, Glass and Metal, % > 4mm fraction | Combined Total: < 1.0 |
| Physical Contaminants | TMECC 02.02-C, Man Made Inert Removal and Classification:<br>Sharps (Sewing needles, straight pins and hypodermic needles), % > 4mm fraction | None Detected |

*TMECC refers to "Test Methods for the Examination of Composting and Compost," published by the United States Department of Agriculture and the United States Compost Council (USCC).

Prior to application, the Contractor shall provide the Engineer with a copy of the soil amendment producer's Compost Technical Data Sheet and a copy of the compost producers STA certification. The Compost Technical Data Sheet shall include laboratory analytical test results, directions for product use, and a list of product ingredients.

Prior to application, the Contractor shall provide the Engineer with a Certificate of Compliance in conformance with the provisions in Section 6-1.07, "Certificates of Compliance," of the Standard Specifications.

**In Section 20-2.10 delete the 8th, 9th, and 10th paragraphs.**

**In Section 20-3.04A delete the last paragraph.**

**Replace Section 20-4.055 with:**

**20-4.055 PRUNING**

Pruning of plants shall be consistent with American National Standards Institute (ANSI), "Tree, Shrub and Other Woody Plant Maintenance Standard Practices," ANSI 300 (Part 1)-2001 and "Best Management Practices Tree Pruning," 2002 (ISBN 1-881956318), published by the International Society of Arboriculture, P.O. Boc 3129, Champaign, IL 61826.

^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^

## SECTION 25 AGGREGATE SUBBASES
**(Issued 02-16-07)**

**In Section 25-1.02A replace the 1st paragraph with:**

Aggregate must be clean and free from organic matter and other deleterious substances. Aggregate must consist of any combination of:

1. Broken stone
2. Crushed gravel
3. Natural rough surfaced gravel
4. Sand
5. Up to 100 percent of any combination of processed:

    5.1. Asphalt concrete
    5.2. Portland cement concrete
    5.3. Lean concrete base
    5.4. Cement treated base

**Replace Section 25-1.02B with:**

**25-1.02B Class 4 Aggregate Subbase**

Aggregate must be clean and free from organic matter and other deleterious substances. Aggregate must consist of any combination of:

1. Broken stone
2. Crushed gravel
3. Natural rough surfaced gravel
4. Sand
5. Up to 100 percent of any combination of processed:

    5.1. Asphalt concrete
    5.2. Portland cement concrete
    5.3. Lean concrete base
    5.4. Cement treated base

^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^

## SECTION 26 AGGREGATE BASES
**(Issued 02-16-07)**

**In Section 26-1.02A replace the 1st paragraph with:**

Aggregate must be clean and free from organic matter and other deleterious substances. Aggregate must consist of any combination of:

1. Broken stone
2. Crushed gravel
3. Natural rough surfaced gravel
4. Sand
5. Up to 100 percent of any combination of processed:

    5.1. Asphalt concrete
    5.2. Portland cement concrete
    5.3. Lean concrete base
    5.4. Cement treated base

**In Section 26-1.02B replace the 1st paragraph with:**

Aggregate must be clean and free from organic matter and other deleterious substances. Aggregate must consist of any combination of:

1. Broken stone
2. Crushed gravel
3. Natural rough surfaced gravel
4. Sand
5. Up to 100 percent of any combination of processed:

    5.1. Asphalt concrete
    5.2. Portland cement concrete
    5.3. Lean concrete base
    5.4. Cement treated base

^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^

## SECTION 27 CEMENT TREATED BASES
**(Issued 07-31-07)**

**In Section 27-1.02 replace the 1st paragraph with:**

Cement shall be Type II portland cement conforming to the provisions in Section 90-2.01A, "Cement."

**In Section 27-1.02 replace the 3rd paragraph with:**

Aggregate for use in Class A cement treated base shall be of such quality that when mixed with cement in an amount not to exceed 5 percent by weight of the dry aggregate and compacted at optimum moisture content, the compressive strength of a sample of the compacted mixture shall not be less than 750 pounds per square inch at 7 days, when tested by California Test 312.

**In Section 27-1.02 replace the 4th paragraph with:**

Aggregate for use in Class B cement treated base shall have a Resistance (R-value) of not less than 60 before mixing with cement and a Resistance (R-value) of not less than 80 after mixing with cement in an amount not to exceed 2.5 percent by weight of the dry aggregate.

**In Section 27-1.07 replace the 9th paragraph with:**

When surfacing material is hot mix asphalt, the low areas shall be filled with hot mix asphalt conforming to the requirements for the lowest layer of hot mix asphalt to be placed as surfacing. This filling shall be done as a separate operation prior to placing the lowest layer of surfacing, and full compensation for this filling will be considered as included in the contract price paid for cement treated base and no additional compensation will be allowed therefor.

^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^

## SECTION 28 LEAN CONCRETE BASE
**(Issued 07-31-07)**

**In Section 28-1.02 replace the 1st paragraph with:**

Cement shall be Type II portland cement conforming to the provisions in Section 90-2.01A, "Cement."

**In Section 28-1.02 replace the 6th paragraph with:**

Aggregate shall be of such quality that, when mixed with cement in an amount not to exceed 300 pounds per cubic yard, and tested in conformance with the requirements in California Test 548, the compressive strength of a sample will be not less than 700 pounds per square inch at 7 days.

**In Section 28-1.06 replace the 2nd paragraph with:**

In advance of curing operations, lean concrete base to be surfaced with hot mix asphalt shall be textured with a drag strip of burlap, a broom or a spring steel tine device which will produce scoring in the finished surface. The scoring shall be parallel with the centerline or transverse thereto. The operation shall be performed at a time and in a manner to produce the coarsest texture practical for the method used.

**In Section 28-1.08 replace the 2nd paragraph with:**

Hardened lean concrete base with a surface lower than 0.05 foot below the grade established by the Engineer shall be removed and replaced with lean concrete base which complies with these specifications, or if permitted by the Engineer, the low areas shall be filled with pavement material as follows:

1. When pavement material is hot mix asphalt, the low areas shall be filled with hot mix asphalt conforming to the requirements for the lowest layer of hot mix asphalt to be placed as pavement. This shall be done as a separate operation prior to placing the lowest layer of pavement, and full compensation for this filling will be considered as included in the contract price paid per cubic yard for lean concrete base and no additional compensation will be allowed therefor.
2. When pavement material is portland cement concrete, the low areas shall be filled with pavement concrete at the time and in the same operation that the pavement is placed. Full compensation for this filling will be considered as included in the contract price paid per cubic yard for lean concrete base and no additional compensation will be allowed therefor.

^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^

## SECTION 29 TREATED PERMEABLE BASES
**(Issued 03-13-09)**

**In Section 29-1.02B replace the 2nd paragraph with:**

Cement shall be Type II portland cement conforming to the provisions in Section 90-2.01A, "Cement."

**In Section 29-1.04A replace the 1st paragraph with:**

Aggregates and asphalt for asphalt treated permeable base shall be stored, proportioned and mixed in the same manner provided for storing, proportioning and mixing aggregates and asphalt for hot mix asphalt in Section 39-1.08, "Production," except as follows:

1. The aggregate need not be separated into sizes.
2. The temperature of the aggregate before adding the asphalt binder shall be not less than 275° F nor more than 325° F.
3. Asphalt treated permeable base stored in excess of 2 hours shall not be used in the work.
4. The aggregate shall be combined with 2.5 percent paving asphalt by weight of the dry aggregate. After testing samples of the Contractor's proposed aggregate supply, the Engineer may order an increase or decrease in the asphalt content. If an increase or decrease is ordered, and the increase or decrease exceeds the specified amount by more than 0.1 percent by weight of the dry aggregate, the compensation payable to the Contractor for the asphalt treated permeable base will be increased or decreased on the basis of the total increase or decrease in asphalt.
5. The asphalt content of the asphalt mixture will be determined, at the option of the Engineer, by extraction tests in conformance with the requirements in California Test 310 or 362, or will be determined in conformance with the requirements in California Test 379. The bitumen ratio pounds of asphalt per 100 pounds of dry aggregate shall not

vary by more than 0.5 pound of asphalt above or 0.5 pound of asphalt below the amount designated by the Engineer. Compliance with this requirement will be determined either by taking samples from trucks at the plant or from the mat behind the paver before rolling. If the sample is taken from the mat behind the paver, the bitumen ratio shall be not less than the amount designated by the Engineer, less 0.7 pound of asphalt per 100 pounds of dry aggregate.

**In Section 29-1.04B replace the 2nd paragraph with:**

Cement treated permeable base shall contain not less than 287 pounds of cement per cubic yard.

**In Section 29-1.05 replace the 1st paragraph with:**

Asphalt treated permeable base shall be spread and compacted as specified for hot mix asphalt under the "Method" construction process in Section 39, "Hot Mix Asphalt," and these specifications.

**In Section 29-1.05 in the 8th paragraph, replace the 2nd sentence with:**

The filter fabric shall conform to the provisions in Section 88-1.02, "Filtration," and shall be placed in conformance with the provisions for placing filter fabric for edge drains in Section 68-3.03, "Installation."

**In Section 29-1.06 in the 9th paragraph, replace the 2nd sentence with:**

The filter fabric shall conform to the provisions in Section 88-1.02, "Filtration," and shall be placed in conformance with the provisions for placing filter fabric for edge drains in Section 68-3.03, "Installation."

**In Section 29-1.07 replace the 2nd paragraph with:**

Hardened treated permeable base with a surface lower than 0.05 foot below the grade established by the Engineer shall be removed and replaced with treated permeable base which complies with these specifications, or if permitted by the Engineer, the low areas shall be filled with pavement material as follows:

1. When pavement material is hot mix asphalt, the low areas shall be filled with hot mix asphalt conforming to the requirements for the lowest layer of hot mix asphalt to be placed as pavement. This shall be done as a separate operation prior to placing the lowest layer of pavement.
2. When pavement material is portland cement concrete, the low areas shall be filled with pavement concrete at the time and in the same operation in which the pavement is placed.
3. Full compensation for filling low areas will be considered as included in the contract price paid per cubic yard for treated permeable base and no additional compensation will be allowed therefor.

^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^

## SECTION 37 BITUMINOUS SEALS
**(Issued 08-17-07)**

**In Section 37-1.03 replace the 4th through 6th paragraphs with:**

On 2-lane two-way roadways, W8-7 "LOOSE GRAVEL" signs and W13-1 (35) speed advisory signs shall be furnished and placed adjacent to both sides of the traveled way where screenings are being spread on a traffic lane. The first W8-7 sign in each direction shall be placed where traffic first encounters loose screenings, regardless of which lane the screenings are being spread on. The W13-1 (35) signs need not be placed in those areas with posted speed limits of less than 40 MPH. The signs shall be placed at maximum 2,000-foot intervals along each side of the traveled way and at public roads or streets entering the seal coat area as directed by the Engineer.

On multilane roadways (freeways, expressways and multilane conventional highways) where screenings are being spread on a traffic lane, W8-7 "LOOSE GRAVEL" signs and W13-1 (35) speed advisory signs shall be furnished and placed adjacent to the outside edge of the traveled way nearest to the lane being worked on. The first W8-7 sign shall be placed where the screenings begin with respect to the direction of travel on that lane. The W13-1 (35) signs need not be placed in

those areas with posted speed limits of less than 40 MPH. The signs shall be placed at maximum 2,000-foot intervals along the edge of traveled way and at on-ramps, public roads or streets entering the seal coat area as directed by the Engineer.

The W8-7 and W13-1 signs shall be maintained in place at each location until final brooming of the seal coat surface at that location is completed. The W8-7 and W13-1 signs shall conform to the provisions for construction area signs in Section 12, "Construction Area Traffic Control Devices." The signs may be set on temporary portable supports with the W13-1 below the W8-7 or on barricades with the W13-1 sign alternating with the W8-7 sign.

**In Section 37-1.07 replace the 2nd paragraph with:**

Rollers shall be oscillating type pneumatic-tired rollers. A minimum of 2 pneumatic-tired rollers conforming to the provisions in Section 39-3.03 "Spreading and Compacting Equipment," shall be furnished.

**In Section 37-1.09 replace the 2nd paragraph with:**

The above prices and payments shall include full compensation for furnishing all labor, materials, tools, equipment and incidentals, and for doing all the work involved in applying seal coat, complete in place, including furnishing, placing, maintaining, and removing W8-7 and W13-1 signs, when required, and temporary supports or barricades for the signs, as shown on the plans, and as specified in these specifications and the special provisions, and as directed by the Engineer.

^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^

## SECTION 39 ASPHALT CONCRETE
**(Issued 03-13-09)**

**Replace Section 39 with:**

## SECTION 39 HOT MIX ASPHALT

### 39-1 GENERAL

#### 39-1.01 DESCRIPTION

Section 39 includes specifications for producing and placing hot mix asphalt (HMA) by mixing aggregate and asphalt binder at a mixing plant and spreading and compacting the HMA mixture.

The special provisions specify one or more type of HMA, including:

1. Type A
2. Type B
3. Open graded friction course (OGFC). OGFC includes hot mix asphalt (open graded), rubberized hot mix asphalt (open graded) (RHMA-O) and rubberized hot mix asphalt (open graded high binder) (RHMA-O-HB)
4. Rubberized hot mix asphalt (gap graded) (RHMA-G)

The special provisions specify the HMA construction process, including:

1. Standard
2. Method
3. Quality Control / Quality Assurance (QC / QA)

#### 39-1.02 MATERIALS

##### 39-1.02A Geosynthetic Pavement Interlayer

Geosynthetic pavement interlayer must comply with the specifications for pavement fabric or paving mat in Section 88-1.07, "Pavement Interlayer."

### 39-1.02B Tack Coat

Tack coat must comply with the specifications for asphaltic emulsion in Section 94, "Asphaltic Emulsion," or asphalt binder in Section 92, "Asphalts." Choose the type and grade.

Notify the Engineer if you dilute asphaltic emulsion with water. The weight ratio of added water to asphaltic emulsion must not exceed 1 to 1.

Measure added water either by weight or volume in compliance with the specifications for weighing, measuring, and metering devices under Section 9-1.01, "Measurement of Quantities," or you may use water meters from water districts, cities, or counties. If you measure water by volume, apply a conversion factor to determine the correct weight.

With each dilution, submit in writing:

1. The weight ratio of water to bituminous material in the original asphaltic emulsion
2. The weight of asphaltic emulsion before diluting
3. The weight of added water
4. The final dilution weight ratio of water to asphaltic emulsion

### 39-1.02C Asphalt Binder

Asphalt binder in HMA must comply with Section 92, "Asphalts," or Section 39-1.02D, "Asphalt Rubber Binder." The special provisions specify the grade.

Asphalt binder for geosynthetic pavement interlayer must comply with Section 92, "Asphalts." Choose from Grades PG 64-10, PG 64-16, or PG 70-10.

### 39-1.02D Asphalt Rubber Binder

#### General

Use asphalt rubber binder in RHMA-G, RHMA-O, and RHMA-O-HB. Asphalt rubber binder must be a combination of:

1. Asphalt binder
2. Asphalt modifier
3. Crumb rubber modifier (CRM)

The combined asphalt binder and asphalt modifier must be 80.0 ± 2.0 percent by weight of the asphalt rubber binder.

#### Asphalt Modifier

Asphalt modifier must be a resinous, high flash point, and aromatic hydrocarbon, and comply with:

**Asphalt Modifier for Asphalt Rubber Binder**

| Quality Characteristic | ASTM | Specification |
|---|---|---|
| Viscosity, $m^2/s$ (x $10^{-6}$) at 100 °C | D 445 | X ± 3 [a] |
| Flash Point, CL.O.C., °C | D 92 | 207 minimum |
| Molecular Analysis | | |
| Asphaltenes, percent by mass | D 2007 | 0.1 maximum |
| Aromatics, percent by mass | D 2007 | 55 minimum |

Note:
[a] The symbol "X" is the proposed asphalt modifier viscosity. "X" must be between 19 and 36. A change in "X" requires a new asphalt rubber binder design.

Asphalt modifier must be from 2.0 percent to 6.0 percent by weight of the asphalt binder in the asphalt rubber binder.

#### Crumb Rubber Modifier

CRM consists of a ground or granulated combination of scrap tire CRM and high natural CRM. CRM must be 75.0 ± 2.0 percent scrap tire CRM and 25.0 ± 2.0 percent high natural CRM by total weight of CRM. Scrap tire CRM must be from any combination of automobile tires, truck tires, or tire buffings.

Sample and test scrap tire CRM and high natural CRM separately. CRM must comply with:

**Crumb Rubber Modifier for Asphalt Rubber Binder**

| Quality Characteristic | Test Method | Specification |
|---|---|---|
| Scrap tire CRM gradation (% passing No. 8 sieve) | LP-10 | 100 |
| High natural CRM gradation (% passing No. 10 sieve) | LP-10 | 100 |
| Wire in CRM (% max.) | LP-10 | 0.01 |
| Fabric in CRM (% max.) | LP-10 | 0.05 |
| CRM particle length (inch max.) [a] | -- | 3/16 |
| CRM specific gravity [a] | CT 208 | 1.1 – 1.2 |
| Natural rubber content in high natural CRM (%) [a] | ASTM D 297 | 40.0 – 48.0 |

Note:
[a] Test at mix design and for Certificate of Compliance.

Only use CRM ground and granulated at ambient temperature. If steel and fiber are cryogenically separated, it must occur before grinding and granulating. Only use cryogenically produced CRM particles that can be ground or granulated and not pass through the grinder or granulator.

CRM must be dry, free-flowing particles that do not stick together. CRM must not cause foaming when combined with the asphalt binder and asphalt modifier. You may add calcium carbonate or talc up to 3 percent by weight of CRM.

**Asphalt Rubber Binder Design and Profile**

Submit in writing an asphalt rubber binder design and profile. In the design, designate the asphalt, asphalt modifier, and CRM and their proportions. The profile is not a specification and only serves to indicate expected trends in asphalt rubber binder properties during binder production. The profile must include the same component sources for the asphalt rubber binder used.

Design the asphalt rubber binder from testing you perform for each quality characteristic and for the reaction temperatures expected during production. The 24-hour (1,440-minute) interaction period determines the design profile. At a minimum, mix asphalt rubber binder components, take samples, and perform and record the following tests:

**Asphalt Rubber Binder Reaction Design Profile**

| Test | Minutes of Reaction [a] | | | | | | | Limits |
|---|---|---|---|---|---|---|---|---|
| | 45 | 60 | 90 | 120 | 240 | 360 | 1440 | |
| Cone penetration @ 77 °F, 0.10-mm (ASTM D 217) | X [b] | | | | X | | X | 25 - 70 |
| Resilience @ 77 °F, percent rebound (ASTM D 5329) | X | | | | X | | X | 18 min. |
| Field softening point, °F (ASTM D 36) | X | | | | X | | X | 125 - 165 |
| Viscosity, centipoises (LP-11) | X | X | X | X | X | X | X | 1,500 - 4,000 |

Notes:
[a] Six hours (360 minutes) after CRM addition, reduce the oven temperature to 275 °F for a period of 16 hours. After the 16-hour (1320 minutes) cool-down after CRM addition, reheat the binder to the reaction temperature expected during production for sampling and testing at 24 hours (1440 minutes).
[b] "X" denotes required testing

**Asphalt Rubber Binder**

After interacting for a minimum of 45 minutes, asphalt rubber binder must comply with:

**Asphalt Rubber Binder**

| Quality Characteristic | Test for Quality Control or Acceptance | Test Method | Specification | |
|---|---|---|---|---|
| | | | Minimum | Maximum |
| Cone penetration @ 77 °F, 0.10-mm | Acceptance | ASTM D 217 | 25 | 70 |
| Resilience @ 77 °F, percent rebound | Acceptance | ASTM D 5329 | 18 | -- |
| Field softening point, °F | Acceptance | ASTM D 36 | 125 | 165 |
| Viscosity @ 375 °F, centipoises | Quality Control | LP-11 | 1,500 | 4,000 |

**39-1.02E Aggregate**

Aggregate must be clean and free from deleterious substances. Aggregate:

1. Retained on the No. 4 sieve is coarse
2. Passing the No. 4 sieve is fine
3. Added and passing the No. 30 sieve is supplemental fine, including:

    3.1. Hydrated lime
    3.2. Portland cement
    3.3. Fines from dust collectors

The special provisions specify the aggregate gradation for each HMA type.

The specified aggregate gradation is before the addition of asphalt binder and includes supplemental fines. The Engineer tests for aggregate grading under California Test 202, modified by California Test 105 if there is a difference in specific gravity of 0.2 or more between the coarse and fine parts of different aggregate blends.

Choose a sieve size target value (TV) within each target value limit presented in the aggregate gradation tables.

**Aggregate Gradation**
**(Percentage Passing)**
**HMA Types A and B**

3/4–inch HMA Types A and B

| Sieve Sizes | Target Value Limits | Allowable Tolerance |
|---|---|---|
| 1" | 100 | — |
| 3/4" | 90 - 100 | TV ±5 |
| 1/2" | 70 - 90 | TV ±6 |
| No. 4 | 45 - 55 | TV ±7 |
| No. 8 | 32 - 40 | TV ±5 |
| No. 30 | 12 - 21 | TV ±4 |
| No. 200 | 2 - 7 | TV ±2 |

1/2–inch HMA Types A and B

| Sieve Sizes | Target Value Limits | Allowable Tolerance |
|---|---|---|
| 3/4" | 100 | — |
| 1/2" | 95 - 99 | TV ±6 |
| 3/8" | 75 - 95 | TV ±6 |
| No. 4 | 55 - 66 | TV ±7 |
| No. 8 | 38 - 49 | TV ±5 |
| No. 30 | 15 - 27 | TV ±4 |
| No. 200 | 2 - 8 | TV ±2 |

3/8–inch HMA Types A and B

| Sieve Sizes | Target Value Limits | Allowable Tolerance |
|---|---|---|
| 1/2" | 100 | — |
| 3/8" | 95 - 100 | TV ±6 |
| No. 4 | 58 - 72 | TV ±7 |
| No. 8 | 34 - 48 | TV ±6 |
| No. 30 | 18 - 32 | TV ±5 |
| No. 200 | 2 - 9 | TV ±2 |

No. 4 HMA Types A and B

| Sieve Sizes | Target Value Limits | Allowable Tolerance |
|---|---|---|
| 3/8" | 100 | — |
| No. 4 | 95 - 100 | TV ±7 |
| No. 8 | 72 - 77 | TV ±7 |
| No. 30 | 37 - 43 | TV ±7 |
| No. 200 | 2 - 12 | TV ±4 |

**Rubberized Hot Mix Asphalt - Gap Graded (RHMA-G)**

3/4–inch RHMA-G

| Sieve Sizes | Target Value Limits | Allowable Tolerance |
|---|---|---|
| 1" | 100 | — |
| 3/4" | 95 - 100 | TV ±5 |
| 1/2" | 83 - 87 | TV ±6 |
| 3/8" | 65 - 70 | TV ±6 |
| No. 4 | 28 - 42 | TV ±7 |
| No. 8 | 14 - 22 | TV ±5 |
| No. 200 | 0 - 6 | TV ±2 |

1/2–inch RHMA-G

| Sieve Sizes | Target Value Limits | Allowable Tolerance |
|---|---|---|
| 3/4" | 100 | — |
| 1/2" | 90 - 100 | TV ±6 |
| 3/8" | 83 - 87 | TV ±6 |
| No. 4 | 28 - 42 | TV ±7 |
| No. 8 | 14 - 22 | TV ±5 |
| No. 200 | 0 - 6 | TV ±2 |

**Open Graded Friction Course (OGFC)**

1–inch OGFC

| Sieve Sizes | Target Value Limits | Allowable Tolerance |
|---|---|---|
| 1 1/2" | 100 | — |
| 1" | 99 - 100 | TV ±5 |
| 3/4" | 85 - 96 | TV ±5 |
| 1/2" | 55 - 71 | TV ±6 |
| No. 4 | 10 - 25 | TV ±7 |
| No. 8 | 6 - 16 | TV ±5 |
| No. 200 | 1 - 6 | TV ±2 |

1/2–inch OGFC

| Sieve Sizes | Target Value Limits | Allowable Tolerance |
|---|---|---|
| 3/4" | 100 | — |
| 1/2" | 95 - 100 | TV ±6 |
| 3/8" | 78 - 89 | TV ±6 |
| No. 4 | 28 - 37 | TV ±7 |
| No. 8 | 7 - 18 | TV ±5 |
| No. 30 | 0 - 10 | TV ±4 |
| No. 200 | 0 - 3 | TV ±2 |

3/8–inch OGFC

| Sieve Sizes | Target Value Limits | Allowable Tolerance |
|---|---|---|
| 1/2" | 100 | — |
| 3/8" | 90 - 100 | TV ±6 |
| No. 4 | 29 - 36 | TV ±7 |
| No. 8 | 7 - 18 | TV ±6 |
| No. 30 | 0 - 10 | TV ±5 |
| No. 200 | 0 - 3 | TV ±2 |

Before the addition of asphalt binder and lime treatment, aggregate must comply with:

**Aggregate Quality**

| Quality Characteristic | Test Method | HMA Type | | | |
|---|---|---|---|---|---|
| | | A | B | RHMA-G | OGFC |
| Percent of crushed particles | CT 205 | | | | |
| Coarse aggregate (% min.) | | | | | |
| One fractured face | | 90 | 25 | -- | 90 |
| Two fractured faces | | 75 | -- | 90 | 75 |
| Fine aggregate (% min) (Passing No. 4 sieve and retained on No. 8 sieve.) | | | | | |
| One fractured face | | 70 | 20 | 70 | 90 |
| Los Angeles Rattler (% max.) | CT 211 | | | | |
| Loss at 100 Rev. | | 12 | -- | 12 | 12 |
| Loss at 500 Rev. | | 45 | 50 | 40 | 40 |
| Sand equivalent (min.) [a] | CT 217 | 47 | 42 | 47 | -- |
| Fine aggregate angularity (% min.) [b] | AASHTO T 304 Method A | 45 | 45 | 45 | -- |
| Flat and elongated particles (% max. by weight @ 5:1) | ASTM D 4791 | 10 | 10 | 10 | 10 |

Notes:
[a] Reported value must be the average of 3 tests from a single sample.
[b] The Engineer waives this specification if HMA contains less than 10 percent of nonmanufactured sand by weight of total aggregate. Manufactured sand is fine aggregate produced by crushing rock or gravel.

### 39-1.02F Reclaimed Asphalt Pavement

You may produce HMA using reclaimed asphalt pavement (RAP). HMA produced using RAP must comply with the specifications for HMA except aggregate quality specifications do not apply to RAP. You may substitute RAP aggregate for a part of the virgin aggregate in HMA in a quantity not exceeding 15.0 percent of the aggregate blend. Do not use RAP in OGFC and RHMA-G.

Assign the substitution rate of RAP aggregate for virgin aggregate with the job mix formula (JMF) submittal. The JMF must include the percent of RAP used. If you change your assigned RAP aggregate substitution rate by more than 5 percent (within the 15.0 percent limit), submit a new JMF.

Process RAP from asphalt concrete. You may process and stockpile RAP throughout the project's life. Prevent material contamination and segregation. Store RAP in stockpiles on smooth surfaces free of debris and organic material. Processed RAP stockpiles must consist only of homogeneous RAP.

## 39-1.03 HOT MIX ASPHALT MIX DESIGN REQUIREMENTS

### 39-1.03A General

A mix design consists of performing California Test 367 and laboratory procedures on combinations of aggregate gradations and asphalt binder contents to determine the optimum binder content (OBC) and HMA mixture qualities. If RAP is used, use Laboratory Procedure LP-9. The result of the mix design becomes the proposed JMF.

Use Form CEM-3512 to document aggregate quality and mix design data. Use Form CEM-3511 to present the JMF.

Laboratories testing aggregate qualities and preparing the mix design and JMF must be qualified under the Department's Independent Assurance Program. Take samples under California Test 125.

The Engineer reviews the aggregate qualities, mix design, and JMF and verifies and accepts the JMF.

You may change the JMF during production. Do not use the changed JMF until the Engineer accepts it. Except when adjusting the JMF in compliance with Section 39-1.03E, "Job Mix Formula Verification," perform a new mix design and submit in writing a new JMF submittal for changing any of the following:

1. Target asphalt binder percentage
2. Asphalt binder supplier
3. Asphalt rubber binder supplier
4. Component materials used in asphalt rubber binder or percentage of any component materials
5. Combined aggregate gradation
6. Aggregate sources
7. Substitution rate for RAP aggregate of more than 5 percent

8. Any material in the JMF

For OGFC, submit in writing a complete JMF submittal except asphalt binder content. The Engineer determines the asphalt binder content under California Test 368 within 20 days of your complete JMF submittal and provides you a Form CEM-3513.

**39-1.03B Hot Mix Asphalt Mix Design**

Perform a mix design that produces HMA in compliance with:

**Hot Mix Asphalt Mix Design Requirements**

| Quality Characteristic | Test Method | HMA Type | | |
|---|---|---|---|---|
| | | A | B | RHMA-G |
| Air voids content (%) | CT 367[a] | 4.0 | 4.0 | Special Provisions |
| Voids in mineral aggregate (% min.) | LP-2 | | | |
| No. 4 grading | | 17.0 | 17.0 | -- |
| 3/8" grading | | 15.0 | 15.0 | -- |
| 1/2" grading | | 14.0 | 14.0 | 18.0 – 23.0[b] |
| 3/4" grading | | 13.0 | 13.0 | 18.0 – 23.0[b] |
| Voids filled with asphalt (%) | LP-3 | | | |
| No. 4 grading | | 76.0 – 80.0 | 76.0 – 80.0 | Note d |
| 3/8" grading | | 73.0 – 76.0 | 73.0 – 76.0 | |
| 1/2" grading | | 65.0 – 75.0 | 65.0 – 75.0 | |
| 3/4" grading | | 65.0 – 75.0 | 65.0 – 75.0 | |
| Dust proportion | LP-4 | | | |
| No. 4 and 3/8" gradings | | 0.9 – 2.0 | 0.9 – 2.0 | Note d |
| 1/2" and 3/4" gradings | | 0.6 – 1.3 | 0.6 – 1.3 | |
| Stabilometer value (min.) [c] | CT 366 | | | |
| No. 4 and 3/8" gradings | | 30 | 30 | -- |
| 1/2" and 3/4" gradings | | 37 | 35 | 23 |

Notes:

[a] Calculate the air voids content of each specimen using California Test 309 and Lab Procedure LP-1. Modify California Test 367, Paragraph C5, to use the exact air voids content specified in the selection of OBC.
[b] Voids in mineral aggregate for RHMA-G must be within this range.
[c] Modify California Test 304, Part 2.B.2.c: "After compaction in the compactor, cool to 140 °± 5 °F by allowing the briquettes to cool at room temperature for 0.5-hour, then place the briquettes in the oven at 140 °F for a minimum of 2 hours and not more than 3 hours."
[d] Report this value in the JMF submittal.

For stability and air voids content, prepare 3 briquettes at the OBC and test for compliance. Report the average of 3 tests. Prepare new briquettes and test if the range of stability for the 3 briquettes is more than 8 points. The average air void content may vary from the specified air void content by ±0.5 percent.

You may use the briquettes used for stability testing to determine bulk specific gravity under CT 308. If you use the same briquettes and tests using bulk specific gravity fail, you may prepare 3 new briquettes and determine a new bulk specific gravity.

**39-1.03C Job Mix Formula Submittal**

Each JMF submittal must consist of:

1. Proposed JMF on Form CEM-3511
2. Mix design documentation on Form CEM-3512 dated within 12 months of submittal
3. JMF verification on Form CEM-3513, if applicable
4. Materials Safety Data Sheets (MSDS) for:

   4.1. Asphalt binder
   4.2. Base asphalt binder used in asphalt rubber binder
   4.3. CRM and asphalt modifier used in asphalt rubber binder

4.4. Blended asphalt rubber binder mixture
4.5. Supplemental fine aggregate except fines from dust collectors
4.6. Antistrip additives

If the JMF must be verified or if the Engineer requests, submit samples of the following materials in labeled containers weighing no more than 50 pounds each (notify the Engineer at least 2 business days before sampling materials):

1. Coarse, fine, and supplemental fine aggregate from stockpiles, cold feed belts, or hot bins. Samples must include at least 120 pounds for each coarse aggregate, 80 pounds for each fine aggregate, and 10 pounds for each type of supplemental fines. The Department combines these aggregate samples to comply with the JMF target values submitted on Form CEM-3511.
2. RAP from stockpiles or RAP system. Samples must be at least 60 pounds.
3. Asphalt binder from the binder supplier. Samples must be in two 1-quart cylindrical shaped cans with open top and friction lids.
4. Asphalt rubber binder with the components blended in the proportions to be used. Samples must be in four 1-quart cylindrical shaped cans with open top and friction lids.

**39-1.03D Job Mix Formula Review**

The Engineer reviews each mix design and proposed JMF within 5 business days from the complete JMF submittal. The review consists of reviewing the mix design procedures and comparing the proposed JMF with the specifications.

The Engineer may verify aggregate qualities during this review period.

**39-1.03E Job Mix Formula Verification**

If you cannot submit a Department-verified JMF on Form CEM-3513 dated within 12 months before HMA production, the Engineer verifies the JMF.

Based on your testing and production experience, you may submit on Form CEM-3511 an adjusted JMF before the Engineer's verification testing. JMF adjustments may include a change in the:

1. Asphalt binder content target value up to ±0.6 percent from the optimum binder content value submitted on Form CEM-3512 except do not adjust the target value for asphalt rubber binder for RHMA-G below 7.0 percent
2. Aggregate gradation target values within the target value limits specified in the aggregate gradation tables

Test samples from the HMA plant to be used to determine possible JMF adjustments.

For HMA Type A, Type B, and RHMA-G, the Engineer verifies the JMF from samples taken from HMA produced by the plant to be used. The Engineer verifies each proposed JMF within 20 days of receiving verification samples. Verification is testing for compliance with the specifications for:

1. Aggregate quality
2. Aggregate gradation (JMF TV ± tolerance)
3. Asphalt binder content (JMF TV ± tolerance)
4. HMA quality specified in the table Hot Mix Asphalt Mix Design Requirements except:

   4.1. Air voids content (design value ± 2.0 percent)
   4.2. Voids filled with asphalt (report only if an adjustment for asphalt binder content target value is less than or equal to ± 0.3 percent from OBC)
   4.3. Dust proportion (report only if an adjustment for asphalt binder content target value is less than or equal to ± 0.3 percent from OBC)

If you request in writing, the Engineer verifies RHMA-G quality requirements within 3 business days of sampling.

In the Engineer's presence and from the same production run, take samples of:

1. Aggregate
2. Asphalt binder
3. RAP
4. HMA

Sample aggregate from cold feed belts or hot bins. Sample RAP from the RAP system. Sample HMA under California Test 125 except if you request in writing and the Engineer approves, you may sample from any of the following locations:

1. The plant
2. A truck
3. A windrow
4. The paver hopper
5. The mat behind the paver

You may sample from a different project including a non-Department project if you make arrangements for the Engineer to be present during sampling.

For aggregate, RAP, and HMA, split the samples into at least 4 parts and label their containers. Submit 3 split parts to the Engineer and use 1 part for your testing.

The Engineer prepares 3 briquettes from a single split sample. To verify the JMF for stability, the Engineer tests the 3 briquettes and reports the average of 3 tests. The Engineer prepares new briquettes if the range of stability for the 3 briquettes is more than 8 points.

The Engineer may use the briquettes used for stability testing to determine bulk specific gravity under CT 308. If the Engineer uses the same briquettes and the tests using bulk specific gravity fail, the Engineer prepares 3 new briquettes and determines a new bulk specific gravity.

If the Engineer verifies the JMF, the Engineer provides you a Form CEM-3513.

If the Engineer's tests on plant-produced samples do not verify the JMF, the Engineer notifies you in writing and you must submit a new JMF submittal or submit an adjusted JMF based on your testing. JMF adjustments may include a change in the:

1. Asphalt binder content target value up to ±0.6 percent from the optimum binder content value submitted on Form CEM-3512 except do not adjust the target value for asphalt rubber binder for RHMA-G below 7.0 percent
2. Aggregate gradation target values within the target value limits specified in the aggregate gradation tables

You may adjust the JMF only once due to a failed verification test. An adjusted JMF requires a new Form CEM-3511 and verification of a plant-produced sample.

The Engineer reverifies the JMF if HMA production has stopped for longer than 30 days and the verified JMF is older than 12 months.

For each HMA type and aggregate size specified, the Engineer verifies at the State's expense up to 2 proposed JMF including a JMF adjusted after verification failure. The Engineer deducts $3,000 from payments for each verification exceeding this limit. This deduction does not apply to verifications initiated by the Engineer or if a JMF expires while HMA production is stopped longer than 30 days.

**39-1.03F Job Mix Formula Renewal**

You may request a JMF renewal by submitting the following:

1. Proposed JMF on Form CEM-3511
2. A previously verified JMF documented on Form CEM-3513 dated within 12 months
3. Mix design documentation on Form CEM-3512 used for the previously verified JMF
4. Samples of aggregates, asphalt binder, and additives
5. Samples of the following materials obtained in the presence of the Engineer and placed in labeled containers weighing no more than 50 pounds each:

    5.1. Coarse, fine, and supplemental fine aggregate from stockpiles, cold feed belts, or hot bins. Samples must include at least 120 pounds for each coarse aggregate, 80 pounds for each fine aggregate, and 10 pounds for each type of supplemental fines. The Department combines these aggregate samples to comply with the JMF target values submitted on Form CEM-3511.

    5.2. RAP from stockpiles or RAP system. Samples must be at least 60 pounds.

    5.3. Asphalt binder from the binder supplier. Samples must be in two 1-quart cylindrical shaped cans with open top and friction lids.

    5.4. Asphalt rubber binder with the components blended in the proportions to be used. Samples must be in four 1-quart cylindrical shaped cans with open top and friction lids.

Notify the Engineer in writing at least 2 business days before sampling materials. Split samples into at least 2 parts. You must test 1 part and provide the Engineer a part. The Engineer retains samples until you provide test results for your part on Form CEM-3514.

The Engineer reviews each proposed JMF within 5 business days from the complete JMF submittal and test results. The review consists of reviewing the mix design procedures, test results from the split samples and comparing the proposed JMF with the specifications.

The Engineer may verify aggregate qualities during this review period.

The Engineer verifies the JMF under Section 39-1.03E, "Job Mix Formula Verification," except:

1. The Engineer verifies each proposed JMF within 30 days of receiving verification samples.
2. You may not adjust the JMF due to a failed verification.
3. For each HMA type and aggregate gradation specified, the Engineer verifies at the State's expense 1 proposed JMF.
4. If the Engineer verifies the JMF renewal, the Engineer provides you a Form CEM-3513.

### 39-1.03G Job Mix Formula Acceptance

You may start HMA production if:

1. The Engineer's review of the JMF shows compliance with the specifications.
2. The Department has verified the JMF within 12 months before HMA production.
3. The Engineer accepts the verified JMF.

## 39-1.04 CONTRACTOR QUALITY CONTROL

### 39-1.04A General

Establish, maintain, and change a quality control system to ensure materials and work comply with the specifications. Submit quality control test results to the Engineer within 3 days of a request except when QC / QA is specified.

You must identify the HMA sampling location in your Quality Control Plan. During production, take samples under California Test 125 except if you request in writing and the Engineer approves, you may sample HMA from:

1. The plant
2. The truck
3. A windrow
4. The paver hopper
5. The mat behind the paver

### 39-1.04B Prepaving Conference

Meet with the Engineer at a prepaving conference at a mutually agreed time and place. Discuss methods of performing the production and paving work.

### 39-1.04C Asphalt Rubber Binder

Take asphalt rubber binder samples from the feed line connecting the asphalt rubber binder tank to the HMA plant. Sample and test asphalt rubber binder under Laboratory Procedure LP-11.

Test asphalt rubber binder for compliance with the viscosity specifications in Section 39-1.02, "Materials." During asphalt rubber binder production and HMA production using asphalt rubber binder, measure viscosity every hour with not less than 1 reading for each asphalt rubber binder batch. Log measurements with corresponding time and asphalt rubber binder temperature. Submit the log daily in writing.

Submit a Certificate of Compliance under Section 6-1.07, "Certificates of Compliance." With the Certificate of Compliance, submit test results in writing for CRM and asphalt modifier with each truckload delivered to the HMA plant. A Certificate of Compliance for asphalt modifier must not represent more than 5,000 pounds. Use an AASHTO-certified laboratory for testing.

Sample and test gradation and wire and fabric content of CRM once per 10,000 pounds of scrap tire CRM and once per 3,400 pounds of high natural CRM. Sample and test scrap tire CRM and high natural CRM separately.

Submit certified weight slips in writing for the CRM and asphalt modifier furnished.

### 39-1.04D Aggregate

Determine the aggregate moisture content and RAP moisture content in continuous mixing plants at least twice a day during production and adjust the plant controller. Determine the RAP moisture content in batch mixing plants at least twice a day during production and adjust the plant controller.

### 39-1.04E Reclaimed Asphalt Pavement

Perform RAP quality control testing each day.

Sample RAP once daily and determine the RAP aggregate gradation under Laboratory Procedure LP-9 and submit the results to the Engineer in writing with the combined aggregate gradation.

### 39-1.04F Density Cores

To determine density for Standard and QC / QA projects, take 4-inch or 6-inch diameter density cores at least once every 5 business days. Take 1 density core for every 250 tons of HMA from random locations the Engineer designates. Take density cores in the Engineer's presence and backfill and compact holes with material authorized by the Engineer. Before submitting a density core to the Engineer, mark it with the density core's location and place it in a protective container.

If a density core is damaged, replace it with a density core taken within 1 foot longitudinally from the original density core. Relocate any density core located within 1 foot of a rumble strip to 1 foot transversely away from the rumble strip.

### 39-1.04G Briquettes

Prepare 3 briquettes for each stability and air voids content determination. Report the average of 3 tests. Prepare new briquettes and test if the range of stability for the 3 briquettes is more than 12 points.

You may use the briquettes used for stability testing to determine bulk specific gravity under CT 308. If you use these briquettes and tests using bulk specific gravity fail, you may prepare 3 new briquettes and determine a new bulk specific gravity.

## 39-1.05 ENGINEER'S ACCEPTANCE

The Engineer's acceptance of HMA is specified in the sections for each HMA construction process.

The Engineer samples materials for testing under California Test 125 and the applicable test method except samples may be taken from:

1. The plant from:

    1.1. A truck
    1.2. An automatic sampling device

2. The mat behind the paver

Sampling must be independent of Contractor quality control, statistically-based, and random.

If you request, the Engineer splits samples and provides you with a part.

The Engineer accepts HMA based on:

1. Accepted JMF
2. Accepted QCP for Standard and QC / QA
3. Compliance with the HMA Acceptance tables
4. Acceptance of a lot for QC / QA
5. Visual inspection

The Engineer prepares 3 briquettes for each stability and air voids content determination. The Engineer reports the average of 3 tests. The Engineer prepares new briquettes and test if the range of stability for the 3 briquettes is more than 8 points.

The Engineer may use the briquettes used for stability testing to determine bulk specific gravity under CT 308. If the Engineer uses the same briquettes and the tests using bulk specific gravity fail, the Engineer prepares 3 new briquettes and determines a new bulk specific gravity.

## 39-1.06 DISPUTE RESOLUTION

You and the Engineer must work together to avoid potential conflicts and to resolve disputes regarding test result discrepancies. Notify the Engineer in writing within 5 days of receiving a test result if you dispute the test result.

If you or the Engineer dispute each other's test results, submit written quality control test results and copies of paperwork including worksheets used to determine the disputed test results to the Engineer. An Independent Third Party (ITP) performs referee testing. Before the ITP participates in a dispute resolution, the ITP must be accredited under the Department's Independent Assurance Program. The ITP must be independent of the project. By mutual agreement, the ITP is chosen from:

1. A Department laboratory
2. A Department laboratory in a district or region not in the district or region the project is located
3. The Transportation Laboratory
4. A laboratory not currently employed by you or your HMA producer

If split quality control or acceptance samples are not available, the ITP uses any available material representing the disputed HMA for evaluation.

## 39-1.07 PRODUCTION START-UP EVALUATION

The Engineer evaluates HMA production and placement at production start-up.

Within the first 750 tons produced on the first day of HMA production, in the Engineer's presence and from the same production run, take samples of:

1. Aggregate
2. Asphalt binder
3. RAP
4. HMA

Sample aggregate from cold feed belts or hot bins. Take RAP samples from the RAP system. Sample HMA under California Test 125 except if you request in writing and the Engineer approves, you may sample HMA from:

1. The plant
2. The truck
3. A windrow
4. The paver hopper
5. The mat behind the paver

For aggregate, RAP, and HMA, split the samples into at least 4 parts and label their containers. Submit 3 split parts to the Engineer and keep 1 part.

For Standard and QC / QA projects, you and the Engineer must test the split samples and report test results in writing within 3 business days of sampling. If you proceed before receipt of the test results, the Engineer may consider the HMA placed to be represented by these test results.

For Standard and QC / QA projects, take 4-inch or 6-inch diameter density cores within the first 750 tons on the first day of HMA production. For each density core, the Engineer reports the bulk specific gravity determined under California Test 308, Method A in addition to the percent of maximum theoretical density. You may test for in-place density at the density core locations and include them in your production tests for percent of maximum theoretical density.

## 39-1.08 PRODUCTION

### 39-1.08A General

Produce HMA in a batch mixing plant or a continuous mixing plant. Proportion aggregate by hot or cold feed control.

HMA plants must be Department-qualified. Before production, the HMA plant must have a current qualification under the Department's Materials Plant Quality Program.

During production, you may adjust:

1. Hot or cold feed proportion controls for virgin aggregate and RAP
2. The set point for asphalt binder content

### 39-1.08B Mixing

Mix HMA ingredients into a homogeneous mixture of coated aggregates.

Asphalt binder must be between 275 °F and 375 °F when mixed with aggregate.

Asphalt rubber binder must be between 375 °F and 425 °F when mixed with aggregate.

When mixed with asphalt binder, aggregate must not be more than 325 °F except aggregate for OGFC with unmodified asphalt binder must be not more than 275 °F. Aggregate temperature specifications do not apply when you use RAP.

HMA with or without RAP must not be more than 325 °F.

### 39-1.08C Asphalt Rubber Binder

Deliver scrap tire CRM and high natural CRM in separate bags.

Either proportion and mix asphalt binder, asphalt modifier, and CRM simultaneously or premix the asphalt binder and asphalt modifier before adding CRM. If you premix asphalt binder and asphalt modifier, mix them for at least 20 minutes. When you add CRM, the asphalt binder and asphalt modifier must be between 375 °F and 440 °F.

Do not use asphalt rubber binder during the first 45 minutes of the reaction period. During this period, the asphalt rubber binder mixture must be between 350 °F and the lower of 425 °F or 25 °F below the asphalt binder's flash point indicated in the MSDS.

If any asphalt rubber binder is not used within 4 hours after the reaction period, discontinue heating. If the asphalt rubber binder drops below 375 °F, reheat before use. If you add more scrap tire CRM to the reheated asphalt rubber binder, the binder must undergo a 45-minute reaction period. The added scrap tire CRM must not exceed 10 percent of the total asphalt rubber binder weight. Reheated and reacted asphalt rubber binder must comply with the viscosity specifications for asphalt rubber binder in Section 39-1.02, "Materials." Do not reheat asphalt rubber binder more than twice.

## 39-1.09 SUBGRADE, TACK COAT, AND GEOSYNTHETIC PAVEMENT INTERLAYER

### 39-1.09A General

Prepare subgrade or apply tack coat to surfaces receiving HMA. If specified, place geosynthetic pavement interlayer over a coat of asphalt binder.

### 39-1.09B Subgrade

Subgrade to receive HMA must comply with the compaction and elevation tolerance specifications in the sections for the material involved. Subgrade must be free of loose and extraneous material. If HMA is paved on existing base or pavement, remove loose paving particles, dirt, and other extraneous material by any means including flushing and sweeping.

### 39-1.09C Tack Coat

Apply tack coat:

1. To existing pavement including planed surfaces
2. Between HMA layers
3. To vertical surfaces of:

    3.1. Curbs
    3.2. Gutters
    3.3. Construction joints

Before placing HMA, apply tack coat in 1 application at the minimum residual rate specified for the condition of the underlying surface:

**Tack Coat Application Rates for HMA Type A, Type B, and RHMA-G**

| HMA over: | Minimum Residual Rates (gallons per square yard) | | |
|---|---|---|---|
| | CSS1/CSS1h, SS1/SS1h and QS1h/CQS1h Asphaltic Emulsion | CRS1/CRS2, RS1/RS2 and QS1/CQS1 Asphaltic Emulsion | Asphalt Binder and PMRS2/PMCRS2 and PMRS2h/PMCRS2h Asphaltic Emulsion |
| New HMA (between layers) | 0.02 | 0.03 | 0.02 |
| Existing AC and PCC pavement | 0.03 | 0.04 | 0.03 |
| Planed pavement | 0.05 | 0.06 | 0.04 |

**Tack Coat Application Rates for OGFC**

| OGFC over: | Minimum Residual Rates (gallons per square yard) | | |
|---|---|---|---|
| | CSS1/CSS1h, SS1/SS1h and QS1h/CQS1h Asphaltic Emulsion | CRS1/CRS2, RS1/RS2 and QS1/CQS1 Asphaltic Emulsion | Asphalt Binder and PMRS2/PMCRS2 and PMRS2h/PMCRS2h Asphaltic Emulsion |
| New HMA | 0.03 | 0.04 | 0.03 |
| Existing AC and PCC pavement | 0.05 | 0.06 | 0.04 |
| Planed pavement | 0.06 | 0.07 | 0.05 |

If you dilute asphaltic emulsion, mix until homogeneous before application.

Apply to vertical surfaces with a residual tack coat rate that will thoroughly coat the vertical face without running off.

If you request in writing and the Engineer authorizes, you may:

1. Change tack coat rates
2. Omit tack coat between layers of new HMA during the same work shift if:

    2.1. No dust, dirt, or extraneous material is present
    2.2. The surface is at least 140 °F

Immediately in advance of placing HMA, apply additional tack coat to damaged areas or where loose or extraneous material is removed.

Close areas receiving tack coat to traffic. Do not track tack coat onto pavement surfaces beyond the job site.

Asphalt binder tack coat must be between 285 °F and 350 °F when applied.

**39-1.09D Geosynthetic Pavement Interlayer**

Place geosynthetic pavement interlayer in compliance with the manufacturer's recommendations.

Before placing the geosynthetic pavement interlayer and asphalt binder:

1. Repair cracks 1/4 inch and wider, spalls, and holes in the pavement. The State pays for this repair work under Section 4-1.03D, "Extra Work."
2. Clean the pavement of loose and extraneous material.

Immediately before placing the interlayer, apply 0.25 gallon ± 0.03 gallon of asphalt binder per square yard of interlayer or until the fabric is saturated. Apply asphalt binder the width of the geosynthetic pavement interlayer plus 3 inches on each side. At interlayer overlaps, apply asphalt binder on the lower interlayer the same overlap distance as the upper interlayer.

Align and place the interlayer with no overlapping wrinkles, except a wrinkle that overlaps may remain if it is less than 1/2 inch thick. If the overlapping wrinkle is more than 1/2 inch thick, cut the wrinkle out and overlap the interlayer no more than 2 inches.

The minimum HMA thickness over the interlayer must be 0.12 foot thick including conform tapers. Do not place the interlayer on a wet or frozen surface.

Overlap the interlayer borders between 2 inches and 4 inches. In the direction of paving, overlap the following roll with the preceding roll at any break.

You may use rolling equipment to correct distortions or wrinkles in the interlayer.

If asphalt binder tracked onto the interlayer or brought to the surface by construction equipment causes interlayer displacement, cover it with a small quantity of HMA.

Before placing HMA on the interlayer, do not expose the interlayer to:

1. Traffic except for crossings under traffic control and only after you place a small HMA quantity
2. Sharp turns from construction equipment
3. Damaging elements

Pave HMA on the interlayer during the same work shift.

**39-1.10 Spreading And Compacting Equipment**

Paving equipment for spreading must be:

1. Self-propelled
2. Mechanical
3. Equipped with a screed or strike-off assembly that can distribute HMA the full width of a traffic lane
4. Equipped with a full-width compacting device
5. Equipped with automatic screed controls and sensing devices that control the thickness, longitudinal grade, and transverse screed slope

Install and maintain grade and slope references.

The screed must produce a uniform HMA surface texture without tearing, shoving, or gouging.

The paver must not leave marks such as ridges and indentations unless you can eliminate them by rolling.

Rollers must be equipped with a system that prevents HMA from sticking to the wheels. You may use a parting agent that does not damage the HMA or impede the bonding of layers.

In areas inaccessible to spreading and compacting equipment:

1. Spread the HMA by any means to obtain the specified lines, grades and cross sections.
2. Use a pneumatic tamper, plate compactor, or equivalent to achieve thorough compaction.

**39-1.11 Transporting, Spreading, And Compacting**

Do not pave HMA on a wet pavement or frozen surface.

You may deposit HMA in a windrow and load it in the paver if:

1. Paver is equipped with a hopper that automatically feeds the screed
2. Loading equipment can pick up the windrowed material and deposit it in the paver hopper without damaging base material
3. Activities for deposit, pick-up, loading, and paving are continuous
4. HMA temperature in the windrow does not fall below 260 °F

You may pave HMA in 1 or more layers on areas less than 5 feet wide and outside the traveled way including shoulders. You may use mechanical equipment other than a paver for these areas. The equipment must produce a uniform smoothness and texture.

HMA handled, spread, or windrowed must not stain the finished surface of any improvement including pavement.

Do not use petroleum products such as kerosene or diesel fuel to release HMA from trucks, spreaders, or compactors.

HMA must be free of:

1. Segregation
2. Coarse or fine aggregate pockets
3. Hardened lumps

Longitudinal joints in the top layer must match specified lane edges. Alternate longitudinal joint offsets in lower layers at least 0.5 foot from each side of the specified lane edges. You may request in writing other longitudinal joint placement patterns.

Until the adjoining through lane's top layer has been paved, do not pave the top layer of:

1. Shoulders

2. Tapers
3. Transitions
4. Road connections
5. Driveways
6. Curve widenings
7. Chain control lanes
8. Turnouts
9. Turn pockets

If the number of lanes change, pave each through lane's top layer before paving a tapering lane's top layer. Simultaneous to paving a through lane's top layer, you may pave an adjoining area's top layer including shoulders. Do not operate spreading equipment on any area's top layer until completing final compaction.

If HMA (leveling) is specified, fill and level irregularities and ruts with HMA before spreading HMA over base, existing surfaces, or bridge decks. You may use mechanical equipment other than a paver for these areas. The equipment must produce a uniform smoothness and texture. HMA used to change an existing surface's cross slope or profile is not HMA (leveling).

If placing HMA against the edge of existing pavement, sawcut or grind the pavement straight and vertical along the joint and remove extraneous material without damaging the surface remaining in place. If placing HMA against the edge of a longitudinal or transverse construction joint and the joint is damaged or not placed to a neat line, sawcut or grind the pavement straight and vertical along the joint and remove extraneous material without damaging the surface remaining in place. Repair or remove and replace damaged pavement at your expense.

Rolling must leave the completed surface compacted and smooth without tearing, cracking, or shoving. Complete finish rolling activities before the pavement surface temperature is:

1. Below 150 °F for HMA with unmodified binder
2. Below 140 °F for HMA with modified binder
3. Below 200 °F for RHMA-G

If a vibratory roller is used as a finish roller, turn the vibrator off.

Do not use a pneumatic tired roller to compact RHMA-G.

For Standard and QC/QA, if a 3/4-inch aggregate grading is specified, you may use a 1/2-inch aggregate grading if the specified paved thickness is from 0.15 foot to 0.20 foot thick.

Spread and compact HMA under Section 39-3.03, "Spreading and Compacting Equipment," and Section 39-3.04, "Transporting, Spreading, and Compacting," for any of the following:

1. Specified paved thickness is less than 0.15 foot.
2. Specified paved thickness is less than 0.20 foot and a 3/4-inch aggregate grading is specified and used.
3. You spread and compact at:

    3.1. Asphalt concrete surfacing replacement areas
    3.2. Leveling courses
    3.3. Areas the Engineer determines conventional compaction and compaction measurement methods are impeded

Do not allow traffic on new HMA pavement until its mid-depth temperature is below 160 °F.

If you request in writing and the Engineer authorizes, you may cool HMA Type A and Type B with water when rolling activities are complete. Apply water under Section 17, "Watering."

Spread sand at a rate between 1 pound and 2 pounds per square yard on new RHMA-G, RHMA-O, and RHMA-O-HB pavement when finish rolling is complete. Sand must be free of clay or organic matter. Sand must comply with Section 90-3.03, "Fine Aggregate Grading." Keep traffic off the pavement until spreading sand is complete.

## 39-1.12 SMOOTHNESS

### 39-1.12A General

Determine HMA smoothness with a profilograph and a straightedge.

Smoothness specifications do not apply to OGFC placed on existing pavement not constructed under the same project.

If portland cement concrete is placed on HMA:

1. Cold plane the HMA finished surface to within specified tolerances if it is higher than the grade specified by the Engineer.
2. Remove and replace HMA if the finished surface is lower than 0.05 foot below the grade specified by the Engineer.

**39-1.12B Straightedge**

The HMA pavement top layer must not vary from the lower edge of a 12-foot long straightedge:

1. More than 0.01 foot when the straight edge is laid parallel with the centerline
2. More than 0.02 foot when the straightedge is laid perpendicular to the centerline and extends from edge to edge of a traffic lane
3. More than 0.02 foot when the straightedge is laid within 24 feet of a pavement conform

**39-1.12C Profilograph**

Under California Test 526, determine the zero (null) blanking band Profile Index ($PI_0$) and must-grinds on the top layer of HMA Type A, Type B, and RHMA-G pavement. Take 2 profiles within each traffic lane, 3 feet from and parallel with the edge of each lane.

A must-grind is a deviation of 0.3 inch or more in a length of 25 feet. You must correct must-grinds.

For OGFC, only determine must-grinds when placed over HMA constructed under the same project. The top layer of the underlying HMA must comply with the smoothness specifications before placing OGFC.

Profile pavement in the Engineer's presence. Choose the time of profiling.

On tangents and horizontal curves with a centerline radius of curvature 2,000 feet or more, the $PI_0$ must be at most 3 inches per 0.1-mile section.

On horizontal curves with a centerline radius of curvature between 1,000 feet and 2,000 feet including pavement within the superelevation transitions, the $PI_0$ must be at most 6 inches per 0.1-mile section.

Before the Engineer accepts HMA pavement for smoothness, submit written final profilograms.

Submit 1 electronic copy of profile information in Microsoft Excel and 1 electronic copy of longitudinal pavement profiles in ".erd" format or other ProVAL compatible format to the Engineer and to:

Smoothness@dot.ca.gov

The following HMA pavement areas do not require a $PI_0$. You must measure these areas with a 12-foot straightedge and determine must-grinds with a profilograph:

1. New HMA with a total thickness less than or equal to 0.25 foot
2. HMA sections of city or county streets and roads, turn lanes and collector lanes that are less than 1,500 feet in length

The following HMA pavement areas do not require a $PI_0$. You must measure these areas with a 12-foot straightedge:

1. Horizontal curves with a centerline radius of curvature less than 1,000 feet including pavement within the superelevation transitions of those curves
2. Within 12 feet of a transverse joint separating the pavement from:

    2.1. Existing pavement not constructed under the same project
    2.2. A bridge deck or approach slab

3. Exit ramp termini, truck weigh stations, and weigh-in-motion areas
4. If steep grades and superelevation rates greater than 6 percent are present on:

    4.1. Ramps
    4.2. Connectors

5. Turn lanes
6. Areas within 15 feet of manholes or drainage transitions
7. Acceleration and deceleration lanes for at-grade intersections
8. Shoulders and miscellaneous areas
9. HMA pavement within 3 feet from and parallel to the construction joints formed between curbs, gutters, or existing pavement

### 39-1.12D Smoothness Correction

If the top layer of HMA Type A, Type B, or RHMA-G pavement does not comply with the smoothness specifications, grind the pavement to within tolerances, remove and replace it, or place a layer of HMA. The Engineer must authorize your choice of correction before the work begins.

Remove and replace the areas of OGFC not in compliance with the must-grind and straightedge specifications, except you may grind OGFC for correcting smoothness:

1. At a transverse joint separating the pavement from pavement not constructed under the same project
2. Within 12 feet of a transverse joint separating the pavement from a bridge deck or approach slab

Corrected HMA pavement areas must be uniform rectangles with edges:

1. Parallel to the nearest HMA pavement edge or lane line
2. Perpendicular to the pavement centerline

Measure the corrected HMA pavement surface with a profilograph and a 12-foot straightedge and correct the pavement to within specified tolerances. If a must-grind area or straightedged pavement cannot be corrected to within specified tolerances, remove and replace the pavement.

On ground areas not overlaid with OGFC, apply fog seal coat under Section 37-1, "Seal Coats."

## 39-1.13 MISCELLANEOUS AREAS AND DIKES

Miscellaneous areas are outside the traveled way and include:

1. Median areas not including inside shoulders
2. Island areas
3. Sidewalks
4. Gutters
5. Gutter flares
6. Ditches
7. Overside drains
8. Aprons at the ends of drainage structures

Spread miscellaneous areas in 1 layer and compact to the specified lines and grades.

For miscellaneous areas and dikes:

1. Do not submit a JMF.
2. Choose the 3/8-inch or 1/2-inch HMA Type A and Type B aggregate gradations.
3. Minimum asphalt binder content must be 6.8 percent for 3/8-inch aggregate and 6.0 percent for 1/2-inch aggregate. If you request in writing and the Engineer authorizes, you may reduce the minimum asphalt binder content.
4. Choose asphalt binder Grade PG 70-10 or the same grade specified for HMA.

## 39-1.14 RUMBLE STRIP

Construct rumble strips by rolling or grinding indentations in the top layer of new HMA surfacing.

Select the method and equipment for constructing ground-in indentations.

Do not construct rumble strips on structures or approach slabs.

Construct rumble strips within 2 inches of the specified alignment. Roller or grinding equipment must be equipped with a sighting device enabling the operator to maintain the rumble strip alignment.

Rolled-in indentations must not vary from the specified dimensions by more than 10 percent.

Ground-in indentations must comply with the specified dimensions within 0.06 inch in depth or 10 percent in length and width.

The Engineer orders grinding or removal and replacement of noncompliant rumble strips to bring them within specified tolerances. Ground surface areas must be neat and uniform in appearance.

The grinding equipment must be equipped with a vacuum attachment to remove residue.

Dispose of removed material under Section 7-1.13, "Disposal of Material Outside the Highway Right of Way."

On ground areas, apply fog seal coat under Section 37-1, "Seal Coats."

## 39-2 STANDARD

### 39-2.01 DESCRIPTION

If HMA is specified as Standard, construct it under Section 39-1, "General," this Section 39-2, "Standard," and Section 39-5, "Measurement and Payment."

### 39-2.02 CONTRACTOR QUALITY CONTROL

#### 39-2.02A Quality Control Plan

Establish, implement, and maintain a Quality Control Plan (QCP) for HMA. The QCP must describe the organization and procedures you will use to:

1. Control the quality characteristics
2. Determine when corrective actions are needed (action limits)
3. Implement corrective actions

When you submit the proposed JMF, submit the written QCP. You and the Engineer must discuss the QCP during the prepaving conference.

The QCP must address the elements affecting HMA quality including:

1. Aggregate
2. Asphalt binder
3. Additives
4. Production
5. Paving

The Engineer reviews each QCP within 5 business days from the submittal. Hold HMA production until the Engineer accepts the QCP in writing. The Engineer's QCP acceptance does not mean your compliance with the QCP will result in acceptable HMA. Section 39-1.05, "Engineer's Acceptance," specifies HMA acceptance.

#### 39-2.02B Quality Control Testing

Perform sampling and testing at the specified frequency for the following quality characteristics:

**Minimum Quality Control – Standard**

| Quality Characteristic | Test Method | Minimum Sampling and Testing Frequency | HMA Type | | | |
|---|---|---|---|---|---|---|
| | | | A | B | RHMA-G | OGFC |
| Aggregate gradation[a] | CT 202 | 1 per 750 tons and any remaining part | JMF ± Tolerance [b] | JMF ± Tolerance [b] | JMF ± Tolerance [b] | JMF ± Tolerance [b] |
| Sand equivalent (min.) [c] | CT 217 | | 47 | 42 | 47 | -- |
| Asphalt binder content (%) | CT 379 or 382 | | JMF ± 0.45 | JMF ± 0.45 | JMF ± 0.50 | JMF ± 0.50 |
| HMA moisture content (%, max.) | CT 226 or CT 370 | 1 per 2,500 tons but not less than 1 per paving day | 1.0 | 1.0 | 1.0 | 1.0 |
| Percent of maximum theoretical density (%) [d, e] | Quality control plan | 2 per business day (min.) | 91 - 97 | 91 - 97 | 91 - 97 | -- |
| Stabilometer value (min.) [c, f]<br>No. 4 and 3/8" gradings<br>1/2" and 3/4" gradings | CT 366 | One per 4,000 tons or 2 per 5 business days, which-ever is more | <br>30<br>37 | <br>30<br>35 | <br>--<br>23 | <br>--<br>-- |
| Air voids content (%) [c, g] | CT 367 | | 4 ± 2 | 4 ± 2 | Specification ± 2 | -- |
| Aggregate moisture content at continuous mixing plants and RAP moisture content at continuous mixing plants and batch mixing plants [h] | CT 226 or CT 370 | 2 per day during production | -- | -- | -- | -- |
| Percent of crushed particles coarse aggregate (%, min.)<br>One fractured face<br>Two fractured faces<br>Fine aggregate (%, min)<br>(Passing No. 4 sieve and retained on No. 8 sieve.)<br>One fractured face | CT 205 | As necessary and designat-ed in the QCP. At least once per project | <br>90<br>75<br><br><br>70 | <br>25<br>--<br><br><br>20 | <br>--<br>90<br><br><br>70 | <br>90<br>75<br><br><br>90 |
| Los Angeles Rattler (%, max.)<br>Loss at 100 rev.<br>Loss at 500 rev. | CT 211 | | <br>12<br>45 | <br>--<br>50 | <br>12<br>40 | <br>12<br>40 |

| | | | | | | |
|---|---|---|---|---|---|---|
| Flat and elongated particles (%, max. by weight @ 5:1) | ASTM D 4791 | | Report only | Report only | Report only | Report only |
| Fine aggregate angularity (%, min.) | AASHTO T 304, Method A | | 45 | 45 | 45 | -- |
| Voids filled with asphalt (%) [i]<br>No. 4 grading<br>3/8" grading<br>1/2" grading<br>3/4" grading | LP-3 | | <br><br>76.0 – 80.0<br>73.0 – 76.0<br>65.0 – 75.0<br>65.0 – 75.0 | <br><br>76.0 – 80.0<br>73.0 – 76.0<br>65.0 – 75.0<br>65.0 – 75.0 | Report only | -- |
| Voids in mineral aggregate (% min.) [i]<br>No. 4 grading<br>3/8" grading<br>1/2" grading<br>3/4" grading | LP-2 | | <br><br>17.0<br>15.0<br>14.0<br>13.0 | <br><br>17.0<br>15.0<br>14.0<br>13.0 | <br><br>--<br>--<br>18.0 – 23.0 [j]<br>18.0 – 23.0 [j] | -- |
| Dust proportion [i]<br>No. 4 and 3/8" gradings<br>1/2" and 3/4" gradings | LP-4 | | <br><br>0.9 – 2.0<br><br>0.6 – 1.3 | <br><br>0.9 – 2.0<br><br>0.6 – 1.3 | Report only | -- |
| Smoothness | Section 39-1.12 | -- | 12-foot straightedge, must-grind, and $PI_0$ | 12-foot straightedge, must-grind, and $PI_0$ | 12-foot straightedge, must-grind, and $PI_0$ | 12-foot straightedge and must-grind |
| Asphalt rubber binder viscosity @ 350 °F, centipoises | Section 39-1.02D | Section 39-1.04C | -- | -- | 1,500 – 4,000 | 1,500 – 4,000 |
| Asphalt modifier | Section 39-1.02D | Section 39-1.04C | -- | -- | Section 39-1.02D | Section 39-1.02D |
| Crumb rubber modifier | Section 39-1.02D | Section 39-1.04C | -- | -- | Section 39-1.02D | Section 39-1.02D |

Notes:
[a] Determine combined aggregate gradation containing RAP under Laboratory Procedure LP-9.
[b] The tolerances must comply with the allowable tolerances in Section 39-1.02E, "Aggregate."
[c] Report the average of 3 tests from a single split sample.
[d] Required for HMA Type A, Type B, and RHMA-G if the specified paved thickness is at least 0.15 foot.
[e] Determine maximum theoretical density (California Test 309) at the frequency specified for Test Maximum Density under California Test 375, Part 5.D.
[f] Modify California Test 304, Part 2.B.2.c: "After compaction in the mechanical compactor, cool to 140 °F ± 5 °F by allowing the briquettes to cool at room temperature for 0.5 hour, then place the briquettes in the oven at 140 °F for a minimum of 2 hours and not more than 3 hours."
[g] Determine the bulk specific gravity of each lab-compacted briquette under California Test 308, Method A, and theoretical maximum specific gravity under California Test 309.
[h] For adjusting the plant controller at the HMA plant.
[i] Report only if the adjustment for asphalt binder content target value is less than or equal to ± 0.3 percent from OBC.
[j] Voids in mineral aggregate for RHMA-G must be within this range.

For any single quality characteristic except smoothness, if 2 consecutive quality control test results do not comply with the action limits or specifications:

1. Stop production.
2. Notify the Engineer in writing.
3. Take corrective action.

4. Demonstrate compliance with the specifications before resuming production and placement on the State highway.

## 39-2.03 ENGINEER'S ACCEPTANCE

### 39-2.03A Testing

The Engineer samples for acceptance testing and tests for:

**HMA Acceptance - Standard**

| Quality Characteristic | Test Method | HMA Type | | | |
|---|---|---|---|---|---|
| | | A | B | RHMA-G | OGFC |
| Aggregate gradation [a] | CT 202 | JMF ± Tolerance [c] | JMF ± Tolerance [c] | JMF ± Tolerance [c] | JMF ± Tolerance [c] |
| Sieve / 3/4" / 1/2" / 3/8" | | | | | |
| 1/2" / X [b] | | | | | |
| 3/8" / X | | | | | |
| No. 4 / X | | | | | |
| No. 8 / X / X / X | | | | | |
| No. 200 / X / X / X | | | | | |
| Sand equivalent (min.) [d] | CT 217 | 47 | 42 | 47 | -- |
| Asphalt binder content (%) | CT 379 or 382 | JMF ± 0.45 | JMF ± 0.45 | JMF ± 0.50 | JMF ± 0.50 |
| HMA moisture content (%, max.) | CT 226 or CT 370 | 1.0 | 1.0 | 1.0 | 1.0 |
| Percent of maximum theoretical density (%) [e, f] | CT 375 | 91 – 97 | 91 – 97 | 91 – 97 | -- |
| Stabilometer value (min.) [d, g] | CT 366 | | | | |
| No. 4 and 3/8" gradings | | 30 | 30 | -- | -- |
| 1/2" and 3/4" gradings | | 37 | 35 | 23 | -- |
| Air voids content (%) [d, h] | CT 367 | 4 ± 2 | 4 ± 2 | Specification ± 2 | -- |
| Percent of crushed particles Coarse aggregate (%, min.) | CT 205 | | | | |
| One fractured face | | 90 | 25 | -- | 90 |
| Two fractured faces | | 75 | -- | 90 | 75 |
| Fine aggregate (%, min) (Passing No. 4 sieve and retained on No. 8 sieve.) One fractured face | | 70 | 20 | 70 | 90 |
| Percent of crushed particles Coarse aggregate (%, min.) | CT 205 | | | | |
| One fractured face | | 90 | 25 | -- | 90 |
| Two fractured faces | | 75 | -- | 90 | 75 |
| Los Angeles Rattler (%, max.) | CT 211 | | | | |
| Loss at 100 rev. | | 12 | -- | 12 | 12 |
| Loss at 500 rev. | | 45 | 50 | 40 | 40 |
| Fine aggregate angularity (%, min.) | AASHTO T 304, Method A | 45 | 45 | 45 | -- |
| Flat and elongated particles (%, max. by weight @ 5:1) | ASTM D 4791 | Report only | Report only | Report only | Report only |
| Voids filled with asphalt (%) [i] | LP-3 | | | | |
| No. 4 grading | | 76.0 – 80.0 | 76.0 – 80.0 | Report only | -- |
| 3/8" grading | | 73.0 – 76.0 | 73.0 – 76.0 | | |
| 1/2" grading | | 65.0 – 75.0 | 65.0 – 75.0 | | |
| 3/4" grading | | 65.0 – 75.0 | 65.0 – 75.0 | | |
| Voids in mineral aggregate (% min.) [i] | LP-2 | | | | |
| No. 4 grading | | 17.0 | 17.0 | -- | -- |
| 3/8" grading | | 15.0 | 15.0 | -- | |
| 1/2" grading | | 14.0 | 14.0 | 18.0 – 23.0 [j] | |
| 3/4" grading | | 13.0 | 13.0 | 18.0 – 23.0 [j] | |
| Dust proportion [i] | LP-4 | | | | -- |
| No. 4 and 3/8" gradings | | 0.9 – 2.0 | 0.9 – 2.0 | Report only | |

| | | | | | |
|---|---|---|---|---|---|
| 1/2" and 3/4" gradings | | 0.6 – 1.3 | 0.6 – 1.3 | | |
| Smoothness | Section 39-1.12 | 12-foot straightedge, must-grind, and $PI_0$ | 12-foot straightedge, must-grind, and $PI_0$ | 12-foot straightedge, must-grind, and $PI_0$ | 12-foot straightedge and must-grind |
| Asphalt binder | Various | Section 92 | Section 92 | Section 92 | Section 92 |
| Asphalt rubber binder | Various | -- | -- | Section 92-1.02(C) and Section 39-1.02D | Section 92-1.02(C) and Section 39-1.02D |
| Asphalt modifier | Various | -- | -- | Section 39-1.02D | Section 39-1.02D |
| Crumb rubber modifier | Various | -- | -- | Section 39-1.02D | Section 39-1.02D |

[a] The Engineer determines combined aggregate gradations containing RAP under Laboratory Procedure LP-9.
[b] "X" denotes the sieves the Engineer considers for the specified aggregate gradation.
[c] The tolerances must comply with the allowable tolerances in Section 39-1.02E, "Aggregate."
[d] The Engineer reports the average of 3 tests from a single split sample.
[e] The Engineer determines percent of maximum theoretical density if the specified paved thickness is at least 0.15 foot under California Test 375 except the Engineer uses:

1. California Test 308, Method A, to determine in-place density of each density core instead of using the nuclear gauge in Part 4, "Determining In-Place Density By The Nuclear Density Device."
2. California Test 309 to determine maximum theoretical density instead of calculating test maximum density in Part 5, "Determining Test Maximum Density."

[f] The Engineer determines maximum theoretical density (California Test 309) at the frequency specified for Test Maximum Density under California Test 375, Part 5.D.
[g] Modify California Test 304, Part 2.B.2.c: "After compaction in the mechanical compactor, cool to 140 °F ±5 °F by allowing the briquettes to cool at room temperature for 0.5 hour, then place the briquettes in the oven at 140 °F for a minimum of 2 hours and not more than 3 hours."
[h] The Engineer determines the bulk specific gravity of each lab-compacted briquette under California Test 308, Method A, and theoretical maximum specific gravity under California Test 309.
[i] Report only if the adjustment for asphalt binder content target value is less than or equal to ± 0.3 percent from OBC.
[j] Voids in mineral aggregate for RHMA-G must be within this range.

No single test result may represent more than the smaller of 750 tons or 1 day's production.

For any single quality characteristic except smoothness, if 2 consecutive acceptance test results do not comply with the specifications:

1. Stop production.
2. Take corrective action.
3. In the Engineer's presence, take samples and split each sample into 4 parts. Test 1 part for compliance with the specifications and submit 3 parts to the Engineer. The Engineer tests 1 part for compliance with the specifications and reserves and stores 2 parts.
4. Demonstrate compliance with the specifications before resuming production and placement on the State highway.

The Engineer tests the density core you take from each 250 tons of HMA production. The Engineer determines the percent of maximum theoretical density for each density core by determining the density core's density and dividing by the maximum theoretical density.

If the specified total paved thickness is at least 0.15 foot and any layer is less than 0.15 foot, the Engineer determines the percent of maximum theoretical density from density cores taken from the final layer measured the full depth of the total paved HMA thickness.

For percent of maximum theoretical density, the Engineer determines a deduction for each test result outside the specifications in compliance with:

**Reduced Payment Factors for Percent of Maximum Theoretical Density**

| HMA Type A and B and RHMA-G Percent of Maximum Theoretical Density | Reduced Payment Factor | HMA Type A and B and RHMA-G Percent of Maximum Theoretical Density | Reduced Payment Factor |
|---|---|---|---|
| 91.0 | 0.0000 | 97.0 | 0.0000 |
| 90.9 | 0.0125 | 97.1 | 0.0125 |
| 90.8 | 0.0250 | 97.2 | 0.0250 |
| 90.7 | 0.0375 | 97.3 | 0.0375 |
| 90.6 | 0.0500 | 97.4 | 0.0500 |
| 90.5 | 0.0625 | 97.5 | 0.0625 |
| 90.4 | 0.0750 | 97.6 | 0.0750 |
| 90.3 | 0.0875 | 97.7 | 0.0875 |
| 90.2 | 0.1000 | 97.8 | 0.1000 |
| 90.1 | 0.1125 | 97.9 | 0.1125 |
| 90.0 | 0.1250 | 98.0 | 0.1250 |
| 89.9 | 0.1375 | 98.1 | 0.1375 |
| 89.8 | 0.1500 | 98.2 | 0.1500 |
| 89.7 | 0.1625 | 98.3 | 0.1625 |
| 89.6 | 0.1750 | 98.4 | 0.1750 |
| 89.5 | 0.1875 | 98.5 | 0.1875 |
| 89.4 | 0.2000 | 98.6 | 0.2000 |
| 89.3 | 0.2125 | 98.7 | 0.2125 |
| 89.2 | 0.2250 | 98.8 | 0.2250 |
| 89.1 | 0.2375 | 98.9 | 0.2375 |
| 89.0 | 0.2500 | 99.0 | 0.2500 |
| < 89.0 | Remove and Replace | > 99.0 | Remove and Replace |

### 39-2.04 TRANSPORTING, SPREADING, AND COMPACTING

Determine the number of rollers needed to obtain the specified density and surface finish.

## 39-3 METHOD

### 39-3.01 DESCRIPTION

If HMA is specified as Method, construct it under Section 39-1, "General," this Section 39-3, "Method," and Section 39-5, "Measurement and Payment."

### 39-3.02 ENGINEER'S ACCEPTANCE

#### 39-3.02A Testing

The Engineer samples for acceptance testing and tests for:

**HMA Acceptance - Method**

| Quality Characteristic | Test Method | HMA Type | | | |
|---|---|---|---|---|---|
| | | A | B | RHMA-G | OGFC |
| Aggregate gradation [a] | CT 202 | JMF ± Tolerance [b] | JMF ± Tolerance [b] | JMF ± Tolerance [b] | JMF ± Tolerance [b] |
| Sand equivalent (min.) [c] | CT 217 | 47 | 42 | 47 | -- |
| Asphalt binder content (%) | CT 379 or 382 | JMF ± 0.45 | JMF ± 0.45 | JMF ± 0.50 | JMF ± 0.50 |
| HMA moisture content (%, max.) | CT 226 or CT 370 | 1.0 | 1.0 | 1.0 | 1.0 |
| Stabilometer value (min.) [c, d] | CT 366 | | | | |
| No. 4 and 3/8" gradings | | 30 | 30 | -- | -- |
| 1/2" and 3/4" gradings | | 37 | 35 | 23 | -- |
| Percent of crushed particles | CT 205 | | | | |
| Coarse aggregate (% min.) | | | | | |
| One fractured face | | 90 | 25 | -- | 90 |
| Two fractured faces | | 75 | -- | 90 | 75 |
| Fine aggregate (% min) (Passing No. 4 sieve and retained on No. 8 sieve.) | | | | | |
| One fractured face | | 70 | 20 | 70 | 90 |
| Los Angeles Rattler (% max.) | CT 211 | | | | |
| Loss at 100 rev. | | 12 | -- | 12 | 12 |
| Loss at 500 rev. | | 45 | 50 | 40 | 40 |
| Air voids content (%) [c, e] | CT 367 | 4 ± 2 | 4 ± 2 | Specification ± 2 | -- |
| Fine aggregate angularity (% min.) | AASHTO T 304, Method A | 45 | 45 | 45 | -- |
| Flat and elongated particles (% max. by weight @ 5:1) | ASTM D 4791 | Report only | Report only | Report only | Report only |
| Voids filled with asphalt (%) [f] | LP-3 | | | Report only | -- |
| No. 4 grading | | 76.0 – 80.0 | 76.0 – 80.0 | | |
| 3/8" grading | | 73.0 – 76.0 | 73.0 – 76.0 | | |
| 1/2" grading | | 65.0 – 75.0 | 65.0 – 75.0 | | |
| 3/4" grading | | 65.0 – 75.0 | 65.0 – 75.0 | | |
| Voids in mineral aggregate (% min.) [f] | LP-2 | | | | -- |
| No. 4 grading | | 17.0 | 17.0 | -- | |
| 3/8" grading | | 15.0 | 15.0 | -- | |
| 1/2" grading | | 14.0 | 14.0 | 18.0 – 23.0 [g] | |
| 3/4" grading | | 13.0 | 13.0 | 18.0 – 23.0 [g] | |
| Dust proportion [f] | LP-4 | | | Report only | -- |
| No. 4 and 3/8" gradings | | 0.9 – 2.0 | 0.9 – 2.0 | | |
| 1/2" and 3/4" gradings | | 0.6 – 1.3 | 0.6 – 1.3 | | |
| Smoothness | Section 39-1.12 | 12-foot straightedge and must-grind | 12-foot straightedge and must-grind | 12-foot straightedge and must-grind | 12-foot straightedge and must-grind |
| Asphalt binder | Various | Section 92 | Section 92 | Section 92 | Section 92 |
| Asphalt rubber binder | Various | -- | -- | Section 92- | Section 92- |

| | | | | | |
|---|---|---|---|---|---|
| | | | | 1.02(C) and Section 39-1.02D | 1.02(C) and Section 39-1.02D |
| Asphalt modifier | Various | -- | -- | Section 39-1.02D | Section 39-1.02D |
| Crumb rubber modifier | Various | -- | -- | Section 39-1.02D | Section 39-1.02D |

[a] The Engineer determines combined aggregate gradations containing RAP under Laboratory Procedure LP-9.
[b] The tolerances must comply with the allowable tolerances in Section 39-1.02E, "Aggregate."
[c] The Engineer reports the average of 3 tests from a single split sample.
[d] Modify California Test 304, Part 2.B.2.c: "After compaction in the mechanical compactor, cool to 140 °F ±5 °F by allowing the briquettes to cool at room temperature for 0.5 hour, then place the briquettes in the oven at 140 °F for a minimum of 2 hours and not more than 3 hours."
[e] The Engineer determines the bulk specific gravity of each lab-compacted briquette under California Test 308, Method A, and theoretical maximum specific gravity under California Test 309.
[f] Report only if the adjustment for asphalt binder content target value is less than or equal to ± 0.3 percent from OBC.
[g] Voids in mineral aggregate for RHMA-G must be within this range.

No single test result may represent more than the smaller of 750 tons or 1 day's production.

For any single quality characteristic except smoothness, if 2 consecutive acceptance test results do not comply with the specifications:

1. Stop production.
2. Take corrective action.
3. In the Engineer's presence, take samples and split each sample into 4 parts. Test 1 part for compliance with the specifications and submit 3 parts to the Engineer. The Engineer tests 1 part for compliance with the specifications and reserves and stores 2 parts.
4. Demonstrate compliance with the specifications before resuming production and placement on the State highway.

### 39-3.03 SPREADING AND COMPACTING EQUIPMENT

Each paver spreading HMA Type A and Type B must be followed by 3 rollers:

1. One vibratory roller specifically designed to compact HMA. The roller must be capable of at least 2,500 vibrations per minute and must be equipped with amplitude and frequency controls. The roller's gross static weight must be at least 7.5 tons.
2. One oscillating type pneumatic-tired roller at least 4 feet wide. Pneumatic tires must be of equal size, diameter, type, and ply. The tires must be inflated to 60 psi minimum and maintained so that the air pressure does not vary more than 5 psi.
3. One steel-tired, 2-axle tandem roller. The roller's gross static weight must be at least 7.5 tons.

Each roller must have a separate operator. Rollers must be self-propelled and reversible.

Compact RHMA-G under the specifications for compacting HMA Type A and Type B except do not use pneumatic-tired rollers.

Compact OGFC with steel-tired, 2-axle tandem rollers. If placing over 300 tons of OGFC per hour, use at least 3 rollers for each paver. If placing less than 300 tons of OGFC per hour, use at least 2 rollers for each paver. Each roller must weigh between 126 pounds to 172 pounds per linear inch of drum width. Turn the vibrator off.

### 39-3.04 TRANSPORTING, SPREADING, AND COMPACTING

Pave HMA in maximum 0.25-foot thick compacted layers.

If the surface to be paved is both in sunlight and shade, pavement surface temperatures are taken in the shade.

Spread HMA Type A and Type B only if atmospheric and surface temperatures are:

**Minimum Atmospheric and Surface Temperatures**

| Compacted Layer Thickness, feet | Atmospheric,° F | | Surface,° F | |
|---|---|---|---|---|
| | Unmodified Asphalt Binder | Modified Asphalt Binder[a] | Unmodified Asphalt Binder | Modified Asphalt Binder [a] |
| < 0.15 | 55 | 50 | 60 | 55 |
| 0.15 – 0.25 | 45 | 45 | 50 | 50 |

Note:
[a] Except asphalt rubber binder.

If the asphalt binder for HMA Type A and Type B is:

1. Unmodified asphalt binder, complete:

   1.1. First coverage of breakdown compaction before the surface temperature drops below 250 °F
   1.2. Breakdown and intermediate compaction before the surface temperature drops below 200 °F
   1.3. Finish compaction before the surface temperature drops below 150 °F

2. Modified asphalt binder, complete:

   2.1. First coverage of breakdown compaction before the surface temperature drops below 240 °F
   2.2. Breakdown and intermediate compaction before the surface temperature drops below 180 °F
   2.3. Finish compaction before the surface temperature drops below 140 °F

For RHMA-G:

1. Only spread and compact if the atmospheric temperature is at least 55 °F and the surface temperature is at least 60 °F.
2. Complete the first coverage of breakdown compaction before the surface temperature drops below 280 °F.
3. Complete breakdown and intermediate compaction before the surface temperature drops below 250 °F.
4. Complete finish compaction before the surface temperature drops below 200 °F.
5. If the atmospheric temperature is below 70 °F, cover loads in trucks with tarpaulins. The tarpaulins must completely cover the exposed load until you transfer the mixture to the paver's hopper or to the pavement surface.

For OGFC with unmodified asphalt binder:

1. Only spread and compact if the atmospheric temperature is at least 55 °F and the surface temperature is at least 60 °F.
2. Complete first coverage using 2 rollers before the surface temperature drops below 240 °F.
3. Complete all compaction before the surface temperature drops below 200 °F.
4. If the atmospheric temperature is below 70 °F, cover loads in trucks with tarpaulins. The tarpaulins must completely cover the exposed load until you transfer the mixture to the paver's hopper or to the pavement surface.

For OGFC with modified asphalt binder except asphalt rubber binder:

1. Only spread and compact if the atmospheric temperature is at least 50 °F and the surface temperature is at least 50 °F.
2. Complete first coverage using 2 rollers before the surface temperature drops below 240 °F.
3. Complete all compaction before the surface temperature drops below 180 °F.
4. If the atmospheric temperature is below 70 °F, cover loads in trucks with tarpaulins. The tarpaulins must completely cover the exposed load until you transfer the mixture to the paver's hopper or to the pavement surface.

For RHMA-O and RHMA-O-HB:

1. Only spread and compact if the atmospheric temperature is at least 55 °F and surface temperature is at least 60 °F.
2 Complete the 1st coverage using 2 rollers before the surface temperature drops below 280 °F.
3. Complete compaction before the surface temperature drops below 250 °F.

4. If the atmospheric temperature is below 70 °F, cover loads in trucks with tarpaulins. The tarpaulins must completely cover the exposed load until the mixture is transferred to the paver's hopper or to the pavement surface.

For RHMA-G and OGFC, tarpaulins are not required if the time from discharge to truck until transfer to the paver's hopper or the pavement surface is less than 30 minutes.

HMA compaction coverage is the number of passes needed to cover the paving width. A pass is 1 roller's movement parallel to the paving in either direction. Overlapping passes are part of the coverage being made and are not a subsequent coverage. Do not start a coverage until completing the prior coverage.

Start rolling at the lower edge and progress toward the highest part.

Perform breakdown compaction of each layer of HMA Type A, Type B, and RHMA-G with 3 coverages using a vibratory roller. The speed of the vibratory roller in miles per hour must not exceed the vibrations per minute divided by 1,000. If the HMA layer thickness is less than 0.08 foot, turn the vibrator off. The Engineer may order fewer coverages if the HMA layer thickness is less than 0.15 foot.

Perform intermediate compaction of each layer of HMA Type A and Type B with 3 coverages using a pneumatic-tired roller at a speed not to exceed 5 mph.

Perform finish compaction of HMA Type A, Type B, and RHMA-G with 1 coverage using a steel-tired roller.

Compact OGFC with 2 coverages using steel-tired rollers.

## 39-4 QUALITY CONTROL / QUALITY ASSURANCE

### 39-4.01 DESCRIPTION

If HMA is specified as Quality Control / Quality Assurance, construct it under Section 39-1, "General," this Section 39-4, "Quality Control / Quality Assurance," and Section 39-5, "Measurement and Payment."

### 39-4.02 GENERAL

The QC / QA construction process consists of:

1. Establishing, maintaining, and changing if needed a quality control system providing assurance the HMA complies with the specifications
2. Sampling and testing at specified intervals, or sublots, to demonstrate compliance and to control process
3. The Engineer sampling and testing at specified intervals to verify testing process and HMA quality
4. The Engineer using test results, statistical evaluation of verified quality control tests, and inspection to accept HMA for payment

A lot is a quantity of HMA. The Engineer designates a new lot when:

1. 20 sublots are complete
2. The JMF changes
3. Production stops for more than 30 days

Each lot consists of no more than 20 sublots. A sublot is 750 tons except HMA paved at day's end greater than 250 tons is a sublot. If HMA paved at day's end is less than 250 tons, you may either make this quantity a sublot or include it in the previous sublot's test results for statistical evaluation.

### 39-4.03 CONTRACTOR QUALITY CONTROL

#### 39-4.03A General

Use a composite quality factor, $QF_C$, and individual quality factors, $QF_{QCi}$, to control your process and evaluate your quality control program. For quality characteristics without quality factors, use your quality control plan's action limits to control process.

Control HMA quality including:

1. Materials
2. Proportioning
3. Spreading and compacting
4. Finished roadway surface

Develop, implement, and maintain a quality control program that includes:

1. Inspection
2. Sampling
3. Testing

**39-4.03B Quality Control Plan**

With the JMF submittal, submit a written Quality Control Plan (QCP). The QCP must comply with the Department's Quality Control Manual for Hot Mix Asphalt Production and Placement. Discuss the QCP with the Engineer during the prepaving conference.

The Engineer reviews each QCP within 5 business days from the submittal. Hold HMA production until the Engineer accepts the QCP in writing. The Engineer's QCP acceptance does not mean your compliance with the QCP will result in acceptable HMA. Section 39-1.05, "Engineer's Acceptance," specifies HMA acceptance.

The QCP must include the name and qualifications of a Quality Control Manager. The Quality Control Manager administers the QCP and during paving must be at the job site within 3 hours of receiving notice. The Quality Control Manager must not be any of the following on the project:

1. Foreman
2. Production or paving crewmember
3. Inspector
4. Tester

The QCP must include action limits and details of corrective action you will take if a test result for any quality characteristic falls outside an action limit.

As work progresses, you must submit a written QCP supplement to change quality control procedures, personnel, tester qualification status, or laboratory accreditation status.

**39-4.03C Quality Control Inspection, Sampling, And Testing**

Sample, test, inspect, and manage HMA quality control.

Provide a roadway inspector while HMA paving activities are in progress. Provide a plant inspector during HMA production.

Inspectors must comply with the Department's Quality Control Manual for Hot Mix Asphalt Production and Placement.

Provide a testing laboratory and personnel for quality control testing. Provide the Engineer unrestricted access to the quality control activities. Before providing services for the project, the Engineer reviews, accredits, and qualifies the testing laboratory and personnel under the Department's Independent Assurance Program.

The minimum random sampling and testing for quality control is:

**Minimum Quality Control – QC / QA**

| Quality Characteristic | Test Method | Minimum Sampling and Testing Frequency | HMA Type | | | Location of Sampling | Max. Reporting Time Allowance |
|---|---|---|---|---|---|---|---|
| | | | A | B | RHMA-G | | |
| Aggregate gradation [a] | CT 202 | 1 per 750 tons | JMF ± Tolerance [b] | JMF ± Tolerance [b] | JMF ± Tolerance [b] | CT 125 | 24 hours |
| Asphalt binder content (%) | CT 379 or 382 | | JMF ±0.45 | JMF ±0.45 | JMF ±0.5 | Loose Mix Behind Paver See CT 125 | |
| Percent of maximum theoretical density (%) [c, d] | QC Plan | | 92 - 96 | 92 - 96 | 91 - 96 | QC Plan | |
| Aggregate moisture content at continuous mixing plants and RAP moisture content at continuous mixing plants and batch mixing plants [e] | CT 226 or CT 370 | 2 per day during production | -- | -- | -- | Stockpiles or cold feed belts | -- |
| Sand equivalent (min.) [f] | CT 217 | 1 per 750 tons | 47 | 42 | 47 | CT 125 | 24 hours |
| HMA moisture content (%,max.) | CT 226 or CT 370 | 1 per 2,500 tons but not less than 1 per paving day | 1.0 | 1.0 | 1.0 | Loose Mix Behind Paver See CT 125 | 24 hours |
| Stabilometer Value (min.) [f, g]<br>No. 4 and 3/8" gradings<br>1/2" and 3/4" gradings | CT 366 | 1 per 4,000 tons or 2 per 5 business days, whichever is more | 30<br>37 | 30<br>35 | --<br>23 | | 48 hours |
| Air voids content (%)[f, h] | CT 367 | | 4 ± 2 | 4 ± 2 | Specification ± 2 | | |

| | | | | | | | |
|---|---|---|---|---|---|---|---|
| Percent of crushed particles coarse aggregate (% min.)<br>One fractured face<br>Two fractured faces<br>Fine aggregate (% min)<br>(Passing No. 4 sieve and retained on No. 8 sieve.)<br>One fractured face | CT 205 | As neces-sary and designat-ed in QCP. At least once per project. | 90<br>75<br>70 | 25<br>--<br>20 | --<br>90<br>70 | CT 125 | 48 hours |
| Los Angeles Rattler (% max.)<br>Loss at 100 rev.<br>Loss at 500 rev. | CT 211 | | 12<br>45 | --<br>50 | 12<br>40 | CT 125 | |
| Fine aggregate angularity (% min.) | AASHTO T 304, Method A | | 45 | 45 | 45 | CT 125 | |
| Flat and elongated particle (% max. by weight @ 5:1) | ASTM D 4791 | | Report only | Report only | Report only | CT 125 | |
| Voids filled with asphalt (%) [i]<br>No. 4 grading<br>3/8" grading<br>1/2" grading<br>3/4" grading | LP-3 | | 76.0 – 80.0<br>73.0 – 76.0<br>65.0 – 75.0<br>65.0 – 75.0 | 76.0 – 80.0<br>73.0 – 76.0<br>65.0 – 75.0<br>65.0 – 75.0 | Report only | LP-3 | |
| Voids in mineral aggregate (% min.) [i]<br>No. 4 grading<br>3/8" grading<br>1/2" grading<br>3/4" grading | LP-2 | | 17.0<br>15.0<br>14.0<br>13.0 | 17.0<br>15.0<br>14.0<br>13.0 | --<br>--<br>18.0 – 23.0[j]<br>18.0 – 23.0[j] | LP-2 | |
| Dust proportion [i]<br>No. 4 and 3/8" gradings<br>1/2" and 3/4" gradings | LP-4 | | 0.9 – 2.0<br>0.6 – 1.3 | 0.9 – 2.0<br>0.6 – 1.3 | Report only | LP-4 | |
| Smoothness | Section 39-1.12 | -- | 12-foot straight-edge, must-grind, and $PI_0$ | 12-foot straight-edge, must-grind, and $PI_0$ | 12-foot straight-edge, must-grind, and $PI_0$ | -- | |
| Asphalt rubber binder viscosity @ 350 °F, centipoises | Section 39-1.02D | -- | -- | -- | 1,500 – 4,000 | Section 39-1.02D | 24 hours |
| Crumb rubber modifier | Section 39-1.02D | -- | -- | -- | Section 39-1.02D | Section 39-1.02D | 48 hours |

Notes:
[a] Determine combined aggregate gradation containing RAP under Laboratory Procedure LP-9.
[b] The tolerances must comply with the allowable tolerances in Section 39-1.02E, "Aggregate."
[c] Required for HMA Type A, Type B, and RHMA-G if the specified paved thickness is at least 0.15 foot.

[d] Determine maximum theoretical density (California Test 309) at the frequency specified for test maximum density under California Test 375, Part 5 D.
[e] For adjusting the plant controller at the HMA plant.
[f] Report the average of 3 tests from a single split sample.
[g] Modify California Test 304, Part 2.B.2.c: "After compaction in the mechanical compactor, cool to 140 °F ± 5 °F by allowing the briquettes to cool at room temperature for 0.5 hour, then place the briquettes in the oven at 140 °F for a minimum of 2 hours and not more than 3 hours."
[h] Determine the bulk specific gravity of each lab-compacted briquette under California Test 308, Method A, and theoretical maximum specific gravity under California Test 309.
[i] Report only if the adjustment for asphalt binder content target value is less than or equal to ± 0.3 percent from OBC.
[j] Voids in mineral aggregate for RHMA-G must be within this range.

Within the specified reporting time, submit written test results including:

1. Sampling location, quantity, and time
2. Testing results
3. Supporting data and calculations

If test results for any quality characteristic are beyond the action limits in the QCP, take corrective actions. Document the corrective actions taken in the inspection records under Section 39-4.03E, "Records of Inspection and Testing."

Stop production, notify the Engineer in writing, take corrective action, and demonstrate compliance with the specifications before resuming production and placement on the State highway if:

1. A lot's composite quality factor, $Q_{FC}$, or an individual quality factor, $QF_{QCi}$ for i = 3, 4, or 5, is below 0.90 determined under Section 39-4.03F, "Statistical Evaluation"
2. An individual quality factor, $QF_{QCi}$ for i = 1 or 2, is below 0.75
3. Quality characteristics for which a quality factor, $QF_{QCi}$, is not determined has 2 consecutive acceptance or quality control tests not in compliance with the specifications

**39-4.03D Charts And Records**

Record sampling and testing results for quality control on forms provided in the "Quality Control Manual for Hot Mix Asphalt," or on forms you submit with the QCP. The QCP must also include form posting locations and submittal times.

Submit quality control test results using the Department's statistical evaluation program, HMAPay, available at

www.dot.ca.gov/hq/construc/hma/index.htm

**39-4.03E Records Of Inspection And Testing**

During HMA production, submit in writing a daily:

1. HMA Construction Daily Record of Inspection. Also make this record available at the HMA plant and job site each day.
2. HMA Inspection and Testing Summary. Include in the summary:

    2.1. Test forms with the testers' signatures and Quality Control Manager's initials.
    2.2. Inspection forms with the inspectors' signatures and Quality Control Manager's initials.
    2.3. A list and explanation of deviations from the specifications or regular practices.
    2.4. A signed statement by the Quality Control Manager that says:

    "It is hereby certified that the information contained in this record is accurate, and that information, tests, or calculations documented herein comply with the specifications of the contract and the standards set forth in the testing procedures. Exceptions to this certification are documented as part of this record."

Retain for inspection the records generated as part of quality control including inspection, sampling, and testing for at least 3 years after final acceptance.

### 39-4.03F Statistical Evaluation

#### General

Determine a lot's composite quality factor, $QF_C$, and the individual quality factors, $QF_{QCi}$. Perform statistical evaluation calculations to determine these quality factors based on quality control test results for:

1. Aggregate gradation
2. Asphalt binder content
3. Percent of maximum theoretical density

The Engineer grants a waiver and you must use 1.0 as the individual quality factor for percent of maximum theoretical density, $QF_{QC5}$, for HMA paved in:

1. Areas where the specified paved thickness is less than 0.15 foot
2. Areas where the specified paved thickness is less than 0.20 foot and a 3/4-inch grading is specified and used
3. Dig outs
4. Leveling courses
5. Areas where, in the opinion of the Engineer, compaction or compaction measurement by conventional methods is impeded

#### Statistical Evaluation Calculations

Use the Variability-Unknown / Standard Deviation Method to determine the percentage of a lot not in compliance with the specifications. The number of significant figures used in the calculations must comply with AASHTO R-11, Absolute Method.

Determine the percentage of work not in compliance with the specification limits for each quality characteristic as follows:

1. Calculate the arithmetic mean ($\overline{X}$) of the test values

$$\overline{X} = \frac{\Sigma x}{n}$$

where:

x = individual test values
n = number of test values

2. Calculate the standard deviation

$$s = \sqrt{\frac{n\,(\Sigma x^2)-(\Sigma x)^2}{n(n-1)}}$$

where:

$\sum(x^2)$ = sum of the squares of individual test values
$(\sum x)^2$ = sum of the individual test values squared
n = number of test values

3. Calculate the upper quality index (Qu)

$$Q_u = \frac{USL - \overline{X}}{s}$$

where:

USL = target value plus the production tolerance or upper specification limit
s = standard deviation
$\overline{X}$ = arithmetic mean

4. Calculate the lower quality index (QL);

$$Q_L = \frac{\overline{X} - LSL}{s}$$

where:

LSL = target value minus production tolerance or lower specification limit
s = standard deviation
$\overline{X}$ = arithmetic mean

5. From the table, Upper Quality Index $Q_U$ or Lower Quality Index $Q_L$, of this Section 39-4.03F, "Statistical Evaluation", determine $P_U$ ;

where:

$P_U$ = the estimated percentage of work outside the USL.
$P_U = 0$, when USL is not specified.

6. From the table, Upper Quality Index $Q_U$ or Lower Quality Index $Q_L$, of this Section 39-4.03F, "Statistical Evaluation," determine $P_L$;

where:

$P_L$ = the estimated percentage of work outside the LSL.
$P_L = 0$, when LSL is not specified.

7. Calculate the total estimated percentage of work outside the USL and LSL, percent defective

Percent defective $= P_U + P_L$

$P_U$ and $P_L$ are determined from:

| $P_U$ or $P_L$ | **Upper Quality Index $Q_U$ or Lower Quality Index $Q_L$** | | | | | | | | | | | | |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| | Sample Size (n) | | | | | | | | | | | | |
| | 5 | 6 | 7 | 8 | 9 | 10-11 | 12-14 | 15-17 | 18-22 | 23-29 | 30-42 | 43-66 | >66 |
| 0 | 1.72 | 1.88 | 1.99 | 2.07 | 2.13 | 2.20 | 2.28 | 2.34 | 2.39 | 2.44 | 2.48 | 2.51 | 2.56 |
| 1 | 1.64 | 1.75 | 1.82 | 1.88 | 1.91 | 1.96 | 2.01 | 2.04 | 2.07 | 2.09 | 2.12 | 2.14 | 2.16 |
| 2 | 1.58 | 1.66 | 1.72 | 1.75 | 1.78 | 1.81 | 1.84 | 1.87 | 1.89 | 1.91 | 1.93 | 1.94 | 1.95 |
| 3 | 1.52 | 1.59 | 1.63 | 1.66 | 1.68 | 1.71 | 1.73 | 1.75 | 1.76 | 1.78 | 1.79 | 1.80 | 1.81 |
| 4 | 1.47 | 1.52 | 1.56 | 1.58 | 1.60 | 1.62 | 1.64 | 1.65 | 1.66 | 1.67 | 1.68 | 1.69 | 1.70 |
| 5 | 1.42 | 1.47 | 1.49 | 1.51 | 1.52 | 1.54 | 1.55 | 1.56 | 1.57 | 1.58 | 1.59 | 1.59 | 1.60 |
| 6 | 1.38 | 1.41 | 1.43 | 1.45 | 1.46 | 1.47 | 1.48 | 1.49 | 1.50 | 1.50 | 1.51 | 1.51 | 1.52 |
| 7 | 1.33 | 1.36 | 1.38 | 1.39 | 1.40 | 1.41 | 1.41 | 1.42 | 1.43 | 1.43 | 1.44 | 1.44 | 1.44 |
| 8 | 1.29 | 1.31 | 1.33 | 1.33 | 1.34 | 1.35 | 1.35 | 1.36 | 1.36 | 1.37 | 1.37 | 1.37 | 1.38 |
| 9 | 1.25 | 1.27 | 1.28 | 1.28 | 1.29 | 1.29 | 1.30 | 1.30 | 1.30 | 1.31 | 1.31 | 1.31 | 1.31 |
| 10 | 1.21 | 1.23 | 1.23 | 1.24 | 1.24 | 1.24 | 1.25 | 1.25 | 1.25 | 1.25 | 1.25 | 1.26 | 1.26 |
| 11 | 1.18 | 1.18 | 1.19 | 1.19 | 1.19 | 1.19 | 1.20 | 1.20 | 1.20 | 1.20 | 1.20 | 1.20 | 1.20 |
| 12 | 1.14 | 1.14 | 1.15 | 1.15 | 1.15 | 1.15 | 1.15 | 1.15 | 1.15 | 1.15 | 1.15 | 1.15 | 1.15 |
| 13 | 1.10 | 1.10 | 1.10 | 1.10 | 1.10 | 1.10 | 1.11 | 1.11 | 1.11 | 1.11 | 1.11 | 1.11 | 1.11 |
| 14 | 1.07 | 1.07 | 1.07 | 1.06 | 1.06 | 1.06 | 1.06 | 1.06 | 1.06 | 1.06 | 1.06 | 1.06 | 1.06 |
| 15 | 1.03 | 1.03 | 1.03 | 1.03 | 1.02 | 1.02 | 1.02 | 1.02 | 1.02 | 1.02 | 1.02 | 1.02 | 1.02 |
| 16 | 1.00 | 0.99 | 0.99 | 0.99 | 0.99 | 0.98 | 0.98 | 0.98 | 0.98 | 0.98 | 0.98 | 0.98 | 0.98 |
| 17 | 0.97 | 0.96 | 0.95 | 0.95 | 0.95 | 0.95 | 0.94 | 0.94 | 0.94 | 0.94 | 0.94 | 0.94 | 0.94 |
| 18 | 0.93 | 0.92 | 0.92 | 0.92 | 0.91 | 0.91 | 0.91 | 0.91 | 0.90 | 0.90 | 0.90 | 0.90 | 0.90 |
| 19 | 0.90 | 0.89 | 0.88 | 0.88 | 0.88 | 0.87 | 0.87 | 0.87 | 0.87 | 0.87 | 0.87 | 0.87 | 0.87 |
| 20 | 0.87 | 0.86 | 0.85 | 0.85 | 0.84 | 0.84 | 0.84 | 0.83 | 0.83 | 0.83 | 0.83 | 0.83 | 0.83 |
| 21 | 0.84 | 0.82 | 0.82 | 0.81 | 0.81 | 0.81 | 0.80 | 0.80 | 0.80 | 0.80 | 0.80 | 0.80 | 0.79 |
| 22 | 0.81 | 0.79 | 0.79 | 0.78 | 0.78 | 0.77 | 0.77 | 0.77 | 0.76 | 0.76 | 0.76 | 0.76 | 0.76 |
| 23 | 0.77 | 0.76 | 0.75 | 0.75 | 0.74 | 0.74 | 0.74 | 0.73 | 0.73 | 0.73 | 0.73 | 0.73 | 0.73 |
| 24 | 0.74 | 0.73 | 0.72 | 0.72 | 0.71 | 0.71 | 0.70 | 0.70 | 0.70 | 0.70 | 0.70 | 0.70 | 0.70 |
| 25 | 0.71 | 0.70 | 0.69 | 0.69 | 0.68 | 0.68 | 0.67 | 0.67 | 0.67 | 0.67 | 0.67 | 0.67 | 0.66 |
| 26 | 0.68 | 0.67 | 0.67 | 0.65 | 0.65 | 0.65 | 0.64 | 0.64 | 0.64 | 0.64 | 0.64 | 0.64 | 0.63 |
| 27 | 0.65 | 0.64 | 0.63 | 0.62 | 0.62 | 0.62 | 0.61 | 0.61 | 0.61 | 0.61 | 0.61 | 0.61 | 0.60 |
| 28 | 0.62 | 0.61 | 0.60 | 0.59 | 0.59 | 0.59 | 0.58 | 0.58 | 0.58 | 0.58 | 0.58 | 0.58 | 0.57 |
| 29 | 0.59 | 0.58 | 0.57 | 0.57 | 0.56 | 0.56 | 0.55 | 0.55 | 0.55 | 0.55 | 0.55 | 0.55 | 0.54 |
| 30 | 0.56 | 0.55 | 0.54 | 0.54 | 0.53 | 0.53 | 0.52 | 0.52 | 0.52 | 0.52 | 0.52 | 0.52 | 0.52 |
| 31 | 0.53 | 0.52 | 0.51 | 0.51 | 0.50 | 0.50 | 0.50 | 0.49 | 0.49 | 0.49 | 0.49 | 0.49 | 0.49 |
| 32 | 0.50 | 0.49 | 0.48 | 0.48 | 0.48 | 0.47 | 0.47 | 0.47 | 0.46 | 0.46 | 0.46 | 0.46 | 0.46 |
| 33 | 0.47 | 0.48 | 0.45 | 0.45 | 0.45 | 0.44 | 0.44 | 0.44 | 0.44 | 0.43 | 0.43 | 0.43 | 0.43 |
| 34 | 0.45 | 0.43 | 0.43 | 0.42 | 0.42 | 0.42 | 0.41 | 0.41 | 0.41 | 0.41 | 0.41 | 0.41 | 0.40 |
| 35 | 0.42 | 0.40 | 0.40 | 0.39 | 0.39 | 0.39 | 0.38 | 0.38 | 0.38 | 0.38 | 0.38 | 0.38 | 0.38 |
| 36 | 0.39 | 0.38 | 0.37 | 0.37 | 0.36 | 0.36 | 0.36 | 0.36 | 0.36 | 0.36 | 0.36 | 0.36 | 0.36 |
| 37 | 0.36 | 0.35 | 0.34 | 0.34 | 0.34 | 0.33 | 0.33 | 0.33 | 0.33 | 0.33 | 0.33 | 0.33 | 0.32 |
| 38 | 0.33 | 0.32 | 0.32 | 0.31 | 0.31 | 0.31 | 0.30 | 0.30 | 0.30 | 0.30 | 0.30 | 0.30 | 0.30 |
| 39 | 0.30 | 0.30 | 0.29 | 0.28 | 0.28 | 0.28 | 0.28 | 0.28 | 0.28 | 0.28 | 0.28 | 0.28 | 0.28 |
| 40 | 0.28 | 0.25 | 0.25 | 0.25 | 0.25 | 0.25 | 0.25 | 0.25 | 0.25 | 0.25 | 0.25 | 0.25 | 0.25 |
| 41 | 0.25 | 0.23 | 0.23 | 0.23 | 0.23 | 0.23 | 0.23 | 0.23 | 0.23 | 0.23 | 0.23 | 0.23 | 0.23 |
| 42 | 0.23 | 0.20 | 0.20 | 0.20 | 0.20 | 0.20 | 0.20 | 0.20 | 0.20 | 0.20 | 0.20 | 0.20 | 0.20 |
| 43 | 0.18 | 0.18 | 0.18 | 0.18 | 0.18 | 0.18 | 0.18 | 0.18 | 0.18 | 0.18 | 0.18 | 0.18 | 0.18 |
| 44 | 0.16 | 0.15 | 0.15 | 0.15 | 0.15 | 0.15 | 0.15 | 0.15 | 0.15 | 0.15 | 0.15 | 0.15 | 0.15 |
| 45 | 0.13 | 0.13 | 0.13 | 0.13 | 0.13 | 0.13 | 0.13 | 0.13 | 0.13 | 0.13 | 0.13 | 0.13 | 0.13 |
| 46 | 0.10 | 0.10 | 0.10 | 0.10 | 0.10 | 0.10 | 0.10 | 0.10 | 0.10 | 0.10 | 0.10 | 0.10 | 0.10 |
| 47 | 0.08 | 0.08 | 0.08 | 0.08 | 0.08 | 0.08 | 0.08 | 0.08 | 0.08 | 0.08 | 0.08 | 0.08 | 0.08 |
| 48 | 0.05 | 0.05 | 0.05 | 0.05 | 0.05 | 0.05 | 0.05 | 0.05 | 0.05 | 0.05 | 0.05 | 0.05 | 0.05 |
| 49 | 0.03 | 0.03 | 0.03 | 0.03 | 0.03 | 0.03 | 0.03 | 0.03 | 0.03 | 0.03 | 0.03 | 0.03 | 0.03 |
| 50 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 |

1. If the value of $Q_U$ or $Q_L$ does not correspond to a value in the table, use the next lower value.
2. If $Q_U$ or $Q_L$ are negative values, $P_U$ or $P_L$ is equal to 100 minus the table value for $P_U$ or $P_L$.

**Quality Factor Determination**

Determine individual quality factors, $QF_{QCi}$, using percent defective = $P_U + P_L$ and:

**Quality Factors**

| Quality Factor | Maximum Allowable Percent Defective ($P_U + P_L$) | | | | | | | | | | | | |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| | Sample Size (n) | | | | | | | | | | | | |
| | 5 | 6 | 7 | 8 | 9 | 10-11 | 12-14 | 15-17 | 18-22 | 23-29 | 30-42 | 43-66 | >66 |
| 1.05 | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| 1.04 | | | 0 | 1 | 3 | 5 | 4 | 4 | 4 | 3 | 3 | 3 | 3 |
| 1.03 | | 0 | 2 | 4 | 6 | 8 | 7 | 7 | 6 | 5 | 5 | 4 | 4 |
| 1.02 | | 1 | 3 | 6 | 9 | 11 | 10 | 9 | 8 | 7 | 7 | 6 | 6 |
| 1.01 | 0 | 2 | 5 | 8 | 11 | 13 | 12 | 11 | 10 | 9 | 8 | 8 | 7 |
| 1.00 | 22 | 20 | 18 | 17 | 16 | 15 | 14 | 13 | 12 | 11 | 10 | 9 | 8 |
| 0.99 | 24 | 22 | 20 | 19 | 18 | 17 | 16 | 15 | 14 | 13 | 11 | 10 | 9 |
| 0.98 | 26 | 24 | 22 | 21 | 20 | 19 | 18 | 16 | 15 | 14 | 13 | 12 | 10 |
| 0.97 | 28 | 26 | 24 | 23 | 22 | 21 | 19 | 18 | 17 | 16 | 14 | 13 | 12 |
| 0.96 | 30 | 28 | 26 | 25 | 24 | 22 | 21 | 19 | 18 | 17 | 16 | 14 | 13 |
| 0.95 | 32 | 29 | 28 | 26 | 25 | 24 | 22 | 21 | 20 | 18 | 17 | 16 | 14 |
| 0.94 | 33 | 31 | 29 | 28 | 27 | 25 | 24 | 22 | 21 | 20 | 18 | 17 | 15 |
| 0.93 | 35 | 33 | 31 | 29 | 28 | 27 | 25 | 24 | 22 | 21 | 20 | 18 | 16 |
| 0.92 | 37 | 34 | 32 | 31 | 30 | 28 | 27 | 25 | 24 | 22 | 21 | 19 | 18 |
| 0.91 | 38 | 36 | 34 | 32 | 31 | 30 | 28 | 26 | 25 | 24 | 22 | 21 | 19 |
| 0.90 | 39 | 37 | 35 | 34 | 33 | 31 | 29 | 28 | 26 | 25 | 23 | 22 | 20 |
| 0.89 | 41 | 38 | 37 | 35 | 34 | 32 | 31 | 29 | 28 | 26 | 25 | 23 | 21 |
| 0.88 | 42 | 40 | 38 | 36 | 35 | 34 | 32 | 30 | 29 | 27 | 26 | 24 | 22 |
| 0.87 | 43 | 41 | 39 | 38 | 37 | 35 | 33 | 32 | 30 | 29 | 27 | 25 | 23 |
| 0.86 | 45 | 42 | 41 | 39 | 38 | 36 | 34 | 33 | 31 | 30 | 28 | 26 | 24 |
| 0.85 | 46 | 44 | 42 | 40 | 39 | 38 | 36 | 34 | 33 | 31 | 29 | 28 | 25 |
| 0.84 | 47 | 45 | 43 | 42 | 40 | 39 | 37 | 35 | 34 | 32 | 30 | 29 | 27 |
| 0.83 | 49 | 46 | 44 | 43 | 42 | 40 | 38 | 36 | 35 | 33 | 31 | 30 | 28 |
| 0.82 | 50 | 47 | 46 | 44 | 43 | 41 | 39 | 38 | 36 | 34 | 33 | 31 | 29 |
| 0.81 | 51 | 49 | 47 | 45 | 44 | 42 | 41 | 39 | 37 | 36 | 34 | 32 | 30 |
| 0.80 | 52 | 50 | 48 | 46 | 45 | 44 | 42 | 40 | 38 | 37 | 35 | 33 | 31 |
| 0.79 | 54 | 51 | 49 | 48 | 46 | 45 | 43 | 41 | 39 | 38 | 36 | 34 | 32 |
| 0.78 | 55 | 52 | 50 | 49 | 48 | 46 | 44 | 42 | 41 | 39 | 37 | 35 | 33 |
| 0.77 | 56 | 54 | 52 | 50 | 49 | 47 | 45 | 43 | 42 | 40 | 38 | 36 | 34 |
| 0.76 | 57 | 55 | 53 | 51 | 50 | 48 | 46 | 44 | 43 | 41 | 39 | 37 | 35 |
| 0.75 | 58 | 56 | 54 | 52 | 51 | 49 | 47 | 46 | 44 | 42 | 40 | 38 | 36 |
| | 60 | 57 | 55 | 53 | 52 | 51 | 48 | 47 | 45 | 43 | 41 | 40 | 37 |
| | 61 | 58 | 56 | 55 | 53 | 52 | 50 | 48 | 46 | 44 | 43 | 41 | 38 |
| Reject | 62 | 59 | 57 | 56 | 54 | 53 | 51 | 49 | 47 | 45 | 44 | 42 | 39 |
| | 63 | 61 | 58 | 57 | 55 | 54 | 52 | 50 | 48 | 47 | 45 | 43 | 40 |
| | 64 | 62 | 60 | 58 | 57 | 55 | 53 | 51 | 49 | 48 | 46 | 44 | 41 |
| Reject Values Greater Than Those Shown Above | | | | | | | | | | | | | |

Notes:

1. To obtain a quality factor when the estimated percent outside specification limits from table, "Upper Quality Index $Q_U$ or Lower Quality Index $Q_L$," does not correspond to a value in the table, use the next larger value.

Compute the composite of single quality factors, $QF_C$, for a lot using:

$$QF_C = \sum_{i=1}^{5} w_i \, QF_{QC_i}$$

where:

$QF_C$ = the composite quality factor for the lot rounded to 2 decimal places.

$QF_{QCi}$ = the quality factor for the individual quality characteristic.

w = the weighting factor listed in the table HMA Acceptance – QC / QA.
*i* = the quality characteristic index number in the table HMA Acceptance – QC / QA.

## 39-4.04 ENGINEER'S QUALITY ASSURANCE

### 39-4.04A General

The Engineer assures quality by:

1. Reviewing mix designs and proposed JMF
2. Inspecting procedures
3. Conducting oversight of quality control inspection and records
4. Verification sampling and testing during production and paving

### 39-4.04B Verification Sampling And Testing

#### General

The Engineer samples:

1. Aggregate to verify gradation
2. HMA to verify asphalt binder content

#### Verification

For aggregate gradation and asphalt binder content, the ratio of verification testing frequency to the minimum quality control testing frequency is 1:5. The Engineer performs at least 3 verification tests per lot.

Using the t-test, the Engineer compares quality control tests results for aggregate gradation and asphalt binder content with corresponding verification test results. The Engineer uses the average and standard deviation of up to 20 sequential sublots for the comparison. The Engineer uses production start-up evaluation tests to represent the first sublot. When there are less than 20 sequential sublots, the Engineer uses the maximum number of sequential sublots available. The 21st sublot becomes the 1st sublot (n = 1) in the next lot.

The t-value for a group of test data is computed as follows:

$$t = \frac{\left|\overline{X}_c - \overline{X}_v\right|}{S_p\sqrt{\frac{1}{n_c} + \frac{1}{n_v}}} \quad \text{and} \quad S_p^2 = \frac{S_c^2(n_c - 1) + S_v^2(n_v - 1)}{n_c + n_v - 2}$$

where:

$n_c$ = Number of quality control tests (2 minimum, 20 maximum).
$n_v$ = Number of verification tests (minimum of 1 required).
$\overline{X}_c$ = Mean of quality control tests.
$\overline{X}_v$ = Mean of verification tests.
$S_p$ = Pooled standard deviation (When $n_v = 1$, $S_p = S_c$).
$S_c$ = Standard deviation of quality control tests.
$S_v$ = Standard deviation of verification tests (when $n_v > 1$).

The comparison of quality control test results and the verification test results is at a level of significance of $\alpha = 0.025$. The Engineer computes t and compares it to the critical t-value, $t_{crit}$, from:

**Critical T-Value**

| Degrees of freedom ($n_c$+$n_v$-2) | $t_{crit}$ (for $\alpha$ = 0.025) | Degrees of freedom ($n_c$+$n_v$-2) | $t_{crit}$ (for $\alpha$ = 0.025) |
|---|---|---|---|
| 1 | 24.452 | 18 | 2.445 |
| 2 | 6.205 | 19 | 2.433 |
| 3 | 4.177 | 20 | 2.423 |
| 4 | 3.495 | 21 | 2.414 |
| 5 | 3.163 | 22 | 2.405 |
| 6 | 2.969 | 23 | 2.398 |
| 7 | 2.841 | 24 | 2.391 |
| 8 | 2.752 | 25 | 2.385 |
| 9 | 2.685 | 26 | 2.379 |
| 10 | 2.634 | 27 | 2.373 |
| 11 | 2.593 | 28 | 2.368 |
| 12 | 2.560 | 29 | 2.364 |
| 13 | 2.533 | 30 | 2.360 |
| 14 | 2.510 | 40 | 2.329 |
| 15 | 2.490 | 60 | 2.299 |
| 16 | 2.473 | 120 | 2.270 |
| 17 | 2.458 | $\infty$ | 2.241 |

If the t-value computed is less than or equal to $t_{crit}$, quality control test results are verified.

If the t-value computed is greater than $t_{crit}$ and both $\overline{X}_v$ and $\overline{X}_c$ comply with acceptance specifications, the quality control tests are verified. You may continue to produce and place HMA with the following allowable differences:

1. $\left|\overline{X}_v - \overline{X}_c\right| \leq 1.0$ percent for any grading
2. $\left|\overline{X}_v - \overline{X}_c\right| \leq 0.1$ percent for asphalt binder content

If the t-value computed is greater than $t_{crit}$ and the $\left|\overline{X}_v - \overline{X}_c\right|$ for grading and asphalt binder content are greater than the allowable differences, quality control test results are not verified and:

1. The Engineer notifies you in writing.
2. You and the Engineer must investigate why the difference exist.
3. If the reason for the difference cannot be found and corrected, the Engineer's test results are used for acceptance and pay.

## 39-4.05 ENGINEER'S ACCEPTANCE

### 39-4.05A Testing

The Engineer samples for acceptance testing and tests for:

**HMA Acceptance – QC / QA**

| Index (i) | Quality Characteristic | | | | Weight-ing Factor (w) | Test Method | HMA Type | | |
|---|---|---|---|---|---|---|---|---|---|
| | | | | | | | A | B | RHMA-G |
| | | Aggregate gradation [a] | | | | | | | |
| | Sieve | 3/4" | 1/2" | 3/8" | | | | | |
| 1 | 1/2" | X [b] | -- | -- | 0.05 | CT 202 | JMF ± Tolerance [c] | | |
| 1 | 3/8" | -- | X | -- | 0.05 | | | | |
| 1 | No. 4 | -- | -- | X | 0.05 | | | | |
| 2 | No. 8 | X | X | X | 0.10 | | | | |
| 3 | No. 200 | X | X | X | 0.15 | | | | |
| 4 | Asphalt binder content (%) | | | | 0.30 | CT 379 or 382 | JMF ± 0.45 | JMF ± 0.45 | JMF ± 0.5 |
| 5 | Percent of maximum theoretical density (%) [d, e] | | | | 0.40 | CT 375 | 92 – 96 | 92 – 96 | 91 – 96 |
| | Sand equivalent (min.) [f] | | | | | CT 217 | 47 | 42 | 47 |
| | Stabilometer value (min.) [f,, g]<br>No. 4 and 3/8" gradings<br>1/2" and 3/4" gradings | | | | | CT 366 | <br>30<br>37 | <br>30<br>35 | <br>--<br>23 |
| | Air voids content (%) [f, h] | | | | | CT 367 | 4 ± 2 | 4 ± 2 | Specifica-tion ± 2 |
| | Percent of crushed particles coarse aggregate (% min.)<br>One fractured face<br>Two fractured faces<br>Fine aggregate (% min)<br>(Passing No. 4 sieve and retained on No. 8 sieve.)<br>One fractured face | | | | | CT 205 | <br>90<br>70<br><br><br>70 | <br>25<br>--<br><br><br>20 | <br>--<br>90<br><br><br>70 |
| | HMA moisture content (%, max.) | | | | | CT 226 or CT 370 | 1.0 | 1.0 | 1.0 |
| | Los Angeles Rattler (% max.)<br>Loss at 100 rev.<br>Loss at 500 rev. | | | | | CT 211 | <br>12<br>45 | <br>--<br>50 | <br>12<br>45 |
| | Fine aggregate angularity (% min.) | | | | | AASHTO T 304, Method A | 45 | 45 | 45 |
| | Flat and elongated particle (% max. by weight @ 5:1) | | | | | ASTM D 4791 | Report only | Report only | Report only |
| | Voids in mineral aggregate (% min.) [i]<br>No. 4 grading<br>3/8" grading<br>1/2" grading<br>3/4" grading | | | | | LP-2 | <br>17.0<br>15.0<br>14.0<br>13.0 | <br>17.0<br>15.0<br>14.0<br>13.0 | (Note j)<br>--<br>--<br>18.0 - 23.0<br>18.0 - 23.0 |
| | Voids filled with asphalt (%) [i]<br>No. 4 grading<br>3/8" grading<br>1/2" grading<br>3/4" grading | | | | | LP-3 | <br>76.0 - 80.0<br>73.0 - 76.0<br>65.0 - 75.0<br>65.0 - 75.0 | <br>76.0 - 80.0<br>73.0 - 76.0<br>65.0 - 75.0<br>65.0 - 75.0 | Report only |
| | Dust proportion [i]<br>No. 4 and 3/8" gradings<br>1/2" and 3/4" gradings | | | | | LP-4 | <br>0.9 - 2.0<br>0.6 - 1.3 | <br>0.9 – 2.0<br>0.6 – 1.3 | Report only |

| | | | | | | |
|---|---|---|---|---|---|---|
| | Smoothness | | Section 39-1.12 | 12-foot straight-edge, must-grind, and $PI_0$ | 12-foot straight-edge, must-grind, and $PI_0$ | 12-foot straight-edge, must-grind, and $PI_0$ |
| | Asphalt binder | | Various | Section 92 | Section 92 | Section 92 |
| | Asphalt rubber binder | | Various | -- | -- | Section 92-1.02(C) and Section 39-1.02D |
| | Asphalt modifier | | Various | -- | -- | Section 39-1.02D |
| | Crumb rubber modifier | | Various | -- | -- | Section 39-1.02D |

Notes:

[a] The Engineer determines combined aggregate gradations containing RAP under Laboratory Procedure LP-9.

[b] "X" denotes the sieves the Engineer considers for the specified aggregate gradation.

[c] The tolerances must comply with the allowable tolerances in Section 39-1.02E, "Aggregate."

[d] The Engineer determines percent of maximum theoretical density if the specified paved thickness is at least 0.15 foot under California Test 375 except the Engineer uses:

1. California Test 308, Method A, to determine in-place density of each density core instead of using the nuclear gauge in Part 4, "Determining In-Place Density By The Nuclear Density Device."
2. California Test 309 to determine maximum theoretical density instead of calculating test maximum density in Part 5, "Determining Test Maximum Density."

[e] The Engineer determines maximum theoretical density (California Test 309) at the frequency specified for Test Maximum Density under California Test 375, Part 5.D.

[f] The Engineer reports the average of 3 tests from a single split sample.

[g] Modify California Test 304, Part 2.B.2.c: "After compaction in the mechanical compactor, cool to 140 °F ± 5 °F by allowing the briquettes to cool at room temperature for 0.5 hour, then place the briquettes in the oven at 140 °F for a minimum of 2 hours and not more than 3 hours."

[h] The Engineer determines the bulk specific gravity of each lab-compacted briquette under California Test 308, Method A, and theoretical maximum specific gravity under California Test 309.

[i] Report only if the adjustment for asphalt binder content target value is less than or equal to ± 0.3 percent from OBC.

[j] Voids in mineral aggregate for RHMA-G must be within this range.

The Engineer determines the percent of maximum theoretical density from the average density of 3 density cores you take from every 750 tons of production or part thereof divided by the maximum theoretical density.

If the specified total paved thickness is at least 0.15 foot and any layer is less than 0.15 foot, the Engineer determines the percent of maximum theoretical density from density cores taken from the final layer measured the full depth of the total paved HMA thickness.

The Engineer stops production and terminates a lot if:

1. The lot's composite quality factor, $Q_{FC}$, or an individual quality factor, $QF_{QCi}$ for i = 3, 4, or 5, is below 0.90 determined under Section 39-4.03F, "Statistical Evaluation"
2. An individual quality factor, $QF_{QCi}$ for i = 1 or 2, is below 0.75
3. Quality characteristics for which a quality factor, $QF_{QCi}$, is not determined has 2 consecutive acceptance or quality control tests not in compliance with the specifications

For any single quality characteristic for which a quality factor, $QF_{QCi}$, is not determined, except smoothness, if 2 consecutive acceptance test results do not comply with specifications:

1. Stop production.
2. Take corrective action.

3. In the Engineer's presence, take samples and split each sample into 4 parts. Test 1 part for compliance with the specifications and submit 3 parts to the Engineer. The Engineer tests 1 part for compliance with the specifications and reserves and stores 2 parts.
4. Demonstrate compliance with the specifications before resuming production and placement on the State highway.

### 39-4.05B Statistical Evaluation, Determination Of Quality Factors And Acceptance

#### Statistical Evaluation and Determination of Quality Factors

To determine the individual quality factor, $QF_{QCi,}$ for any quality factor i = 1 through 5 or a lot's composite quality factor, $QF_C$, for acceptance and payment adjustment, the Engineer uses the evaluation specifications under Section 39-4.03F, "Statistical Evaluation," and:

1. Verified quality control test results for aggregate gradation
2. Verified quality control test results for asphalt binder content
3. The Engineer's test results for percent of maximum theoretical density

#### Lot Acceptance Based on Quality Factors

The Engineer accepts a lot based on the quality factors determined for aggregate gradation and asphalt binder content, $QF_{QCi}$ for i = 1 through 4, using the total number of verified quality control test result values and the total percent defective ($P_U + P_L$).

The Engineer accepts a lot based on the quality factor determined for maximum theoretical density, $QF_{QC5}$, using the total number of test result values from density cores and the total percent defective ($P_U + P_L$).

The Engineer calculates the quality factor for the lot, $QF_C$, which is a composite of weighted individual quality factors, $QF_{QCi}$, determined for each quality characteristic in the HMA Acceptance – QC / QA table in Section 39-4.05A, "Testing."

The Engineer accepts a lot based on quality factors if:

1. The current composite quality factor, $QF_C$, is 0.90 or greater
2. Each individual quality factor, $QF_{QCi}$ for i = 3, 4, and 5, is 0.90 or greater
3. Each individual quality factor, $QF_{QCi}$ for i = 1 and 2, is 0.75 or greater

No single quality characteristic test may represent more than the smaller of 750 tons or 1 day's production.

#### Payment Adjustment

If a lot is accepted, the Engineer adjusts payment with the following formula:

$$PA = \sum_{i=1}^{n} HMACP * wi * \left[QFQCi * (HMATT - WHMATTi) + WHMATTi\right] - (HMACP * HMATT)$$

where:

| | |
|---|---|
| PA = | Payment adjustment rounded to 2 decimal places. |
| *HMACP* = | HMA contract price. |
| *HMATT* = | HMA total tons represented in the lot. |
| $WHMATT_i$ = | Total tons of waived quality characteristic HMA. |
| $QF_{QCi}$ = | Running quality factor for the individual quality characteristic. $QF_{QCi}$ for i = 1 through 4 must be from verified Contractor's QC results. $QF_{QC5}$ must be determined from the Engineer's results on density cores taken for percent of maximum theoretical density determination. |
| *w* = | Weighting factor listed in the HMA acceptance table. |
| *i* = | Quality characteristic index number in the HMA acceptance table. |

If the payment adjustment is a negative value, the Engineer deducts this amount from payment. If the payment adjustment is a positive value, the Engineer adds this amount to payment.

The 21st sublot becomes the 1st sublot (n = 1) in the next lot. When the 21st sequential sublot becomes the 1st sublot, the previous 20 sequential sublots become a lot for which the Engineer determines a quality factor. The Engineer uses this quality factor to pay for the HMA in the lot. If the next lot consists of less than 8 sublots, these sublots must be added to the previous lot for quality factor determination using 21 to 27 sublots.

### 39-4.05C Dispute Resolution

For a lot, if you or the Engineer dispute any quality factor, $QF_{QCi}$, or verification test result, every sublot in that lot must be retested.

Referee tests must be performed under the specifications for acceptance testing.

Any quality factor, $QF_{QCi}$, must be determined using the referee tests.

For any quality factor, $QF_{QCi}$, for i = 1 through 5, dispute resolution:

1. If the difference between the quality factors for $QF_{QCi}$ using the referee test result and the disputed test result is less than or equal to 0.01, the original test result is correct.
2. If the difference between the quality factor for $QF_{QCi}$ using the referee test result and the disputed test result is more than 0.01, the quality factor determined from the referee tests supersedes the previously determined quality factor.

## 39-5 MEASUREMENT AND PAYMENT

### 39-5.01 MEASUREMENT

The contract item for HMA is measured by weight. The weight of each HMA mixture designated in the Engineer's Estimate must be the combined mixture weight.

If tack coat, asphalt binder, and asphaltic emulsion are paid with separate contract items, their contract items are measured under Section 92, "Asphalts," or Section 94, "Asphaltic Emulsions," as the case may be.

If recorded batch weights are printed automatically, the contract item for HMA is measured by using the printed batch weights, provided:

1. Total aggregate and supplemental fine aggregate weight per batch is printed. If supplemental fine aggregate is weighed cumulatively with the aggregate, the total aggregate batch weight must include the supplemental fine aggregate weight.
2. Total asphalt binder weight per batch is printed.
3. Each truckload's zero tolerance weight is printed before weighing the first batch and after weighing the last batch.
4. Time, date, mix number, load number and truck identification is correlated with a load slip.
5. A copy of the recorded batch weights is certified by a licensed weighmaster and submitted to the Engineer.

The contract item for placing HMA dike is measured by the linear foot along the completed length. The contract item for placing HMA in miscellaneous areas is measured as the in-place compacted area in square yards. In addition to the quantities measured on a linear foot or square yard basis, the HMA for dike and miscellaneous areas are measured by weight.

The contract item for geosynthetic pavement interlayer is measured by the square yard for the actual pavement area covered.

### 39-5.02 PAYMENT

The contract prices paid per ton for hot mix asphalt as designated in the Engineer's Estimate include full compensation for furnishing all labor, materials, tools, equipment, and incidentals for doing all the work involved in constructing hot mix asphalt, complete in place, as shown on the plans, as specified in these specifications and the special provisions, and as directed by the Engineer.

If HMA is specified to comply with Section 39-4, "Quality Control / Quality Assurance," the Engineer adjusts payment under that section.

Full compensation for the Quality Control Plan and prepaving conference is included in the contract prices paid per ton for hot mix asphalt as designated in the Engineer's Estimate and no additional compensation will be allowed therefor.

Full compensation for performing and submitting mix designs and for Contractor sampling, testing, inspection, testing facilities, and preparation and submittal of results is included in the contract prices paid per ton for HMA as designated in the Engineer's Estimate and no additional compensation will be allowed therefor.

Full compensation for reclaimed asphalt pavement is included in the contract prices paid per ton for HMA as designated in the Engineer's Estimate and no additional compensation will be allowed therefor.

The contract price paid per ton for hot mix asphalt (leveling) includes full compensation for furnishing all labor, materials, tools, equipment, and incidentals for doing all the work involved in hot mix asphalt (leveling), complete in place, as shown on the plans, as specified in these specifications and the special provisions, and as directed by the Engineer.

The State pays for HMA dike at the contract price per linear foot for place HMA dike and by the ton for HMA. The contract prices paid per linear foot for place hot mix asphalt dike as designated in the Engineer's Estimate include full compensation for furnishing all labor, tools, equipment, and incidentals, and for doing all the work involved in placing HMA dike, complete in place, including excavation, backfill, and preparation of the area to receive the dike, as shown on the plans, as specified in these specifications and the special provisions, and as directed by the Engineer.

The State pays for HMA specified to be a miscellaneous area at the contract price per square yard for place hot mix asphalt (miscellaneous area) and per ton for hot mix asphalt. The contract price paid per square yard for place hot mix asphalt (miscellaneous area) includes full compensation for furnishing all labor, tools, equipment, and incidentals, and for doing all the work involved in placing HMA (miscellaneous area) complete in place, including excavation, backfill, and preparation of the area to receive HMA (miscellaneous area), as shown on the plans, as specified in these specifications and the special provisions, and as directed by the Engineer.

If the Quality Control / Quality Assurance construction process is specified, HMA placed in dikes and miscellaneous areas is paid for at the contract price per ton for hot mix asphalt under Section 39-4, "Quality Control / Quality Assurance." Section 39-4.05B, "Statistical Evaluation, Determination of Quality Factors and Acceptance," does not apply to HMA placed in dikes and miscellaneous areas.

If there are no contract items for place hot mix asphalt dike and place hot mix asphalt (miscellaneous area) and the work is specified, full compensation for constructing HMA dikes and HMA (miscellaneous areas) including excavation, backfill, and preparation of the area to receive HMA dike or HMA (miscellaneous area) is included in the contract price paid per ton for the hot mix asphalt designated in the Engineer's Estimate and no separate payment will be made therefor.

The contract price paid per square yard for geosynthetic pavement interlayer includes full compensation for furnishing all labor, materials, tools, equipment, and incidentals, and for doing all the work involved in placing geosynthetic pavement interlayer, complete in place, as shown on the plans, as specified in these specifications and the special provisions, and as directed by the Engineer.

The contract price paid per ton for paving asphalt (binder, geosynthetic pavement interlayer) includes full compensation for furnishing all labor, materials, tools, equipment, and incidentals, and for doing all the work involved in applying paving asphalt (binder, geosynthetic pavement interlayer), complete in place, including spreading sand to cover exposed binder material, as shown on the plans, as specified in these specifications and the special provisions, and as directed by the Engineer.

Full compensation for small quantities of HMA placed on geosynthetic pavement interlayer to prevent displacement during construction is included in the contract price paid per ton for the HMA being paved over the interlayer and no separate payment will be made therefor.

The contract price paid per ton for tack coat includes full compensation for furnishing all labor, materials, tools, equipment, and incidentals, and for doing all the work involved in applying tack coat, complete in place, as shown on the plans, as specified in these specifications and the special provisions, and as directed by the Engineer.

The Engineer does not adjust payment for increases or decreases in the quantities for tack coat, regardless of the reason for the increase or decrease. Section 4-1.03B, "Increased or Decreased Quantities," does not apply to the items for tack coat.

Full compensation for performing smoothness testing, submitting written and electronic copies of tests, and performing corrective work including applying fog seal coat is included in the contract price paid per ton for the HMA designated in the Engineer's Estimate and no separate payment will be made therefor.

Full compensation for spreading sand on RHMA-G, RHMA-O, and RHMA-O-HB surfaces and for sweeping and removing excess sand is included in the contract price paid per ton for rubberized hot mix asphalt as designated in the Engineer's Estimate and no separate payment will be made therefor.

If the Engineer fails to comply with a specification within a specified time, and if, in the opinion of the Engineer, work completion is delayed because of the failure, the Engineer adjusts payment and contract time under Section 8-1.09, "Right of Way Delays."

If the dispute resolution ITP determines the Engineer's test results are correct, the Engineer deducts the ITP's testing costs from payments. If the ITP determines your test results are correct, the State pays the ITP's testing costs. If, in the Engineer's opinion, work completion is delayed because of incorrect Engineer test results, the Engineer adjusts payment and contract time under Section 8-1.09, "Right of Way Delays."

^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^

## SECTION 40 PORTLAND CEMENT CONCRETE PAVEMENT

**(Issued 01-05-07)**

**Replace Section 40-1.015 with:**

**40-1.015 (Blank)**

**Replace Section 40-1.05 with:**

**40-1.05 PROPORTIONING**

Aggregate and cementitious material proportioning shall conform to the provisions in Section 90-5, "Proportioning."

**Replace Section 40-1.105 with:**

**40-1.105 EXIT RAMP TERMINI**

Concrete pavement shall be constructed at the ends of exit ramps when required by the plans or the special provisions. Texturing for exit ramp termini shall be by means of heavy brooming in a direction normal to ramp centerline. The hardened surface shall have a coefficient of friction not less than 0.35 as determined by California Test 342. Minimum cementitious material content of concrete in pavement for exit ramp termini shall be 590 pounds per cubic yard.

**In Section 40-1.14 replace the 1st paragraph with:**

The contract price paid per cubic yard for concrete pavement shall include full compensation for furnishing all labor, materials (including cementitious material in the amount specified), tools, equipment, and incidentals, and for doing all the work involved in constructing the portland cement concrete pavement, complete in place, as shown on the plans, and as specified in these specifications and the special provisions, and as directed by the Engineer.

^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^

## SECTION 41 PAVEMENT SUBSEALING AND JACKING

**(Issued 01-05-07)**

**In Section 41-1.02 replace the 2nd and 3rd paragraphs with:**

Cement for grout shall be Type II portland cement conforming to the provisions in Section 90-2.01A, "Cement."

Fly ash shall conform to the requirements in AASHTO Designation: M 295 for either Class C or for Class F. The brand of fly ash used in the work shall conform to the provisions for approval of admixture brands in Section 90-4.03, "Admixture Approval."

**In Section 41-1.02 replace the 5th paragraph with:**

Chemical admixtures and calcium chloride may be used. Chemical admixtures in the grout mix shall conform to the provisions in Section 90-4, "Admixtures." Calcium chloride shall conform to ASTM Designation: D 98.

^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^

## SECTION 49 PILING

**(Issued 12-19-08)**

**In Section 49-1.03 replace the 4th paragraph with:**

Modification to the specified installation methods and specified pile tip elevation will not be considered at locations where settlement, tension demands, or lateral load demands control design pile tip elevations or when the plans state that specified pile tip elevation shall not be revised.

**In Section 49-1.03 in the 6th paragraph, replace the 1st sentence with:**

Indicator compression pile load testing shall conform to the requirements in ASTM Designation: D 1143-81.

**In Section 49-1.03 in the 7th paragraph, replace the 1st sentence with:**

Indicator tension pile load testing shall conform to the requirements in ASTM Designation: D 3689-90.

**In Section 49-1.03 replace the 9th paragraph with:**

The Contractor shall furnish piling of sufficient length to obtain the specified tip elevation shown on the plans or specified in the special provisions.

**In Section 49-1.04 replace the 6th paragraph with:**

The Contractor may use additional cementitious material in the concrete for the load test and anchor piles.

**In Section 49-6.01 replace the 1st paragraph with:**

The length of timber, steel, and precast prestressed concrete piles, and of cast-in-place concrete piles consisting of driven shells filled with concrete, shall be measured along the longest side, from the tip elevation shown on the plans to the plane of pile cut-off.

**In Section 49-6.02 add:**

When pile tips are revised by the Engineer for timber, steel, and precast prestressed concrete piles, and for cast-in-place concrete piles consisting of driven shells filled with concrete, the additional length required, including all materials, equipment, and labor for furnishing, splicing, and installing the piling, will be paid for as extra work as provided in Section 4-1.03D, "Extra Work."

^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^

## SECTION 50 PRESTRESSING CONCRETE
**(Issued 04-04-08)**

**In Section 50-1.05 in the 3rd paragraph, delete item A.**

**In Section 50-1.07 replace the 2nd paragraph with:**

Ducts shall be fabricated with either welded or interlocked seams. Galvanizing of the welded seam will not be required. Ducts shall have sufficient strength to maintain their correct alignment during placing of concrete. Joints between sections of duct shall be positive metallic connections which do not result in angle changes at the joints. Waterproof tape shall be used at the connections. Ducts shall be bent without crimping or flattening. Transition couplings connecting the ducts to anchoring devices shall be either ferrous metal or polyolefin. Ferrous metal transition couplings need not be galvanized.

**In Section 50-1.07 replace the 7th paragraph with:**

All ducts with a total length of 400 feet or more shall be vented. Vents shall be placed at intervals of not more than 400 feet and shall be located within 6 feet of every high point in the duct profile. Vents shall be 1/2 inch minimum diameter standard pipe or suitable plastic pipe. Connections to ducts shall be made with metallic or plastic structural fasteners. Plastic components, if selected, shall not react with the concrete or enhance corrosion of the prestressing steel and shall be free of water soluble chlorides. The vents shall be mortar tight, taped as necessary, and shall provide means for injection of grout through the vents and for sealing the vents. Ends of vents shall be removed one inch below the roadway surface after grouting has been completed.

**In Section 50-1.08 in the 11th paragraph, replace item B with:**

B. When the concrete is designated by class or cementitious material content, either the concrete compressive strength shall have reached the strength shown on the plans at the time of stressing or at least 28 days shall have elapsed since the last concrete to be prestressed has been placed, whichever occurs first.

**In Section 50-1.09 replace the 2nd and 3rd paragraphs with:**

Grout shall consist of cement and water and may contain an admixture if approved by the Engineer.

Cement shall conform to the provisions in Section 90-2.01A, "Cement."

**In Section 50-1.11 replace the 1st paragraph with:**

No separate payment will be made for pretensioning precast concrete members. Payment for pretensioning precast concrete members shall be considered as included in the contract price paid for furnish precast members as provided for in Section 51, "Concrete Structures."

^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^

## SECTION 51 CONCRETE STRUCTURES
**(Issued 05-02-08)**

**In Section 51-1.05 in the 11th paragraph, replace the 1st sentence with:**

Form panels for exposed surfaces shall be furnished and placed in uniform widths of not less than 3 feet and in uniform lengths of not less than 6 feet, except at the end of continuously formed surfaces where the final panel length required is less than 6 feet.

**In Section 51-1.06C in the 11th paragraph, replace the 1st sentence with:**

Falsework for box culverts and other structures with decks lower than the roadway pavement and with span lengths of 14 feet or less shall not be released until the last placed concrete has attained a compressive strength of 1,600 psi, provided that curing of the concrete is not interrupted.

**In Section 51-1.11 replace the 6th paragraph with:**

Construction methods and equipment employed by the Contractor shall conform to the provisions in Section 7-1.02, "Load Limitations."

**In Section 51-1.12D replace the 4th paragraph with:**

Expanded polystyrene shall be a commercially available polystyrene board. Expanded polystyrene shall have a minimum flexural strength of 35 psi determined in conformance with the requirements in ASTM Designation: C 203 and a compressive yield strength of between 16 and 40 psi at 5 percent compression. Surfaces of expanded polystyrene against which concrete is placed shall be faced with hardboard. Hardboard shall be 1/8 inch minimum thickness, conforming to ANSI A135.4, any class. Other facing materials may be used provided they furnish equivalent protection. Boards shall be held in place by nails, waterproof adhesive, or other means approved by the Engineer.

**In Section 51-1.12F replace the 3rd paragraph with:**

Type A and AL joint seals shall consist of a groove in the concrete that is filled with field-mixed silicone sealant.

**In Section 51-1.12F in the 6th paragraph, replace the table with:**

| Movement Rating (MR) | Seal Type |
|---|---|
| MR ≤ 1 inch | Type A or Type B |
| 1 inch < MR ≤ 2 inches | Type B |
| 2 inches < MR ≤ 4 inches | Joint Seal Assembly (Strip Seal) |
| MR > 4 inches | Joint Seal Assembly (Modular Unit) or Seismic Joint |

**In Section 51-1.12F(3)(a) replace the 1st and 2nd paragraphs with:**

The sealant must consist of a 2-component silicone sealant that will withstand up to ±50 percent movement. Silicone sealants must be tested under California Test 435 and must comply with the following:

| Specification | Requirement |
|---|---|
| Modulus at 150 percent elongation | 8-75 psi |
| Recovery | 21/32 inch max. |
| Notch Test | Notched or loss of bond 1/4 inch, max. |
| Water Resistance | Notched or loss of bond 1/4 inch, max. |
| Ultraviolet Exposure<br>ASTM Designation: G 154, Table X2.1,Cycle 2. | No more than slight checking or cracking. |
| Cone Penetration | 4.5-12.0 mm |

**In Section 51-1.12F(3)(a) delete the 3rd and 8th paragraphs.**

**In Section 51-1.12F(3)(a) replace the 10th paragraph with:**

A Certificate of Compliance accompanied by a certified test report must be furnished for each batch of silicone sealant in conformance with the provisions in Section 6-1.07, "Certificates of Compliance."

**In Section 51-1.12F(3)(b) replace the 2nd paragraph with:**

The preformed elastomeric joint seal must conform to the requirements in ASTM D 2628 and the following:

1. The seal must consist of a multichannel, nonporous, homogeneous material furnished in a finished extruded form.
2. The minimum depth of the seal measured at the contact surface must be at least 95 percent of the minimum uncompressed width of the seal as designated by the manufacturer.
3. When tested in conformance with the requirements in California Test 673 for Type B seals, joint seals must provide a movement rating (MR) of not less than that shown on the plans.
4. The top and bottom edges of the joint seal must maintain continuous contact with the sides of the groove over the entire range of joint movement.
5. The seal must be furnished full length for each joint with no more than 1 shop splice in any 60-foot length of seal.
6. The Contractor must demonstrate the adequacy of the procedures to be used in the work before installing seals in the joints.
7. One field splice per joint may be made at locations and by methods approved by the Engineer. The seals are to be manufactured full length for the intended joint, then cut at the approved splice section and rematched before splicing. The Contractor must submit splicing details prepared by the joint seal manufacturer for approval before beginning splicing work.
8. Shop splices and field splices must have no visible offset of exterior surfaces and must show no evidence of bond failure.
9. At all open ends of the seal that would admit water or debris, each cell must be filled to a depth of 3 inches with commercial quality open cell polyurethane foam or closed by other means subject to approval by the Engineer.

**In Section 51-1.12F(3)(b) replace the 7th paragraph with:**

The joint seal must be installed full length for each joint with equipment that does not twist or distort the seal, elongate the seal longitudinally, or otherwise cause damage to the seal or to the concrete forming the groove.

**In Section 51-1.12F(3)(b) in the 11th paragraph, replace the 1st sentence with:**

Samples of the prefabricated joint seals, not less than 3 feet in length, will be taken by the Engineer from each lot of material.

**In Section 51-1.12H(1) in the 6th paragraph, replace the 4th and 5th sentences with:**

Each ply of fabric shall have a breaking strength of not less than 800 pounds per inch of width in each thread direction when 3" x 36" samples are tested on split drum grips. The bond between double plies shall have a minimum peel strength of 20 pounds per inch.

**In Section 51-1.12H(1) in the 8th paragraph in the table, replace the hardness (Type A) requirements with:**

| | | |
|---|---|---|
| Hardness (Type A) | D 2240 with 2kg mass. | 55 ±5 |

**In Section 51-1.12H(2) in the 1st paragraph in item A, replace the 1st and 2nd sentences with:**

The bearings shall consist of alternating steel laminates and internal elastomer laminates with top and bottom elastomer covers. Steel laminates shall have a nominal thickness of 0.075 inch (14 gage).

**In Section 51-1.135 replace the 1st paragraph with:**

Mortar shall be composed of cementitious material, sand, and water proportioned and mixed as specified in this Section 51-1.135.

**In Section 51-1.135 replace the 3rd paragraph with:**

The proportion of cementitious material to sand, measured by volume, shall be 1 to 2 unless otherwise specified.

**In Section 51-1.17 in 4th paragraph, replace the 3rd sentence with:**

The surfaces shall have a profile trace showing no high points in excess of 0.25 inch, and the portions of the surfaces within the traveled way shall have a profile count of 5 or less in any 100 foot section.

**Add:**

**51-1.17A Deck Crack Treatment**

The Contractor shall use all means necessary to minimize the development of shrinkage cracks.

The Contractor shall remove all equipment and materials from the deck and clean the surface as necessary for the Engineer to measure the surface crack intensity. Surface crack intensity will be determined by the Engineer after completion of concrete cure, before prestressing, and before the release of falsework. In any 500 square foot portion of deck within the limits of the new concrete deck, should the intensity of cracking be such that there are more than 16 feet of cracks whose width at any location exceeds 0.02 inch, the deck shall be treated with methacrylate resin. The area of deck to be treated shall have a width that extends for the entire width of new deck inside the concrete barriers and a length that extends at least 5 feet beyond the furthest single continuous crack outside the 500 square foot portion, measured from where that crack exceeds 0.02 inch in width, as determined by the Engineer.

Deck crack treatment shall include furnishing, testing, and application of methacrylate resin and sand. If grinding is required, deck treatment shall take place before grinding.

**51-1.17A(1) Submittals**

Before starting deck treatment, the Contractor shall submit plans in conformance with Section 5-1.02, "Plans and Working Drawings," for the following:

1. Public safety plan for the use of methacrylate resin

2. Placement plan for the construction operation

The plans shall identify materials, equipment, and methods to be used.
The public safety plan for the use of methacrylate resin shall include details for the following:

1. Shipping
2. Storage
3. Handling
4. Disposal of residual methacrylate resin and the containers

The placement plan for construction shall include the following:

1. Schedule of deck treatment for each bridge. The schedule shall be consistent with "Maintaining Traffic" of the special provisions and shall include time for the Engineer to perform California Test 342.
2. Methods and materials to be used, including the following:

    2.1. Description of equipment for applying the resin
    2.2. Description of equipment for applying the sand
    2.3. Gel time range and final cure time for the resin

If the measures proposed in the safety plan are inadequate to provide for public safety associated with the use of methacrylate resin, the Engineer will reject the plan and direct the Contractor to revise the plan. Directions for revisions will be in writing and include detailed comments. The Engineer will notify the Contractor of the approval or rejection of a submitted or revised plan within 15 days of receipt of that plan.

In the event the Engineer fails to complete the review within the time allowed, and if, in the opinion of the Engineer, completion of the work is delayed or interfered with by reason of the Engineer's delay in completing the review, the Contractor will be compensated for any resulting loss, and an extension of time will be granted, in the same manner as provided for in Section 8-1.09, "Right of Way Delays."

**51-1.17A(2) Materials**

Before using methacrylate resin, a Material Safety Data Sheet shall be submitted for each shipment of resin.

Methacrylate resin shall be low odor and have a high molecular weight. Before adding initiator, the resin shall have a maximum volatile content of 30 percent when tested in conformance with the requirements in ASTM Designation: D 2369, and shall conform to the following:

| PROPERTY | REQUIREMENT | TEST METHOD |
|---|---|---|
| * Viscosity | 25 cP, maximum, (Brookfield RVT with UL adaptor, 50 RPM at 77°F | ASTM D 2196 |
| * Specific Gravity | 0.90 minimum, at 77°F | ASTM D 1475 |
| * Flash Point | 180°F, minimum | ASTM D 3278 |
| * Vapor Pressure | 1.0 mm Hg, maximum, at 77°F | ASTM D 323 |
| Tack-free Time | 400 minutes, maximum at 25°C | Specimen prepared per California Test 551 |
| PCC Saturated Surface-Dry Bond Strength | 3.5 MPa, minimum at 24 hours and 21±1°C | California Test 551 |
| * Test shall be performed before adding initiator. | | |

**51-1.17A(3) Testing**

The Contractor shall allow 20 days for sampling and testing by the Engineer of the methacrylate resin before proposed use. If bulk resin is to be used, the Contractor shall notify the Engineer in writing at least 15 days before the delivery of the bulk resin to the job site. Bulk resin is any resin stored in containers in excess of 55 gallons.

Before starting production treatment, the Contractor shall treat a test area of approximately 500 square feet that is within the project limits and at a location approved by the Engineer. When available the test area shall be outside of the traveled way. Weather and pavement conditions during the test treatment shall be similar to those expected on the deck. Equipment used for testing shall be similar to those used for deck treating operations.

During test and production deck treatment, test tiles shall be used to evaluate the resin cure time. The Contractor shall coat at least one 4" x 4" commercial quality smooth glazed tile for each batch of methacrylate resin. The coated tile shall be placed adjacent to the corresponding treated area. Sand shall not be applied to the test tiles.

The acceptance criteria for a treated area is as follows:

1. The test tiles are dry to the touch.
2. The treated deck surface is tack free (non-oily).
3. The sand cover adheres and resists brushing by hand.
4. Excess sand has been removed by vacuuming or sweeping.
5. The coefficient of friction is at least 0.35 when tested in conformance with California Test 342.

Deck treatment on the test area shall demonstrate that the methods and materials meet the acceptance criteria and that the production work will be completed within the specified time for maintaining traffic.

If a test or production area fails to meet the acceptance criteria, as determined by the Engineer, the treatment will be rejected, and the treatment shall be removed and replaced until the area complies with the acceptance criteria.

**51-1.17A(4) Construction**

Equipment shall be fitted with suitable traps, filters, drip pans, or other devices as necessary to prevent oil or other deleterious material from being deposited on the deck.

Before deck treatment with methacrylate resin, the bridge deck surface shall be cleaned by abrasive blasting, and all loose material shall be blown from visible cracks using high-pressure air. Concrete curing seals shall be cleaned from the deck surface to be treated, and the deck shall be dry when blast cleaning is performed. If the deck surface becomes contaminated at any time before placing the resin, the deck surface shall be cleaned by abrasive blasting.

Where abrasive blasting is being performed within 10 feet of a lane occupied by public traffic, the residue including dust shall be removed immediately after contact between the abrasive and the surface being treated. The removal shall be by a vacuum attachment operating concurrently with the abrasive blasting operation.

A compatible promoter/initiator system shall be capable of providing the resin gel time range shown on the placement plan. Gel time shall be adjusted to compensate for the changes in temperature throughout treatment application.

Resin shall be applied by machine and by using a two-part resin system with a promoted resin for one part and an initiated resin for the other part. This two-part resin system shall be combined at equal volumes to the spray bars through separate positive displacement pumps. Combining of the 2 components shall be by either static in-line mixers or by external intersecting spray fans. The pump pressure at the spray bars shall not be great enough to cause appreciable atomization of the resin. Compressed air shall not be used to produce the spray. A shroud shall be used to enclose the spray bar apparatus.

At the Contractor's option, manual application may be used. For manual application, (1) the quantity of resin mixed with promoter and initiator shall be limited to 5 gallons at a time, and (2) the resin shall be distributed by squeegees and brooms within 10 minutes after application.

The Contractor shall apply methacrylate resin only to the specified area. Barriers, railing, joints, and drainage facilities shall be adequately protected to prevent contamination by the treatment material. Contaminated items shall be repaired at the Contractor's expense.

The relative humidity shall be less than 90 percent at the time of treatment. The prepared area shall be dry and the surface temperature shall be at least 50 °F and not more than 100 °F when the resin is applied. The rate of application of promoted/initiated resin shall be approximately 90 square feet per gallon; the exact rate shall be determined by the Engineer.

The deck surfaces to be treated shall be completely covered with resin so the resin penetrates and fills all cracks. The resin shall be applied within 5 minutes after complete mixing. A significant increase in viscosity shall be cause for rejection. Excess material shall be redistributed by squeegees or brooms within 10 minutes after application. For textured deck surfaces, including grooved surfaces, excess material shall be removed from the texture indentations.

After the resin has been applied, at least 20 minutes shall elapse before applying sand. The sand shall be commercial quality dry blast sand. At least 95 percent of the sand shall pass the No. 8 sieve and at least 95 percent shall be retained on

the No. 20 sieve. The sand shall be applied at a rate of approximately 2 pounds per square yard or until refusal as determined by the Engineer.

Traffic will not be allowed on treated areas until the acceptance criteria has been met as determined by the Engineer.

**In Section 51-1.18C replace the 2nd paragraph with:**

When Class 2 surface finish (gun finish) is specified, ordinary surface finish shall first be completed. The concrete surfaces shall then be abrasive blasted to a rough texture and thoroughly washed down with water. While the washed surfaces are damp, but not wet, a finish coating of machine applied mortar, approximately 1/4 inch thick, shall be applied in not less than 2 passes. The coating shall be pneumatically applied and shall consist of either (1) sand, cementitious material, and water mechanically mixed prior to its introduction to the nozzle, or (2) premixed sand and cementitious material to which water is added prior to its expulsion from the nozzle. The use of admixtures shall be subject to the approval of the Engineer as provided in Section 90, "Portland Cement Concrete." Unless otherwise specified, supplementary cementitious materials will not be required. The proportion of cementitious material to sand shall be not less than one to 4, unless otherwise directed by the Engineer. Sand shall be of a grading suitable for the purpose intended. The machines shall be operated and the coating shall be applied in conformance with standard practice. The coating shall be firmly bonded to the concrete surfaces on which it is applied.

**In Section 51-1.18C replace the 5th paragraph with:**

When surfaces to be finished are in pedestrian undercrossings, the sand shall be silica sand and the cementitious material shall be standard white portland cement.

**In Section 51-1.23, add:**

Full compensation for deck crack treatment, including execution of the public safety plan, shall be considered as included in the contract price paid per cubic yard for structural concrete, bridge, and no additional compensation will be allowed therefor.

^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^

## SECTION 52 REINFORCEMENT
**(Issued 12-07-07)**

**In Section 52-1.07 in the 11th paragraph, replace the table with:**

| Height Zone (H) (Feet above ground) | Wind Pressure Value (psf) |
|---|---|
| $H \leq 30$ | 20 |
| $30 < H \leq 50$ | 25 |
| $50 < H \leq 100$ | 30 |
| $H > 100$ | 35 |

**In Section 52-1.08B(1) in the 2nd paragraph, replace the table with:**

| Reinforcing Bar Number | Total Slip |
|---|---|
| 4 | 0.010-inch |
| 5 | 0.010-inch |
| 6 | 0.010-inch |
| 7 | 0.014-inch |
| 8 | 0.014-inch |
| 9 | 0.014-inch |
| 10 | 0.018-inch |
| 11 | 0.018-inch |
| 14 | 0.024-inch |
| 18 | 0.030-inch |

**In Section 52-1.08B(2) in the 6th paragraph, replace the subparagraph with:**

The minimum preheat and interpass temperatures shall be 400º F for Grade 40 bars and 600º F for Grade 60 bars. Immediately after completing the welding, at least 6 inches of the bar on each side of the splice shall be covered by an insulated wrapping to control the rate of cooling. The insulated wrapping shall remain in place until the bar has cooled below 200º F.

**In Section 52-1.08C in the 3rd paragraph, replace item A with:**

A. Proper facilities, including a calibrated tensile testing machine capable of breaking the largest size of reinforcing bar to be tested.

**In Section 52-1.08C replace the 5th paragraph with:**

Prequalification and production sample splices and testing shall conform to California Test 670 and these specifications.

**In Section 52-1.08C delete the 6th paragraph.**

**In Section 52-1.08C(2)(a) replace the 5th paragraph with:**

If 3 or more sample splices from a production test conform to the provisions in this Section 52-1.08C(2), "Service Splice Test Criteria," all splices in the lot represented by this production test will be considered acceptable.

**In Section 52-1.08C(3) replace the 2nd paragraph with:**

A minimum of 1 control bar shall be removed from the same bar as, and adjacent to, all ultimate prequalification, production, and quality assurance sample splices. The lengths of control bars shall conform to the lengths specified for sample splices in California Test 670. The portion of adjacent bar remaining in the work shall also be identified with weatherproof markings that correspond to its adjacent control bar.

**In Section 52-1.08C(3) in the 6th paragraph, replace the 2nd sentence with:**

In addition, necking of the bar, as defined in California Test 670, shall occur at rupture regardless of whether the bar breaks inside or outside the affected zone.

^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^

## SECTION 53 SHOTCRETE

**(Issued 11-02-07)**

**In Section 53-1.01 replace the 3rd paragraph with:**

The dry-mix process shall consist of delivering dry mixed aggregate and cementitious material pneumatically or mechanically to the nozzle body and adding water and mixing the materials in the nozzle body. The wet-mix process shall consist of delivering mixed aggregate, cement, and water pneumatically to the nozzle and adding any admixture at the nozzle.

**In Section 53-1.02 replace the 1st through 4th paragraphs with:**

Cementitious material, fine aggregate, and mixing water shall conform to the provisions in Section 90, "Portland Cement Concrete."

Shotcrete to be mixed and applied by the dry-mix process shall consist of one part cementitious material to not more than 4.5 parts fine aggregate, thoroughly mixed in a dry state before being charged into the machine. Measurement may be either by volume or by weight. The fine aggregate shall contain not more than 6 percent moisture by weight.

Shotcrete to be mixed and applied by the wet-mix process shall consist of cementitious material, fine aggregate, and water and shall contain not less than 632 pounds of cementitious material per cubic yard. A maximum of 30 percent pea gravel may be substituted for fine aggregate. The maximum size of pea gravel shall be such that 100 percent passes the 1/2 inch screen and at least 90 percent passes the 3/8 inch screen.

Admixtures may be added to shotcrete and shall conform to the provisions in Section 90-4, "Admixtures."

**In Section 53-1.04 in the 3rd paragraph, replace item C with:**

C. Aggregate and cementitious material that have been mixed for more than 45 minutes shall not be used unless otherwise permitted by the Engineer.

**Replace Section 53-1.07 with:**

**53-1.07 MEASUREMENT**

Quantities of shotcrete will be measured by the cubic yard computed from measurements, along the slope, of actual areas placed and the theoretical thickness shown on the plans. The Department does not pay for shotcrete placed outside the dimensions shown on the plans or to fill low foundation.

**Replace Section 53-1.08 with:**

**53-1.08 PAYMENT**

The contract price paid per cubic yard for shotcrete shall include full compensation for furnishing all labor, materials, tools, equipment, and incidentals, and for doing all the work involved in placing shotcrete, including preparing the foundation, wire reinforcement, structure backfill, joint filling material, and if required by the plans, drains with sacked pervious backfill material, as shown on the plans, as specified in these specifications and the special provisions, and as directed by the Engineer.

^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^

## SECTION 55 STEEL STRUCTURES

**(Issued 05-02-08**

**In Section 55-1.05 replace the 3rd paragraph with:**

Construction methods and equipment employed by the Contractor shall conform to the provisions in Section 7-1.02, "Load Limitations."

**In Section 55-2.01 in the 5th paragraph in the table, replace the CVN impact value for Grade HPS 50W with:**

| | |
|---|---|
| Grade HPS 50W* (4 inches and under in thickness) | 20 at 10 ºF |

**In Section 55-3.05 replace the 1st paragraph with:**

Surfaces of bearing and base plates and other metal surfaces that are to come in contact with each other or with ground concrete surfaces or with asbestos sheet packing shall be flat to within 1/32-inch tolerance in 12 inches and to within 1/16-inch tolerance overall. Surfaces of bearing and base plates and other metal bearing surfaces that are to come in contact with preformed fabric pads, elastomeric bearing pads, or mortar shall be flat to within 1/8-inch tolerance in 12 inches and to within 3/16-inch tolerance overall.

**In Section 55-3.10 in the 1st paragraph, replace item B with:**

B. Internal threads shall conform to the requirements in ASTM Designation: A 563.

**In Section 55-3.19 replace the 3rd paragraph with:**

Immediately before setting bearing assemblies or masonry plates directly on ground concrete surfaces, the Contractor shall thoroughly clean the surfaces of the concrete and the metal to be in contact and shall apply a coating of nonsag polysulfide or polyurethane caulking conforming to the requirements in ASTM Designation: C 920 to contact areas to provide full bedding.

**In Section 55-3.19 replace the 5th paragraph with:**

Mortar to be placed below masonry plates or bearing plates of the bearing assemblies and in anchor bolt sleeves or canisters shall conform to the provisions in Section 51-1.135, "Mortar," except that the proportion of cementitious material to sand shall be 1:3.

**In Section 55-4.01 in the 1st paragraph, replace item D with:**

D. To determine the pay quantities of galvanized metal, the weight to be added to the calculated weight of the base metal for the galvanizing will be determined from the table of weights of zinc coatings specified in ASTM Designation: A 153/A 153M.

^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^

## SECTION 56 SIGNS
**(Issued 03-16-07)**

**In Section 56-1.03 replace the 5th paragraph with:**

Clips, eyes, or removable brackets shall be affixed to all signs and all posts and shall be used to secure the sign during shipping and for lifting and moving during erection as necessary to prevent damage to the finished galvanized or painted surfaces. Brackets on tubular sign structures shall be removed after erection. Details of the devices shall be shown on the working drawings.

**In Section 56-1.10 replace the 4th paragraph with:**

The contract price paid per pound for install sign structure of the type or types designated in the Engineer's Estimate shall include full compensation for furnishing all labor, materials, tools, equipment and incidentals, and for doing all the work involved in installing sign structures, complete in place, including installing anchor bolt assemblies, removable sign panel frames, and sign panels and performing any welding, painting or galvanizing required during installation, as shown on the plans, as specified in these specifications and the special provisions, and as directed by the Engineer.

**In Section 56-2.03 replace the 4th paragraph with:**

Backfill material for metal posts shall consist of minor concrete conforming to the provisions in Section 90-10, "Minor Concrete," and shall contain not less than 463 pounds of cementitious material per cubic yard.

^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^

## SECTION 59 PAINTING
**(Issued 05-01-06)**

**In Section 59-2.12 replace the 3rd and 4th paragraphs with:**

Contact surfaces of stiffeners, railings, built up members or open seam exceeding 6 mils in width that would retain moisture, shall be caulked with polysulfide or polyurethane sealing compound conforming to the requirements in ASTM Designation: C 920, Type S, Grade NS, Class 25, Use O, or other approved material.

The dry film thickness of the paint will be measured in place with a calibrated Type 2 magnetic film thickness gage in conformance with the requirements in SSPC-PA 2, "Measurement of Dry Coating Thickness with Magnetic Gages," of the "SSPC: The Society for Protective Coatings," except that there shall be no limit to the number or location of spot measurements to verify compliance with specified thickness requirements.

^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^

## SECTION 64 PLASTIC PIPE
**(Issued 07-31-07)**

**In Section 64-1.06 replace the 1st paragraph with:**

At locations where pipe is to be backfilled with concrete as shown on the plans, the concrete backfill shall be constructed of minor concrete or Class 4 concrete conforming to the provisions in Section 90, "Portland Cement Concrete." Minor concrete shall contain not less than 380 pounds of cementitious material per cubic yard. The concrete to be used will be designated in the contract item or shown on the plans.

**In Section 64-1.06 replace the 3rd paragraph with:**

The surface of the concrete backfill shall be broomed with a heavy broom to produce a uniform rough surface if hot mix asphalt is to be placed directly thereon.

^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^

## SECTION 65 REINFORCED CONCRETE PIPE
**(Issued 07-31-07)**

**In Section 65-1.02 replace the 1st paragraph with:**

Cementitious material and aggregate shall conform to the provisions in Section 90-2, "Materials" except that mortar strengths relative to Ottawa sand and grading requirements shall not apply to the aggregate. Use of supplemental cementitious material shall conform to AASHTO Designation: M 170.

**In Section 65-1.02A(1) in the 11th paragraph, replace item c with:**

c. Cementitious material and aggregate for non-reinforced concrete pipe shall conform to the provisions in Section 65-1.02, "Materials."

**In Section 65-1.035 replace the 1st paragraph with:**

At locations where pipe is to be backfilled with concrete as shown on the plans, the concrete backfill shall be constructed of minor concrete or Class 4 concrete in conformance with the provisions in Section 90, "Portland Cement Concrete." Minor concrete shall contain not less than 380 pounds of cementitious material per cubic yard. The concrete to be used will be designated in the contract item.

**In Section 65-1.035 replace the 3rd paragraph with:**

The surface of the concrete backfill shall be broomed with a heavy broom to produce a uniform rough surface if hot mix asphalt is to be placed directly thereon.

**In Section 65-1.06 in the 2nd paragraph, replace the 1st subparagraph with:**

Cement Mortar. - Mortar shall be composed of one part cementitious material and 2 parts sand by volume. Supplementary cementitious material will not be required.

^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^

## SECTION 66 CORRUGATED METAL PIPE
**(Issued 07-31-07)**

**In Section 66-1.045 replace the 1st paragraph with:**

At locations where pipe is to be backfilled with concrete as shown on the plans, the concrete backfill shall be constructed of minor concrete or Class 4 concrete conforming to the provisions in Section 90, "Portland Cement Concrete." Minor concrete shall contain not less than 380 pounds of cementitious material per cubic yard. The concrete to be used will be designated in the contract item or shown on the plans.

**In Section 66-1.045 replace the 3rd paragraph with:**

The surface of the concrete backfill shall be broomed with a heavy broom to produce a uniform rough surface if hot mix asphalt is to be placed directly thereon.

^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^

## SECTION 68 SUBSURFACE DRAINS
**(Issued 07-31-07)**

**In Section 68-3.02D replace the 1st and 2nd paragraphs with:**

Concrete for splash pads shall be produced from minor concrete conforming to the provisions in Section 90-10, "Minor Concrete." Minor concrete shall contain not less than 470 pounds of cementitious material per cubic yard.

Mortar placed where edge drain outlets and vents connect to drainage pipe and existing drainage inlets shall conform to the provisions in Section 51-1.135, "Mortar."

**In Section 68-3.03 replace the 13th paragraph with:**

Cement treated permeable material, which is not covered with hot mix asphalt within 12 hours after compaction of the permeable material, shall be cured by either sprinkling the material with a fine spray of water every 4 hours during daylight hours or covering the material with a white polyethylene sheet, not less than 6 mils thick. The above curing requirements shall begin at 7:00 a.m. on the morning following compaction of the cement treated permeable material and continue for the next 72 hours or until the material is covered with hot mix asphalt, whichever is less. The cement treated permeable material shall not be sprayed with water during the first 12 hours after compacting, but may be covered with the polyethylene sheet during the first 12 hours or prior to the beginning of the cure period.

**In Section 68-3.03 replace the 17th and 18th paragraphs with:**

Hot mix asphalt for backfilling trenches in existing paved areas shall be produced from commercial quality aggregates and asphalt and mixed at a central mixing plant. The aggregate shall conform to the 3/4 inch grading, or the 1/2 inch grading for Type A and Type B hot mix asphalt specified in Section 39-1.02E, "Aggregate." The amount of asphalt binder to be mixed with the aggregate shall be between 4 percent and 7 percent by weight of the dry aggregate, as determined by the Engineer.

Hot mix asphalt backfill shall be spread and compacted in approximately 2 equal layers by methods that will produce a hot mix asphalt surfacing of uniform smoothness, texture and density. Each layer shall be compacted before the temperature of the mixture drops below 250 ºF. Prior to placing the hot mix asphalt backfill, a tack coat of asphaltic emulsion conforming to the provisions in Section 94, "Asphaltic Emulsions," shall be applied to the vertical edges of existing pavement at an approximate rate of 0.05 gallon per square yard.

**In Section 68-3.03 replace the 20th paragraph with:**

Type A pavement markers conforming to the details shown on the plans and the provisions in Section 85, "Pavement Markers," shall be placed on paved shoulders or dikes at outlet, vent and cleanout locations as directed by the Engineer. The waiting period for placing pavement markers on new hot mix asphalt surfacing will not apply.

**Replace Section 68-3.05 with:**

**68-3.05 PAYMENT**

The contract price paid per linear foot for plastic pipe (edge drain) of the size or sizes shown in the Engineer's Estimate shall include full compensation for furnishing all labor, materials, tools, equipment, and incidentals and for doing all the work involved in installing edge drains complete in place, including excavation (and removal of any concrete deposits that may occur along the lower edge of the concrete pavement in Type 1 installations) and hot mix asphalt backfill for Type 1 edge drain installation, tack coat, filter fabric, and treated permeable material, as shown on the plans, as specified in these specifications and the special provisions, and as directed by the Engineer.

The contract price paid per linear foot for plastic pipe (edge drain outlet) of the size or sizes shown in the Engineer's Estimate shall include full compensation for furnishing all labor, materials, tools, equipment, and incidentals and for doing all the work involved in installing edge drain outlets, vents and cleanouts complete in place, including outlet and vent covers, expansion plugs, pavement markers, concrete splash pads, connecting outlets and vents to drainage facilities, and excavation and backfill [aggregate base, hot mix asphalt, tack coat, and native material] for outlets, vents, and cleanouts to be installed in embankments and existing shoulders, as shown on the plans, as specified in these specifications and the special provisions, and as directed by the Engineer.

^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^

## SECTION 69 OVERSIDE DRAINS
**(Issued 07-31-07)**

**In Section 69-1.01 replace the 1st paragraph with:**

This work shall consist of furnishing and installing entrance tapers, pipe downdrains, tapered inlets, flume downdrains, anchor assemblies, reducers, slip joints and hot mix asphalt overside drains to collect and carry surface drainage down the roadway slopes as shown on the plans or as directed by the Engineer and as specified in these specifications and the special provisions.

**Replace Section 69-1.02D with:**

**69-1.02D Hot Mix Asphalt**

Hot mix asphalt for overside drains shall conform to the provisions in Section 39-1.13, "Miscellaneous Areas."

**Replace Section 69-1.04 with:**

**69-1.04 HOT MIX ASPHALT OVERSIDE DRAINS**

Hot mix asphalt overside drains shall be constructed as shown on the plans or as directed by the Engineer. The hot mix asphalt shall be placed in conformance with the provisions in Section 39-1.13, "Miscellaneous Areas."

**In Section 69-1.06 replace the 2nd paragraph with:**

Quantities of hot mix asphalt placed for overside drains will be paid for as provided in Section 39-5, "Measurement and Payment," for hot mix asphalt placed in miscellaneous areas.

^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^

## SECTION 70 MISCELLANEOUS FACILITIES

**(Issued 07-18-08)**

**In Section 70-1.02C replace the 2nd paragraph with:**

Precast concrete flared end sections shall conform to the requirements for Class III Reinforced Concrete Pipe in AASHTO Designation: M 170M. Cementitious materials and aggregate shall conform to the provisions in Section 90-2, "Materials," except that mortar strengths relative to Ottawa sand and grading requirements shall not apply to the aggregate. Use of supplementary cementitious material shall conform to the requirements in AASHTO Designation: M 170. The area of steel reinforcement per linear foot of flared end section shall be at least equal to the minimum steel requirements for circular reinforcement in circular pipe for the internal diameter of the circular portion of the flared end section. The basis of acceptance of the precast concrete flared end section shall conform to the requirements of Section 5.1.2 of AASHTO Designation: M 170.

**In Section 70-1.02H replace the 1st paragraph with:**

Precast concrete pipe risers and pipe reducers, and precast concrete pipe sections, adjustment rings and tapered sections for pipe energy dissipators, pipe inlets and pipe manholes shall conform to the requirements in AASHTO Designation: M 199M/M 199, except that the cementitious material and aggregate shall conform to the provisions in Section 90-2, "Materials," except that mortar strengths relative to Ottawa sand and grading requirements shall not apply to the aggregate. Use of supplementary cementitious material shall conform to the requirements in AASHTO Designation: M 170.

**In Section 70-1.03 replace the 2nd paragraph with:**

Cutoff walls for precast concrete flared end sections shall be constructed of minor concrete conforming to the provisions in Section 90-10, "Minor Concrete." Minor concrete shall contain not less than 470 pounds of cementitious material per cubic yard.

^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^

## SECTION 72 SLOPE PROTECTION

**(Issued 03-13-09)**

**In Section 72-4.04 replace the 6th paragraph with:**

Pervious backfill material, if required by the plans, shall be placed as shown. A securely tied sack containing one cubic foot of pervious backfill material shall be placed at each weep hole and drain hole. The sack material shall conform to the requirements for filter fabric in Section 88-1.02, "Filtration."

^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^

## SECTION 73 CONCRETE CURBS AND SIDEWALKS
**(Issued 07-31-07)**

**In Section 73-1.01 in the 2nd paragraph, replace item 2 with:**

2. Minor concrete shall contain not less than 463 pounds of cementitious material per cubic yard except that when extruded or slip-formed curbs are constructed using 3/8-inch maximum size aggregate, minor concrete shall contain not less than 548 pounds of cementitious material per cubic yard.

**In Section 73-1.06 replace the 15th paragraph with:**

Where hot mix asphalt or portland cement concrete pavements are to be placed around or adjacent to manholes, pipe inlets or other miscellaneous structures in sidewalk, gutter depression, island paving, curb ramps or driveway areas, the structures shall not be constructed to final grade until after the pavements have been constructed for a reasonable distance on each side of the structures.

^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^

## SECTION 74 PUMPING PLANT EQUIPMENT
**(Issued 07-01-08)**

**In Section 74-1.02 delete the 2nd paragraph.**

^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^

## SECTION 75 MISCELLANEOUS METAL
**(Issued 01-18-08)**

**In Section 75-1.03 replace the 13th paragraph with:**

Concrete anchorage devices shall be mechanical expansion or resin capsule types installed in drilled holes or cast-in-place insert types. The anchorage devices shall be selected from the Department's Pre-Qualified Products List at:

http://www.dot.ca.gov/hq/esc/approved_products_list

The anchorage devices shall be a complete system, including threaded studs, hex nuts, and cut washers. Thread dimensions for externally threaded concrete anchorage devices prior to zinc coating, shall conform to the requirements in ANSI Standard: B1.1 having Class 2A tolerances or ANSI Standard: B1.13M having Grade 6g tolerances. Thread dimensions for internally threaded concrete anchorage devices shall conform to the requirements in ASTM A 563.

**In Section 75-1.03 replace the 18th paragraph with:**

Mechanical expansion anchors shall, when installed in accordance with the manufacturer's instructions and these specifications and tested in conformance with the requirements in California Test 681, withstand the application of a sustained tension test load of at least the following values for at least 48 hours with a movement not greater than 0.035 inch:

| Stud Diameter (inches) | Sustained Tension Test Load (pounds) |
|---|---|
| *3/4 | 5,000 |
| 5/8 | 4,100 |
| 1/2 | 3,200 |
| 3/8 | 2,100 |
| 1/4 | 1,000 |

* Maximum stud diameter permitted for mechanical expansion anchors.

Resin capsule anchors shall, when installed in accordance with the manufacturer's instructions and these specifications and tested in conformance with the requirements in California Test 681, withstand the application of a sustained tension test load of at least the following values for at least 48 hours with a movement not greater than 0.010 inch:

| Stud Diameter (inches) | Sustained Tension Test Load (pounds) |
|---|---|
| 1-1/4 | 31,000 |
| 1 | 17,900 |
| 7/8 | 14,400 |
| 3/4 | 5,000 |
| 5/8 | 4,100 |
| 1/2 | 3,200 |
| 3/8 | 2,100 |
| 1/4 | 1,000 |

At least 25 days before use, the Contractor shall submit one sample of each resin capsule anchor per lot to the Transportation Laboratory for testing. A lot of resin capsule anchors is 100 units, or fraction thereof, of the same brand and product name.

**In Section 75-1.03 replace the 20th paragraph with:**

The Pre-Qualified Products List for concrete anchorage devices has been developed from data previously furnished by suppliers or manufacturers for each type and size. Approval of additional anchorage device types and sizes is contingent upon the Contractor submitting to the Engineer one sample of each type of concrete anchorage device, manufacturer's installation instructions, and certified results of tests, either by a private testing laboratory or the manufacturer, indicating compliance with the above requirements.

**In Section 75-1.03 replace the 24th paragraph with:**

Sealing compound, for caulking and adhesive sealing, shall be a polysulfide or polyurethane material conforming to the requirements in ASTM Designation: C 920, Type S, Grade NS, Class 25, Use O.

**In Section 75-1.035 in the 3rd paragraph, replace the 1st sentence with:**

Cables shall be 3/4 inch preformed, 6 x 19, wire strand core or independent wire rope core (IWRC), galvanized in conformance with the requirements in Federal Specification RR-W-410, right regular lay, manufactured of improved plow steel with a minimum breaking strength of 23 tons.

**In Section 75-1.035 in the 4th paragraph, replace item C with:**

C. Nuts shall conform to the requirements in ASTM Designation: A 563 including Appendix X1, except lubrication is not required.

**In Section 75-1.035 replace the 12th paragraph with:**

Concrete for filling cable drum units shall conform to the provisions in Section 90-10, "Minor Concrete," or at the option of the Contractor, may be a mix with 3/8-inch maximum size aggregate and not less than 675 pounds of cementitious material per cubic yard.

**In Section 75-1.05 replace the 6th paragraph with:**

Galvanizing of iron and steel hardware and nuts and bolts, when specified or shown on the plans, shall conform to the requirements in ASTM Designation: A 153/A 153M, except whenever threaded studs, bolts, nuts, and washers are specified to conform to the requirements in ASTM Designation: A 307, A 325, A 449, A 563, or F 436 and zinc coating is required, they shall be hot-dip zinc coated or mechanically zinc coated in conformance with the requirements in the ASTM Designations. Unless otherwise specified, galvanizing shall be performed after fabrication.

**In Section 75-1.05 replace the 8th paragraph with:**

Tapping of nuts or other internally threaded parts to be used with zinc coated bolts, anchor bars or studs shall be done after galvanizing and shall conform to the requirements for thread dimensions and overtapping allowances in ASTM Designation: A 563.

^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^

## SECTION 80 FENCES
**(Issued 01-05-07)**

**In Section 80-3.01F replace the 4th paragraph with:**

Portland cement concrete for metal post and brace footings and for deadmen shall be minor concrete conforming to the provisions in Section 90-10, "Minor Concrete." Minor concrete shall contain not less than 470 pounds of cementitious material per cubic yard.

**In Section 80-4.01C replace the 4th paragraph with:**

Portland cement concrete for metal post and for deadmen shall be produced from minor concrete conforming to the provisions in Section 90-10, "Minor Concrete." Minor concrete shall contain not less than 470 pounds of cementitious material per cubic yard.

^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^

## SECTION 83 RAILINGS AND BARRIERS
**(Issued 04-03-09)**

**In Section 83-1.02 replace the 7th paragraph with:**

Mortar shall conform to the provisions in Section 51-1.135, "Mortar," and shall consist of one part by volume of cementitious material and 3 parts of clean sand.

**In Section 83-1.02B in the 24th paragraph in the 8th subparagraph, replace the 1st sentence with:**

Anchor cable shall be 3/4 inch preformed, 6 x 19, wire strand core or independent wire rope core (IWRC), galvanized in conformance with the requirements in Federal Specification RR-W-410, right regular lay, manufactured of improved plow steel with a minimum breaking strength of 23 tons.

**In Section 83-1.02E in the 6th paragraph, replace the 2nd sentence with:**

Cable shall be galvanized in conformance with the requirements in Federal Specification RR-W-410.

**In Section 83-1.02I replace the 5th paragraph with:**

Where shown on the plans, cables used in the frame shall be 5/16 inch in diameter, wire rope, with a minimum breaking strength of 5,000 pounds and shall be galvanized in conformance with the requirements in Federal Specification RR-W-410.

**In Section 83-1.02I replace the 14th paragraph with:**

Chain link fabric shall be 11-gage conforming to one of the following:

1. AASHTO Designation: M181, Type I, Class C
2. AASHTO Designation: M181, Type IV, Class A
3. ASTM F 1345, Class 2

**In Section 83-2.02D(1) replace the 5th paragraph with:**

When concrete barriers are to be constructed on existing structures, the dowels shall be bonded in holes drilled in the existing concrete. Drilling of holes and bonding of dowels shall conform to the following:

1. The bonding materials shall be either magnesium phosphate concrete, modified high alumina based concrete or portland cement based concrete. Magnesium phosphate concrete shall be either single component (water activated) or dual component (with a prepackaged liquid activator). Modified high alumina based concrete and portland cement based concrete shall be water activated. Bonding materials shall conform to the following requirements:

| Property | Test Method | Requirements |
|---|---|---|
| Compressive Strength | | |
| at 3 hours, MPa | California Test 551 | 21 min. |
| at 24 hours, MPa | California Test 551 | 35 min. |
| Flexure Strength | | |
| at 24 hours, MPa | California Test 551 | 3.5 min. |
| Bond Strength: at 24 hours | | |
| SSD Concrete, MPa | California Test 551 | 2.1 min. |
| Dry Concrete, MPa | California Test 551 | 2.8 min. |
| Water Absorption, % | California Test 551 | 10 max. |
| Abrasion Resistance | | |
| at 24 hours, grams | California Test 550 | 25 max. |
| Drying Shrinkage at 4 days, % | ASTM Designation: C 596 | 0.13 max. |
| Soluble Chlorides by weight, % | California Test 422 | 0.05 max. |
| Water Soluble Sulfates by weight, % | California Test 417 | 0.25 max. |

2. Magnesium phosphate concrete shall be formulated for minimum initial set time of 15 minutes and minimum final set time of 25 minutes at 70° F. The materials, prior to use, shall be stored in a cool, dry environment.
3. Mix water used with water activated material shall conform to the provisions in Section 90-2.03, "Water."
4. The quantity of water for single component type or liquid activator (for dual component type) to be blended with the dry component, shall be within the limits recommended by the manufacturer and shall be the least amount required to produce a pourable batter.
5. Addition of retarders, when required and approved by the Engineer, shall be in conformance with the manufacturer's recommendations.
6. Before using concrete material that has not been previously approved, a minimum of 45 pounds shall be submitted to the Engineer for testing. The Contractor shall allow 45 days for the testing. Each shipment of concrete material that has been previously approved shall be accompanied by a Certificate of Compliance as provided in Section 6-1.07, "Certificates of Compliance."

7. Magnesium phosphate concrete shall not be mixed in containers or worked with tools containing zinc, cadmium, aluminum or copper metals. Modified high alumina based concrete shall not be mixed in containers or worked with tools containing aluminum.
8. The surface of any dowel coated with zinc or cadmium shall be coated with a colored lacquer before installation of the dowel. The lacquer shall be allowed to dry thoroughly before embedment of the dowels.
9. The holes shall be drilled by methods that will not shatter or damage the concrete adjacent to the hole. The diameter of the drilled hole shall be $^1/_2$ inch larger than the nominal diameter of the dowels.
10. The drilled holes shall be clean and dry at the time of placing the bonding material and the steel dowels. Bonding material and dowel shall completely fill the drilled hole. The surface temperature shall be 40° F or above when the bonding material is placed.
11. After bonding, dowels shall remain undisturbed for a minimum of 3 hours or until the bonding material has reached a strength sufficient to support the dowels. Dowels that are improperly bonded, as determined by the Engineer, shall be removed. The holes shall be cleaned or new holes shall be drilled and the dowels replaced and securely bonded to the concrete. Removing, redrilling and replacing improperly bonded dowels shall be performed at the Contractor's expense. Modified high alumina based concrete and portland cement based concrete shall be cured in conformance with the provisions in Section 90-7.01B, "Curing Compound Method," of the Standard Specifications. Magnesium phosphate concrete shall not be cured.

**In Section 83-2.02D(2) in the 1st paragraph, replace item b with:**

b. If the 3/8-inch maximum size aggregate grading is used to construct extruded or slip-formed concrete barriers, the cementitious material content of the minor concrete shall be not less than 675 pounds per cubic yard.

**In Section 83-2.02D(2) replace the 3rd paragraph with:**

The concrete paving between the tops of the 2 walls of concrete barrier (Types 50E, 60E, 60GE, and 60SE) and the optional concrete slab at the base between the 2 walls of concrete barrier (Types 50E, 60E, 60GE, and 60SE) shall be constructed of minor concrete conforming to the provisions of Section 90-10, "Minor Concrete," except that the minor concrete shall contain not less than 505 pounds of cementitious material per cubic yard.

^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^

## SECTION 85: PAVEMENT MARKERS
**(Issued 07-31-07)**

**In Section 85-1.06 replace the 6th paragraph with:**

Pavement markers shall not be placed on new hot mix asphalt surfacing or seal coat until the surfacing or seal coat has been opened to public traffic for a period of not less than 7 days when hot melt bituminous adhesive is used, and not less than 14 days when epoxy adhesive is used.

**In Section 85-1.06 in the 14th paragraph, replace the 2nd sentence with:**

Cleaning shall be done by blast cleaning on all surfaces regardless of age or type, except that blast cleaning of clean, new hot mix asphalt and clean, new seal coat surfaces will not be required when hot melt bituminous adhesive is used.

^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^

## SECTION 86 SIGNALS, LIGHTING AND ELECTRICAL SYSTEMS
**(Issued 08-15-08)**

**In Section 86-1.02 delete the 2nd paragraph.**

**In Section 86-2.02 in the 1st paragraph, replace the 1st sentence with:**

Improvements such as sidewalks, curbs, gutters, portland cement concrete and hot mix asphalt pavement, underlying material, lawns and plants and any other improvements removed, broken or damaged by the Contractor's operations, shall be replaced or reconstructed with the same kind of material as found on the work or with materials of equal quality.

**In Section 86-2.03 replace the 3rd, 4th, and 5th paragraph with:**

Except when located on structures, foundations for posts, standards, and pedestals shall be placed "in the solid" and monolithic.

After each post, standard, and pedestal is in proper position, mortar shall be placed under the base plate as shown on the plans. The exposed portions shall be finished to present a neat appearance. Mortar shall conform to Section 51-1.135, "Mortar," except the mortar shall consist of one part by volume of cementitious material and 3 parts of clean sand.

Reinforced cast-in-drilled-hole concrete pile foundations shall conform to the provisions in Section 49, "Piling," with the following exceptions:

A. Material resulting from drilling holes shall be disposed of in conformance with the provisions in Section 86-2.01, "Excavating and Backfilling,"
B. Concrete for cast-in-drilled-hole concrete piles will not be considered as designated by compressive strength.

**In Section 86-2.05C in the 18th paragraph, replace item D with:**

D. The conduit shall be placed in the bottom of the trench, and the trench shall be backfilled with minor concrete conforming to the provisions in Section 90-10, "Minor Concrete." Minor concrete shall contain not less than 590 pounds of cementitious material per cubic yard. Concrete backfill shall be placed to the pavement surface except, when the trench is in hot mix asphalt pavement and additional pavement is not being placed, the top 0.10 foot of the trench shall be backfilled with hot mix asphalt produced from commercial quality paving asphalt and aggregates.

**In Section 86-2.05C in the 18th paragraph, replace item E with:**

E. Prior to spreading hot mix asphalt, tack coat shall be applied in conformance with the provisions in Section 39, "Hot Mix Asphalt." Spreading and compacting of hot mix asphalt shall be performed by any method which will produce a hot mix asphalt surfacing of uniform smoothness, texture and density.

**In Section 86-2.05C in the 23rd paragraph, replace item C with:**

C. Precast concrete conduit cradles shall conform to the dimensions shown on the plans and shall be constructed of minor concrete and commercial quality welded wire fabric. Minor concrete shall conform to the provisions in Section 90-10, "Minor Concrete," and shall contain not less than 590 pounds of cementitious material per cubic yard. The cradles shall be moist cured for not less than 3 days.

**In Section 86-2.05C in the 23rd paragraph, replace item G with:**

G. The space around conduits through bridge abutment walls shall be filled with mortar conforming to the provisions in Section 51-1.135, "Mortar," except that the proportion of cementitious material to sand shall be 1 to 3.

**In Section 86-2.07 replace the 5th paragraph with:**

Concrete placed around and under traffic pull boxes as shown on the plans shall be minor concrete conforming to the provisions in Section 90-10, "Minor Concrete."

**In Section 86-2.08A in the table, replace the traffic signal controller cabinet requirements with:**

| | | | | | |
|---|---|---|---|---|---|
| Traffic Signal Controller Cabinet | Ungrounded Circuit Conductor | Blk | None | CON-1 | 6 |
| | Grounded Circuit Conductor | Wht | None | CON-2 | 6 |

**In Section 86-4.06 in the 1st paragraph, replace the 1st sentence with:**

Message symbols for pedestrian signal faces shall be white WALKING PERSON and Portland orange UPRAISED HAND conforming to the requirements in the Institute of Transportation Engineers Standards: "Pedestrian Traffic Control Signal Indications" and the "California MUTCD."

**In Section 86-4.07 in the 10th paragraph, replace the 2nd sentence with:**

The color of "UPRAISED HAND" shall be Portland orange conforming to the requirements of the Institute of Transportation Engineers Standards: "Pedestrian Traffic Control Signal Indications" and the "California MUTCD."

**In Section 86-5.01A(5) in section "Elastomeric Sealant" in the 1st paragraph, replace the 2nd sentence with:**

Sealant shall be suitable for use in both hot mix asphalt and portland cement concrete.

**In Section 86-5.01A(5) in section "Asphatic Emulsion Sealant" in the 1st paragraph, replace the 1st sentence with:**

Asphaltic emulsion sealant shall conform to the requirements in State Specification 8040-41A-15 and shall be used only for filling slots in hot mix asphalt pavement.

**In Section 86-5.01A(5) in section "Hot-Melt Rubberized Asphalt Sealant" in the 1st paragraph, replace the 3rd sentence with:**

Sealant shall be suitable for use in both hot mix asphalt and portland cement concrete.

**In Section 86-5.01A(5) in section "Hot-Melt Rubberized Asphalt Sealant," replace the 10th paragraph with:**

If hot mix asphalt surfacing is to be placed, the loop conductors shall be installed prior to placing the uppermost layer of hot mix asphalt. The conductors shall be installed, as shown on the plans, in the compacted layer of hot mix asphalt immediately below the uppermost layer. Installation details shall be as shown on the plans, except the sealant shall fill the slot flush to the surface.

**In Section 86-5.01D replace the 1st paragraph with:**

When a foundation for a pressure-sensitive vehicle detector is to be removed, the hole left by removing the detector frame and foundation shall be filled with minor concrete, except the roadway surface shall be reconstructed with material to match existing surfacing. Minor concrete shall conform to the provisions in Section 90-10, "Minor Concrete," except that the concrete shall contain not less than 420 pounds of cementitious material per cubic yard for hot mix asphalt surfaced roadways and not less than 590 pounds of cementitious material per cubic yard for portland cement concrete surfaced roadways.

**In Section 86-8.01 replace the 1st paragraph with:**

The contract lump sum price or prices paid for signal, ramp metering, flashing beacon, lighting, sign illumination, traffic monitoring station, highway advisory radio systems, closed circuit television systems, or combinations thereof; for modifying or removing those systems; for temporary systems; or the lump sum or unit prices paid for various units of those systems; or the lump sum or per foot price paid for conduit of the various sizes, types and installation methods listed in the Engineer's Estimate shall include full compensation for furnishing all labor, materials, tools, equipment and incidentals, and for doing all the work involved in furnishing and installing, modifying, or removing the systems, combinations or units thereof, as shown on the plans, as specified in these specifications and the special provisions, and as directed by the Engineer, including any necessary pull boxes (except when the type required is shown as a separate contract item); excavation and backfill; concrete foundations (except when shown as a separate contract item); pedestrian barricades; furnishing and installing illuminated street name signs; installing sign panels on pedestrian barricades, on flashing beacon standards, and on traffic signal mast arms; restoring sidewalk, pavement and appurtenances damaged or destroyed during construction; salvaging existing materials; and making all required tests.

^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^

## SECTION 88: ENGINEERING FABRICS
**(Issued 03-13-09)**

**Replace Section 88 with:**
## SECTION 88: GEOSYNTHETICS

### 88-1.01 GENERAL

#### 88-1.01A Summary

Section 88 includes specifications for geosynthetics. Geosynthetics are used for:

1. Filtration
2. Drainage
3. Reinforcement
4. Water pollution control
5. Channel and shore protection
6. Pavement interlayer

#### 88-1.01B Submittals

Submit:

1. Certificate of Compliance under Section 6-1.07, "Certificates of Compliance"
2. Samples representing each lot
3. Minimum average roll values (MARV)

Label submittals with the manufacturer's name and product information.

#### 88-1.01C Quality Control and Assurance

Treat geosynthetics to resist degradation from exposure to sunlight. Using covers, protect geosynthetics from moisture, sunlight, and shipping and storage damage.

### 88-1.02 FILTRATION

Geosynthetics used for filter fabric must be permeable and nonwoven. Filter fabric must consist of 1 of the following:

1. Polyester
2. Polypropylene
3. Combined polyester and polypropylene

Filter fabric must comply with:

**Filter Fabric**

| Property | ASTM | Specification | | |
|---|---|---|---|---|
| | | Class A | Class B | Class C |
| Grab breaking load, 1-inch grip, lb minimum in each direction | D 4632 | 157 | | |
| Apparent elongation, percent minimum in each direction | D 4632 | 50 | | |
| Hydraulic bursting strength, psi minimum | D 3786 | 210 | | |
| Ultraviolet resistance, percent minimum retained grab breaking load, 500 hr | D 4355 | 70 | | |
| Permittivity, $sec^{-1}$ minimum | D 4491 | 0.5 | 0.2 | 0.1 |
| Apparent opening size, average roll value, U.S. Standard sieve size maximum | D 4751 | 40 | 60 | 70 |

## 88-1.03 DRAINAGE

Geocomposite wall drain must consist of a polymeric core with filter fabric integrally bonded to 1 or both sides of the core creating a stable drainage void.

Filter fabric must comply with Section 88-1.02, "Filtration."

Geocomposite wall drain must comply with:

**Geocomposite Wall Drain**

| Property | ASTM | Specification |
|---|---|---|
| Thickness with fabric, inches maximum | -- | 2 |
| Transmissivity, gradient = 1.0, normal stress = 5,000 psf, gal/min/ft | D 4716 | 4 |

## 88-1.04 REINFORCEMENT

### 88-1.04A General

Geosynthetic used for geotechnical subsurface reinforcement must be either of the following:

1. Geotextile
2. Geogrid

Geotextile permittivity must be at least 0.05 $sec^{-1}$ determined under ASTM D 4491.

Geogrid must have a regular and defined open area. The open area must be from 50 to 90 percent of the total grid area.

### 88-1.04B Long Term Design Strength

Long Term Design Strength (LTDS) of geosynthetic reinforcement is the ultimate tensile strength in the primary strength direction divided by reduction factors. Calculate the LTDS from the guidelines in Geosynthetic Research Institute (GRI) Standard Practice GG4a, GRI GG4b, or GRI GT7.

The product of the appropriate reduction factors must be at least 1.30. Determine the reduction factor for creep using a 75-year design life for permanent applications and a 5-year design life for temporary applications. Determine the installation damage reduction factor based on the characteristics of the backfill materials used.

If test data is not available, use default values of reduction factors in the GRI Standard Practice to calculate LTDS.

Submit the LTDS and its supporting calculations at least 15 days before placing geosynthetic reinforcement. Do not install before the Engineer's approval. The LTDS must be signed by an engineer who is registered as a civil engineer in the State.

## 88-1.05 WATER POLLUTION CONTROL

Geosynthetics used for water pollution control must comply with:

**Water Pollution Control Geosynthetics**

| Property | ASTM | Application | | | | |
|---|---|---|---|---|---|---|
| | | Silt Fence | | Sediment Filter Bag | Gravel-Filled Bags | Temporary Cover |
| | | Woven | Non-woven | | | |
| Grab breaking load, 1-inch grip, lb minimum in each direction | D 4632 | 120 | 120 | 255 | 205 | 200 |
| Apparent elongation, percent minimum, in each direction | D 4632 | 15 | 50 | 50 | 50 | 50 |
| Water flow rate, gallons per minute/square foot maximum average roll value | D 4491 | 10 - 50 | 100 - 150 | 80 - 200 | 80 - 150 | 75 - 120 |
| Permittivity, $sec^{-1}$ minimum | D 4491 | 0.05 | 0.05 | 1.5 | 1.2 | 0.08 |
| Apparent opening size, U.S. Standard sieve size maximum average roll value | D 4751 | 30 | 30 | 20 - 40 | 40 - 80 | 100 |
| Ultraviolet resistance, percent minimum retained grab breaking load, 500 hr. | D 4355 | 70 | 70 | 70 | 70 | 70 |

## 88-1.06 CHANNEL AND SHORE PROTECTION

Rock slope protection (RSP) fabric must be a permeable, nonwoven, needle-punched geotextile. RSP fabric consists of 1 of the following:

1. Polyester
2. Polypropylene
3. Combined polyester and polypropylene

Polymers must be either virgin compounds or clean reworked material. Do not subject virgin compounds to use or processing other than required for initial manufacture. Clean reworked material must be previously processed material from the processor's own production that has been reground, pelletized, or solvated. RSP fabric must not consist of more than 20 percent by weight of clean reworked material. Do not use recycled materials from either post-consumer or post-industrial sources.

Class 8 or Class 10 RSP fabric must comply with:

**Rock Slope Protection Fabric**

| Property | ASTM | Specification | |
|---|---|---|---|
| | | Class 8 | Class 10 |
| Weight, oz/yd$^2$ minimum | D 5261 | 7.5 | 9.5 |
| Grab breaking load, lb 1-inch grip, min. in each direction | D 4632 | 200 | 250 |
| Apparent elongation, percent min., in each direction | D 4632 | 50 | 50 |
| Permittivity, sec$^{-1}$, minimum | D 4491 | 1.0 | 0.70 |
| Apparent opening size, U.S. Standard sieve size minimum and maximum | D 4751 | 70 - 100 | 70 - 100 |
| Ultraviolet resistance, percent minimum retained grab breaking load, 500 hr. | D4355 | 70 | 70 |

## 88-1.07 PAVEMENT INTERLAYER

### 88-1.07A Paving Fabric

Geosynthetics used for paving fabric must be nonwoven. Paving fabric must comply with:

**Geosynthetic Paving Fabric**

| Property | ASTM | Specification |
|---|---|---|
| Mass per unit area, oz/yd$^2$ minimum | D 5261 | 4.1 |
| Grab breaking load, lb 1-inch grip, minimum, in each direction | D 4632 | 100 |
| Apparent elongation, percent minimum in each direction | D 4632 | 50 |
| Hydraulic bursting strength, psi minimum | D 3786 | 200 |
| Melting point, °F minimum | D 276 | 325 |
| Asphalt retention, gal/yd$^2$ minimum | D 6140 | 0.2 |

### 88-1.07B Paving Mat

Geosynthetics used for paving mat must be a nonwoven fiberglass and polyester hybrid material. Paving mat must comply with:

**Geosynthetic Paving Mat**

| Property | ASTM | Specification |
|---|---|---|
| Breaking force, lb/2 inches minimum | D 5035 | 45 |
| Ultimate elongation, percent maximum | D 5035 | 5 |
| Mass per unit area, oz/ sq yd minimum | D 5261 | 3.7 |
| Melting point, °F minimum | D 276 | 400 |
| Asphalt retention, gal/yd$^2$ minimum | D 6140 | 0.10 |

### 88-1.07C Paving Grid

Geosynthetics used for paving grid must be a geopolymer material formed into a grid of integrally connected elements with openings. Paving grid must comply with:

**Geosynthetic Paving Grid**

| Property | Test | Specification | | |
|---|---|---|---|---|
| | | Class I | Class II | Class III |
| Tensile strength at ultimate, lb/in [a] minimum | ASTM D 6637 | 560 x 1,120 | 560 | 280 |
| Aperture size, inch minimum | Calipered | 0.5 | 0.5 | 0.5 |
| Elongation, % maximum | ASTM D 6637 | 12 | 12 | 12 |
| Mass per area, oz / sqyd minimum | ASTM D 5261 | 16 | 10 | 5.5 |
| Melting point, °F minimum | ASTM D 276 | 325 | 325 | 325 |

Note:
[a] For Class I, machine direction x cross direction. For Class II and Class III, both directions.

### 88-1.07D Paving Geocomposite Grid

Paving geocomposite grid consists of paving grid specified under Section 88-1.07C, "Paving Grid," bonded or integrated with filter fabric specified under Section 88-1.02, "Filtration."

Paving geocomposite grid must have a peel strength of at least 10 pounds per foot determined under ASTM D 413.

### 88-1.07E Geocomposite Strip Membrane

Geocomposite strip membrane must consist of various widths of strips manufactured from of asphaltic rubber and geosynthetics. Geocomposite strip membrane must comply with:

**Geocomposite Strip Membrane**

| Property | ASTM | Specification |
|---|---|---|
| Strip tensile strength, lbs/inch minimum | D 882 | 50 |
| Elongation at break, % minimum | D 882 | 50 |
| Resistance to puncture, lbs. minimum | E 154 | 200 |
| Permeance, perms maximum | E 96/E 96M | 0.10 |
| Pliability, 1/4 inch mandrel with sample conditioned at 25 °F | D 146 | No cracks in fabric or bitumen |
| Melting point, °F | D 276 | 325 |

### 88-1.08 PAYMENT

The Department measures and pays for geosynthetics under the specifications requiring their use.

^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^

## SECTION 90 PORTLAND CEMENT CONCRETE
**(Issued 12-05-08)**

**Replace Section 90 with:**

## SECTION 90 PORTLAND CEMENT CONCRETE

## 90-1 GENERAL

### 90-1.01 DESCRIPTION

Portland cement concrete shall be composed of cementitious material, fine aggregate, coarse aggregate, admixtures if used, and water, proportioned and mixed as specified in these specifications.

The Contractor shall determine the mix proportions for concrete in conformance with these specifications.

Class 1 concrete shall contain not less than 675 pounds of cementitious material per cubic yard.

Class 2 concrete shall contain not less than 590 pounds of cementitious material per cubic yard.

Class 3 concrete shall contain not less than 505 pounds of cementitious material per cubic yard.

Class 4 concrete shall contain not less than 420 pounds of cementitious material per cubic yard.

Minor concrete shall contain not less than 550 pounds of cementitious material per cubic yard unless otherwise specified in these specifications or the special provisions.

Unless otherwise designated on the plans or specified in these specifications or the special provisions, the amount of cementitious material used per cubic yard of concrete in structures or portions of structures shall conform to the following:

| Use | Cementitious Material Content (Pounds/CY) |
|---|---|
| Concrete designated by compressive strength: | |
| Deck slabs and slab spans of bridges | 675 min., 800 max. |
| Roof sections of exposed top box culverts | 675 min., 800 max. |
| Other portions of structures | 590 min., 800 max. |
| Concrete not designated by compressive strength: | |
| Deck slabs and slab spans of bridges | 675 min. |
| Roof sections of exposed top box culverts | 675 min. |
| Prestressed members | 675 min. |
| Seal courses | 675 min. |
| Other portions of structures | 590 min. |
| Concrete for precast members | 590 min., 925 max. |

Whenever the 28-day compressive strength shown on the plans is greater than 3,600 pounds per square inch, the concrete shall be designated by compressive strength. If the plans show a 28-day compressive strength that is 4,000 pounds per square inch or greater, an additional 14 days will be allowed to obtain the specified strength. The 28-day compressive strengths shown on the plans that are 3,600 pounds per square inch or less are shown for design information only and are not a requirement for acceptance of the concrete.

Concrete designated by compressive strength shall be proportioned such that the concrete will attain the strength shown on the plans or specified in the special provisions.

Concrete shall be proportioned to conform to the following shrinkage limitations when tested in conformance with the requirements of AASHTO Designation: T 160, modified as follows:

| Condition | Maximum Shrinkage of Laboratory Cast Specimens at 28 days Drying (average of 3, %) |
|---|---|
| Paving concrete | 0.050 |
| Bridge deck concrete | 0.045 |

Note: Shrinkage requirement is waived for concrete that is used for precast elements.

Shrinkage tests shall be either:

A. Performed by a laboratory accredited to perform AASHTO Designation: T 160, or
B. Performed by a laboratory that maintains a current rating of 3 or better for the Cement and Concrete Reference Laboratory (CCRL) concrete proficiency sample program.

Laboratory cast specimens shall have a 4" x 4" cross section. Specimens shall be removed from the molds 23 ± 1 hours after mixing the concrete and placed in lime water at 73 ± 3 °F to 7 days age. A comparator reading shall be taken at 7 days

age and recorded as the initial reading. Specimens then shall be stored in a humidity controlled room maintained at 73 ± 3 °F and 50 ± 4 percent relative humidity for the remainder of the test. Subsequent readings shall be taken at 7, 14, 21, and 28 days drying.

Test data verifying conformance to the shrinkage limitations shall be submitted with the mix design. Shrinkage testing data accepted by the Engineer no more than 3 years prior to the first working day of this contract will be acceptable for this entire contract, provided the data was for concrete with similar proportions and the same materials and material sources to be used on this contract. Concrete shall be considered to have similar proportions if, when compared to concrete to be used on this project, no more than 2 mix design elements are varied. Varied mix design elements shall fall within the tolerances in the following table:

| Mix Design Element | Tolerance (±) |
|---|---|
| Water to cementitious material ratio | 0.03 |
| Total water content | 5 % |
| Coarse aggregate (weight per cubic yard) | 10 % |
| Fine aggregate (weight per cubic yard) | 10 % |
| Supplementary cementitious material content | 5 % |
| Admixture (as originally dosed) | 25 % |

Note: Admixtures must be of the same brand.

Before using concrete for which the mix proportions have been determined by the Contractor, or in advance of revising those mix proportions, the Contractor shall submit in writing to the Engineer a copy of the mix design.

Compliance with cementitious material content requirements will be verified in conformance with procedures described in California Test 518 for cement content. For testing purposes, supplementary cementitious material shall be considered to be cement. Batch proportions shall be adjusted as necessary to produce concrete having the specified cementitious material content.

If any concrete has a cementitious material, portland cement, or supplementary cementitious material content that is less than the minimum required, the concrete shall be removed. However, if the Engineer determines that the concrete is structurally adequate, the concrete may remain in place and the Contractor shall pay to the State $0.25 for each pound of cementitious material, portland cement, or supplementary cementitious material that is less than the minimum required. The Department may deduct the amount from any moneys due, or that may become due, the Contractor under the contract. The deductions will not be made unless the difference between the contents required and those actually provided exceeds the batching tolerances permitted by Section 90-5, "Proportioning." No deductions will be made based on the results of California Test 518.

The requirements of the preceding paragraph shall not apply to minor concrete or commercial quality concrete.

## 90-2 MATERIALS

### 90-2.01 CEMENTITIOUS MATERIALS

Unless otherwise specified, cementitious material shall be either a combination of Type II or Type V portland cement and a supplementary cementitious material, or a blended cement.

Cementitious materials used in cast-in-place concrete for exposed surfaces of like elements of a structure shall be from the same sources and of the same proportions.

Cementitious materials shall be protected from moisture until used. Sacked cementitious materials shall be piled to permit access for tallying, inspecting, and identifying each shipment.

Facilities shall be provided to ensure that cementitious materials meeting this Section 90-2.01 are kept separate from other cementitious materials. Sampling cementitious materials shall be in conformance with California Test 125.

The Contractor shall furnish a Certificate of Compliance for cementious materials in conformance with the provisions in Section 6-1.07, "Certificates of Compliance." The Certificate of Compliance shall indicate the source by name and location (including country, state, and city). If cementitious material is delivered directly to the job site, the Certificate of Compliance shall be signed by the cementitious material supplier. If the cementitious material is used in ready-mixed concrete or in precast concrete products purchased as such by the Contractor, the Certificate of Compliance shall be signed by the manufacturer of the concrete or product.

#### 90-2.01A Cement

Portland cement shall conform to the requirements in ASTM Designation: C 150 except the $C_3S$ content of Type II cement shall not exceed 65 percent.

Blended cement shall conform to the requirements for Portland Blast-Furnace Slag Cement, Type IS (MS) or Portland-Pozzolan Cement, Type IP (MS) in AASHTO Designation: M 240 and shall be comprised of an intimate and uniform blend

of Type II or Type V cement and supplementary cementitious material in an amount conforming to the requirements in Section 90-2.01C, "Required Use of Supplementary Cementitious Materials."

In addition, blended cement, Type II portland cement, and Type V portland cement shall conform to the following requirements:

A. The cement shall not contain more than 0.60-percent by mass of alkalies, calculated as the percentage of $Na_2O$ plus 0.658 times the percentage of $K_2O$, when determined by methods as required in AASHTO Designation: T 105; and
B. The autoclave expansion shall not exceed 0.50-percent

Type III portland cement shall be used only as specified in the special provisions or with the approval of the Engineer. Type III portland cement shall conform to the additional requirements listed above for Type II portland cement.

**90-2.01B Supplementary Cementitious Materials (SCM)**

Fly ash shall conform to the requirements in AASHTO Designation: M 295, Class F, and the following:

A. Calcium oxide content shall not exceed 10 percent.
B. The available alkali, as sodium oxide equivalent, shall not exceed 1.5 percent when determined in conformance with the requirements in ASTM Designation: C 311 or the total alkali, as sodium oxide equivalent, shall not exceed 5.0 percent when determined in conformance with the requirements in AASHTO Designation: T 105.
C. Commingling of fly ash from different sources at uncontrolled ratios is permissible only if the following criteria are satisfied:

    1. Sources of fly ash to be commingled shall be on the approved list of materials for use in concrete.
    2. Testing of the commingled product is the responsibility of the fly ash supplier.
    3. Each fly ash's running average of density shall not differ from any other by more than 0.01-pound per cubic inch at the time of commingling.
    4. Each fly ash's running average of loss on ignition shall not differ from any other by more than one percent at the time of commingling.
    5. The final product of commingled fly ash shall conform to the requirement in AASHTO Designation: M 295.

Raw or calcined natural pozzolans shall conform to the requirements in AASHTO Designation: M 295, Class N and the following requirements:

A. Calcium oxide content shall not exceed 10 percent.
B. The available alkali, as sodium oxide equivalent, shall not exceed 1.5 percent when determined in conformance with the requirements in ASTM Designation: C 311 or the total alkali, as sodium oxide equivalent, shall not exceed 5.0 percent when determined in conformance with the requirements in AASHTO Designation: T 105.

Ground Granulated Blast Furnace Slag (GGBFS) shall conform to the requirements in AASHTO Designation: M 302, Grade 100 or Grade 120.

Silica Fume shall conform to the requirements of AASHTO Designation: M 307, with reduction in mortar expansion of 80 percent, minimum, using the cement from the proposed mix design.

**90-2.01C Required Use Of Supplementary Cementitious Materials**

The amount of portland cement and SCM used in portland cement concrete shall conform to the minimum cementitious material content provisions in Section 90-1.01, "Description," or Section 90-4.05, "Optional Use of Chemical Admixtures," and the following:

A. If a blended cement conforming to the provisions in Section 90-2.01A, "Cement," is used, the minimum amount of SCM incorporated into the cement shall conform to the provisions in this Section 90-2.01C.
B. Fly ash or natural pozzolan, silica fume, or GGBFS shall not be used with Type IP or Type IS cements.

Use of SCMs shall conform to the following:

A. If fly ash or natural pozzolan is used:

1. The minimum amount of portland cement shall not be less than 75 percent by weight of the specified minimum cementitious material content.
2. The minimum amount of fly ash or natural pozzolan shall be 25 percent by weight of the total amount of cementitious material.
3. The total amount of fly ash or natural pozzolan shall not exceed 35 percent by weight of the total amount of cementitious material to be used in the mix. If Section 90-1.01, "Description," specifies a maximum cementitious material content in pounds per cubic yard, the total weight of portland cement and fly ash or natural pozzolan per cubic yard shall not exceed the specified maximum cementitious material content.

B. If silica fume is used:

1. The amount of silica fume shall not be less than 10 percent by weight of the total amount of cementitious material.
2. The amount of portland cement shall not be less than 75 percent by weight of the specified minimum cementitious material content.
3. If Section 90-1.01, "Description," specifies a maximum cementitious material content in pounds per cubic yard, the total weight of portland cement and silica fume per cubic yard shall not exceed the specified maximum cementitious material content.

C. If GGBFS is used:

1. The minimum amount of GGBFS shall be either:
   a. Forty percent of the total cementitious material to be used, if the aggregates used in the concrete are on the Department's list of "Approved Aggregates For Use in Concrete with Reduced Fly Ash."
   b. No less than 50 percent.

2. The amount of GGBFS shall not exceed 60 percent by weight of the total amount of cementitious materials to be used.

**90-2.02 AGGREGATES**

Aggregates shall be free from deleterious coatings, clay balls, roots, bark, sticks, rags, and other extraneous material.

The Contractor shall provide safe and suitable facilities, including necessary splitting devices for obtaining samples of aggregates, in conformance with California Test 125.

Aggregates shall be of such character that it will be possible to produce workable concrete within the limits of water content provided in Section 90-6.06, "Amount of Water and Penetration."

Aggregates shall have not more than 10 percent loss when tested for soundness in conformance with the requirements in California Test 214. The soundness requirement for fine aggregate will be waived, provided that the durability index, $D_f$, of the fine aggregate is 60 or greater when tested for durability in conformance with California Test 229.

If the results of any one or more of the Cleanness Value, Sand Equivalent, or aggregate grading tests do not meet the requirements specified for "Operating Range" but all meet the "Contract Compliance" requirements, the placement of concrete shall be suspended at the completion of the current pour until tests or other information indicate that the next material to be used in the work will comply with the requirements specified for "Operating Range."

If the results of either or both the Cleanness Value and coarse aggregate grading tests do not meet the requirements specified for "Contract Compliance," the concrete that is represented by the tests shall be removed. However, if the Engineer determines that the concrete is structurally adequate, the concrete may remain in place, and the Contractor shall pay to the State $3.50 per cubic yard for paving concrete and $5.50 per cubic yard for all other concrete for the concrete represented by these tests and left in place. The Department may deduct the amount from any moneys due, or that may become due, the Contractor under the contract.

If the results of either or both the Sand Equivalent and fine aggregate grading tests do not meet the requirements specified for "Contract Compliance," the concrete which is represented by the tests shall be removed. However, if the Engineer determines that the concrete is structurally adequate, the concrete may remain in place, and the Contractor shall pay to the State $3.50 per cubic yard for paving concrete and $5.50 per cubic yard for all other concrete for the concrete represented by these tests and left in place. The Department may deduct the amount from any moneys due, or that may become due, the Contractor under the contract.

The 2 preceding paragraphs apply individually to the "Contract Compliance" requirements for coarse aggregate and fine aggregate. When both coarse aggregate and fine aggregate do not conform to the "Contract Compliance" requirements, both

paragraphs shall apply. The payments specified in those paragraphs are in addition to any payments made in conformance with the provisions in Section 90-1.01, "Description."

No single Cleanness Value, Sand Equivalent, or aggregate grading test shall represent more than 300 cubic yards of concrete or one day's pour, whichever is smaller.

When the source of an aggregate is changed, the Contractor shall adjust the mix proportions and submit in writing to the Engineer a copy of the mix design before using the aggregates.

**90-2.02A Coarse Aggregate**

Coarse aggregate shall consist of gravel, crushed gravel, crushed rock, reclaimed aggregate, crushed air-cooled iron blast furnace slag or combinations thereof. Crushed air-cooled blast furnace slag shall not be used in reinforced or prestressed concrete.

Reclaimed aggregate is aggregate that has been recovered from plastic concrete by washing away the cementitious material. Reclaimed aggregate shall conform to all aggregate requirements.

Coarse aggregate shall conform to the following quality requirements:

| Tests | California Test | Requirements |
|---|---|---|
| Loss in Los Angeles Rattler (after 500 revolutions) | 211 | 45% max. |
| Cleanness Value | | |
| Operating Range | 227 | 75 min. |
| Contract Compliance | 227 | 71 min. |

In lieu of the above Cleanness Value requirements, a Cleanness Value "Operating Range" limit of 71, minimum, and a Cleanness Value "Contract Compliance" limit of 68, minimum, will be used to determine the acceptability of the coarse aggregate if the Contractor furnishes a Certificate of Compliance, as provided in Section 6-1.07, "Certificates of Compliance," certifying that:

A. Coarse aggregate sampled at the completion of processing at the aggregate production plant had a Cleanness Value of not less than 82 when tested in conformance with the requirements in California Test 227; and
B. Prequalification tests performed in conformance with the requirements in California Test 549 indicated that the aggregate would develop a relative strength of not less than 95 percent and would have a relative shrinkage not greater than 105 percent, based on concrete.

**90-2.02B Fine Aggregate**

Fine aggregate shall consist of natural sand, manufactured sand produced from larger aggregate or a combination thereof. Manufactured sand shall be well graded.

Fine aggregate shall conform to the following quality requirements:

| Test | California Test | Requirements |
|---|---|---|
| Organic Impurities | 213 | Satisfactory[a] |
| Mortar Strengths Relative to Ottawa Sand | 515 | 95%, min. |
| Sand Equivalent: | | |
| Operating Range | 217 | 75, min. |
| Contract Compliance | 217 | 71, min. |

a Fine aggregate developing a color darker than the reference standard color solution may be accepted if it is determined by the Engineer, from mortar strength tests, that a darker color is acceptable.

In lieu of the above Sand Equivalent requirements, a Sand Equivalent "Operating Range" limit of 71, minimum, and a Sand Equivalent "Contract Compliance" limit of 68, minimum, will be used to determine the acceptability of the fine aggregate if the Contractor furnishes a Certificate of Compliance, as provided in Section 6-1.07, "Certificates of Compliance," certifying that:

A. Fine aggregate sampled at the completion of processing at the aggregate production plant had a Sand Equivalent value of not less than 82 when tested by California Test 217; and

B. Prequalification tests performed in conformance with California Test 549 indicated that the aggregate would develop a relative strength of not less than 95 percent and would have a relative shrinkage not greater than 105 percent, based on concrete.

### 90-2.03 WATER

In conventionally reinforced concrete work, the water for curing, for washing aggregates, and for mixing shall be free from oil and shall not contain more than 1,000 parts per million of chlorides as Cl, when tested in conformance with California Test 422, nor more than 1,300 parts per million of sulfates as $SO_4$, when tested in conformance with California Test 417. In prestressed concrete work, the water for curing, for washing aggregates, and for mixing shall be free from oil and shall not contain more than 650 parts per million of chlorides as Cl, when tested in conformance with California Test 422, nor more than 1,300 parts per million of sulfates as $SO_4$, when tested in conformance with California Test 417. In no case shall the water contain an amount of impurities that will cause either: 1) a change in the setting time of cement of more than 25 percent when tested in conformance with the requirements in ASTM Designation: C 191 or ASTM Designation: C 266 or 2) a reduction in the compressive strength of mortar at 14 days of more than 5 percent, when tested in conformance with the requirements in ASTM Designation: C 109, when compared to the results obtained with distilled water or deionized water, tested in conformance with the requirements in ASTM Designation: C 109.

In nonreinforced concrete work, the water for curing, for washing aggregates and for mixing shall be free from oil and shall not contain more than 2,000 parts per million of chlorides as Cl, when tested in conformance with California Test 422, or more than 1,500 parts per million of sulfates as $SO_4$, when tested in conformance with California Test 417.

In addition to the above provisions, water for curing concrete shall not contain impurities in a sufficient amount to cause discoloration of the concrete or produce etching of the surface.

Water reclaimed from mixer wash-out operations may be used in mixing concrete. The water shall not contain coloring agents or more than 300 parts per million of alkalis ($Na_2O + 0.658\ K_2O$) as determined on the filtrate. The specific gravity of the water shall not exceed 1.03 and shall not vary more than ±0.010 during a day's operations.

### 90-2.04 Admixture Materials

Admixture materials shall conform to the requirements in the following ASTM Designations:

A. Chemical Admixtures—ASTM Designation: C 494.
B. Air-entraining Admixtures—ASTM Designation: C 260.

## 90-3 AGGREGATE GRADINGS

### 90-3.01 GENERAL

Before beginning concrete work, the Contractor shall submit in writing to the Engineer the gradation of the primary aggregate nominal sizes that the Contractor proposes to furnish. If a primary coarse aggregate or the fine aggregate is separated into 2 or more sizes, the proposed gradation shall consist of the gradation for each individual size, and the proposed proportions of each individual size, combined mathematically to indicate one proposed gradation. The proposed gradation shall meet the grading requirements shown in the table in this section, and shall show the percentage passing each of the sieve sizes used in determining the end result.

The Engineer may waive, in writing, the gradation requirements in this Section 90-3.01 and in Sections 90-3.02, "Coarse Aggregate Grading," 90-3.03, "Fine Aggregate Grading," and 90-3.04, "Combined Aggregate Gradings," if, in the Engineer's opinion, furnishing the gradation is not necessary for the type or amount of concrete work to be constructed.

Gradations proposed by the Contractor shall be within the following percentage passing limits:

| Primary Aggregate Nominal Size | Sieve Size | Limits of Proposed Gradation |
|---|---|---|
| 1 1/2" x 3/4" | 1" | 19 - 41 |
| 1" x No. 4 | 3/4" | 52 - 85 |
| 1" x No. 4 | 3/8" | 15 - 38 |
| 1/2" x No. 4 | 3/8" | 40 - 78 |
| 3/8" x No. 8 | 3/8" | 50 - 85 |
| Fine Aggregate | No. 16 | 55 - 75 |
| Fine Aggregate | No. 30 | 34 - 46 |
| Fine Aggregate | No. 50 | 16 - 29 |

Should the Contractor change the source of supply, the Contractor shall submit in writing to the Engineer the new gradations before their intended use.

### 90-3.02 COARSE AGGREGATE GRADING

The grading requirements for coarse aggregates are shown in the following table for each size of coarse aggregate:

| | Percentage Passing Primary Aggregate Nominal Sizes | | | | | | | |
|---|---|---|---|---|---|---|---|---|
| | 1 1/2" x 3/4" | | 1" x No. 4 | | 1/2" x No. 4 | | 3/8" x No. 8 | |
| Sieve Sizes | Operating Range | Contract Compliance | Operating Range | Contract Compliance | Operating Range | Contract Compliance | Operating Range | Contract Compliance |
| 2" | 100 | 100 | — | — | — | — | — | — |
| 1 1/2" | 88 - 100 | 85 - 100 | 100 | 100 | — | — | — | — |
| 1" | X ±18 | X ±25 | 88 - 100 | 86 - 100 | — | — | — | — |
| 3/4" | 0 - 17 | 0 - 20 | X ±15 | X ±22 | 100 | 100 | — | — |
| 1/2" | — | — | — | — | 82 - 100 | 80 - 100 | 100 | 100 |
| 3/8" | 0 - 7 | 0 - 9 | X ±15 | X ±22 | X ±15 | X ±22 | X ±15 | X ±20 |
| No. 4 | — | — | 0 - 16 | 0 - 18 | 0 - 15 | 0 - 18 | 0 - 25 | 0 - 28 |
| No. 8 | — | — | 0 - 6 | 0 - 7 | 0 - 6 | 0 - 7 | 0 - 6 | 0 - 7 |

In the above table, the symbol X is the gradation that the Contractor proposes to furnish for the specific sieve size as provided in Section 90-3.01, "General."

Coarse aggregate for the 1 1/2 inch, maximum, combined aggregate grading as provided in Section 90-3.04, "Combined Aggregate Gradings," shall be furnished in 2 or more primary aggregate nominal sizes. Each primary aggregate nominal size may be separated into 2 sizes and stored separately, provided that the combined material conforms to the grading requirements for that particular primary aggregate nominal size.

When the one inch, maximum, combined aggregate grading as provided in Section 90-3.04, "Combined Aggregate Gradings," is to be used, the coarse aggregate may be separated into 2 sizes and stored separately, provided that the combined material shall conform to the grading requirements for the 1" x No. 4 primary aggregate nominal size.

### 90-3.03 FINE AGGREGATE GRADING

Fine aggregate shall be graded within the following limits:

| | Percentage Passing | |
|---|---|---|
| Sieve Sizes | Operating Range | Contract Compliance |
| 3/8" | 100 | 100 |
| No. 4 | 95 - 100 | 93 - 100 |
| No. 8 | 65 - 95 | 61 - 99 |
| No. 16 | X ±10 | X ±13 |
| No. 30 | X ±9 | X ±12 |
| No. 50 | X ±6 | X ±9 |
| No. 100 | 2 - 12 | 1 - 15 |
| No. 200 | 0 - 8 | 0 - 10 |

In the above table, the symbol X is the gradation that the Contractor proposes to furnish for the specific sieve size as provided in Section 90-3.01, "General."

In addition to the above required grading analysis, the distribution of the fine aggregate sizes shall be such that the difference between the total percentage passing the No. 16 sieve and the total percentage passing the No. 30 sieve shall be between 10 and 40, and the difference between the percentage passing the No. 30 and No. 50 sieves shall be between 10 and 40.

Fine aggregate may be separated into 2 or more sizes and stored separately, provided that the combined material conforms to the grading requirements specified in this Section 90-3.03.

### 90-3.04 COMBINED AGGREGATE GRADINGS

Combined aggregate grading limits shall be used only for the design of concrete mixes. Concrete mixes shall be designed so that aggregates are combined in proportions that shall produce a mixture within the grading limits for combined aggregates as specified herein.

The combined aggregate grading, except when otherwise specified in these specifications or the special provisions, shall be either the 1 1/2 inch, maximum grading, or the 1 inch, maximum grading, at the option of the Contractor.

Grading Limits of Combined Aggregates

| Sieve Sizes | Percentage Passing | | | |
|---|---|---|---|---|
| | 1 1/2" Max. | 1" Max. | 1/2" Max. | 3/8" Max. |
| 2" | 100 | — | — | — |
| 1 1/2" | 90 - 100 | 100 | — | — |
| 1" | 50 - 86 | 90 - 100 | — | — |
| 3/4" | 45 - 75 | 55 - 100 | 100 | — |
| 1/2" | — | — | 90 - 100 | 100 |
| 3/8" | 38 - 55 | 45 - 75 | 55 - 86 | 50 - 100 |
| No. 4 | 30 - 45 | 35 - 60 | 45 - 63 | 45 - 63 |
| No. 8 | 23 - 38 | 27 - 45 | 35 - 49 | 35 - 49 |
| No. 16 | 17 - 33 | 20 - 35 | 25 - 37 | 25 - 37 |
| No. 30 | 10 - 22 | 12 - 25 | 15 - 25 | 15 - 25 |
| No. 50 | 4 - 10 | 5 - 15 | 5 - 15 | 5 - 15 |
| No. 100 | 1 - 6 | 1 - 8 | 1 - 8 | 1 - 8 |
| No. 200 | 0 - 3 | 0 - 4 | 0 - 4 | 0 - 4 |

Changes from one grading to another shall not be made during the progress of the work unless permitted by the Engineer.

## 90-4 ADMIXTURES

### 90-4.01 GENERAL

Admixtures used in portland cement concrete shall conform to and be used in conformance with the provisions in this Section 90-4 and the special provisions. Admixtures shall be used when specified or ordered by the Engineer and may be used at the Contractor's option as provided herein.

Chemical admixtures and air-entraining admixtures containing chlorides as Cl in excess of one percent by weight of admixture, as determined by California Test 415, shall not be used.

Admixtures shall be uniform in properties throughout their use in the work. Should it be found that an admixture as furnished is not uniform in properties, its use shall be discontinued.

If more than one admixture is used, the admixtures shall be compatible with each other so that the desirable effects of all admixtures used will be realized.

Chemical admixtures shall be used in conformance with the manufacturer's written recommendations.

### 90-4.02 MATERIALS

Admixture materials shall conform to the provisions in Section 90–2.04, "Admixture Materials."

### 90-4.03 ADMIXTURE APPROVAL

No admixture brand shall be used in the work unless it is on the Department's current list of approved brands for the type of admixture involved.

Admixture brands will be considered for addition to the approved list if the manufacturer of the admixture submits to the Transportation Laboratory a sample of the admixture accompanied by certified test results demonstrating that the admixture complies with the requirements in the appropriate ASTM Designation and these specifications. The sample shall be sufficient to permit performance of all required tests. Approval of admixture brands will be dependent upon a determination as to compliance with the requirements, based on the certified test results submitted, together with tests the Department may elect to perform.

If the Contractor proposes to use an admixture of a brand and type on the current list of approved admixture brands, the Contractor shall furnish a Certificate of Compliance from the manufacturer, as provided in Section 6-1.07, "Certificates of Compliance," certifying that the admixture furnished is the same as that previously approved. If a previously approved admixture is not accompanied by a Certificate of Compliance, the admixture shall not be used in the work until the Engineer has had sufficient time to make the appropriate tests and has approved the admixture for use. The Engineer may take samples for testing at any time, whether or not the admixture has been accompanied by a Certificate of Compliance.

### 90-4.04 REQUIRED USE OF CHEMICAL ADMIXTURES

If the use of a chemical admixture is specified, the admixture shall be used at the dosage specified, except that if no dosage is specified, the admixture shall be used at the dosage normally recommended by the manufacturer of the admixture.

### 90-4.05 OPTIONAL USE OF CHEMICAL ADMIXTURES

The Contractor may use Type A or F, water-reducing; Type B, retarding; or Type D or G, water-reducing and retarding admixtures as described in ASTM Designation: C 494 to conserve cementitious material or to facilitate any concrete construction application subject to the following conditions:

A. If a water-reducing admixture or a water-reducing and retarding admixture is used, the cementitious material content specified or ordered may be reduced by a maximum of 5 percent by weight, except that the resultant cementitious material content shall be not less than 505 pounds per cubic yard; and
B. When a reduction in cementitious material content is made, the dosage of admixture used shall be the dosage used in determining approval of the admixture.

Unless otherwise specified, a Type C accelerating chemical admixture conforming to the requirements in ASTM Designation: C 494, may be used in portland cement concrete. Inclusion in the mix design submitted for approval will not be required provided that the admixture is added to counteract changing conditions that contribute to delayed setting of the portland cement concrete, and the use or change in dosage of the admixture is approved in writing by the Engineer.

### 90-4.06 REQUIRED USE OF AIR-ENTRAINING ADMIXTURES

When air-entrainment is specified or ordered by the Engineer, the air-entraining admixture shall be used in amounts to produce a concrete having the specified air content as determined by California Test 504.

### 90-4.07 OPTIONAL USE OF AIR-ENTRAINING ADMIXTURES

When air-entrainment has not been specified or ordered by the Engineer, the Contractor will be permitted to use an air-entraining admixture to facilitate the use of any construction procedure or equipment provided that the average air content, as determined by California Test 504, of 3 successive tests does not exceed 4 percent, and no single test value exceeds 5.5 percent. If the Contractor elects to use an air-entraining admixture in concrete for pavement, the Contractor shall so indicate at the time the Contractor designates the source of aggregate.

### 90-4.08 BLANK

### 90-4.09 BLANK

### 90-4.10 PROPORTIONING AND DISPENSING LIQUID ADMIXTURES

Chemical admixtures and air-entraining admixtures shall be dispensed in liquid form. Dispensers for liquid admixtures shall have sufficient capacity to measure at one time the prescribed quantity required for each batch of concrete. Each dispenser shall include a graduated measuring unit into which liquid admixtures are measured to within ±5 percent of the prescribed quantity for each batch. Dispensers shall be located and maintained so that the graduations can be accurately read from the point at which proportioning operations are controlled to permit a visual check of batching accuracy prior to discharge. Each measuring unit shall be clearly marked for the type and quantity of admixture.

Each liquid admixture dispensing system shall be equipped with a sampling device consisting of a valve located in a safe and readily accessible position such that a sample of the admixture may be withdrawn slowly by the Engineer.

If more than one liquid admixture is used in the concrete mix, each liquid admixture shall have a separate measuring unit and shall be dispensed by injecting equipment located in such a manner that the admixtures are not mixed at high concentrations and do not interfere with the effectiveness of each other. When air-entraining admixtures are used in conjunction with other liquid admixtures, the air-entraining admixture shall be the first to be incorporated into the mix, unless it is demonstrated that a different sequence improves performance.

When automatic proportioning devices are required for concrete pavement, dispensers for liquid admixtures shall operate automatically with the batching control equipment. The dispensers shall be equipped with an automatic warning system in good operating condition that will provide a visible or audible signal at the point at which proportioning operations are controlled when the quantity of admixture measured for each batch of concrete varies from the preselected dosage by more than 5 percent, or when the entire contents of the measuring unit are not emptied from the dispenser into each batch of concrete.

Unless liquid admixtures are added to premeasured water for the batch, their discharge into the batch shall be arranged to flow into the stream of water so that the admixtures are well dispersed throughout the batch, except that air-entraining admixtures may be dispensed directly into moist sand in the batching bins provided that adequate control of the air content of the concrete can be maintained.

Liquid admixtures requiring dosages greater than one-half gallon per cubic yard shall be considered to be water when determining the total amount of free water as specified in Section 90-6.06, "Amount of Water and Penetration."

### 90-4.11 BLANK

## 90-5 PROPORTIONING

### 90-5.01 STORAGE OF AGGREGATES

Aggregates shall be stored or stockpiled in such a manner that separation of coarse and fine particles of each size shall be avoided and the various sizes shall not become intermixed before proportioning.

Aggregates shall be stored or stockpiled and handled in a manner that prevent contamination by foreign materials. In addition, storage of aggregates at batching or mixing facilities that are erected subsequent to the award of the contract and that furnish concrete to the project shall conform to the following:

A. Intermingling of the different sizes of aggregates shall be positively prevented. The Contractor shall take the necessary measures to prevent intermingling. The preventive measures may include, but are not necessarily limited to, physical separation of stockpiles or construction of bulkheads of adequate length and height; and
B. Contamination of aggregates by contact with the ground shall be positively prevented. The Contractor shall take the necessary measures to prevent contamination. The preventive measures shall include, but are not necessarily limited to, placing aggregates on wooden platforms or on hardened surfaces consisting of portland cement concrete, asphalt concrete, or cement treated material.

In placing aggregates in storage or in moving the aggregates from storage to the weigh hopper of the batching plant, any method that may cause segregation, degradation, or the combining of materials of different gradings that will result in any size of aggregate at the weigh hopper failing to meet the grading requirements, shall be discontinued. Any method of handling aggregates that results in excessive breakage of particles shall be discontinued. The use of suitable devices to reduce impact of falling aggregates may be required by the Engineer.

### 90-5.02 PROPORTIONING DEVICES

Weighing, measuring, or metering devices used for proportioning materials shall conform to the requirements in Section 9-1.01, "Measurement of Quantities," and this Section 90-5.02. In addition, automatic weighing systems shall comply with the requirements for automatic proportioning devices in Section 90-5.03A, "Proportioning for Pavement." Automatic devices shall be automatic to the extent that the only manual operation required for proportioning the aggregates, cement, and supplementary cementitious material for one batch of concrete is a single operation of a switch or starter.

Proportioning devices shall be tested as frequently as the Engineer may deem necessary to ensure their accuracy.

Weighing equipment shall be insulated against vibration or movement of other operating equipment in the plant. When the plant is in operation, the weight of each batch of material shall not vary from the weight designated by the Engineer by more than the tolerances specified herein.

Equipment for cumulative weighing of aggregate shall have a zero tolerance of ±0.5 percent of the designated total batch weight of the aggregate. For systems with individual weigh hoppers for the various sizes of aggregate, the zero tolerance shall be ±0.5 percent of the individual batch weight designated for each size of aggregate. Equipment for cumulative weighing of cement and supplementary cementitious material shall have a zero tolerance of ±0.5 percent of the designated total batch weight of the cement and supplementary cementitious material. Equipment for weighing cement or supplementary cementitious material separately shall have a zero tolerance of ±0.5 percent of their designated individual batch weights. Equipment for measuring water shall have a zero tolerance of ±0.5 percent of its designated weight or volume.

The weight indicated for any batch of material shall not vary from the preselected scale setting by more than the following:

A. Aggregate weighed cumulatively shall be within 1.0 percent of the designated total batch weight of the aggregate. Aggregates weighed individually shall be within 1.5 percent of their respective designated batch weights; and
B. Cement shall be 99 to 102 percent of its designated batch weight. When weighed individually, supplementary cementitious material shall be 99 to 102 percent of its designated batch weight. When supplementary cementitious material and cement are permitted to be weighed cumulatively, cement shall be weighed first to 99 to 102 percent of

its designated batch weight, and the total for cement and supplementary cementitious material shall be 99 to 102 percent of the sum of their designated batch weights; and

C. Water shall be within 1.5 percent of its designated weight or volume.

Each scale graduation shall be approximately 0.001 of the total capacity of the scale. The capacity of scales for weighing cement, supplementary cementitious material, or cement plus supplementary cementitious material and aggregates shall not exceed that of commercially available scales having single graduations indicating a weight not exceeding the maximum permissible weight variation above, except that no scale shall be required having a capacity of less than 1,000 pounds, with one pound graduations.

**90-5.03 PROPORTIONING**

Proportioning shall consist of dividing the aggregates into the specified sizes, each stored in a separate bin, and combining them with cementitious material and water as provided in these specifications. Aggregates shall be proportioned by weight.

At the time of batching, aggregates shall have been dried or drained sufficiently to result in a stable moisture content such that no visible separation of water from aggregate will take place during transportation from the proportioning plant to the point of mixing. In no event shall the free moisture content of the fine aggregate at the time of batching exceed 8 percent of its saturated, surface-dry weight.

Should separate supplies of aggregate material of the same size group, but of different moisture content or specific gravity or surface characteristics affecting workability, be available at the proportioning plant, withdrawals shall be made from one supply exclusively and the materials therein completely exhausted before starting upon another.

Bulk Type IP (MS) cement shall be weighed in an individual hopper and shall be kept separate from the aggregates until the ingredients are released for discharge into the mixer.

Bulk cement and supplementary cementitious material may be weighed in separate, individual weigh hoppers or may be weighed in the same weigh hopper and shall be kept separate from the aggregates until the ingredients are released for discharge into the mixer. If the cement and supplementary cementitious material are weighed cumulatively, the cement shall be weighed first.

If cement and supplementary cementitious material are weighed in separate weigh hoppers, the weigh systems for the proportioning of the aggregate, the cement, and the supplementary cementitious material shall be individual and distinct from all other weigh systems. Each weigh system shall be equipped with a hopper, a lever system, and an indicator to constitute an individual and independent material-weighing device. The cement and the supplementary cementitious material shall be discharged into the mixer simultaneously with the aggregate.

The scales and weigh hoppers for bulk weighing cement, supplementary cementitious material, or cement plus supplementary cementitious material shall be separate and distinct from the aggregate weighing equipment.

For batches of one cubic yard or more, the batching equipment shall conform to one of the following combinations:

A. Separate boxes and separate scale and indicator for weighing each size of aggregate.
B. Single box and scale indicator for all aggregates.
C. Single box or separate boxes and automatic weighing mechanism for all aggregates.

In order to check the accuracy of batch weights, the gross weight and tare weight of batch trucks, truck mixers, truck agitators, and non-agitating hauling equipment shall be determined when ordered by the Engineer. The equipment shall be weighed on scales designated by the Engineer.

**90-5.03A Proportioning For Pavement**

Aggregates and bulk supplementary cementitious material for use in pavement shall be proportioned by weight by means of automatic proportioning devices of approved type conforming to these specifications.

The Contractor shall install and maintain in operating condition an electronically actuated moisture meter that will indicate, on a readily visible scale, changes in the moisture content of the fine aggregate as it is batched within a sensitivity of 0.5 percent by weight of the fine aggregate.

The batching of cement, supplementary cementitious material, or cement plus supplementary cementitious material and aggregate shall be interlocked so that a new batch cannot be started until all weigh hoppers are empty, the proportioning devices are within zero tolerance, and the discharge gates are closed. The interlock shall permit no part of the batch to be discharged until all aggregate hoppers and the cement and supplementary cementitious material hoppers or the cement plus supplementary cementitious material hopper are charged with weights that are within the tolerances specified in Section 90-5.02, "Proportioning Devices."

If interlocks are required for cement and supplementary cementitious material charging mechanisms and cement and supplementary cementitious material are weighed cumulatively, their charging mechanisms shall be interlocked to prevent the introduction of mineral admixture until the weight of cement in the cement weigh hopper is within the tolerances specified in Section 90-5.02, "Proportioning Devices."

If concrete is completely mixed in stationary paving mixers, the supplementary cementitious materials shall be weighed in a separate weigh hopper and the supplementary cementitious material and cement shall be introduced simultaneously into the mixer proportionately with the aggregate. If the Contractor provides certification that the stationary mixer is capable of mixing the cement, supplementary cementitious material, aggregates, and water uniformly before discharge, weighing the supplementary cementitious material cumulatively with the cement is permitted. Certification shall contain the following:

A. Test results for 2 compressive strength test cylinders of concrete taken within the first one-third and 2 compressive strength test cylinders of concrete taken within the last one-third of the concrete discharged from a single batch from the stationary paving mixer. Strength tests and cylinder preparation will be in conformance with the provisions of Section 90-9, "Compressive Strength";
B. Calculations demonstrating that the difference in the averages of 2 compressive strengths taken in the first one-third is no greater than 7.5 percent different than the averages of 2 compressive strengths taken in the last one-third of the concrete discharged from a single batch from the stationary paving mixer. Strength tests and cylinder preparation will be in conformance with the provisions of Section 90-9, "Compressive Strength;" and
C. The mixer rotation speed and time of mixing before discharge that are required to produce a mix that meets the requirements above.

The discharge gate on the cement and supplementary cementitious material hoppers or the cement plus supplementary cementitious material hopper shall be designed to permit regulating the flow of cement, supplementary cementitious material, or cement plus supplementary cementitious material into the aggregate as directed by the Engineer.

If separate weigh boxes are used for each size of aggregate, the discharge gates shall permit regulating the flow of each size of aggregate as directed by the Engineer.

Material discharged from the several bins shall be controlled by gates or by mechanical conveyors. The means of withdrawal from the several bins, and of discharge from the weigh box, shall be interlocked so that not more than one bin can discharge at a time, and so that the weigh box cannot be tripped until the required quantity from each of the several bins has been deposited therein. Should a separate weigh box be used for each size of aggregate, all may be operated and discharged simultaneously.

If the discharge from the several bins is controlled by gates, each gate shall be actuated automatically so that the required mass is discharged into the weigh box, after which the gate shall automatically close and lock.

The automatic weighing system shall be designed so that all proportions required may be set on the weighing controller at the same time.

## 90-6 MIXING AND TRANSPORTING

### 90-6.01 GENERAL

Concrete shall be mixed in mechanically operated mixers, except that when permitted by the Engineer, batches not exceeding 1/3 cubic yard may be mixed by hand methods in conformance with the provisions in Section 90-6.05, "Hand-Mixing."

Equipment having components made of aluminum or magnesium alloys that would have contact with plastic concrete during mixing, transporting, or pumping of portland cement concrete shall not be used.

Concrete shall be homogeneous and thoroughly mixed, and there shall be no lumps or evidence of undispersed cementitious material.

Uniformity of concrete mixtures will be determined by differences in penetration as determined by California Test 533, or slump as determined by ASTM Designation: C 143, and by variations in the proportion of coarse aggregate as determined by California Test 529.

When the mix design specifies a penetration value, the difference in penetration, determined by comparing penetration tests on 2 samples of mixed concrete from the same batch or truck mixer load, shall not exceed 1/2-inch. When the mix design specifies a slump value, the difference in slump, determined by comparing slump tests on 2 samples of mixed concrete from the same batch or truck mixer load, shall not exceed the values given in the table below. Variation in the proportion of coarse aggregate will be determined by comparing the results of tests of 2 samples of mixed concrete from the same batch or truck mixer load and the difference between the 2 results shall not exceed 170 pounds per cubic yard of concrete.

| Average Slump | Maximum Permissible Difference |
|---|---|
| Less than 4" | 1" |
| 4" to 6" | 1 1/2" |
| Greater than 6" to 9" | 2" |

The Contractor shall furnish samples of the freshly mixed concrete and provide satisfactory facilities for obtaining the samples.

**90-6.02 MACHINE MIXING**

Concrete mixers may be of the revolving drum or the revolving blade type, and the mixing drum or blades shall be operated uniformly at the mixing speed recommended by the manufacturer. Mixers and agitators that have an accumulation of hard concrete or mortar shall not be used.

The temperature of mixed concrete, immediately before placing, shall be not less than 50° F or more than 90° F. Aggregates and water shall be heated or cooled as necessary to produce concrete within these temperature limits. Neither aggregates nor mixing water shall be heated to exceed 150° F. If ice is used to cool the concrete, discharge of the mixer will not be permitted until all ice is melted.

The batch shall be so charged into the mixer that some water will enter in advance of cementitious materials and aggregates. All water shall be in the drum by the end of the first one-fourth of the specified mixing time.

Cementitious materials shall be batched and charged into the mixer by means that will not result either in loss of cementitious materials due to the effect of wind, in accumulation of cementitious materials on surfaces of conveyors or hoppers, or in other conditions that reduce or vary the required quantity of cementitious material in the concrete mixture.

Paving and stationary mixers shall be operated with an automatic timing device. The timing device and discharge mechanism shall be interlocked so that during normal operation no part of the batch will be discharged until the specified mixing time has elapsed.

The total elapsed time between the intermingling of damp aggregates and all cementitious materials and the start of mixing shall not exceed 30 minutes.

The size of batch shall not exceed the manufacturer's guaranteed capacity.

When producing concrete for pavement or base, suitable batch counters shall be installed and maintained in good operating condition at job site batching plants and stationary mixers. The batch counters shall indicate the exact number of batches proportioned and mixed.

Concrete shall be mixed and delivered to the job site by means of one of the following combinations of operations:

A. Mixed completely in a stationary mixer and the mixed concrete transported to the point of delivery in truck agitators or in nonagitating hauling equipment (central-mixed concrete).
B. Mixed partially in a stationary mixer, and the mixing completed in a truck mixer (shrink-mixed concrete).
C. Mixed completely in a truck mixer (transit-mixed concrete).
D. Mixed completely in a paving mixer.

Agitators may be truck mixers operating at agitating speed or truck agitators. Each mixer and agitator shall have attached thereto in a prominent place a metal plate or plates on which is plainly marked the various uses for which the equipment is designed, the manufacturer's guaranteed capacity of the drum or container in terms of the volume of mixed concrete and the speed of rotation of the mixing drum or blades.

Truck mixers shall be equipped with electrically or mechanically actuated revolution counters by which the number of revolutions of the drum or blades may readily be verified.

When shrink-mixed concrete is furnished, concrete that has been partially mixed at a central plant shall be transferred to a truck mixer and all requirements for transit-mixed concrete shall apply. No credit in the number of revolutions at mixing speed will be allowed for partial mixing in a central plant.

**90-6.03 TRANSPORTING MIXED CONCRETE**

Mixed concrete may be transported to the delivery point in truck agitators or truck mixers operating at the speed designated by the manufacturer of the equipment as agitating speed, or in non-agitating hauling equipment, provided the consistency and workability of the mixed concrete upon discharge at the delivery point is suitable for adequate placement and consolidation in place, and provided the mixed concrete after hauling to the delivery point conforms to the provisions in Section 90-6.01, "General."

Truck agitators shall be loaded not to exceed the manufacturer's guaranteed capacity and shall maintain the mixed concrete in a thoroughly mixed and uniform mass during hauling.

Bodies of nonagitating hauling equipment shall be constructed so that leakage of the concrete mix, or any part thereof, will not occur at any time.

Concrete hauled in open-top vehicles shall be protected during hauling against rain or against exposure to the sun for more than 20 minutes when the ambient temperature exceeds 75° F.

No additional mixing water shall be incorporated into the concrete during hauling or after arrival at the delivery point, unless authorized by the Engineer. If the Engineer authorizes additional water to be incorporated into the concrete, the drum shall be revolved not less than 30 revolutions at mixing speed after the water is added and before discharge is commenced.

The rate of discharge of mixed concrete from truck mixer-agitators shall be controlled by the speed of rotation of the drum in the discharge direction with the discharge gate fully open.

If a truck mixer or agitator is used for transporting concrete to the delivery point, discharge shall be completed within 1.5 hours or before 250 revolutions of the drum or blades, whichever occurs first, after the introduction of the cement to the aggregates. Under conditions contributing to quick stiffening of the concrete, or if the temperature of the concrete is 85° F or above, the time allowed may be less than 1.5 hours. If an admixture is used to retard the set time, the temperature of the concrete shall not exceed 85° F, the time limit shall be 2 hours, and the revolution limitation shall be 300.

If nonagitating hauling equipment is used for transporting concrete to the delivery point, discharge shall be completed within one hour after the addition of the cement to the aggregates. Under conditions contributing to quick stiffening of the concrete, or when the temperature of the concrete is 85° F or above, the time between the introduction of cement to the aggregates and discharge shall not exceed 45 minutes.

Each load of concrete delivered at the job site shall be accompanied by a weighmaster certificate showing the mix identification number, nonrepeating load number, date and time at which the materials were batched, the total amount of water added to the load, and for transit-mixed concrete, the reading of the revolution counter at the time the truck mixer is charged with cement. This weighmaster certificate shall also show the actual scale weights (pounds) for the ingredients batched. Theoretical or target batch weights shall not be used as a substitute for actual scale weights.

Weighmaster certificates shall be provided in printed form, or if approved by the Engineer, the data may be submitted in electronic media. Electronic media shall be presented in a tab-delimited format on a 3 1/2-inch diskette with a capacity of at least 1.4 megabytes. Captured data, for the ingredients represented by each batch shall be "line feed, carriage return" (LFCR) and "one line, separate record" with allowances for sufficient fields to satisfy the amount of data required by these specifications.

The Contractor may furnish a weighmaster certificate accompanied by a separate certificate that lists the actual batch weights or measurements for a load of concrete provided that both certificates are imprinted with the same nonrepeating load number that is unique to the contract and delivered to the jobsite with the load.

Weighmaster certificates furnished by the Contractor shall conform to the provisions in Section 9-1.01, "Measurement of Quantities."

### 90-6.04 TIME OR AMOUNT OF MIXING

Mixing of concrete in paving or stationary mixers shall continue for the required mixing time after all ingredients, except water and admixture, if added with the water, are in the mixing compartment of the mixer before any part of the batch is released. Transfer time in multiple drum mixers shall not be counted as part of the required mixing time.

The required mixing time, in paving or stationary mixers, of concrete used for concrete structures, except minor structures, shall be not less than 90 seconds or more than 5 minutes, except that when directed by the Engineer in writing, the requirements of the following paragraph shall apply.

The required mixing time, in paving or stationary mixers, except as provided in the preceding paragraph, shall be not less than 50 seconds or more than 5 minutes.

The minimum required revolutions at the mixing speed for transit-mixed concrete shall not be less than that recommended by the mixer manufacturer, but in no case shall the number of revolutions be less than that required to consistently produce concrete conforming to the provisions for uniformity in Section 90-6.01, "General."

When a high range water-reducing admixture is added to the concrete at the job site, the total number of revolutions shall not exceed 300.

### 90-6.05 HAND-MIXING

Hand-mixed concrete shall be made in batches of not more than 1/3 cubic yard and shall be mixed on a watertight, level platform. The proper amount of coarse aggregate shall be measured in measuring boxes and spread on the platform and the fine aggregate shall be spread on this layer, the 2 layers being not more than one foot in total depth. On this mixture shall be spread the dry cementitious materials and the whole mass turned no fewer than 2 times dry; then sufficient clean water shall be added, evenly distributed, and the whole mass again turned no fewer than 3 times, not including placing in the carriers or forms.

### 90-6.06 AMOUNT OF WATER AND PENETRATION

The amount of water used in concrete mixes shall be regulated so that the penetration of the concrete as determined by California Test 533 or the slump of the concrete as determined by ASTM Designation: C 143 is within the nominal values shown in the following table. When the penetration or slump of the concrete is found to exceed the nominal values listed, the mixture of subsequent batches shall be adjusted to reduce the penetration or slump to a value within the nominal range shown. Batches of concrete with a penetration or slump exceeding the maximum values listed shall not be used in the work. If Type F or Type G chemical admixtures are added to the mix, the penetration requirements shall not apply and the slump shall not exceed 9 inches after the chemical admixtures are added.

| Type of Work | Nominal | | Maximum | |
|---|---|---|---|---|
| | Penetration (inches) | Slump (inches) | Penetration (inches) | Slump (inches) |
| Concrete Pavement | 0 - 1 | — | 1 1/2 | — |
| Non-reinforced concrete facilities | 0 - 1 1/2 | — | 2 | — |
| Reinforced concrete structures | | | | |
| Sections over 12 inches thick | 0 - 1 1/2 | — | 2 1/2 | — |
| Sections 12 inches thick or less | 0 - 2 | — | 3 | — |
| Concrete placed under water | — | 6 - 8 | — | 9 |
| Cast-in-place concrete piles | 2 1/2 - 3 1/2 | 5 - 7 | 4 | 8 |

The amount of free water used in concrete shall not exceed 310 pounds per cubic yard, plus 20 pounds for each required 100 pounds of cementitious material in excess of 550 pounds per cubic yard.

The term free water is defined as the total water in the mixture minus the water absorbed by the aggregates in reaching a saturated surface-dry condition.

If there are adverse or difficult conditions that affect the placing of concrete, the above specified penetration and free water content limitations may be exceeded providing the Contractor is granted permission by the Engineer in writing to increase the cementitious material content per cubic yard of concrete. The increase in water and cementitious material shall be at a ratio not to exceed 30 pounds of water per added 100 pounds of cementitious material per cubic yard. Full compensation for additional cementitious material and water added under these conditions shall be considered as included in the contract price paid for the concrete work involved and no additional compensation will be allowed therefor.

The equipment for supplying water to the mixer shall be constructed and arranged so that the amount of water added can be measured accurately. Any method of discharging water into the mixer for a batch shall be accurate within 1.5 percent of the quantity of water required to be added to the mix for any position of the mixer. Tanks used to measure water shall be designed so that water cannot enter while water is being discharged into the mixer and discharge into the mixer shall be made rapidly in one operation without dribbling. All equipment shall be arranged so as to permit checking the amount of water delivered by discharging into measured containers.

## 90-7 CURING CONCRETE

### 90-7.01 METHODS OF CURING

Newly placed concrete shall be cured by the methods specified in this Section 90-7.01 and the special provisions.

#### 90-7.01A Water Method

The concrete shall be kept continuously wet by the application of water for a minimum curing period of 7 days after the concrete has been placed.

Cotton mats, rugs, carpets, or earth or sand blankets may be used as a curing medium to retain the moisture during the curing period.

If a curing medium consisting of cotton mats, rugs, carpets, polyethylene sheeting, polyethylene sheeting on burlap, or earth or sand blankets is to be used to retain the moisture, the entire surface of the concrete shall be kept damp by applying water with a nozzle that so atomizes the flow that a mist and not a spray is formed, until the surface of the concrete is covered with the curing medium. The moisture from the nozzle shall not be applied under pressure directly upon the concrete and shall not be allowed to accumulate on the concrete in a quantity sufficient to cause a flow or wash the surface. At the expiration of the curing period, the concrete surfaces shall be cleared of all curing media.

At the option of the Contractor, a curing medium consisting of white opaque polyethylene sheeting extruded onto burlap may be used to cure concrete structures. The polyethylene sheeting shall have a minimum thickness of 4-mil, and shall be extruded onto 10-ounce burlap.

At the option of the Contractor, a curing medium consisting of polyethylene sheeting may be used to cure concrete columns. The polyethylene sheeting shall have a minimum thickness of 10-mil achieved in a single layer of material.

If the Contractor chooses to use polyethylene sheeting or polyethylene sheeting on burlap as a curing medium, these media and any joints therein shall be secured as necessary to provide moisture retention and shall be within 3 inches of the concrete at all points along the surface being cured. When these media are used, the temperature of the concrete shall be monitored during curing. If the temperature of the concrete cannot be maintained below 140° F, use of these curing media shall be disallowed.

When concrete bridge decks and flat slabs are to be cured without the use of a curing medium, the entire surface of the bridge deck or slab shall be kept damp by the application of water with an atomizing nozzle as specified above, until the concrete has set, after which the entire surface of the concrete shall be sprinkled continuously with water for a period of not less than 7 days.

**90-7.01B Curing Compound Method**

Surfaces of the concrete that are exposed to the air shall be sprayed uniformly with a curing compound.

Curing compounds to be used shall be as follows:

1. Pigmented curing compound conforming to the requirements in ASTM Designation: C 309, Type 2, Class B, except the resin type shall be poly-alpha-methylstyrene.
2. Pigmented curing compound conforming to the requirements in ASTM Designation: C 309, Type 2, Class B.
3. Pigmented curing compound conforming to the requirements in ASTM Designation: C 309, Type 2, Class A.
4. Nonpigmented curing compound conforming to the requirements in ASTM Designation: C 309, Type 1, Class B.
5. Nonpigmented curing compound conforming to the requirements in ASTM Designation: C 309, Type 1, Class A.
6. Nonpigmented curing compound with fugitive dye conforming to the requirements in ASTM Designation: C 309, Type 1-D, Class A.

The infrared scan for the dried vehicle from curing compound (1) shall match the infrared scan on file at the Transportation Laboratory.

The loss of water for each type of curing compound, when tested in conformance with the requirements in California Test 534, shall not be more than 0.28-pounds per square yard in 24 hours.

The curing compound to be used will be specified elsewhere in these specifications or in the special provisions.

If the use of curing compound is required or permitted elsewhere in these specifications or in the special provisions and no specific kind is specified, any of the curing compounds listed above may be used.

Curing compound shall be applied at a nominal rate of one gallon per 150 square feet, unless otherwise specified.

At any point, the application rate shall be within ±50 square feet per gallon of the nominal rate specified, and the average application rate shall be within ±25 square feet per gallon of the nominal rate specified when tested in conformance with the requirements in California Test 535. Runs, sags, thin areas, skips, or holidays in the applied curing compound shall be evidence that the application is not satisfactory.

Curing compounds shall be applied using power operated spray equipment. The power operated spraying equipment shall be equipped with an operational pressure gage and a means of controlling the pressure. Hand spraying of small and irregular areas that are not reasonably accessible to mechanical spraying equipment, in the opinion of the Engineer, may be permitted.

The curing compound shall be applied to the concrete following the surface finishing operation, immediately before the moisture sheen disappears from the surface, but before any drying shrinkage or craze cracks begin to appear. In the event of any drying or cracking of the surface, application of water with an atomizing nozzle as specified in Section 90-7.01A, "Water Method," shall be started immediately and shall be continued until application of the compound is resumed or started; however, the compound shall not be applied over any resulting freestanding water. Should the film of compound be damaged from any cause before the expiration of 7 days after the concrete is placed in the case of structures and 72 hours in the case of pavement, the damaged portion shall be repaired immediately with additional compound.

At the time of use, compounds containing pigments shall be in a thoroughly mixed condition with the pigment uniformly dispersed throughout the vehicle. A paddle shall be used to loosen all settled pigment from the bottom of the container, and a power driven agitator shall be used to disperse the pigment uniformly throughout the vehicle.

Agitation shall not introduce air or other foreign substance into the curing compound.

The manufacturer shall include in the curing compound the necessary additives for control of sagging, pigment settling, leveling, de-emulsification, or other requisite qualities of a satisfactory working material. Pigmented curing compounds shall be manufactured so that the pigment does not settle badly, does not cake or thicken in the container, and does not become granular or curdled. Settlement of pigment shall be a thoroughly wetted, soft, mushy mass permitting the complete and easy

vertical penetration of a paddle. Settled pigment shall be easily redispersed, with minimum resistance to the sideways manual motion of the paddle across the bottom of the container, to form a smooth uniform product of the proper consistency.

Curing compounds shall remain sprayable at temperatures above 40° F and shall not be diluted or altered after manufacture.

The curing compound shall be packaged in clean 274-gallon totes, 55-gallon barrels or 5-gallon pails shall be supplied from a suitable storage tank located at the jobsite. The containers shall comply with "Title 49, Code of Federal Regulations, Hazardous Materials Regulations." The 274-gallon totes and the 55-gallon barrels shall have removable lids and airtight fasteners. The 5-gallon pails shall be round and have standard full open head and bail. Lids with bungholes will not be permitted. Settling or separation of solids in containers, except tanks, must be completely redispersed with low speed mixing prior to use, in conformance with these specifications and the manufacturer's recommendations. Mixing shall be accomplished either manually by use of a paddle or by use of a mixing blade driven by a drill motor, at low speed. Mixing blades shall be the type used for mixing paint. On-site storage tanks shall be kept clean and free of contaminants. Each tank shall have a permanent system designed to completely redisperse settled material without introducing air or other foreign substances.

Steel containers and lids shall be lined with a coating that will prevent destructive action by the compound or chemical agents in the air space above the compound. The coating shall not come off the container or lid as skins. Containers shall be filled in a manner that will prevent skinning. Plastic containers shall not react with the compound.

Each container shall be labeled with the manufacturer's name, kind of curing compound, batch number, volume, date of manufacture, and volatile organic compound (VOC) content. The label shall also warn that the curing compound containing pigment shall be well stirred before use. Precautions concerning the handling and the application of curing compound shall be shown on the label of the curing compound containers in conformance with the Construction Safety Orders and General Industry Safety Orders of the State.

Containers of curing compound shall be labeled to indicate that the contents fully comply with the rules and regulations concerning air pollution control in the State.

When the curing compound is shipped in tanks or tank trucks, a shipping invoice shall accompany each load. The invoice shall contain the same information as that required herein for container labels.

Curing compound will be sampled by the Engineer at the source of supply, at the job site, or at both locations.

Curing compound shall be formulated so as to maintain the specified properties for a minimum of one year. The Engineer may require additional testing before use to determine compliance with these specifications if the compound has not been used within one year or whenever the Engineer has reason to believe the compound is no longer satisfactory.

Tests will be conducted in conformance with the latest ASTM test methods and methods in use by the Transportation Laboratory.

### 90-7.01C Waterproof Membrane Method

The exposed finished surfaces of concrete shall be sprayed with water, using a nozzle that so atomizes the flow that a mist and not a spray is formed, until the concrete has set, after which the curing membrane, shall be placed. The curing membrane shall remain in place for a period of not less than 72 hours.

Sheeting material for curing concrete shall conform to the requirements in AASHTO Designation: M 171 for white reflective materials.

The sheeting material shall be fabricated into sheets of such width as to provide a complete cover for the entire concrete surface. Joints in the sheets shall be securely cemented together in such a manner as to provide a waterproof joint. The joint seams shall have a minimum lap of 0.33-foot.

The sheets shall be securely weighted down by placing a bank of earth on the edges of the sheets or by other means satisfactory to the Engineer.

Should any portion of the sheets be broken or damaged before the expiration of 72 hours after being placed, the broken or damaged portions shall be immediately repaired with new sheets properly cemented into place.

Sections of membrane that have lost their waterproof qualities or have been damaged to such an extent as to render them unfit for curing the concrete shall not be used.

### 90-7.01D Forms-In-Place Method

Formed surfaces of concrete may be cured by retaining the forms in place. The forms shall remain in place for a minimum period of 7 days after the concrete has been placed, except that for members over 20 inches in least dimension the forms shall remain in place for a minimum period of 5 days.

Joints in the forms and the joints between the end of forms and concrete shall be kept moisture tight during the curing period. Cracks in the forms and cracks between the forms and the concrete shall be resealed by methods subject to the approval of the Engineer.

## 90-7.02 CURING PAVEMENT

The entire exposed area of the pavement, including edges, shall be cured by the waterproof membrane method, or curing compound method using curing compound (1) or (2) as the Contractor may elect. Should the side forms be removed before the expiration of 72 hours following the start of curing, the exposed pavement edges shall also be cured. If the pavement is cured by means of the curing compound method, the sawcut and all portions of the curing compound that have been disturbed by sawing operations shall be restored by spraying with additional curing compound.

Curing shall commence as soon as the finishing process provided in Section 40-1.10, "Final Finishing," has been completed. The method selected shall conform to the provisions in Section 90-7.01, "Methods of Curing."

When the curing compound method is used, the compound shall be applied to the entire pavement surface by mechanical sprayers. Spraying equipment shall be of the fully atomizing type equipped with a tank agitator that provides for continual agitation of the curing compound during the time of application. The spray shall be adequately protected against wind, and the nozzles shall be so oriented or moved mechanically transversely as to result in the minimum specified rate of coverage being applied uniformly on exposed faces. Hand spraying of small and irregular areas, and areas inaccessible to mechanical spraying equipment, in the opinion of the Engineer, will be permitted. When the ambient air temperature is above 60° F, the Contractor shall fog the surface of the concrete with a fine spray of water as specified in Section 90-7.01A, "Water Method." The surface of the pavement shall be kept moist between the hours of 10:00 a.m. and 4:30 p.m. on the day the concrete is placed. However, the fogging done after the curing compound has been applied shall not begin until the compound has set sufficiently to prevent displacement. Fogging shall be discontinued if ordered in writing by the Engineer.

## 90-7.03 CURING STRUCTURES

Newly placed concrete for cast-in-place structures, other than highway bridge decks, shall be cured by the water method, the forms-in-place method, or, as permitted herein, by the curing compound method, in conformance with the provisions in Section 90-7.01, "Methods of Curing."

The curing compound method using a pigmented curing compound may be used on concrete surfaces of construction joints, surfaces that are to be buried underground, and surfaces where only ordinary surface finish is to be applied and on which a uniform color is not required and that will not be visible from a public traveled way. If the Contractor elects to use the curing compound method on the bottom slab of box girder spans, the curing compound shall be curing compound (1).

The top surface of highway bridge decks shall be cured by both the curing compound method and the water method. The curing compound shall be curing compound (1).

Concrete surfaces of minor structures, as defined in Section 51-1.02, "Minor Structures," shall be cured by the water method, the forms-in-place method or the curing compound method.

When deemed necessary by the Engineer during periods of hot weather, water shall be applied to concrete surfaces being cured by the curing compound method or by the forms-in-place method, until the Engineer determines that a cooling effect is no longer required. Application of water for this purpose will be paid for as extra work as provided in Section 4-1.03D, "Extra Work."

## 90-7.04 CURING PRECAST CONCRETE MEMBERS

Precast concrete members shall be cured in conformance with any of the methods specified in Section 90-7.01, "Methods of Curing." Curing shall be provided for the minimum time specified for each method or until the concrete reaches its design strength, whichever is less. Steam curing may also be used for precast members and shall conform to the following provisions:

A. After placement of the concrete, members shall be held for a minimum 4-hour presteaming period. If the ambient air temperature is below 50° F, steam shall be applied during the presteaming period to hold the air surrounding the member at a temperature between 50° F and 90° F.
B. To prevent moisture loss on exposed surfaces during the presteaming period, members shall be covered as soon as possible after casting or the exposed surfaces shall be kept wet by fog spray or wet blankets.
C. Enclosures for steam curing shall allow free circulation of steam about the member and shall be constructed to contain the live steam with a minimum moisture loss. The use of tarpaulins or similar flexible covers will be permitted, provided they are kept in good repair and secured in such a manner as to prevent the loss of steam and moisture.
D. Steam at the jets shall be at low pressure and in a saturated condition. Steam jets shall not impinge directly on the concrete, test cylinders, or forms. During application of the steam, the temperature rise within the enclosure shall not exceed 40° F per hour. The curing temperature throughout the enclosure shall not exceed 150° F and shall be maintained at a constant level for a sufficient time necessary to develop the required transfer strength. Control cylinders shall be covered to prevent moisture loss and shall be placed in a location where temperature is representative of the average temperature of the enclosure.

E. Temperature recording devices that will provide an accurate, continuous, permanent record of the curing temperature shall be provided. A minimum of one temperature recording device per 200 feet of continuous bed length will be required for checking temperature.
F. Members in pretension beds shall be detensioned immediately after the termination of steam curing while the concrete and forms are still warm, or the temperature under the enclosure shall be maintained above 60° F until the stress is transferred to the concrete.
G. Curing of precast concrete will be considered completed after termination of the steam curing cycle.

### 90-7.05 CURING PRECAST PRESTRESSED CONCRETE PILES

Newly placed concrete for precast prestressed concrete piles shall be cured in conformance with the provisions in Section 90-7.04, "Curing Precast Concrete Members," except that piles in a corrosive environment shall be cured as follows:

A. Piles shall be either steam cured or water cured. If water curing is used, the piles shall be kept continuously wet by the application of water in conformance with the provisions in Section 90-7.01A, "Water Method."
B. If steam curing is used, the steam curing provisions in Section 90-7.04, "Curing Precast Concrete Members," shall apply except that the piles shall be kept continuously wet for their entire length for a period of not less than 3 days, including the holding and steam curing periods.

### 90-7.06 CURING SLOPE PROTECTION

Concrete slope protection shall be cured in conformance with any of the methods specified in Section 90-7.01, "Methods of Curing."

Concreted-rock slope protection shall be cured in conformance with any of the methods specified in Section 90-7.01, "Methods of Curing," with a blanket of earth kept wet for 72 hours, or by sprinkling with a fine spray of water every 2 hours during the daytime for a period of 3 days.

### 90-7.07 CURING MISCELLANEOUS CONCRETE WORK

Exposed surfaces of curbs shall be cured by pigmented curing compounds as specified in Section 90-7.01B, "Curing Compound Method."

Concrete sidewalks, gutter depressions, island paving, curb ramps, driveways, and other miscellaneous concrete areas shall be cured in conformance with any of the methods specified in Section 90-7.01, "Methods of Curing."

Shotcrete shall be cured for at least 72 hours by spraying with water, by a moist earth blanket, or by any of the methods provided in Section 90-7.01, "Methods of Curing."

Mortar and grout shall be cured by keeping the surface damp for 3 days.

After placing, the exposed surfaces of sign structure foundations, including pedestal portions, if constructed, shall be cured for at least 72 hours by spraying with water, by a moist earth blanket, or by any of the methods provided in Section 90-7.01, "Methods of Curing."

## 90-8 PROTECTING CONCRETE

### 90-8.01 GENERAL

In addition to the provisions in Section 7-1.16, "Contractor's Responsibility for the Work and Materials," the Contractor shall protect concrete as provided in this Section 90-8. If required by the Engineer, the Contractor shall submit a written outline of the proposed methods for protecting the concrete.

The Contractor shall protect concrete from damage from any cause, which shall include, but not be limited to: rain, heat, cold, wind, Contractor's actions, and actions of others.

Concrete shall not be placed on frozen or ice-coated ground or subgrade nor on ice-coated forms, reinforcing steel, structural steel, conduits, precast members, or construction joints.

Under rainy conditions, placing of concrete shall be stopped before the quantity of surface water is sufficient to damage surface mortar or cause a flow or wash of the concrete surface, unless the Contractor provides adequate protection against damage.

Concrete that has been frozen or damaged by other causes, as determined by the Engineer, shall be removed and replaced by the Contractor at the Contractor's expense.

### 90-8.02 PROTECTING CONCRETE STRUCTURES

Structure concrete and shotcrete used as structure concrete shall be maintained at a temperature of not less than 45° F for 72 hours after placing and at not less than 40° F for an additional 4 days.

### 90-8.03 PROTECTING CONCRETE PAVEMENT

Pavement concrete shall be maintained at a temperature of not less than 40° F for 72 hours.

Except as provided in Section 7-1.08, "Public Convenience," the Contractor shall protect concrete pavement against construction and other activities that abrade, scar, discolor, reduce texture depth, lower coefficient of friction, or otherwise damage the surface. Stockpiling, drifting, or excessive spillage of soil, gravel, petroleum products, and concrete or asphalt mixes on the surface of concrete pavement is prohibited unless otherwise specified in these specifications, the special provisions or permitted by the Engineer.

If ordered by the Engineer or shown on the plans or specified in the special provisions, pavement crossings shall be constructed for the convenience of public traffic. The material and work necessary for the construction of the crossings, and their subsequent removal and disposal, will be paid for at the contract unit prices for the items of work involved and if there are no contract items for the work involved, payment for pavement crossings will be made by extra work as provided in Section 4-1.03D, "Extra Work.". Where public traffic will be required to cross over the new pavement, Type III portland cement may be used in concrete, if permitted in writing by the Engineer. The pavement may be opened to traffic as soon as the concrete has developed a modulus of rupture of 550 pounds per square inch. The modulus of rupture will be determined by California Test 523.

No traffic or Contractor's equipment, except as hereinafter provided, will be permitted on the pavement before a period of 10 days has elapsed after the concrete has been placed, nor before the concrete has developed a modulus of rupture of at least 550 pounds per square inch. Concrete that fails to attain a modulus of rupture of 550 pounds per square inch within 10 days shall not be opened to traffic until directed by the Engineer.

Equipment for sawing weakened plane joints will be permitted on the pavement as specified in Section 40-1.08B, "Weakened Plane Joints."

When requested in writing by the Contractor, the tracks on one side of paving equipment will be permitted on the pavement after a modulus of rupture of 350 pounds per square inch has been attained, provided that:

A. Unit pressure exerted on the pavement by the paver shall not exceed 20 pounds per square inch;
B. Tracks with cleats, grousers, or similar protuberances shall be modified or shall travel on planks or equivalent protective material, so that the pavement is not damaged; and
C. No part of the track shall be closer than one foot from the edge of pavement.

In case of visible cracking of, or other damage to the pavement, operation of the paving equipment on the pavement shall be immediately discontinued.

Damage to the pavement resulting from early use of pavement by the Contractor's equipment as provided above shall be repaired by the Contractor.

The State will furnish the molds and machines for testing the concrete for modulus of rupture, and the Contractor, at the Contractor's expense, shall furnish the material and whatever labor the Engineer may require.

## 90-9 COMPRESSIVE STRENGTH

### 90-9.01 GENERAL

Concrete compressive strength requirements consist of a minimum strength that shall be attained before various loads or stresses are applied to the concrete and, for concrete designated by strength, a minimum strength at the age of 28 days or at the age otherwise allowed in Section 90-1.01, "Description." The various strengths required are specified in these specifications or the special provisions or are shown on the plans.

The compressive strength of concrete will be determined from test cylinders that have been fabricated from concrete sampled in conformance with the requirements of California Test 539. Test cylinders will be molded and initially field cured in conformance with California Test 540. Test cylinders will be cured and tested after receipt at the testing laboratory in conformance with the requirements of California Test 521. A strength test shall consist of the average strength of 2 cylinders fabricated from material taken from a single load of concrete, except that, if any cylinder should show evidence of improper sampling, molding, or testing, that cylinder shall be discarded and the strength test shall consist of the strength of the remaining cylinder.

When concrete compressive strength is specified as a prerequisite to applying loads or stresses to a concrete structure or member, test cylinders for other than steam cured concrete will be cured in conformance with Method 1 of California Test 540. The compressive strength of concrete determined for these purposes will be evaluated on the basis of individual tests.

When concrete is designated by 28-day compressive strength rather than by cementitious material content, the concrete strength to be used as a basis for acceptance of other than steam cured concrete will be determined from cylinders cured in conformance with Method 1 of California Test 540. If the result of a single compressive strength test at the maximum age specified or allowed is below the specified strength but is 95 percent or more of the specified strength, the Contractor shall

make corrective changes, subject to approval of the Engineer, in the mix proportions or in the concrete fabrication procedures, before placing additional concrete, and shall pay to the State $10 for each in-place cubic yard of concrete represented by the deficient test. If the result of a single compressive strength test at the maximum age specified or allowed is below 95 percent of the specified strength, but is 85 percent or more of the specified strength, the Contractor shall make the corrective changes specified above, and shall pay to the State $15 for each in-place cubic yard of concrete represented by the deficient test. In addition, such corrective changes shall be made when the compressive strength of concrete tested at 7 days indicates, in the judgment of the Engineer, that the concrete will not attain the required compressive strength at the maximum age specified or allowed. Concrete represented by a single test that indicates a compressive strength of less than 85 percent of the specified 28-day compressive strength will be rejected in conformance with the provisions in Section 6-1.04, "Defective Materials."

If the test result indicates that the compressive strength at the maximum curing age specified or allowed is below the specified strength, but is 85 percent or more of the specified strength, payments to the State as required above shall be made, unless the Contractor, at the Contractor's expense, obtains and submits evidence acceptable to the Engineer that the strength of the concrete placed in the work meets or exceeds the specified 28-day compressive strength. If the test result indicates a compressive strength at the maximum curing age specified or allowed below 85 percent, the concrete represented by that test will be rejected, unless the Contractor, at the Contractor's expense, obtains and submits evidence acceptable to the Engineer that the strength and quality of the concrete placed in the work are acceptable. If the evidence consists of tests made on cores taken from the work, the cores shall be obtained and tested in conformance with the requirements in ASTM Designation: C 42.

No single compressive strength test shall represent more than 320 cubic yards.

If a precast concrete member is steam cured, the compressive strength of the concrete will be determined from test cylinders that have been handled and stored in conformance with Method 3 of California Test 540. The compressive strength of steam cured concrete will be evaluated on the basis of individual tests representing specific portions of production. If the concrete is designated by 28-day compressive strength rather than by cementitious material content, the concrete shall be considered to be acceptable whenever its compressive strength reaches the specified 28-day compressive strength provided that strength is reached in not more than the maximum number of days specified or allowed after the member is cast.

When concrete is specified by compressive strength, prequalification of materials, mix proportions, mixing equipment, and procedures proposed for use will be required prior to placement of the concrete. Prequalification shall be accomplished by the submission of acceptable certified test data or trial batch reports by the Contractor. Prequalification data shall be based on the use of materials, mix proportions, mixing equipment, procedures, and size of batch proposed for use in the work.

Certified test data, in order to be acceptable, shall indicate that not less than 90 percent of at least 20 consecutive tests exceed the specified strength at the maximum number of cure days specified or allowed, and none of those tests are less than 95 percent of specified strength. Strength tests included in the data shall be the most recent tests made on concrete of the proposed mix design and all shall have been made within one year of the proposed use of the concrete.

Trial batch test reports, in order to be acceptable, shall indicate that the average compressive strength of 5 consecutive concrete cylinders, taken from a single batch, at not more than 28 days (or the maximum age allowed) after molding shall be at least 580 pounds per square inch greater than the specified 28-day compressive strength, and no individual cylinder shall have a strength less than the specified strength at the maximum age specified or allowed. Data contained in the report shall be from trial batches that were produced within one year of the proposed use of specified strength concrete in the project. Whenever air-entrainment is required, the air content of trial batches shall be equal to or greater than the air content specified for the concrete without reduction due to tolerances.

Tests shall be performed in conformance with either the appropriate California Test methods or the comparable ASTM test methods. Equipment employed in testing shall be in good condition and shall be properly calibrated. If the tests are performed during the life of the contract, the Engineer shall be notified sufficiently in advance of performing the tests in order to witness the test procedures.

The certified test data and trial batch test reports shall include the following information:

A. Date of mixing.
B. Mixing equipment and procedures used.
C. The size of batch in cubic yards and the weight, type, and source of all ingredients used.
D. Penetration or slump (if the concrete will be placed under water or placed in cast-in-place concrete piles) of the concrete.
E. The air content of the concrete if an air-entraining admixture is used.
F. The age at time of testing and strength of all concrete cylinders tested.

Certified test data and trial batch test reports shall be signed by an official of the firm that performed the tests.

When approved by the Engineer, concrete from trial batches may be used in the work at locations where concrete of a lower quality is required and the concrete will be paid for as the type or class of concrete required at that location.

After materials, mix proportions, mixing equipment, and procedures for concrete have been prequalified for use, additional prequalification by testing of trial batches will be required prior to making changes that, in the judgment of the Engineer, could result in a strength of concrete below that specified.

The Contractor's attention is directed to the time required to test trial batches and the Contractor shall be responsible for production of trial batches at a sufficiently early date so that the progress of the work is not delayed.

When precast concrete members are manufactured at the plant of an established manufacturer of precast concrete members, the mix proportions of the concrete shall be determined by the Contractor, and a trial batch and prequalification of the materials, mix proportions, mixing equipment, and procedures will not be required.

## 90-10 MINOR CONCRETE

### 90-10.01 GENERAL

Concrete for minor structures, slope paving, curbs, sidewalks and other concrete work, when designated as minor concrete on the plans, in the specifications, or in the contract item, shall conform to the provisions specified herein.

The Engineer, at the Engineer's discretion, will inspect and test the facilities, materials and methods for producing the concrete to ensure that minor concrete of the quality suitable for use in the work is obtained.

### 90-10.02 MATERIALS

Minor concrete shall conform to the following requirements:

#### 90-10.02A Cementitious Material

Cementitious material shall conform to the provisions in Section 90-1.01, "Description."

#### 90-10.02B Aggregate

Aggregate shall be clean and free from deleterious coatings, clay balls, roots, and other extraneous materials.

Use of crushed concrete or reclaimed aggregate is acceptable only if the aggregate satisfies all aggregate requirements.

The Contractor shall submit to the Engineer for approval, a grading of the combined aggregate proposed for use in the minor concrete. After acceptance of the grading, aggregate furnished for minor concrete shall conform to that grading, unless a change is authorized in writing by the Engineer.

The Engineer may require the Contractor to furnish periodic test reports of the aggregate grading furnished. The maximum size of aggregate used shall be at the option of the Contractor, but in no case shall the maximum size be larger than 1 1/2-inch or smaller than 3/4-inch.

The Engineer may waive, in writing, the gradation requirements in this Section 90-10.02B, if, in the Engineer's opinion, the furnishing of the gradation is not necessary for the type or amount of concrete work to be constructed.

#### 90-10.02C Water

Water used for washing, mixing, and curing shall be free from oil, salts, and other impurities that would discolor or etch the surface or have an adverse affect on the quality of the concrete.

#### 90-10.02D Admixtures

The use of admixtures shall conform to the provisions in Section 90-4, "Admixtures."

### 90-10.03 PRODUCTION

Cementitious material, water, aggregate, and admixtures shall be stored, proportioned, mixed, transported, and discharged in conformance with recognized standards of good practice that will result in concrete that is thoroughly and uniformly mixed, that is suitable for the use intended, and that conforms to requirements specified herein. Recognized standards of good practice are outlined in various industry publications such as are issued by American Concrete Institute, AASHTO, or the Department.

The cementitious material content of minor concrete shall conform to the provisions in Section 90-1.01, "Description."

The amount of water used shall result in a consistency of concrete conforming to the provisions in Section 90-6.06, "Amount of Water and Penetration." Additional mixing water shall not be incorporated into the concrete during hauling or after arrival at the delivery point, unless authorized by the Engineer.

Discharge of ready-mixed concrete from the transporting vehicle shall be made while the concrete is still plastic and before stiffening occurs. An elapsed time of 1.5 hours (one hour in non-agitating hauling equipment), or more than 250 revolutions of the drum or blades, after the introduction of the cementitious material to the aggregates, or a temperature

of concrete of more than 90° F will be considered conditions contributing to the quick stiffening of concrete. The Contractor shall take whatever action is necessary to eliminate quick stiffening, except that the addition of water will not be permitted.

The required mixing time in stationary mixers shall be not less than 50 seconds or more than 5 minutes.

The minimum required revolutions at mixing speed for transit-mixed concrete shall be not less than that recommended by the mixer manufacturer, and shall be increased, if necessary, to produce thoroughly and uniformly mixed concrete.

When a high range water-reducing admixture is added to the concrete at the job site, the total number of revolutions shall not exceed 300.

Each load of ready-mixed concrete shall be accompanied by a weighmaster certificate that shall be delivered to the Engineer at the discharge location of the concrete, unless otherwise directed by the Engineer. The weighmaster certificate shall be clearly marked with the date and time of day when the load left the batching plant and, if hauled in truck mixers or agitators, the time the mixing cycle started.

A Certificate of Compliance conforming to the provisions in Section 6–1.07, "Certificates of Compliance," shall be furnished to the Engineer, prior to placing minor concrete from a source not previously used on the contract, stating that minor concrete to be furnished meets contract requirements, including minimum cementitious material content specified.

### 90-10.04 CURING MINOR CONCRETE

Curing minor concrete shall conform to the provisions in Section 90-7, "Curing Concrete."

### 90-10.05 PROTECTING MINOR CONCRETE

Protecting minor concrete shall conform to the provisions in Section 90-8, "Protecting Concrete," except the concrete shall be maintained at a temperature of not less than 40° F for 72 hours after placing.

### 90-10.06 MEASUREMENT AND PAYMENT

Minor concrete will be measured and paid for in conformance with the provisions specified in the various sections of these specifications covering concrete construction when minor concrete is specified in the specifications, shown on the plans, or indicated by contract item in the Engineer's Estimate.

## 90-11 MEASUREMENT AND PAYMENT

### 90-11.01 MEASUREMENT

Portland cement concrete will be measured in conformance with the provisions specified in the various sections of these specifications covering construction requiring concrete.

For concrete measured at the mixer, the volume in cubic feet shall be computed as the total weight of the batch in pounds divided by the density of the concrete in pounds per cubic foot. The total weight of the batch shall be calculated as the sum of all materials, including water, entering the batch. The density of the concrete will be determined in conformance with the requirements in California Test 518.

### 90-11.02 PAYMENT

Portland cement concrete will be paid for in conformance with the provisions specified in the various sections of these specifications covering construction requiring concrete.

Full compensation for furnishing and incorporating admixtures required by these specifications or the special provisions will be considered as included in the contract prices paid for the concrete involved and no additional compensation will be allowed therefor.

Should the Engineer order the Contractor to incorporate any admixtures in the concrete when their use is not required by these specifications or the special provisions, furnishing the admixtures and adding them to the concrete will be paid for as extra work as provided in Section 4-1.03D, "Extra Work."

Should the Contractor use admixtures in conformance with the provisions in Section 90-4.05, "Optional Use of Chemical Admixtures," or Section 90-4.07, "Optional Use of Air-entraining Admixtures," or should the Contractor request and obtain permission to use other admixtures for the Contractor's benefit, the Contractor shall furnish those admixtures and incorporate them into the concrete at the Contractor's expense and no additional compensation will be allowed therefor.

^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^

## SECTION 91 PAINT
**(Issued 05-1-06)**

**Replace Section 91-3 with:**

### 91-3 PAINTS FOR TIMBER

**91-3.01 WOOD PRIMER, LATEX-BASE**

**Classification:**

This specification covers a ready-mixed priming paint for use on unpainted wood or exterior woodwork. It shall conform with the requirements in the Detailed Performance Standards of the Master Painters Institute (MPI) for exterior wood primers, and be listed on the Exterior Latex Wood Primer MPI List Number 6.

**91-3.02 PAINT; LATEX-BASE FOR EXTERIOR WOOD, WHITE AND TINTS**

**Classification:**

This specification covers a ready-mixed paint for use on wood surfaces subject to outside exposures. This paint shall conform to the requirements in the Detailed Performance Standards of the Master Painters Institute (MPI) for Paint, Latex, Exterior, and shall be listed on the following MPI Approved Products List:

A. Exterior Latex, Flat MPI Gloss Level 1, MPI List Number 10.
B. Exterior Latex, Semi-Gloss, MPI Gloss Level 5, MPI List Number 11.
C. Exterior Latex, Gloss, MPI Gloss Level 6, MPI List Number 119.

Unpainted wood shall first be primed with wood primer conforming to the provisions in Section 91-3.01, "Wood Primer, Latex-Base."

**Replace Section 91-4 with:**

### 91-4 MISCELLANEOUS PAINTS

**91-4.01 THROUGH 91-4.04 (BLANK)**

**91-4.05 PAINT; ACRYLIC EMULSION, EXTERIOR WHITE AND LIGHT AND MEDIUM TINTS**

**Classification:**

This specification covers an acrylic emulsion paint designed for use on exterior masonry. This paint shall conform to the requirements in the Detailed Performance Standards of the Master Painters Institute (MPI) for Paint, Latex, Exterior, and shall be listed on the following MPI Approved Products Lists:

A. Exterior Latex, Flat MPI Gloss Level 1, MPI List Number 10.
B. Exterior Latex, Semi-Gloss, MPI Gloss Level 5, MPI List Number 11.
C. Exterior Latex, Gloss, MPI Gloss Level 6, MPI List Number 119.

This paint may be tinted by using "universal" or "all purpose" concentrates.

^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^

## SECTION 92 ASPHALTS
**(Issued 03-21-08)**

**Replace Section 92 with:**

### SECTION 92 ASPHALTS

## 92-1.01 DESCRIPTION

Asphalt is refined petroleum or a mixture of refined liquid asphalt and refined solid asphalt that are prepared from crude petroleum. Asphalt is:

1. Free from residues caused by the artificial distillation of coal, coal tar, or paraffin
2. Free from water
3. Homogeneous

## 92-1.02 MATERIALS

### GENERAL

Furnish asphalt under the Department's "Certification Program for Suppliers of Asphalt." The Department maintains the program requirements, procedures, and a list of approved suppliers at:

http://www.dot.ca.gov/hq/esc/Translab/fpm/fpmcoc.htm

Transport, store, use, and dispose of asphalt safely.
Prevent the formation of carbonized particles caused by overheating asphalt during manufacturing or construction.

### GRADES

Performance graded (PG) asphalt binder is:

Performance Graded Asphalt Binder

| Property | AASHTO Test Method | Specification Grade | | | | |
|---|---|---|---|---|---|---|
| | | PG 58-22 [a] | PG 64-10 | PG 64-16 | PG 64-28 | PG 70-10 |
| Original Binder | | | | | | |
| Flash Point, Minimum °C | T 48 | 230 | 230 | 230 | 230 | 230 |
| Solubility, Minimum % [b] | T 44 | 99 | 99 | 99 | 99 | 99 |
| Viscosity at 135°C, [c] Maximum, Pa·s | T 316 | 3.0 | 3.0 | 3.0 | 3.0 | 3.0 |
| Dynamic Shear, Test Temp. at 10 rad/s, °C | T 315 | 58 | 64 | 64 | 64 | 70 |
| Minimum G*/sin(delta), kPa | | 1.00 | 1.00 | 1.00 | 1.00 | 1.00 |
| RTFO Test, [e] Mass Loss, Maximum, % | T 240 | 1.00 | 1.00 | 1.00 | 1.00 | 1.00 |
| RTFO Test Aged Binder | | | | | | |
| Dynamic Shear, Test Temp. at 10 rad/s, °C | T 315 | 58 | 64 | 64 | 64 | 70 |
| Minimum G*/sin(delta), kPa | | 2.20 | 2.20 | 2.20 | 2.20 | 2.20 |
| Ductility at 25°C Minimum, cm | T 51 | 75 | 75 | 75 | 75 | 75 |
| PAV [f] Aging, Temperature, °C | R 28 | 100 | 100 | 100 | 100 | 110 |
| RTFO Test and PAV Aged Binder | | | | | | |
| Dynamic Shear, Test Temp. at 10 rad/s, °C | T 315 | 22 [d] | 31 [d] | 28 [d] | 22 [d] | 34 [d] |
| Maximum G*sin(delta), kPa | | 5000 | 5000 | 5000 | 5000 | 5000 |
| Creep Stiffness, Test Temperature, °C | T 313 | -12 | 0 | -6 | -18 | 0 |
| Maximum S-value, Mpa | | 300 | 300 | 300 | 300 | 300 |
| Minimum M-value | | 0.300 | 0.300 | 0.300 | 0.300 | 0.300 |

Notes:

a. Use as asphalt rubber base stock for high mountain and high desert area.

b. The Engineer waives this specification if the supplier is a Quality Supplier as defined by the Department's "Certification Program for Suppliers of Asphalt."

c. The Engineer waives this specification if the supplier certifies the asphalt binder can be adequately pumped and mixed at temperatures meeting applicable safety standards.

d. Test the sample at 3°C higher if it fails at the specified test temperature. G*sin(delta) remains 5000 kPa maximum.

e. "RTFO Test" means the asphaltic residue obtained using the Rolling Thin Film Oven Test, AASHTO Test Method T 240 or ASTM Designation: D 2872. The residue from mass change determination may be used for other tests.

f. "PAV" means Pressurized Aging Vessel.

Performance graded polymer modified asphalt binder (PG Polymer Modified) is:

Performance Graded Polymer Modified Asphalt Binder [a]

| Property | AASHTO Test Method | Specification Grade | | |
|---|---|---|---|---|
| | | PG 58-34 PM | PG 64-28 PM | PG 76-22 PM |
| Original Binder | | | | |
| Flash Point, Minimum °C | T 48 | 230 | 230 | 230 |
| Solubility, Minimum % [b] | T 44[c] | 98.5 | 98.5 | 98.5 |
| Viscosity at 135°C, [d]<br>Maximum, Pa·s | T 316 | 3.0 | 3.0 | 3.0 |
| Dynamic Shear,<br>Test Temp. at 10 rad/s, °C<br>Minimum G*/sin(delta), kPa | T 315 | 58<br>1.00 | 64<br>1.00 | 76<br>1.00 |
| RTFO Test ,<br>Mass Loss, Maximum, % | T 240 | 1.00 | 1.00 | 1.00 |
| RTFO Test Aged Binder | | | | |
| Dynamic Shear,<br>Test Temp. at 10 rad/s, °C<br>Minimum G*/sin(delta), kPa | T 315 | 58<br>2.20 | 64<br>2.20 | 76<br>2.20 |
| Dynamic Shear,<br>Test Temp. at 10 rad/s, °C<br>Maximum (delta), % | T 315 | Note e<br>80 | Note e<br>80 | Note e<br>80 |
| Elastic Recovery[f],<br>Test Temp., °C<br>Minimum recovery, % | T 301 | 25<br>75 | 25<br>75 | 25<br>65 |
| PAV[g] Aging,<br>Temperature, °C | R 28 | 100 | 100 | 110 |
| RTFO Test and PAV Aged Binder | | | | |
| Dynamic Shear,<br>Test Temp. at 10 rad/s, °C<br>Maximum G*sin(delta), kPa | T 315 | 16<br>5000 | 22<br>5000 | 31<br>5000 |
| Creep Stiffness,<br>Test Temperature, °C<br>Maximum S-value, MPa<br>Minimum M-value | T 313 | -24<br>300<br>0.300 | -18<br>300<br>0.300 | -12<br>300<br>0.300 |

Notes:

a. Do not modify PG Polymer Modified using acid modification.

b. The Engineer waives this specification if the supplier is a Quality Supplier as defined by the Department's "Certification Program for Suppliers of Asphalt."

c. The Department allows ASTM D 5546 instead of AASHTO T 44

d. The Engineer waives this specification if the supplier certifies the asphalt binder can be adequately pumped and mixed at temperatures meeting applicable safety standards.

e. Test temperature is the temperature at which G*/sin(delta) is 2.2 kPa. A graph of log G*/sin(delta) plotted against temperature may be used to determine the test temperature when G*/sin(delta) is 2.2 kPa. A graph of (delta) versus temperature may be used to determine delta at the temperature when G*/sin(delta) is 2.2 kPa. The Engineer also accepts direct measurement of (delta) at the temperature when G*/sin(delta) is 2.2 kPa.

f. Tests without a force ductility clamp may be performed.

g. "PAV" means Pressurized Aging Vessel.

**SAMPLING**

Provide a sampling device in the asphalt feed line connecting the plant storage tanks to the asphalt weighing system or spray bar. Make the sampling device accessible between 24 and 30 inches above the platform. Provide a receptacle for flushing the sampling device.

Include with the sampling device a valve:

1. Between 1/2 and 3/4 inch in diameter
2. Manufactured in a manner that a one-quart sample may be taken slowly at any time during plant operations
3. Maintained in good condition

Replace failed valves.

In the Engineer's presence, take 2 one-quart samples per operating day. Provide round, friction top, one-quart containers for storing samples.

**92-1.03 EXECUTION**

If asphalt is applied, you must comply with the heating and application specifications for liquid asphalt in Section 93, "Liquid Asphalts."

**92-1.04 MEASUREMENT**

If the contract work item for asphalt is paid by weight, the Department measures asphalt tons by complying with the specifications for weight determination of liquid asphalt in Section 93, "Liquid Asphalts."

The Engineer determines the asphalt weight from volumetric measurements if you:

1. Use a partial asphalt load
2. Use asphalt at a location other than a mixing plant and no scales within 20 miles are available and suitable
3. Deliver asphalt in either of the following:

    3.1. A calibrated truck with each tank accompanied by its measuring stick and calibration card
    3.2. A truck equipped with a calibrated thermometer that determines the asphalt temperature at the delivery time and with a vehicle tank meter complying with the specifications for weighing, measuring, and metering devices in Section 9-1.01, "Measurement of Quantities"

If you furnish hot mix asphalt from a mixing plant producing material for only one project, the Engineer determines the asphalt quantity by measuring the volume in the tank at the project's start and end provided the tank is calibrated and equipped with its measuring stick and calibration card.

The Engineer determines pay quantities from volumetric measurements as follows:

1. Before converting the volume to weight, the Engineer reduces the measured volume to that which the asphalt would occupy at 60 °F.
2. The Engineer uses 235 gallons per ton and 8.51 pounds per gallon for the average weight and volume for PG and PG Polymer Modified asphalt grades at 60 °F.
3. The Engineer uses the Conversion Table in Section 93, "Liquid Asphalts."

^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^

## SECTION 93 LIQUID ASPHALTS
**(Issued 11-03-06)**

**In Section 93-1.04 replace the 9th paragraph with:**

The following Legend and Conversion Table is to be used for converting volumes of liquid asphalt products, Grades 70 to 3000, inclusive, and paving asphalt Grades PG 58-22, PG 64-10, PG 64-16, PG 64-28, and PG 70-10, and Grades PG 58-34 PM, PG 64-28 PM, and PG 76-22 PM.