

DEPARTMENT OF TRANSPORTATION
DIVISION OF ENGINEERING SERVICES
OFFICE ENGINEER, MS 43
1727 30TH STREET
P.O. BOX 168041
SACRAMENTO, CA 95816-8041
FAX (916) 227-6214
TTY (916) 227-8454



*Flex your power!
Be energy efficient!*

**** WARNING ** WARNING ** WARNING ** WARNING ****

This document is intended for informational purposes only.

Users are cautioned that California Department of Transportation (Department) does not assume any liability or responsibility based on these electronic files or for any defective or incomplete copying, excerpting, scanning, faxing or downloading of the contract documents. As always, for the official paper versions of the bidders packages and non-bidder packages, including addenda write to the California Department of Transportation, Plans and Bid Documents, Room 0200, P.O. Box 942874, Sacramento, CA 94272-0001, telephone (916) 654-4490 or fax (916) 654-7028. Office hours are 7:30 a.m. to 4:15 p.m. When ordering bidder or non-bidder packages it is important that you include a telephone number and fax number, P.O. Box and street address so that you can receive addenda.

September 6, 2006

04-SM-101-0.0/10.9
04-OC9504

Addendum No. 1

Dear Contractor:

This addendum is being issued to the contract for construction on State highway in SAN MATEO COUNTY IN EAST PALO ALTO, MENLO PARK AND REDWOOD CITY FROM SANTA CLARA COUNTY LINE TO 0.2 KM NORTH OF WHIPPLE AVENUE OVERCROSSING.

Submit bids for this work with the understanding and full consideration of this addendum. The revisions declared in this addendum are an essential part of the contract.

Bids for this work will be opened on September 20, 2006.

This addendum is being issued to revise the Notice to Contractors and Special Provisions and the Proposal and Contract.

In the Notice to Contractors and Special Provisions, "IMPORTANT SPECIAL NOTICES," the following Special Notice is added as follows:

- "• The specifications for this project require the production of asphalt-rubber binder. The Air Quality Management District must approve the production and placement of asphalt-rubber binder and rubberized asphalt concrete, in addition to the Operating Permits required to produce asphalt concrete. Air Quality Management Districts have stopped production of these products due to failure to obtain necessary approvals."

In the Notice to Contractors and Special Provisions, "STANDARD PLANS LIST," the following Standard Plan is added as follows:

"A77L5 Metal Beam Railing Terminal System (Type FLEAT)"

In the Proposal and Contract, the Engineer's Estimate Items 13 and 29 are revised, Item 14 is deleted, and the "Cost Per Day" for the "TOTAL BID (B)" is provided as attached.

Addendum No. 1
Page 2
September 6, 2006

04-SM-101-0.0/10.9
04-0C9504

To Proposal and Contract book holders:

Replace the entire Engineer's Estimate in the Proposal with the attached revised Engineer's Estimate. The revised Engineer's Estimate is to be used in the bid.

Inquiries or questions in regard to this addendum must be communicated as a bidder inquiry and must be made as noted in the NOTICE TO CONTRACTORS section of the Notice to Contractors and Special Provisions.

Indicate receipt of this addendum by filling in the number of this addendum in the space provided on the signature page of the proposal.

Submit bids in the Proposal and Contract book you now possess. Holders who have already mailed their book will be contacted to arrange for the return of their book.

Inform subcontractors and suppliers as necessary.

This office is sending this addendum by confirmed facsimile to all book holders to ensure that each receives it. A copy of this addendum is available for the contractor's use on the Internet Site:

http://www.dot.ca.gov/hq/esc/oe/weekly_ads/addendum_page.html

If you are not a Proposal and Contract book holder, but request a book to bid on this project, you must comply with the requirements of this letter before submitting your bid.

Sincerely,

ORIGINAL SIGNED BY

REBECCA D. HARNAGEL, Chief
Office of Plans, Specifications & Estimates
Office Engineer

Attachments

**ENGINEER'S ESTIMATE
04-0C9504**

Item No.	Item Code	Item Description	Unit of Measure	Estimated Quantity	Unit Price	Item Total
1	070012	PROGRESS SCHEDULE (CRITICAL PATH METHOD)	LS	LUMP SUM	LUMP SUM	
2	070018	TIME-RELATED OVERHEAD	LS	LUMP SUM	LUMP SUM	
3	074019	PREPARE STORM WATER POLLUTION PREVENTION PLAN	LS	LUMP SUM	LUMP SUM	
4	074020	WATER POLLUTION CONTROL	LS	LUMP SUM	LUMP SUM	
5	074038	TEMPORARY DRAINAGE INLET PROTECTION	EA	130		
6	074042	TEMPORARY CONCRETE WASHOUT (PORTABLE)	LS	LUMP SUM	LUMP SUM	
7 (S)	120090	CONSTRUCTION AREA SIGNS	LS	LUMP SUM	LUMP SUM	
8 (S)	120100	TRAFFIC CONTROL SYSTEM	LS	LUMP SUM	LUMP SUM	
9 (S)	128650	PORTABLE CHANGEABLE MESSAGE SIGN	EA	4		
10	038340	REMOVE HEADLIGHT GLARE SCREEN	M	10 300		
11	150771	REMOVE ASPHALT CONCRETE DIKE	M	100		
12	151625	RECONSTRUCT METAL BEAM GUARD RAILING (WOOD POST)	M	140		
13 (S)	153103	COLD PLANE ASPHALT CONCRETE PAVEMENT	M2	369 000		
14	BLANK					
15	156590	REMOVE CRASH CUSHION (SAND FILLED)	EA	40		
16	198007	IMPORTED MATERIAL (SHOULDER BACKING)	TONN	1000		
17	260210	AGGREGATE BASE (APPROACH SLAB)	M3	3		
18	374002	ASPHALTIC EMULSION (FOG SEAL COAT)	TONN	1		
19	390095	REPLACE ASPHALT CONCRETE SURFACING	M3	40		
20	390102	ASPHALT CONCRETE (TYPE A)	TONN	1200		

**ENGINEER'S ESTIMATE
04-0C9504**

Item No.	Item Code	Item Description	Unit of Measure	Estimated Quantity	Unit Price	Item Total
21	390126	RUBBERIZED ASPHALT CONCRETE (TYPE G)	TONN	39 000		
22	394046	PLACE ASPHALT CONCRETE DIKE (TYPE D)	M	100		
23	397001	ASPHALTIC EMULSION (PAINT BINDER)	TONN	72		
24	401108	REPLACE CONCRETE PAVEMENT (RAPID STRENGTH CONCRETE)	M3	610		
25 (S)	420201	GRIND EXISTING CONCRETE PAVEMENT	M2	80 500		
26	510087	STRUCTURAL CONCRETE, APPROACH SLAB (TYPE R)	M3	30		
27	510800	PAVING NOTCH EXTENSION	M3	1		
28 (S)	519117	JOINT SEAL (MR 30 MM)	M	33		
29 (S)	832003	METAL BEAM GUARD RAILING (WOOD POST)	M	13		
30 (S)	839585	ALTERNATIVE FLARED TERMINAL SYSTEM	EA	13		
31	839604	CRASH CUSHION (REACT 9CBB)	EA	1		
32	839605	CRASH CUSHION (REACT 9SCBS)	EA	2		
33 (S)	840515	THERMOPLASTIC PAVEMENT MARKING	M2	280		
34 (S)	840561	100 MM THERMOPLASTIC TRAFFIC STRIPE	M	50 900		
35 (S)	840563	200 MM THERMOPLASTIC TRAFFIC STRIPE	M	3250		
36 (S)	840564	200 MM THERMOPLASTIC TRAFFIC STRIPE (BROKEN 3.66 M - 0.92 M)	M	6230		
37 (S)	840571	100 MM THERMOPLASTIC TRAFFIC STRIPE (BROKEN 5.18 M - 2.14 M)	M	330		
38 (S)	850101	PAVEMENT MARKER (NON-REFLECTIVE)	EA	18 500		
39 (S)	850111	PAVEMENT MARKER (RETROREFLECTIVE)	EA	8690		
40 (S)	038341	MODIFY INDUCTIVE LOOP DETECTORS	LS	LUMP SUM	LUMP SUM	

