

APPENDIX B

LICENSE TO ENTER AND DIG PERMITS

ORIGINAL

**Doyle Drive Replacement Project
License to Enter and Conduct
Geotechnical Investigations**

Modification No. 2

This document shall serve to modify the License to Enter ("License") given by the Presidio Trust ("Trust") to the State of California Department of Transportation ("State") and to the San Francisco County Transportation Authority ("Authority") effective November 15, 2007 for the temporary non-exclusive use of certain specified locations within Area B of the Presidio of San Francisco ("Area B") to conduct geotechnical investigations leading to the final design of the Doyle Drive Replacement Project.

Scope of Work. The permissible scope of work under this Modification shall be the collection of soil and groundwater samples from 133 soil borings within the Doyle Drive Replacement Project construction zone. The borings shall be advanced with hollow-stem auger, direct push, hand auger, and/or rotary drill rig methods. Proposed excavation areas and boring locations are shown on Exhibit No. 3 to the License, Figures 1 and 2, and the boring depths are presented on Exhibit No. 3 to the License, Table 1. Proposed boring depths range from approximately 2.5 feet to 120 feet below ground surface. Drilling shall be conducted in one phase under this Modification. All activities associated with this work (hereinafter, the "Soil and Groundwater Sampling Work") shall be conducted strictly in accordance with Exhibit No. 3 to the License. Only the Soil and Groundwater Sampling Work as described therein shall be allowed under this License unless all parties properly execute a written amendment hereto. All Soil and Groundwater Sampling Work shall also be conducted strictly in accordance with the terms and conditions contained herein and the terms and conditions of the License. All terms and conditions of the License and Exhibit No. 1 to the License not changed by this Modification No. 2 shall remain in full force and effect.

Term. This Modification shall extend the term of the License through midnight on April 31, 2008.

Licensed Area. In addition to those areas allowed for entrance under the License, this Modification shall serve to allow Licensees to enter the areas as shown in Figures 1 and 2 on Exhibit No. 3.

Understanding with Respect to Certain Language in Exhibit No. 3. With respect to Exhibit No. 3 to the License, the parties hereby agree that the mutual understanding of the last sentence of the third paragraph on Page 1 of that exhibit ("The SIR/SMP will be finalized for the Presidio Trust's approval") is that the SIR/SMP is subject to approval by the Trust and may not be implemented until such approval is given in writing.

Facsimile Signatures. This document and modifications hereto will be considered signed when the signature of a party is delivered by facsimile transmission to the other parties. Such facsimile signature shall be treated in all respects as having the same effect as an original signature. Signatures shall be transmitted to the following numbers.

To the Trust: 415 561 5308, Attention: Mark Helmbrecht.

To the State: 510 541 5542, Attention: Nidal Tuqan.

To the Authority: 415 522 4812, Attention: Lee Saage.

Counterparts. This document may be executed in any number of counterparts, each of which shall be an original, but all of which together shall constitute one instrument.

Effectiveness. This document shall be effective only when signed by all parties.

THE UNDERSIGNED HAVE READ AND EXPRESSLY AGREE TO ALL OF THE TERMS OF THIS MODIFICATION NO. 2.


LICENSEES

State of California Department of Transportation



NIDAL TUQAN
Project Manager

11/7/08
Date

APPROVED AS TO FORM



Todd M. Van Santen
Deputy Attorney

San Francisco County Transportation Authority



Jose Luis Moscovich
Executive Director

11/13/08
Date

APPROVED AS TO FORM


Stanley Taylor
Counsel


MODIFICATION TO LICENSE GRANTED BY THE PRESIDIO TRUST



Craig R. Middleton
Executive Director

11/17/08
Date

APPROVED AS TO FORM



Al Rosen
Deputy General Counsel



EXCAVATION CLEARANCE


CLEARANCE NUMBER: 4043 USA NUMBER: Contractor Is Responsible For Calling In USA
DATE CLEARANCE ISSUED: 11/25/08 JOB #: _____
CLEARANCE EXPIRATION: ** N/A
** For extension of clearance expiration date, call Excavation Clearance Official two (2) days before clearance expiration at 415-561-5327.

CLEARANCE ISSUED TO: Cheri Page or Ray Boyer
ADDRESS: _____

CONTACT: Cheri Page
PHONE NUMBER: 707.762.5233 CELLULAR: 707.322.8625
FAX NUMBER: 707.762.5271 E-MAIL ADDRESS: cheri@baseline-env.com

LOCATION OF UTILITY / EXCAVATION: Doyle Drive Environmental Borings (Dig Permit No. 1) – Drill and sample 44 borings.

COMMENTS: **MUST HAND DIG NEAR ANY MARKED UTILITIES. CONTRACTOR IS RESPONSIBLE FOR CALLING IN U.S.A.**

Signature of Permitting Department Official: 

MANDATORY INSTRUCTIONS FOR CLEARANCE HOLDER

1. This Excavation Clearance must be available for inspection at the excavation site at all times. Failure to maintain this Excavation Clearance is grounds to have the project halted.
2. The Presidio Trust will identify all Presidio Trust operated and maintained utilities: potable water, sanitary sewer, storm sewer, electric cable and communication lines. The location of these utilities are identified in the field with spray paint and/or flags denoting the approximate utility location on the ground surface within the excavation area. The spray paint represents approximate location of utilities, the Contractor / Clearance Holder must exercise extreme care when excavating near utilities.
3. The Contractor and/or Clearance Holder will be responsible for repair to all located and identified Presidio Trust utilities damaged during construction. Utilities shall be repaired to the satisfaction of the Presidio Trust Utility Department.
4. This Excavation Clearance acknowledges that the utility locating organization, USA DIG, was contacted in regards to the proposed excavation. The appropriate USA DIG clearance number appears at the top of the clearance. This clearance does not cover any other utility not identified above in item 2. Contractor and / or Clearance Holder shall coordinate for repair or replacement of any non-Presidio Trust utility damaged during excavation or project construction with the appropriate utility owner.
5. Contractor and clearance holder jointly and severally agree to defend, indemnify, and hold harmless the Presidio Trust for all costs, claims, or settlement, or actions of any kind whatsoever arising from or associated with damage to any non-Presidio Trust utility and damage to any identified and located Presidio Trust utility.
6. The contractor and Clearance Holder shall notify the Presidio Trust Permit Department a minimum of 48 hours before burying any utilities. The Permit Department will inspect the excavation to ensure the use of proper procedures and materials, including proper bedding, the use of locator tape and tracer wire, that there is no deteriorous material in the bedding or backfill material, and that proper compaction of the backfill is obtained.
7. Contractor and / or Clearance Holder will be responsible to comply with OSHA Excavation Standards, as contained in 29 CFR, Parts 1926.650 through 1926.652.


NOTICE: EXCAVATION CLEARANCE IS ONLY AND INDICATION OF THE LOCATION OF UTILITIES IN THE IDENTIFIED EXCAVATION AREA. NO EXCAVATION OR GROUND BREAKING OF ANY KIND IS PERMITTED ANYWHERE AT THE PRESIDIO UNTIL THE APPLICANT HAS RECEIVED THIS CLEARANCE AND PROJECT REVIEW APPROVAL IF WARRANTED.

FOR URGENT MATTERS ONCE AN EXCAVATION HAS BEGUN, THE EXCAVATION CLEARANCE OFFICIAL CAN BE REACHED AT 415-760-0918.

PLEASE REVIEW RESOURCE PROTECTION COMMENTS ON PAGE 2 OF THIS CLEARANCE.

12-4-08

Date


Clearance Holder (Please Sign Here After Reading Instructions)



EXCAVATION CLEARANCE

Notes / Comments to Clearance Holder: Doyle Drive (Dig Permit No.1) Environmental Borings

UTILITIES:

CONTRACTOR IS RESPONSIBLE FOR CALLING IN U.S.A.

Anthony Carrillo

11-25-08

Utility Department Excavation

Date

ARCHAEOLOGY / HISTORIC PRESERVATION:

This project was reviewed by N2 team members and determined to have no adverse effect under Section 106 of the NHPA and determined to be consistent with a Categorical Exclusion under NEPA with the following stipulations:

- Please be aware that this is in an area of archaeological sensitivity. If any artifacts (shell, bone, ceramics), features, or other historic materials are encountered during excavation, work shall be halted immediately and Presidio Trust archaeologist Eric Blind (561-5091) will be contacted.
- CalTrans is providing an archaeological monitor for this project. CalTrans and its archaeological monitor are responsible for the professional documentation of any archaeological features or artifacts discovered in the field. Original monitoring notes, records, and photographs will be provided to Presidio Archaeology Lab Collections Manager, Liz Clevenger. All artifacts and other items collected in the field shall be turned over to the Archaeology Lab with the field notes.
- Please contact the Historic Compliance Coordinator (561-5062) or the Environmental Protection Specialist (561-2756) if there are any changes to the project.

No further NHPA or NEPA review is required.

Kerry Boutte

11-24-08

Environmental Protec. Specialist/
Historical Compliance Coordinator

Date

Archaeological Discovery Notice: If historic or archaeological remains (glass, metal, ceramic, bone, shell, etc) are found during any excavation associated with work under this dig permit, notification will be provided to the Presidio Trust Archaeologists (Eric Blind at 415-561-5091/415-850-5166 or Sannie Osborn at 415-561-5090/415-716-8519) so the discovery can be examined, recorded, and an in-field decision can be made regarding its treatment. In particular, if any human remains or associated artifacts are found, all work must stop in the vicinity of the discovery. The finds must be protected and left as found, and the designated archaeologists must be contacted immediately. (Source 43 CFR 10.4 [Inadvertent Discoveries]; 43 CFR 7.4 [Prohibited Acts and Criminal Penalties])

NATURAL RESOURCES:

For all borings:

Implement appropriate (BMPs) Best Management Practices to protect stormwater. No soil or sediment should leave the site or enter the storm drain.

If activity will be performed between January 1st and August 1st and if the project will impact vegetation taller than 8" a nesting bird survey is required. Please contact Tania Pollak for more information (561-2733)

Specific concerns:

E83- This boring is in a sensitive natural area, please coordinate with Mark Frey (561-4148)

E92- This boring is in a sensitive natural area, please coordinate with Mark Frey (561-4148)

E96 - if this boring is more than 5 feet outside of the overpass, please coordinate with Mark Frey (561-4148)

E121 - This boring is in a sensitive natural area, please coordinate with Mark Frey (561-4148)

E118- This boring is in a sensitive natural area, please coordinate with Mark Frey (561-4148)

Mark Frey

11-14-08

Natural Resources Specialist

Date

ENVIRONMENTAL REMEDIATION:

OK for environmental.

Jennifer Yata

11-13-08

Environmental Specialist

Date

FORESTRY/ROADS & GROUNDS/IRRIGATION:

I have reviewed the above referenced excavation clearance and have the following requirements:


1. Applicant shall provide, erect and maintain all lights, barriers, warning signs, and all other items as required for the proper protection of workers, residents and the public.
2. Applicant shall not remove, injure, or destroy trees or other plants without prior approval.
3. Trenching or excavating within ten (10) foot tree protection zone shall not be permitted. Hand digging within the ten (10) foot tree protection zone may be permitted with written authorization of the Forestry Manager.
4. The Applicant shall take all necessary precautions to protect existing site structures to remain. These include but are not limited to existing signs, curb and gutter, sidewalks, and paved roads, parking areas and landscape. Any damage to existing structures is the responsibility of the Applicant. The Roads Supervisor shall approve methods of repair to correct damage to existing structures. Finish treatment shall match existing.
5. Specifications for repair and replacement of asphalt or concrete removed for excavation shall be reviewed and approved by the Roads Supervisor.

Roy Blomquist

12-1-08

Forestry/Roads & Grounds Dept.

Date



EXCAVATION CLEARANCE

CLEARANCE NUMBER: 4066 USA NUMBER: Contractor Is Responsible For Calling In USA
DATE CLEARANCE ISSUED: 1/9/09 JOB #: _____
CLEARANCE EXPIRATION: ** N/A
** For extension of clearance expiration date, call Excavation Clearance Official two (2) days before clearance expiration at 415-561-5327.

CLEARANCE ISSUED TO: Cheri Page

ADDRESS: _____

CONTACT: Cheri Page

PHONE NUMBER: 707.762.5233 CELLULAR: 707.322.8625

FAX NUMBER: 707.762.5271 E-MAIL ADDRESS: cheri@baseline-env.com

LOCATION OF UTILITY / EXCAVATION: Doyle Drive Environmental Borings (Dig Permit No. 2) – Drill and sample 43 borings.

COMMENTS: CONTRACTOR IS RESPONSIBLE FOR CALLING IN U.S.A. (1.800.227.2600)

Signature of Permitting Department Official: 

MANDATORY INSTRUCTIONS FOR CLEARANCE HOLDER

1. This Excavation Clearance must be available for inspection at the excavation site at all times. Failure to maintain this Excavation Clearance is grounds to have the project halted.
2. The Presidio Trust will identify all Presidio Trust operated and maintained utilities: potable water, sanitary sewer, storm sewer, electric cable and communication lines. The location of these utilities are identified in the field with spray paint and/or flags denoting the approximate utility location on the ground surface within the excavation area. The spray paint represents approximate location of utilities, the Contractor / Clearance Holder must exercise extreme care when excavating near utilities.
3. The Contractor and/or Clearance Holder will be responsible for repair to all located and identified Presidio Trust utilities damaged during construction. Utilities shall be repaired to the satisfaction of the Presidio Trust Utility Department.
4. This Excavation Clearance permit requires the issuee to contact USA to have utilities marked and remarked as required by USA guidelines.
5. Contractor and/or Clearance Holder jointly and severally agree to defend, indemnify, and hold harmless the Presidio Trust for all costs, claims, or settlement, or actions of any kind whatsoever arising from or associated with damage to any non-Presidio Trust utility and damage to any identified and located Presidio Trust utility.
6. The Contractor and/or Clearance Holder shall notify the Presidio Trust Permit Department a minimum of 48 hours before burying any utilities. The Permit Department will inspect the excavation to ensure the use of proper procedures and materials, including proper bedding, the use of locator tape and tracer wire, that there is no deteriorious material in the bedding or backfill material, and that proper compaction of the backfill is obtained.
7. Contractor and/or Clearance Holder will be responsible to comply with OSHA Excavation Standards, as contained in 29 CFR, Parts 1926.650 through 1926.652.
8. This Excavation Clearance allows activity only within the limitation of the entry license agreement, lease agreement or development agreement.

NOTICE: EXCAVATION CLEARANCE IS ONLY AND INDICATION OF THE LOCATION OF UTILITIES IN THE IDENTIFIED EXCAVATION AREA. NO EXCAVATION OR GROUND BREAKING OF ANY KIND IS PERMITTED ANYWHERE AT THE PRESIDIO UNTIL THE APPLICANT HAS RECEIVED THIS CLEARANCE AND PROJECT REVIEW APPROVAL IF WARRANTED.

FOR URGENT MATTERS ONCE AN EXCAVATION HAS BEGUN, THE EXCAVATION CLEARANCE OFFICIAL CAN BE REACHED AT 415-760-0918.

PLEASE REVIEW RESOURCE PROTECTION COMMENTS ATTACHED TO THIS CLEARANCE.

1/12/2009
Date


Clearance Holder (Please Sign Here & Attached Review Comments After Reading Instructions)



EXCAVATION CLEARANCE

Notes / Comments to Clearance Holder: Doyle Drive Environmental Borings (Dig Permit No. 2)

UTILITIES:

CONTRACTOR IS RESPONSIBLE FOR CALLING IN U.S.A. (1.800.227.2600)

Anthony Carrillo

1-9-09 *te*

Utility Department Excavation

Date

ARCHAEOLOGY / HISTORIC PRESERVATION:

This project was reviewed by N2 team members and determined to have no adverse effect under Section 106 of the NHPA and determined to be consistent with a Categorical Exclusion under NEPA with the following stipulations:

- Please be aware that this is in an area of archaeological sensitivity. If any artifacts (shell, bone, ceramics), features, or other historic materials are encountered during excavation, work shall be halted immediately and Presidio Trust archaeologist Eric Blind (561-5091) will be contacted.
- CalTrans is providing an archaeological monitor for this project. CalTrans and its archaeological monitor are responsible for the professional documentation of any archaeological features or artifacts discovered in the field. Original monitoring notes, records, and photographs will be provided to Presidio Archaeology Lab Collections Manager, Liz Clevenger. All artifacts and other items collected in the field shall be turned over to the Archaeology Lab with the field notes.
- Please contact the Historic Compliance Coordinator (561-5062) or the Environmental Protection Specialist (561-2756) if there are any changes to the project.

No further NHPA or NEPA review is required.

Kerry Boutte

12-17-08 *te*

Environmental Protec. Specialist/
Historical Compliance Coordinator

Date

Archaeological Discovery Notice: If historic or archaeological remains (glass, metal, ceramic, bone, shell, etc) are found during any excavation associated with work under this dig permit, notification will be provided to the Presidio Trust Archaeologists (Eric Blind at 415-561-5091/415-850-5166 or Sannie Osborn at 415-561-5090/415-716-8519) so the discovery can be examined, recorded, and an in-field decision can be made regarding its treatment. In particular, if any human remains or associated artifacts are found, all work must stop in the vicinity of the discovery. The finds must be protected and left as found, and the designated archaeologists must be contacted immediately. (Source 43 CFR 10.4 [Inadvertent Discoveries]; 43 CFR 7.4 [Prohibited Acts and Criminal Penalties])

NATURAL RESOURCES:

For all borings:

Implement appropriate BMPs to protect stormwater. No soil or sediment should leave the site or enter the storm drain.

If activity will be performed between January 1st and August 1st and if the project will impact vegetation taller than 8" a nesting bird survey is required. Please contact Tania Pollak for more information (561-2733)

For E 73: Please avoid the woody vegetation in the area. If woody vegetation must be removed please call Mark Frey (760-1541).

Mark Frey

12-18-08 *te*

Natural Resources Specialist

Date

ENVIRONMENTAL REMEDIATION:

Boring locations E 45, 50, 51, 53 are located in an area of anticipated petroleum contamination. Project Manager to coordinate with Jennifer Yata prior to drilling in these locations. Also, please note the building immediately to the west of location E45 has been demolished.

Jennifer Yata

12-18-08 *te*

Environmental Specialist

Date

FORESTRY/ROADS & GROUNDS/IRRIGATION:

I have reviewed the above referenced excavation clearance and have the following requirements:

1. Applicant shall be responsible for providing a traffic control plan in consultation with the Trust Roads Supervisor (561-4122) and Trust Transportation Manager (561-5438) prior to the start of work and conduct all operations to protect the public minimize interference with roads, streets, walks, and other adjacent facilities.
2. Applicant or applicant's contractor shall erect and maintain all lights, barriers, warning signs, and all other items as required for the proper protection of workers, residents and the public at his/her sole expense.
3. Applicant shall insure that trees or other plants are not removed, injured, or destroyed without prior approval.
4. Prior to initiating any construction activity, including demolition or grading, temporary protective fencing shall be installed at any tree in the immediate vicinity of construction. Fencing is to be located a minimum of ten (10) feet from the tree trunk. If space and logistics permit, fencing shall be placed at the drip line of the tree. Fencing shall be temporary self-supporting chain link fence: 6' height, 2-inch mesh, unless otherwise approved and shall form a continuous barrier without entry points around all individual trees. The fencing shall serve as a barrier to prevent encroachment of any type of construction activity, equipment, materials storage and personnel without the permission of the Trust Forestry Manager (561-4299).
5. Trenching or excavating within ten (10) foot tree protection zone shall not be permitted. Hand digging within the ten (10) foot tree protection zone may be permitted with written authorization of the Forestry Manager.
6. The Applicant shall insure that all necessary precautions are taken to protect existing site structures to remain. These include but are not limited to existing signs, curb and gutter, sidewalks, and paved roads, parking areas, irrigation and landscape. Any damage to existing structures is the responsibility of the applicant or applicant's contractor and shall be corrected by applicant at no additional expense to the Presidio Trust. The Roads Supervisor shall approve methods of repair to correct damage to existing structures. Finish treatment shall match existing.
7. Specifications for repair and replacement of asphalt or concrete removed for excavation shall be reviewed and approved by the Roads Supervisor.
8. All litter and debris shall be confined to the construction site and shall be placed in receptacles, trash cans, and/or dumpsters provided by applicant or applicant's contractor. Applicant or applicant's contractor shall be responsible for the daily clean-up of debris that blows from the construction site to adjacent areas.
9. Applicant shall provide a on site contact number to the Roads Supervisor including a number for after hours emergencies.
10. Applicant shall insure that work sites are left in a clean and safe condition after each days work and at the end of the project.

Roy Blomquist

1-7-09



Forestry/Roads & Grounds Dept.

Date



EXCAVATION CLEARANCE

CLEARANCE NUMBER: 5012 USA NUMBER: Contractor Is Responsible For Calling In USA
DATE CLEARANCE ISSUED: 4/6/09 JOB #:
CLEARANCE EXPIRATION: ** N/A
** For extension of clearance expiration date, call Excavation Clearance Official two (2) days before clearance expiration at 415-561-5327.

CLEARANCE ISSUED TO: Ray Boyer or Cheri Page
ADDRESS:

CONTACT: Cheri Page
PHONE NUMBER: 707.762.5233 CELLULAR: 707.322.8625
FAX NUMBER: 707.762.5271 E-MAIL ADDRESS: cheri@baseline-env.com

LOCATION OF UTILITY / EXCAVATION: Doyle Drive Environmental Borings - Drill and sample 48 borings (Dig Permit No. #3).

COMMENTS: MUST HAND DIG NEAR ANY MARKED UTILITY. CONTRACTOR IS RESPONSIBLE FOR CALLING IN U.S.A. NOTE: BORING "E2" MUST EITHER BE RELOCATED OR OTHERWISE HAND DUG SO THAT ALL UTILITIES IN AREA ARE EXPOSED PRIOR TO DRILLING.

Signature of Permitting Department Official: [Handwritten Signature]

MANDATORY INSTRUCTIONS FOR CLEARANCE HOLDER

- 1. This Excavation Clearance must be available for inspection at the excavation site at all times. Failure to maintain this Excavation Clearance is grounds to have the project halted.
2. The Presidio Trust will identify all Presidio Trust operated and maintained utilities: potable water, sanitary sewer, storm sewer, electric cable and communication lines. The location of these utilities are identified in the field with spray paint and/or flags denoting the approximate utility location on the ground surface within the excavation area. The spray paint represents approximate location of utilities, the Contractor / Clearance Holder must exercise extreme care when excavating near utilities.
3. The Contractor and/or Clearance Holder will be responsible for repair to all located and identified Presidio Trust utilities damaged during construction. Utilities shall be repaired to the satisfaction of the Presidio Trust Utility Department.
4. This Excavation Clearance permit requires the issuee to contact USA to have utilities marked and remarked as required by USA guidelines.
5. Contractor and/or Clearance Holder jointly and severally agree to defend, indemnify, and hold harmless the Presidio Trust for all costs, claims, or settlement, or actions of any kind whatsoever arising from or associated with damage to any non-Presidio Trust utility and damage to any identified and located Presidio Trust utility.
6. The Contractor and/or Clearance Holder shall notify the Presidio Trust Permit Department a minimum of 48 hours before burying any utilities. The Permit Department will inspect the excavation to ensure the use of proper procedures and materials, including proper bedding, the use of locator tape and tracer wire, that there is no deteriorious material in the bedding or backfill material, and that proper compaction of the backfill is obtained.
7. Contractor and/or Clearance Holder will be responsible to comply with OSHA Excavation Standards, as contained in 29 CFR, Parts 1926.650 through 1926.652.
8. This Excavation Clearance allows activity only within the limitation of the entry license agreement, lease agreement or development agreement.

NOTICE: EXCAVATION CLEARANCE IS ONLY AND INDICATION OF THE LOCATION OF UTILITIES IN THE IDENTIFIED EXCAVATION AREA. NO EXCAVATION OR GROUND BREAKING OF ANY KIND IS PERMITTED ANYWHERE AT THE PRESIDIO UNTIL THE APPLICANT HAS RECEIVED THIS CLEARANCE AND PROJECT REVIEW APPROVAL IF WARRANTED.

FOR URGENT MATTERS ONCE AN EXCAVATION HAS BEGUN, THE EXCAVATION CLEARANCE OFFICIAL CAN BE REACHED AT 415-760-0918.

PLEASE REVIEW RESOURCE PROTECTION COMMENTS ATTACHED TO THIS CLEARANCE.

4/7/2009 Date Clearance Holder (Please Sign Here & Attached Review Comments after Reading Instructions)

Unexploded ordnances have been found within the Presidio. Please take all necessary precautions and consult the Trust's Environmental Health and Safety Officer at 415.561.4141.



EXCAVATION CLEARANCE

Notes / Comments to Clearance Holder: **Doyle Drive Environmental Borings (Dig Permit No. #3)**

UTILITIES:

MUST HAND DIG NEAR ANY MARKED UTILITIES. CONTRACTOR IS RESPONSIBLE FOR CALLING IN U.S.A.

NOTE: BORING "E2" MUST EITHER BE RELOCATED OR OTHERWISE HAND DUG SO THAT ALL UTILITIES IN AREA ARE EXPOSED PRIOR TO DRILLING.

Anthony Carillo

4-6-09

Utility Department Excavation

Date

ARCHAEOLOGY / HISTORIC PRESERVATION:

This project was reviewed by N² team members and was determined to have no adverse effect under Section 106 of the NHPA and to be consistent with a Categorical Exclusion under NEPA with the following stipulations for excavation:

- Please be aware that this is an area of archaeological sensitivity. If any artifacts (shell, bone, ceramics, charcoal), features, or other historic materials are encountered during excavation, work shall be halted immediately, and Presidio Trust archaeologists Eric Blind (561-5091) or Liz Clevenger (561-5086) will be contacted.
- CalTrans will continue to provide an archaeological monitor for this project. Original monitoring notes, records, and photographs will be provided to Presidio Archaeology Lab Collections Manager, Liz Clevenger. All artifacts and other items collected in the field are property of the Presidio Trust and shall be turned over to the Archaeology Lab with the field notes. CalTrans and its archaeological monitor are responsible for the professional documentation of any archaeological features or artifacts discovered in the field.
- Please contact the Historic Compliance Coordinator (561-5062) or Environmental Protection Specialist (561-2756) if there are any changes to the project.

No further NHPA or NEPA review is required.

Kerry Boutte

3-30-09

Environmental Protec. Specialist/

Date

Historical Compliance Coordinator

Archaeological Discovery Notice: If historic or archaeological remains (glass, metal, ceramic, bone, shell, etc) are found during any excavation associated with work under this dig permit, notification will be provided to the Presidio Trust Archaeologists (Eric Blind at 415-561-5091/415-850-5166) so the discovery can be examined, recorded, and an in-field decision can be made regarding its treatment. In particular, if any human remains or associated artifacts are found, all work must stop in the vicinity of the discovery. The finds must be protected and left as found, and the designated archaeologists must be contacted immediately.

(Source 43 CFR 10.4 [Inadvertent Discoveries]; 43 CFR 7.4 [Prohibited Acts and Criminal Penalties])

NATURAL RESOURCES:

Implement appropriate Best Management Practices to protect stormwater. No soil or sediment should leave the site or enter the storm drain.

If activity will be performed between January 1st and August 1st and if the project will impact vegetation taller than 8" a nesting bird survey may be required. Please contact Tania Pollak for more information (561-2733)

Mark Frey

3-30-09

Natural Resources Specialist

Date

ENVIRONMENTAL REMEDIATION:

OK for environmental. Please note that there might be an unidentified subsurface metal tank/utility/structure in the vicinity of boring locations E28 and E29. If petroleum impacted soil is observed, please contact Jennifer Yata immediately at 415-760-1865.

Jennifer Yata

3-27-09

Environmental Specialist

Date

FORESTRY/ROADS & GROUNDS/IRRIGATION:

I have reviewed the above referenced excavation clearance and have the following requirements:

1. Applicant shall be responsible for providing a traffic control plan in consultation with the Trust Roads Supervisor (561-4122) and Trust Transportation Manager (561-5438) prior to the start of work and conduct all operations to protect the public minimize interference with roads, streets, walks, and other adjacent facilities.
 2. Applicant or applicant's contractor shall erect and maintain all lights, barriers, warning signs, and all other items as required for the proper protection of workers, residents and the public at his/her sole expense.
 3. Applicant shall insure that trees or other plants are not removed, injured or destroyed without prior approval. Trees and ornamental plants which are damaged by failure to protect and abide by the intent of protection of living plant materials here in the National Park will be charged for the full replacement value of any and all such damaged plants and trees. Every plant not approved for removal must be protected from environmental damage, driving vehicles near or digging which may damage roots below or at grade and it is the responsibility of the permit holder to protect plants from all collateral damage at all times.
 4. Prior to initiating any construction activity, including demolition or grading, temporary protective fencing shall be installed at any tree in the immediate vicinity of construction. Fencing is to be located a minimum of ten (10) feet from the tree trunk. If space and logistics permit, fencing shall be placed at the drip line of the tree. Fencing shall be temporary self-supporting chain link fence: 6' height, 2-inch mesh, unless otherwise approved and shall form a continuous barrier without entry points around all individual trees. The fencing shall serve as a barrier to prevent encroachment of any type of construction activity, equipment, materials storage and personnel without the permission of the Trust Forestry Manager (561-4299).
 5. Trenching or excavating within ten (10) foot tree protection zone **shall not be permitted**. Hand digging within the ten (10) foot tree protection zone may be permitted with written authorization of the Forestry Manager.
 6. The Applicant shall insure that all necessary precautions are taken to protect existing site structures to remain. These include but are not limited to existing signs, curb and gutter, sidewalks, and paved roads, parking areas, irrigation and landscape. Any damage to existing structures is the responsibility of the applicant or applicant's contractor and shall be corrected by applicant at no additional expense to the Presidio Trust. The Grounds or Roads Supervisor shall approve methods of repair to correct damage to existing structures. Finish treatment shall match existing.
 7. Specifications for repair and replacement of asphalt or concrete removed for excavation shall be reviewed and approved by the Roads Supervisor.
 8. All litter and debris shall be confined to the construction site and shall be placed in receptacles, trash cans, and/or dumpsters provided by applicant or applicant's contractor. Applicant or applicant's contractor shall be responsible for the daily clean-up of debris that blows from the construction site to adjacent areas.
 9. Applicant shall provide a on site contact number to the Roads Supervisor including a number for after hours emergencies.
 10. Applicant shall insure that work sites are left in a clean and safe condition after each days work and at the end of the project.
- There is irrigation in the vicinity of borings E 17, E19 and E 38. Patricia Lazar (725-0031) should be contacted when these 3 borings are done.
- Dig Sites ARE EITHER ON MAINLINES OR IN CLOSE PROXCIMITRY E14, E15, E16, E17, E18, E19, E20, E21, E22, E23, E41, E39, E24, E25, E28, E10, E8, E4, E2.

Roy Blomquist / Greg Sychoff

3-26-09/3-30-09

Forestry/Roads & Grounds Dept.

Date