

DEPARTMENT OF TRANSPORTATION
DIVISION OF ENGINEERING SERVICES
OFFICE ENGINEER, MS 43
1727 30TH STREET
P.O. BOX 168041
SACRAMENTO, CA 95816-8041
FAX (916) 227-6214
TTY 711



*Flex your power!
Be energy efficient!*

November 5, 2010

04-Ala-580-R8.3
04-172424
Project ID 0400020197
IM-580-1(048)E

Addendum No. 1

Dear Contractor:

This addendum is being issued to the contract for CONSTRUCTION ON STATE HIGHWAY IN ALAMEDA COUNTY NEAR LIVERMORE EAST OF CROSS ROAD 2.2 MILES SOUTHEAST OF ROUTE 580 GREENVILLE ROAD UNDERCROSSING.

Submit bids for this work with the understanding and full consideration of this addendum. The revisions declared in this addendum are an essential part of the contract.

Bids for this work will be opened on Wednesday, November 10, 2010.

This addendum is being issued to revise the Project Plans, the Notice to Bidders and Special Provisions, the Bid book, and the Federal Minimum Wages with Modification Number 15 dated 10/29/10.

Project Plan Sheets 12 and 14 are revised. Copies of the revised sheets are attached for substitution for the like-numbered sheets.

Project Plan Sheet 3A is added. A copy of the added sheet is attached for addition to the project plans.

In the Notice to Bidders and Special Provisions, the thirteenth paragraph in the "NOTICE TO BIDDERS," is revised as follows:

"Complete the work within 90 calendar days."

In the Special Provisions, Section 10-1.01, "ORDER OF WORK," the following paragraph is added after the third paragraph:

"First order of work is to construct fence (Type BW, 5 strand, Metal Post) along Patterson Pass Road."

In the Special Provisions, Section 10-1.15, "EXISTING HIGHWAY FACILITIES," subsection "REMOVE FENCE," is added as follows:

"REMOVE FENCE

Existing fence, at those locations shown on the plans to be removed, shall be removed and disposed of.

Existing fence shall not be removed until replacement fence has been installed or until the existing fence is no longer required unless otherwise directed by the Engineer."

In the Bid book, in the "Bid Item List," Items 11 and 25 are revised as attached.

Addendum No. 1
Page 2
November 5, 2010

04-Ala-580-R8.3
04-172424
Project ID 0400020197
IM-580-1(048)E

To Bid book holders:

Replace pages 3 and 4 of the "Bid Item List" in the Bid book with the attached revised pages 3 and 4 of the Bid Item List. The revised Bid Item List is to be used in the bid.

Inquiries or questions in regard to this addendum must be communicated as a bidder inquiry and must be made as noted in the Notice to Bidders section of the Notice to Bidders and Special Provisions.

Indicate receipt of this addendum by filling in the number of this addendum in the space provided on the signature page of the Bid book.

Submit bids in the Bid book you now possess. Holders who have already mailed their book will be contacted to arrange for the return of their book.


Inform subcontractors and suppliers as necessary.

This addendum, attachments and the modified wage rates are available for the Contractors' download on the Web site:

http://www.dot.ca.gov/hq/esc/oe/project_ads_addenda/04/04-172424

If you are not a Bid book holder, but request a book to bid on this project, you must comply with the requirements of this letter before submitting your bid.

Sincerely,



BIJAN SARTIPI
District Director
For AADD projects from District 4

Attachments

BID ITEM LIST
04-172424

Item No.	Item Code	Item Description	Unit of Measure	Estimated Quantity	Unit Price	Item Total
1	071325	TEMPORARY FENCE (TYPE ESA)	LF	4,390		
2	074016	CONSTRUCTION SITE MANAGEMENT	LS	LUMP SUM	LUMP SUM	
3	074019	PREPARE STORM WATER POLLUTION PREVENTION PLAN	LS	LUMP SUM	LUMP SUM	
4	074028	TEMPORARY FIBER ROLL	LF	3,700		
5	074029	TEMPORARY SILT FENCE	LF	2,000		
6	074033	TEMPORARY CONSTRUCTION ENTRANCE	EA	1		
7	074034	TEMPORARY COVER	SQYD	1,210		
8	074040	TEMPORARY HYDRAULIC MULCH (BONDED FIBER MATRIX)	SQYD	9,680		
9	074041	STREET SWEEPING	LS	LUMP SUM	LUMP SUM	
10	074057	STORM WATER ANNUAL REPORT	EA	1		
11	150605	REMOVE FENCE	LF	5,360		
12	150805	REMOVE CULVERT	LF	43		
13	160101	CLEARING AND GRUBBING	LS	LUMP SUM	LUMP SUM	
14	170101	DEVELOP WATER SUPPLY	LS	LUMP SUM	LUMP SUM	
15	190101	ROADWAY EXCAVATION	CY	38,600		
16 (F)	019783	GEOSYNTHETIC CLAY LINER	SQYD	25,000		
17	203002	EROSION CONTROL (COMPOST BLANKET)	CY	560		
18	203021	FIBER ROLLS	LF	6,650		
19	203026	MOVE-IN/MOVE-OUT (EROSION CONTROL)	EA	2		
20	203032	EROSION CONTROL (HYDROSEED) (ACRE)	ACRE	9		

BID ITEM LIST
04-172424

Item No.	Item Code	Item Description	Unit of Measure	Estimated Quantity	Unit Price	Item Total
21	260201	CLASS 2 AGGREGATE BASE	CY	120		
22	665037	36" CORRUGATED STEEL PIPE (.109" THICK)	LF	120		
23	721008	ROCK SLOPE PROTECTION (LIGHT, METHOD B)	CY	870		
24	729010	ROCK SLOPE PROTECTION FABRIC	SQYD	1,760		
25	800007	FENCE (TYPE BW, 5 STRAND, METAL POST)	LF	7,820		
26	801130	6' WIRE MESH GATE	EA	5		
27	999990	MOBILIZATION	LS	LUMP SUM	LUMP SUM	

TOTAL BID:

\$ _____