

DEPARTMENT OF TRANSPORTATION

DIVISION OF ENGINEERING SERVICES

OFFICE ENGINEER

1727 30th Street MS-43

P.O. BOX 168041

SACRAMENTO, CA 95816-8041

FAX (916) 227-6214

www.dot.ca.gov/hq/esc/oe



*Serious Drought.
Help save water!*

June 11, 2015

04-SM-280-R0.3/M27.1
04-1G8304
Project ID 0400020615
ACHSNHPIG-2801-1(142)E

Addendum No. 2

Dear Contractor:

This addendum is being issued to the contract for CONSTRUCTION ON STATE HIGHWAY IN SAN MATEO COUNTY AT VARIOUS LOCATIONS.

Submit bids for this work with the understanding and full consideration of this addendum. The revisions declared in this addendum are an essential part of the contract.

Bids for this work will be opened on Thursday, June 18, 2015.

This addendum is being issued to revise the project plans the and *Notice to Bidders and Special Provisions*.

Project plan sheets 1 and 44 are replaced and attached for substitution for the like-numbered sheets.

Project plan sheet 74A is added and attached for addition to the project plans.

In the *Notice to Bidders and Special Provisions*, in the "STANDARD PLANS LIST," the following Standard Plans are added as follows:

"ES-13A", "RSP ES-8A"

In the *Notice to Bidders and Special Provisions*, the seventh paragraph is revised as follows:

"The Contractor must have either a Class A license or a combination of Class C licenses which constitutes a majority of the work."

In the Special Provisions, Section 86-1.01, is added as attached.

In the Special Provisions, Section 86-2.06B(1)(c)(ii) "Warranty" is replaced as follows:

"Replace Section 86-2.06B(1)(c)(ii) with the following

86-2.06B(1)(c)(ii) Warranty

Provide a 2-year manufacturer's replacement warranty for the pull box and cover. The warranty period starts on the date of Contract acceptance.

Deliver replacement parts within 5 business days after you receive notification of a failed pull box, cover, or both to the Department's Maintenance Electrical Shop at: 30 Rickard Street, San Francisco, CA, 94134."

Addendum No. 2
Page 2
June 11, 2015

04-SM-280-R0.3/M27.1
04-1G8304
Project ID 0400020615
ACHSNHPIG-2801-1(142)E

In the Special Provisions, Section 86-2.08A, is added as follows:

"Add to section 86-2.08A:

Wrap conductors around the projecting end of conduit in pull boxes as shown. Secure conductors and cables to the projecting end of the conduit in pull boxes."

In the Special Provisions, Section 86-2.08E, is added as follows:

"Replace the 1st sentence of the 1st paragraph of section 86-2.08E with:

Signal interconnect cable must be the 6-pair type with stranded tinned copper no. 20 conductors."

In the Special Provisions, Section 86-2.09E, is added as follows:

"Replace the 1st paragraph of section 86-2.09E with:

Splices must be insulated by "Method B."

Delete the 6th and 7th paragraphs of section 86-2.09E."

To *Bid* book holders:

Inquiries or questions in regard to this addendum must be communicated as a bidder inquiry and must be made as noted in the *Notice to Bidders* section of the *Notice to Bidders and Special Provisions*.

Submit the *Bid* book as described in the *Electronic Bidding Guide* at the Bidders' Exchange website.

http://www.dot.ca.gov/hq/esc/oe/electronic_bidding/electronic_bidding.html

Inform subcontractors and suppliers as necessary.

This addendum, EBS addendum file and attachments are available for the Contractors' download on the Web site:

http://www.dot.ca.gov/hq/esc/oe/project_ads_addenda/04/04-1G8304

If you are not a *Bid* book holder, but request a book to bid on this project, you must comply with the requirements of this letter before submitting your bid.

Sincerely,



BIJAN SARTIPI
District Director

Attachments

Add to the end of the 1st paragraph of section 86-1.01:

This work is shown on plan sheets labeled E . The work involved in each bid item is shown on a sheet with a title matching the bid item description except for the following bid items:

1. Maintaining the existing traffic management system during construction

Lighting equipment is included in the following structures:

1. Route 1/280 Sep Tunnel 35-0173L
2. Edgewood Road UC 35-0250L and R

Communication conduit is included in the following structures:

1. Route 1/280 Sep Tunnel 35-0173L