**** WARNING ** WARNING ** WARNING ** WARNING ****
This document is intended for informational purposes only.

Users are cautioned that California Department of Transportation (Department) does not assume any liability or responsibility based on these electronic files or for any defective or incomplete copying, exerpting, scanning, faxing or downloading of the contract documents. As always, for the official paper versions of the bidders packages and non-bidder packages, including addenda write to the California Department of Transportation, Plans and Bid Documents, Room 0200, P.O. Box 942874, Sacramento, CA 94272-0001, telephone (916) 654-4490 or fax (916) 654-7028. Office hours are 7:30 a.m. to 4:15 p.m. When ordering bidder or non-bidder packages it is important that you include a telephone number and fax number, P.O. Box and street address so that you can receive addenda.

STATE OF CALIFORNIA

DEPARTMENT OF TRANSPORTATION

NOTICE TO CONTRACTORS

AND

SPECIAL PROVISIONS

FOR CONSTRUCTION ON STATE HIGHWAY IN

THE CITY AND COUNTY OF SAN FRANCISCO FROM SOUTH VAN NESS AVENUE TO MARKET STREET ON THE CENTRAL FREEWAY

DISTRICT 04, ROUTE 101

For Use in Connection with Standard Specifications Dated JULY 1999, Standard Plans Dated JULY 1999, and Labor Surcharge and Equipment Rental Rates.

CONTRACT NO. 04-291004

04-SF-101-R 8.0/R 8.5

Federal Aid Project

ACNH-Q101(049)E

Bids Open: September 3, 2003
Dated: July 14, 2003

OSD

****

IMPORTANT SPECIAL NOTICES

****

- A+B BIDDING SPECIAL NOTICE

The bidder's attention is directed to Section 2, "Proposal Requirements and Conditions," Section 3, "Award and Execution of Contract," and Section 4, "Beginning of Work, Time of Completion and Liquidated Damages," in the special provisions. In addition to the item prices and totals, the proposal shall set forth the number of working days bid to complete the work on the contract, except plant establishment. Bids will be compared on the basis of the sum of the item totals on the Engineer's Estimate for the work to be done (TOTAL BID (A)), plus the product of the number of working days bid to complete the work, except plant establishment, and the cost per day shown on the Engineer's Estimate (TOTAL BID (B)). The lowest bid will be determined on the basis of the "Total Basis for Comparison of Bids (A+B)" set forth in the Engineer's Estimate.

Bids in which the number of working days bid for completion of the work, except plant establishment, exceed the maximum number of days specified will be considered non-responsive and will be rejected.

- DBEs must be certified by the California Unified Certification Program (CUCP). See Section 2, "Proposal Requirements and Conditions," of these special provisions for further details. The available sources for identifying certified DBEs have also been revised.

- The time allotted for the successful bidder to execute the contract and return it, together with the contract bonds, to the Department, has been revised. See Section 3, "Award and Execution of Contract," of these special provisions. Additional time will no longer be granted for return of the executed documents.

TABLE OF CONTENTS

NOTICE TO CONTRACTORS 1
COPY OF ENGINEER'S ESTIMATE 3
SPECIAL PROVISIONS 10
SECTION 1. SPECIFICATIONS AND PLANS 10
AMENDMENTS TO JULY 1999 STANDARD SPECIFICATIONS 10
SECTION 2. PROPOSAL REQUIREMENTS AND CONDITIONS 54
2-1.01 GENERAL 54
2-1.015 FEDERAL LOBBYING RESTRICTIONS 54
2-1.02 DISADVANTAGED BUSINESS ENTERPRISE (DBE) 55
2-1.02A DBE GOAL FOR THIS PROJECT 56
2-1.02B SUBMISSION OF DBE INFORMATION 57
SECTION 3. AWARD AND EXECUTION OF CONTRACT 58
SECTION 4. BEGINNING OF WORK, TIME OF COMPLETION AND LIQUIDATED DAMAGES 58
SECTION 5. GENERAL 59
SECTION 5-1. MISCELLANEOUS 59
5-1.01 PLANS AND WORKING DRAWINGS 59
5-1.011 EXAMINATION OF PLANS, SPECIFICATIONS, CONTRACT, AND SITE OF WORK 59
5-1.012 DIFFERING SITE CONDITIONS 59
5-1.013 LINES AND GRADES 59
5-1.015 LABORATORY 59
5-1.017 CONTRACT BONDS 59
5-1.019 COST REDUCTION INCENTIVE 59
5-1.02 LABOR NONDISCRIMINATION 60
5-1.022 PAYMENT OF WITHHELD FUNDS 60
5-1.03 INTEREST ON PAYMENTS 60
5-1.04 PUBLIC SAFETY 60
5-1.05 TESTING 61
5-1.06 REMOVAL OF ASBESTOS AND HAZARDOUS SUBSTANCES 62
5-1.07 YEAR 2000 COMPLIANCE 62
5-1.075 BUY AMERICA REQUIREMENTS 62
5-1.08 SUBCONTRACTOR AND DBE RECORDS 62
5-1.083 DBE CERTIFICATION STATUS 63
5-1.086 PERFORMANCE OF DBE SUBCONTRACTORS AND SUPPLIERS 63
5-1.09 SUBCONTRACTING 63
5-1.10 PROMPT PROGRESS PAYMENT TO SUBCONTRACTORS 64
5-1.102 PROMPT PAYMENT OF WITHHELD FUNDS TO SUBCONTRACTORS 64
5-1.103 RECORDS 64
5-1.11 PARTNERING 64
5–1.114 VALUE ANALYSIS 65
5-1.12 DISPUTE REVIEW BOARD 65
5-1.13 FORCE ACCOUNT PAYMENT 75
5-1.14 AREAS FOR CONTRACTOR'S USE 76
5-1.15 PAYMENTS 76
5-1.16 SOUND CONTROL REQUIREMENTS 76
5-1.17 PROJECT APPEARANCE 77
5-1.18 HAZARDOUS AND NON-HAZARDOUS MATERIAL, GENERAL 77
APPLICABLE RULES AND REGULATIONS 78
PERMITS AND LICENSES 78
SAMPLING AND ANALYSIS 78
MEASUREMENT AND PAYMENT 78
5-1.19 HEALTH, SAFETY AND WORK PLAN 78
SAFETY 79
MEASUREMENT AND PAYMENT 79

SECTION 6. (BLANK) 79
SECTION 7. (BLANK) 79
SECTION 8. MATERIALS 79
SECTION 8-1. MISCELLANEOUS 79
8-1.01 SUBSTITUTION OF NON-METRIC MATERIALS AND PRODUCTS 79
8-1.02 PREQUALIFIED AND TESTED SIGNING AND DELINEATION MATERIALS 85
8-1.03 STATE-FURNISHED MATERIALS 90
8-1.04 ENGINEERING FABRICS 91
SECTION 8-2. CONCRETE 91
8-2.01 PORTLAND CEMENT CONCRETE 91
SECTION 8-3. WELDING 92
8-3.01 WELDING 92
GENERAL 92
WELDING QUALITY CONTROL 94
PAYMENT 96
SECTION 9. DESCRIPTION OF BRIDGE WORK 96
SECTION 10. CONSTRUCTION DETAILS 97
SECTION 10-1. GENERAL 97
10-1.01 ORDER OF WORK 97
10-1.02 PHOTO SURVEY OF EXISTING FACILITIES 98
10-1.03 VIBRATION MONITORING 99
LOCATION OF VIBRATION MONITORING AND PHOTO SURVEY 99
GENERAL 100
VIBRATION MONITORING PERSONNEL 100
VIBRATION MONITORING SUBMITTALS 100
VIBRATION MONITORING EQUIPMENT 101
VIBRATION MONITORING 101
DATA COLLECTION 102
DATA REDUCTION, PROCESSING, PLOTTING AND REPORTING 102
PAYMENT 102
10-1.04 SEWER VIDEO SURVEY 102
10-1.05 WATER POLLUTION CONTROL 103
RETENTION OF FUNDS 104
STORM WATER POLLUTION PREVENTION PLAN PREPARATION, APPROVAL AND AMENDMENTS 105
COST BREAK-DOWN 106
SWPPP IMPLEMENTATION 108
MAINTENANCE 109
REPORTING REQUIREMENTS 109
SAMPLING AND ANALYTICAL REQUIREMENTS 110
PAYMENT 111
10-1.06 TEMPORARY MULCH 112
MATERIALS 112
APPLICATION 112
MEASUREMENT AND PAYMENT 112
10-1.07 TEMPORARY COVER 113
MATERIALS 113
INSTALLATION 114
MAINTENANCE 114
MEASUREMENT AND PAYMENT 114
10-1.08 TEMPORARY CONCRETE WASHOUT FACILITY 114
MATERIALS 115
INSTALLATION 115
MAINTENANCE 116
MEASUREMENT AND PAYMENT 116
10-1.09 TEMPORARY FENCE 116
10-1.10 PRESERVATION OF PROPERTY 116
10-1.11 TEMPORARY CONSTRUCTION ENTRANCE 117

MATERIALS 117
INSTALLATION 118
MAINTENANCE 118
MEASUREMENT AND PAYMENT 118
10-1.12 TEMPORARY DRAINAGE INLET PROTECTION 119
MATERIALS 119
INSTALLATION AND MAINTENANCE 120
MEASUREMENT AND PAYMENT 120
10-1.13 DAMAGE REPAIR 121
10-1.14 RELIEF FROM MAINTENANCE AND RESPONSIBILITY 121
10-1.15 SCAFFOLDING 121
10-1.16 COOPERATION 122
10-1.17 PROGRESS SCHEDULE (CRITICAL PATH METHOD) 122
DEFINITIONS 122
GENERAL REQUIREMENTS 122
COMPUTER SOFTWARE 124
NETWORK DIAGRAMS, REPORTS AND DATA 124
PRE-CONSTRUCTION SCHEDULING CONFERENCE 125
BASELINE SCHEDULE 125
UPDATE SCHEDULE 126
TIME IMPACT ANALYSIS 126
FINAL UPDATE SCHEDULE 126
RETENTION 126
PAYMENT 127
10-1.18 TIME-RELATED OVERHEAD 127
10-1.19 OBSTRUCTIONS 129
10-1.20 DUST CONTROL 131
AIR QUALITY REQUIREMENTS 131
10-1.21 MOBILIZATION 131
10-1.22 BRIDGE CONSTRUCTION SURVEYING 131
STATE FURNISHED SURVEY CONTROL STAKES 132
MEASUREMENT AND PAYMENT 133
10-1.23 CONSTRUCTION AREA TRAFFIC CONTROL DEVICES 133
10-1.24 CONSTRUCTION AREA SIGNS 133
10-1.25 MAINTAINING TRAFFIC 134
CITY OF SAN FRANCISCO TRAFFIC LANE, PEDESTRIAN WALKWAY AND PARKING REQUIREMENTS 136
10-1.26 CLOSURE REQUIREMENTS AND CONDITIONS 141
CLOSURE SCHEDULE 141
CONTINGENCY PLAN 141
LATE REOPENING OF CLOSURES 141
LATE RE-OPENING OF LOCAL CITY STREET 142
COMPENSATION 142
10-1.27 TRAFFIC CONTROL SYSTEM FOR LANE CLOSURE 142
STATIONARY LANE CLOSURE 142
MOVING LANE CLOSURE 143
PAYMENT 143
10-1.28 TEMPORARY PAVEMENT DELINEATION 144
GENERAL 144
TEMPORARY LANELINE AND CENTERLINE DELINEATION 144
TEMPORARY EDGELINE DELINEATION 144
TEMPORARY TRAFFIC STRIPE (PAINT) 145
TEMPORARY PAVEMENT MARKING (PAINT) 145
TEMPORARY PAVEMENT MARKERS 145
MEASUREMENT AND PAYMENT 146
10-1.29 BARRICADE 146
10-1.30 PORTABLE CHANGEABLE MESSAGE SIGN 146
10-1.31 TEMPORARY RAILING 147

10-1.32 CHANNELIZER....147
10-1.33 PORTABLE DELINEATORS....147
10-1.34 TEMPORARY CRASH CUSHION MODULE....147
10-1.35 TEMPORARY CRASH CUSHION (QUADGUARD)....148
10-1.36 EXISTING HIGHWAY FACILITIES....149
EXISTING PAINT SYSTEMS....149
ABANDON CULVERT....152
ABANDON INLET....153
REMOVE FENCE....153
REMOVE CHANNELIZERS....153
REMOVE CRASH CUSHION (SAND FILLED)....153
REMOVE PAVEMENT MARKER....153
REMOVE TRAFFIC STRIPE AND PAVEMENT MARKING....153
REMOVE DRAINAGE FACILITY....154
REMOVE ROADSIDE SIGN AND SIGN OVERLAY....155
RECONSTRUCT CHAIN LINK FENCE....155
ADJUST MANHOLE....155
REMOVE BASE AND SURFACING....155
REMOVE ASPHALT CONCRETE SURFACING....155
COLD PLANE ASPHALT CONCRETE PAVEMENT....155
EXISTING HIGHWAY IRRIGATION FACILITIES....156
BRIDGE REMOVAL....156
REMOVE CONCRETE....158
REMOVE CONCRETE BARRIER (TYPE K)....158
10-1.37 CLEARING AND GRUBBING....158
10-1.38 EARTHWORK....158
10-1.39 HAZARDOUS AND NON-HAZARDOUS MATERIAL EXCAVATION....159
MEASUREMENT AND PAYMENT....160
10-1.40 DEWATERING....161
MATERIALS....162
MONITORING....162
MEASUREMENT AND PAYMENT....162
10-1.41 CONTROLLED LOW STRENGTH MATERIAL....163
10-1.42 FIBER ROLLS....163
MATERIALS....164
INSTALLATION....164
MEASUREMENT AND PAYMENT....164
10-1.43 DRAIN INLET PROTECTION....164
MATERIALS....164
INSTALLATION....165
MEASUREMENT AND PAYMENT....165
10-1.44 AGGREGATE SUBBASE....165
10-1.45 AGGREGATE BASE (CLASS 2)....166
10-1.46 AGGREGATE BASE (CLASS 3)....166
10-1.47 ASPHALT CONCRETE....167
10-1.48 PORTLAND CEMENT CONCRETE BASE....167
10-1.49 PILING....168
GENERAL....168
CAST-IN-DRILLED-HOLE CONCRETE PILES....168
MEASUREMENT AND PAYMENT (PILING)....178
10-1.50 PRESTRESSING CONCRETE....179
10-1.51 CONCRETE STRUCTURES....179
GENERAL....179
FALSEWORK....179
DECK CRACK TREATMENT....180
MEASUREMENT AND PAYMENT....182
10-1.52 PTFE BEARING....182
CLEANING....184

PAINTING 184
10-1.53 PTFE SPHERICAL BEARING 186
10-1.54 STRUCTURE APPROACH SLABS (TYPE N) 189
GENERAL 189
STRUCTURE APPROACH DRAINAGE SYSTEM 189
ENGINEERING FABRICS 189
TREATED PERMEABLE BASE UNDER APPROACH SLAB 190
APPROACH SLABS 190
JOINTS 191
MEASUREMENT AND PAYMENT 191
10-1.55 SEALING JOINTS 191
10-1.56 JOINT SEAL ASSEMBLIES (MAXIMUM MOVEMENT RATING, 100 MM) 191
CLEANING 192
PAINTING 192
ALTERNATIVE JOINT SEAL ASSEMBLY 193
10-1.57 SEISMIC JOINT ASSEMBLY (MOVEMENT RATING EXCEEDING 100 MM) 194
CLEANING 195
PAINTING 195
10-1.58 REFINISHING BRIDGE DECKS 196
PORTLAND CEMENT CONCRETE 197
RAPID SETTING CONCRETE 197
FINISHING REQUIREMENTS 198
MEASUREMENT AND PAYMENT 198
10-1.59 ARCHITECTURAL FINISH (EXPOSED AGGREGATE) 198
TEST PANEL 198
CURING 198
MEASUREMENT AND PAYMENT 199
10-1.60 ARCHITECTURAL SURFACE (TEXTURED CONCRETE) 199
TEST PANEL 199
FORM LINERS 199
RELEASING FORM LINERS 200
CURING 200
MEASUREMENT AND PAYMENT 200
10-1.61 COLORED CONCRETE 200
10-1.62 MINOR CONCRETE (PIPE COVER) 201
10-1.63 REINFORCEMENT 201
ULTIMATE BUTT SPLICES 201
SERVICE BUTT SPLICES 205
MEASUREMENT AND PAYMENT 207
10-1.64 STEEL STRUCTURES 208
GENERAL 208
MATERIALS 208
TEMPORARY FALSEWORK TOWERS 208
CHECK TESTING 208
ROTATIONAL CAPACITY TESTING PRIOR TO SHIPMENT TO JOB SITE 209
INSTALLATION TENSION TESTING AND ROTATIONAL CAPACITY TESTING AFTER ARRIVAL ON THE JOB SITE 213
SURFACE PREPARATION 213
SEALING 213
WELDING 213
CURVED GIRDERS 213
MEASUREMENT AND PAYMENT 214
10-1.65 ROADSIDE SIGNS 214
10-1.66 INSTALL SIGN PANEL ON EXISTING FRAME 215
10-1.67 CLEAN AND PAINT STRUCTURAL STEEL 215
CLEANING 215
PAINTING 216
MEASUREMENT AND PAYMENT 217

10-1.68 ALTERNATIVE PIPE....217
10-1.69 PLASTIC PIPE....217
10-1.70 REINFORCED CONCRETE PIPE....217
10-1.71 PLASTIC PIPE....218
10-1.72 WELDED STEEL PIPE....218
10-1.73 MISCELLANEOUS CONCRETE CONSTRUCTION....218
10-1.74 MISCELLANEOUS IRON AND STEEL....218
10-1.75 MISCELLANEOUS METAL (BRIDGE)....218
10-1.76 CONCRETE BARRIER....219
10-1.77 CRASH CUSHION (ADIEM)....219
10-1.78 CRASH CUSHION, SAND FILLED....220
10-1.79 THERMOPLASTIC TRAFFIC STRIPE AND PAVEMENT MARKING....220
10-1.80 PAINT TRAFFIC STRIPE AND PAVEMENT MARKING....221
10-1.81 PAVEMENT MARKERS....221
SECTION 10-2. HIGHWAY PLANTING AND IRRIGATION SYSTEMS....221
10-2.01 GENERAL....221
PROGRESS INSPECTIONS....222
COST BREAK-DOWN....222
10-2.02 (BLANK)....225
10-2.03 (BLANK)....225
10-2.04 HIGHWAY PLANTING....225
HIGHWAY PLANTING MATERIALS....225
ROADSIDE CLEARING....225
PESTICIDES....226
PREPARING PLANTING AREAS....226
PREPARE HOLES....226
PLANTING....226
PALM TREE PLANTING....226
PLANTING....227
STREET TREE PLANTING....227
PLANT ESTABLISHMENT WORK....228
10-2.05 IRRIGATION SYSTEMS....228
VALVE BOXES....229
ELECTRIC AUTOMATIC IRRIGATION COMPONENTS....229
ARMOR-CLAD CONDUCTORS....230
IRRIGATION SYSTEMS FUNCTIONAL TEST....230
PIPE....230
IRRIGATION CONDUIT....231
WATER METER....231
BACKFLOW PREVENTER ASSEMBLIES....231
BACKFLOW PREVENTER ASSEMBLY ENCLOSURE....231
TESTING BACKFLOW PREVENTERS....232
SPRINKLERS....232
WYE STRAINERS....232
FINAL IRRIGATION SYSTEM CHECK....232
SECTION 10-3. SIGNALS, LIGHTING AND ELECTRICAL SYSTEMS....232
10-3.01 DESCRIPTION....232
10-3.02 COST BREAK-DOWN....233
10-3.03 ABBREVIATIONS....233
10-3.04 FOUNDATIONS....233
10-3.05 STANDARDS, STEEL PEDESTALS AND POSTS....233
10-3.06 CONDUIT....233
10-3.07 PULL BOXES....234
10-3.08 CABLES, CONDUCTORS AND WIRING....234
10-3.09 CLOSED CIRCUIT TELEVISION CABLES....234
COAXIAL CABLE CONNECTORS (TVL COAXIAL CABLES)....236
TESTING....236
10-3.10 TELEPHONE CABLE....236

10-3.11 BONDING AND GROUNDING 237
10-3.12 SERVICE 237
ELECTRIC SERVICE (IRRIGATION) 237
10-3.13 NUMBERING ELECTRICAL EQUIPMENT 237
10-3.14 STATE-FURNISHED CONTROLLER ASSEMBLIES 237
10-3.15 IRRIGATION CONTROLLER ENCLOSURE CABINET 238
10-3.16 TELEPHONE DEMARCATION CABINET 238
10-3.17 FLASHING BEACONS 239
10-3.18 DETECTORS 239
PREFORMED INDUCTIVE LOOPS 239
10-3.19 LUMINAIRES 239
10-3.20 PHOTOELECTRIC CONTROLS 239
10-3.21 EXTINGUISHABLE MESSAGE SIGN 239
HOUSING 239
BALLASTS, CONTROL RELAYS AND TERMINAL BLOCKS 240
LAMPHOLDERS AND LAMPS 240
CONDUCTORS AND WIRING 240
LUG DISCONNECT 240
TESTING 240
SIGN OPERATION 241
10-3.22 CAMERA UNIT 241
CAMERA 241
LENS 243
ENVIRONMENTAL HOUSING 243
CAMERA UNIT CABLE ASSEMBLY 244
10-3.23 PAN/TILT UNIT 245
General 245
Electrical 245
Mechanical 245
Environmental 245
Pan and tilt unit mounting 246
10-3.24 CAMERA JUNCTION BOX 246
10-3.25 CAMERA CONTROL UNIT 246
General 246
Mechanical 246
Electrical 247
Environmental 249
CCU messages 250
Serial communications protocol 250
10-3.26 VIDEO ENCODER UNIT 251
General 251
Acceptable equipment 251
Qualifying specifications 251
Accessory items 253
10-3.27 INTEGRATED SERVICES DIGITAL NETWORK TERMINAL ADAPTER UNIT 253
General 253
Qualifying specifications 253
10-3.28 CAMERA STATION 254
GENERAL 254
CABLES AND CONNECTORS 254
INSTALLATION OF CAMERA STATION 255
CAMERA UNIT MOUNTING 255
CAMERA STATION TESTING 255
10-3.29 CAMERA POLES 256
10-3.30 CELLULAR DIGITAL PACKET DATA WIRELESS MODEM 256
MODEM 256
POWER SUPPLY 259
MODEM MOUNTING BRACKET AND HARDWARE 260

D SERIAL COMMUNICATION CABLE 260
ANTENNA 260
10-3.31 SERVICE MANUAL REQUIREMENTS 260
General information section 260
Theory of operations section 261
Maintenance section 261
Replacement parts section 261
Diagram section 261
Physical requirements 261
10-3.32 TRAFFIC OPERATIONS SYSTEM EQUIPMENT TESTING 261
10-3.33 CITY OF SAN FRANCISCO ELECTRICAL SPECIAL PROVISIONS 261
MAINTAINING EXISTING CITY TRAFFIC SIGNAL AND STREET LIGHTING SYSTEMS 261
FOUNDATIONS 262
CONDUIT 262
PULL BOXES 263
CONDUCTORS AND WIRING 264
BONDING AND GROUNDING 264
SIGNAL MOUNTING ASSEMBLIES 264
SIGNAL POLES 265
STREET LIGHTING 265
DELIVERY OF SALVAGED EQUIPMENT TO CITY YARDS 265
DAMAGE TO WORK OR PROPERTY 266
CORRECTION OF DEFECTS AFTER ACCEPTANCE 266
PROGRESS SCHEDULE 267
EXTENSIONS OF TIME ALLOWED FOR COMPLETION OF WORK 267
WORK AT UTILITY FACILITIES 267
FLAGMAN 268
CLASSES OF CONCRETE 268
10-3.34 REMOVING, REINSTALLING OR SALVAGING ELECTRICAL EQUIPMENT 268
10-3.35 PAYMENT 268
SECTION 10-4. CITY OF SAN FRANCISCO SPECIAL PROVISIONS 269
10-4.01 TRAFFIC CONTROL BY UNIFORMED OFF-DUTY SAN FRANCISCO POLICE OFFICER 269
10-4.02 VITRIFIED CLAY PIPE 270
10-4.03 SAN FRANCISCO CATCH BASIN 270
10-4.04 SAN FRANCISCO MANHOLE 271
10-4.05 GRANITE CURB 271
PART 1 - GENERAL 271
RELATED CITY OF SAN FRANCISCO SECTIONS 271
REFERENCES 272
SUBMITTALS 272
QUALITY ASSURANCE 272
DELIVERY, STORAGE, AND HANDLING 272
PART 2 - PRODUCTS 273
MATERIALS 273
ACCESSORIES 274
STONE FABRICATION AND REUSE 274
PART 3 - EXECUTION 274
MIXES 274
SETTING 275
DOWELS 275
CLEANING 275
PROTECTION OF FINISHED WORK 275
DEFECTIVE WORK 276
MEASUREMENT AND PAYMENT 276
10-4.06 MANUFACTURED STONE PAVING 276
PART 1 - GENERAL 276
RELATED CITY OF SAN FRANCISCO SECTIONS 276
REFERENCE 276

SUBMITTALS....276
QUALITY ASSURANCE....277
PROJECT SITE CONDITIONS....277
MOCK-UP....277
WARRANTY....277
PRODUCT DELIVERY, STORAGE AND HANDLING....277
MAINTENANCE....277
COORDINATION....278
PART 2 - PRODUCTS....278
STONE PAVERS....278
PART 3 - EXECUTION....279
FIELD QUALITY CONTROL....279
INSTALLATION....279
PROTECTION....280
REPAIR AND REPLACEMENT....280
MEASUREMENT AND PAYMENT....280
10-4.07 BRICK SIDEWALK....280
PART 1 - GENERAL....280
RELATED CITY OF SAN FRANCISCO SECTIONS....280
REFERENCES....280
SUBMITTALS....281
MOCK-UPS....281
QUALITY ASSURANCE....282
MAINTENANCE....282
PART 2 - PRODUCTS....282
BRICKS....282
EXPANSION JOINT MATERIALS....283
MORTAR....283
CONCRETE BASE....283
PART 3 - EXECUTION....283
FIELD QUALITY CONTROL....283
INSTALLATION....284
MIXES....284
EXPANSION JOINT LOCATIONS....284
EXPANSION JOINT INSTALLATION....285
MORTAR PROPORTIONING AND MIXING....285
FRAMES AND CASTINGS....285
MEASUREMENT AND PAYMENT....285
10-4.08 WROUGHT IRON FENCE....285
MATERIALS....286
INSTALLATION....286
MEASUREMENT AND PAYMENT....286
SECTION 11. (BLANK)....287
SECTION 12. (BLANK)....287
SECTION 13: RAILROAD RELATIONS AND INSURANCE REQUIREMENTS....287
13-1: RELATIONS WITH RAILROAD COMPANY....287
13-1.01 GENERAL....287
13-1.02 RAILROAD REQUIREMENTS....287
13-1.03 PROTECTION OF RAILROAD FACILITIES....289
13-1.04 WORK BY RAILROAD....289
13-1.05 DELAYS DUE TO WORK BY RAILROAD....289
13-1.06 LEGAL RELATIONS....290
13-1.07 INDEMNIFICATION....290
13-2 RAILROAD PROTECTIVE INSURANCE....290
INSURANCE....292
SECTION 14. FEDERAL REQUIREMENTS FOR FEDERAL-AID CONSTRUCTION PROJECTS....296

STANDARD PLANS LIST

The Standard Plan sheets applicable to this contract include, but are not limited to those indicated below. The Revised Standard Plans (RSP) and New Standard Plans (NSP) which apply to this contract are included as individual sheets of the project plans.

A10A	Abbreviations
A10B	Symbols
A20A	Pavement Markers and Traffic Lines, Typical Details
A20B	Pavement Markers and Traffic Lines, Typical Details
A20C	Pavement Markers and Traffic Lines, Typical Details
A20D	Pavement Markers and Traffic Lines, Typical Details
A24A	Pavement Markings - Arrows
A24B	Pavement Markings - Arrows
A24E	Pavement Markings - Words and Crosswalks
A62A	Excavation and Backfill - Miscellaneous Details
A62B	Limits of Payment for Excavation and Backfill - Bridge Surcharge and Wall
A62C	Limits of Payment for Excavation and Backfill - Bridge
A62D	Excavation and Backfill - Concrete Pipe Culverts
RSP A62DA	Excavation and Backfill - Concrete Pipe Culverts
A62F	Excavation and Backfill - Metal and Plastic Culverts
A76A	Concrete Barrier Type 60
A76B	Concrete Barrier Type 60
A81A	Crash Cushion, Sand Filled (Unidirectional)
A82B	Crash Cushion (Type ADIEM)
A85	Chain Link Fence
A87	Curbs, Dikes and Driveways
RSP D72	Drainage Inlets
D73	Drainage Inlets
D74C	Drainage Inlet Details
D77B	Bicycle Proof Grate Details
D78	Gutter Depressions
D79	Precast Reinforced Concrete Pipe - Direct Design Method
D88	Construction Loads On Culverts
H1	Planting and Irrigation - Abbreviations
H2	Planting and Irrigation - Symbols
H3	Planting and Irrigation Details
H4	Planting and Irrigation Details
H5	Planting and Irrigation Details
H7	Planting and Irrigation Details
H8	Planting and Irrigation Details
T1A	Temporary Crash Cushion, Sand Filled (Unidirectional)
T1B	Temporary Crash Cushion, Sand Filled (Bidirectional)
RSP T2	Temporary Crash Cushion, Sand Filled (Shoulder Installations)
T3	Temporary Railing (Type K)
T10	Traffic Control System for Lane Closure On Freeways and Expressways
T13	Traffic Control System for Lane Closure On Two Lane Conventional Highways
T14	Traffic Control System for Ramp Closure
T15	Traffic Control System for Moving Lane Closure On Multilane Highways
T17	Traffic Control System for Moving Lane Closure On Two Lane Highways
B0-1	Bridge Details
RSP B0-3	Bridge Details
B0-5	Bridge Details
B0-13	Bridge Details
RSP B3-1	Retaining Wall Type 1 - H=1200 Through 9100 mm

B6-21	Joint Seals (Maximum Movement Rating = 50 mm)
B7-11	Utility Details
B8-5	Cast-in-Place Prestressed Girder Details
RSP B11-56	Concrete Barrier Type 736
RS1	Roadside Signs, Typical Installation Details No. 1
RS2	Roadside Signs - Wood Post, Typical Installation Details No. 2
RS3	Roadside Signs - Laminated Wood Box Post Typical Installation Details No. 3
ES-1A	Signal, Lighting and Electrical Systems - Symbols and Abbreviations
ES-1B	Signal, Lighting and Electrical Systems - Symbols and Abbreviations
ES-2A	Signal, Lighting and Electrical Systems - Service Equipment
ES-2C	Signal, Lighting and Electrical Systems - Service Equipment Notes, Type III Series
ES-2D	Signal, Lighting and Electrical Systems - Service Equipment and Typical Wiring Diagram Type III-A Series
ES-2E	Signal, Lighting and Electrical Systems - Service Equipment and Typical Wiring Diagram Type III-B Series
ES-3A	Signal, Lighting and Electrical Systems - Controller Cabinet Details
ES-3B	Signal, Lighting and Electrical Systems - Controller Cabinet Details
ES-3C	Signal, Lighting and Electrical Systems - Controller Cabinet Details
ES-3F	Signal, Lighting and Electrical Systems - Telephone Demarcation Cabinet Details, Type C
ES-3G	Signal, Lighting and Electrical Systems – Telephone Demarcation Cabinet, Type C Details
ES-3H	Signal, Lighting and Electrical Systems – Irrigation Controller Enclosure Cabinet
ES-4A	Signal, Lighting and Electrical Systems - Signal Heads and Mountings
ES-4B	Signal, Lighting and Electrical Systems - Signal Heads and Mountings
ES-4C	Signal, Lighting and Electrical Systems - Signal Heads and Mountings
ES-4D	Signal, Lighting and Electrical Systems - Signal Heads and Mountings
ES-4E	Signal, Lighting and Electrical Systems - Signal Heads and Mountings
ES-5A	Signal, Lighting and Electrical Systems - Detectors
ES-5B	Signal, Lighting and Electrical Systems - Detectors
ES-5E	Signal, Lighting and Electrical Systems - Detectors
RSP ES-6A	Lighting Standards - Types 15, 21 and 22
RSP ES-6B	Lighting Standards - Types 15 AND 21, Barrier Rail Mounted Details
ES-7B	Signal and Lighting Standards - Type 1 Standards and Equipment Numbering
RSP ES-7D	Signal and Lighting Standards - Case 2 Arm Loading, Wind Velocity = 129 km/h, Arm Lengths 4.6 m to 9.1 m
ES-7M	Signal and Lighting Standards - Details No. 1
ES-7N	Signal and Lighting Standards - Details No. 2
ES-8	Signal, Lighting and Electrical Systems - Pull Box Details
ES-9B	Signal, Lighting and Electrical Systems - Electrical Details, Structure Installations
ES-9C	Signal, Lighting and Electrical Systems - Electrical Details, Structure Installations
ES-9D	Signal, Lighting and Electrical Systems - Electrical Details, Structure Installations
ES-9E	Signal, Lighting and Electrical Systems - Electrical Details, Structure Installations
ES-10	Signal, Lighting and Electrical Systems - Isolux Diagrams
ES-11	Signal, Lighting and Electrical Systems - Foundation Installations
ES-13A	Signal, Lighting and Electrical Systems - Splicing Details
ES-13B	Signal, Lighting and Electrical Systems - Wiring Details and Fuse Ratings
ES-14A	Signal, Lighting and Electrical Systems - Extinguishable Message Sign, 250 mm Letters
ES-14B	Signal, Lighting and Electrical Systems - Extinguishable Message Sign, 250 mm Letters
ES-14C	Signal, Lighting and Electrical Systems - Extinguishable Message Sign and Flashing Beacons
ES-15A	Sign Illumination - Mercury Vapor Sign Illumination Equipment
ES-15C	Sign Illumination - Sign Illumination Equipment
ES-15D	Sign Illumination - Sign Illumination Control
ES-16A	Closed Circuit Television Pole Details

DEPARTMENT OF TRANSPORTATION

NOTICE TO CONTRACTORS

CONTRACT NO. 04-291004

04-SF-101-R 8.0/R 8.5

Sealed proposals for the work shown on the plans entitled:

STATE OF CALIFORNIA; DEPARTMENT OF TRANSPORTATION; PROJECT PLANS FOR CONSTRUCTION ON STATE HIGHWAY IN THE CITY AND COUNTY OF SAN FRANCISCO FROM SOUTH VAN NESS AVENUE TO MARKET STREET ON THE CENTRAL FREEWAY

will be received at the Department of Transportation, 1120 N Street, Room 0200, MS #26, Sacramento, CA 95814, until 2 o'clock p.m. on September 3, 2003, at which time they will be publicly opened and read in Room 0100 at the same address.

Proposal forms for this work are included in a separate book entitled:

STATE OF CALIFORNIA; DEPARTMENT OF TRANSPORTATION; PROPOSAL AND CONTRACT FOR CONSTRUCTION ON STATE HIGHWAY IN THE CITY AND COUNTY OF SAN FRANCISCO FROM SOUTH VAN NESS AVENUE TO MARKET STREET ON THE CENTRAL FREEWAY

General work description: Viaduct consisting of CIDH piles, concrete columns and steel girders to be constructed and roads to be resurfaced with asphalt concrete.

This project has a goal of 16 percent disadvantaged business enterprise (DBE) participation.

No prebid meeting is scheduled for this project.

THIS PROJECT IS SUBJECT TO THE "BUY AMERICA" PROVISIONS OF THE SURFACE TRANSPORTATION ASSISTANCE ACT OF 1982 AS AMENDED BY THE INTERMODAL SURFACE TRANSPORTATION EFFICIENCY ACT OF 1991.

Bids are required for the entire work described herein.

At the time this contract is awarded, the Contractor shall possess either a Class A license or a combination of Class C licenses which constitutes a majority of the work.

This contract is subject to state contract nondiscrimination and compliance requirements pursuant to Government Code, Section 12990.

Bidder inquiries may be made as follows:

The Department will consider bidder inquiries only when a completed "Bidder Inquiry" form is submitted. A copy of the "Bidder Inquiry" form is available at the Internet address shown below. The bidder inquiry shall include the bidder's name and telephone number. Submit "Bidder Inquiry" forms to :

Construction Program Duty Senior
111 Grand Avenue
Oakland, CA 94612

Fax Number: (510) 622-1805
E-mail: DUTY_SENIOR_DISTRICT04@dot.ca.gov
Tel. Number: (510) 286-5209

To expedite processing, submittal of "Bidder Inquiry" forms via Fax or E-mail is preferred.

To the extent feasible and at the discretion of the Department, completed "Bidder Inquiry" forms submitted for consideration will be investigated, and responses will be posted on the Internet at:

http://www.dot.ca.gov/hq/esc/oe/project_status/bid_inq.html

The responses to bidders' inquiries, unless incorporated into formal addenda to the contract, are not a part of the contract, and are provided for the bidder's convenience only. In some instances, the question and answer may represent a summary of the matters discussed rather than a word-for-word recitation. The availability or use of information provided in the responses to bidders' inquiries is not to be construed in any way as a waiver of the provisions of Section 2-1.03 of the Standard Specifications or any other provision of the contract, the plans, Standard Specifications or Special Provisions, nor to excuse the contractor from full compliance with those contract requirements. Bidders are cautioned that subsequent responses or contract addenda may affect or vary a response previously given.

Project plans, special provisions, and proposal forms for bidding this project can only be obtained at the Department of Transportation, Plans and Bid Documents, Room 0200, MS #26, Transportation Building, 1120 N Street, Sacramento, California 95814, FAX No. (916) 654-7028, Telephone No. (916) 654-4490. Use FAX orders to expedite orders for project plans, special provisions and proposal forms. FAX orders must include credit card charge number, card expiration date and authorizing signature. Project plans, special provisions, and proposal forms may be seen at the above Department of Transportation office and at the offices of the District Directors of Transportation at Irvine, Oakland, and the district in which the work is situated. Standard Specifications and Standard Plans are available through the State of California, Department of Transportation, Publications Unit, 1900 Royal Oaks Drive, Sacramento, CA 95815, Telephone No. (916) 445-3520.

Cross sections for this project are not available.

The successful bidder shall furnish a payment bond and a performance bond.

The Department of Transportation hereby notifies all bidders that it will affirmatively ensure that in any contract entered into pursuant to this advertisement, disadvantaged business enterprises will be afforded full opportunity to submit bids in response to this invitation.

The U.S. Department of Transportation (DOT) provides a toll-free "hotline" service to report bid rigging activities. Bid rigging activities can be reported Mondays through Fridays, between 8:00 a.m. and 5:00 p.m., eastern time, Telephone No. 1-800-424-9071. Anyone with knowledge of possible bid rigging, bidder collusion, or other fraudulent activities should use the "hotline" to report these activities. The "hotline" is part of the DOT's continuing effort to identify and investigate highway construction contract fraud and abuse and is operated under the direction of the DOT Inspector General. All information will be treated confidentially and caller anonymity will be respected.

Pursuant to Section 1773 of the Labor Code, the general prevailing wage rates in the county, or counties, in which the work is to be done have been determined by the Director of the California Department of Industrial Relations. These wages are set forth in the General Prevailing Wage Rates for this project, available at the Labor Compliance Office at the offices of the District Director of Transportation for the district in which the work is situated, and available from the California Department of Industrial Relations' internet web site at: http://www.dir.ca.gov. The Federal minimum wage rates for this project as predetermined by the United States Secretary of Labor are available through the California Department of Transportation's Electronic Project Document Distribution Site on the internet at http://hqidoc1.dot.ca.gov/. Addenda to modify the Federal minimum wage rates, if necessary, will be issued to holders of "Proposal and Contract" books. Future effective general prevailing wage rates which have been predetermined and are on file with the California Department of Industrial Relations are referenced but not printed in the general prevailing wage rates.

If there is a difference between the minimum wage rates predetermined by the United States Secretary of Labor and the general prevailing wage rates determined by the Director of the California Department of Industrial Relations for similar classifications of labor, the Contractor and subcontractors shall pay not less than the higher wage rate. The Department will not accept lower State wage rates not specifically included in the Federal minimum wage determinations. This includes "helper" (or other classifications based on hours of experience) or any other classification not appearing in the Federal wage determinations. Where Federal wage determinations do not contain the State wage rate determination otherwise available for use by the Contractor and subcontractors, the Contractor and subcontractors shall pay not less than the Federal minimum wage rate which most closely approximates the duties of the employees in question.

DEPARTMENT OF TRANSPORTATION

Deputy Director Transportation Engineering

Dated July 14, 2003

KEB

COPY OF ENGINEER'S ESTIMATE

(NOT TO BE USED FOR BIDDING PURPOSES)

04-291004

Item	Item Code	Item	Unit of Measure	Estimated Quantity
1	031708	LEAD COMPLIANCE PLAN (REMOVE YELLOW TRAFFIC STRIPE)	LS	LUMP SUM
2 (S)	031709	PHOTO SURVEY OF EXISTING FACILITIES	LS	LUMP SUM
3 (S)	031710	SEWER VIDEO SURVEY	LS	LUMP SUM
4 (S)	031711	VIBRATION MONITORING	LS	LUMP SUM
5	070012	PROGRESS SCHEDULE (CRITICAL PATH METHOD)	LS	LUMP SUM
6	070018	TIME-RELATED OVERHEAD	LS	LUMP SUM
7	071322	TEMPORARY FENCE (TYPE CL-1.8)	M	1180
8	074019	PREPARE STORM WATER POLLUTION PREVENTION PLAN	LS	LUMP SUM
9	074020	WATER POLLUTION CONTROL	LS	LUMP SUM
10	031712	DEWATERING	LS	LUMP SUM
11 (S)	074026	TEMPORARY MULCH	M3	210
12	074032	TEMPORARY CONCRETE WASHOUT FACILITY	EA	40
13	074033	TEMPORARY CONSTRUCTION ENTRANCE	EA	10
14	074034	TEMPORARY COVER	M2	150
15	031713	TEMPORARY DRAINAGE INLET PROTECTION	EA	4
16	049506	BRIDGE CONSTRUCTION SURVEYING	LS	LUMP SUM
17 (S)	120090	CONSTRUCTION AREA SIGNS	LS	LUMP SUM
18 (S)	120100	TRAFFIC CONTROL SYSTEM	LS	LUMP SUM
19 (S)	120116	TYPE II BARRICADE	EA	19
20 (S)	120120	TYPE III BARRICADE	EA	65

Item	Item Code	Item	Unit of Measure	Estimated Quantity
21	120140	BARRICADE (LEFT IN PLACE)	EA	4
22 (S)	120149	TEMPORARY PAVEMENT MARKING (PAINT)	M2	59
23 (S)	120159	TEMPORARY TRAFFIC STRIPE (PAINT)	M	5610
24 (S)	120165	CHANNELIZER (SURFACE MOUNTED)	EA	29
25 (S)	120182	PORTABLE DELINEATOR	EA	410
26 (S)	120300	TEMPORARY PAVEMENT MARKER	EA	10
27 (S)	128650	PORTABLE CHANGEABLE MESSAGE SIGN	EA	2
28 (S)	129000	TEMPORARY RAILING (TYPE K)	M	880
29 (S)	129100	TEMPORARY CRASH CUSHION MODULE	EA	110
30 (S)	031714	TEMPORARY CRASH CUSHION (QUADGUARD)	EA	1
31	150206	ABANDON CULVERT	EA	14
32	150221	ABANDON INLET	EA	1
33	150605	REMOVE FENCE	M	90
34	150714	REMOVE THERMOPLASTIC TRAFFIC STRIPE	M	2220
35	150704	REMOVE YELLOW THERMOPLASTIC TRAFFIC STRIPE	M	980
36	150715	REMOVE THERMOPLASTIC PAVEMENT MARKING	M2	7
37	150722	REMOVE PAVEMENT MARKER	EA	650
38	150730	REMOVE CHANNELIZERS	EA	22
39	150742	REMOVE ROADSIDE SIGN	EA	2
40	150764	REMOVE SIGN OVERLAY	EA	2

Item	Item Code	Item	Unit of Measure	Estimated Quantity
41	150805	REMOVE CULVERT	M	39
42	150820	REMOVE INLET	EA	3
43	150826	REMOVE MANHOLE	EA	2
44	150857	REMOVE ASPHALT CONCRETE SURFACING	M3	350
45	150860	REMOVE BASE AND SURFACING	M3	420
46 (S)	151540	RECONSTRUCT CHAIN LINK FENCE	M	270
47	152432	ADJUST MANHOLE	EA	1
48 (S)	153103	COLD PLANE ASPHALT CONCRETE PAVEMENT	M2	6730
49	153210	REMOVE CONCRETE	M3	450
50	153229	REMOVE CONCRETE BARRIER (TYPE K)	M	55
51	156590	REMOVE CRASH CUSHION (SAND FILLED)	EA	1
52 (S)	157560	BRIDGE REMOVAL (PORTION)	LS	LUMP SUM
53	160101	CLEARING AND GRUBBING	LS	LUMP SUM
54	031715	ROADWAY EXCAVATION (HAZARDOUS)	M3	410
55 (F)	192003	STRUCTURE EXCAVATION (BRIDGE)	M3	20
56 (F)	049496	STRUCTURE EXCAVATION, (BRIDGE), TYPE H	M3	1130
57 (F)	049497	STRUCTURE EXCAVATION, (RETAINING WALL) TYPE H	M3	870
58 (F)	193003	STRUCTURE BACKFILL (BRIDGE)	M3	1200
59 (F)	193013	STRUCTURE BACKFILL (RETAINING WALL)	M3	1350
60 (F)	193031	PERVIOUS BACKFILL MATERIAL (RETAINING WALL)	M3	90

Item	Item Code	Item	Unit of Measure	Estimated Quantity
61	198001	IMPORTED BORROW	M3	4870
62 (S)	200001	HIGHWAY PLANTING	LS	LUMP SUM
63 (S)	203021	FIBER ROLLS	M	66
64 (S)	031732	DRAIN INLET PROTECTION	EA	1
65 (S)	204099	PLANT ESTABLISHMENT WORK	LS	LUMP SUM
66 (S)	208000	IRRIGATION SYSTEM	LS	LUMP SUM
67 (S)	208304	WATER METER	EA	2
68	250401	CLASS 4 AGGREGATE SUBBASE	M3	620
69 (F)	260201	CLASS 2 AGGREGATE BASE	M3	340
70	260301	CLASS 3 AGGREGATE BASE	M3	820
71	270065	ASPHALTIC EMULSION (CURING SEAL)	TONN	1.2
72	390102	ASPHALT CONCRETE (TYPE A)	TONN	1780
73	405030	PORTLAND CEMENT CONCRETE BASE	M3	210
74 (S)	490665	1.8 M CAST-IN-DRILLED-HOLE CONCRETE PILING	M	630
75 (S)	049498	1.8 M CAST-IN-DRILL HOLE CONCRETE PILING (ROCK SOCKET)	M	9
76 (S)	490669	2.1 M CAST-IN-DRILLED-HOLE CONCRETE PILING	M	170
77 (S)	500001	PRESTRESSING CAST-IN-PLACE CONCRETE	LS	LUMP SUM
78 (F)	510051	STRUCTURAL CONCRETE, BRIDGE FOOTING	M3	162
79 (F)	510053	STRUCTURAL CONCRETE, BRIDGE	M3	3020
80 (F)	049499	STRUCTURAL CONCRETE, BRIDGE (COLORED)	M3	1615

Item	Item Code	Item	Unit of Measure	Estimated Quantity
81 (F)	049500	STRUCTURAL CONCRETE, RETAINING WALL FOOTING	M3	154
82 (F)	049501	STRUCTURAL CONCRETE, RETAINING WALL (COLORED)	M3	392
83 (F)	510086	STRUCTURAL CONCRETE, APPROACH SLAB (TYPE N)	M3	67
84 (F)	510502	MINOR CONCRETE (MINOR STRUCTURE)	M3	17
85	510522	MINOR CONCRETE (PIPE COVER)	M3	55
86 (F)	049502	ARCHITECTURAL FINISH (EXPOSED AGGREGATE)	M2	1127
87 (F)	049503	ARCHITECTURAL TREATMENT (RANDOM CUT STONE)	M2	740
88 (F)	515020	REFINISH BRIDGE DECK	M2	39
89 (S)	518050	PTFE BEARING	EA	14
90 (S)	518051	PTFE SPHERICAL BEARING	EA	28
91 (S)	519120	JOINT SEAL (MR 15 MM)	M	27
92 (S)	519128	JOINT SEAL ASSEMBLY (MR 100 MM)	M	27
93 (S)	049504	SEISMIC JOINT ASSEMBLY (MR>100MM)	M	27
94 (S-F)	520102	BAR REINFORCING STEEL (BRIDGE)	KG	1 347 000
95 (S-F)	520103	BAR REINFORCING STEEL (RETAINING WALL)	KG	22 900
96 (F)	550203	FURNISH STRUCTURAL STEEL (BRIDGE)	KG	2 610 000
97 (S-F)	550204	ERECT STRUCTURAL STEEL (BRIDGE)	KG	2 610 000
98	562004	METAL (RAIL MOUNTED SIGN)	KG	1100
99	566011	ROADSIDE SIGN - ONE POST	EA	11
100	566012	ROADSIDE SIGN - TWO POST	EA	3

Item	Item Code	Item	Unit of Measure	Estimated Quantity
101	568016	INSTALL SIGN PANEL ON EXISTING FRAME	EA	12
102 (S)	590115	CLEAN AND PAINT STRUCTURAL STEEL	LS	LUMP SUM
103 (S)	590135	SPOT BLAST CLEAN AND PAINT UNDERCOAT	M2	13
104 (S)	590301	WORK AREA MONITORING	LS	LUMP SUM
105	620904	300 MM ALTERNATIVE PIPE CULVERT	M	97
106	681140	80 MM PLASTIC PIPE (APPROACH SLAB DRAIN OUTLET)	M	14
107	031716	150 MM WELDED STEEL PIPE (3.4 MM THICK)	M	61
108	031717	250 MM VITRIFIED CLAY PIPE	M	57
109	031718	300 MM VITRIFIED CLAY PIPE	M	48
110	031719	450 MM VITRIFIED CLAY PIPE	M	42
111	031720	600 MM WELDED STEEL PIPE (3.4 MM THICK)	M	36
112	031721	SAN FRANCISCO MANHOLE	EA	8
113	031722	SAN FRANCISCO CATCH BASIN	EA	4
114	031723	GRANITE CURB	M	75
115	731502	MINOR CONCRETE (MISCELLANEOUS CONSTRUCTION)	M3	320
116	031724	MANUFACTURED STONE PAVING	M2	130
117	031725	BRICK SIDEWALK	M2	430
118 (S-F)	750001	MISCELLANEOUS IRON AND STEEL	KG	2202
119 (S-F)	750501	MISCELLANEOUS METAL (BRIDGE)	KG	12 450
120 (S)	031726	WROUGHT IRON FENCE	M	350

Item	Item Code	Item	Unit of Measure	Estimated Quantity
121 (S)	031727	WROUGHT IRON PEDESTRIAN GATE	EA	2
122 (S)	031728	WROUGHT IRON VEHICULAR GATE	EA	2
123 (S)	839591	CRASH CUSHION, SAND FILLED	EA	1
124 (S)	839603	CRASH CUSHION (ADIEM)	EA	1
125 (F)	839702	CONCRETE BARRIER (TYPE 60A)	M	442
126	839703	CONCRETE BARRIER (TYPE 60C)	M	25
127 (F)	839725	CONCRETE BARRIER (TYPE 736)	M	1020
128 (F)	839728	CONCRETE BARRIER (TYPE 736R)	M	84
129 (S)	840515	THERMOPLASTIC PAVEMENT MARKING	M2	200
130 (S)	840561	100 MM THERMOPLASTIC TRAFFIC STRIPE	M	6010
131 (S)	840563	200 MM THERMOPLASTIC TRAFFIC STRIPE	M	1190
132 (S)	850101	PAVEMENT MARKER (NON-REFLECTIVE)	EA	1450
133 (S)	850111	PAVEMENT MARKER (RETROREFLECTIVE)	EA	680
134 (S)	031730	MODIFY LIGHTING (CITY)	LS	LUMP SUM
135 (S)	860297	SIGNAL AND LIGHTING (CITY)	LS	LUMP SUM
136 (S)	860460	LIGHTING AND SIGN ILLUMINATION	LS	LUMP SUM
137 (S)	031731	TRAFFIC OPERATIONS SYSTEM	LS	LUMP SUM
138 (S)	860640	IRRIGATION CONTROLLER ENCLOSURE CABINET	EA	1
139	999990	MOBILIZATION	LS	LUMP SUM

STATE OF CALIFORNIA

DEPARTMENT OF TRANSPORTATION

SPECIAL PROVISIONS

Annexed to Contract No. 04-291004

SECTION 1. SPECIFICATIONS AND PLANS

The work embraced herein shall conform to the provisions in the Standard Specifications dated July 1999, and the Standard Plans dated July 1999, of the Department of Transportation insofar as the same may apply, and these special provisions.

In case of conflict between the Standard Specifications and these special provisions, the special provisions shall take precedence over and shall be used in lieu of the conflicting portions.

AMENDMENTS TO JULY 1999 STANDARD SPECIFICATIONS

UPDATED JUNE 19, 2003

Amendments to the Standard Specifications set forth in these special provisions shall be considered as part of the Standard Specifications for the purposes set forth in Section 5-1.04, "Coordination and Interpretation of Plans, Standard Specifications and Special Provisions," of the Standard Specifications. Whenever either the term "Standard Specifications is amended" or the term "Standard Specifications are amended" is used in the special provisions, the text or table following the term shall be considered an amendment to the Standard Specifications. In case of conflict between such amendments and the Standard Specifications, the amendments shall take precedence over and be used in lieu of the conflicting portions.

SECTION 2: PROPOSAL REQUIREMENTS AND CONDITIONS

Issue Date: June 19, 2003

Section 2-1.03, "Examination of Plans, Specifications, Contract, and Site of Work," of the Standard Specifications is amended to read:

2-1.03 Examination of Plans, Specifications, Contract, and Site of Work

- The bidder shall examine carefully the site of the work contemplated, the plans and specifications, and the proposal and contract forms therefor. The submission of a bid shall be conclusive evidence that the bidder has investigated and is satisfied as to the general and local conditions to be encountered, as to the character, quality and scope of work to be performed, the quantities of materials to be furnished and as to the requirements of the proposal, plans, specifications and the contract.
- The submission of a bid shall also be conclusive evidence that the bidder is satisfied as to the character, quality and quantity of surface and subsurface materials or obstacles to be encountered insofar as this information was reasonably ascertainable from an inspection of the site and the records of exploratory work done by the Department as shown in the bid documents, as well as from the plans and specifications made a part of the contract.
- Where the Department has made investigations of site conditions including subsurface conditions in areas where work is to be performed under the contract, or in other areas, some of which may constitute possible local material sources, bidders or contractors may, upon written request, inspect the records of the Department as to those investigations subject to and upon the conditions hereinafter set forth.

• Where there has been prior construction by the Department or other public agencies within the project limits, records of the prior construction that are currently in the possession of the Department and which have been used by, or are known to, the designers and administrators of the project will be made available for inspection by bidders or contractors, upon written request, subject to the conditions hereinafter set forth. The records may include, but are not limited to, as-built drawings, design calculations, foundation and site studies, project reports and other data assembled in connection with the investigation, design, construction and maintenance of the prior projects.

• Inspection of the records of investigations and project records may be made at the office of the district in which the work is situated, or in the case of records of investigations related to structure work, at the Transportation Laboratory in Sacramento, California.

• When a log of test borings or other record of geotechnical data obtained by the Department's investigation of surface and subsurface conditions is included with the contract plans, it is furnished for the bidders' or Contractor's information and its use shall be subject to the conditions and limitations set forth in this Section 2-1.03.

• In some instances, information considered by the Department to be of possible interest to bidders or contractors has been compiled as "Materials Information." The use of the "Materials Information" shall be subject to the conditions and limitations set forth in this Section 2-1.03 and Section 6-2, "Local Materials."

• When cross sections are not included with the plans, but are available, bidders or contractors may inspect the cross sections and obtain copies for their use, at their expense.

• When cross sections are included with the contract plans, it is expressly understood and agreed that the cross sections do not constitute part of the contract, do not necessarily represent actual site conditions or show location, character, dimensions and details of work to be performed, and are included in the plans only for the convenience of bidders and their use is subject to the conditions and limitations set forth in this Section 2-1.03.

• When contour maps were used in the design of the project, the bidders may inspect those maps, and if available, they may obtain copies for their use.

• The availability or use of information described in this Section 2-1.03 is not to be construed in any way as a waiver of the provisions of the first paragraph in this Section 2-1.03 and bidders and contractors are cautioned to make independent investigations and examinations as they deem necessary to be satisfied as to conditions to be encountered in the performance of the work and, with respect to possible local material sources, the quality and quantity of material available from the property and the type and extent of processing that may be required in order to produce material conforming to the requirements of the specifications.

• The Department assumes no responsibility for conclusions or interpretations made by a bidder or contractor based on the information or data made available by the Department. The Department does not assume responsibility for representation made by its officers or agents before the execution of the contract concerning surface or subsurface conditions, unless that representation is expressly stated in the contract.

• No conclusions or interpretations made by a bidder or contractor from the information and data made available by the Department will relieve a bidder or contractor from properly fulfilling the terms of the contract.

SECTION 5: CONTROL OF WORK

Issue Date: December 31, 2001

Section 5-1.02A, "Trench Excavation Safety Plans," of the Standard Specifications is amended to read:

5-1.02A Excavation Safety Plans

• The Construction Safety Orders of the Division of Occupational Safety and Health shall apply to all excavations. For all excavations 1.5 m or more in depth, the Contractor shall submit to the Engineer a detailed plan showing the design and details of the protective systems to be provided for worker protection from the hazard of caving ground during excavation. The detailed plan shall include any tabulated data and any design calculations used in the preparation of the plan. Excavation shall not begin until the detailed plan has been reviewed and approved by the Engineer.

• Detailed plans of protective systems for which the Construction Safety Orders require design by a registered professional engineer shall be prepared and signed by an engineer who is registered as a Civil Engineer in the State of California, and shall include the soil classification, soil properties, soil design calculations that demonstrate adequate stability of the protective system, and any other design calculations used in the preparation of the plan.

• No plan shall allow the use of a protective system less effective than that required by the Construction Safety Orders.

• If the detailed plan includes designs of protective systems developed only from the allowable configurations and slopes, or Appendices, contained in the Construction Safety Orders, the plan shall be submitted at least 5 days before the Contractor intends to begin excavation. If the detailed plan includes designs of protective systems developed from tabulated

data, or designs for which design by a registered professional engineer is required, the plan shall be submitted at least 3 weeks before the Contractor intends to begin excavation.

- Attention is directed to Section 7-1.01E, "Trench Safety."

SECTION 9: MEASUREMENT AND PAYMENT

Issue Date: November 18, 2002

Section 9-1.04, "Notice of Potential Claim," of the Standard Specifications is amended to read:

9-1.04 NOTICE OF POTENTIAL CLAIM

- It is the intention of this section that disputes between the parties arising under and by virtue of the contract be brought to the attention of the Engineer at the earliest possible time in order that the matters may be resolved, if possible, or other appropriate action promptly taken.
- Disputes will not be considered unless the Contractor has first complied with specified notice or protest requirements, including Section 4-1.03, "Changes," Section 5-1.116, "Differing Site Conditions," Section 8-1.06, "Time of Completion," Section 8-1.07, "Liquidated Damages," and Section 8-1.10, "Utility and Non-Highway Facilities."
- For disputes arising under and by virtue of the contract, including an act or failure to act by the Engineer, the Contractor shall provide a signed written initial notice of potential claim to the Engineer within 5 days from the date the dispute first arose. The initial notice of potential claim shall provide the nature and circumstances involved in the dispute which shall remain consistent through the dispute. The initial notice of potential claim shall be submitted on Form CEM-6201A furnished by the Department and shall be certified with reference to the California False Claims Act, Government Code Sections 12650-12655. The Contractor shall assign an exclusive identification number for each dispute, determined by chronological sequencing, based on the date of the dispute.
- The exclusive identification number for each dispute shall be used on the following corresponding documents:

A. Initial notice of potential claim.
B. Supplemental notice of potential claim.
C. Full and final documentation of potential claim.
D. Corresponding claim included in the Contractor's written statement of claims.

- The Contractor shall provide the Engineer the opportunity to examine the site of work within 5 days from the date of the initial notice of potential claim. The Contractor shall proceed with the performance of contract work unless otherwise specified or directed by the Engineer.
- Throughout the disputed work, the Contractor shall maintain records that provide a clear distinction between the incurred direct costs of disputed work and that of undisputed work. The Contractor shall allow the Engineer access to the Contractor's project records deemed necessary by the Engineer to evaluate the potential claim within 20 days of the date of the Engineer's written request.
- Within 15 days of submitting the initial notice of potential claim, the Contractor shall provide a signed supplemental notice of potential claim to the Engineer that provides the following information:

A. The complete nature and circumstances of the dispute which caused the potential claim.
B. The contract provisions that provide the basis of claim.
C. The estimated cost of the potential claim, including an itemized breakdown of individual costs and how the estimate was determined.
D. A time impact analysis of the project schedule that illustrates the effect on the scheduled completion date due to schedule changes or disruptions where a request for adjustment of contract time is made.

- The information provided in items A and B above shall provide the Contractor's complete reasoning for additional compensation or adjustments.
- The supplemental notice of potential claim shall be submitted on Form CEM-6201B furnished by the Department and shall be certified with reference to the California False Claims Act, Government Code Sections 12650-12655. The Engineer will evaluate the information presented in the supplemental notice of potential claim and provide a written response to the Contractor within 20 days of its receipt. If the estimated cost or effect on the scheduled completion date changes, the Contractor shall update information in items C and D above as soon as the change is recognized and submit this information to the Engineer.

- Within 30 days of the completion of work related to the potential claim, the Contractor shall provide the full and final documentation of potential claim to the Engineer that provides the following information:

A. A detailed factual narration of events fully describing the nature and circumstances that caused the dispute, including, but not limited to, necessary dates, locations, and items of work affected by the dispute.
B. The specific provisions of the contract that support the potential claim and a statement of the reasons these provisions support and provide a basis for entitlement of the potential claim.
C. When additional monetary compensation is requested, the exact amount requested calculated in conformance with Section 9-1.03, "Force Account Payment," or Section 8-1.09, "Right of Way Delays," including an itemized breakdown of individual costs. These costs shall be segregated into the following cost categories:

    1. Labor – A listing of individuals, classifications, regular hours and overtime hours worked, dates worked, and other pertinent information related to the requested reimbursement of labor costs.
    2. Materials – Invoices, purchase orders, location of materials either stored or incorporated into the work, dates materials were transported to the project or incorporated into the work, and other pertinent information related to the requested reimbursement of material costs.
    3. Equipment – Listing of detailed description (make, model, and serial number), hours of use, dates of use and equipment rates. Equipment rates shall be at the applicable State rental rate as listed in the Department of Transportation publication entitled "Labor Surcharge and Equipment Rental Rates," in effect when the affected work related to the dispute was performed.
    4. Other categories as specified by the Contractor or the Engineer.

D. When an adjustment of contract time is requested the following information shall be provided:

    1. The specific dates for which contract time is being requested.
    2. The specific reasons for entitlement to a contract time adjustment.
    3. The specific provisions of the contract that provide the basis for the requested contract time adjustment.
    4. A detailed time impact analysis of the project schedule. The time impact analysis shall show the effect of changes or disruptions on the scheduled completion date to demonstrate entitlement to a contract time adjustment.

E. The identification and copies of the Contractor's documents and the substance of oral communications that support the potential claim.

- The full and final documentation of the potential claim shall be submitted on Form CEM-6201C furnished by the Department and shall be certified with reference to the California False Claims Act, Government Code Sections 12650-12655.
- Pertinent information, references, arguments, and data to support the potential claim shall be included in the full and final documentation of potential claim. Information submitted subsequent to the full and final documentation submittal will not be considered. Information required in the full and final documentation of potential claim, as listed in items A to E above, that is not applicable to the dispute may be exempted as determined by the Engineer. No full and final documentation of potential claim will be considered that does not have the same nature and circumstances, and basis of claim as those specified on the initial and supplemental notices of potential claim.
- The Engineer will evaluate the information presented in the full and final documentation of potential claim and provide a written response to the Contractor within 30 days of its receipt unless otherwise specified. The Engineer's receipt of the full and final documentation of potential claim shall be evidenced by postal receipt or the Engineer's written receipt if delivered by hand. If the full and final documentation of potential claim is submitted by the Contractor after acceptance of the work by the Director, the Engineer need not provide a written response.
- Provisions in this section shall not apply to those claims for overhead costs and administrative disputes that occur after issuance of the proposed final estimate. Administrative disputes are disputes of administrative deductions or retentions, contract item quantities, contract item adjustments, interest payments, protests of contract change orders as provided in Section 4-1.03A, "Procedure and Protest," and protests of the weekly statement of working days as provided in Section 8-1.06, "Time of Completion." Administrative disputes that occur prior to issuance of the proposed final estimate shall follow applicable requirements of this section. Information listed in the supplemental notice and full and final documentation of potential claim that is not applicable to the administrative dispute may be exempted as determined by the Engineer.
- Unless otherwise specified in the special provisions, the Contractor may pursue the administrative claim process pursuant to Section 9-1.07B, "Final Payment and Claims," for any potential claim found by the Engineer to be without merit.

• Failure of the Contractor to conform to specified dispute procedures shall constitute a failure to pursue diligently and exhaust the administrative procedures in the contract, and is deemed as the Contractor's waiver of the potential claim and a waiver of the right to a corresponding claim for the disputed work in the administrative claim process in conformance with Section 9-1.07B, "Final Payment of Claims," and shall operate as a bar to arbitration pursuant to Section 10240.2 of the California Public Contract Code.

Section 9-1.07B, "Final Payment and Claims," of the Standard Specifications is amended to read:

9-1.07B Final Payment and Claims

• After acceptance by the Director, the Engineer will make a proposed final estimate in writing of the total amount payable to the Contractor, including an itemization of the total amount, segregated by contract item quantities, extra work and other bases for payment, and shall also show each deduction made or to be made for prior payments and amounts to be kept or retained under the provisions of the contract. Prior estimates and payments shall be subject to correction in the proposed final estimate. The Contractor shall submit written approval of the proposed final estimate or a written statement of claims arising under or by virtue of the contract so that the Engineer receives the written approval or statement of claims no later than close of business of the thirtieth day after receiving the proposed final estimate. If the thirtieth day falls on a Saturday, Sunday or legal holiday, then receipt of the written approval or statement of claims by the Engineer shall not be later than close of business of the next business day. The Contractor's receipt of the proposed final estimate shall be evidenced by postal receipt. The Engineer's receipt of the Contractor's written approval or statement of claims shall be evidenced by postal receipt or the Engineer's written receipt if delivered by hand.

• On the Contractor's approval, or if the Contractor files no claim within the specified period of 30 days, the Engineer will issue a final estimate in writing in conformance with the proposed final estimate submitted to the Contractor, and within 30 days thereafter the State will pay the entire sum so found to be due. That final estimate and payment thereon shall be conclusive and binding against both parties to the contract on all questions relating to the amount of work done and the compensation payable therefor, except as otherwise provided in Sections 9-1.03C, "Records," and 9-1.09, "Clerical Errors."

• If the Contractor within the specified period of 30 days files claims, the Engineer will issue a semifinal estimate in conformance with the proposed final estimate submitted to the Contractor and within 30 days thereafter the State will pay the sum found to be due. The semifinal estimate and corresponding payment shall be conclusive and binding against both parties to the contract on each question relating to the amount of work done and the compensation payable therefor, except insofar as affected by the claims filed within the time and in the manner required hereunder and except as otherwise provided in Sections 9-1.03C, "Records," and 9-1.09, "Clerical Errors."

• Except for claims for overhead costs and administrative disputes that occur after issuance of the proposed final estimate, the Contractor shall only provide the following two items of information for each claim:

A. The exclusive identification number that corresponds to the supporting full and final documentation of potential claim.
B. The final amount of requested additional compensation.

• If the final amount of requested additional compensation is different than the amount of requested compensation included in the full and final documentation of potential claim, the Contractor shall provide in the written statement of claims the reasons for the changed amount, the specific provisions of the contract which support the changed amount, and a statement of the reasons the provisions support and provide a basis for the changed amount. If the Contractor's claim fails to provide an exclusive identification number or if there is a disparity in the provided exclusive identification number, the Engineer will notify the Contractor of the omission or disparity. The Contractor shall have 15 days after receiving notification from the Engineer to correct the omission or disparity. If after the 15 days has elapsed, there is still an omission or disparity of the exclusive identification number assigned to the claim, the Engineer will assign the number. No claim will be considered that has any of the following deficiencies:

A. The claim does not have the same nature, circumstances, and basis as the corresponding full and final documentation of potential claim.
B. The claim does not have a corresponding full and final documentation of potential claim.
C. The claim was not included in the written statement of claims.
D. The Contractor did not comply with applicable notice or protest requirements of Sections 4-1.03, "Changes," 5-1.116, "Differing Site Condition," 8-1.06, "Time of Completion," 8-1.07, "Liquidated Damages," 8-1.10, "Utility and Non-Highway Facilities," and 9-1.04, "Notice of Potential Claim."

- Administrative disputes that occur after issuance of the proposed final estimate shall be included in the Contractor's written statement of claims in sufficient detail to enable the Engineer to ascertain the basis and amounts of those claims.
- The Contractor shall keep full and complete records of the costs and additional time incurred for work for which a claim for additional compensation is made. The Engineer or designated claim investigators or auditors shall have access to those records and any other records as may be required by the Engineer to determine the facts or contentions involved in the claims. Failure to permit access to those records shall be sufficient cause for denying the claims.
- The written statement of claims submitted by the Contractor shall be accompanied by a notarized certificate containing the following language:

> Under the penalty of law for perjury or falsification and with specific reference to the California False Claims Act, Government Code Section 12650 et. seq., the undersigned,
>
> _____ .
> *(name)*
>
> _____ *of*
> *(title)*
>
> _____ .
> *(company)*
>
> hereby certifies that the claim for the additional compensation and time, if any, made herein for the work on this contract is a true statement of the actual costs incurred and time sought, and is fully documented and supported under the contract between parties.
>
> Dated _____
>
> /s/ _____
>
> Subscribed and sworn before me this _____ day
>
> of _____ .
>
> _____
> *(Notary Public)*
> My Commission
> Expires _____

- Failure to submit the notarized certificate will be sufficient cause for denying the claim.
- Claims for overhead type expenses or costs, in addition to being certified as stated above, shall be supported and accompanied by an audit report of an independent Certified Public Accountant. Omission of a supporting audit report of an independent Certified Public Accountant shall result in denial of the claim and shall operate as a bar to arbitration, as to the claim, in conformance with the requirements in Section 10240.2 of the California Public Contract Code. Claims for overhead type expenses or costs shall be subject to audit by the State at its discretion. The costs of performing an audit examination and submitting the report shall be borne by the Contractor. The Certified Public Accountant's audit examination shall be performed in conformance with the requirements of the American Institute of Certified Public Accountants Attestation Standards. The audit examination and report shall depict the Contractor's project and company-wide financial records and shall specify the actual overall average daily rates for both field and home office overhead for the entire duration of the project, and whether the costs have been properly allocated. The rates of field and home office overhead shall exclude unallowable costs as determined in Title 48 of the Federal Acquisition Regulations, Chapter 1, Part 31. The audit examination and report shall determine if the rates of field and home office overhead are:

A. Allowable in conformance with the requirements in Title 48 of the Federal Acquisition Regulations, Chapter 1, Part 31.
B. Adequately supported by reliable documentation.
C. Related solely to the project under examination.

- Costs or expenses incurred by the State in reviewing or auditing claims that are not supported by the Contractor's cost accounting or other records shall be deemed to be damages incurred by the State within the meaning of the California False Claims Act.

- If the Contractor files a timely written statement of claims in response to the proposed final estimate, the District that administers the contract will submit a claim position letter to the Contractor by hand delivery or deposit in the U.S. mail within 135 days of acceptance of the contract. The claim position letter will delineate the District's position on the Contractor's claims. If the Contractor disagrees with the claim position letter, the Contractor shall submit a written notification of its disagreement and a written request to meet with the board of review, to be received by the District not later than 15 days after the Contractor's receipt of the claim position letter. The written notification of disagreement shall set forth the basis for the Contractor's disagreement and be submitted to the office designated in the claim position letter. The Contractor's failure to provide a timely written notification of disagreement or timely written request to meet with the board of review shall constitute the Contractor's acceptance and agreement with the determinations provided in the claim position letter and with final payment pursuant to the claim position letter.
- If the Contractor files a timely notification of disagreement with the District claim position letter and a timely request to meet with the board of review, then the board of review, designated by the District Director to review claims that remain in dispute, will meet with the Contractor within 45 days after receipt by the District of the notification of disagreement.
- If the District fails to submit a claim position letter to the Contractor within 135 days after the acceptance of the contract and the Contractor has claims that remain in dispute, the Contractor may request a meeting with the board of review designated by the District Director to review claims that remain in dispute. The Contractor's request for a meeting shall identify the claims that remain in dispute. If the Contractor files a request for a meeting, the board of review will meet with the Contractor within 45 days after the District receives the request for the meeting.
- Attendance by the Contractor at the board of review meeting shall be mandatory. The board of review will review those claims and make a written recommendation thereon to the District Director. The final determination of claims, made by the District Director, will be sent to the Contractor by hand delivery or deposit in the U.S. mail. The Engineer will then make and issue the Engineer's final estimate in writing and within 30 days thereafter the State will pay the entire sum, if any, found due thereon. That final estimate shall be conclusive and binding against both parties to the contract on all questions relating to the amount of work done and the compensation payable therefor, except as otherwise provided in Sections 9-1.03C, "Records," and 9-1.09, "Clerical Errors."
- Failure of the Contractor to conform to the specified dispute procedures shall constitute a failure to pursue diligently and exhaust the administrative procedures in the contract and shall operate as a bar to arbitration in conformance with the requirements in Section 10240.2 of the California Public Contract Code.

SECTION 19: EARTHWORK

Issue Date: December 31, 2001

The third paragraph of Section 19-1.02, "Preservation of Property," of the Standard Specifications is amended to read:

- In addition to the provisions in Sections 5-1.02, "Plans and Working Drawings," and 5-1.02A, "Excavation Safety Plans," detailed plans of the protective systems for excavations on or affecting railroad property will be reviewed for adequacy of protection provided for railroad facilities, property, and traffic. These plans shall be submitted at least 9 weeks before the Contractor intends to begin excavation requiring the protective systems. Approval by the Engineer of the detailed plans for the protective systems will be contingent upon the plans being satisfactory to the railroad company involved.

SECTION 42: GROOVE AND GRIND PAVEMENT

Issue Date: December 31, 2001

The last sentence of the first subparagraph of the third paragraph in Section 42-2.02, "Construction," of the Standard Specifications is amended to read:

> After grinding has been completed, the pavement shall conform to the straightedge and profile requirements specified in Section 40-1.10, "Final Finishing."

SECTION 49: PILING

Issue Date: April 30, 2003

The first paragraph in Section 49-1.03, "Determination of Length," of the Standard Specifications is amended to read:

• Foundation piles of any material shall be of such length as is required to develop the nominal resistance, to obtain the specified penetration, and to extend into the cap or footing block as shown on the plans, or specified in the special provisions.

The fourth paragraph in Section 49-1.03, "Determination of Length," of the Standard Specifications is amended to read:

• Modification to the specified installation methods and specified pile tip elevation will not be considered at locations where tension or lateral load demands control design pile tip elevations or when the plans state that specified pile tip elevation shall not be revised.

The sixth and seventh paragraphs in Section 49-1.03, "Determination of Length," of the Standard Specifications are amended to read:

• Indicator compression pile load testing shall conform to the requirements in ASTM Designation: D 1143. The pile shall sustain the first compression test load applied which is equal to the nominal resistance in compression, as shown on the plans, with no more than 13 mm total vertical movement at the top of the pile measured relative to the top of the pile prior to the start of compression load testing.

• Indicator tension pile load testing shall conform to the requirements in ASTM Designation: D 3689. The loading apparatus described as "Load Applied to Pile by Hydraulic Jack(s) Acting at One End of Test Beam(s) Anchored to the Pile" shall not be used. The pile shall sustain the first tension test load applied which is equal to the nominal resistance in tension, as shown on the plans, with no more than 13 mm total vertical movement at the top of the pile measured relative to the top of the pile prior to the start of tension load testing.

The ninth paragraph in Section 49-1.03, "Determination of Length," of the Standard Specifications is amended to read:

• For driven piling, the Contractor shall furnish piling of sufficient length to obtain both the specified tip elevation and nominal resistance shown on the plans or specified in the special provisions. For cast-in-drilled-hole concrete piling, the Contractor shall construct piling of such length to develop the nominal resistance in compression and to obtain the specified tip elevation shown on the plans or specified in the special provisions.

The tenth paragraph in Section 49-1.03, "Determination of Length," of the Standard Specifications is deleted.

The fourth paragraph in Section 49-1.04, "Load Test Piles," of the Standard Specifications is amended to read:

• Load test piles and anchor piles which are not to be incorporated in the completed structure shall be removed in conformance with the provisions in Section 15-4.02, "Removal Methods," and the remaining holes shall be backfilled with earth or other suitable material approved by the Engineer.

The first paragraph in Section 49-1.05, "Driving Equipment," of the Standard Specifications is amended to read:

• Driven piles shall be installed with impact hammers that are approved in writing by the Engineer. Impact hammers shall be steam, hydraulic, air or diesel hammers. Impact hammers shall develop sufficient energy to drive the piles at a penetration rate of not less than 3 mm per blow at the specified nominal resistance.

The seventh paragraph in Section 49-1.05, "Driving Equipment," of the Standard Specifications is amended to read:

• When necessary to obtain the specified penetration and when authorized by the Engineer, the Contractor may supply and operate one or more water jets and pumps, or furnish the necessary drilling apparatus and drill holes not greater than the least dimension of the pile to the proper depth and drive the piles therein. Jets shall not be used at locations where the stability of embankments or other improvements would be endangered. In addition, for steel piles, steel shells, or steel casings, when necessary to obtain the specified penetration or to prevent damage to the pile during installation, the Contractor shall provide special driving tips or heavier pile sections or take other measures as approved by the Engineer.

• The use of followers or underwater hammers for driving piles will be permitted if authorized in writing by the Engineer. When a follower or underwater hammer is used, its efficiency shall be verified by furnishing the first pile in each bent or footing sufficiently long and driving the pile without the use of a follower or underwater hammer.

The second paragraph in Section 49-1.07, "Driving," of the Standard Specifications is amended to read:

• Timber piles shall be fresh-headed and square and when permitted by the Engineer, the heads of the piles may be protected by means of heavy steel or wrought iron rings. During driving operations timber piling shall be restrained from lateral movement at intervals not to exceed 6 m over the length between the driving head and the ground surface. During driving operations, the timber pile shall be kept moving by continuous operation of the hammer. When the blow count exceeds either 2 times the blow count required in 300 mm, or 3 times the blow count required in 75 mm for the nominal resistance as shown on the plans, computed in conformance with the provisions in Section 49-1.08, "Pile Driving Acceptance Criteria," additional aids shall be used to obtain the specified penetration. These aids may include the use of water jets or drilling, where permitted, or the use of a larger hammer employing a heavy ram striking with a low velocity.

Section 49-1.08, "Bearing Value and Penetration," of the Standard Specifications is amended to read:

49-1.08 PILE DRIVING ACCEPTANCE CRITERIA

• Except for piles to be load tested, driven piles shall be driven to a value of not less than the nominal resistance shown on the plans unless otherwise specified in the special provisions or permitted in writing by the Engineer. In addition, when a pile tip elevation is specified, driven piles shall penetrate at least to the specified tip elevation, unless otherwise permitted in writing by the Engineer. Piles to be load tested shall be driven to the specified tip elevation.

• When the pile nominal resistance is omitted from the plans or the special provisions, timber piles shall be driven to a nominal resistance of 800 kN, and steel and concrete piles shall be driven to a nominal resistance of 1250 kN.

• The nominal resistance for driven piles shall be determined from the following formula in which "R_u" is the nominal resistance in kilonewtons, "E_r" is the manufacturer's rating for joules of energy developed by the hammer at the observed field drop height, and "N" is the number of hammer blows in the last 300 millimeters. (maximum value to be used for N is 100):

$$R_u = (7 * (E_r)^{1/2} * \log_{10} (0.83 * N)) - 550$$

Section 49-3.01, "Description," of the Standard Specifications is amended by deleting the fifth paragraph.

The sixth paragraph in Section 49-4.01, "Description," of the Standard Specifications is amended to read:

• Lifting anchors used in precast prestressed concrete piles without a class designation ending in "C" (corrosion resistant) shall be removed, and the holes filled in conformance with the provisions in Section 51-1.18A, "Ordinary Surface Finish."

The first and second paragraphs in Section 49-4.01, "Description," of the Standard Specifications are amended to read:

• Cast-in-place concrete piles shall consist of one of the following:

A. Steel shells driven permanently to the required nominal resistance and penetration and filled with concrete.
B. Steel casings installed permanently to the required penetration and filled with concrete.
C. Drilled holes filled with concrete.
D. Rock sockets filled with concrete.

• The drilling of holes shall conform to the provisions in these specifications. Concrete filling for cast-in-place concrete piles is designated by compressive strength and shall have a minimum 28-day compressive strength of 25 MPa. At the option of the Contractor, the combined aggregate grading for the concrete shall be either the 25-mm maximum grading, the 12.5-mm maximum grading, or the 9.5-mm maximum grading. Concrete shall conform to the provisions in Section 90, "Portland Cement Concrete," and Section 51, "Concrete Structures." Reinforcement shall conform to the provisions in Section 52, "Reinforcement."

The fourth paragraph in Section 49-4.03, "Drilled Holes," of the Standard Specifications is amended to read:

• After placing reinforcement and prior to placing concrete in the drilled hole, if caving occurs or deteriorated foundation material accumulates on the bottom of the hole, the bottom of the drilled hole shall be cleaned. The Contractor shall verify that the bottom of the drilled hole is clean.

The first and second paragraphs in Section 49-4.04, "Steel Shells," of the Standard Specifications are amended to read:

• Steel shells shall be sufficiently watertight to exclude water during the placing of concrete. The shells may be cylindrical or tapered, step-tapered, or a combination of either, with cylindrical sections.

The first paragraph in Section 49-4.05, "Inspection," of the Standard Specifications is amended to read:

• After being driven and prior to placing reinforcement and concrete therein, the steel shells shall be examined for collapse or reduced diameter at any point. Any shell which is improperly driven or broken or shows partial collapse to such an extent as to materially decrease its nominal resistance will be rejected. Rejected shells shall be removed and replaced, or a new shell shall be driven adjacent to the rejected shell. Rejected shells which cannot be removed shall be filled with concrete by the Contractor at the Contractor's expense. When a new shell is driven to replace a rejected shell, the Contractor, at the Contractor's expense, shall enlarge the footing as determined necessary by the Engineer.

The third paragraph in Section 49-6.02, "Payment," of the Standard Specifications is amended to read:

• The contract price paid per meter for cast-in-drilled-hole concrete piling shall include full compensation for furnishing all labor, materials, tools, equipment, and incidentals, and for doing all work involved in drilling holes, disposing of material resulting from drilling holes, temporarily casing holes and removing water when necessary, furnishing and placing concrete and reinforcement, and constructing reinforced concrete extensions, complete in place, to the required penetration, as shown on the plans, as specified in these specifications and in the special provisions, and as directed by the Engineer.

The seventh paragraph in Section 49-6.02, "Payment," of the Standard Specifications is amended to read

• The contract unit price paid for drive pile shall include full compensation for furnishing all labor, materials, tools, equipment, and incidentals, and for doing all the work involved in driving timber, concrete and steel piles, driving steel shells for cast-in-place concrete piles, placing filling materials for cast-in-place concrete piles and cutting off piles, all complete in place to the required nominal resistance and penetration as shown on the plans and as specified in these specifications and the special provisions, and as directed by the Engineer.

The ninth paragraph in Section 49-6.02, "Payment," of the Standard Specifications is amended to read:

• Full compensation for all jetting, drilling, providing special driving tips or heavier sections for steel piles or shells, or other work necessary to obtain the specified penetration and nominal resistance of the piles, for predrilling holes through embankment and filling the space remaining around the pile with sand or pea gravel, for disposing of material resulting from jetting, drilling or predrilling holes, and for all excavation and backfill involved in constructing concrete extensions as shown on the plans, and as specified in these specifications and the special provisions, and as directed by the Engineer shall be considered as included in the contract unit price paid for drive pile or in the contract price paid per meter for cast-in-drilled-hole concrete piling, and no additional compensation will be allowed therefor.

Section 49-6.02, "Payment," of the Standard Specifications is amended by adding the following paragraphs:

Full compensation for furnishing and placing additional testing reinforcement, for load test anchorages, and for cutting off test piles, shall be considered as included in the contract price paid for piling of the type or class shown in the Engineer's Estimate, and no additional compensation will be allowed.

No additional compensation or extension of time will be made for additional foundation investigation, installation and testing of indicator piling, cutting off piling and restoring the foundation investigation and indicator pile sites, and review of request by the Engineer

SECTION 50: PRESTRESSING CONCRETE

Issue Date: November 18, 2002

Section 50-1.02, "Drawings," of the Standard Specifications is amended by adding the following paragraph after the second paragraph:

• Each working drawing submittal shall consist of plans for a single bridge or portion thereof. For multi-frame bridges, each frame shall require a separate working drawing submittal.

Section 50-1.05, "Prestressing Steel," of the Standard Specifications is amended to read:

• Prestressing steel shall be high-tensile wire conforming to the requirements in ASTM Designation: A 421, including Supplement I; high-tensile seven-wire strand conforming to the requirements in ASTM Designation: A 416; or uncoated high-strength steel bars conforming to the requirements in ASTM Designation: A 722, including all supplementary requirements. The maximum mass requirement of ASTM Designation: A 722 will not apply.

• In addition to the requirements of ASTM Designation: A 722, for deformed bars, the reduction of area shall be determined from a bar from which the deformations have been removed. The bar shall be machined no more than necessary to remove the deformations over a length of 300 mm, and reduction will be based on the area of the machined portion.

• In addition to the requirements specified herein, epoxy-coated seven-wire prestressing steel strand shall be grit impregnated and filled in conformance with the requirements in ASTM Designation: A 882/A 882M, including Supplement I, and the following:

A. The coating material shall be on the Department's list of approved coating materials for epoxy-coated strand, available from the Transportation Laboratory.
B. The film thickness of the coating after curing shall be 381 µm to 1143 µm.
C. Prior to coating the strand, the Contractor shall furnish to the Transportation Laboratory a representative 230-g sample from each batch of epoxy coating material to be used. Each sample shall be packaged in an airtight container identified with the manufacturer's name and batch number.
D. Prior to use of the epoxy-coated strand in the work, written certifications referenced in ASTM Designation: A 882/A 882M, including a representative load-elongation curve for each size and grade of strand to be used and a copy of the quality control tests performed by the manufacturer, shall be furnished to the Engineer.
E. In addition to the requirements in Section 50-1.10, "Samples for Testing," four 1.5-m long samples of coated strand and one 1.5-m long sample of uncoated strand of each size and reel shall be furnished to the Engineer for testing. These samples, as selected by the Engineer, shall be representative of the material to be used in the work.
F. Epoxy-coated strand shall be cut using an abrasive saw.
G. All visible damage to coatings caused by shipping and handling, or during installation, including cut ends, shall be repaired in conformance with the requirements in ASTM Designation: A 882/A 882M. The patching material shall be furnished by the manufacturer of the epoxy powder and shall be applied in conformance with the manufacturer's written recommendations. The patching material shall be compatible with the original epoxy coating material and shall be inert in concrete.

• All bars in any individual member shall be of the same grade, unless otherwise permitted by the Engineer.

• When bars are to be extended by the use of couplers, the assembled units shall have a tensile strength of not less than the manufacturer's minimum guaranteed ultimate tensile strength of the bars. Failure of any one sample to meet this requirement will be cause for rejection of the heat of bars and lot of couplers. The location of couplers in the member shall be subject to approval by the Engineer.

• Wires shall be straightened if necessary to produce equal stress in all wires or wire groups or parallel lay cables that are to be stressed simultaneously or when necessary to ensure proper positioning in the ducts.

• Where wires are to be button-headed, the buttons shall be cold formed symmetrically about the axes of the wires. The buttons shall develop the minimum guaranteed ultimate tensile strength of the wire. No cold forming process shall be used that causes indentations in the wire. Buttonheads shall not contain wide open splits, more than 2 splits per head, or splits not parallel with the axis of the wire.

• Prestressing steel shall be protected against physical damage and rust or other results of corrosion at all times from manufacture to grouting or encasing in concrete. Prestressing steel that has sustained physical damage at any time shall be rejected. The development of visible rust or other results of corrosion shall be cause for rejection, when ordered by the Engineer.

• Epoxy-coated prestressing steel strand shall be covered with an opaque polyethylene sheeting or other suitable protective material to protect the strand from exposure to sunlight, salt spray, and weather. For stacked coils, the protective covering shall be draped around the perimeter of the stack. The covering shall be adequately secured; however, it should

allow for air circulation around the strand to prevent condensation under the covering. Epoxy-coated strand shall not be stored within 300 m of ocean or tidal water for more than 2 months.

- Prestressing steel shall be packaged in containers or shipping forms for the protection of the steel against physical damage and corrosion during shipping and storage. Except for epoxy-coated strand, a corrosion inhibitor which prevents rust or other results of corrosion, shall be placed in the package or form, or shall be incorporated in a corrosion inhibitor carrier type packaging material, or when permitted by the Engineer, may be applied directly to the steel. The corrosion inhibitor shall have no deleterious effect on the steel or concrete or bond strength of steel to concrete. Packaging or forms damaged from any cause shall be immediately replaced or restored to original condition.
- The shipping package or form shall be clearly marked with a statement that the package contains high-strength prestressing steel, and the type of corrosion inhibitor used, including the date packaged.
- Prestressing steel for post-tensioning which is installed in members prior to placing and curing of the concrete, and which is not epoxy-coated, shall be continuously protected against rust or other results of corrosion, until grouted, by means of a corrosion inhibitor placed in the ducts or applied to the steel in the duct. The corrosion inhibitor shall conform to the provisions specified herein.
- When steam curing is used, prestressing steel for post-tensioning shall not be installed until the steam curing is completed.
- Water used for flushing ducts shall contain either quick lime (calcium oxide) or slaked lime (calcium hydroxide) in the amount of 0.01-kg/L. Compressed air used to blow out ducts shall be oil free.
- When prestressing steel for post-tensioning is installed in the ducts after completion of concrete curing, and if stressing and grouting are completed within 10 days after the installation of the prestressing steel, rust which may form during those 10 days will not be cause for rejection of the steel. Prestressing steel installed, tensioned, and grouted in this manner, all within 10 days, will not require the use of a corrosion inhibitor in the duct following installation of the prestressing steel. Prestressing steel installed as above but not grouted within 10 days shall be subject to all the requirements in this section pertaining to corrosion protection and rejection because of rust. The requirements in this section pertaining to tensioning and grouting within 10 days shall not apply to epoxy-coated prestressing steel strand.
- Any time prestressing steel for pretensioning is placed in the stressing bed and is exposed to the elements for more than 36 hours prior to encasement in concrete, adequate measures shall be taken by the Contractor, as approved by the Engineer, to protect the steel from contamination or corrosion.
- After final fabrication of the seven-wire prestressing steel strand, no electric welding of any form shall be performed on the prestressing steel. Whenever electric welding is performed on or near members containing prestressing steel, the welding ground shall be attached directly to the steel being welded.
- Pretensioned prestressing steel shall be cut off flush with the end of the member. For epoxy-coated prestressing steel, only abrasive saws shall be used to cut the steel. The exposed ends of the prestressing steel and a 25-mm strip of adjoining concrete shall be cleaned and painted. Cleaning shall be by wire brushing or abrasive blast cleaning to remove all dirt and residue on the metal or concrete surfaces. Immediately after cleaning, the surfaces shall be covered with one application of unthinned zinc-rich primer (organic vehicle type) conforming to the provisions in Section 91, "Paint," except that 2 applications shall be applied to surfaces which will not be covered by concrete or mortar. Aerosol cans shall not be used. The paint shall be thoroughly mixed at the time of application and shall be worked into any voids in the prestressing tendons.

The thirteenth paragraph in Section 50-1.08, "Prestressing," of the Standard Specifications is amended to read:

- Prestressing steel in pretensioned members shall not be cut or released until the concrete in the member has attained a compressive strength of not less than the value shown on the plans or 28 MPa, whichever is greater. In addition to these concrete strength requirements, when epoxy-coated prestressing steel strand is used, the steel shall not be cut or released until the temperature of the concrete surrounding the strand is less than 65°C, and falling.

The fifth paragraph in Section 50-1.10, "Samples for Testing," of the Standard Specifications is amended to read:

- The following samples of materials and tendons, selected by the Engineer from the prestressing steel at the plant or jobsite, shall be furnished by the Contractor to the Engineer well in advance of anticipated use:

  A. For wire or bars, one 2-m long sample and for strand, one 1.5-m long sample, of each size shall be furnished for each heat or reel.
  B. For epoxy-coated strand, one 1.5-m long sample of uncoated strand of each size shall be furnished for each reel.

C. If the prestressing tendon is a bar, one 2-m long sample shall be furnished and in addition, if couplers are to be used with the bar, two 1.25-m long samples of bar, equipped with one coupler and fabricated to fit the coupler, shall be furnished.

The second paragraph in Section 50-1.11, "Payment," of the Standard Specifications is amended to read:

• The contract lump sum prices paid for prestressing cast-in-place concrete of the types listed in the Engineer's Estimate shall include full compensation for furnishing all labor, materials, tools, equipment, and incidentals, and for doing all work involved in furnishing, placing, and tensioning the prestressing steel in cast-in-place concrete structures, complete in place, as shown on the plans, as specified in these specifications and the special provisions, and as directed by the Engineer.

SECTION 51: CONCRETE STRUCTURES

Issue Date: April 16, 2003

The first and second paragraph in Section 51-1.06A, "Falsework Design and Drawings," of the Standard Specifications are amended to read:

• The Contractor shall submit to the Engineer working drawings and design calculations for falsework proposed for use at bridges. For bridges where the height of any portion of the falsework, as measured from the ground line to the soffit of the superstructure, exceeds 4.25 m; or where any individual falsework clear span length exceeds 4.85 m; or where provision for vehicular, pedestrian, or railroad traffic through the falsework is made; the drawings shall be signed by an engineer who is registered as a Civil Engineer in the State of California. Six sets of the working drawings and 2 copies of the design calculations shall be furnished. Additional working drawings and design calculations shall be submitted to the Engineer when specified in "Railroad Relations and Insurance" of the special provisions.

• The falsework drawings shall include details of the falsework erection and removal operations showing the methods and sequences of erection and removal and the equipment to be used. The details of the falsework erection and removal operations shall demonstrate the stability of all or any portions of the falsework during all stages of the erection and removal operations.

The seventh paragraph in Section 51-1.06A, "Falsework Design and Drawings," of the Standard Specifications is amended to read:

• In the event that several falsework plans are submitted simultaneously, or an additional plan is submitted for review before the review of a previously submitted plan has been completed, the Contractor shall designate the sequence in which the plans are to be reviewed. In such event, the time to be provided for the review of any plan in the sequence shall be not less than the review time specified above for that plan, plus 2 weeks for each plan of higher priority which is still under review. A falsework plan submittal shall consist of plans for a single bridge or portion thereof. For multi-frame bridges, each frame shall require a separate falsework plan submittal.

Section 51-1.06A, "Falsework Design and Drawings," of the Standard Specifications is amended by adding the following paragraphs:

• If structural composite lumber is proposed for use, the falsework drawings shall clearly identify the structural composite lumber members by grade (E value), species, and type. The Contractor shall provide technical data from the manufacturer showing the tabulated working stress values of the composite lumber. The Contractor shall furnish a certificate of compliance as specified in Section 6-1.07, "Certificates of Compliance," for each delivery of structural composite lumber to the project site.

• For falsework piles with a calculated loading capacity greater than 900 kN, the falsework piles shall be designed by an engineer who is registered as either a Civil Engineer or a Geotechnical Engineer in the State of California, and the calculations shall be submitted to the Engineer.

The first paragraph in Section 51-1.06A(1), "Design Loads," of the Standard Specifications is amended to read:

• The design load for falsework shall consist of the sum of dead and live vertical loads, and an assumed horizontal load. The minimum total design load for any falsework, including members that support walkways, shall be not less than 4800 N/m^2 for the combined live and dead load regardless of slab thickness.

The eighth paragraph in Section 51-1.06A(1), "Design Loads," of the Standard Specifications is amended to read:

• In addition to the minimum requirements specified in this Section 51-1.06A, falsework for box girder structures with internal falsework bracing systems using flexible members capable of withstanding tensile forces only, shall be designed to include the vertical effects caused by the elongation of the flexible member and the design horizontal load combined with the dead and live loads imposed by concrete placement for the girder stems and connected bottom slabs. Falsework comprised of individual steel towers with bracing systems using flexible members capable of withstanding tensile forces only to resist overturning, shall be exempt from these additional requirements.

The third paragraph in Section 51-1.06B, "Falsework Construction," of the Standard Specifications is amended to read:

• When falsework is supported on piles, the piles shall be driven and the actual nominal resistance assessed in conformance with the provisions in Section 49, "Piling."

Section 51-1.06B, "Falsework Construction," of the Standard Specifications is amended by adding the following paragraphs:

• For falsework piles with a calculated nominal resistance greater than 1800 kN, the Contractor shall conduct dynamic monitoring of pile driving and generate field acceptance criteria based on a wave equation analysis. These analyses shall be signed by an engineer who is registered as a Civil Engineer in the State of California and submitted to the Engineer prior to completion of falsework erection.

• Prior to the placement of falsework members above the stringers, the final bracing system for the falsework shall be installed.

Section 51-1.06C, "Removing Falsework," of the Standard Specifications is amended by adding the following paragraph:

• The falsework removal operation shall be conducted in such a manner that any portion of the falsework not yet removed remains in a stable condition at all times.

The sixth paragraph in Section 51-1.09, "Placing Concrete," of the Standard Specifications is amended to read:

• Vibrators used to consolidate concrete containing epoxy-coated bar reinforcement or epoxy-coated prestressing steel shall have a resilient covering to prevent damage to the epoxy-coating on the reinforcement or prestressing steel.

The table in the ninth paragraph of Section 51-1.12H(1), "Plain and Fabric Reinforced Elastomeric Bearing Pads," of the Standard Specifications is amended to read:

Tensile strength, percent	-15
Elongation at break, percent	-40; but not less than 300% total elongation of the material
Hardness, points	+10

The first sentence of the fourth paragraph in Section 51-1.17, "Finish Bridge Decks," of the Standard Specifications is amended to read:

• The smoothness of completed roadway surfaces of structures, approach slabs and the adjacent 15 m of approach pavement, and the top surfaces of concrete decks which are to be covered with another material, will be tested by the Engineer with a bridge profilograph in conformance with the requirements in California test 547 and the requirements herein.

Section 51-1.17, "Finishing Bridge Decks," of the Standard Specifications is amended by deleting the seventh, thirteenth and fourteenth paragraphs.

The fourteenth paragraph in Section 51-1.23, "Payment," of the Standard Specifications is amended by deleting "and injecting epoxy in cracks".

SECTION 52: REINFORCEMENT

Issue Date: December 31, 2001

The third paragraph in Section 52-1.04, "Inspection," of the Standard Specifications is amended to read:

• A Certificate of Compliance conforming to the provisions in Section 6-1.07, "Certificates of Compliance," shall also be furnished for each shipment of epoxy-coated bar reinforcement or wire reinforcement certifying that the coated reinforcement conforms to the requirements in ASTM Designation: A 775/A 775M or A 884/A 884M, respectively, and the provisions in Section 52-1.02B, "Epoxy-coated Reinforcement." The Certificate of Compliance shall include all of the certifications specified in ASTM Designation: A 775/A 775M or A 884/A 884M respectively, and a statement that the coating material has been prequalified by acceptance testing performed by the Valley Forge Laboratories, Inc., Devon, Pennsylvania.

The third paragraph in Section 52-1.08C, "Mechanical Butt Splices," of the Standard Specifications is amended to read:

• The total slip of the reinforcing bars within the splice sleeve after loading in tension to 200 MPa and relaxing to 20 MPa shall not exceed the values listed in the following table. The slip shall be measured between gage points that are clear of the splice sleeve.

Reinforcing Bar Number	Total Slip (μm)
13	250
16	250
19	250
22	350
25	350
29	350
32	450
36	450
43	600
57	750

The first paragraph in Section 52-1.08C(5), "Sleeve-Lockshear Bolt Mechanical Butt Splices," of the Standard Specifications is amended to read:

• The sleeve-lockshear bolt type of mechanical butt splices shall consist of a seamless steel sleeve, center hole with centering pin, and bolts that are tightened until the bolt heads shear off with the bolt ends left embedded in the reinforcing bars. The seamless steel sleeve shall be either formed into a V configuration or shall have 2 serrated steel strips welded to the inside of the sleeve.

Section 52-1.08F, "Nondestructive Splice Tests," of the Standard Specifications is amended by deleting the seventh paragraph.

SECTION 55: STEEL STRUCTURES

Issue Date: December 31, 2001

Section 55-3.14, "Bolted Connections," of the Standard Specifications is amended by adding the following after the ninth paragraph:

• If a torque multiplier is used in conjunction with a calibrated wrench as a method for tightening fastener assemblies to the required tension, both the multiplier and the wrench shall be calibrated together as a system. The same length input and output sockets and extensions that will be used in the work shall also be included in the calibration of the system. The manufacturer's torque multiplication ratio shall be adjusted during calibration of the system, such that when this adjusted ratio is multiplied by the actual input calibrated wrench reading, the product is a calculated output torque that is within

2 percent of the true output torque. When this system is used in the work to perform any installation tension testing, rotational capacity testing, fastener tightening, or tension verification, it shall be used, intact as calibrated.

The sixth paragraph of Section 55-4.02, "Payment," of the Standard Specifications is amended to read:

- If a portion or all of the structural steel is fabricated more than 480 air line kilometers from both Sacramento and Los Angeles, additional shop inspection expenses will be sustained by the State. Whereas it is and will be impracticable and extremely difficult to ascertain and determine the actual increase in these expenses, it is agreed that payment to the Contractor for furnishing the structural steel from each fabrication site located more than 480 air line kilometers from both Sacramento and Los Angeles will be reduced $5000 or by an amount computed at $0.044 per kilogram of structural steel fabricated, whichever is greater, or in the case of each fabrication site located more than 4800 air line kilometers from both Sacramento and Los Angeles, payment will be reduced $8000 or by $0.079 per kilogram of structural steel fabricated, whichever is greater.

SECTION 56: SIGNS

Issue Date: December 31, 2001

Section 56-1.01, "Description," of the Standard Specifications is amended by deleting the third paragraph.

The sixth through the thirteenth paragraphs in Section 56-1.03, "Fabrication," of the Standard Specifications are amended to read:

- High-strength bolted connections, where shown on the plans, shall conform to the provisions in Section 55-3.14, "Bolted Connections," except that only fastener assemblies consisting of a high-strength bolt, nut, hardened washer, and direct tension indicator shall be used.
- High-strength fastener assemblies, and any other bolts, nuts, and washers attached to sign structures shall be zinc-coated by the mechanical deposition process.
- An alternating snugging and tensioning pattern for anchor bolts and high-strength bolted splices shall be used. Once tensioned, high-strength fastener components and direct tension indicators shall not be reused.
- For bolt diameters less than 10 mm, the diameter of the bolt hole shall be not more than 0.80-mm larger than the nominal bolt diameter. For bolt diameters greater than or equal to 10 mm, the diameter of the bolt hole shall be not more than 1.6 mm larger than the nominal bolt diameter.
- Sign structures shall be fabricated into the largest practical sections prior to galvanizing.
- Ribbed sheet metal panels for box beam closed truss sign structures shall be fastened to the truss members by cap screws or bolts as shown on the plans, or by 4.76 mm stainless steel blind rivets conforming to Industrial Fasteners Institute, Standard IFI-114, Grade 51. The outside diameter of the large flange rivet head shall be not less than 15.88 mm in diameter. Web splices in ribbed sheet metal panels may be made with similar type blind rivets of a size suitable for the thickness of material being connected.
- Spalling or chipping of concrete structures shall be repaired by the Contractor at the Contractor's expense.
- Overhead sign supports shall have an aluminum identification plate permanently attached near the base, adjacent to the traffic side on one of the vertical posts, using either stainless steel rivets or stainless steel screws. As a minimum, the information on the plate shall include the name of the manufacturer, the date of manufacture and the contract number.

SECTION 59: PAINTING

Issue Date: December 31, 2001

Section 59-2.01, "General," of the Standard Specifications is amended by adding the following paragraphs after the first paragraph:

- Unless otherwise specified, no painting Contractors or subcontractors will be permitted to commence work without having the following current "SSPC: The Society for Protective Coatings" (formerly the Steel Structures Painting Council) certifications in good standing:

A. For cleaning and painting structural steel in the field, certification in conformance with the requirements in Qualification Procedure No. 1, "Standard Procedure For Evaluating Painting Contractors (Field Application to Complex Industrial Structures)" (SSPC-QP 1).
B. For removing paint from structural steel, certification in conformance with the requirements in Qualification Procedure No. 2, "Standard Procedure For Evaluating Painting Contractors (Field Removal of Hazardous Coatings from Complex Structures)" (SSPC-QP 2).
C. For cleaning and painting structural steel in a permanent painting facility, certification in conformance with the requirements in Qualification Procedure No. 3, "Standard Procedure For Evaluating Qualifications of Shop Painting Applicators" (SSPC-QP 3). The AISC's Sophisticated Paint Endorsement (SPE) quality program will be considered equivalent to SSPC-QP 3.

The third paragraph of Section 59-2.03, "Blast Cleaning," of the Standard Specifications is amended to read:

• Exposed steel or other metal surfaces to be blast cleaned shall be cleaned in conformance with the requirements in Surface Preparation Specification No. 6, "Commercial Blast Cleaning," of the "SSPC: The Society for Protective Coatings." Blast cleaning shall leave all surfaces with a dense, uniform, angular anchor pattern of not less than 35 µm as measured in conformance with the requirements in ASTM Designation: D 4417.

The first paragraph of Section 59-2.06, "Hand Cleaning," of the Standard Specifications is amended to read:

• Dirt, loose rust and mill scale, or paint which is not firmly bonded to the surfaces shall be removed in conformance with the requirements in Surface Preparation Specification No. 2, "Hand Tool Cleaning," of the "SSPC: The Society for Protective Coatings." Edges of old remaining paint shall be feathered.

The fourth paragraph of Section 59-2.12, "Painting," of the Standard Specifications is amended to read:

• The dry film thickness of the paint will be measured in place with a calibrated Type 2 magnetic film thickness gage in conformance with the requirements of specification SSPC-PA2 of the "SSPC: The Society for Protective Coatings."

SECTION 75: MISCELLANEOUS METAL

Issue Date: December 31, 2001

The table in the tenth paragraph of Section 75-1.02, "Miscellaneous Iron and Steel," of the Standard Specifications is amended to read:

Material	Specification
Steel bars, plates and shapes	ASTM Designation: A 36/A 36M or A 575, A 576 (AISI or M Grades 1016 through 1030 except Grade 1017)
Steel fastener components for general applications:	
Bolts and studs	ASTM Designation: A 307
Headed anchor bolts	ASTM Designation: A 307, Grade B, including S1 supplementary requirements
Nonheaded anchor bolts	ASTM Designation: A 307, Grade C, including S1 supplementary requirements and S1.6 of AASHTO Designation: M 314 supplementary requirements or AASHTO Designation: M 314, Grade 36 or 55, including S1 supplementary requirements
High-strength bolts and studs, threaded rods, and nonheaded anchor bolts	ASTM Designation: A 449, Type 1
Nuts	ASTM Designation: A 563, including Appendix X1*
Washers	ASTM Designation: F 844
Components of high-strength steel fastener assemblies for use in structural steel joints:	
Bolts	ASTM Designation: A 325, Type 1
Tension control bolts	ASTM Designation: F 1852, Type 1
Nuts	ASTM Designation: A 563, including Appendix X1*
Hardened washers	ASTM Designation: F 436, Type 1, Circular, including S1 supplementary requirements
Direct tension indicators	ASTM Designation: F 959, Type 325, zinc-coated
Stainless steel fasteners (Alloys 304 & 316) for general applications:	
Bolts, screws, studs, threaded rods, and nonheaded anchor bolts	ASTM Designation: F 593 or F 738M
Nuts	ASTM Designation: F 594 or F 836M
Washers	ASTM Designation: A 240/A 240M and ANSI B 18.22M
Carbon-steel castings	ASTM Designation: A 27/A 27M, Grade 65-35 [450-240], Class 1
Malleable iron castings	ASTM Designation: A 47, Grade 32510 or A 47M, Grade 22010
Gray iron castings	ASTM Designation: A 48, Class 30B
Ductile iron castings	ASTM Designation: A 536, Grade 65-45-12
Cast iron pipe	Commercial quality
Steel pipe	Commercial quality, welded or extruded
Other parts for general applications	Commercial quality

* Zinc-coated nuts that will be tightened beyond snug or wrench tight shall

be furnished with a dyed dry lubricant conforming to Supplementary Requirement S2 in ASTM Designation: A 563.

The table in the eighteenth paragraph of Section 75-1.03, "Miscellaneous Bridge Metal," of the Standard Specifications is amended to read:

Stud Diameter (millimeters)	Sustained Tension Test Load (kilonewtons)
29.01-33.00	137.9
23.01-29.00	79.6
21.01-23.00	64.1
* 18.01-21.00	22.2
15.01-18.00	18.2
12.01-15.00	14.2
9.01-12.00	9.34
6.00-9.00	4.23

* Maximum stud diameter permitted for mechanical expansion anchors.

The table in the nineteenth paragraph of Section 75-1.03, "Miscellaneous Bridge Metal," of the Standard Specifications is amended to read:

Stud Diameter (millimeters)	Ultimate Tensile Load (kilonewtons)
30.01-33.00	112.1
27.01-30.00	88.1
23.01-27.00	71.2
20.01-23.00	51.6
16.01-20.00	32.0
14.01-16.00	29.4
12.00-14.00	18.7

The table in the twenty-second paragraph of Section 75-1.03, "Miscellaneous Bridge Metal," of the Standard Specifications is amended to read:

Installation Torque Values, (newton meters)

Stud Diameter (millimeters)	Shell Type Mechanical Expansion Anchors	Integral Stud Type Mechanical Expansion Anchors	Resin Capsule Anchors and Cast-in-Place Inserts
29.01-33.00	—	—	540
23.01-29.00	—	—	315
21.01-23.00	—	—	235
18.01-21.00	110	235	200
15.01-18.00	45	120	100
12.01-15.00	30	65	40
9.01-12.00	15	35	24
6.00-9.00	5	10	—

SECTION 83: RAILINGS AND BARRIERS

Issue Date: June 13, 2002

The ninth paragraph in Section 83-1.02B, "Metal Beam Guard Railing," of the Standard Specifications is amended to read:

- The grades and species of wood posts and blocks shall be No. 1 timbers (also known as No. 1 structural) Douglas fir or No. 1 timbers Southern yellow pine. Wood posts and blocks shall be graded in conformance with the provisions in Section 57-2, "Structural Timber," of the Standard Specifications, except allowances for shrinkage after mill cutting shall in no case exceed 5 percent of the American Lumber Standards minimum sizes, at the time of installation.

The eleventh paragraph in Section 83-1.02B, "Metal Beam Guard Railing," of the Standard Specifications is amended to read:

- Wood posts and blocks shall be pressure treated after fabrication in conformance with the provisions in Section 58, "Preservative Treatment of Lumber, Timber and Piling," of the Standard Specifications with creosote, creosote coal tar solution, creosote petroleum solution (50-50), pentachlorophenol in hydrocarbon solvent, copper naphthenate, ammoniacal copper arsenate, or ammoniacal copper zinc arsenate. In addition to the preservatives listed above, Southern yellow pine may also be pressure treated with chromated copper arsenate. When other than one of the creosote processes is used, blocks shall have a minimum retention of 6.4 Kg/m^3, and need not be incised.

SECTION 85: PAVEMENT MARKERS

Issue Date: May 16, 2003

The second through fifth paragraphs in Section 85-1.03, "Sampling, Tolerances and Packaging," of the Standard Specifications are amended to read:

Sampling

- Twenty markers selected at random will constitute a representative sample for each lot of markers.
- The lot size shall not exceed 25000 markers.

Tolerances

- Three test specimens will be randomly selected from the sample for each test and tested in conformance with these specifications. Should any one of the 3 specimens fail to conform with the requirements in these specifications, 6 additional specimens will be tested. The failure of any one of these 6 specimens shall be cause for rejection of the entire lot or shipment represented by the sample.
- The entire sample of retroreflective pavement markers will be tested for reflectance. The failure of 10 percent or more of the original sampling shall be cause for rejection.

Section 85-1.04, "Non-Reflective Pavement Markers," of the Standard Specifications is amended to read:

85-1.04 Non-Reflective Pavement Markers

- Non-reflective pavement markers (Types A and AY) shall be, at the option of the Contractor, either ceramic or plastic conforming to these specifications.
- The top surface of the marker shall be convex with a gradual change in curvature. The top, bottom and sides shall be free of objectionable marks or discoloration that will affect adhesion or appearance.
- The bottom of markers shall have areas of integrally formed protrusions or indentations, which will increase the effective bonding surface area of adhesive. The bottom surface of the marker shall not deviate more than 1.5 mm from a flat surface. The areas of protrusion shall have faces parallel to the bottom of the marker and shall project approximately one mm from the bottom.

The second through fourth paragraphs of Section 85-1.04A, "Non-Reflective Pavement Markers (Ceramic)," of the Standard Specifications are deleted.

The table in the fifth paragraph in Section 85-1.04A, "Non-Reflective Pavement Markers (Ceramic)," of the Standard Specifications is amended to read:

Testing

- Tests shall be performed in conformance with the requirements in California test 669.

Test	Test Description	Requirement
a	Bond strength	4.8 MPa, min.
b	Glaze thickness	180 µm, min.
c	Hardness	6 Moh, min.
d	Luminance factor, Type A, white markers only, glazed surface	75, min.
e	Yellowness index, Type A, white markers only, glazed surface	7, max.
f	Color-yellow, Type AY, yellow markers only. The chromaticity coordinates shall be within a color box defined in CTM 669	Pass
g	Compressive strength	6700 N, min.
h	Water absorption	2.0 %, max.
i	Artificial weathering, 500 hours exposure, yellowness index	20, max.

Section 85-1.04B, "Non-Reflective Pavement Markers (Plastic)," of the Standard Specifications is amended to read:

85-1.04B Non-Reflective Pavement Markers (Plastic)

- Plastic non-reflective pavement markers Types A and AY shall be, at the option of the Contractor, either polypropylene or acrylonitrile-butadiene-styrene (ABS) plastic type.
- Plastic markers shall conform to the testing requirements specified in Section 85-1.04A, "Non-Reflective Pavement Markers (Ceramic)," except that Tests a, b, c, and h shall not apply. The plastic markers shall not be coated with substances that interfere with the ability of the adhesive bonding to the marker.

The sixth and seventh paragraphs in Section 85-1.05, "Retroreflective Pavement Markers," of the Standard Specifications are amended to read:

Testing

- Tests shall be performed in conformance with the requirements in California test 669.

Test Description	Requirement		
Bond strength[a]	3.4 MPa, min.		
Compressive strength[b]	8900 N, min.		
Abrasion resistance, marker must meet the respective specific intensity minimum requirements after abrasion.	Pass		
Water Soak Resistance	No delamination of the body or lens system of the marker nor loss of reflectance		
	Specific Intensity		
Reflectance	Clear	Yellow	Red
0° Incidence Angle, min.	3.0	1.5	0.75
20° Incidence Angle, min.	1.2	0.60	0.30
After one year field evaluation	0.30	0.15	0.08

a Failure of the marker body or filler material prior to reaching 3.4 MPa shall constitute a failing bond strength test.

b Deformation of the marker of more than 3 mm at a load of less than 8900 N or delamination of the shell and the filler material of more than 3 mm regardless of the load required to break the marker shall be cause for rejection of the markers as specified in Section 85-1.03, "Sampling, Tolerances and Packaging."

- Pavement markers to be placed in pavement recesses shall conform to the above requirements for retroreflective pavement markers except that the minimum compressive strength requirement shall be 5338 N.

The eighth paragraph of Section 85-1.05, "Retrorelective Pavement Markers" of the Standard Specifications is deleted.

The eighth paragraph in Section 85-1.06, "Replacement," of the Standard Specifications is amended to read:

- Epoxy adhesive shall not be used to apply non-reflective plastic pavement markers.

SECTION 86: SIGNALS, LIGHTING AND ELECTRICAL SYSTEMS

Issue Date: June 19, 2003

The seventh paragraph of Section 86-2.03, "Foundations," of the Standard Specifications is amended to read:

- Forms shall be true to line and grade. Tops of foundations for posts and standards, except special foundations, shall be finished to curb or sidewalk grade or as directed by the Engineer. Forms shall be rigid and securely braced in place. Conduit ends and anchor bolts shall be placed in proper position and to proper height, and anchor bolts shall be held in place by means of rigid top and bottom templates. The bottom template shall be made of steel. The bottom template shall provide proper spacing and alignment of the anchor bolts near their bottom embedded end. The bottom template shall be installed before placing footing concrete. Anchor bolts shall not be installed more than 1:40 from vertical.

Section 86-2.03, "Foundations," of the Standard Specifications is amended by deleting the eighth paragraph.

The twelfth paragraph of Section 86-2.03, "Foundations," of the Standard Specifications is amended to read:

- Plumbing of the standards shall be accomplished by adjusting the leveling nuts before placing the mortar or before the foundation is finished to final grade. Shims, or other similar devices shall not be used for plumbing or raking of posts, standards or pedestals. After final adjustments of both top nuts and leveling nuts on anchorage assemblies have been made, firm contact shall exist between all bearing surfaces of the anchor bolt nuts, washers, and the base plate.

The first paragraph of Section 86-2.04, "Standards, Steel Pedestals and Posts," of the Standard Specifications is amended to read:

• Standards for traffic signals and lighting, and steel pedestals for cabinets and other similar equipment, shall be located as shown on the plans. Bolts, nuts and washers, and anchor bolts for use in signal and lighting support structures shall conform to the provisions in Section 55-2, "Materials." Except when bearing-type connections or slipbases are specified, high-strength bolted connections shall conform to the provisions in Section 55-3.14, "Bolted Connections." Welding, nondestructive testing (NDT) of welds, and acceptance and repair criteria for NDT of steel members shall conform to the requirements of AWS D1.1 and the contract special provisions.

The second paragraph of Section 86-2.04, "Standards, Steel Pedestals and Posts," of the Standard Specifications is amended to read:

• On each lighting standard except Type 1, one rectangular corrosion resistant metal identification tag shall be permanently attached above the hand hole, near the base of the standard, using stainless steel rivets. On each signal pole support, two corrosion resistant metal identification tags shall be attached, one above the hand hole near the base of the vertical standard and one on the underside of the signal mast arm near the arm plate. As a minimum, the information on each identification tag shall include the name of the manufacturer, the date of manufacture, the identification number as shown on the plans, the contract number, and a unique identification code assigned by the fabricator. This number shall be traceable to a particular contract and the welds on that component, and shall be readable after the support structure is coated and installed. The lettering shall be a minimum of 7 mm high. The information may be either depressed or raised, and shall be legible.

The fourth paragraph of Section 86-2.04, "Standards, Steel Pedestals and Posts" of the Standard Specifications is amended to read:

• Ferrous metal parts of standards, with shaft length of 4.6 m and longer, shall conform to the details shown on the plans, the provisions in Section 55, "Steel Structures," except as otherwise noted, and the following requirements:

Except as otherwise specified, standards shall be fabricated from sheet steel of weldable grade having a minimum yield strength, after fabrication, of 276 MPa.

Certified test reports which verify conformance to the minimum yield strength requirements shall be submitted to the Engineer. The test reports may be the mill test reports for the as-received steel or, when the as-received steel has a lower yield strength than required, the Contractor shall provide supportive test data which provides assurance that the Contractor's method of cold forming will consistently increase the tensile properties of the steel to meet the specified minimum yield strength. The supportive test data shall include tensile properties of the steel after cold forming for specific heats and thicknesses.

When a single-ply 8-mm thick pole is specified, a 2-ply pole with equivalent section modulus may be substituted.

Standards may be fabricated of full-length sheets or shorter sections. Each section shall be fabricated from not more than 2 pieces of sheet steel. Where 2 pieces are used, the longitudinal welded seams shall be directly opposite one another. When the sections are butt-welded together, the longitudinal welded seams on adjacent sections shall be placed to form continuous straight seams from base to top of standard.

Butt-welded circumferential joints of tubular sections requiring CJP groove welds shall be made using a metal sleeve backing ring inside each joint. The sleeve shall be 3-mm nominal thickness, or thicker, and manufactured from steel having the same chemical composition as the steel in the tubular sections to be joined. When the sections to be joined have different specified minimum yield strengths, the steel in the sleeve shall have the same chemical composition as the tubular section having the higher minimum yield strength. The width of the metal sleeve shall be consistent with the type of NDT chosen and shall be a minimum width of 25 mm. The sleeve shall be centered at the joint and be in contact with the tubular section at the point of the weld at time of fit-up.

Welds shall be continuous.

The weld metal at the transverse joint shall extend to the sleeve, making the sleeve an integral part of the joint.

During fabrication, longitudinal seams on vertical tubular members of cantilevered support structures shall be centered on and along the side of the pole that the pole plate is located. Longitudinal seams on horizontal tubular members, including signal and luminaire arms, shall be within +/-45 degrees of the bottom of the arm.

The longitudinal welds in steel tubular sections may be made by the electric resistance welding process.

Longitudinal seam welds shall have 60 percent minimum penetration, except that within 150 mm of circumferential welds, longitudinal seam welds shall be CJP groove welds. In addition, longitudinal seam welds on lighting support structures having telescopic pole segment splices shall be CJP groove welds on the female end for a length on each end equal to the designated slip fit splice length plus 150 mm.

Exposed circumferential welds, except fillet and fatigue-resistant welds, shall be ground flush (-0, +2mm) with the base metal prior to galvanizing or painting.

Circumferential welds and base plate-to-pole welds may be repaired only one time without written permission from the Engineer.

Exposed edges of the plates that make up the base assembly shall be finished smooth and exposed corners of the plates shall be broken unless otherwise shown on the plans. Shafts shall be provided with slip-fitter shaft caps.

Flatness of surfaces of 1) base plates that are to come in contact with concrete, grout, or washers and leveling nuts 2) plates in high-strength bolted connections, 3) plates in joints where cap screws are used to secure luminaire and signal arms, and 4) plates used for breakaway slip base assemblies shall conform to the requirements of ASTM A6.

Standards shall be straight, with a permissive variation not to exceed 25 mm measured at the midpoint of a 9-m or 11-m standard and not to exceed 20 mm measured at the midpoint of a 5-m through 6-m standard. Variation shall not exceed 25 mm at a point 4.5 m above the base plate for Type 35 and Type 36 standards.

Zinc-coated nuts used on fastener assemblies having a specified preload (obtained by specifying a prescribed tension, torque value, or degree of turn) shall be provided with a colored lubricant that is clean and dry to the touch. The color of the lubricant shall be in contrast to the zinc coating on the nut so that the presence of the lubricant is visually obvious. In addition, either the lubricant shall be insoluble in water, or fastener components shall be shipped to the job site in a sealed container.

No holes shall be made in structural members unless the holes are shown on the plans or are approved in writing by the Engineer.

Standards with an outside diameter of 300 mm or less shall be round. Standards with an outside diameter greater than 300 mm shall be round or multisided. Multisided standards shall have a minimum of 12 sides which shall be convex and shall have a minimum bend radius of 100 mm.

Mast arms for standards shall be fabricated from material as specified for standards, and shall conform to the dimensions shown on the plans.

The cast steel option for slip bases shall be fabricated from material conforming to the requirements in ASTM Designation: A 27/A 27M, Grade 70-40. Other comparable material may be used if written permission is given by the Engineer. The casting tolerances shall be in conformance with the Steel Founder's Society of America recommendations (green sand molding).

One casting from each lot of 50 castings or less shall be subject to radiographic inspection, in conformance with the requirements in ASTM Designation: E 94. The castings shall comply with the acceptance criteria severity level 3 or better for the types and categories of discontinuities in conformance with the requirements in ASTM Designations: E 186 and E 446. If the one casting fails to pass the inspection, 2 additional castings shall be radiographed. Both of these castings shall pass the inspection or the entire lot of 50 will be rejected.

Material certifications, consisting of physical and chemical properties, and radiographic films of the castings shall be filed at the manufacturer's office. These certifications and films shall be available for inspection upon request.

High-strength bolts, nuts and flat washers used to connect slip base plates shall conform to the requirements in ASTM Designation: A 325 or A 325M and shall be galvanized in conformance with the provisions in Section 75-1.05, "Galvanizing."

Plate washers shall be fabricated by saw cutting and drilling steel plate conforming to the requirements in AISI Designation: 1018, and be galvanized in conformance with the provisions in Section 75-1.05, "Galvanizing." Prior to galvanizing, burrs and sharp edges shall be removed and holes shall be chamfered sufficiently on each side to allow the bolt head to make full contact with the washer without tension on the bolt.

High-strength cap screws shown on the plans for attaching arms to standards shall conform to the requirements in ASTM Designation: A 325, A 325M or ASTM Designation: A 449, and shall comply with the mechanical requirements in ASTM Designation: A 325 or A 325M after galvanizing. The cap screws shall be galvanized in conformance with the provisions in Section 75-1.05, "Galvanizing." The threads of the cap screws shall be coated with a colored lubricant that is clean and dry to the touch. The color of the lubricant shall be in contrast to the color of the zinc coating on the cap screw so that presence of the lubricant is visually obvious. In addition, either the lubricant shall be insoluble in water, or fastener components shall be shipped to the job site in a sealed container.Unless otherwise specified, bolted connections attaching signal or luminaire arms to poles shall be considered slip critical. Galvanized faying surfaces on plates on luminaire and signal arms and matching plate surfaces on poles shall be roughened by hand using a wire brush prior to assembly and shall conform to the requirements for Class C surface conditions for slip-critical connections in "Specification for Structural Joints Using ASTM A 325 or A 490 Bolts," a specification approved by the Research Council on Structural Connections (RCSC) of the Engineering Foundation. For faying surfaces required to be painted, the paint shall be an approved type, brand, and thickness that has been tested and approved according to the RCSC Specification as a Class B coating.

Samples of fastener components will be randomly taken from each production lot by the Engineer and submitted, along with test reports required by appropriate ASTM fastener specifications, for QA testing and evaluation. Sample sizes for each fastener component shall be as determined by the Engineer.

The seventh paragraph of 86-2.04, "Standards, Steel Pedestals and Posts" of the Standard Specifications is amended to read:

• To avoid interference of arm plate-to-tube welds with cap screw heads, and to ensure cap screw heads can be turned using conventional installation tools, fabricators shall make necessary adjustments to details prior to fabrication and properly locate the position of arm tubes on arm plates during fabrication.

Section 86-8.01, "Payment," of the Standard Specifications is amended by adding the following paragraph after the first paragraph:

• If a portion or all of the poles for signal, lighting and electrical systems pursuant to Standard Specification Section 86, "Signals, Lighting and Electrical Systems," is fabricated more than 480 air line kilometers from both Sacramento and Los Angeles, additional shop inspection expenses will be sustained by the State. Whereas it is and will be impracticable and extremely difficult to ascertain and determine the actual increase in such expenses, it is agreed that payment to the Contractor for furnishing such items from each fabrication site located more than 480 air line kilometers from both Sacramento and Los Angeles will be reduced $5000; in addition, in the case where a fabrication site is located more than 4800 air line kilometers from both Sacramento and Los Angeles, payment will be reduced an additional $3000 per each fabrication site ($8000 total per site).

SECTION 88: ENGINEERING FABRIC

Issue Date: January 15, 2002

Section 88-1.02, "Pavement Reinforcing Fabric," of the Standard Specifications is amended to read:

• Pavement reinforcing fabric shall be 100 percent polypropylene staple fiber fabric material, needle-punched, thermally bonded on one side, and conform to the following:

Specification	Requirement
Weight, grams per square meter ASTM Designation: D 5261	140
Grab tensile strength (25-mm grip), kilonewtons, min. in each direction ASTM Designation: D 4632	0.45
Elongation at break, percent min. ASTM Designation: D 4632	50
Asphalt retention by fabric, grams per square meter. (Residual Minimum) ASTM Designation: D 6140	900

Note: Weight, grab, elongation and asphalt retention are based on Minimum Average Roll Value (MARV)

SECTION 90: PORTLAND CEMENT CONCRETE

Issue Date: June 19, 2003

Section 90, "Portland Cement Concrete," of the Standard Specifications is amended to read:

SECTION 90: PORTLAND CEMENT CONCRETE

90-1 GENERAL

90-1.01 DESCRIPTION

• Portland cement concrete shall be composed of cementitious material, fine aggregate, coarse aggregate, admixtures if used, and water, proportioned and mixed as specified in these specifications.

• The Contractor shall determine the mix proportions for concrete in conformance with these specifications. Unless otherwise specified, cementitious material shall be a combination of cement and mineral admixture. Cementitious material shall be either:

1. "Type IP (MS) Modified" cement; or
2. A combination of "Type II Modified" portland cement and mineral admixture; or
3. A combination of Type V portland cement and mineral admixture.

• Type III portland cement shall be used only as allowed in the special provisions or with the approval of the Engineer.

• Class 1 concrete shall contain not less than 400 kg of cementitious material per cubic meter.

• Class 2 concrete shall contain not less than 350 kg of cementitious material per cubic meter.

• Class 3 concrete shall contain not less than 300 kg of cementitious material per cubic meter.

• Class 4 concrete shall contain not less than 250 kg of cementitious material per cubic meter.

• Minor concrete shall contain not less than 325 kg of cementitious material per cubic meter unless otherwise specified in these specifications or the special provisions.

• Unless otherwise designated on the plans or specified in these specifications or the special provisions, the amount of cementitious material used per cubic meter of concrete in structures or portions of structures shall conform to the following:

Use	Cementitious Material Content (kg/m3)
Concrete designated by compressive strength:	
Deck slabs and slab spans of bridges	400 min., 475 max.
Roof sections of exposed top box culverts	400 min., 475 max.
Other portions of structures	350 min., 475 max.
Concrete not designated by compressive strength:	
Deck slabs and slab spans of bridges	400 min.
Roof sections of exposed top box culverts	400 min.
Prestressed members	400 min.
Seal courses	400 min.
Other portions of structures	350 min.
Concrete for precast members	350 min., 550 max.

• Whenever the 28-day compressive strength shown on the plans is greater than 25 MPa, the concrete shall be designated by compressive strength. If the plans show a 28-day compressive strength that is 28 MPa or greater, an additional 14 days will be allowed to obtain the specified strength. The 28-day compressive strengths shown on the plans that are 25 MPa or less are shown for design information only and are not a requirement for acceptance of the concrete.

• Concrete designated by compressive strength shall be proportioned such that the concrete will attain the strength shown on the plans or specified in the special provisions.

• Before using concrete for which the mix proportions have been determined by the Contractor, or in advance of revising those mix proportions, the Contractor shall submit in writing to the Engineer a copy of the mix design.

• Compliance with cementitious material content requirements will be verified in conformance with procedures described in California Test 518 for cement content. For testing purposes, mineral admixture shall be considered to be cement. Batch proportions shall be adjusted as necessary to produce concrete having the specified cementitious material content.

• If any concrete has a cementitious material, portland cement, or mineral admixture content that is less than the minimum required, the concrete shall be removed. However, if the Engineer determines that the concrete is structurally adequate, the concrete may remain in place and the Contractor shall pay to the State $0.55 for each kilogram of cementitious material, portland cement, or mineral admixture that is less than the minimum required. The Department may deduct the amount from any moneys due, or that may become due, the Contractor under the contract. The deductions will not be made unless the difference between the contents required and those actually provided exceeds the batching tolerances permitted by Section 90-5, "Proportioning." No deductions will be made based on the results of California Test 518.

• The requirements of the preceding paragraph shall not apply to minor concrete or commercial quality concrete.

90-2 MATERIALS

90-2.01 CEMENT

• Unless otherwise specified, cement shall be either "Type IP (MS) Modified" cement, "Type II Modified" portland cement or Type V portland cement.

• "Type IP (MS) Modified" cement shall conform to the requirements for Type IP (MS) cement in ASTM Designation: C 595, and shall be comprised of an intimate and uniform blend of Type II cement and not more than 35 percent by mass of mineral admixture. The type and minimum amount of mineral admixture used in the manufacture of "Type IP (MS) Modified" cement shall be in conformance with the provisions in Section 90-4.08, "Required Use of Mineral Admixtures."

• "Type II Modified" portland cement shall conform to the requirements for Type II portland cement in ASTM Designation: C 150.

• In addition, "Type IP (MS) Modified" cement and "Type II Modified" portland cement shall conform to the following requirements:

A. The cement shall not contain more than 0.60-percent by mass of alkalies, calculated as the percentage of Na_2O plus 0.658 times the percentage of K_2O, when determined by either direct intensity flame photometry or by the atomic absorption method. The instrument and procedure used shall be qualified as to precision and accuracy in conformance with the requirements in ASTM Designation: C 114;
B. The autoclave expansion shall not exceed 0.50-percent; and
C. Mortar, containing the cement to be used and Ottawa sand, when tested in conformance with California test 527, shall not expand in water more than 0.010 percent and shall not contract in air more than 0.048 percent, except that when cement is to be used for precast prestressed concrete piling, precast prestressed concrete members, or steam cured concrete products, the mortar shall not contract in air more than 0.053 percent.

• Type III and Type V portland cements shall conform to the requirements in ASTM Designation: C 150 and the additional requirements listed above for "Type II Modified" portland cement, except that when tested in conformance with California test 527, mortar containing Type III portland cement shall not contract in air more than 0.075 percent.

• Cement used in the manufacture of cast-in-place concrete for exposed surfaces of like elements of a structure shall be from the same cement mill.

• Cement shall be protected from exposure to moisture until used. Sacked cement shall be piled to permit access for tally, inspection, and identification of each shipment.

• Adequate facilities shall be provided to assure that cement meeting the provisions specified in this Section 90-2.01 shall be kept separate from other cement in order to prevent any but the specified cement from entering the work. Safe and suitable facilities for sampling cement shall be provided at the weigh hopper or in the feed line immediately in advance of the hopper, in conformance with California test 125.

• If cement is used prior to sampling and testing as provided in Section 6-1.07, "Certificates of Compliance," and the cement is delivered directly to the site of the work, the Certificate of Compliance shall be signed by the cement manufacturer or supplier of the cement. If the cement is used in ready-mixed concrete or in precast concrete products purchased as such by the Contractor, the Certificate of Compliance shall be signed by the manufacturer of the concrete or product.

• Cement furnished without a Certificate of Compliance shall not be used in the work until the Engineer has had sufficient time to make appropriate tests and has approved the cement for use.

90-2.02 AGGREGATES

• Aggregates shall be free from deleterious coatings, clay balls, roots, bark, sticks, rags, and other extraneous material.

• Natural aggregates shall be thoroughly and uniformly washed before use.

• The Contractor, at the Contractor's expense, shall provide safe and suitable facilities, including necessary splitting devices for obtaining samples of aggregates, in conformance with California test 125.

• Aggregates shall be of such character that it will be possible to produce workable concrete within the limits of water content provided in Section 90-6.06, "Amount of Water and Penetration."

• Aggregates shall have not more than 10 percent loss when tested for soundness in conformance with the requirements in California test 214. The soundness requirement for fine aggregate will be waived, provided that the durability index, D_f, of the fine aggregate is 60, or greater, when tested for durability in conformance with California test 229.

• If the results of any one or more of the Cleanness Value, Sand Equivalent, or aggregate grading tests do not meet the requirements specified for "Operating Range" but all meet the "Contract Compliance" requirements, the placement of

concrete shall be suspended at the completion of the current pour until tests or other information indicate that the next material to be used in the work will comply with the requirements specified for "Operating Range."

• If the results of either or both the Cleanness Value and coarse aggregate grading tests do not meet the requirements specified for "Contract Compliance," the concrete that is represented by the tests shall be removed. However, if the Engineer determines that the concrete is structurally adequate, the concrete may remain in place, and the Contractor shall pay to the State $4.60 per cubic meter for paving concrete and $7.20 per cubic meter for all other concrete for the concrete represented by these tests and left in place. The Department may deduct the amount from any moneys due, or that may become due, the Contractor under the contract.

• If the results of either or both the Sand Equivalent and fine aggregate grading tests do not meet the requirements specified for "Contract Compliance," the concrete which is represented by the tests shall be removed. However, if the Engineer determines that the concrete is structurally adequate, the concrete may remain in place, and the Contractor shall pay to the State $4.60 per cubic meter for paving concrete and $7.20 per cubic meter for all other concrete for the concrete represented by these tests and left in place. The Department may deduct the amount from any moneys due, or that may become due, the Contractor under the contract.

• The 2 preceding paragraphs apply individually to the "Contract Compliance" requirements for coarse aggregate and fine aggregate. When both coarse aggregate and fine aggregate do not conform to the "Contract Compliance" requirements, both paragraphs shall apply. The payments specified in those paragraphs shall be in addition to any payments made in conformance with the provisions in Section 90-1.01, "Description."

• No single Cleanness Value, Sand Equivalent or aggregate grading test shall represent more than 250 m^3 of concrete or one day's pour, whichever is smaller.

•

• When the source of an aggregate is changed, the Contractor shall adjust the mix proportions and submit in writing to the Engineer a copy of the mix design before using the aggregates.

90-2.02A Coarse Aggregate

• Coarse aggregate shall consist of gravel, crushed gravel, crushed rock, crushed air-cooled iron blast furnace slag or combinations thereof. Crushed air-cooled blast furnace slag shall not be used in reinforced or prestressed concrete.

• Coarse aggregate shall conform to the following quality requirements:

Tests	California Test	Requirements
Loss in Los Angeles Rattler (after 500 revolutions)	211	45% max.
Cleanness Value		
Operating Range	227	75 min.
Contract Compliance	227	71 min.

• In lieu of the above Cleanness Value requirements, a Cleanness Value "Operating Range" limit of 71, minimum, and a Cleanness Value "Contract Compliance" limit of 68, minimum, will be used to determine the acceptability of the coarse aggregate if the Contractor furnishes a Certificate of Compliance, as provided in Section 6-1.07, "Certificates of Compliance," certifying that:

1. coarse aggregate sampled at the completion of processing at the aggregate production plant had a Cleanness Value of not less than 82 when tested by California test 227; and
2. prequalification tests performed in conformance with the requirements in California test 549 indicated that the aggregate would develop a relative strength of not less than 95 percent and would have a relative shrinkage not greater than 105 percent, based on concrete.

90-2.02B Fine Aggregate

• Fine aggregate shall consist of natural sand, manufactured sand produced from larger aggregate or a combination thereof. Manufactured sand shall be well graded.

• Fine aggregate shall conform to the following quality requirements:

Test	California Test	Requirements
Organic Impurities	213	Satisfactory[a]
Mortar Strengths Relative to Ottawa Sand	515	95%, min.
Sand Equivalent:		
Operating Range	217	75, min.
Contract Compliance	217	71, min.

a Fine aggregate developing a color darker than the reference standard color solution may be accepted if it is determined by the Engineer, from mortar strength tests, that a darker color is acceptable.

• In lieu of the above Sand Equivalent requirements, a Sand Equivalent "Operating Range" limit of 71 minimum and a Sand Equivalent "Contract Compliance" limit of 68 minimum will be used to determine the acceptability of the fine aggregate if the Contractor furnishes a Certificate of Compliance, as provided in Section 6-1.07, "Certificates of Compliance," certifying that:

1. fine aggregate sampled at the completion of processing at the aggregate production plant had a Sand Equivalent value of not less than 82 when tested by California test 217; and
2. prequalification tests performed in conformance with California test 549 indicated that the aggregate would develop a relative strength of not less than 95 percent and would have a relative shrinkage not greater than 105 percent, based on concrete.

90-2.03 WATER

• In conventionally reinforced concrete work, the water for curing, for washing aggregates, and for mixing shall be free from oil and shall not contain more than 1000 parts per million of chlorides as Cl, when tested in conformance with California test 422, nor more than 1300 parts per million of sulfates as SO_4, when tested in conformance with California test 417. In prestressed concrete work, the water for curing, for washing aggregates, and for mixing shall be free from oil and shall not contain more than 650 parts per million of chlorides as Cl, when tested in conformance with California test 422, nor more than 1300 parts per million of sulfates as SO_4, when tested in conformance with California test 417. In no case shall the water contain an amount of impurities that will cause either: 1) a change in the setting time of cement of more than 25 percent when tested in conformance with the requirements in ASTM Designation: C 191 or ASTM Designation: C 266 or 2) a reduction in the compressive strength of mortar at 14 days of more than 5 percent, when tested in conformance with the requirements in ASTM Designation: C 109, when compared to the results obtained with distilled water or deionized water, tested in conformance with the requirements in ASTM Designation: C 109.

• In non-reinforced concrete work, the water for curing, for washing aggregates and for mixing shall be free from oil and shall not contain more than 2000 parts per million of chlorides as Cl, when tested in conformance with California test 422, or more than 1500 parts per million of sulfates as SO_4, when tested in conformance with California test 417.

• In addition to the above provisions, water for curing concrete shall not contain impurities in a sufficient amount to cause discoloration of the concrete or produce etching of the surface.

• Water reclaimed from mixer wash-out operations may be used in mixing concrete. The water shall not contain coloring agents or more than 300 parts per million of alkalis (Na_2O + 0.658 K_2O) as determined on the filtrate. The specific gravity of the water shall not exceed 1.03 and shall not vary more than ±0.010 during a day's operations.

90-2.04 ADMIXTURE MATERIALS

• Admixture materials shall conform to the requirements in the following ASTM Designations:

A. Chemical Admixtures—ASTM Designation: C 494.
B. Air-entraining Admixtures—ASTM Designation: C 260.
C. Calcium Chloride—ASTM Designation: D 98.
D. Mineral Admixtures—Coal fly ash; raw or calcined natural pozzolan as specified in ASTM Designation: C 618; silica fume conforming to the requirements in ASTM Designation: C 1240, with reduction of mortar expansion of 80 percent, minimum, using the cement from the proposed mix design.

• Unless otherwise specified in the special provisions, mineral admixtures shall be used in conformance with the provisions in Section 90-4.08, "Required Use of Mineral Admixtures."

90-3 AGGREGATE GRADINGS

90-3.01 GENERAL

• Before beginning concrete work, the Contractor shall submit in writing to the Engineer the gradation of the primary aggregate nominal sizes that the Contractor proposes to furnish. If a primary coarse aggregate or the fine aggregate is separated into 2 or more sizes, the proposed gradation shall consist of the gradation for each individual size, and the proposed proportions of each individual size, combined mathematically to indicate one proposed gradation. The proposed gradation shall meet the grading requirements shown in the table in this section, and shall show the percentage passing each of the sieve sizes used in determining the end result.

• The Engineer may waive, in writing, the gradation requirements in this Section 90-3.01 and in Sections 90-3.02, "Coarse Aggregate Grading," 90-3.03, "Fine Aggregate Grading," and 90-3.04, "Combined Aggregate Gradings," if, in the Engineer's opinion, furnishing the gradation is not necessary for the type or amount of concrete work to be constructed.

• Gradations proposed by the Contractor shall be within the following percentage passing limits:

Primary Aggregate Nominal Size	Sieve Size	Limits of Proposed Gradation
37.5-mm x 19-mm	25-mm	19 - 41
25-mm x 4.75-mm	19-mm	52 - 85
25-mm x 4.75-mm	9.5-mm	15 - 38
12.5-mm x 4.75-mm	9.5-mm	40 - 78
9.5-mm x 2.36-mm	9.5-mm	50 - 85
Fine Aggregate	1.18-mm	55 - 75
Fine Aggregate	600-µm	34 - 46
Fine Aggregate	300-µm	16 - 29

• Should the Contractor change the source of supply, the Contractor shall submit in writing to the Engineer the new gradations before their intended use.

90-3.02 COARSE AGGREGATE GRADING

• The grading requirements for coarse aggregates are shown in the following table for each size of coarse aggregate:

	Percentage Passing Primary Aggregate Nominal Sizes							
	37.5-mm x 19-mm		25-mm x 4.75-mm		12.5-mm x 4.75-mm		9.5-mm x 2.36-mm	
Sieve Sizes	Operating Range	Contract Compliance	Operating Range	Contract Compliance	Operating Range	Contract Compliance	Operating Range	Contract Compliance
50-mm	100	100	—	—	—	—	—	—
37.5-mm	88-100	85-100	100	100	—	—	—	—
25-mm	x ± 18	X ± 25	88-100	86-100	—	—	—	—
19-mm	0-17	0-20	X ± 15	X ± 22	100	100	—	—
12.5-mm	—	—	—	—	82-100	80-100	100	100
9.5-mm	0-7	0-9	X ± 15	X ± 22	X ± 15	X ± 22	X ± 15	X ± 20
4.75-mm	—	—	0-16	0-18	0-15	0-18	0-25	0-28
2.36-mm	—	—	0-6	0-7	0-6	0-7	0-6	0-7

• In the above table, the symbol X is the gradation that the Contractor proposes to furnish for the specific sieve size as provided in Section 90-3.01, "General."

• Coarse aggregate for the 37.5-mm, maximum, combined aggregate grading as provided in Section 90-3.04, "Combined Aggregate Gradings," shall be furnished in 2 or more primary aggregate nominal sizes. Each primary aggregate nominal size may be separated into 2 sizes and stored separately, provided that the combined material conforms to the grading requirements for that particular primary aggregate nominal size.

• When the 25-mm, maximum, combined aggregate grading as provided in Section 90-3.04, "Combined Aggregate Gradings," is to be used, the coarse aggregate may be separated into 2 sizes and stored separately, provided that the combined material shall conform to the grading requirements for the 25-mm x 4.75-mm primary aggregate nominal size.

90-3.03 FINE AGGREGATE GRADING

- Fine aggregate shall be graded within the following limits:

Sieve Sizes	Percentage Passing	
	Operating Range	Contract Compliance
9.5-mm	100	100
4.75-mm	95-100	93-100
2.36-mm	65-95	61-99
1.18-mm	X ± 10	X ± 13
600-µm	X ± 9	X ± 12
300-µm	X ± 6	X ± 9
150-µm	2-12	1-15
75-µm	0-8	0-10

- In the above table, the symbol X is the gradation that the Contractor proposes to furnish for the specific sieve size as provided in Section 90-3.01, "General."
- In addition to the above required grading analysis, the distribution of the fine aggregate sizes shall be such that the difference between the total percentage passing the 1.18-mm sieve and the total percentage passing the 600-µm sieve shall be between 10 and 40, and the difference between the percentage passing the 600-µm and 300-µm sieves shall be between 10 and 40.
- Fine aggregate may be separated into 2 or more sizes and stored separately, provided that the combined material conforms to the grading requirements specified in this Section 90-3.03.

90-3.04 COMBINED AGGREGATE GRADINGS

- Combined aggregate grading limits shall be used only for the design of concrete mixes. Concrete mixes shall be designed so that aggregates are combined in proportions that shall produce a mixture within the grading limits for combined aggregates as specified herein. Within these limitations, the relative proportions shall be as ordered by the Engineer, except as otherwise provided in Section 90-1.01, "Description."
- The combined aggregate grading, except when otherwise specified in these specifications or the special provisions, shall be either the 37.5-mm, maximum grading, or the 25-mm, maximum grading, at the option of the Contractor.

Grading Limits of Combined Aggregates

Sieve Sizes	Percentage Passing			
	37.5-mm Max.	25-mm Max.	12.5-mm Max.	9.5-mm Max.
50-mm	100	—	—	—
37.5-mm	90-100	100	—	—
25-mm	50-86	90-100	—	—
19-mm	45-75	55-100	100	—
12.5-mm	—	—	90-100	100
9.5-mm	38-55	45-75	55-86	50 - 100
4.75-mm	30-45	35-60	45-63	45 - 63
2.36-mm	23-38	27-45	35-49	35 - 49
1.18-mm	17-33	20-35	25-37	25 - 37
600-µm	10-22	12-25	15-25	15 - 25
300-µm	4-10	5-15	5-15	5 - 15
150-µm	1-6	1-8	1-8	1 - 8
75-µm	0-3	0-4	0-4	0 - 4

- Changes from one grading to another shall not be made during the progress of the work unless permitted by the Engineer.

90-4 ADMIXTURES

90-4.01 GENERAL

- Admixtures used in portland cement concrete shall conform to and be used in conformance with the provisions in this Section 90-4 and the special provisions. Admixtures shall be used when specified or ordered by the Engineer and may be used at the Contractor's option as provided herein.
- Chemical admixtures and air-entraining admixtures containing chlorides as Cl in excess of one percent by mass of admixture, as determined by California test 415, shall not be used in prestressed or reinforced concrete.
- Calcium chloride shall not be used in concrete except when otherwise specified.
- Mineral admixture used in concrete for exposed surfaces of like elements of a structure shall be from the same source and of the same percentage.
- Admixtures shall be uniform in properties throughout their use in the work. Should it be found that an admixture as furnished is not uniform in properties, its use shall be discontinued.
- If more than one admixture is used, the admixtures shall be compatible with each other so that the desirable effects of all admixtures used will be realized.

90-4.02 MATERIALS

- Admixture materials shall conform to the provisions in Section 90–2.04, "Admixture Materials."

90-4.03 ADMIXTURE APPROVAL

- No admixture brand shall be used in the work unless it is on the Department's current list of approved brands for the type of admixture involved.
- Admixture brands will be considered for addition to the approved list if the manufacturer of the admixture submits to the Transportation Laboratory a sample of the admixture accompanied by certified test results demonstrating that the admixture complies with the requirements in the appropriate ASTM Designation and these specifications. The sample shall be sufficient to permit performance of all required tests. Approval of admixture brands will be dependent upon a determination as to compliance with the requirements, based on the certified test results submitted, together with tests the Department may elect to perform.
- When the Contractor proposes to use an admixture of a brand and type on the current list of approved admixture brands, the Contractor shall furnish a Certificate of Compliance from the manufacturer, as provided in Section 6-1.07, "Certificates of Compliance," certifying that the admixture furnished is the same as that previously approved. If a previously approved admixture is not accompanied by a Certificate of Compliance, the admixture shall not be used in the work until the Engineer has had sufficient time to make the appropriate tests and has approved the admixture for use. The Engineer may take samples for testing at any time, whether or not the admixture has been accompanied by a Certificate of Compliance.
- If a mineral admixture is delivered directly to the site of the work, the Certificate of Compliance shall be signed by the manufacturer or supplier of the mineral admixture. If the mineral admixture is used in ready-mix concrete or in precast concrete products purchased as such by the Contractor, the Certificate of Compliance shall be signed by the manufacturer of the concrete or product.

90-4.04 REQUIRED USE OF CHEMICAL ADMIXTURES AND CALCIUM CHLORIDE

- When the use of a chemical admixture or calcium chloride is specified, the admixture shall be used at the dosage specified, except that if no dosage is specified, the admixture shall be used at the dosage normally recommended by the manufacturer of the admixture.
- Calcium chloride shall be dispensed in liquid, flake, or pellet form. Calcium chloride dispensed in liquid form shall conform to the provisions for dispensing liquid admixtures in Section 90-4.10, "Proportioning and Dispensing Liquid Admixtures."

90-4.05 OPTIONAL USE OF CHEMICAL ADMIXTURES

- The Contractor will be permitted to use Type A or F, water-reducing; Type B, retarding; or Type D or G, water-reducing and retarding admixtures as described in ASTM Designation: C 494 to conserve cementitious material or to facilitate any concrete construction application subject to the following conditions:

A. When a water-reducing admixture or a water-reducing and retarding admixture is used, the cementitious material content specified or ordered may be reduced by a maximum of 5 percent by mass, except that the resultant cementitious material content shall be not less than 300 kilograms per cubic meter; and
B. When a reduction in cementitious material content is made, the dosage of admixture used shall be the dosage used in determining approval of the admixture.

• Unless otherwise specified, a Type C accelerating chemical admixture conforming to the requirements in ASTM Designation: C 494, may be used in portland cement concrete. Inclusion in the mix design submitted for approval will not be required provided that the admixture is added to counteract changing conditions that contribute to delayed setting of the portland cement concrete, and the use or change in dosage of the admixture is approved in writing by the Engineer.

90-4.06 REQUIRED USE OF AIR-ENTRAINING ADMIXTURES

• When air-entrainment is specified or ordered by the Engineer, the air-entraining admixture shall be used in amounts to produce a concrete having the specified air content as determined by California test 504.

90-4.07 OPTIONAL USE OF AIR-ENTRAINING ADMIXTURES

• When air-entrainment has not been specified or ordered by the Engineer, the Contractor will be permitted to use an air-entraining admixture to facilitate the use of any construction procedure or equipment provided that the average air content, as determined by California Test 504, of 3 successive tests does not exceed 4 percent, and no single test value exceeds 5.5 percent. If the Contractor elects to use an air-entraining admixture in concrete for pavement, the Contractor shall so indicate at the time the Contractor designates the source of aggregate as provided in Section 40-1.015, "Cement Content."

90-4.08 REQUIRED USE OF MINERAL ADMIXTURES

• Unless otherwise specified, mineral admixture shall be combined with cement to make cementitious material.

• The calcium oxide content of mineral admixtures shall not exceed 10 percent and the available alkali, as sodium oxide equivalent, shall not exceed 1.5 percent when determined in conformance with the requirements in ASTM Designation: C 618.

• The amounts of cement and mineral admixture used in cementitious material shall be sufficient to satisfy the minimum cementitious material content requirements specified in Section 90-1.01, "Description," or Section 90-4.05, "Optional Use of Chemical Admixtures," and shall conform to the following:

A. The minimum amount of cement shall not be less than 75 percent by mass of the specified minimum cementitious material content;
B. The minimum amount of mineral admixture to be combined with cement shall be determined using one of the following criteria:

    1. When the calcium oxide content of a mineral admixture is equal to or less than 2 percent by mass, the amount of mineral admixture shall not be less than 15 percent by mass of the total amount of cementitious material to be used in the mix;
    2. When the calcium oxide content of a mineral admixture is greater than 2 percent, the amount of mineral admixture shall not be less than 25 percent by mass of the total amount of cementitious material to be used in the mix;
    3. When a mineral admixture that conforms to the provisions for silica fume in Section 90-2.04, "Admixture Materials," is used, the amount of mineral admixture shall not be less than 10 percent by mass of the total amount of cementitious material to be used in the mix

C. The total amount of mineral admixture shall not exceed 35 percent by mass of the total amount of cementitious material to be used in the mix. Where Section 90-1.01, "Description," specifies a maximum cementitious content in kilograms per cubic meter, the total mass of cement and mineral admixture per cubic meter shall not exceed the specified maximum cementitious material content.

90-4.09 BLANK

90-4.10 PROPORTIONING AND DISPENSING LIQUID ADMIXTURES

• Chemical admixtures and air-entraining admixtures shall be dispensed in liquid form. Dispensers for liquid admixtures shall have sufficient capacity to measure at one time the prescribed quantity required for each batch of concrete. Each dispenser shall include a graduated measuring unit into which liquid admixtures are measured to within ±5 percent of the prescribed quantity for each batch. Dispensers shall be located and maintained so that the graduations can be accurately read from the point at which proportioning operations are controlled to permit a visual check of batching accuracy prior to discharge. Each measuring unit shall be clearly marked for the type and quantity of admixture.

• Each liquid admixture dispensing system shall be equipped with a sampling device consisting of a valve located in a safe and readily accessible position such that a sample of the admixture may be withdrawn slowly by the Engineer.

• If more than one liquid admixture is used in the concrete mix, each liquid admixture shall have a separate measuring unit and shall be dispensed by injecting equipment located in such a manner that the admixtures are not mixed at high concentrations and do not interfere with the effectiveness of each other. When air-entraining admixtures are used in conjunction with other liquid admixtures, the air-entraining admixture shall be the first to be incorporated into the mix.

• When automatic proportioning devices are required for concrete pavement, dispensers for liquid admixtures shall operate automatically with the batching control equipment. The dispensers shall be equipped with an automatic warning system in good operating condition that will provide a visible or audible signal at the point at which proportioning operations are controlled when the quantity of admixture measured for each batch of concrete varies from the preselected dosage by more than 5 percent, or when the entire contents of the measuring unit are not emptied from the dispenser into each batch of concrete.

• Unless liquid admixtures are added to premeasured water for the batch, their discharge into the batch shall be arranged to flow into the stream of water so that the admixtures are well dispersed throughout the batch, except that air-entraining admixtures may be dispensed directly into moist sand in the batching bins provided that adequate control of the air content of the concrete can be maintained.

• Liquid admixtures requiring dosages greater than 2.5 L/m^3 shall be considered to be water when determining the total amount of free water as specified in Section 90-6.06, "Amount of Water and Penetration."

• Special admixtures, such as "high range" water reducers that may contribute to a high rate of slump loss, shall be measured and dispensed as recommended by the admixture manufacturer and as approved by the Engineer.

90-4.11 STORAGE, PROPORTIONING, AND DISPENSING OF MINERAL ADMIXTURES

• Mineral admixtures shall be protected from exposure to moisture until used. Sacked material shall be piled to permit access for tally, inspection and identification for each shipment.

• Adequate facilities shall be provided to assure that mineral admixtures meeting the specified requirements are kept separate from other mineral admixtures in order to prevent any but the specified mineral admixtures from entering the work. Safe and suitable facilities for sampling mineral admixtures shall be provided at the weigh hopper or in the feed line immediately in advance of the hopper.

• Mineral admixtures shall be incorporated into concrete using equipment conforming to the requirements for cement weigh hoppers, and charging and discharging mechanisms in ASTM Designation: C 94, in Section 90-5.03, "Proportioning," and in this Section 90-4.11.

• When concrete is completely mixed in stationary paving mixers, the mineral admixture shall be weighed in a separate weigh hopper conforming to the provisions for cement weigh hoppers and charging and discharging mechanisms in Section 90-5.03A, "Proportioning for Pavement," and the mineral admixture and cement shall be introduced simultaneously into the mixer proportionately with the aggregate. If the mineral admixture is not weighed in a separate weigh hopper, the Contractor shall provide certification that the stationary mixer is capable of mixing the cement, admixture, aggregates and water uniformly prior to discharge. Certification shall contain the following:

A. Test results for 2 compressive strength test cylinders of concrete taken within the first one-third and 2 compressive strength test cylinders of concrete taken within the last one-third of the concrete discharged from a single batch from the stationary paving mixer. Strength tests and cylinder preparation will be in conformance with the provisions of Section 90-9, "Compressive Strength;"
B. Calculations demonstrating that the difference in the averages of 2 compressive strengths taken in the first one-third is no greater than 7.5 percent different than the averages of 2 compressive strengths taken in the last one-third of the concrete discharged from a single batch from the stationary paving mixer. Strength tests and cylinder preparation will be in conformance with the provisions of Section 90-9, "Compressive Strength;" and
C. The mixer rotation speed and time of mixing prior to discharge that are required to produce a mix that meets the requirements above.

90-5 PROPORTIONING

90-5.01 STORAGE OF AGGREGATES

• Aggregates shall be stored or stockpiled in such a manner that separation of coarse and fine particles of each size shall be avoided and also that the various sizes shall not become intermixed before proportioning.

• Aggregates shall be stored or stockpiled and handled in a manner that shall prevent contamination by foreign materials. In addition, storage of aggregates at batching or mixing facilities that are erected subsequent to the award of the contract and that furnish concrete to the project shall conform to the following:

A. Intermingling of the different sizes of aggregates shall be positively prevented. The Contractor shall take the necessary measures to prevent intermingling. The preventive measures may include, but are not necessarily limited to, physical separation of stockpiles or construction of bulkheads of adequate length and height; and
B. Contamination of aggregates by contact with the ground shall be positively prevented. The Contractor shall take the necessary measures to prevent contamination. The preventive measures shall include, but are not necessarily limited to, placing aggregates on wooden platforms or on hardened surfaces consisting of portland cement concrete, asphalt concrete, or cement treated material.

• In placing aggregates in storage or in moving the aggregates from storage to the weigh hopper of the batching plant, any method that may cause segregation, degradation, or the combining of materials of different gradings that will result in any size of aggregate at the weigh hopper failing to meet the grading requirements, shall be discontinued. Any method of handling aggregates that results in excessive breakage of particles shall be discontinued. The use of suitable devices to reduce impact of falling aggregates may be required by the Engineer.

90-5.02 PROPORTIONING DEVICES

• Weighing, measuring, or metering devices used for proportioning materials shall conform to the requirements in Section 9-1.01, "Measurement of Quantities," and this Section 90-5.02. In addition, automatic weighing systems shall comply with the requirements for automatic proportioning devices in Section 90-5.03A, "Proportioning for Pavement." Automatic devices shall be automatic to the extent that the only manual operation required for proportioning the aggregates, cement, and mineral admixture for one batch of concrete is a single operation of a switch or starter.

• Proportioning devices shall be tested at the expense of the Contractor as frequently as the Engineer may deem necessary to ensure their accuracy.

• Weighing equipment shall be insulated against vibration or movement of other operating equipment in the plant. When the plant is in operation, the mass of each batch of material shall not vary from the mass designated by the Engineer by more than the tolerances specified herein.

• Equipment for cumulative weighing of aggregate shall have a zero tolerance of ±0.5 percent of the designated total batch mass of the aggregate. For systems with individual weigh hoppers for the various sizes of aggregate, the zero tolerance shall be ±0.5 percent of the individual batch mass designated for each size of aggregate. Equipment for cumulative weighing of cement and mineral admixtures shall have a zero tolerance of ±0.5 percent of the designated total batch mass of the cement and mineral admixture. Equipment for weighing cement or mineral admixture separately shall have a zero tolerance of ±0.5 percent of their designated individual batch masses. Equipment for measuring water shall have a zero tolerance of ±0.5 percent of its designated mass or volume.

• The mass indicated for any batch of material shall not vary from the preselected scale setting by more than the following:

A. Aggregate weighed cumulatively shall be within 1.0 percent of the designated total batch mass of the aggregate. Aggregates weighed individually shall be within 1.5 percent of their respective designated batch masses; and
B. Cement shall be within 1.0 percent of its designated batch mass. When weighed individually, mineral admixture shall be within 1.0 percent of its designated batch mass. When mineral admixture and cement are permitted to be weighed cumulatively, cement shall be weighed first to within 1.0 percent of its designated batch mass, and the total for cement and mineral admixture shall be within 1.0 percent of the sum of their designated batch masses; and
C. Water shall be within 1.5 percent of its designated mass or volume.

• Each scale graduation shall be approximately 0.001 of the total capacity of the scale. The capacity of scales for weighing cement, mineral admixture, or cement plus mineral admixture and aggregates shall not exceed that of commercially available scales having single graduations indicating a mass not exceeding the maximum permissible mass variation above, except that no scale shall be required having a capacity of less than 500 kg, with 0.5-kg graduations.

90-5.03 PROPORTIONING

• Proportioning shall consist of dividing the aggregates into the specified sizes, each stored in a separate bin, and combining them with cement, mineral admixture, and water as provided in these specifications. Aggregates shall be proportioned by mass.

• At the time of batching, aggregates shall have been dried or drained sufficiently to result in a stable moisture content such that no visible separation of water from aggregate will take place during transportation from the proportioning plant to the point of mixing. In no event shall the free moisture content of the fine aggregate at the time of batching exceed 8 percent of its saturated, surface-dry mass.

- Should separate supplies of aggregate material of the same size group, but of different moisture content or specific gravity or surface characteristics affecting workability, be available at the proportioning plant, withdrawals shall be made from one supply exclusively and the materials therein completely exhausted before starting upon another.
- Bulk "Type IP (MS) Modified" cement shall be weighed in an individual hopper and shall be kept separate from the aggregates until the ingredients are released for discharge into the mixer.
- Bulk cement and mineral admixture may be weighed in separate, individual weigh hoppers or may be weighed in the same weigh hopper and shall be kept separate from the aggregates until the ingredients are released for discharge into the mixer. If the cement and mineral admixture are weighed cumulatively, the cement shall be weighed first.
- When cement and mineral admixtures are weighed in separate weigh hoppers**,** the weigh systems for the proportioning of the aggregate, the cement, and the mineral admixture shall be individual and distinct from all other weigh systems. Each weigh system shall be equipped with a hopper, a lever system, and an indicator to constitute an individual and independent material weighing device. The cement and the mineral admixture shall be discharged into the mixer simultaneously with the aggregate.
- The scales and weigh hoppers for bulk weighing cement, mineral admixture, or cement plus mineral admixture shall be separate and distinct from the aggregate weighing equipment.
- For batches with a volume of one cubic meter or more, the batching equipment shall conform to one of the following combinations:

A. Separate boxes and separate scale and indicator for weighing each size of aggregate.
B. Single box and scale indicator for all aggregates.
C. Single box or separate boxes and automatic weighing mechanism for all aggregates.

- In order to check the accuracy of batch masses, the gross mass and tare mass of batch trucks, truck mixers, truck agitators, and non-agitating hauling equipment shall be determined when ordered by the Engineer. The equipment shall be weighed at the Contractor's expense on scales designated by the Engineer.

90-5.03A Proportioning for Pavement

- Aggregates and bulk cement, mineral admixture, and cement plus mineral admixture for use in pavement shall be proportioned by mass by means of automatic proportioning devices of approved type conforming to these specifications.
- The Contractor shall install and maintain in operating condition an electronically actuated moisture meter that will indicate, on a readily visible scale, changes in the moisture content of the fine aggregate as it is batched within a sensitivity of 0.5 percent by mass of the fine aggregate.
- The batching of cement, mineral admixture, or cement plus mineral admixture and aggregate shall be interlocked so that a new batch cannot be started until all weigh hoppers are empty, the proportioning devices are within zero tolerance, and the discharge gates are closed. The interlock shall permit no part of the batch to be discharged until all aggregate hoppers and the cement and mineral admixture hoppers or the cement plus mineral admixture hopper are charged with masses that are within the tolerances specified in Section 90-5.02, "Proportioning Devices."
- When interlocks are required for cement and mineral admixture charging mechanisms and cement and mineral admixtures are weighed cumulatively, their charging mechanisms shall be interlocked to prevent the introduction of mineral admixture until the mass of cement in the cement weigh hopper is within the tolerances specified in Section 90-5.02, "Proportioning Devices."
- The discharge gate on the cement and mineral admixture hoppers or the cement plus mineral admixture hopper shall be designed to permit regulating the flow of cement, mineral admixture, or cement plus mineral admixture into the aggregate as directed by the Engineer.
- When separate weigh boxes are used for each size of aggregate, the discharge gates shall permit regulating the flow of each size of aggregate as directed by the Engineer.
- Material discharged from the several bins shall be controlled by gates or by mechanical conveyors. The means of withdrawal from the several bins, and of discharge from the weigh box, shall be interlocked so that not more than one bin can discharge at a time, and so that the weigh box cannot be tripped until the required quantity from each of the several bins has been deposited therein. Should a separate weigh box be used for each size of aggregate, all may be operated and discharged simultaneously.
- When the discharge from the several bins is controlled by gates, each gate shall be actuated automatically so that the required mass is discharged into the weigh box, after which the gate shall automatically close and lock.
- The automatic weighing system shall be designed so that all proportions required may be set on the weighing controller at the same time.

90-6 MIXING AND TRANSPORTING

90-6.01 GENERAL

• Concrete shall be mixed in mechanically operated mixers, except that when permitted by the Engineer, batches not exceeding 0.25 m^3 may be mixed by hand methods in conformance with the provisions in Section 90-6.05, "Hand-Mixing."

• Equipment having components made of aluminum or magnesium alloys that would have contact with plastic concrete during mixing, transporting, or pumping of portland cement concrete shall not be used.

• Concrete shall be homogeneous and thoroughly mixed, and there shall be no lumps or evidence of undispersed cement, mineral admixture, or cement plus mineral admixture.

• Uniformity of concrete mixtures will be determined by differences in penetration as determined by California Test 533, or slump as determined by ASTM Designation: C 143, and by variations in the proportion of coarse aggregate as determined by California Test 529.

• When the mix design specifies a penetration value, the difference in penetration, determined by comparing penetration tests on 2 samples of mixed concrete from the same batch or truck mixer load, shall not exceed 10 mm. When the mix design specifies a slump value, the difference in slump, determined by comparing slump tests on 2 samples of mixed concrete from the same batch or truck mixer load, shall not exceed the values given in the table below. Variation in the proportion of coarse aggregate will be determined by comparing the results of tests of 2 samples of mixed concrete from the same batch or truck mixer load and the difference between the 2 results shall not exceed 100 kg per cubic meter of concrete.

Average Slump	Maximum Permissible Difference
Less than 100-mm	25-mm
100-mm to 150-mm	38-mm
Greater than 150-mm to 225-mm	50-mm

• The Contractor, at the Contractor's expense, shall furnish samples of the freshly mixed concrete and provide satisfactory facilities for obtaining the samples.

90-6.02 MACHINE MIXING

• Concrete mixers may be of the revolving drum or the revolving blade type, and the mixing drum or blades shall be operated uniformly at the mixing speed recommended by the manufacturer. Mixers and agitators that have an accumulation of hard concrete or mortar shall not be used.

• The temperature of mixed concrete, immediately before placing, shall be not less than 10°C or more than 32°C. Aggregates and water shall be heated or cooled as necessary to produce concrete within these temperature limits. Neither aggregates nor mixing water shall be heated to exceed 65°C. If ice is used to cool the concrete, discharge of the mixer will not be permitted until all ice is melted.

• The batch shall be so charged into the mixer that some water will enter in advance of cementitious materials and aggregates. All water shall be in the drum by the end of the first one-fourth of the specified mixing time.

• Cementitious materials shall be batched and charged into the mixer by means that will not result either in loss of cementitious materials due to the effect of wind, in accumulation of cementitious materials on surfaces of conveyors or hoppers, or in other conditions that reduce or vary the required quantity of cementitious material in the concrete mixture.

• Paving and stationary mixers shall be operated with an automatic timing device. The timing device and discharge mechanism shall be interlocked so that during normal operation no part of the batch will be discharged until the specified mixing time has elapsed.

• The total elapsed time between the intermingling of damp aggregates and all cementitious materials and the start of mixing shall not exceed 30 minutes.

• The size of batch shall not exceed the manufacturer's guaranteed capacity.

• When producing concrete for pavement or base, suitable batch counters shall be installed and maintained in good operating condition at jobsite batching plants and stationary mixers. The batch counters shall indicate the exact number of batches proportioned and mixed.

• Concrete shall be mixed and delivered to the jobsite by means of one of the following combinations of operations:

A. Mixed completely in a stationary mixer and the mixed concrete transported to the point of delivery in truck agitators or in non-agitating hauling equipment (central-mixed concrete).
B. Mixed partially in a stationary mixer, and the mixing completed in a truck mixer (shrink-mixed concrete).
C. Mixed completely in a truck mixer (transit-mixed concrete).
D. Mixed completely in a paving mixer.

- Agitators may be truck mixers operating at agitating speed or truck agitators. Each mixer and agitator shall have attached thereto in a prominent place a metal plate or plates on which is plainly marked the various uses for which the equipment is designed, the manufacturer's guaranteed capacity of the drum or container in terms of the volume of mixed concrete and the speed of rotation of the mixing drum or blades.
- Truck mixers shall be equipped with electrically or mechanically actuated revolution counters by which the number of revolutions of the drum or blades may readily be verified.
- When shrink-mixed concrete is furnished, concrete that has been partially mixed at a central plant shall be transferred to a truck mixer and all requirements for transit-mixed concrete shall apply. No credit in the number of revolutions at mixing speed shall be allowed for partial mixing in a central plant.

90-6.03 TRANSPORTING MIXED CONCRETE

- Mixed concrete may be transported to the delivery point in truck agitators or truck mixers operating at the speed designated by the manufacturer of the equipment as agitating speed, or in non-agitating hauling equipment, provided the consistency and workability of the mixed concrete upon discharge at the delivery point is suitable for adequate placement and consolidation in place, and provided the mixed concrete after hauling to the delivery point conforms to the provisions in Section 90-6.01, "General."
- Truck agitators shall be loaded not to exceed the manufacturer's guaranteed capacity and shall maintain the mixed concrete in a thoroughly mixed and uniform mass during hauling.
- Bodies of non-agitating hauling equipment shall be constructed so that leakage of the concrete mix, or any part thereof, will not occur at any time.
- Concrete hauled in open-top vehicles shall be protected during hauling against rain or against exposure to the sun for more than 20 minutes when the ambient temperature exceeds 24°C.
- No additional mixing water shall be incorporated into the concrete during hauling or after arrival at the delivery point, unless authorized by the Engineer. If the Engineer authorizes additional water to be incorporated into the concrete, the drum shall be revolved not less than 30 revolutions at mixing speed after the water is added and before discharge is commenced.
- The rate of discharge of mixed concrete from truck mixer-agitators shall be controlled by the speed of rotation of the drum in the discharge direction with the discharge gate fully open.
- When a truck mixer or agitator is used for transporting concrete to the delivery point, discharge shall be completed within 1.5 hours or before 250 revolutions of the drum or blades, whichever occurs first, after the introduction of the cement to the aggregates. Under conditions contributing to quick stiffening of the concrete, or when the temperature of the concrete is 30°C or above, the time allowed may be less than 1.5 hours.
- When non-agitating hauling equipment is used for transporting concrete to the delivery point, discharge shall be completed within one hour after the addition of the cement to the aggregates. Under conditions contributing to quick stiffening of the concrete, or when the temperature of the concrete is 30°C or above, the time between the introduction of cement to the aggregates and discharge shall not exceed 45 minutes.
- Each load of concrete delivered at the jobsite shall be accompanied by a weighmaster certificate showing the mix identification number, non-repeating load number, date and time at which the materials were batched, the total amount of water added to the load, and for transit-mixed concrete, the reading of the revolution counter at the time the truck mixer is charged with cement. This weighmaster certificate shall also show the actual scale masses (kilograms) for the ingredients batched. Theoretical or target batch masses shall not be used as a substitute for actual scale masses.
- Weighmaster certificates shall be provided in printed form, or if approved by the Engineer, the data may be submitted in electronic media. Electronic media shall be presented in a tab-delimited format on a 90 mm diskette with a capacity of at least 1.4 megabytes. Captured data, for the ingredients represented by each batch shall be "line feed, carriage return" (LFCR) and "one line, separate record" with allowances for sufficient fields to satisfy the amount of data required by these specifications.
- The Contractor may furnish a weighmaster certificate accompanied by a separate certificate that lists the actual batch masses or measurements for a load of concrete provided that both certificates are imprinted with the same non-repeating load number that is unique to the contract and delivered to the jobsite with the load.
- Weighmaster certificates furnished by the Contractor shall conform to the provisions in Section 9-1.01, "Measurement of Quantities."

90-6.04 TIME OR AMOUNT OF MIXING

- Mixing of concrete in paving or stationary mixers shall continue for the required mixing time after all ingredients, except water and admixture, if added with the water, are in the mixing compartment of the mixer before any part of the batch is released. Transfer time in multiple drum mixers shall not be counted as part of the required mixing time.

• The required mixing time, in paving or stationary mixers, of concrete used for concrete structures, except minor structures, shall be not less than 90 seconds or more than 5 minutes, except that when directed by the Engineer in writing, the requirements of the following paragraph shall apply.

• The required mixing time, in paving or stationary mixers, except as provided in the preceding paragraph, shall be not less than 50 seconds or more than 5 minutes.

• The minimum required revolutions at the mixing speed for transit-mixed concrete shall not be less than that recommended by the mixer manufacturer, but in no case shall the number of revolutions be less than that required to consistently produce concrete conforming to the provisions for uniformity in Section 90-6.01, "General."

90-6.05 HAND-MIXING

• Hand-mixed concrete shall be made in batches of not more than 0.25 m^3 and shall be mixed on a watertight, level platform. The proper amount of coarse aggregate shall be measured in measuring boxes and spread on the platform and the fine aggregate shall be spread on this layer, the 2 layers being not more than 0.3 meters in total depth. On this mixture shall be spread the dry cement and mineral admixture and the whole mass turned no fewer than 2 times dry; then sufficient clean water shall be added, evenly distributed, and the whole mass again turned no fewer than 3 times, not including placing in the carriers or forms.

90-6.06 AMOUNT OF WATER AND PENETRATION

• The amount of water used in concrete mixes shall be regulated so that the penetration of the concrete as determined by California Test 533 or the slump of the concrete as determined by ASTM Designation: C 143 is within the "Nominal" values shown in the following table. When the penetration or slump of the concrete is found to exceed the nominal values listed, the mixture of subsequent batches shall be adjusted to reduce the penetration or slump to a value within the nominal range shown. Batches of concrete with a penetration or slump exceeding the maximum values listed shall not be used in the work. When Type F or Type G chemical admixtures are added to the mix, the penetration requirements shall not apply and the slump shall not exceed 225 mm after the chemical admixtures are added.

Type of Work	Nominal		Maximum	
	Penetration (mm)	Slump (mm)	Penetration (mm)	Slump (mm)
Concrete Pavement	0-25	—	40	—
Non-reinforced concrete facilities	0-35	—	50	—
Reinforced concrete structures				
Sections over 300-mm thick	0-35	—	65	—
Sections 300-mm thick or less	0-50	—	75	—
Concrete placed under water	—	150-200	—	225
Cast-in-place concrete piles	65-90	130-180	100	200

• The amount of free water used in concrete shall not exceed 183 kg/m^3, plus 20 kg for each required 100 kg of cementitious material in excess of 325 kg/m^3.

• The term free water is defined as the total water in the mixture minus the water absorbed by the aggregates in reaching a saturated surface-dry condition.

• Where there are adverse or difficult conditions that affect the placing of concrete, the above specified penetration and free water content limitations may be exceeded providing the Contractor is granted permission by the Engineer in writing to increase the cementitious material content per cubic meter of concrete. The increase in water and cementitious material shall be at a ratio not to exceed 30 kg of water per added 100 kg of cementitious material per cubic meter. The cost of additional cementitious material and water added under these conditions shall be at the Contractor's expense and no additional compensation will be allowed therefor.

• The equipment for supplying water to the mixer shall be constructed and arranged so that the amount of water added can be measured accurately. Any method of discharging water into the mixer for a batch shall be accurate within 1.5 percent of the quantity of water required to be added to the mix for any position of the mixer. Tanks used to measure water shall be designed so that water cannot enter while water is being discharged into the mixer and discharge into the mixer shall be made rapidly in one operation without dribbling. All equipment shall be arranged so as to permit checking the amount of water delivered by discharging into measured containers.

90-7 CURING CONCRETE

90-7.01 METHODS OF CURING

- Newly placed concrete shall be cured by the methods specified in this Section 90-7.01 and the special provisions.

90-7.01A Water Method

- The concrete shall be kept continuously wet by the application of water for a minimum curing period of 7 days after the concrete has been placed.
- When a curing medium consisting of cotton mats, rugs, carpets, or earth or sand blankets is to be used to retain the moisture, the entire surface of the concrete shall be kept damp by applying water with a nozzle that so atomizes the flow that a mist and not a spray is formed, until the surface of the concrete is covered with the curing medium. The moisture from the nozzle shall not be applied under pressure directly upon the concrete and shall not be allowed to accumulate on the concrete in a quantity sufficient to cause a flow or wash the surface. At the expiration of the curing period, the concrete surfaces shall be cleared of all curing mediums.
- When concrete bridge decks and flat slabs are to be cured without the use of a curing medium, the entire surface of the bridge deck or slab shall be kept damp by the application of water with an atomizing nozzle as specified in the preceding paragraph, until the concrete has set, after which the entire surface of the concrete shall be sprinkled continuously with water for a period of not less than 7 days.

90-7.01B Curing Compound Method

- Surfaces of the concrete that are exposed to the air shall be sprayed uniformly with a curing compound.
- Curing compounds to be used shall be as follows:

1. Pigmented curing compound conforming to the requirements in ASTM Designation: C 309, Type 2, Class B, except the resin type shall be poly-alpha-methylstyrene.
2. Pigmented curing compound conforming to the requirements in ASTM Designation: C 309, Type 2, Class B.
3. Pigmented curing compound conforming to the requirements in ASTM Designation: C 309, Type 2, Class A.
4. Non-pigmented curing compound conforming to the requirements in ASTM Designation: C 309, Type 1, Class B.
5. Non-pigmented curing compound conforming to the requirements in ASTM Designation: C 309, Type 1, Class A.
6. Non-pigmented curing compound with fugitive dye conforming to the requirements in ASTM Designation: C 309, Type 1-D, Class A.

- The infrared scan for the dried vehicle from curing compound (1) shall match the infrared scan on file at the Transportation Laboratory.
- The loss of water for each type of curing compound, when tested in conformance with the requirements in California Test 534, shall not be more than 0.15-kg/m^2 in 24 hours.
- The curing compound to be used will be specified elsewhere in these specifications or in the special provisions.
- When the use of curing compound is required or permitted elsewhere in these specifications or in the special provisions and no specific kind is specified, any of the curing compounds listed above may be used.
- Curing compound shall be applied at a nominal rate of 3.7 m^2/L, unless otherwise specified.
- At any point, the application rate shall be within ±1.2 m^2/L of the nominal rate specified, and the average application rate shall be within ±0.5 m^2/L of the nominal rate specified when tested in conformance with the requirements in California Test 535. Runs, sags, thin areas, skips, or holidays in the applied curing compound shall be evidence that the application is not satisfactory.
- Curing compounds shall be applied using power operated spray equipment. The power operated spraying equipment shall be equipped with an operational pressure gage and a means of controlling the pressure. Hand spraying of small and irregular areas that are not reasonably accessible to mechanical spraying equipment, in the opinion of the Engineer, may be permitted.
- The curing compound shall be applied to the concrete following the surface finishing operation, immediately before the moisture sheen disappears from the surface, but before any drying shrinkage or craze cracks begin to appear. In the event of any drying or cracking of the surface, application of water with an atomizing nozzle as specified in Section 90-7.01A, "Water Method," shall be started immediately and shall be continued until application of the compound is resumed or started; however, the compound shall not be applied over any resulting freestanding water. Should the film of compound be damaged from any cause before the expiration of 7 days after the concrete is placed in the case of structures and 72 hours in the case of pavement, the damaged portion shall be repaired immediately with additional compound.
- At the time of use, compounds containing pigments shall be in a thoroughly mixed condition with the pigment uniformly dispersed throughout the vehicle. A paddle shall be used to loosen all settled pigment from the bottom of the container, and a power driven agitator shall be used to disperse the pigment uniformly throughout the vehicle.
- Agitation shall not introduce air or other foreign substance into the curing compound.

- The manufacturer shall include in the curing compound the necessary additives for control of sagging, pigment settling, leveling, de-emulsification, or other requisite qualities of a satisfactory working material. Pigmented curing compounds shall be manufactured so that the pigment does not settle badly, does not cake or thicken in the container, and does not become granular or curdled. Settlement of pigment shall be a thoroughly wetted, soft, mushy mass permitting the complete and easy vertical penetration of a paddle. Settled pigment shall be easily redispersed, with minimum resistance to the sideways manual motion of the paddle across the bottom of the container, to form a smooth uniform product of the proper consistency.
- Curing compounds shall remain sprayable at temperatures above 4°C and shall not be diluted or altered after manufacture.
- The curing compound shall be packaged in clean 1040-L totes, 210-L barrels

or 19-L pails shall be supplied from a suitable storage tank located at the jobsite. The containers shall comply with "Title 49, Code of Federal Regulations, Hazardous Materials Regulations." The 1040-L totes and the 210-L barrels shall have removable lids and airtight fasteners. The 19-L pails shall be round and have standard full open head and bail. Lids with bungholes shall not be permitted. Settling or separation of solids in containers, except tanks, must be completely redispersed with low speed mixing prior to use, in conformance with these specifications and the manufacturer's recommendations. Mixing shall be accomplished either manually by use of a paddle or by use of a mixing blade driven by a drill motor, at low speed. Mixing blades shall be the type used for mixing paint. On site storage tanks shall be kept clean and free of contaminants. Each tank shall have a permanent system designed to completely redisperse settled material without introducing air or other foreign substances.

- Steel containers and lids shall be lined with a coating that will prevent destructive action by the compound or chemical agents in the air space above the compound. The coating shall not come off the container or lid as skins. Containers shall be filled in a manner that will prevent skinning. Plastic containers shall not react with the compound.
- Each container shall be labeled with the manufacturer's name, kind of curing compound, batch number, volume, date of manufacture, and volatile organic compound (VOC) content. The label shall also warn that the curing compound containing pigment shall be well stirred before use. Precautions concerning the handling and the application of curing compound shall be shown on the label of the curing compound containers in conformance with the Construction Safety Orders and General Industry Safety Orders of the State of California.
- Containers of curing compound shall be labeled to indicate that the contents fully comply with the rules and regulations concerning air pollution control in the State of California.
- When the curing compound is shipped in tanks or tank trucks, a shipping invoice shall accompany each load. The invoice shall contain the same information as that required herein for container labels.
- Curing compound will be sampled by the Engineer at the source of supply or at the jobsite or at both locations.
- Curing compound shall be formulated so as to maintain the specified properties for a minimum of one year. The Engineer may require additional testing before use to determine compliance with these specifications if the compound has not been used within one year or whenever the Engineer has reason to believe the compound is no longer satisfactory.
- Tests will be conducted in conformance with the latest ASTM test methods and methods in use by the Transportation Laboratory.

90-7.01C Waterproof Membrane Method

- The exposed finished surfaces of concrete shall be sprayed with water, using a nozzle that so atomizes the flow that a mist and not a spray is formed, until the concrete has set, after which the curing membrane shall be placed. The curing membrane shall remain in place for a period of not less than 72 hours.
- Sheeting material for curing concrete shall conform to the requirements in AASHTO Designation: M 171 for white reflective materials.
- The sheeting material shall be fabricated into sheets of such width as to provide a complete cover for the entire concrete surface. Joints in the sheets shall be securely cemented together in such a manner as to provide a waterproof joint. The joint seams shall have a minimum lap of 100 mm.
- The sheets shall be securely weighted down by placing a bank of earth on the edges of the sheets or by other means satisfactory to the Engineer.
- Should any portion of the sheets be broken or damaged before the expiration of 72 hours after being placed, the broken or damaged portions shall be immediately repaired with new sheets properly cemented into place.
- Sections of membrane that have lost their waterproof qualities or have been damaged to such an extent as to render them unfit for curing the concrete shall not be used.

90-7.01D Forms-In-Place Method

• Formed surfaces of concrete may be cured by retaining the forms in place. The forms shall remain in place for a minimum period of 7 days after the concrete has been placed, except that for members over 0.5-m in least dimension the forms shall remain in place for a minimum period of 5 days.

• Joints in the forms and the joints between the end of forms and concrete shall be kept moisture tight during the curing period. Cracks in the forms and cracks between the forms and the concrete shall be resealed by methods subject to the approval of the Engineer.

90-7.02 CURING PAVEMENT

• The entire exposed area of the pavement, including edges, shall be cured by the waterproof membrane method, or curing compound method using curing compound (1) or (2) as the Contractor may elect. Should the side forms be removed before the expiration of 72 hours following the start of curing, the exposed pavement edges shall also be cured. If the pavement is cured by means of the curing compound method, the sawcut and all portions of the curing compound that have been disturbed by sawing operations shall be restored by spraying with additional curing compound.

• Curing shall commence as soon as the finishing process provided in Section 40-1.10, "Final Finishing," has been completed. The method selected shall conform to the provisions in Section 90-7.01, "Methods of Curing."

• When the curing compound method is used, the compound shall be applied to the entire pavement surface by mechanical sprayers. Spraying equipment shall be of the fully atomizing type equipped with a tank agitator that provides for continual agitation of the curing compound during the time of application. The spray shall be adequately protected against wind, and the nozzles shall be so oriented or moved mechanically transversely as to result in the minimum specified rate of coverage being applied uniformly on exposed faces. Hand spraying of small and irregular areas, and areas inaccessible to mechanical spraying equipment, in the opinion of the Engineer, will be permitted. When the ambient air temperature is above 15°C, the Contractor shall fog the surface of the concrete with a fine spray of water as specified in Section 90-7.01A, "Water Method." The surface of the pavement shall be kept moist between the hours of 10:00 a.m. and 4:30 p.m. on the day the concrete is placed. However, the fogging done after the curing compound has been applied shall not begin until the compound has set sufficiently to prevent displacement. Fogging shall be discontinued if ordered in writing by the Engineer.

90-7.03 CURING STRUCTURES

• Newly placed concrete for cast-in-place structures, other than highway bridge decks, shall be cured by the water method, the forms-in-place method, or, as permitted herein, by the curing compound method, in conformance with the provisions in Section 90-7.01, "Methods of Curing."

• The curing compound method using a pigmented curing compound may be used on concrete surfaces of construction joints, surfaces that are to be buried underground, and surfaces where only Ordinary Surface Finish is to be applied and on which a uniform color is not required and that will not be visible from a public traveled way. If the Contractor elects to use the curing compound method on the bottom slab of box girder spans, the curing compound shall be curing compound (1).

• The top surface of highway bridge decks shall be cured by both the curing compound method and the water method. The curing compound shall be curing compound (1).

• Concrete surfaces of minor structures, as defined in Section 51-1.02, "Minor Structures," shall be cured by the water method, the forms-in-place method or the curing compound method.

• When deemed necessary by the Engineer during periods of hot weather, water shall be applied to concrete surfaces being cured by the curing compound method or by the forms-in-place method, until the Engineer determines that a cooling effect is no longer required. Application of water for this purpose will be paid for as extra work as provided in Section 4-1.03D, "Extra Work."

90-7.04 CURING PRECAST CONCRETE MEMBERS

• Precast concrete members shall be cured in conformance with any of the methods specified in Section 90-7.01, "Methods of Curing." Curing shall be provided for the minimum time specified for each method or until the concrete reaches its design strength, whichever is less. Steam curing may also be used for precast members and shall conform to the following provisions:

A. After placement of the concrete, members shall be held for a minimum 4-hour presteaming period. If the ambient air temperature is below 10°C, steam shall be applied during the presteaming period to hold the air surrounding the member at a temperature between 10°C and 32°C.
B. To prevent moisture loss on exposed surfaces during the presteaming period, members shall be covered as soon as possible after casting or the exposed surfaces shall be kept wet by fog spray or wet blankets.

C. Enclosures for steam curing shall allow free circulation of steam about the member and shall be constructed to contain the live steam with a minimum moisture loss. The use of tarpaulins or similar flexible covers will be permitted, provided they are kept in good repair and secured in such a manner as to prevent the loss of steam and moisture.
D. Steam at the jets shall be at low pressure and in a saturated condition. Steam jets shall not impinge directly on the concrete, test cylinders, or forms. During application of the steam, the temperature rise within the enclosure shall not exceed 22°C per hour. The curing temperature throughout the enclosure shall not exceed 65°C and shall be maintained at a constant level for a sufficient time necessary to develop the required transfer strength. Control cylinders shall be covered to prevent moisture loss and shall be placed in a location where temperature is representative of the average temperature of the enclosure.
E. Temperature recording devices that will provide an accurate, continuous, permanent record of the curing temperature shall be provided. A minimum of one temperature recording device per 60 m of continuous bed length will be required for checking temperature.
F. Members in pretension beds shall be detensioned immediately after the termination of steam curing while the concrete and forms are still warm, or the temperature under the enclosure shall be maintained above 15°C until the stress is transferred to the concrete.
G. Curing of precast concrete will be considered completed after termination of the steam curing cycle.

90-7.05 CURING PRECAST PRESTRESSED CONCRETE PILES

• Newly placed concrete for precast prestressed concrete piles shall be cured in conformance with the provisions in Section 90-7.04, "Curing Precast Concrete Members," except that piles with a class designation ending in C (corrosion resistant) shall be cured as follows:

A. Piles shall be either steam cured or water cured. If water curing is used, the piles shall be kept continuously wet by the application of water in conformance with the provisions in Section 90-7.01A, "Water Method."
B. If steam curing is used, the steam curing provisions in Section 90-7.04, "Curing Precast Concrete Members," shall apply except that the piles shall be kept continuously wet for their entire length for a period of not less than 3 days, including the holding and steam curing periods.

90-7.06 CURING SLOPE PROTECTION

• Concrete slope protection shall be cured in conformance with any of the methods specified in Section 90-7.01, "Methods of Curing."

• Concreted-rock slope protection shall be cured in conformance with any of the methods specified in Section 90-7.01, "Methods of Curing," or with a blanket of earth kept wet for 72 hours, or by sprinkling with a fine spray of water every 2 hours during the daytime for a period of 3 days.

90-7.07 CURING MISCELLANEOUS CONCRETE WORK

• Exposed surfaces of curbs shall be cured by pigmented curing compounds as specified in Section 90-7.01B, "Curing Compound Method."

• Concrete sidewalks, gutter depressions, island paving, curb ramps, driveways, and other miscellaneous concrete areas shall be cured in conformance with any of the methods specified in Section 90-7.01, "Methods of Curing."

• Shotcrete shall be cured for at least 72 hours by spraying with water, or by a moist earth blanket, or by any of the methods provided in Section 90-7.01, "Methods of Curing."

• Mortar and grout shall be cured by keeping the surface damp for 3 days.

• After placing, the exposed surfaces of sign structure foundations, including pedestal portions, if constructed, shall be cured for at least 72 hours by spraying with water, or by a moist earth blanket, or by any of the methods provided in Section 90-7.01, "Methods of Curing."

90-8 PROTECTING CONCRETE

90-8.01 GENERAL

• In addition to the provisions in Section 7-1.16, "Contractor's Responsibility for the Work and Materials," the Contractor shall protect concrete as provided in this Section 90-8.

• Concrete shall not be placed on frozen or ice-coated ground or subgrade nor on ice-coated forms, reinforcing steel, structural steel, conduits, precast members, or construction joints.

• Under rainy conditions, placing of concrete shall be stopped before the quantity of surface water is sufficient to damage surface mortar or cause a flow or wash of the concrete surface, unless the Contractor provides adequate protection against damage.

• Concrete that has been frozen or damaged by other causes, as determined by the Engineer, shall be removed and replaced by the Contractor at the Contractor's expense.

90-8.02 PROTECTING CONCRETE STRUCTURES

• Structure concrete and shotcrete used as structure concrete shall be maintained at a temperature of not less than 7°C for 72 hours after placing and at not less than 4°C for an additional 4 days. When required by the Engineer, the Contractor shall submit a written outline of the proposed methods for protecting the concrete.

90-8.03 PROTECTING CONCRETE PAVEMENT

• Pavement concrete shall be maintained at a temperature of not less than 4°C for 72 hours. When required by the Engineer, the Contractor shall submit a written outline of the proposed methods for protecting the concrete.

• Except as provided in Section 7-1.08, "Public Convenience," the Contractor shall protect concrete pavement against construction and other activities that abrade, scar, discolor, reduce texture depth, lower coefficient of friction, or otherwise damage the surface. Stockpiling, drifting, or excessive spillage of soil, gravel, petroleum products, and concrete or asphalt mixes on the surface of concrete pavement is prohibited unless otherwise specified in these specifications, the special provisions or permitted by the Engineer.

• When ordered by the Engineer or shown on the plans or specified in the special provisions, pavement crossings shall be constructed for the convenience of public traffic. The material and work necessary for the construction of the crossings, and their subsequent removal and disposal, will be paid for at the contract unit prices for the items of work involved and if there are no contract items for the work involved, payment for pavement crossings will be made by extra work as provided in Section 4-1.03D, "Extra Work.". Where public traffic will be required to cross over the new pavement, Type III portland cement may be used in concrete, if permitted in writing by the Engineer. The pavement may be opened to traffic as soon as the concrete has developed a modulus of rupture of 3.8 MPa. The modulus of rupture will be determined by California Test 523.

• No traffic or Contractor's equipment, except as hereinafter provided, will be permitted on the pavement before a period of 10 days has elapsed after the concrete has been placed, nor before the concrete has developed a modulus of rupture of at least 3.8 MPa. Concrete that fails to attain a modulus of rupture of 3.8 MPa within 10 days shall not be opened to traffic until directed by the Engineer.

• Equipment for sawing weakened plane joints will be permitted on the pavement as specified in Section 40-1.08B, "Weakened Plane Joints."

• When requested in writing by the Contractor, the tracks on one side of paving equipment will be permitted on the pavement after a modulus of rupture of 2.4 MPa has been attained, provided that:

A. Unit pressure exerted on the pavement by the paver shall not exceed 135 kPa;
B. Tracks with cleats, grousers, or similar protuberances shall be modified or shall travel on planks or equivalent protective material, so that the pavement is not damaged; and
C. No part of the track shall be closer than 0.3-m from the edge of pavement.

• In case of visible cracking of, or other damage to the pavement, operation of the paving equipment on the pavement shall be immediately discontinued.

• Damage to the pavement resulting from early use of pavement by the Contractor's equipment as provided above shall be repaired by the Contractor at the Contractor's expense.

• The State will furnish the molds and machines for testing the concrete for modulus of rupture, and the Contractor, at the Contractor's expense, shall furnish the material and whatever labor the Engineer may require.

90-9 COMPRESSIVE STRENGTH

90-9.01 GENERAL

• Concrete compressive strength requirements consist of a minimum strength that shall be attained before various loads or stresses are applied to the concrete and, for concrete designated by strength, a minimum strength at the age of 28 days or at the age otherwise allowed in Section 90-1.01, "Description." The various strengths required are specified in these specifications or the special provisions or are shown on the plans.

- The compressive strength of concrete will be determined from test cylinders that have been fabricated from concrete sampled in conformance with the requirements of California test 539. Test cylinders will be molded and initially field cured in conformance with California Test 540. Test cylinders will be cured and tested after receipt at the testing laboratory in conformance with the requirements of California test 521. A strength test shall consist of the average strength of 2 cylinders fabricated from material taken from a single load of concrete, except that, if any cylinder should show evidence of improper sampling, molding, or testing, that cylinder shall be discarded and the strength test shall consist of the strength of the remaining cylinder.
- When concrete compressive strength is specified as a prerequisite to applying loads or stresses to a concrete structure or member, test cylinders for other than steam cured concrete will be cured in conformance with Method 1 of California Test 540. The compressive strength of concrete determined for these purposes will be evaluated on the basis of individual tests.
- When concrete is designated by 28-day compressive strength rather than by cementitious material content, the concrete strength to be used as a basis for acceptance of other than steam cured concrete will be determined from cylinders cured in conformance with Method 1 of California Test 540. If the result of a single compressive strength test at the maximum age specified or allowed is below the specified strength but is 95 percent or more of the specified strength, the Contractor shall, at the Contractor's expense, make corrective changes, subject to approval of the Engineer, in the mix proportions or in the concrete fabrication procedures, before placing additional concrete, and shall pay to the State $14 for each in-place cubic meter of concrete represented by the deficient test. If the result of a single compressive strength test at the maximum age specified or allowed is below 95 percent of the specified strength, but is 85 percent or more of the specified strength, the Contractor shall make the corrective changes specified above, and shall pay to the State $20 for each in place cubic meter of concrete represented by the deficient test. In addition, such corrective changes shall be made when the compressive strength of concrete tested at 7 days indicates, in the judgment of the Engineer, that the concrete will not attain the required compressive strength at the maximum age specified or allowed. Concrete represented by a single test that indicates a compressive strength of less than 85 percent of the specified 28-day compressive strength will be rejected in conformance with the provisions in Section 6-1.04, "Defective Materials."
- If the test result indicates that the compressive strength at the maximum curing age specified or allowed is below the specified strength, but is 85 percent or more of the specified strength, payments to the State as required above shall be made, unless the Contractor, at the Contractor's expense, obtains and submits evidence acceptable to the Engineer that the strength of the concrete placed in the work meets or exceeds the specified 28-day compressive strength. If the test result indicates a compressive strength at the maximum curing age specified or allowed below 85 percent, the concrete represented by that test will be rejected, unless the Contractor, at the Contractor's expense, obtains and submits evidence acceptable to the Engineer that the strength and quality of the concrete placed in the work are acceptable. If the evidence consists of tests made on cores taken from the work, the cores shall be obtained and tested in conformance with the requirements in ASTM Designation: C 42.
- No single compressive strength test shall represent more than 250 m^3.
- When a precast concrete member is steam cured, the compressive strength of the concrete will be determined from test cylinders that have been handled and stored in conformance with Method 3 of California Test 540. The compressive strength of steam cured concrete will be evaluated on the basis of individual tests representing specific portions of production. When the concrete is designated by 28-day compressive strength rather than by cementitious material content, the concrete shall be considered to be acceptable whenever its compressive strength reaches the specified 28-day compressive strength provided that strength is reached in not more than the maximum number of days specified or allowed after the member is cast.
- When concrete is specified by compressive strength, prequalification of materials, mix proportions, mixing equipment, and procedures proposed for use will be required prior to placement of the concrete. Prequalification shall be accomplished by the submission of acceptable certified test data or trial batch reports by the Contractor. Prequalification data shall be based on the use of materials, mix proportions, mixing equipment, procedures, and size of batch proposed for use in the work.
- Certified test data, in order to be acceptable, shall indicate that not less than 90 percent of at least 20 consecutive tests exceed the specified strength at the maximum number of cure days specified or allowed, and none of those tests are less than 95 percent of specified strength. Strength tests included in the data shall be the most recent tests made on concrete of the proposed mix design and all shall have been made within one year of the proposed use of the concrete.
- Trial batch test reports, in order to be acceptable, shall indicate that the average compressive strength of 5 consecutive concrete cylinders, taken from a single batch, at not more than 28 days (or the maximum age allowed) after molding shall be at least 4 MPa greater than the specified 28-day compressive strength, and no individual cylinder shall have a strength less than the specified strength at the maximum age specified or allowed. Data contained in the report shall be from trial batches that were produced within one year of the proposed use of specified strength concrete in the project. Whenever air-entrainment is required, the air content of trial batches shall be equal to or greater than the air content specified for the concrete without reduction due to tolerances.

- Tests shall be performed in conformance with either the appropriate California Test methods or the comparable ASTM test methods. Equipment employed in testing shall be in good condition and shall be properly calibrated. If the tests are performed during the life of the contract, the Engineer shall be notified sufficiently in advance of performing the tests in order to witness the test procedures.
- The certified test data and trial batch test reports shall include the following information:

A. Date of mixing.
B. Mixing equipment and procedures used.
C. The size of batch in cubic meters and the mass, type, and source of all ingredients used.
D. Penetration of the concrete.
E. The air content of the concrete if an air-entraining admixture is used.
F. The age at time of testing and strength of all concrete cylinders tested.

- Certified test data and trial batch test reports shall be signed by an official of the firm that performed the tests.
- When approved by the Engineer, concrete from trial batches may be used in the work at locations where concrete of a lower quality is required and the concrete will be paid for as the type or class of concrete required at that location.
- After materials, mix proportions, mixing equipment, and procedures for concrete have been prequalified for use, additional prequalification by testing of trial batches will be required prior to making changes that, in the judgment of the Engineer, could result in a strength of concrete below that specified.
- The Contractor's attention is directed to the time required to test trial batches and the Contractor shall be responsible for production of trial batches at a sufficiently early date so that the progress of the work is not delayed.
- When precast concrete members are manufactured at the plant of an established manufacturer of precast concrete members, the mix proportions of the concrete shall be determined by the Contractor, and a trial batch and prequalification of the materials, mix proportions, mixing equipment, and procedures will not be required.

90-10 MINOR CONCRETE

90-10.01 GENERAL

- Concrete for minor structures, slope paving, curbs, sidewalks and other concrete work, when designated as minor concrete on the plans, in the specifications, or in the contract item, shall conform to the provisions specified herein.
- The Engineer, at the Engineer's discretion, will inspect and test the facilities, materials and methods for producing the concrete to ensure that minor concrete of the quality suitable for use in the work is obtained.

90-10.02 MATERIALS

- Minor concrete shall conform to the following requirements:

90-10.02A Cementitious Material

- Cementitious material shall conform to the provisions in Section 90-1.01, "Description."

90-10.02B Aggregate

- Aggregate shall be clean and free from deleterious coatings, clay balls, roots, and other extraneous materials.
- The Contractor shall submit to the Engineer for approval, a grading of the combined aggregate proposed for use in the minor concrete. After acceptance of the grading, aggregate furnished for minor concrete shall conform to that grading, unless a change is authorized in writing by the Engineer.
- The Engineer may require the Contractor to furnish periodic test reports of the aggregate grading furnished. The maximum size of aggregate used shall be at the option of the Contractor, but in no case shall the maximum size be larger than 37.5 mm or smaller than 19 mm.
- The Engineer may waive, in writing, the gradation requirements in this Section 90-10.02B, if, in the Engineer's opinion, the furnishing of the gradation is not necessary for the type or amount of concrete work to be constructed.

90-10.02C Water

- Water used for washing, mixing, and curing shall be free from oil, salts, and other impurities that would discolor or etch the surface or have an adverse affect on the quality of the concrete.

90-10.02D Admixtures

- The use of admixtures shall conform to the provisions in Section 90-4, "Admixtures."

90-10.03 PRODUCTION

- Cementitious material, water, aggregate, and admixtures shall be stored, proportioned, mixed, transported, and discharged in conformance with recognized standards of good practice that will result in concrete that is thoroughly and uniformly mixed, that is suitable for the use intended, and that conforms to requirements specified herein. Recognized standards of good practice are outlined in various industry publications such as are issued by American Concrete Institute, AASHTO, or the Department.
- The cementitious material content of minor concrete shall conform to the provisions in Section 90-1.01, "Description."
- The amount of water used shall result in a consistency of concrete conforming to the provisions in Section 90-6.06, "Amount of Water and Penetration." Additional mixing water shall not be incorporated into the concrete during hauling or after arrival at the delivery point, unless authorized by the Engineer.
- Discharge of ready-mixed concrete from the transporting vehicle shall be made while the concrete is still plastic and before stiffening occurs. An elapsed time of 1.5 hours (one hour in non-agitating hauling equipment), or more than 250 revolutions of the drum or blades, after the introduction of the cementitious material to the aggregates, or a temperature of concrete of more than 32°C will be considered conditions contributing to the quick stiffening of concrete. The Contractor shall take whatever action is necessary to eliminate quick stiffening, except that the addition of water will not be permitted.
- The required mixing time in stationary mixers shall be not less than 50 seconds or more than 5 minutes.
- The minimum required revolutions at mixing speed for transit-mixed concrete shall be not less than that recommended by the mixer manufacturer, and shall be increased, if necessary, to produce thoroughly and uniformly mixed concrete.
- Each load of ready-mixed concrete shall be accompanied by a weighmaster certificate that shall be delivered to the Engineer at the discharge location of the concrete, unless otherwise directed by the Engineer. The weighmaster certificate shall be clearly marked with the date and time of day when the load left the batching plant and, if hauled in truck mixers or agitators, the time the mixing cycle started.
- A Certificate of Compliance conforming to the provisions in Section 6–1.07, "Certificates of Compliance," shall be furnished to the Engineer, prior to placing minor concrete from a source not previously used on the contract, stating that minor concrete to be furnished meets contract requirements, including minimum cementitious material content specified.

90-10.04 CURING MINOR CONCRETE

- Curing minor concrete shall conform to the provisions in Section 90-7, "Curing Concrete."

90-10.05 PROTECTING MINOR CONCRETE

- Protecting minor concrete shall conform to the provisions in Section 90-8, "Protecting Concrete," except the concrete shall be maintained at a temperature of not less than 4°C for 72 hours after placing.

90-10.06 MEASUREMENT AND PAYMENT

- Minor concrete will be measured and paid for in conformance with the provisions specified in the various sections of these specifications covering concrete construction when minor concrete is specified in the specifications, shown on the plans, or indicated by contract item in the Engineer's Estimate.

90-11 MEASUREMENT AND PAYMENT

90-11.01 MEASUREMENT

- Portland cement concrete will be measured in conformance with the provisions specified in the various sections of these specifications covering construction requiring concrete.
- When it is provided that concrete will be measured at the mixer, the volume in cubic meters shall be computed as the total mass of the batch in kilograms divided by the density of the concrete in kilograms per cubic meter. The total mass of the batch shall be calculated as the sum of all materials, including water, entering the batch. The density of the concrete will be determined in conformance with the requirements in California Test 518.

90-11.02 PAYMENT

- Portland cement concrete will be paid for in conformance with the provisions specified in the various sections of these specifications covering construction requiring concrete.

- Full compensation for furnishing and incorporating admixtures required by these specifications or the special provisions will be considered as included in the contract prices paid for the concrete involved and no additional compensation will be allowed therefor.
- Should the Engineer order the Contractor to incorporate any admixtures in the concrete when their use is not required by these specifications or the special provisions, furnishing the admixtures and adding them to the concrete will be paid for as extra work as provided in Section 4-1.03D, "Extra Work."
- Should the Contractor use admixtures in conformance with the provisions in Section 90-4.05, "Optional Use of Chemical Admixtures," or Section 90-4.07, "Optional Use of Air-entraining Admixtures," or should the Contractor request and obtain permission to use other admixtures for the Contractor's benefit, the Contractor shall furnish those admixtures and incorporate them into the concrete at the Contractor's expense and no additional compensation will be allowed therefor.

END OF AMENDMENTS

SECTION 2. PROPOSAL REQUIREMENTS AND CONDITIONS

2-1.01 GENERAL

The bidder's attention is directed to the provisions in Section 2, "Proposal Requirements and Conditions," of the Standard Specifications and these special provisions for the requirements and conditions which the bidder must observe in the preparation of the Proposal form and the submission of the bid.

In addition to the subcontractors required to be listed in conformance with Section 2-1.054, "Required Listing of Proposed Subcontractors," of the Standard Specifications, each proposal shall have listed therein the portion of work that will be performed by each subcontractor listed.

The proposal shall set forth the unit prices, item totals, TOTAL BID (A), the number of working days bid for completion of the work, except plant establishment, the product of the working days bid and the cost per day shown on the Engineer's Estimate (TOTAL BID (B)), and the "Total Basis for Comparison of Bids (A+B)," in clearly legible figures, in the respective spaces provided, and shall be signed by the bidder, who shall fill out the blanks in the proposal form as therein required.

The Bidder's Bond form mentioned in the last paragraph in Section 2-1.07, "Proposal Guaranty," of the Standard Specifications will be found following the signature page of the Proposal.

The amount of the bidder's security required in Section 2-1.07, "Proposal Guaranty," of the Standard Specifications shall be based on the "TOTAL BID (A)" set forth on the proposal form.

Submit request for substitution of an "or equal" item, and the data substantiating the request to the Department of Transportation, Division Of Construction - Duty Senior, Mail Station: 3 - B, 111 Grand Avenue / P. O. Box 23660, Oakland, Ca 94623-0660, so that the request is received by the Department by close of business on the fourth day, not including Saturdays, Sundays and legal holidays, following bid opening.

In conformance with Public Contract Code Section 7106, a Noncollusion Affidavit is included in the Proposal. Signing the Proposal shall also constitute signature of the Noncollusion Affidavit.

The contractor, sub recipient or subcontractor shall not discriminate on the basis of race, color, national origin, or sex in the performance of this contract. The contractor shall carry out applicable requirements of 49 CFR part 26 in the award and administration of DOT-assisted contracts. Failure by the contractor to carry out these requirements is a material breach of this contract, which may result in the termination of this contract or such other remedy as the recipient deems appropriate. Each subcontract signed by the bidder must include this assurance.

2-1.015 FEDERAL LOBBYING RESTRICTIONS

Section 1352, Title 31, United States Code prohibits Federal funds from being expended by the recipient or any lower tier subrecipient of a Federal-aid contract to pay for any person for influencing or attempting to influence a Federal agency or Congress in connection with the awarding of any Federal-aid contract, the making of any Federal grant or loan, or the entering into of any cooperative agreement.

If any funds other than Federal funds have been paid for the same purposes in connection with this Federal-aid contract, the recipient shall submit an executed certification and, if required, submit a completed disclosure form as part of the bid documents.

A certification for Federal-aid contracts regarding payment of funds to lobby Congress or a Federal agency is included in the Proposal. Standard Form - LLL, "Disclosure of Lobbying Activities," with instructions for completion of the Standard Form is also included in the Proposal. Signing the Proposal shall constitute signature of the Certification.

The above-referenced certification and disclosure of lobbying activities shall be included in each subcontract and any lower-tier contracts exceeding $100,000. All disclosure forms, but not certifications, shall be forwarded from tier to tier until received by the Engineer.

The Contractor, subcontractors and any lower-tier contractors shall file a disclosure form at the end of each calendar quarter in which there occurs any event that requires disclosure or that materially affects the accuracy of the information contained in any disclosure form previously filed by the Contractor, subcontractors and any lower-tier contractors. An event that materially affects the accuracy of the information reported includes:

A. A cumulative increase of $25,000 or more in the amount paid or expected to be paid for influencing or attempting to influence a covered Federal action; or
B. A change in the person(s) or individual(s) influencing or attempting to influence a covered Federal action; or,
C. A change in the officer(s), employee(s), or Member(s) contacted to influence or attempt to influence a covered Federal action.

2-1.02 DISADVANTAGED BUSINESS ENTERPRISE (DBE)

This project is subject to Part 26, Title 49, Code of Federal Regulations entitled "Participation by Disadvantaged Business Enterprises in Department of Transportation Financial Assistance Programs." The Regulations in their entirety are incorporated herein by this reference.

Bidders shall be fully informed respecting the requirements of the Regulations and the Department's Disadvantaged Business Enterprise (DBE) program developed pursuant to the Regulations; particular attention is directed to the following matters:

A. A DBE must be a small business concern as defined pursuant to Section 3 of U.S. Small Business Act and relevant regulations promulgated pursuant thereto.
B. A DBE may participate as a prime contractor, subcontractor, joint venture partner with a prime or subcontractor, vendor of material or supplies, or as a trucking company.
C. A DBE bidder, not bidding as a joint venture with a non-DBE, will be required to document one or a combination of the following:

    1. The bidder will meet the goal by performing work with its own forces.
    2. The bidder will meet the goal through work performed by DBE subcontractors, suppliers or trucking companies.
    3. The bidder, prior to bidding, made adequate good faith efforts to meet the goal.

D. A DBE joint venture partner must be responsible for specific contract items of work, or portions thereof. Responsibility means actually performing, managing and supervising the work with its own forces. The DBE joint venture partner must share in the capital contribution, control, management, risks and profits of the joint venture. The DBE joint venturer must submit the joint venture agreement with the proposal or the DBE Information form required in the Section entitled "Submission of DBE Information" of these special provisions.
E. A DBE must perform a commercially useful function, i.e., must be responsible for the execution of a distinct element of the work and must carry out its responsibility by actually performing, managing and supervising the work.
F. DBEs must be certified by the California Unified Certification Program (CUCP). It is the contractor's responsibility to confirm that the firm is DBE certified as of the date of bid opening. Listings of DBEs certified by the CUCP are available from the following sources:

    1. The Department's DBE Directory, which is published quarterly. This Directory may be obtained from the Department of Transportation, Materiel Operations Branch, Publication Distribution Unit, 1900 Royal Oaks Drive, Sacramento, California 95815, Telephone: (916) 445-3520.
    2. The Department's web site at http://www.dot.ca.gov/hq/bep.
    3. The organizations listed in the Section entitled "DBE Goal for this Project" of these special provisions.

G. Credit for materials or supplies purchased from DBEs will be as follows:

    1. If the materials or supplies are obtained from a DBE manufacturer, 100 percent of the cost of the materials or supplies will count toward the DBE goal. A DBE manufacturer is a firm that operates or maintains a factory or establishment that produces, on the premises, the materials, supplies, articles, or equipment required under the contract and of the general character described by the specifications.
    2. If the materials or supplies are purchased from a DBE regular dealer, 60 percent of the cost of the materials or supplies will count toward the DBE goal. A DBE regular dealer is a firm that owns, operates, or maintains a

store, warehouse, or other establishment in which the materials, supplies, articles or equipment of the general character described by the specifications and required under the contract are bought, kept in stock, and regularly sold or leased to the public in the usual course of business. To be a DBE regular dealer, the firm must be an established, regular business that engages, as its principal business and under its own name, in the purchase and sale or lease of the products in question. A person may be a DBE regular dealer in such bulk items as petroleum products, steel, cement, gravel, stone, or asphalt without owning, operating, or maintaining a place of business as provided in this paragraph G.2. if the person both owns and operates distribution equipment for the products. Any supplementing of regular dealers' own distribution equipment shall be by a long-term lease agreement and not on an ad hoc or contract-by-contract basis. Packagers, brokers, manufacturers' representatives, or other persons who arrange or expedite transactions are not DBE regular dealers within the meaning of this paragraph G.2.

3. Credit for materials or supplies purchased from a DBE which is neither a manufacturer nor a regular dealer will be limited to the entire amount of fees or commissions charged for assistance in the procurement of the materials and supplies, or fees or transportation charges for the delivery of materials or supplies required on a job site, provided the fees are reasonable and not excessive as compared with fees charged for similar services.

H. Credit for DBE trucking companies will be as follows:

1. The DBE must be responsible for the management and supervision of the entire trucking operation for which it is responsible on a particular contract, and there cannot be a contrived arrangement for the purpose of meeting the DBE goal.
2. The DBE must itself own and operate at least one fully licensed, insured, and operational truck used on the contract.
3. The DBE receives credit for the total value of the transportation services it provides on the contract using trucks its owns, insures, and operates using drivers it employs.
4. The DBE may lease trucks from another DBE firm, including an owner-operator who is certified as a DBE. The DBE who leases trucks from another DBE receives credit for the total value of the transportation services the lessee DBE provides on the contract.
5. The DBE may also lease trucks from a non-DBE firm, including an owner-operator. The DBE who leases trucks from a non-DBE is entitled to credit only for the fee or commission it receives as a result of the lease arrangement. The DBE does not receive credit for the total value of the transportation services provided by the lessee, since these services are not provided by a DBE.
6. For the purposes of this paragraph H, a lease must indicate that the DBE has exclusive use of and control over the truck. This does not preclude the leased truck from working for others during the term of the lease with the consent of the DBE, so long as the lease gives the DBE absolute priority for use of the leased truck. Leased trucks must display the name and identification number of the DBE.

I. Noncompliance by the Contractor with the requirements of the regulations constitutes a breach of this contract and may result in termination of the contract or other appropriate remedy for a breach of this contract.

J. Bidders are encouraged to use services offered by financial institutions owned and controlled by DBEs.

2-1.02A DBE GOAL FOR THIS PROJECT

The Department has established the following goal for Disadvantaged Business Enterprise (DBE) participation for this project:

Disadvantaged Business Enterprise (DBE): 16 percent

Bidders may use the services of the following firms to contact interested DBEs. These firms are available to assist DBEs in preparing bids for subcontracting or supplying materials.

The following firms may be contacted for projects in the following locations:

Districts 04, 05 (except San Luis Obispo and Santa Barbara Counties), 06 (except Kern County) and 10:	Districts 08 and 11:
Triaxial Management Services, Inc. - Oakland 1545 Willow Street, 1st Floor Oakland, CA 94607 Telephone: (510) 286-1313 FAX No.: (510) 286-6792	Padilla & Associates - San Diego 2725 Congress Street, Suite 1D San Diego, CA 92110 Telephone: (619) 725-0843 FAX No.: (619) 725-0854

Districts 07, 08, and 12; in San Luis Obispo and Santa Barbara Counties in District 05; and in Kern County in District 06:	Districts 01, 02, 03 and 09:
Padilla & Associates - Los Angeles 5675 East Telegraph Rd., Suite A-260 Los Angeles, CA 90040 Telephone: (323) 728-8847 FAX No.: (323) 728-8867	Triaxial Management Services, Inc. - Sacramento 930 Alhambra Blvd., #205 Sacramento, CA 95816 Telephone: (916) 553-4172 FAX No.: (916) 553-4173

2-1.02B SUBMISSION OF DBE INFORMATION

The required DBE information shall be submitted on the "CALTRANS BIDDER - DBE INFORMATION" form included in the Proposal. If the DBE information is not submitted with the bid, the DBE Information form shall be removed from the documents prior to submitting the bid.

It is the bidder's responsibility to make enough work available to DBEs and to select those portions of the work or material needs consistent with the available DBEs to meet the goal for DBE participation or to provide information to establish that, prior to bidding, the bidder made adequate good faith efforts to do so.

If DBE information is not submitted with the bid, the apparent successful bidder (low bidder), the second low bidder and the third low bidder shall submit DBE information to the Department of Transportation, 1120 N Street, Room 0200, MS #26, Sacramento, California 95814 so the information is received by the Department no later than 4:00 p.m. on the fourth day, not including Saturdays, Sundays and legal holidays, following bid opening. DBE information sent by U.S. Postal Service certified mail with return receipt and certificate of mailing and mailed on or before the third day, not including Saturdays, Sundays and legal holidays, following bid opening will be accepted even if it is received after the fourth day following bid opening. Failure to submit the required DBE information by the time specified will be grounds for finding the bid or proposal nonresponsive. Other bidders need not submit DBE information unless requested to do so by the Department.

The bidder's DBE information shall establish that good faith efforts to meet the DBE goal have been made. To establish good faith efforts, the bidder shall demonstrate that the goal will be met or that, prior to bidding, adequate good faith efforts to meet the goal were made.

Bidders are cautioned that even though their submittal indicates they will meet the stated DBE goal, their submittal should also include their adequate good faith efforts information along with their DBE goal information to protect their eligibility for award of the contract in the event the Department, in its review, finds that the goal has not been met.

The bidder's DBE information shall include the names, addresses and phone numbers of DBE firms that will participate, with a complete description of work or supplies to be provided by each, the dollar value of each DBE transaction, and a written confirmation from the DBE that it is participating in the contract. A copy of the DBE's quote will serve as written confirmation that the DBE is participating in the contract. When 100 percent of a contract item of work is not to be performed or furnished by a DBE, a description of the exact portion of that work to be performed or furnished by that DBE shall be included in the DBE information, including the planned location of that work. The work that a DBE prime contractor has committed to performing with its own forces as well as the work that it has committed to be performed by DBE subcontractors, suppliers and trucking companies will count toward the goal.

The information necessary to establish the bidder's adequate good faith efforts to meet the DBE goal should include:

A. The names and dates of each publication in which a request for DBE participation for this project was placed by the bidder.
B. The names and dates of written notices sent to certified DBEs soliciting bids for this project and the dates and methods used for following up initial solicitations to determine with certainty whether the DBEs were interested.
C. The items of work which the bidder made available to DBE firms, including, where appropriate, any breaking down of the contract work items (including those items normally performed by the bidder with its own forces) into economically feasible units to facilitate DBE participation. It is the bidder's responsibility to demonstrate that sufficient work to meet the DBE goal was made available to DBE firms.
D. The names, addresses and phone numbers of rejected DBE firms, the firms selected for that work, and the reasons for the bidder's choice.
E. Efforts made to assist interested DBEs in obtaining bonding, lines of credit or insurance, and any technical assistance or information related to the plans, specifications and requirements for the work which was provided to DBEs.
F. Efforts made to assist interested DBEs in obtaining necessary equipment, supplies, materials, or related assistance or services, excluding supplies and equipment the DBE subcontractor purchases or leases from the prime contractor or its affiliate.
G. The names of agencies contacted to provide assistance in contacting, recruiting and using DBE firms.
H. Any additional data to support a demonstration of good faith efforts.

SECTION 3. AWARD AND EXECUTION OF CONTRACT

The bidder's attention is directed to the provisions in Section 3, "Award and Execution of Contract," of the Standard Specifications and these special provisions for the requirements and conditions concerning award and execution of contract.

Bids will be compared on the basis of the Engineer's Estimate of the quantities of work to be done and the number of working days bid for completion of the work, except plant establishment. The award of the contract, if it be awarded, will be to the lowest responsible bidder whose proposal complies with all the requirements prescribed and who has met the goal for DBE participation or has demonstrated, to the satisfaction of the Department, adequate good faith efforts to do so. Meeting the goal for DBE participation or demonstrating, to the satisfaction of the Department, adequate good faith efforts to do so is a condition for being eligible for award of contract. The lowest bid will be determined on the basis of the "Total Basis for Comparison of Bids (A+B)" set forth in the proposal. The contract price for the awarded contract will be the "Total Bid (A)" set forth in the proposal.

Bids in which the number of working days bid for completion of the work, except plant establishment, exceed 525 will be considered non-responsive and will be rejected.

The contract shall be executed by the successful bidder and shall be returned, together with the contract bonds, to the Department so that it is received within 10 days, not including Saturdays, Sundays and legal holidays, after the bidder has received the contract for execution. Failure to do so shall be just cause for forfeiture of the proposal guaranty. The executed contract documents shall be delivered to the following address: Department of Transportation MS 43, Attn: Office Engineer, 1727 30th Street, Sacramento, CA 95816.

A "Payee Data Record" form will be included in the contract documents to be executed by the successful bidder. The purpose of the form is to facilitate the collection of taxpayer identification data. The form shall be completed and returned to the Department by the successful bidder with the executed contract and contract bonds. For the purposes of the form, payee shall be deemed to mean the successful bidder. The form is not to be completed for subcontractors or suppliers. Failure to complete and return the "Payee Data Record" form to the Department as provided herein will result in the retention of 31 percent of payments due the contractor and penalties of up to $20,000. This retention of payments for failure to complete the "Payee Data Record" form is in addition to any other retention of payments due the Contractor.

SECTION 4. BEGINNING OF WORK, TIME OF COMPLETION AND LIQUIDATED DAMAGES

Attention is directed to the provisions in Sections 8-1.03, "Beginning of Work," 8-1.06, "Time of Completion," 8-1.07, "Liquidated Damages," and 20-4.08, "Plant Establishment Work," of the Standard Specifications and these special provisions.

The Contractor shall begin work within 15 calendar days after the contract has been approved by the Attorney General or the attorney appointed and authorized to represent the Department of Transportation.

The work, except plant establishment work, shall be diligently prosecuted to completion before the expiration of **the NUMBER OF WORKING DAYS BID** beginning on the fifteenth calendar day after approval of the contract.

The Contractor shall pay to the State of California the sum of $15,000 per day, for each and every calendar day's delay in finishing the work, except plant establishment work, after expiration of the number of working days bid, until work requiring closure of lanes or shoulders on State Highway Route 101 is complete, and the new structure terminating at Market/Octavia has been opened to public traffic.

The Contractor shall pay to the State of California the sum of $7,000 per day, for each and every calendar day's delay in finishing the work, except plant establishment work, after expiration of the number of working days bid, if no further lane or shoulder closures are required on State Highway Route 101 to complete the remaining work, and the new structure terminating at Market/Octavia has been opened to public traffic.

The Contractor shall diligently prosecute the plant establishment work to completion before the expiration of the number of working days specified in Section 10-2.04, "Highway Planting," of these special provisions, beginning on the day after completion of the planting work (except plant establishment work and other items of work specified to be performed for the life of the contract). The Contractor shall pay to the State of California the sum of $600 per day, for each and every calendar day's delay in completing the plant establishment work in excess of the number of working days specified.

In no case will liquidated damages of more than $22,000 per day be assessed.

SECTION 5. GENERAL

SECTION 5-1. MISCELLANEOUS

5-1.01 PLANS AND WORKING DRAWINGS

When the specifications require working drawings to be submitted to the Division of Structure Design, the drawings shall be submitted to: Division of Structure Design, Documents Unit, Mail Station 9, 1801 30th Street, Sacramento, CA 95816, Telephone 916 227-8252.

5-1.011 EXAMINATION OF PLANS, SPECIFICATIONS, CONTRACT, AND SITE OF WORK

Attention is directed to "Differing Site Conditions" of these special provisions regarding physical conditions at the site which may differ from those indicated in "Materials Information," log of test borings or other geotechnical information obtained by the Department's investigation of site conditions.

5-1.012 DIFFERING SITE CONDITIONS

Attention is directed to Section 5-1.116, "Differing Site Conditions," of the Standard Specifications.

During the progress of the work, if subsurface or latent conditions are encountered at the site differing materially from those indicated in the "Materials Information," log of test borings, other geotechnical data obtained by the Department's investigation of subsurface conditions, or an examination of the conditions above ground at the site, the party discovering those conditions shall promptly notify the other party in writing of the specific differing conditions before they are disturbed and before the affected work is performed.

The Contractor will be allowed 15 days from the notification of the Engineer's determination of whether or not an adjustment of the contract is warranted, in which to file a notice of potential claim in conformance with the provisions of Section 9-1.04, "Notice of Potential Claim," of the Standard Specifications and as specified herein; otherwise the decision of the Engineer shall be deemed to have been accepted by the Contractor as correct. The notice of potential claim shall set forth in what respects the Contractor's position differs from the Engineer's determination and provide any additional information obtained by the Contractor, including but not limited to additional geotechnical data. The notice of potential claim shall be accompanied by the Contractor's certification that the following were made in preparation of the bid: a review of the contract, a review of the "Materials Information," a review of the log of test borings and other records of geotechnical data to the extent they were made available to bidders prior to the opening of bids, and an examination of the conditions above ground at the site. Supplementary information, obtained by the Contractor subsequent to the filing of the notice of potential claim, shall be submitted to the Engineer in an expeditious manner.

5-1.013 LINES AND GRADES

Attention is directed to Section 5-1.07, "Lines and Grades," of the Standard Specifications.

Stakes or marks will be set by the Engineer in conformance with the requirements in Chapter 12, "Construction Surveys," of the Department's Surveys Manual.

5-1.015 LABORATORY

When a reference is made in the specifications to the "Laboratory," the reference shall mean Division of Engineering Services - Materials Engineering and Testing Services and Division of Engineering Services - Geotechnical Services of the Department of Transportation, or established laboratories of the various Districts of the Department, or other laboratories authorized by the Department to test materials and work involved in the contract. When a reference is made in the specifications to the "Transportation Laboratory," the reference shall mean Division of Engineering Services - Materials

Engineering and Testing Services and Division of Engineering Services - Geotechnical Services, located at 5900 Folsom Boulevard, Sacramento, CA 95819, Telephone (916) 227-7000.

5-1.017 CONTRACT BONDS

Attention is directed to Section 3-1.02, "Contract Bonds," of the Standard Specifications and these special provisions.

The payment bond shall be in a sum not less than one hundred percent of the total amount payable by the terms of the contract.

5-1.019 COST REDUCTION INCENTIVE

Attention is directed to Section 5-1.14, "Cost Reduction Incentive," of the Standard Specifications.

Prior to preparing a written cost reduction proposal, the Contractor shall request a meeting with the Engineer to discuss the proposal in concept. Items of discussion will also include permit issues, impact on other projects, impact on the project schedule, peer reviews, overall merit of the proposal, and review times required by the Department and other agencies.

If a cost reduction proposal submitted by the Contractor, and subsequently approved by the Engineer, provides for a reduction in contract time, 50 percent of that contract time reduction shall be credited to the State by reducing the contract working days, not including plant establishment. Attention is directed to "Beginning of Work, Time of Completion and Liquidated Damages" of these special provisions regarding the working days.

If a cost reduction proposal submitted by the Contractor, and subsequently approved by the Engineer, provides for a reduction in traffic congestion or avoids traffic congestion during construction, 60 percent of the estimated net savings in construction costs attributable to the cost reduction proposal will be paid to the Contractor. In addition to the requirements in Section 5-1.14, "Cost Reduction Incentive," of the Standard Specifications, the Contractor shall provide detailed comparisons of the traffic handling between the existing contract and the proposed change, and estimates of the traffic volumes and congestion.

5-1.02 LABOR NONDISCRIMINATION

Attention is directed to the following Notice that is required by Chapter 5 of Division 4 of Title 2, California Code of Regulations.

NOTICE OF REQUIREMENT FOR NONDISCRIMINATION PROGRAM

(GOV. CODE, SECTION 12990)

Your attention is called to the "Nondiscrimination Clause", set forth in Section 7-1.01A(4), "Labor Nondiscrimination," of the Standard Specifications, which is applicable to all nonexempt State contracts and subcontracts, and to the "Standard California Nondiscrimination Construction Contract Specifications" set forth therein. The specifications are applicable to all nonexempt State construction contracts and subcontracts of $5000 or more.

5-1.022 PAYMENT OF WITHHELD FUNDS

Payment of withheld funds shall conform to Section 9-1.065, "Payment of Withheld Funds," of the Standard Specifications and these special provisions.

Funds withheld from progress payments to ensure performance of the contract that are eligible for payment into escrow or to an escrow agent pursuant to Section 10263 of the California Public Contract Code do not include funds withheld or deducted from payment due to failure of the Contractor to fulfill a contract requirement.

5-1.03 INTEREST ON PAYMENTS

Interest shall be payable on progress payments, payments after acceptance, final payments, extra work payments, and claim payments as follows:

A. Unpaid progress payments, payment after acceptance, and final payments shall begin to accrue interest 30 days after the Engineer prepares the payment estimate.
B. Unpaid extra work bills shall begin to accrue interest 30 days after preparation of the first pay estimate following receipt of a properly submitted and undisputed extra work bill. To be properly submitted, the bill must be submitted within 7 days of the performance of the extra work and in conformance with the provisions in Section 9-1.03C, "Records," and Section 9-1.06, "Partial Payments," of the Standard Specifications. An undisputed extra work bill not submitted within 7 days of performance of the extra work will begin to accrue interest 30 days after the preparation of the second pay estimate following submittal of the bill.

C. The rate of interest payable for unpaid progress payments, payments after acceptance, final payments, and extra work payments shall be 10 percent per annum.
D. The rate of interest payable on a claim, protest or dispute ultimately allowed under this contract shall be 6 percent per annum. Interest shall begin to accrue 61 days after the Contractor submits to the Engineer information in sufficient detail to enable the Engineer to ascertain the basis and amount of said claim, protest or dispute.

The rate of interest payable on any award in arbitration shall be 6 percent per annum if allowed under the provisions of Civil Code Section 3289.

5-1.04 PUBLIC SAFETY

The Contractor shall provide for the safety of traffic and the public in conformance with the provisions in Section 7-1.09, "Public Safety," of the Standard Specifications and these special provisions.

The Contractor shall install temporary railing (Type K) between a lane open to public traffic and an excavation, obstacle or storage area when the following conditions exist:

A. Excavations.—The near edge of the excavation is 3.6 m or less from the edge of the lane, except:

1. Excavations covered with sheet steel or concrete covers of adequate thickness to prevent accidental entry by traffic or the public.
2. Excavations less than 0.3-m deep.
3. Trenches less than 0.3-m wide for irrigation pipe or electrical conduit, or excavations less than 0.3-m in diameter.
4. Excavations parallel to the lane for the purpose of pavement widening or reconstruction.
5. Excavations in side slopes, where the slope is steeper than 1:4 (vertical:horizontal).
6. Excavations protected by existing barrier or railing.

B. Temporarily Unprotected Permanent Obstacles.—The work includes the installation of a fixed obstacle together with a protective system, such as a sign structure together with protective railing, and the Contractor elects to install the obstacle prior to installing the protective system; or the Contractor, for the Contractor's convenience and with permission of the Engineer, removes a portion of an existing protective railing at an obstacle and does not replace such railing complete in place during the same day.
C. Storage Areas.—Material or equipment is stored within 3.6 m of the lane and the storage is not otherwise prohibited by the provisions of the Standard Specifications and these special provisions.

The approach end of temporary railing (Type K), installed in conformance with the provisions in this section "Public Safety" and in Section 7-1.09, "Public Safety," of the Standard Specifications, shall be offset a minimum of 4.6 m from the edge of the traffic lane open to public traffic. The temporary railing shall be installed on a skew toward the edge of the traffic lane of not more than 0.3-m transversely to 3 m longitudinally with respect to the edge of the traffic lane. If the 4.6-m minimum offset cannot be achieved, the temporary railing shall be installed on the 10 to 1 skew to obtain the maximum available offset between the approach end of the railing and the edge of the traffic lane, and an array of temporary crash cushion modules shall be installed at the approach end of the temporary railing.

Temporary railing (Type K) shall conform to the provisions in Section 12-3.08, "Temporary Railing (Type K)," of the Standard Specifications. Temporary railing (Type K), conforming to the details shown on 1999 Standard Plan T3, may be used. Temporary railing (Type K) fabricated prior to January 1, 1993, and conforming to 1988 Standard Plan B11-30 may be used, provided the fabrication date is printed on the required Certificate of Compliance.

Temporary crash cushion modules shall conform to the provisions in "Temporary Crash Cushion Module" of these special provisions.

Except for installing, maintaining and removing traffic control devices, whenever work is performed or equipment is operated in the following work areas, the Contractor shall close the adjacent traffic lane unless otherwise provided in the Standard Specifications and these special provisions:

Approach Speed of Public Traffic (Posted Limit) (Kilometers Per Hour)	Work Areas
Over 72 (45 Miles Per Hour)	Within 1.8 m of a traffic lane but not on a traffic lane
56 to 72 (35 to 45 Miles Per Hour)	Within 0.9-m of a traffic lane but not on a traffic lane

The lane closure provisions of this section shall not apply if the work area is protected by permanent or temporary railing or barrier.

When traffic cones or delineators are used to delineate a temporary edge of a traffic lane, the line of cones or delineators shall be considered to be the edge of the traffic lane, however, the Contractor shall not reduce the width of an existing lane to less than 3 m without written approval from the Engineer.

When work is not in progress on a trench or other excavation that required closure of an adjacent lane, the traffic cones or portable delineators used for the lane closure shall be placed off of and adjacent to the edge of the traveled way. The spacing of the cones or delineators shall be not more than the spacing used for the lane closure.

Suspended loads or equipment shall not be moved nor positioned over public traffic or pedestrians.

Full compensation for conforming to the provisions in this section "Public Safety," including furnishing and installing temporary railing (Type K) and temporary crash cushion modules, shall be considered as included in the contract prices paid for the various items of work involved and no additional compensation will be allowed therefor.

5-1.05 TESTING

Testing of materials and work shall conform to the provisions in Section 6-3, "Testing," of the Standard Specifications and these special provisions.

Whenever the provisions of Section 6-3.01, "General," of the Standard Specifications refer to tests or testing, it shall mean tests to assure the quality and to determine the acceptability of the materials and work.

The Engineer will deduct the costs for testing of materials and work found to be unacceptable, as determined by the tests performed by the Department, and the costs for testing of material sources identified by the Contractor which are not used for the work, from moneys due or to become due to the Contractor. The amount deducted will be determined by the Engineer.

5-1.06 REMOVAL OF ASBESTOS AND HAZARDOUS SUBSTANCES

When the presence of asbestos or hazardous substances are not shown on the plans or indicated in the specifications and the Contractor encounters materials which the Contractor reasonably believes to be asbestos or a hazardous substance as defined in Section 25914.1 of the Health and Safety Code, and the asbestos or hazardous substance has not been rendered harmless, the Contractor may continue work in unaffected areas reasonably believed to be safe. The Contractor shall immediately cease work in the affected area and report the condition to the Engineer in writing.

In conformance with Section 25914.1 of the Health and Safety Code, removal of asbestos or hazardous substances including exploratory work to identify and determine the extent of the asbestos or hazardous substance will be performed by separate contract.

If delay of work in the area delays the current controlling operation, the delay will be considered a right of way delay and the Contractor will be compensated for the delay in conformance with the provisions in Section 8-1.09, "Right of Way Delays," of the Standard Specifications.

5-1.07 YEAR 2000 COMPLIANCE

This contract is subject to Year 2000 Compliance for automated devices in the State of California.

Year 2000 compliance for automated devices in the State of California is achieved when embedded functions have or create no logical or mathematical inconsistencies when dealing with dates prior to and beyond 1999. The year 2000 is recognized and processed as a leap year. The product shall operate accurately in the manner in which the product was intended for date operation without requiring manual intervention.

The Contractor shall provide the Engineer a Certificate of Compliance from the manufacturer in conformance with the provisions in Section 6-1.07, "Certificates of Compliance," of the Standard Specifications for all automated devices furnished for the project.

5-1.075 BUY AMERICA REQUIREMENTS

Attention is directed to the "Buy America" requirements of the Surface Transportation Assistance Act of 1982 (Section 165) and the Intermodal Surface Transportation Efficiency Act of 1991 (ISTEA) Sections 1041(a) and 1048(a), and the regulations adopted pursuant thereto. In conformance with the law and regulations, all manufacturing processes for steel and iron materials furnished for incorporation into the work on this project shall occur in the United States; with the exception that pig iron and processed, pelletized and reduced iron ore manufactured outside of the United States may be used in the domestic manufacturing process for such steel and iron materials. The application of coatings, such as epoxy coating, galvanizing, painting, and other coatings that protect or enhance the value of steel or iron materials shall be considered a manufacturing process subject to the "Buy America" requirements.

A Certificate of Compliance conforming to the provisions in Section 6-1.07, "Certificates of Compliance," of the Standard Specifications shall be furnished for steel and iron materials. The certificates, in addition to certifying that the

materials comply with the specifications, shall specifically certify that all manufacturing processes for the materials occurred in the United States, except for the above exceptions.

The requirements imposed by the law and regulations do not prevent a minimal use of foreign steel and iron materials if the total combined cost of the materials used does not exceed one-tenth of one percent (0.1 percent) of the total contract cost or $2500, whichever is greater. The Contractor shall furnish the Engineer acceptable documentation of the quantity and value of the foreign steel and iron prior to incorporating the materials into the work.

5-1.08 SUBCONTRACTOR AND DBE RECORDS

The Contractor shall maintain records showing the name and business address of each first-tier subcontractor. The records shall also show the name and business address of every DBE subcontractor, DBE vendor of materials and DBE trucking company, regardless of tier. The records shall show the date of payment and the total dollar figure paid to all of these firms. DBE prime contractors shall also show the date of work performed by their own forces along with the corresponding dollar value of the work.

Upon completion of the contract, a summary of these records shall be prepared on Form CEM-2402 (F) and certified correct by the Contractor or the Contractor's authorized representative, and shall be furnished to the Engineer. The form shall be furnished to the Engineer within 90 days from the date of contract acceptance. $10,000 will be withheld from payment until the Form CEM-2402 (F) is submitted. The amount will be returned to the Contractor when a satisfactory Form CEM-2402 (F) is submitted.

Prior to the fifteenth of each month, the Contractor shall submit documentation to the Engineer showing the amount paid to DBE trucking companies listed in the Contractor's DBE information. This monthly documentation shall indicate the portion of the revenue paid to DBE trucking companies which is claimed toward DBE participation. The Contractor shall also obtain and submit documentation to the Engineer showing the amount paid by DBE trucking companies to all firms, including owner-operators, for the leasing of trucks. The DBE who leases trucks from a non-DBE is entitled to credit only for the fee or commission it receives as a result of the lease arrangement. The records must confirm that the amount of credit claimed toward DBE participation conforms with Section 2-1.02, "Disadvantaged Business Enterprise," of these special provisions.

The Contractor shall also obtain and submit documentation to the Engineer showing the truck number, owner's name, California Highway Patrol CA number, and if applicable, the DBE certification number of the owner of the truck for all trucks used during that month for which DBE participation will be claimed. This documentation shall be submitted on Form CEM-2404 (F).

5-1.083 DBE CERTIFICATION STATUS

If a DBE subcontractor is decertified during the life of the project, the decertified subcontractor shall notify the Contractor in writing with the date of decertification. If a subcontractor becomes a certified DBE during the life of the project, the subcontractor shall notify the Contractor in writing with the date of certification. The Contractor shall furnish the written documentation to the Engineer.

Upon completion of the contract, Form CEM-2403 (F) indicating the DBE's existing certification status shall be signed and certified correct by the Contractor. The certified form shall be furnished to the Engineer within 90 days from the date of contract acceptance.

5-1.086 PERFORMANCE OF DBE SUBCONTRACTORS AND SUPPLIERS

The DBEs listed by the Contractor in response to the provisions in Section 2-1.02B, "Submission of DBE Information," and Section 3, "Award and Execution of Contract," of these special provisions, which are determined by the Department to be certified DBEs, shall perform the work and supply the materials for which they are listed, unless the Contractor has received prior written authorization to perform the work with other forces or to obtain the materials from other sources.

Authorization to use other forces or sources of materials may be requested for the following reasons:

A. The listed DBE, after having had a reasonable opportunity to do so, fails or refuses to execute a written contract, when such written contract, based upon the general terms, conditions, plans and specifications for the project, or on the terms of such subcontractor's or supplier's written bid, is presented by the Contractor.
B. The listed DBE becomes bankrupt or insolvent.
C. The listed DBE fails or refuses to perform the subcontract or furnish the listed materials.
D. The Contractor stipulated that a bond was a condition of executing a subcontract and the listed DBE subcontractor fails or refuses to meet the bond requirements of the Contractor.
E. The work performed by the listed subcontractor is substantially unsatisfactory and is not in substantial conformance with the plans and specifications, or the subcontractor is substantially delaying or disrupting the progress of the work.

F. It would be in the best interest of the State.

The Contractor shall not be entitled to any payment for such work or material unless it is performed or supplied by the listed DBE or by other forces (including those of the Contractor) pursuant to prior written authorization of the Engineer.

5-1.09 SUBCONTRACTING

Attention is directed to the provisions in Section 8-1.01, "Subcontracting," of the Standard Specifications, and Section 2, "Proposal Requirements and Conditions," and Section 3, "Award and Execution of Contract," of these special provisions.

Pursuant to the provisions of Section 1777.1 of the Labor Code, the Labor Commissioner publishes and distributes a list of contractors ineligible to perform work as a subcontractor on a public works project. This list of debarred contractors is available from the Department of Industrial Relations web site at:

http://www.dir.ca.gov/DLSE/Debar.html.

The provisions in the third paragraph of Section 8-1.01, "Subcontracting," of the Standard Specifications, that the Contractor shall perform with the Contractor's own organization contract work amounting to not less than 50 percent of the original contract price, is not changed by the Federal Aid requirement specified under "Required Contract Provisions Federal-Aid Construction Contracts" in Section 14 of these special provisions that the Contractor perform not less than 30 percent of the original contract work with the Contractor's own organization.

Each subcontract and any lower tier subcontract that may in turn be made shall include the "Required Contract Provisions Federal-Aid Construction Contracts" in Section 14 of these special provisions. This requirement shall be enforced as follows:

A. Noncompliance shall be corrected. Payment for subcontracted work involved will be withheld from progress payments due, or to become due, until correction is made. Failure to comply may result in termination of the contract.

In conformance with the Federal DBE regulations Sections 26.53(f)(1) and 26.53(f)(2) Part 26, Title 49 CFR:

A. The Contractor shall not terminate for convenience a DBE subcontractor listed in response to Section 2-1.02B, "Submission of DBE Information," and then perform that work with its own forces, or those of an affiliate without the written consent of the Department, and
B. If a DBE subcontractor is terminated or fails to complete its work for any reason, the Contractor will be required to make good faith efforts to substitute another DBE subcontractor for the original DBE subcontractor, to the extent needed to meet the contract goal.

The requirement in Section 2-1.02, "Disadvantaged Business Enterprise (DBE)," of these special provisions that DBEs must be certified on the date bids are opened does not apply to DBE substitutions after award of the contract.

5-1.10 PROMPT PROGRESS PAYMENT TO SUBCONTRACTORS

Attention is directed to the provisions in Sections 10262 and 10262.5 of the Public Contract Code and Section 7108.5 of the Business and Professions Code concerning prompt payment to subcontractors.

5-1.102 PROMPT PAYMENT OF WITHHELD FUNDS TO SUBCONTRACTORS

The Contractor shall return all moneys withheld in retention from the subcontractor within 30 days after receiving payment for work satisfactorily completed, even if the other contract work is not completed and has not been accepted in conformance with Section 7-1.17, "Acceptance of Contract," of the Standard Specifications. This requirement shall not be construed to limit or impair any contractual, administrative, or judicial remedies otherwise available to the Contractor or subcontractor in the event of a dispute involving late payment or nonpayment by the Contractor or deficient subcontract performance or noncompliance by a subcontractor.

5-1.103 RECORDS

The Contractor shall maintain cost accounting records for the contract pertaining to, and in such a manner as to provide a clear distinction between, the following six categories of costs of work during the life of the contract:

A. Direct costs of contract item work.

B. Direct costs of changes in character in conformance with Section 4-1.03C, "Changes in Character of Work," of the Standard Specifications.
C. Direct costs of extra work in conformance with Section 4-1.03D, "Extra Work," of the Standard Specifications.
D. Direct costs of work not required by the contract and performed for others.
E. Direct costs of work performed under a notice of potential claim in conformance with the provisions in Section 9-1.04, "Notice of Potential Claim," of the Standard Specifications.
F. Indirect costs of overhead.

Cost accounting records shall include the information specified for daily extra work reports in Section 9-1.03C, "Records," of the Standard Specifications. The requirements for furnishing the Engineer completed daily extra work reports shall only apply to work paid for on a force account basis.

The cost accounting records for the contract shall be maintained separately from other contracts, during the life of the contract, and for a period of not less than 3 years after the date of acceptance of the contract. If the Contractor intends to file claims against the Department, the Contractor shall keep the cost accounting records specified above until complete resolution of all claims has been reached.

5-1.11 PARTNERING

The State will promote the formation of a "Partnering" relationship with the Contractor in order to effectively complete the contract to the benefit of both parties. The purpose of this relationship is to maintain a cooperative communication and to mutually resolve conflicts at the lowest responsible management level.

The Contractor may request the formation of a "Partnering" relationship by submitting a request in writing to the Engineer after approval of the contract. If the Contractor's request for "Partnering" is approved by the Engineer, scheduling of a "Partnering Workshop," selecting the "Partnering" facilitator and workshop site, and other administrative details shall be as agreed to by both parties. If agreed to by the parties, additional "Partnering Workshops" will be conducted as needed throughout the life of the contract.

A one-day "Training in Partnering Concepts" session will be conducted regardless of whether the Contractor requests the formation of a "Partnering" relationship. The "Training in Partnering Concepts" session will be conducted locally for the Contractor's and the Engineer's project representatives. The Contractor shall be represented by a minimum of 2 representatives, one being the Contractor's authorized representative pursuant to Section 5-1.06, "Superintendence," of the Standard Specifications. Scheduling of the "Training in Partnering Concepts" session and selection of the trainer and training site shall be determined cooperatively by the Contractor and the Engineer. If, upon the Contractor's request, "Partnering" is approved by the Engineer, the "Training in Partnering Concepts" session shall be conducted prior to the initial "Partnering Workshop."

The costs involved in providing the "Training in Partnering Concepts" trainer and training site will be borne entirely by the State. The costs will be determined in conformance with the provisions in Section 9-1.03B, "Work Performed by Special Forces or Other Special Services," of the Standard Specifications, and paying to the Contractor the sum of that cost, except no markups will be allowed.

The costs involved in providing the "Partnering Workshop" facilitator and workshop site will be borne equally by the State and the Contractor. The division of cost will be made by determining the cost in providing the "Partnering Workshop" facilitator and workshop site in conformance with the provisions in Section 9-1.03B, "Work Performed by Special Forces or Other Special Services," of the Standard Specifications, and paying to the Contractor one-half of that cost, except no markups will be allowed.

All other costs associated with "Training in Partnering Concepts" and "Partnering Workshops" will be borne separately by the party incurring the costs, such as wages and travel expenses, and no additional compensation will be allowed therefor.

The establishment of a "Partnering" relationship will not change or modify the terms and conditions of the contract and will not relieve either party of the legal requirements of the contract.

5–1.114 VALUE ANALYSIS

The Contractor may submit to the Engineer, in writing, a request for a "Value Analysis" workshop. The purpose for having a workshop is to identify value enhancing opportunities and to consider modifications to the plans and specifications that will reduce either the total cost, time of construction or traffic congestion, without impairing, in any manner, the essential functions or characteristics of the project including, but not limited to, service life, economy of operation, ease of maintenance, benefits to the travelling public, desired appearance, or design and safety standards.

To maximize the potential benefits of a workshop, the request should be submitted to the Engineer early in the project after approval of the contract. If the Contractor's request for a "Value Analysis" workshop is approved by the Engineer, scheduling of a workshop, selecting the facilitator and workshop site, and other administrative details shall be determined cooperatively by the Contractor and the Engineer.

The workshop shall be conducted in conformance with the methodology described in the Department's "Value Analysis Team Guide" available at the Department's web site at:

http://www.dot.ca.gov/hq/oppd/value/

The facilitator shall be a Certified Value Specialist (CVS) as recognized by the Society of American Value Engineers (SAVE) International, which may be contacted as follows:

SAVE International, 60 Revere Drive, Northbrook, IL 60062
Telephone 1-847-480-1730, FAX 1-847-480-9282

The Contractor may submit recommendations resulting from a "Value Analysis" workshop for approval by the Engineer as cost reduction incentive proposals in conformance with the provisions in Section 5-1.14, "Cost Reduction Incentive," of the Standard Specifications.

The costs involved in providing the "Value Analysis" facilitator and workshop site will be borne equally by the State and the Contractor. The division of cost will be made by determining the cost in providing the "Value Analysis" facilitator and workshop site in conformance with the provisions in Section 9-1.03B, "Work Performed by Special Forces or Other Special Services," of the Standard Specifications, and paying to the Contractor one-half of that cost, except no markups will be allowed.

All other costs associated with the "Value Analysis" workshop will be borne separately by the party incurring the costs, such as wages and travel expenses, and no additional compensation will be allowed therefor.

5-1.12 DISPUTE REVIEW BOARD

GENERAL

To assist in the resolution of disputes or potential claims arising out of the work of this project, a Dispute Review Board, hereinafter referred to as the "DRB," shall be established by the Engineer and Contractor cooperatively upon approval of the contract. The DRB is intended to assist the contract administrative claims resolution process as specified in the provisions in Section 9-1.04, "Notice of Potential Claim," and Section 9-1.07B, "Final Payment and Claims," of the Standard Specifications and these special provisions. The DRB shall not serve as a substitute for provisions in the specifications in regard to filing potential claims. The requirements and procedures established in this section shall be a prerequisite to filing a claim, filing for arbitration, or filing for litigation prior or subsequent to project completion.

The DRB shall be utilized when dispute or potential claim resolution at the project level is unsuccessful. The DRB shall function as specified herein until the day of acceptance of the contract, at which time the work of the DRB will cease except for completion of unfinished reports. No DRB dispute meetings shall take place later than 30 days prior to acceptance of contract. After acceptance of contract, disputes or potential claims which have followed the dispute resolution processes of the Standard Specifications and these special provisions, but have not been resolved, shall be stated or restated by the Contractor, in response to the Proposed Final Estimate within the time limits provided in Section 9-1.07B, "Final Payment and Claims," of the Standard Specifications. The State will review those claims in conformance with the provisions in Section 9-1.07B of the Standard Specifications. Following the adherence to and completion of the contractual administrative claims procedure, the Contractor may file for arbitration in conformance with the provisions in Section 9-1.10, "Arbitration," of the Standard Specifications and these special provisions.

Disputes, as used in this section, shall include differences of opinion, properly noticed as provided hereinafter, between the State and Contractor on matters related to the work and other subjects considered by the State or Contractor, or by both, to be of concern to the DRB on this project, except matters relating to Contractor, subcontractor or supplier potential claims not actionable against the Department as specified in these special provisions or quantification of disputes for overhead type expenses or costs. Disputes for overhead type expenses or costs shall conform to the requirements of Section 9-1.07B, "Final Payment and Claims," of the Standard Specifications. Whenever the term "dispute" or "disputes" is used herein, it shall be deemed to include potential claims as well as disputes.

The DRB shall serve as an advisory body to assist in the resolution of disputes between the State and the Contractor, hereinafter referred to as the "parties." The DRB shall consider disputes referred to it, and furnish written reports containing findings and recommendations pertaining to those disputes, to the parties to aid in resolution of the differences between them. DRB findings and recommendations are not binding on the parties.

SELECTION PROCESS, DISCLOSURE AND APPOINTMENTS

The DRB shall consist of one member selected by the State and approved by the Contractor, one member selected by the Contractor and approved by the State, and a third member selected by the first 2 members and approved by both the State and the Contractor. The third member shall act as the DRB Chairperson.

DRB members shall be especially knowledgeable in the type of construction and contract documents potentially anticipated by the contract. DRB members shall discharge their responsibilities impartially as an independent body, considering the facts and circumstances related to the matters under consideration, pertinent provisions of the contract and applicable laws and regulations.

The State and the Contractor shall nominate and approve DRB members in conformance with the terms and conditions of the Dispute Review Board Agreement and these special provisions, within 45 days of the approval of the contract. Each party shall provide written notification to the other of the name of their selected DRB nominee along with the prospective member's complete written disclosure statement.

Disclosure statements shall include a resume of the prospective member's experience and a declaration statement describing past, present, anticipated, and planned relationships, including indirect relationships through the prospective member's primary or full-time employer, to this project and with the parties involved in this construction contract, including but not limited to, relevant subcontractors or suppliers to the parties, parties' principals, or parties' counsel. DRB members shall also include a full disclosure of close professional or personal relationships with all key members of the contract. Objections to nominees must be based on a specific breech or violation of nominee responsibilities or on nominee qualifications under these provisions unless otherwise specified. The Contractor or the State may, on a one-time basis, object to the other's nominee without specifying a reason and this person will not be selected for the DRB. Another person shall then be nominated within 15 days.

The first duty of the State and Contractor selected members of the DRB shall be to select and recommend a prospective third DRB member to the parties for final selection and approval. The first 2 DRB members shall proceed with the selection of the third DRB member immediately upon receiving written notification from the State of their selection, and shall provide their recommendation simultaneously to the parties within 15 days of the notification.

The first 2 DRB members shall select a third DRB member subject to mutual approval of the parties or may mutually concur on a list of potentially acceptable third DRB members and submit the list to the parties for final selection and approval of the third member. The goal in the selection of the third member is to complement the professional experience of the first 2 members and to provide leadership for the DRB's activities.

The third prospective DRB member shall supply a full disclosure statement to the first 2 DRB members and to the parties prior to appointment.

An impasse shall be considered to have been reached if the parties are unable to approve a third member within 15 days of receipt of the recommendation of the first 2 DRB members, or if the first 2 DRB members are unable to agree upon a recommendation within their 15 day time limit. In the event of an impasse in selection of third DRB member the State and the Contractor shall each propose 3 candidates for the third DRB member position. The parties shall select the candidates proposed under this paragraph from the current list of arbitrators certified by the Public Works Contract Arbitration Committee created by Article 7.2 (commencing with Section 10245) of the State Contract Act. The first 2 DRB members shall then select one of the 6 proposed candidates in a blind draw.

No DRB member shall have prior direct involvement in this contract. No member shall have a financial interest in this contract or the parties thereto, within a period of 6 months prior to award of this contract or during the contract, except as follows:

A. Compensation for services on this DRB.
B. Ownership interest in a party or parties, documented by the prospective DRB member, that has been reviewed and determined in writing by the State to be sufficiently insignificant to render the prospective member acceptable to the State.
C. Service as a member of other Dispute Review Boards on other contracts.
D. Retirement payments or pensions received from a party that are not tied to, dependent on or affected by the net worth of the party.
E. The above provisions apply to parties having a financial interest in this contract, including but not limited to contractors, subcontractors, suppliers, consultants, and legal and business services.

The Contractor or the State may reject any of the three DRB members who fail to fully comply at all times with all required employment and financial disclosure conditions of DRB membership as described in the Dispute Review Board Agreement and as specified herein. A copy of the Dispute Review Board Agreement is included in this section.

The Contractor, the State, and the 3 members of the DRB shall complete and adhere to the Dispute Review Board Agreement in administration of this DRB within 15 days of the parties' concurrence in the selection of the third member. No DRB meeting shall take place until the Dispute Review Board Agreement has been signed by all parties. The State authorizes the Engineer to execute and administer the terms of the Agreement. The person(s) designated by the Contractor as authorized to execute contract change orders shall be authorized to execute and administer the terms of this agreement, or to delegate the authority in writing. The operation of the DRB shall be in conformance with the terms of the Dispute Review Board Agreement.

COMPENSATION

The State and the Contractor shall bear the costs and expenses of the DRB equally. Each DRB member shall be compensated at an agreed rate of $1,200 per day if time spent per meeting, including on-site time plus one hour of travel time, is greater than 4 hours. Each DRB member shall be compensated at an agreed rate of $700 per day if time spent per meeting, including on-site time plus one hour of travel time, is less than or equal to 4 hours. The agreed rates shall be considered full compensation for on-site time, travel expenses, transportation, lodging, time for travel and incidentals for each day, or portion thereof, that the DRB member is at an authorized DRB meeting. No additional compensation will be made for time spent by DRB members in review and research activities outside the official DRB meetings unless that time, (such as time spent evaluating and preparing recommendations on specific issues presented to the DRB), has been specifically agreed to in advance by the State and Contractor. Time away from the project, which has been specifically agreed to in advance by the parties, will be compensated at an agreed rate of $125 per hour. The agreed amount of $125 per hour shall include all incidentals including expenses for telephone, fax, and computer services. Members serving on more than one DRB involving the Department, regardless of the number of meetings per day, shall not be paid more than the all inclusive rate per day or rate per hour for an individual project. The State will provide, at no cost to the Contractor, administrative services such as conference facilities and secretarial services to the DRB. These special provisions and the Dispute Review Board Agreement state the provisions for compensation and expenses of the DRB. DRB members shall be compensated at the same daily and hourly rate. The Contractor shall make direct payments to each DRB member for their participation in authorized meetings and approved hourly rate charges from invoices submitted by each DRB member. The State will reimburse the Contractor for the State's share of the costs. There will be no markups applied to expenses connected with the DRB, either by the DRB members or by the Contractor when requesting payment of the State's share of DRB expenses. Regardless of the DRB recommendation, neither party shall be entitled to reimbursement of DRB costs from the other party.

REPLACEMENT OF DRB MEMBERS

Service of a DRB member may be terminated at any time with not less than 15 days notice as follows:

A. The State may terminate service of the State appointed member.
B. The Contractor may terminate service of the Contractor appointed member.
C. Upon the written recommendation of the State and Contractor appointed members for the removal of the third member.
D. Upon resignation of a member.
E. The State or Contractor may terminate the service of any member who fails to fully comply with all required employment and financial disclosure conditions of DRB membership

When a member of the DRB is replaced, the replacement member shall be appointed in the same manner as the replaced member was appointed. The appointment of a replacement DRB member will begin promptly upon determination of the need for replacement and shall be completed within 15 days. Changes in either of the DRB members chosen by the two parties will not require re-selection of the third member, unless both parties agree to such re-selection in writing. The Dispute Review Board Agreement shall be amended to reflect the change of a DRB member.

OPERATION

The following procedure shall be used for dispute resolution:

A. If the Contractor objects to any decision, act or order of the Engineer, the Contractor shall give written notice of potential claim in conformance with the provisions in Section 9-1.04, "Notice of Potential Claim," of the Standard Specifications and these special provisions, including the provision of applicable cost documentation; or file written protests or notices in conformance with the provisions in the Standard Specifications and these special provisions.
B. The Engineer will respond, in writing, to the Contractor's written supplemental notice of potential claim within 20 days of receipt of the notice.
C. Within 15 days after receipt of the Engineer's written response, the Contractor shall, if the Contractor still objects, file a written reply with the Engineer, stating clearly and in detail the basis of the objection.
D. Following an objection to the Engineer's written response, the Contractor shall refer the dispute to the DRB if the Contractor wishes to further pursue the objection to the Engineer's decision. The Contractor shall make the referral in writing to the DRB, simultaneously copied to the State, within 21 days after receipt of the written response from the Engineer. The written dispute referral shall describe the disputed matter in individual discrete segments so that it will be clear to both parties and the DRB what discrete elements of the dispute have been resolved, and which

remain unresolved, and shall include an estimate of the cost of the affected work and impacts, if any, on project completion.

E. By failing to submit the written notice of referral to the DRB, within 21 days after receipt of the Engineer's written response to the supplemental notice of potential claim, the Contractor waives future claims and arbitration on the matter in contention.

F. The Contractor and the State shall each be afforded an opportunity to be present and to be heard by the DRB, and to offer evidence. Either party furnishing written evidence or documentation to the DRB must furnish copies of such information to the other party a minimum of 15 days prior to the date the DRB is scheduled to convene the meeting for the dispute. Either party shall produce such additional evidence as the DRB may deem necessary to reach an understanding and a determination of the dispute. The party furnishing additional evidence shall furnish copies of such additional evidence to the other party at the same time the evidence is provided to the DRB. The DRB shall not consider evidence not furnished in conformance with the terms specified herein.

G. Upon receipt by the DRB of a written referral of a dispute, the DRB shall convene to review and consider the dispute. The dispute meeting shall be held no earlier than 30 days and no later than 60 days after receipt of the written referral unless otherwise agreed to by all parties. The DRB shall determine the time and location of the DRB dispute meeting, with due consideration for the needs and preferences of the parties while recognizing the paramount importance of a timely hearing of the dispute.

H. There shall be no participation of either party's attorneys at DRB dispute meetings.

I. There shall be no participation of persons who are not directly involved in the contract or who do not have direct knowledge of the dispute, including but not limited to consultants, except for expert testimony allowed at the discretion of the DRB and with approval prior to the dispute meeting by both parties.

J. The DRB shall furnish a report, containing findings and recommendations as described in the Dispute Review Board Agreement, in writing to both the State and the Contractor. The DRB may request clarifying information of either party within 10 days after the DRB dispute meeting. Requested information shall be submitted to the DRB within 10 days of the DRB request. The DRB shall complete its report, including minority opinion, if any, and submit it to the parties within 30 days of the DRB dispute meeting, except that time extensions may be granted at the request of the DRB with the written concurrence of both parties. The report shall include the facts and circumstances related to the matters under consideration, pertinent provisions of the contract, applicable laws and regulations, and actual costs and time incurred as shown on the Contractor's cost accounting records. The DRB shall make recommendations on the merit of the dispute and, if appropriate, recommend guidelines for determining compensation.

K. Within 30 days after receiving the DRB's report, both the State and the Contractor shall respond to the DRB in writing signifying that the dispute is either resolved or remains unresolved. Failure to provide the written response within the time specified, or a written rejection of the DRB's recommendation or response to a request for reconsideration presented in the report by either party, shall conclusively indicate that the party(s) failing to respond accepts the DRB recommendation. Immediately after responses have been received from both parties, the DRB shall provide copies of both responses to the parties simultaneously. Either party may request clarification of elements of the DRB's report from the DRB prior to responding to the report. The DRB shall consider any clarification request only if submitted within 10 days of receipt of the DRB's report, and if submitted simultaneously in writing to both the DRB and the other party. Each party may submit only one request for clarification for any individual DRB report. The DRB shall respond, in writing, to requests for clarification within 10 days of receipt of such requests.

L. The DRB's recommendations, stated in the DRB's reports, are not binding on either party. Either party may seek a reconsideration of a recommendation of the DRB. The DRB shall only grant a reconsideration based upon submission of new evidence and if the request is submitted within the 30-day time limit specified for response to the DRB's written report. Each party may submit only one request for reconsideration regarding an individual DRB recommendation.

M. If the State and the Contractor are able to resolve their dispute with the aid of the DRB's report, the State and Contractor shall promptly accept and implement the recommendations of the DRB. If the parties cannot agree on compensation within 60 days of the acceptance by both parties of the DRB's recommendation, either party may request the DRB to make a recommendation regarding compensation.

N. The State or the Contractor shall not call DRB members who served on the DRB for this contract as witnesses in arbitration proceedings which may arise from this contract, and all documents created by the DRB shall be inadmissible as evidence in subsequent arbitration proceedings, except the DRB's final written reports on each issue brought before it.

O. The State and Contractor shall jointly indemnify and hold harmless the DRB members from and against all claims, damages, losses, and expenses, including but not limited to attorney's fees, arising out of and resulting from the findings and recommendations of the DRB.

P. The DRB members shall have no claim against the State or the Contractor, or both, from claimed harm arising out of the parties' evaluations of the DRB's report.

DISPUTES INVOLVING SUBCONTRACTOR POTENTIAL CLAIMS

For purposes of this section, a "subcontractor potential claim" shall include any potential claim by a subcontractor (including also any pass through potential claims by a lower tier subcontractor or supplier) against the Contractor that is actionable by the Contractor against the Department which arises from the work, services, or materials provided or to be provided in connection with the contract. If the Contractor determines to pursue a dispute against the Department that includes a subcontractor potential claim, the dispute shall be processed and resolved in conformance with these special provisions and in conformance with the following:

A. The Contractor shall identify clearly in submissions pursuant to this section, that portion of the dispute that involves a subcontractor potential claim or potential claims.
B. The Contractor shall include, as part of its submission pursuant to Step D above, a certification (False Claims Act Certification) by the subcontractor's or supplier's officer, partner, or authorized representative with authority to bind the subcontractor and with direct knowledge of the facts underlying the subcontractor potential claim. The Contractor shall submit a certification that the subcontractor potential claim is acknowledged and forwarded by the Contractor. The form for these certifications is available from the Engineer.
C. At DRB dispute meetings involving one or more subcontractor potential claims, the Contractor shall require that each subcontractor involved in the dispute have present an authorized representative with actual knowledge of the facts underlying the subcontractor potential claim to assist in presenting the subcontractor potential claim and to answer questions raised by the DRB members or the Department's representatives.
D. Failure by the Contractor to declare a subcontractor potential claim on behalf of its subcontractor (including lower tier subcontractors' and suppliers' pass through potential claims) at the time of submission of the Contractor's potential claims, as provided hereunder, shall constitute a release of the State by the Contractor of such subcontractor potential claim.
E. The Contractor shall include in all subcontracts under this contract that subcontractors and suppliers of any tier (a) agree to submit subcontractor potential claims to the Contractor in a proper form and in sufficient time to allow processing by the Contractor in conformance with the Dispute Review Board resolution specifications; (b) agree to be bound by the terms of the Dispute Review Board provisions to the extent applicable to subcontractor potential claims; (c) agree that, to the extent a subcontractor potential claim is involved, completion of all steps required under these Dispute Review Board special provisions shall be a condition precedent to pursuit by the subcontractor of other remedies permitted by law, including without limitation of a lawsuit against the Contractor; and (d) agree that the existence of a dispute resolution process for disputes involving subcontractor potential claims shall not be deemed to create any claim, right, or cause of action by any subcontractor or supplier against the Department.

Notwithstanding the foregoing, this Dispute Review Board special provision shall not apply to, and the DRB shall not have the authority to consider, subcontractor potential claims between the subcontractor(s) or supplier(s) and the Contractor that are not actionable by the Contractor against the Department.

RETENTION

Failure of the Contractor to nominate and approve DRB members in conformance with the terms and conditions of the Dispute Review Board Agreement and these special provisions shall result in the retention of 25 percent of the estimated value of all work performed during each estimate period in which the Contractor fails to comply with the requirements of this section as determined by the Engineer. DRB retentions will be released for payment on the next monthly estimate for partial payment following the date that the Contractor has nominated and approved DRB members and no interest will be due the Contractor.

DISPUTE REVIEW BOARD AGREEMENT

A copy of the "Dispute Review Board Agreement" to be executed by the Contractor, State and the 3 DRB members after approval of the contract follows:

Form 6202 Rev (09/01/02)

DISPUTE REVIEW BOARD AGREEMENT

_____
(Contract Identification)

Contract No. _____

THIS DISPUTE REVIEW BOARD AGREEMENT, hereinafter called "AGREEMENT", made and entered into this _____ day of _____, _____, between the State of California, acting through the California Department of Transportation and the Director of Transportation, hereinafter called the "STATE," _____ _____ hereinafter called the "CONTRACTOR," and the Dispute Review Board, hereinafter called the "DRB" consisting of the following members:

_____ ,
(Contractor Appointee)

_____ ,
(State Appointee)

and _____
(Third Person)

WITNESSETH, that

WHEREAS, the STATE and the CONTRACTOR, hereinafter called the "parties," are now engaged in the construction on the State Highway project referenced above; and

WHEREAS, the special provisions for the above referenced contract provides for the establishment and operation of the DRB to assist in resolving disputes; and

WHEREAS, the DRB is composed of three members, one selected by the STATE, one selected by the CONTRACTOR, and the third member selected by the other two members and approved by the parties;

NOW THEREFORE, in consideration of the terms, conditions, covenants, and performance contained herein, or attached and incorporated and made a part hereof, the STATE, the CONTRACTOR, and the DRB members hereto agree as follows:

SECTION I DESCRIPTION OF WORK

To assist in the resolution of disputes between the parties, the contract provides for the establishment and the operation of the DRB. The intent of the DRB is to fairly and impartially consider disputes placed before it and provide written recommendations for resolution of these disputes to both parties. The members of this DRB shall perform the services necessary to participate in the DRB's actions as designated in Section II, Scope of Work.

SECTION II SCOPE OF WORK

The scope of work of the DRB includes, but is not limited to, the following:

A. OBJECTIVE

The principal objective of the DRB is to assist in the timely resolution of disputes between the parties arising from performance of this contract. It is not intended for either party to default on their normal responsibility to amicably and fairly settle their differences by indiscriminately assigning them to the DRB. It is intended that the mere existence of the DRB will encourage the parties to resolve disputes without resorting to this review procedure. But when a dispute that is serious enough to warrant the DRB's review does develop, the process for prompt and efficient action will be in place.

B. PROCEDURES

The DRB shall render written reports on disputes between the parties arising from the construction contract. Prior to consideration of a dispute, the DRB shall establish rules and regulations that will govern the conduct of its business and reporting procedures in conformance with the requirements of the contract and the terms of this AGREEMENT. DRB recommendations, resulting from its consideration of a dispute, shall be furnished in writing to both parties. The recommendations shall be based on facts and circumstances involved in the dispute, pertinent contract provisions, applicable laws and regulations. The recommendations shall find one responsible party in a dispute; shared or "jury" determinations shall not be rendered. The DRB shall make recommendations on the merit of the dispute, and if appropriate, recommend guidelines for determining compensation. If the parties cannot agree on compensation within 60 days of the acceptance by both parties of the DRB's recommendation, either party may request the DRB to make a recommendation regarding compensation.

The DRB shall refrain from officially giving advice or consulting services to anyone involved in the contract. The individual members shall act in a completely independent manner and while serving as members of the DRB shall have no consulting business connections with either party or its principals or attorneys or other affiliates (subcontractors, suppliers, etc.) who have a beneficial interest in the contract.

During scheduled meetings of the DRB as well as during dispute meetings, DRB members shall refrain from expressing opinions on the merits of statements on matters under dispute or potential dispute. Opinions of DRB members expressed in private sessions shall be kept strictly confidential. Individual DRB members shall not meet with, or discuss contract issues with individual parties, except as directed by the DRB Chairperson. Such discussions or meetings shall be disclosed to both parties. Other discussions regarding the project between the DRB members and the parties shall be in the presence of all three members and both parties. Individual DRB members shall not undertake independent investigations of any kind pertaining to disputes or potential disputes, except with the knowledge of both parties and as expressly directed by the DRB Chairperson.

C. CONSTRUCTION SITE VISITS, PROGRESS MEETINGS AND FIELD INSPECTIONS

The DRB members shall visit the project site and meet with representatives of the parties to keep abreast of construction activities and to develop familiarity with the work in progress. Scheduled progress meetings shall be held at or near the project site. The DRB shall meet at least once at the start of the project, and at least once every 4 months thereafter. The frequency, exact time, and duration of additional site visits and progress meetings shall be as recommended by the DRB and approved by the parties consistent with the construction activities or matters under consideration and dispute. Each meeting shall consist of a round table discussion and a field inspection of the work being performed on the contract, if necessary. Each meeting shall be attended by representatives of both parties. The agenda shall generally be as follows:

1. Meeting opened by the DRB Chairperson.
2. Remarks by the STATE's representative.
3. A description by the CONTRACTOR's representative of work accomplished since the last meeting; the current schedule status of the work; and a forecast for the coming period.
4. An outline by the CONTRACTOR's representative of potential problems and a description of proposed solutions.
5. An outline by the STATE's representative of the status of the work as the STATE views it.
6. A brief description by the CONTRACTOR's or STATE's representative of potential claims or disputes which have surfaced since the last meeting.
7. A summary by the STATE's representative, the CONTRACTOR's representative, or the DRB of the status of past disputes and potential claims.

The STATE's representative will prepare minutes of all progress meetings and circulate them for revision and approval by all concerned within 10 days of the meeting.

The field inspection shall cover all active segments of the work, the DRB being accompanied by both parties' representatives. The field inspection may be waived upon mutual agreement of the parties.

D. DRB CONSIDERATION AND HANDLING OF DISPUTES

Upon receipt by the DRB of a written referral of a dispute, the DRB shall convene to review and consider the dispute. The dispute meeting shall be held no earlier than 30 days and no later than 60 days after receipt of the written referral, unless otherwise agreed to by all parties. The DRB shall determine the time and location of DRB dispute meetings, with due consideration for the needs and preferences of the parties while recognizing the paramount importance of speedy resolution of issues. No dispute meetings shall take place later than 30 days prior to acceptance of contract.

Normally, dispute meetings shall be conducted at or near the project site. However, any location that would be more convenient and still provide required facilities and access to necessary documentation shall be satisfactory.

Both parties shall be given the opportunity to present their evidence at these dispute meetings. It is expressly understood that the DRB members are to act impartially and independently in the consideration of the contract provisions, applicable laws and regulations, and the facts and conditions surrounding any dispute presented by either party, and that the recommendations concerning any such dispute are advisory and nonbinding on the parties.

The DRB may request that written documentation and arguments from both parties be sent to each DRB member, through the DRB Chairperson, for review before the dispute meeting begins. A party furnishing written documentation to the DRB shall furnish copies of such information to the other party at the same time that such information is supplied to the DRB.

DRB dispute meetings shall be informal. There shall be no testimony under oath or cross-examination. There shall be no reporting of the procedures by a shorthand reporter or by electronic means. Documents and verbal statements shall be received by the DRB in conformance with acceptance standards established by the DRB. These standards need not comply with prescribed legal laws of evidence.

The third DRB member shall act as Chairperson for dispute meetings and all other DRB activities. The parties shall have a representative at all dispute meetings. Failure to attend a duly noticed dispute meeting by either of the parties shall be conclusively considered by the DRB as indication that the non-attending party considers written submittals as their entire and complete argument. The claimant shall discuss the dispute, followed by the other party. Each party shall then be allowed one or more rebuttals until all aspects of the dispute are thoroughly covered. DRB members shall ask questions, seek clarification, and request further data from either of the parties as may be necessary to assist in making a fully informed recommendation. The DRB may request from either party documents or information that would assist the DRB in making its findings and recommendations including, but not limited to, documents used by the CONTRACTOR in preparing the bid for the project. A refusal by a party to provide information requested by the DRB may be considered by the DRB as an indication that the requested material would tend to disprove that party's position. In large or complex cases, additional dispute meetings may be necessary in order to consider all the evidence presented by both parties. All involved parties shall maintain the confidentiality of all documents and information, as provided in this AGREEMENT.

During dispute meetings, no DRB member shall express an opinion concerning the merit of any facet of the case. DRB deliberations shall be conducted in private, with interim individual views kept strictly confidential.

After dispute meetings are concluded, the DRB shall meet in private and reach a conclusion supported by 2 or more members. Private sessions of the DRB may be held at a location other than the job site or by electronic conferencing as deemed appropriate, in order to expedite the process.

The DRB's findings and recommendations, along with discussion of reasons therefor, shall then be submitted as a written report to both parties. Recommendations shall be based on the pertinent contract provisions, applicable laws and regulations, and facts and circumstances related to the dispute. The report shall be thorough in discussing the facts considered, the contract language, law or regulation viewed by the DRB as pertinent to the issues, and the DRB's interpretation and philosophy in arriving at its conclusions and recommendations. The DRB's report shall stand on its own, without attachments or appendices. The DRB Chairperson shall furnish a copy of the written recommendation report to the DRB Coordinator, Division of Construction, MS 44, P.O. Box 942874, Sacramento, CA 94274.

With prior written approval of both parties, the DRB may obtain technical services necessary to adequately review the disputes presented, including audit, geotechnical, schedule analysis and other services. The parties' technical staff may supply those services as appropriate. The cost of technical services, as agreed to by the parties, shall be borne equally by the 2 parties as specified in an approved contract change order. The CONTRACTOR will not be entitled to markups for the payments made for these services.

The DRB shall resist submittal of incremental portions of information by either party, in the interest of making a fully informed decision and recommendation.

The DRB shall make every effort to reach a unanimous decision. If this proves impossible, the dissenting member shall prepare a minority opinion, which shall be included in the DRB's report.

Although both parties should place weight upon the DRB's recommendations, they are not binding. Either party may appeal a recommendation to the DRB for reconsideration. However, reconsideration shall only be allowed when there is new evidence to present, and the DRB shall accept only one appeal from each party pertaining to an individual DRB recommendation. The DRB shall hear appeals in conformance with the terms described in the Section entitled "Dispute Review Board" in the special provisions.

E. DRB MEMBER REPLACEMENT

Should the need arise to appoint a replacement DRB member, the replacement DRB member shall be appointed in the same manner as the original DRB members were appointed. The selection of a replacement DRB member shall begin promptly upon notification of the necessity for a replacement and shall be completed within 15 days. This AGREEMENT shall be amended to indicate change in DRB membership.

SECTION III CONTRACTOR RESPONSIBILITIES

The CONTRACTOR shall furnish to each DRB member one copy of pertinent documents that are or may become necessary for the DRB to perform their function. Pertinent documents are written notices of potential claim, responses to those notices, drawings or sketches, calculations, procedures, schedules, estimates, or other documents which are used in the performance of the work or in justifying or substantiating the CONTRACTOR's position. The CONTRACTOR shall also furnish a copy of such pertinent documents to the STATE, in conformance with the terms outlined in the special provisions.

SECTION IV STATE RESPONSIBILITIES

The STATE will furnish the following services and items:

A. CONTRACT RELATED DOCUMENTS

The STATE will furnish to each DRB member one copy of Notice to Contractors and Special Provisions, Proposal and Contract, Plans, Standard Specifications, and Standard Plans, change orders, written instructions issued by the STATE to the CONTRACTOR, or other documents pertinent to any dispute that has been referred to the DRB and necessary for the DRB to perform its function.

B. COORDINATION AND SERVICES

The STATE, through the Engineer, will, in cooperation with the CONTRACTOR, coordinate the operations of the DRB. The Engineer will arrange or provide conference facilities at or near the project site and provide secretarial and copying services to the DRB without charge to the CONTRACTOR.

SECTION V TIME FOR BEGINNING AND COMPLETION

Once established, the DRB shall be in operation until the day of acceptance of the contract. The DRB members shall not begin work under the terms of this AGREEMENT until authorized in writing by the STATE.

SECTION VI PAYMENT

A. ALL INCLUSIVE RATE PAYMENT

The STATE and the CONTRACTOR shall bear the costs and expenses of the DRB equally. Each DRB member shall be compensated at an agreed rate of $1,200 per day if time spent per meeting, including on-site time plus one hour of travel time, is greater than 4 hours. Each DRB member shall be compensated at an agreed rate of $700 per day if time spent per meeting, including on-site time plus one hour of travel time, is less than or equal to 4 hours. The agreed rates shall be considered full compensation for on-site time, travel expenses, transportation, lodging, time for travel and incidentals for each day, or portion thereof, that the DRB member is at an authorized DRB meeting. No additional compensation will be made for time spent by DRB members in review and research activities outside the official DRB meetings unless that time has been specifically agreed to in advance by the STATE and CONTRACTOR. Time away from the project that has been specifically agreed to in advance by the parties will be compensated at an agreed rate of $125 per hour. The agreed amount of $125 per hour shall include all incidentals including expenses for telephone, fax, and computer services. Members serving on more than one DRB involving the State, regardless of the number of meetings per day, shall not be paid more than the all inclusive rate per day or rate per hour for an individual project. The STATE will provide, at no cost to the CONTRACTOR, administrative services such as conference facilities and secretarial services to the DRB.

B. PAYMENTS

DRB members shall be compensated at the same rate. The CONTRACTOR shall make direct payments to each DRB member for their participation in authorized meetings and approved hourly rate charges from invoices submitted by each DRB member. The STATE will reimburse the CONTRACTOR for its share of the costs of the DRB.

The DRB members may submit invoices to the CONTRACTOR for partial payment for work performed and services rendered for their participation in authorized meetings not more often than once per month during the progress of the work. The invoices shall be in a format approved by the parties and accompanied by a general description of activities performed during that billing period. Payment for hourly fees, at the agreed rate, shall not be paid to a DRB member until the amount and extent of those fees are approved by the STATE and CONTRACTOR.

Invoices shall be accompanied by original supporting documents, which the CONTRACTOR shall include with the extra work billing when submitting for reimbursement of the STATE's share of cost from the STATE. The CONTRACTOR will be reimbursed for one-half of approved costs of the DRB. No markups will be added to the CONTRACTOR's payment.

C. INSPECTION OF COSTS RECORDS

The DRB members and the CONTRACTOR shall keep available for inspection by representatives of the STATE and the United States, for a period of 3 years after final payment, the cost records and accounts pertaining to this AGREEMENT. If any litigation, claim, or audit arising out of, in connection with, or related to this contract is initiated before the expiration of the 3-year period, the cost records and accounts shall be retained until such litigation, claim, or audit involving the records is completed.

SECTION VII ASSIGNMENT OF TASKS OF WORK

The DRB members shall not assign the work of this AGREEMENT.

SECTION VIII TERMINATION OF DRB MEMBERS

DRB members may resign from the DRB by providing not less than 15 days written notice of the resignation to the STATE and CONTRACTOR. DRB members may be terminated by their original appointing power or by either party, for failing to fully comply at all times with all required employment and financial disclosure conditions of DRB membership in conformance with the terms of the contract.

SECTION IX LEGAL RELATIONS

The parties hereto mutually understand and agree that the DRB member in the performance of duties on the DRB, is acting in the capacity of an independent agent and not as an employee of either party.

No party to this AGREEMENT shall bear a greater responsibility for damages or personal injury than is normally provided by Federal or State of California Law.

Notwithstanding the provisions of this contract that require the CONTRACTOR to indemnify and hold harmless the STATE, the parties shall jointly indemnify and hold harmless the DRB members from and against all claims, damages, losses, and expenses, including but not limited to attorney's fees, arising out of and resulting from the findings and recommendations of the DRB.

SECTION X CONFIDENTIALITY

The parties hereto mutually understand and agree that all documents and records provided by the parties in reference to issues brought before the DRB, which documents and records are marked "Confidential - for use by the DRB only," shall be kept in confidence and used only for the purpose of resolution of subject disputes, and for assisting in development of DRB findings and recommendations; that such documents and records will not be utilized or revealed to others, except to officials of the parties who are authorized to act on the subject disputes, for any purposes, during the life of the DRB. Upon termination of this AGREEMENT, said confidential documents and records, and all copies thereof, shall be returned to the parties who furnished them to the DRB. However, the parties understand that such documents shall be subsequently discoverable and admissible in court or arbitration proceedings unless a protective order has been obtained by the party seeking further confidentiality.

SECTION XI DISPUTES

Disputes between the parties hereto, including disputes between the DRB members and either party or both parties, arising out of the work or other terms of this AGREEMENT, which cannot be resolved by negotiation and mutual concurrence between the parties, or through the administrative process provided in the contract, shall be resolved by arbitration as provided in Section 9-1.10, "Arbitration," of the Standard Specifications.

SECTION XII VENUE, APPLICABLE LAW, AND PERSONAL JURISDICTION

In the event that any party, including an individual member of the DRB, deems it necessary to institute arbitration proceedings to enforce any right or obligation under this AGREEMENT, the parties hereto agree that such action shall be initiated in the Office of Administrative Hearings of the State of California. The parties hereto agree that all questions shall be resolved by arbitration by application of California law and that the parties to such arbitration shall have the right of appeal from such decisions to the Superior Court in conformance with the laws of the State of California. Venue for the arbitration shall be Sacramento or any other location as agreed to by the parties.

SECTION XIII FEDERAL REVIEW AND REQUIREMENTS

On Federal-Aid contracts, the Federal Highway Administration shall have the right to review the work of the DRB in progress, except for private meetings or deliberations of the DRB.

Other Federal requirements in this agreement shall only apply to Federal-Aid contracts.

SECTION XIV CERTIFICATION OF THE CONTRACTOR, THE DRB MEMBERS, AND THE STATE

IN WITNESS WHEREOF, the parties hereto have executed this AGREEMENT as of the day and year first above written.

DRB MEMBER

By: _____

Title: _____

DRB MEMBER

By: _____

Title : _____

DRB MEMBER

By : _____

Title : _____

CONTRACTOR

By: _____

Title: _____

CALIFORNIA STATE DEPARTMENT OF TRANSPORTATION

By: _____

Title: _____

5-1.13 FORCE ACCOUNT PAYMENT

The second, third and fourth paragraphs of Section 9-1.03A, "Work Performed by Contractor," in the Standard Specifications, shall not apply.

Attention is directed to "Time-Related Overhead" of these special provisions.

To the total of the direct costs for work performed on a force account basis, computed as provided in Sections 9-1.03A(1), "Labor," 9-1.03A(2), "Materials," and 9-1.03A(3), "Equipment Rental," of the Standard Specifications, there will be added the following markups:

Cost	Percent Markup
Labor	28
Materials	10
Equipment Rental	10

The above markups shall be applied to work performed on a force account basis, regardless of whether the work revises the current contract completion date.

The above markups, together with payments made for time-related overhead pursuant to "Time-Related Overhead" of these special provisions, shall constitute full compensation for all overhead costs for work performed on a force account basis. These overhead costs shall be deemed to include all items of expense not specifically designated as cost or equipment rental in conformance with the provisions in Sections 9-1.03A(1), "Labor," 9-1.03A(2), "Materials," and 9-1.03A(3), "Equipment Rental," of the Standard Specifications. The total payment made as provided above and in the first paragraph of Section 9-1.03A, "Work Performed by Contractor," of the Standard Specifications shall be deemed to be the actual cost of the work performed on a force account basis, and shall constitute full compensation therefor.

Full compensation for overhead costs for work performed on a force account basis, and for which no adjustment is made to the lump sum price bid for time-related overhead conforming to the provisions in "Time-Related Overhead" of these special provisions, shall be considered as included in the markups specified above, and no additional compensation will be allowed therefor.

When extra work to be paid for on a force account basis is performed by a subcontractor, approved in conformance with the provisions in Section 8-1.01, "Subcontracting," of the Standard Specifications, an additional markup of 7 percent will be added to the total cost of that extra work including all markups specified in this section "Force Account Payment". The additional 7 percent markup shall reimburse the Contractor for additional administrative costs, and no other additional payment will be made by reason of performance of the extra work by a subcontractor.

5-1.14 AREAS FOR CONTRACTOR'S USE

Attention is directed to the provisions in Section 7-1.19, "Rights in Land and Improvements," of the Standard Specifications and these special provisions.

The highway right of way shall be used only for purposes that are necessary to perform the required work. The Contractor shall not occupy the right of way, or allow others to occupy the right of way, for purposes which are not necessary to perform the required work.

No State-owned parcels adjacent to the right of way are available for the exclusive use of the Contractor within the contract limits. The Contractor shall secure, at the Contractor's own expense, areas required for plant sites, storage of equipment or materials, or for other purposes.

No area is available within the contract limits for the exclusive use of the Contractor. However, temporary storage of equipment and materials on State property may be arranged with the Engineer, subject to the prior demands of State maintenance forces and to other contract requirements. Use of the Contractor's work areas and other State-owned property shall be at the Contractor's own risk, and the State shall not be held liable for damage to or loss of materials or equipment located within such areas.

The Contractor shall remove equipment, materials, and rubbish from the work areas and other State-owned property which the Contractor occupies. The Contractor shall leave the areas in a presentable condition in conformance with the provisions in Section 4-1.02, "Final Cleaning Up," of the Standard Specifications.

5-1.15 PAYMENTS

Attention is directed to Sections 9-1.06, "Partial Payments," and 9-1.07, "Payment After Acceptance," of the Standard Specifications and these special provisions.

For the purpose of making partial payments pursuant to Section 9-1.06, "Partial Payments," of the Standard Specifications, the amount set forth for the contract items of work hereinafter listed shall be deemed to be the maximum value of the contract item of work which will be recognized for progress payment purposes:

A.	Clearing and Grubbing	$20,000.00
B.	Progress Schedule (Critical Path Method)	$20,000.00
C.	Bridge Removal (Portion)	$195,600.00

After acceptance of the contract pursuant to the provisions in Section 7-1.17, "Acceptance of Contract," of the Standard Specifications, the amount, if any, payable for a contract item of work in excess of the maximum value for progress payment purposes hereinabove listed for the item, will be included for payment in the first estimate made after acceptance of the contract.

In determining the partial payments to be made to the Contractor, only the following listed materials will be considered for inclusion in the payment as materials furnished but not incorporated in the work:

A. Alternative Pipe Culverts
B. Vitrified Clay Pipe
C. Welded Steel Pipe
D. San Francisco Manhole
E. San Francisco Catch Basin
F. Brick Sidewalk
G. Wrought Iron Fence and Gates
H. Pavement Markers
I. Lighting standards
J. Luminaires
K. Prestressing Steel for Cast-in-place Members (Sealed Packages Only)
L. Prestressing Ducts and Anchorages
M. PTFE Bearing
N. PTFE Spherical Bearing
O. Joint Seal Assembly
P. Seismic Joint Assembly
Q. Bar Reinforcing Steel
R. Structural Steel
S. Miscellaneous Metal (Bridge)

5-1.16 SOUND CONTROL REQUIREMENTS

Sound control shall conform to the provisions in Section 7-1.01I, "Sound Control Requirements," of the Standard Specifications and these special provisions.

The noise level from the Contractor's operations, between the hours of 9:00 p.m. and 6:00 a.m., shall not exceed 86 dbA at a distance of 15 m. This requirement shall not relieve the Contractor from responsibility for complying with local ordinances regulating noise level.

The Contractor's attention is directed to the City and County of San Francisco Noise Control Ordinance (article 29 of the San Francisco Police Code, Ordinance No. 274-72). The Contractor shall have a copy of the said Noise Control Ordinance in his possession prior to the beginning of work.

The Contractor shall submit his plan to mitigate construction noise impacts and to comply with the noise criteria specified herein, including the method of construction, the equipment to be used, and acoustical treatments if necessary, to the Engineer and to the City of San Francisco Senior Street Inspector (415) 554-5816 within 30 calendar days following the date of the Notice to Proceed.

The Contractor shall obtain a night noise permit by contacting the City and County of San Francisco, Department of Public Works at (415) 554-5815 for night work between 8:00 p.m. and 7:00 a.m.

The noise level requirement shall apply to the equipment on the job or related to the job, including but not limited to trucks, transit mixers or transient equipment that may or may not be owned by the Contractor. The use of loud sound signals shall be avoided in favor of light warnings except those required by safety laws for the protection of personnel.

Full compensation for conforming to the requirements of this section shall be considered as included in the prices paid for the various contract items of work involved and no additional compensation will be allowed therefor.

5-1.17 PROJECT APPEARANCE

The Contractor shall maintain a neat appearance to the work.

In areas visible to the public, the following shall apply:

A. When practicable, broken concrete and debris developed during clearing and grubbing shall be disposed of concurrently with its removal. If stockpiling is necessary, the material shall be removed or disposed of weekly.
B. Trash bins shall be furnished for debris from structure construction. Debris shall be placed in trash bins daily. Forms or falsework that are to be re-used shall be stacked neatly concurrently with their removal. Forms and falsework that are not to be re-used shall be disposed of concurrently with their removal.

Full compensation for conforming to the provisions in this section, not otherwise provided for, shall be considered as included in prices paid for the various contract items of work involved and no additional compensation will be allowed therefor.

5-1.18 HAZARDOUS AND NON-HAZARDOUS MATERIAL, GENERAL

Attention is directed to "Hazardous and Non-Hazardous Material Excavation" under "Earthwork" of these special provisions regarding the removal and disposal of hazardous and non-hazardous material.

Hazardous and non-hazardous material has been discovered through testing within the project limits. Testing consisted of collecting and analyzing samples from within the limits of excavation shown on the plans The complete reports entitled "Site Investigation Report, Soil and Groundwater Investigation, Route 101 Central Freeway, San Francisco, California dated May 29, 1998", "Hazardous Waste Site Investigation Report, Route 101 Central Freeway Demolition Project from South Van Ness Avenue to Fell Street, dated April 18, 2002", and "Site Investigation Report, Route 101 Central Freeway Replacement Project, South Van Ness Avenue to Market Street, San Francisco, California, dated April 2003" are available for inspection at the Department of Transportation, Duty Senior's Desk, 111 Grand Avenue, Oakland, California, (510) 286-5209. The test results included in these reports have been used for disposal characterization of material within the project limits and shall not be construed as identifying all locations within the project limits that contain contaminants.

Within the context of this contract, the designation "hazardous" shall apply to soil material with contaminant levels that meet or exceed the contaminant levels specified in Title 22. in the California Code of Regulations (CCR), Section 66261.24.

The designation "hazardous" shall also apply to materials designated as hazardous under the Resource Conservation and Recovery Act (RCRA), to material with Semi Volatile Organic Compounds (SVOCs) greater than Preliminary Remediation Goals (PRGs) for Industrial Wastes, and to materials with Total Petroleum Hydrocarbons (TPH) or Total Recoverable Petroleum Hydrocarbons (TRPH) greater than 100 mg/kg.

Within the context of this contract, the designation "non-hazardous" shall apply to soil material with contaminant levels below the levels specified in the California Code of Regulations Title 22, the Preliminary Remediation Goals (PRGs) for Industrial Wastes, and/or with TPH and TRPH levels less than or equal to 100, and/or with non-detect contaminant levels.

Characterization and disposal of additional material resulting from excavations performed outside of the pay limits shown on the plans, specified in the Standard Specifications, or specified or directed by the Engineer, for the Contractor's convenience, shall be at the Contractor's expense. This resultant material shall be presumed to be hazardous material if the test results for the location indicate that the material being excavated is hazardous material. The Contractor shall dispose of the resultant material in conformance with the provisions in "Earthwork" of these special provisions. When the material must be removed from highway right of way, the Contractor shall furnish replacement material suitable for the purpose intended in conformance with the provisions in Section 19, "Earthwork," of the Standard Specifications.

APPLICABLE RULES AND REGULATIONS

Excavation, transport and disposal of hazardous material and non-hazardous material shall be in accordance with the rules and regulations of the following agencies:

United States Department of Transportation (USDOT)
United States Environmental Protection Agency (USEPA)
California Environmental Protection Agency (CAL-EPA)

1. Department of Toxic Substance Control (DTSC)
2. Integrated Waste Management Board
3. Regional Water Quality Control Board, Region 2 (RWQCB)
4. State Air Resources Board

Bay Area Air Quality Management District (BAAQMD)
California Division of Occupational Safety and Health Administration (CAL-OSHA)
City and County of San Francisco Department of Public Works

PERMITS AND LICENSES

The Contractor shall procure all permits and licenses, pay all charges and fees, and give all notices necessary and incident to the due and lawful prosecution of the work, including registration for transporting vehicles carrying the hazardous material. The California Environmental Quality Act (CEQA) of 1970 (Chapter 1433, Stats. 1970), as amended may be applicable to permits, licenses and authorizations which the Contractor shall obtain from all agencies in connection with performing the work of the contract. The Contractor shall comply with the provisions of said statutes in obtaining such permits, licenses and other authorizations. The Contractor shall also comply with the provisions in section 7-1.04 "Permits and Licenses" of the Standard Specifications.

The Engineer will obtain the Environmental Protection Agency Generator Identification No. and Board of Equalization Identification Number as the State is the Generator.

SAMPLING AND ANALYSIS

The Contractor shall test the material to be excavated at his own expense for any additional acceptance requirements put forth by the disposal facility. Sampling and analysis shall be performed using the sampling and analysis procedure required by the disposal facility. The Contractor shall take samples and obtain analyses under the supervision and guidance of a registered professional experienced in site characterization.

The Contractor may perform additional tests on the material to be excavated at his option and expense for confirmation of the material classification as hazardous or non-hazardous. Sampling and analysis shall be the same or equivalent tests specified in the Materials Information Handout. Sampling and analysis shall be based on guidelines in USEPA, SW 846, "Test Methods for Evaluating Solid Waste, Volume II: Field Manual Physical/Chemical Methods".

The Contractor shall submit for approval by the Engineer, his sampling and analysis procedure and plan, and the name and address, and Environmental Laboratory Program (ELAP) certification number of the laboratory to be used fifteen (15) working days prior to beginning any sampling or analysis for additional disposal facility requirements, reclassification of material excavated under contract, or characterization of any additional material The sampling and analysis procedure and plan shall be prepared under the guidance of a registered professional experienced in site characterization. Analytical results shall be sent by facsimile or hand delivered to the Engineer as soon as they are available. The Engineer will make the final decision on reclassification or characterization of the material after review of the test data. Five (5) working days shall be allowed for the review of test data. If hazardous material is reclassified as non-hazardous the State shall be credited by the amount saved by the Contractor due to less transportation and disposal costs as determined by the Engineer. A summary report of sampling protocols, chain of custody, analysis and laboratory data sheets shall be supplied to the Engineer within 30 days of the completion of sampling. If in the opinion of the Engineer, completion of the work is delayed or interfered with by reason of the Engineer's delay in completing the review, the Contractor will be compensated for any resulting loss, and an extension of time will be granted, in the same manner as provided for in Section 8-1.09, "Right of Ways Delays" of the Standard Specifications.

MEASUREMENT AND PAYMENT

Full compensation for conforming to the requirements of this section shall be considered as included in the prices paid for the various contract items of work affected by this section and no additional compensation will be allowed therefor.

5-1.19 HEALTH, SAFETY AND WORK PLAN

The Contractor shall prepare a detailed Site Health, Safety and Work Plan for all site personnel in accordance with the California Code of Regulations, DTSC and CAL-OSHA regulations. The Health, Safety and Work Plan shall include, at a minimum, but not limited to key site safety personnel, risks associated with the work, training requirements, appropriate personal protective equipment, medical surveillance requirements, air monitoring requirements, work zones, physical barriers, and decontamination requirements. The Health, Safety and Work Plan shall be submitted at least fifteen (15) working days prior to beginning any work for review and acceptance by the Engineer. If the plan is unacceptable it shall be returned, within fifteen (15) working days of the submittal, to the Contractor for revision. The Engineer shall have five (5) working days to review and accept or reject the revised plan from the date the revised plan is received from the Contractor. No work shall proceed until the plan is accepted by the Engineer. Prior to submittal, the Contractor shall have the Health, Safety and Work Plan approved by a Civil Engineer, registered in the State of California and by a Certified Industrial Hygienist.

SAFETY

Prior to performing any work at the locations containing material classified as hazardous, all personnel, including State Personnel, shall complete a CAL-OSHA 40 hour safety training program which meets 29 CFR 1910.120 and 8 CCR 5192 covering the potential hazards as identified. The training, including subsequent training required until the completion of the work, shall be provided by the Contractor. The Contractor shall provide a certification of completion of the Safety Training Program to all personnel. Any personal protective equipment required by the Contractor's Health, Safety and Work Plan for personnel working within the exclusion zone will be supplied to State personnel by the Contractor. The number of State personnel requiring the above mentioned safety training program and personal protective equipment will be 4.

The decontamination area shall be located outside of the exclusion zone. Water from decontamination procedures shall be collected and disposed of at an appropriate disposal site by the Contractor. Non-reusable protective equipment, once used by any personnel, including State personnel, shall be collected and disposed of at an appropriate disposal site by the Contractor.

MEASUREMENT AND PAYMENT

Full compensation for Site Health, Safety, and Work Plan, which shall include full compensation for furnishing all labor, materials, tools, equipment, incidentals, and for doing all work involved in preparing and implementing the Site Health, Safety, and Work Plan including paying the Civil Engineer and Certified Industrial Hygienist and for providing training, personal protective equipment, and medical surveillance shall be considered as included in the prices paid for various contract items of work affected by this section and no additional compensation will be allowed therefor.

SECTION 6. (BLANK)

SECTION 7. (BLANK)

SECTION 8. MATERIALS

SECTION 8-1. MISCELLANEOUS

8-1.01 SUBSTITUTION OF NON-METRIC MATERIALS AND PRODUCTS

Only materials and products conforming to the requirements of the specifications shall be incorporated in the work. When metric materials and products are not available, and when approved by the Engineer, and at no cost to the State, materials and products in the United States Standard Measures which are of equal quality and of the required properties and characteristics for the purpose intended, may be substituted for the equivalent metric materials and products, subject to the following provisions:

A. Materials and products shown on the plans or in the special provisions as being equivalent may be substituted for the metric materials and products specified or detailed on the plans.
B. Before other non-metric materials and products will be considered for use, the Contractor shall furnish, at the Contractor's expense, evidence satisfactory to the Engineer that the materials and products proposed for use are equal to or better than the materials and products specified or detailed on the plans. The burden of proof as to the

quality and suitability of substitutions shall be upon the Contractor and the Contractor shall furnish necessary information as required by the Engineer. The Engineer will be the sole judge as to the quality and suitability of the substituted materials and products and the Engineer's decision will be final.

C. When the Contractor elects to substitute non-metric materials and products, including materials and products shown on the plans or in the special provisions as being equivalent, the list of sources of material specified in Section 6-1.01, "Source of Supply and Quality of Materials," of the Standard Specification shall include a list of substitutions to be made and contract items involved. In addition, for a change in design or details, the Contractor shall submit plans and working drawings in conformance with the provisions in Section 5-1.02, "Plans and Working Drawings," of the Standard Specifications. The plans and working drawings shall be submitted at least 7 days before the Contractor intends to begin the work involved.

Unless otherwise specified, the following substitutions of materials and products will be allowed:

SUBSTITUTION TABLE FOR SIZES OF HIGH STRENGTH STEEL FASTENERS
ASTM Designation: A 325M

METRIC SIZE SHOWN ON THE PLANS mm x thread pitch	SIZE TO BE SUBSTITUTED inch
M16 x 2	5/8
M20 x 2.5	3/4
M22 x 2.5	7/8
M24 x 3	1
M27 x 3	1-1/8
M30 x 3.5	1-1/4
M36 x 4	1-1/2

SUBSTITUTION TABLE FOR PLAIN WIRE REINFORCEMENT
ASTM Designation: A 82

METRIC SIZE SHOWN ON THE PLANS mm^2	SIZE TO BE SUBSTITUTED $inch^2$ x 100
MW9	W1.4
MW10	W1.6
MW13	W2.0
MW15	W2.3
MW19	W2.9
MW20	W3.1
MW22	W3.5
MW25	W3.9, except W3.5 in piles only
MW26	W4.0
MW30	W4.7
MW32	W5.0
MW35	W5.4
MW40	W6.2
MW45	W6.5
MW50	W7.8
MW55	W8.5, except W8.0 in piles only
MW60	W9.3
MW70	W10.9, except W11.0 in piles only
MW80	W12.4
MW90	W14.0
MW100	W15.5

SUBSTITUTION TABLE FOR BAR REINFORCEMENT

METRIC BAR DESIGNATION NUMBER[1] SHOWN ON THE PLANS	BAR DESIGNATION NUMBER[2] TO BE SUBSTITUTED
10	3
13	4
16	5
19	6
22	7
25	8
29	9
32	10
36	11
43	14
57	18

[1]Bar designation numbers approximate the number of millimeters of the nominal diameter of the bars.

[2]Bar numbers are based on the number of eighths of an inch included in the nominal diameter of the bars.

No adjustment will be required in spacing or total number of reinforcing bars due to a difference in minimum yield strength between metric and non-metric bars.

SUBSTITUTION TABLE FOR SIZES OF:

(1) STEEL FASTENERS FOR GENERAL APPLICATIONS (ASTM Designation: A 307 or AASHTO Designation: M 314, Grade 36 or 55), and

(2) HIGH STRENGTH STEEL FASTENERS (ASTM Designation: A 325 or A 449)

METRIC SIZE SHOWN ON THE PLANS mm	SIZE TO BE SUBSTITUTED inch
6 or 6.35	1/4
8 or 7.94	5/16
10 or 9.52	3/8
11 or 11.11	7/16
13 or 12.70	1/2
14 or 14.29	9/16
16 or 15.88	5/8
19 or 19.05	3/4
22 or 22.22	7/8
24, 25, or 25.40	1
29 or 28.58	1-1/8
32 or 31.75	1-1/4
35 or 34.93	1-3/8
38 or 38.10	1-1/2
44 or 44.45	1-3/4
51 or 50.80	2
57 or 57.15	2-1/4
64 or 63.50	2-1/2
70 or 69.85	2-3/4
76 or 76.20	3
83 or 82.55	3-1/4
89 or 88.90	3-1/2
95 or 95.25	3-3/4
102 or 101.60	4

SUBSTITUTION TABLE FOR NOMINAL THICKNESS OF SHEET METAL

UNCOATED HOT AND COLD ROLLED SHEETS		HOT-DIPPED ZINC COATED SHEETS (GALVANIZED)	
METRIC THICKNESS SHOWN ON THE PLANS mm	GAGE TO BE SUBSTITUTED inch	METRIC THICKNESS SHOWN ON THE PLANS mm	GAGE TO BE SUBSTITUTED inch
7.94	0.3125	4.270	0.1681
6.07	0.2391	3.891	0.1532
5.69	0.2242	3.510	0.1382
5.31	0.2092	3.132	0.1233
4.94	0.1943	2.753	0.1084
4.55	0.1793	2.372	0.0934
4.18	0.1644	1.994	0.0785
3.80	0.1495	1.803	0.0710
3.42	0.1345	1.613	0.0635
3.04	0.1196	1.461	0.0575
2.66	0.1046	1.311	0.0516
2.28	0.0897	1.158	0.0456
1.90	0.0747	1.006 or 1.016	0.0396
1.71	0.0673	0.930	0.0366
1.52	0.0598	0.853	0.0336
1.37	0.0538	0.777	0.0306
1.21	0.0478	0.701	0.0276
1.06	0.0418	0.627	0.0247
0.91	0.0359	0.551	0.0217
0.84	0.0329	0.513	0.0202
0.76	0.0299	0.475	0.0187
0.68	0.0269	--------	--------
0.61	0.0239	--------	--------
0.53	0.0209	--------	--------
0.45	0.0179	--------	--------
0.42	0.0164	--------	--------
0.38	0.0149	--------	--------

SUBSTITUTION TABLE FOR WIRE

METRIC THICKNESS SHOWN ON THE PLANS mm	WIRE THICKNESS TO BE SUBSTITUTED inch	GAGE NO.
6.20	0.244	3
5.72	0.225	4
5.26	0.207	5
4.88	0.192	6
4.50	0.177	7
4.11	0.162	8
3.76	0.148	9
3.43	0.135	10
3.05	0.120	11
2.69	0.106	12
2.34	0.092	13
2.03	0.080	14
1.83	0.072	15
1.57	0.062	16
1.37	0.054	17
1.22	0.048	18
1.04	0.041	19
0.89	0.035	20

SUBSTITUTION TABLE FOR PIPE PILES

METRIC SIZE SHOWN ON THE PLANS mm x mm	SIZE TO BE SUBSTITUTED inch x inch
PP 360 x 4.55	NPS 14 x 0.179
PP 360 x 6.35	NPS 14 x 0.250
PP 360 x 9.53	NPS 14 x 0.375
PP 360 x 11.12	NPS 14 x 0.438
PP 406 x 12.70	NPS 16 x 0.500
PP 460 x T	NPS 18 x T"
PP 508 x T	NPS 20 x T"
PP 559 x T	NPS 22 x T"
PP 610 x T	NPS 24 x T"
PP 660 x T	NPS 26 x T"
PP 711 x T	NPS 28 x T"
PP 762 x T	NPS 30 x T"
PP 813 x T	NPS 32 x T"
PP 864 x T	NPS 34 x T"
PP 914 x T	NPS 36 x T"
PP 965 x T	NPS 38 x T"
PP 1016 x T	NPS 40 x T"
PP 1067 x T	NPS 42 x T"
PP 1118 x T	NPS 44 x T"
PP 1219 x T	NPS 48 x T"
PP 1524 x T	NPS 60 x T"

The thickness in millimeters (T) represents an exact conversion of the thickness in inches (T").

SUBSTITUTION TABLE FOR STRUCTURAL TIMBER AND LUMBER

METRIC MINIMUM DRESSED DRY, SHOWN ON THE PLANS mm x mm	METRIC MINIMUM DRESSED GREEN, SHOWN ON THE PLANS mm x mm	NOMINAL SIZE TO BE SUBSTITUTED inch x inch
19x89	20x90	1x4
38x89	40x90	2x4
64x89	65x90	3x4
89x89	90x90	4x4
140x140	143x143	6x6
140x184	143x190	6x8
184x184	190x190	8x8
235x235	241x241	10x10
286x286	292x292	12x12

SUBSTITUTION TABLE FOR NAILS AND SPIKES

METRIC COMMON NAIL, SHOWN ON THE PLANS Length, mm Diameter, mm	METRIC BOX NAIL, SHOWN ON THE PLANS Length, mm Diameter, mm	METRIC SPIKE, SHOWN ON THE PLANS Length, mm Diameter, mm	SIZE TO BE SUBSTITUTED Penny-weight
50.80 2.87	50.80 2.51	_____	6d
63.50 3.33	63.50 2.87	_____	8d
76.20 3.76	76.20 3.25	76.20 4.88	10d
82.55 3.76	82.55 3.25	82.55 4.88	12d
88.90 4.11	88.90 3.43	88.90 5.26	16d
101.60 4.88	101.60 3.76	101.60 5.72	20d
114.30 5.26	114.30 3.76	114.30 6.20	30d
127.00 5.72	127.00 4.11	127.00 6.68	40d
_____	_____	139.70 7.19	50d
_____	_____	152.40 7.19	60d

SUBSTITUTION TABLE FOR IRRIGATION COMPONENTS

METRIC WATER METERS, TRUCK LOADING STANDPIPES, VALVES, BACKFLOW PREVENTERS, FLOW SENSORS, WYE STRAINERS, FILTER ASSEMBLY UNITS, PIPE SUPPLY LINES, AND PIPE IRRIGATION SUPPLY LINES SHOWN ON THE PLANS DIAMETER NOMINAL (DN) mm	NOMINAL SIZE TO BE SUBSTITUTED inch
15	1/2
20	3/4
25	1
32	1-1/4
40	1-1/2
50	2
65	2-1/2
75	3
100	4
150	6
200	8
250	10
300	12
350	14
400	16

Unless otherwise specified, substitutions of United States Standard Measures standard structural shapes corresponding to the metric designations shown on the plans and in conformance with the requirements in ASTM Designation: A 6/A 6M, Annex 2, will be allowed.

8-1.02 PREQUALIFIED AND TESTED SIGNING AND DELINEATION MATERIALS

The Department maintains the following list of Prequalified and Tested Signing and Delineation Materials. The Engineer shall not be precluded from sampling and testing products on the list of Prequalified and Tested Signing and Delineation Materials.

The manufacturer of products on the list of Prequalified and Tested Signing and Delineation Materials shall furnish the Engineer a Certificate of Compliance in conformance with the provisions in Section 6-1.07, "Certificates of Compliance," of the Standard Specifications for each type of traffic product supplied.

For those categories of materials included on the list of Prequalified and Tested Signing and Delineation Materials, only those products shown within the listing may be used in the work. Other categories of products, not included on the list of Prequalified and Tested Signing and Delineation Materials, may be used in the work provided they conform to the requirements of the Standard Specifications.

Materials and products may be added to the list of Prequalified and Tested Signing and Delineation Materials if the manufacturer submits a New Product Information Form to the New Product Coordinator at the Transportation Laboratory. Upon a Departmental request for samples, sufficient samples shall be submitted to permit performance of required tests. Approval of materials or products will depend upon compliance with the specifications and tests the Department may elect to perform.

PAVEMENT MARKERS, PERMANENT TYPE

Retroreflective With Abrasion Resistant Surface (ARS)

A. Apex, Model 921AR (100 mm x 100 mm)

B. Avery Dennison (formerly Stimsonite), Models C88 (100 mm x 100 mm), 911 (100 mm x 100 mm) and 953 (70 mm x 114 mm)
C. Ray-O-Lite, Model "AA" ARS (100 mm x 100 mm)
D. 3M Series 290 (89 mm x 100 mm)
E. 3M Series 290 PSA, with pressure sensitive adhesive pad (89 mm x 100 mm)

Retroreflective With Abrasion Resistant Surface (ARS)

(for recessed applications only)

A. Avery Dennison (formerly Stimsonite), Model 948 (58 mm x 119 mm)
B. Avery Dennison (formerly Stimsonite), Model 944SB (51 mm x 100 mm)*
C. Ray-O-Lite, Model 2002 (58 mm x 117 mm)
D. Ray-O-Lite, Model 2004 ARS (51 mm x 100 mm)*
*For use only in 114 mm wide (older) recessed slots

Non-Reflective, 100 mm Round

A. Alpine Products, "D-Dot" and "ANR" (ABS)
B. Apex Universal (Ceramic)
C. Apex Universal, Models 929 (ABS) and 929PP (Polypropylene)
D. Elgin Molded Plastics, "Empco-Lite" Model 900 (ABS)
E. Hi-Way Safety, Inc., Models P20-2000W and 2001Y (ABS)
F. Interstate Sales, "Diamond Back" (ABS) and (Polypropylene)
G. Novabrite Models Cdot (White) Cdot-y (Yellow), Ceramic
H. Novabrite Models Adot-w (White) Adot-y (Yellow), (ABS)
I. Novabrite Models Pdot-w (White) Pdot-y (Yellow), Polypropylene
J. Road Creations, Model RCB4NR (Acrylic)
K. Three D Traffic Works TD10000 (ABS), TD10500 (Polypropylene)
L. Zumar Industries, "Titan TM40A" (ABS)

PAVEMENT MARKERS, TEMPORARY TYPE

Temporary Markers For Long Term Day/Night Use (6 months or less)

A. Apex Universal, Model 924 (100 mm x 100 mm)
B. Elgin Molded Plastics, "Empco-Lite" Model 901 (100 mm x 100 mm)
C. Road Creations, Model R41C (100 mm x 100 mm)
D. Vega Molded Products "Temporary Road Marker" (75 mm x 100 mm)

Temporary Markers For Short Term Day/Night Use (14 days or less)

(For seal coat or chip seal applications, clear protective covers are required)

A. Apex Universal, Model 932
B. Bunzl Extrusion, Models T.O.M., T.R.P.M., and "HH" (High Heat)
C. Hi-Way Safety, Inc., Model 1280/1281

STRIPING AND PAVEMENT MARKING MATERIAL

Permanent Traffic Striping and Pavement Marking Tape

A. Advanced Traffic Marking, Series 300 and 400
B. Brite-Line, Series 1000
C. Brite-Line, "DeltaLine XRP"
D. Swarco Industries, "Director 35" (For transverse application only)
E. Swarco Industries, "Director 60"
F. 3M, "Stamark" Series 380 and 5730
G. 3M, "Stamark" Series 420 (For transverse application only)

Temporary (Removable) Striping and Pavement Marking Tape (6 months or less)

A. Advanced Traffic Marking, Series 200
B. Brite-Line, Series 100
C. Garlock Rubber Technologies, Series 2000
D. P.B. Laminations, Aztec, Grade 102

E. Swarco Industries, "Director-2"
F. Trelleborg Industri, R140 Series
G. 3M, Series 620 "CR", and Series A750
H. 3M, Series A145, Removable Black Line Mask
(Black Tape: for use only on Asphalt Concrete Surfaces)
I. Advanced Traffic Marking Black "Hide-A-Line"
(Black Tape: for use only on Asphalt Concrete Surfaces)
J. Brite-Line "BTR" Black Removable Tape
(Black Tape: for use only on Asphalt Concrete Surfaces)
K. Trelleborg Industri, RB-140
(Black Tape: for use only on Asphalt Concrete Surfaces)

Preformed Thermoplastic (Heated in place)

A. Avery Dennison, "Hotape"
B. Flint Trading, "Premark," "Premark 20/20 Flex," and "Premark 20/20 Flex Plus"

Ceramic Surfacing Laminate, 150 mm x 150 mm

A. Safeline Industries/Highway Ceramics, Inc.

CLASS 1 DELINEATORS

One Piece Driveable Flexible Type, 1700 mm

A. Bunzl Extrusion, "Flexi-Guide Models 400 and 566"
B. Carsonite, Curve-Flex CFRM-400
C. Carsonite, Roadmarker CRM-375
D. FlexStake, Model 654 TM
E. GreenLine Models HWD1-66 and CGD1-66
F. J. Miller Industries, Model JMI-375 (with soil anchor)

Special Use Type, 1700 mm

A. Bunzl Extrusion, Model FG 560 (with 450 mm U-Channel base)
B. Carsonite, "Survivor" (with 450 mm U-Channel base)
C. Carsonite, Roadmarker CRM-375 (with 450 mm U-Channel base)
D. FlexStake, Model 604
E. GreenLine Models HWDU and CGD (with 450 mm U-Channel base)
F. Impact Recovery Model D36, with #105 Driveable Base
G. Safe-Hit with 200 mm pavement anchor (SH248-GP1)
H. Safe-Hit with 380 mm soil anchor (SH248-GP2) and with 450 mm soil anchor (SH248-GP3)

Surface Mount Type, 1200 mm

A. Bent Manufacturing Company, Masterflex Model MF-180EX-48
B. Carsonite, "Super Duck II"
C. FlexStake, Surface Mount, Models 704 and 754 TM
D. Impact Recovery Model D48, with #101 Fixed (Surface-Mount) Base
E. Three D Traffic Works "Channelflex" Part No. 522248W

CHANNELIZERS

Surface Mount Type, 900 mm

A. Bent Manufacturing Company, Masterflex Models MF-360-36 (Round) and MF-180-36 (Flat)
B. Bunzl Extrusion, Flexi-Guide Models FG300LD and FG300UR
C. Carsonite, "Super Duck" (Flat SDF-436, Round SDR-336)
D. Carsonite, "Super Duck II" Model SDCF203601MB "The Channelizer"
E. FlexStake, Surface Mount, Models 703 and 753 TM
F. GreenLine, Model SMD-36
G. Hi-Way Safety, Inc. "Channel Guide Channelizer" Model CGC36
H. Impact Recovery Model D36, with #101 Fixed (Surface-Mount) Base
I. Repo, Models 300 and 400

J. Safe-Hit, Guide Post, Model SH236SMA
K. The Line Connection, "Dura-Post" Model DP36-3 (Permanent)
L. The Line Connection, "Dura-Post" Model DP36-3C (Temporary)
M. Three D Traffic Works "Channelflex" Part No. 522053W

Lane Separation System

A. Bunzl "Flexi-Guide (FG) 300 Curb System"
B. Qwick Kurb, "Klemmfix Guide System"
C. Recycled Technology, Inc. "Safe-Lane System"

CONICAL DELINEATORS, 1070 mm
(For 700 mm Traffic Cones, see Standard Specifications)
A. Bent Manufacturing Company "T-Top"
B. Plastic Safety Systems "Navigator-42"
C. Radiator Specialty Company "Enforcer"
D. Roadmaker Company "Stacker"
E. TrafFix Devices "Grabber"

OBJECT MARKERS
Type "K", 450 mm

A. Bunzl, Model FG318PE
B. Carsonite, Model SMD 615
C. FlexStake, Model 701 KM
D. Repo, Models 300 and 400
E. Safe-Hit, Model SH718SMA
F. The Line Connection, Model DP21-4K

Type "K-4" / "Q" Object Markers, 600 mm

A. Bent Manufacturing "Masterflex" Model MF-360-24
B. Bunzl Extrusion, Model FG324PE
C. Carsonite, Super Duck II
D. FlexStake, Model 701KM
E. Repo, Models 300 and 400
F. Safe-Hit, Models SH8 24SMA_WA and SH8 24GP3_WA
G. The Line Connection, Model DP21-4Q
H. Three D Traffic Works "Q" Marker, Part No. 531702W

CONCRETE BARRIER MARKERS AND
TEMPORARY RAILING (TYPE K) REFLECTORS
Impactable Type

A. ARTUK, "FB"
B. Bunzl Extrusion, Models PCBM-12 and PCBM-T12
C. Duraflex Corp., "Flexx 2020" and "Electriflexx"
D. Hi-Way Safety, Inc., Model GMKRM100
E. Plastic Safety Systems "BAM" Models OM-BARR and OM-BWAR
F. Sun-Lab Technology, "Safety Guide Light Model TM-5"
G. Three D Traffic Works "Roadguide" TD9000 Series

Non-Impactable Type

A. ARTUK, JD Series
B. Plastic Safety Systems "BAM" Models OM-BITARW and OM-BITARA
C. Vega Molded Products, Models GBM and JD

THRIE BEAM BARRIER MARKERS
(For use to the left of traffic)
A. Bunzl Extrusion, "Mini" (75 mm x 254 mm)

B. Duraflex Corp., "Railrider"

CONCRETE BARRIER DELINEATORS, 400 mm
(For use to the right of traffic)
A. Bunzl Extrusion, Model PCBM T-16
B. Safe-Hit, Model SH216RBM
C. Sun-Lab Technology, "Safety Guide Light, Model TM16," (75 mm x 300 mm)
D. Three D Traffic Works "Roadguide" TD9416 Series

CONCRETE BARRIER-MOUNTED MINI-DRUM (260 mm x 360 mm x 570 mm)
A. Stinson Equipment Company "SaddleMarker"

SOUND WALL DELINEATOR
(Applied vertically. Place top of 75 mm x 300 mm reflective element at 1200 mm above roadway)
A. Bunzl Extrusion, PCBM S-36
B. Sun-Lab Technology, "Safety Guide Light, Model SM12," (75 mm x 300 mm)

GUARD RAILING DELINEATOR
(Place top of reflective element at 1200 mm above plane of roadway)

Wood Post Type, 686 mm

A. Bunzl Extrusion, FG 427 and FG 527
B. Carsonite, Model 427
C. FlexStake, Model 102 GR
D. GreenLine GRD 27
E. J. Miller Model JMI-375G
F. Safe-Hit, Model SH227GRD
G. Three D Traffic Works "Guardflex" TD5100 Series

Steel Post Type

A. Carsonite, Model CFGR-327 with CFGRBK300 Mounting Bracket

RETROREFLECTIVE SHEETING

Channelizers, Barrier Markers, and Delineators

A. Avery Dennison T-6500 Series (Formerly Stimsonite, Series 6200) (For rigid substrate devices only)
B. Avery Dennison WR-6100 Series
C. Nippon Carbide, Flexible Ultralite Grade (ULG) II
D. Reflexite, PC-1000 Metalized Polycarbonate
E. Reflexite, AC-1000 Acrylic
F. Reflexite, AP-1000 Metalized Polyester
G. Reflexite, Conformalight, AR-1000 Abrasion Resistant Coating
H. 3M, High Intensity

Traffic Cones, 330 mm Sleeves

A. Reflexite SB (Polyester), Vinyl or "TR" (Semi-transparent)

Traffic Cones, 100 mm and 150 mm Sleeves

A. Nippon Carbide, Flexible Ultralite Grade (ULG) II
B. Reflexite, Vinyl, "TR" (Semi-transparent) or "Conformalight"
C. 3M Series 3840

Barrels and Drums

A. Avery Dennison WR-6100
B. Nippon Carbide, Flexible Ultralite Grade (ULG) II
C. Reflexite, "Conformalight", "Super High Intensity" or "High Impact Drum Sheeting"
D. 3M Series 3810

Barricades: Type I, Medium-Intensity (Typically Enclosed Lens, Glass-Bead Element)

A. American Decal, Adcolite
B. Avery Dennison, T-1500 and T-1600 series
C. 3M Engineer Grade, Series 3170

Barricades: Type II, Medium-High-Intensity (Typically Enclosed Lens, Glass-Bead Element)

A. Avery Dennison, T-2500 Series
B. Kiwalite Type II
C. Nikkalite 1800 Series

Signs: Type II, Medium-High-Intensity (Typically Enclosed Lens, Glass-Bead Element)

A. Avery Dennison, T-2500 Series
B. Kiwalite, Type II
C. Nikkalite 1800 Series

Signs: Type III, High-Intensity (Typically Encapsulated Glass-Bead Element)

A. Avery Dennison, T-5500 Series
B. Nippon Carbide, Nikkalite Brand Ultralite Grade II
C. 3M Series 3870

Signs: Type IV, High-Intensity (Typically Unmetallized Microprismatic Element)

A. Avery Dennison, T-6500 Series (Formerly Stimsonite Series 6200)
B. Nippon Carbide, Crystal Grade, 94000 Series

Signs: Type VI, Elastomeric (Roll-Up) High-Intensity, without Adhesive

A. Avery Dennison, WU-6014 (Fluorescent orange)
B. Novabrite LLC, "Econobrite"
B. Reflexite "Vinyl" (Orange)
C. Reflexite "SuperBright" (Fluorescent orange)
D. Reflexite "Marathon" (Fluorescent orange)
E. 3M Series RS34 (Orange) and RS20 (Fluorescent orange)

Signs: Type VII, Super-High-Intensity (Typically Unmetallized Microprismatic Element)

A. 3M LDP Series 3970

Signs: Type VIII, Super-High-Intensity (Typically Unmetallized Microprismatic Element)

A. Avery Dennison, T-7500 Series

Signs: Type IX, Very-High-Intensity (Typically Unmetallized Microprismatic Element)

A. 3M VIP Series 3990 Diamond Grade

SPECIALTY SIGNS

A. All Sign Products, STOP Sign (All Plastic), 750 mm
B. Relexite "Endurance" Work Zone Sign (with Semi-Rigid Plastic Substrate)

SIGN SUBSTRATE

Fiberglass Reinforced Plastic (FRP)

A. Fiber-Brite
B. Sequentia, "Polyplate"
C. Inteplast Group "InteCel" (13 mm for Post-Mounted CZ Signs, 1200 mm or less)

Aluminum Composite

A. Alcan Composites "Dibond Material, 2 mm"
B. Mitsubishi Chemical America, Alpolic 350

8-1.03 STATE-FURNISHED MATERIALS

Attention is directed to Section 6-1.02, "State-Furnished Materials," of the Standard Specifications and these special provisions.

The following materials will be furnished to the Contractor:

A. Sign panels for roadside signs and overhead sign structures.
B. Sign overlay panels for overhead sign structures.
C. Hardware for mounting sign panels as follows:

   1. Blind rivets for mounting overlapping legend at sign panel joints.
   2. Closure inserts.
   3. Aluminum bolts and nuts and steel beveled washers for mounting laminated sign panels on overhead sign structures.
   4. Aluminum bolts, nuts, and washers for mounting overhead formed panels.

D. Lamps for vehicular traffic signal units, Type A pedestrian signals, flashing beacon units, and sign lighting fixtures.
E. Model Type 170 controller assembly (Model 334), including controller unit, completely wired controller cabinet, and inductive loop detector sensor units.
F. City signal and lighting standards with anchor bolts, signal and pedestrian heads and mountings.
G. City lighting standards "North Yorkshire" with anchor bolts and luminaires.

Completely wired controller cabinets, with auxiliary equipment but without controller unit, will be furnished to the Contractor at the Caltrans Maintenance Station, 30 Rickard Street, San Francisco, CA 94134.

City signal and lighting standards with anchor bolts, signal heads and mountings as shown on E-11 and E-12 shall be picked up at Traffic Signal Shop yard at, 901 Rankin Street, San Francisco. Appointments for pick up and deliveries shall be made between 9 AM-3 PM and be made at least 24 hours in advance by calling the Signal Maintenance at (415) 550-2736.

City lighting standard, "North Yorkshire," with anchor bolts and luminaires to be installed as shown on the plans shall be picked up at the 30 Rickard Street, San Francisco. CA 94134. Pick up of the standard shall be made at least 24 hours in advance by calling the Caltrans Maintenance Yard at (415) 330-6509.

The Contractor shall notify the Engineer not less than 48 hours before State-furnished material is to be picked up by the Contractor. A full description of the material and the time the material will be picked up shall be provided.

The Contractor shall submit a written request to the Engineer for the delivery of State-furnished materials at least 15 days in advance of their intended use, except that the written request for the delivery of State-furnished sign panels and sign panel overlays for roadside signs and overhead signs structures shall be submitted at least 90 days in advance of their intended installation. The request shall state the quantity and the type of each material.

Padlocks for the backflow preventer assembly enclosures, backflow preventer assembly blankets, walk gates, and irrigation controller enclosure cabinets will be furnished to the Contractor.

8-1.04 ENGINEERING FABRICS

Engineering fabrics shall conform to the provisions in Section 88, "Engineering Fabrics," of the Standard Specifications and these special provisions.

Filter fabric for this project shall be ultraviolet (UV) ray protected.

SECTION 8-2. CONCRETE

8-2.01 PORTLAND CEMENT CONCRETE

Portland cement concrete shall conform to the provisions in Section 90, "Portland Cement Concrete," of the Standard Specifications and these special provisions.

References to Section 90-2.01, "Portland Cement," of the Standard Specifications shall mean Section 90-2.01, "Cement," of the Standard Specifications.

Mineral admixture shall be combined with cement in conformance with the provisions in Section 90-4.08, "Required Use of Mineral Admixtures," of the Standard Specifications for the concrete materials specified in Section 56-2, "Roadside Signs," of the Standard Specifications.

The requirements of Section 90-4.08, "Required Use of Mineral Admixture," of the Standard Specifications shall not apply to Section 19-3.025C, "Soil Cement Bedding," of the Standard Specifications.

The Department maintains a list of sources of fine and coarse aggregate that have been approved for use with a reduced amount of mineral admixture in the total amount of cementitious material to be used. A source of aggregate will be considered for addition to the approved list if the producer of the aggregate submits to the Transportation Laboratory certified test results from a qualified testing laboratory that verify the aggregate complies with the requirements. Prior to starting the testing, the aggregate test shall be registered with the Department. A registration number can be obtained by calling (916) 227-7228. The registration number shall be used as the identification for the aggregate sample in correspondence with the Department. Upon request, a split of the tested sample shall be provided to the Department. Approval of aggregate will depend upon compliance with the specifications, based on the certified test results submitted, together with any replicate testing the Department may elect to perform. Approval will expire 3 years from the date the most recent registered and evaluated sample was collected from the aggregate source.

Qualified testing laboratories shall conform to the following requirements:

A. Laboratories performing ASTM Designation: C 1293 shall participate in the Cement and Concrete Reference Laboratory (CCRL) Concrete Proficiency Sample Program and shall have received a score of 3 or better on all tests of the previous 2 sets of concrete samples.
B. Laboratories performing ASTM Designation: C 1260 shall participate in the Cement and Concrete Reference Laboratory (CCRL) Pozzolan Proficiency Sample Program and shall have received a score of 3 or better on the shrinkage and soundness tests of the previous 2 sets of pozzolan samples.

Aggregates on the list shall conform to one of the following requirements:

A. When the aggregate is tested in conformance with the requirements in California Test 554 and ASTM Designation: C 1293, the average expansion at one year shall be less than or equal to 0.040 percent; or
B. When the aggregate is tested in conformance with the requirements in California Test 554 and ASTM Designation: C 1260, the average of the expansion at 16 days shall be less than or equal to 0.15 percent.

The amounts of cement and mineral admixture used in cementitious material shall be sufficient to satisfy the minimum cementitious material content requirements specified in Section 90-1.01, "Description," or Section 90-4.05, "Optional Use of Chemical Admixtures," of the Standard Specifications and shall conform to the following:

A. The minimum amount of cement shall not be less than 75 percent by mass of the specified minimum cementitious material content.
B. The minimum amount of mineral admixture to be combined with cement shall be determined using one of the following criteria:

    1. When the calcium oxide content of a mineral admixture is equal to or less than 2 percent by mass, the amount of mineral admixture shall not be less than 15 percent by mass of the total amount of cementitious material to be used in the mix.
    2. When the calcium oxide content of a mineral admixture is greater than 2 percent by mass, and any of the aggregates used are not listed on the approved list as specified in these special provisions, then the amount of mineral admixture shall not be less than 25 percent by mass of the total amount of cementitious material to be used in the mix.
    3. When the calcium oxide content of a mineral admixture is greater than 2 percent by mass and the fine and coarse aggregates are listed on the approved list as specified in these special provisions, then the amount of mineral admixture shall not be less than 15 percent by mass of the total amount of cementitious material to be used in the mix.
    4. When a mineral admixture that conforms to the provisions for silica fume in Section 90-2.04, "Admixture Materials," of the Standard Specifications is used, the amount of mineral admixture shall not be less than 10 percent by mass of the total amount of cementitious material to be used in the mix.
    5. When a mineral admixture that conforms to the provisions for silica fume in Section 90-2.04, "Admixture Materials," of the Standard Specifications is used and the fine and coarse aggregates are listed on the approved list as specified in these special provisions, then the amount of mineral admixture shall not be less than 7 percent by mass of the total amount of cementitious material to be used in the mix.

C. The total amount of mineral admixture shall not exceed 35 percent by mass of the total amount of cementitious material to be used in the mix. Where Section 90-1.01, "Description," of the Standard Specifications specifies a maximum cementitious content in kilograms per cubic meter, the total mass of cement and mineral admixture per cubic meter shall not exceed the specified maximum cementitious material content.

The Contractor will be permitted to use Type III portland cement for concrete used in the manufacture of precast concrete members.

SECTION 8-3. WELDING

8-3.01 WELDING

GENERAL

Flux core welding electrodes conforming to the requirements of AWS A5.20 E6XT-4 or E7XT-4 shall not be used to perform welding for this project.

Wherever reference is made to the following AWS welding codes in the Standard Specifications, on the plans, or in these special provisions, the year of adoption for these codes shall be as listed:

AWS Code	Year of Adoption
D1.1	2000
D1.4	1998
D1.5	1995
D1.5 (metric only)	1996

Requirements of the AWS welding codes shall apply unless specified otherwise in the Standard Specifications, on the plans, or in these special provisions. Wherever the abbreviation AWS is used, it shall be equivalent to the abbreviations ANSI/AWS or ANSI/AASHTO/AWS.

Sections 6.1.2 through 6.1.4.3 of AWS D 1.1, Sections 7.1.1 and 7.1.2 of AWS D 1.4, and Sections 6.1.1.1 through 6.1.3.3 of AWS D 1.5 are replaced with the following:

Quality Control (QC) shall be the responsibility of the Contractor. As a minimum, the Contractor shall perform inspection and testing of each weld joint prior to welding, during welding, and after welding as specified in this section and as necessary to ensure that materials and workmanship conform to the requirements of the contract documents.

The QC Inspector shall be the duly designated person who acts for and on behalf of the Contractor for inspection, testing, and quality related matters for all welding.

Quality Assurance (QA) is the prerogative of the Engineer. The QA Inspector is the duly designated person who acts for and on behalf of the Engineer.

The QC Inspector shall be responsible for quality control acceptance or rejection of materials and workmanship, and shall be currently certified as an AWS Certified Welding Inspector (CWI) in conformance with the requirements in AWS QC1, "Standard and Guide for Qualification of Welding Inspectors."

The QC Inspector may be assisted by an Assistant QC Inspector provided that this individual is currently certified as an AWS Certified Associate Welding Inspector (CAWI) in conformance with the requirements in AWS QC1, "Standard and Guide for Qualification of Welding Inspectors," or has equivalent qualifications. The QC Inspector shall monitor the Assistant QC Inspector's work, and shall be responsible for signing all reports.

When the term "Inspector" is used without further qualification, it shall refer to the QC Inspector.

Section 6.14.6, "Personnel Qualification," of AWS D 1.1, Section 7.7.6, "Personnel Qualification," of AWS D 1.4, and Section 6.1.3.4, "Personnel Qualification," of AWS D 1.5 are replaced with the following:

Personnel performing nondestructive testing (NDT) shall be qualified and certified in conformance with the requirements of the American Society for Nondestructive Testing (ASNT) Recommended Practice No. SNT-TC-1A and the Written Practice of the NDT firm. The Written Practice of the NDT firm shall meet or exceed the guidelines of the ASNT Recommended Practice No. SNT-TC-1A. Only individuals who are 1) certified as an NDT Level II, or 2) Level III technicians who hold a current ASNT Level III certificate in that discipline and are authorized and certified to perform the work of Level II technicians, shall perform NDT, review the results, and prepare the written reports.

Section 6.5.4, "Scope of Examination," of AWS D 1.1 and Section 7.5.4 of AWS D 1.4 are replaced with the following:

The QC Inspector shall inspect and approve each joint preparation, assembly practice, welding technique, and the performance of each welder, welding operator, and tack welder to make certain that the applicable requirements of this code and the approved welding procedure specification (WPS) are met.

Section 6.5.4 of AWS D 1.5 is replaced with the following:

The QC Inspector shall inspect and approve each joint preparation, assembly practice, welding technique, and the performance of each welder, welding operator, and tack welder to make certain that the applicable requirements of this code and the approved WPS are met. The QC Inspector shall examine the work to make certain that it meets the requirements of Sections 3 and 9.21. The size and contour of all welds shall be measured using suitable gages. Visual inspection for cracks in welds and base metal, and for other discontinuities should be aided by strong light magnifiers, or such other devices as may be helpful. Acceptance criteria different from those specified in this code may be used when approved by the Engineer.

Section 6.6.5, "Nonspecified Nondestructive Testing Other Than Visual," of AWS D 1.1, Section 6.6.5 of AWS D 1.4 and Section 6.6.5 of AWS D 1.5 shall not apply.

For any welding, the Engineer may direct the Contractor to perform NDT that is in addition to the visual inspection or NDT specified in the AWS welding codes, in the Standard Specifications, or in these special provisions. Additional NDT required by the Engineer, will be paid for as extra work as provided in Section 4-1.03D, "Extra Work," of the Standard Specifications. Should any welding deficiencies be discovered by this additional NDT, the cost of the testing will not be paid for as extra work but shall be at the Contractor's expense.

Required repair work to correct welding deficiencies, whether discovered by the required visual inspection or NDT, or by additional NDT directed by the Engineer, and any associated delays or expenses caused to the Contractor by performing these repairs, shall be at the Contractor's expense.

The Engineer shall have the authority to verify the qualifications or certifications of any welder, QC Inspector, or NDT personnel to specified levels by retests or other means.

A sufficient number of QC Inspectors shall be provided to ensure continuous inspection when any welding is being performed. Continuous inspection, as a minimum, shall include (1) having QC Inspectors continually present on the shop floor or project site when any welding operation is being performed, and (2) having a QC Inspector within such close proximity of all welding operations so that inspections by the QC Inspector of each operation, at each welding location, shall not lapse for a period exceeding 30 minutes.

Inspection and approval of all joint preparations, assembly practices, welding techniques, and the performance of each welder, welding operator, and tack welder shall be documented by the QC Inspector on a daily basis for each day that welding is performed. The QC Inspector shall confirm and document compliance with the requirements of the AWS code criteria and the requirements of these special provisions on all weld joints before welding, during welding, and after the completion of each weld.

When joint details that are not prequalified by the applicable AWS codes are proposed for use in the work, welders using these details shall perform a qualification test plate using the approved WPS variables and the joint detail to be used in production. The test plate shall be the maximum thickness to be used in production. The test plate shall be mechanically or radiographically tested as directed by the Engineer. Mechanical and radiographic testing and acceptance criteria shall be as specified in the applicable AWS codes.

The period of effectiveness for a welder's or welding operator's qualification shall be a maximum of 3 years for the same weld process, welding position, and weld type. A valid qualification at the beginning of work on a contract will be acceptable for the entire period of the contract, as long as the welder's work remains satisfactory.

WELDING QUALITY CONTROL

Welding quality control shall conform to the requirements in the AWS welding codes, the Standard Specifications, and these special provisions.

Unless otherwise specified, welding quality control shall apply when any work is welded in conformance with the provisions in Section 49, "Piling," Section 52, "Reinforcement," Section 55, "Steel Structures," Section 56-1, "Overhead Sign Structures," Section 75-1.035, "Bridge Joint Restrainer Units," or Section 86-2.04, "Standards, Steel Pedestals and Posts," of the Standard Specifications.

In addition, welding quality control shall apply when welding is performed for the following work:

A. Seismic Joint Assembly (MR > 100 mm)

The welding of fracture critical members (FCMs) shall conform to the provisions specified in the Fracture Control Plan (FCP) and herein.

The Contractor shall designate in writing a welding Quality Control Manager (QCM). The QCM shall be responsible directly to the Contractor for the quality of welding, including materials and workmanship, performed by the Contractor and subcontractors.

The QCM shall be the sole individual responsible to the Contractor for submitting, receiving, and approving all correspondence, required submittals, and reports to and from the Engineer.

The QCM shall not be employed or compensated by any subcontractor, or by other persons or entities hired by subcontractors, who will provide other services or materials for the project. The QCM may be an employee of the Contractor.

Welding inspection personnel or NDT firms to be used in the work shall not be employed or compensated by any subcontractor, or by other persons or entities hired by subcontractors, who will provide other services or materials for the project, except for the following conditions:

A. The welding is performed at a permanent fabrication or manufacturing facility which is certified under the AISC Quality Certification Program, Category Cbr, Major Steel Bridges.
B. The welding is performed at a permanent fabrication or manufacturing facility which is certified under the AISC Quality Certification Program, Category Sbd, Conventional Steel Building Structures. This condition shall apply only for work welded in conformance with the provisions in Section 56-1, "Overhead Sign Structures" or Section 86-2.04, "Standards, Steel Pedestals and Posts," of the Standard Specifications.
C. The welding is performed on pipe pile material at a permanent pipe manufacturing facility where an automatic welding process or seamless pipe operation is used in conformance with the requirements in the applicable welding code as specified elsewhere in these special provisions.

For welding performed at such facilities, the inspection personnel or NDT firms may be employed or compensated by the facility performing the welding.

Prior to submitting the Welding Quality Control Plan (WQCP) required herein, a pre-welding meeting between the Engineer, Contractor, and any entity performing welding for this project, shall be held to discuss the requirements for the WQCP.

The Contractor shall submit to the Engineer, in conformance with the provisions in Section 5-1.02, "Plans and Working Drawings," of the Standard Specifications, 3 copies of a separate WQCP for each item of work for which welding is to be performed.

The Contractor shall allow the Engineer 2 weeks to review the WQCP submittal after a complete plan has been received. Except for work that is welded in conformance with Section 86-2.04, "Standards, Steel Pedestals and Posts," of the Standard Specifications, and for pipe piling produced at a permanent manufacturing facility as specified above, no welding shall be performed until the WQCP is approved in writing by the Engineer. Materials welded in conformance with Section 86-2.04, "Standards, Steel Pedestals and Posts," of the Standard Specifications, and pipe piling produced at such permanent manufacturing facilities, shall not be incorporated into the work until the WQCP is approved in writing by the Engineer. In the event the Engineer fails to complete the review within the time allowed, and if, in the opinion of the Engineer, completion of the work is delayed or interfered with by reason of the Engineer's delay in completing the review, the Contractor will be compensated for any resulting loss, and an extension of time will be granted, in the same manner as provided for in Section 8-1.09, "Right of Way Delays," of the Standard Specifications.

An amended WQCP or any addendum to the approved WQCP shall be submitted to, and approved in writing by the Engineer, for proposed revisions to the approved WQCP. An amended WQCP or addendum will be required for revisions to the WQCP, including but not limited to a revised WPS, additional welders, changes in NDT firms or procedures, QC, or NDT personnel, or updated systems for tracking and identifying welds. The Engineer shall have 3 working days to complete the review of the amended WQCP or addendum. Work affected by the proposed revisions shall not be performed until the amended WQCP or addendum has been approved. In the event the Engineer fails to complete the review within the time allowed, and if, in the opinion of the Engineer, completion of the work is delayed or interfered with by reason of the Engineer's delay in completing the review, the Contractor will be compensated for any resulting loss, and an extension of time will be granted, in the same manner as provided for in Section 8-1.09, "Right of Way Delays," of the Standard Specifications.

Each WQCP shall include the applicable portions of the following, as determined by the Engineer:

A. The name of the welding firm and any required NDT inspection personnel or firms.
B. A manual prepared by the NDT inspection personnel or firm that shall include equipment, testing procedures, code of safe practices, the Written Practice of the NDT inspection personnel or firm, and the names, qualifications, and documentation of certifications for all personnel to be used.
C. The name of the QCM and the names, qualifications, and documentation of certifications for all QC Inspectors and Assistant QC Inspectors to be used.
D. An organizational chart showing all QC personnel and their assigned QC responsibilities.
E. The methods and frequencies for performing all required quality control procedures, including QC inspection forms to be used, as required by the specifications including:

1. all visual inspections.
2. all NDT including radiographic geometry, penetrameter and shim selection, film quality, film processing, radiograph identification and marking system, and film interpretation and reports.
3. calibration procedures and calibration frequency for all NDT equipment.

F. A system for the identification and tracking of all welds, NDT, and any required repairs, and a procedure for the reinspection of repaired welds. The system shall have provisions for 1) permanently identifying each weld and the person who performed the weld, 2) placing all identification and tracking information on each radiograph, 3) a method of reporting nonconforming welds to the Engineer, and 4) a method of documentation of repairs and reinspection of nonconforming welds.
G. Standard procedures for performing noncritical repair welds. Noncritical repair welds are defined as welds to deposit additional weld beads or layers to compensate for insufficient weld size and to fill limited excavations that were performed to remove unacceptable edge or surface discontinuities, rollover or undercut. The depth of these excavations shall not exceed 65 percent of the specified weld size.
H. The WPS, including documentation of all supporting Procedure Qualification Record (PQR) tests performed, and the name of the testing laboratory who performed the tests, to verify the acceptability of the WPS. The submitted WPS shall be within the allowable period of effectiveness.
I. Documentation of all certifications for welders for each weld process and position that will be used. Certifications shall list the electrodes used, test position, base metal and thickness, tests performed, and the witnessing authority. All certifications shall be within the allowable period of effectiveness.
J. One authorized copy or original code book for each of all AWS welding codes and the FCP which are applicable to the welding to be performed. These codes and the FCP shall become the permanent property of the Department.
K. Forms to be used for Certificates of Compliance, daily production logs, and daily reports.

After final approval of the WQCP, amended WQCP, or addendum, the Contractor shall submit 7 copies to the Engineer of the approved documents.

It is expressly understood that the Engineer's approval of the Contractor's WQCP shall not relieve the Contractor of any responsibility under the contract for the successful completion of the work in conformance with the requirements of the plans and specifications. The Engineer's approval shall not constitute a waiver of any requirement of the plans and specifications nor relieve the Contractor of any obligation thereunder; and defective work, materials, and equipment may be rejected notwithstanding approval of the WQCP.

A daily production log for welding shall be kept by the QCM for each day that welding is performed. The log shall clearly indicate the locations of all welding, except partial penetration longitudinal seam welds performed in conformance with Section 86-2.04, "Standards, Steel Pedestals and Posts," of the Standard Specifications. The log shall include the welders' names, amount of welding performed, any problems or deficiencies discovered, and any testing or repair work performed, at each location. The daily report from each QC Inspector shall also be included in the log.

The following items shall be included in a Welding Report that is to be submitted to the Engineer within 7 days following the performance of any welding. For work welded in conformance with Section 86-2.04, "Standards, Steel Pedestals and Posts," of the Standard Specifications, and for piling produced at a permanent manufacturing facility, the following items shall be included in a Welding Report that is to be submitted to the Engineer 48 hours prior to furnishing a Certificate of Compliance for the material:

A. Reports of all visual weld inspections and NDT.
B. Radiographs and radiographic reports, and other required NDT reports.
C. Documentation that the Contractor has evaluated all radiographs and other nondestructive tests and corrected all rejectable deficiencies, and all repaired welds have been reexamined by the required NDT and found acceptable.
D. Daily production log.

Radiographic envelopes shall have clearly written on the outside of the envelope the following information: name of the QCM, name of the nondestructive testing firm, name of the radiographer, date, contract number, complete part description, and all included weld numbers or a report number, as detailed in the WQCP. In addition, all innerleaves shall have clearly written on them the part description and all included weld numbers, as detailed in the WQCP.

Reports regarding NDT, including radiographs, shall be signed by both the NDT technician and the person that performed the review, and then submitted directly to the QCM for review and signature prior to submittal to the Engineer. Corresponding names shall be clearly printed or typewritten next to all signatures.

The Engineer will review the Welding Report to determine if the Contractor is in conformance with the WQCP. Unless otherwise specified, the Engineer shall be allowed 7 working days to review the report and respond in writing after a

complete Welding Report has been received. Prior to receiving notification from the Engineer of the Contractor's conformance with the WQCP, the Contractor may encase in concrete or cover welds for which a Welding Report has been submitted. However, should the Contractor elect to encase or cover those welds prior to receiving notification from the Engineer, it is expressly understood that the Contractor shall not be relieved of the responsibility for incorporating material in the work that conforms to the requirements of the plans and specifications. Material not conforming to these requirements will be subject to rejection. Should the Contractor elect to wait to encase or cover welds pending notification by the Engineer, and in the event the Engineer fails to complete the review within the time allowed, and if, in the opinion of the Engineer, completion of the work is delayed or interfered with by reason of the Engineer's delay in completing the review, the Contractor will be compensated for any resulting loss, and an extension of time will be granted, in the same manner as provided for in Section 8-1.09, "Right of Way Delays," of the Standard Specifications.

The QC Inspector shall provide reports to the QCM on a daily basis for each day that welding is performed.

Except for noncritical weld repairs, the Engineer shall be notified immediately in writing when welding problems, deficiencies, base metal repairs, or any other type of repairs not submitted in the WQCP are discovered and also of the proposed repair procedures to correct them. The Contractor shall allow the Engineer one week to review these procedures. No remedial work shall begin until the repair procedures are approved in writing by the Engineer. In the event the Engineer fails to complete the review within the time allowed, and if, in the opinion of the Engineer, completion of the work is delayed or interfered with by reason of the Engineer's delay in completing the review, the Contractor will be compensated for any resulting loss, and an extension of time will be granted, in the same manner as provided for in Section 8-1.09, "Right of Way Delays," of the Standard Specifications.

The QCM shall sign and furnish to the Engineer, a Certificate of Compliance in conformance with the provisions in Section 6-1.07, "Certificates of Compliance," of the Standard Specifications for each item of work for which welding was performed. The certificate shall state that all of the materials and workmanship incorporated in the work, and all required tests and inspections of this work, have been performed in conformance with the details shown on the plans, the Standard Specifications, and these special provisions.

PAYMENT

Full compensation for conforming to the requirements of this section shall be considered as included in the contract prices paid for the various items of work involved and no additional compensation will be allowed therefor.

SECTION 9. DESCRIPTION OF BRIDGE WORK

The bridge work to be done consists, in general, of constructing the following bridge, as shown on the plans and briefly described as follows:

Central Viaduct (Replace)
(Bridge No. 34-0077)

A multiple-span steel girder bridge with prestressed concrete bent caps approximately 433 meters in length. Foundations utilize cast-in-drilled hole concrete piling.

SECTION 10. CONSTRUCTION DETAILS

SECTION 10-1. GENERAL

10-1.01 ORDER OF WORK

Order of work shall conform to the provisions in Section 5-1.05, "Order of Work," of the Standard Specifications and these special provisions.

Temporary railing (Type K) and temporary crash cushions shall be secured in place prior to commencing work for which the temporary railing and crash cushions are required.

As a first order of work the Contractor shall examine, perform video services and photograph facilities in accordance with the requirements in, "Photo Survey of Existing Facilities", "Vibration Monitoring" and "Sewer Video Survey" of these special provisions.

Attention is directed to "Water Pollution Control" of these special provisions regarding the submittal and approval of the Storm Water Pollution Control Program prior to performing work having potential to cause water pollution.

Attention is directed to "Obstructions" of these special provisions regarding utility work on McCoppin Street between Valencia Street and Market Street.

The first order of work shall be to place the order for the electrical equipment. The Engineer shall be furnished a statement from the vendor that the order for the electrical equipment has been received and accepted by the vendor.

All work on city streets in the City of San Francisco shall require a permit from the City of San Francisco. The permit shall be at no cost to the Contractor, except penalties for violations of the permit regulations shall be the responsibility of the Contractor. Regulations and local ordinances for the City of San Francisco will be available to the prospective bidders at:

Bureau of Street Use and Mapping
Department of Public Work
875 Stevenson Street, Room 460
San Francisco, CA 94103
Telephone: (415) 554-5810

The uppermost layer of new pavement shall not be placed until all underlying conduits and loop detectors have been installed.

Prior to commencement of the traffic signal functional test at any location, all items of work related to signal control shall be completed and all roadside signs, pavement delineation, and pavement markings shall be in place at that location.

No overhead sign panel shall be installed until the overhead sign lighting is completely operational.

No above ground electrical work shall be performed on any system within the project site until all Contractor-furnished electrical materials for that individual system have been tested and delivered to Contractor.

Attention is directed to "Maintaining Traffic" and "Temporary Pavement Delineation" of these special provisions and to the stage construction sheets of the plans.

Attention is directed to "Progress Schedule (Critical Path Method)" of these special provisions regarding the submittal of a general time-scaled logic diagram within 10 days after approval of the contract. The diagram shall be submitted prior to performing any work that may be affected by any proposed deviations to the construction staging of the project.

The work shall be performed in conformance with the stages of construction shown on the plans. Nonconflicting work in subsequent stages may proceed concurrently with work in preceding stages, provided satisfactory progress is maintained in the preceding stages of construction.

In each stage, after completion of the preceding stage, the first order of work shall be the removal of existing pavement delineation as directed by the Engineer. Pavement delineation removal shall be coordinated with new delineation so that lane lines are provided at all times on traveled ways open to public traffic.

Before obliterating any pavement delineation (traffic stripes, pavement markings, and pavement markers) that is to be replaced on the same alignment and location, as determined by the Engineer, the pavement delineation shall be referenced by the Contractor, with a sufficient number of control points to reestablish the alignment and location of the new pavement delineation. The references shall include the limits or changes in striping pattern, including one- and 2-way barrier lines, limit lines, crosswalks and other pavement markings. Full compensation for referencing existing pavement delineation shall be considered as included in the contract prices paid for new pavement delineation and no additional compensation will be allowed therefor.

Prior to applying asphalt concrete, the Contractor shall cover all manholes, valve and monument covers, grates, or other exposed facilities located within the area of application, using a plastic or oil resistant construction paper secured to the facility being covered by tape or adhesive. The covered facilities shall be referenced by the Contractor, with a sufficient number of control points to relocate the facilities after the asphalt concrete has been placed. After completion of the asphalt concrete paving operation, all covers shall be removed and disposed of in a manner satisfactory to the Engineer. Full compensation for covering manholes, valve and monument covers, grates, or other exposed facilities, referencing, and removing temporary cover shall be considered as included in the contract price paid per tonne for asphalt concrete (type A), and no additional compensation will be allowed therefor.

The Contractor shall notify the Engineer at least 72 hours in advance of starting work within each State owned parking lot facility within the project limits. The 4 parking lot facilities are shown below and indicate the bent and abutment locations within:

1. Lot SFX 101-59/60: (Bents 1 and 2)
2. Lot 101-26: (Bents 5 through 7)
3. Lot 101-25: (Bents 8 and 9)
4. Lot 101-23/24: (Bent 10 and Abutment)

Not less than 60 days prior to planting the plants, the Contractor shall furnish the Engineer a statement from the vendor that the order for the plants required for this contract, including inspection plants, has been received and accepted by the vendor. The statement from the vendor shall include the names, sizes, and quantities of plants ordered and the anticipated date of delivery.

The Contractor shall place orders for replacement plants with the vendor at the appropriate time so that the roots of the replacement plants are not in a root-bound condition.

Attention is directed to "Irrigation Systems Functional Test" of these special provisions, regarding restrictions for planting operations.

Unless otherwise shown on the plans or specified in these special provisions, conduits to be jacked or drilled or installed by the open trench method for water line crossovers and sprinkler control crossovers shall be installed prior to the installation of other pipe supply lines.

Attention is directed to Section 20-5.027B, "Wiring Plans and Diagrams," of the Standard Specifications regarding submittal of working drawings.

Attention is directed to "Irrigation Controller Enclosure Cabinet" of these special provisions regarding preinstalling irrigation components in the irrigation controller enclosure cabinet prior to field installation.

Attention is directed to "Palm Tree Planting" of these special provisions regarding the time restraints specified for palm tree planting.

10-1.02 PHOTO SURVEY OF EXISTING FACILITIES

This work shall consist of preparing a photo survey and crack monitoring of existing facilities, buildings, sub sidewalk basements, and other improvements which could be damaged by the Contractor's operations. The Contractor shall prepare the photo survey prior to and after performing construction activities and as directed by the Engineer. The crack monitoring shall be on existing cracks and shall be completed with the first photo survey and periodically throughout construction activities. The Contractor shall obtain consent from property owners prior to performing any photo survey or crack monitoring. Refusal of a property owner to allow photo survey or crack monitoring shall be duly documented by the Contractor.

The photo survey shall consist of photographic and video recordings of the conditions of the facilities (internal and external cracks in structures, settlement, leakage and the like) and shall document the condition of the foundations, walls, ceiling, roof, improvements and other building elements on the interiors and exteriors of specified facilities.

The pre-construction photo survey shall be conducted at least 10 days prior to construction activities. The post-construction photo survey shall be performed on the same facilities within 5 working days after completion of construction activities.

The photo survey and crack monitoring shall be conducted at facilities shown in the table entitled "Vibration Monitoring and Photo Survey" in "Vibration Monitoring," elsewhere in these special provisions and as directed by the Engineer. Photo survey of any listed facility shall be completed within 26m of that particular building or structure.

Crack monitoring shall be with a calibrated crack monitoring device approved by the Engineer.

The Contractor shall submit to the Engineer for approval a complete description of the work to be completed for each surveyed location. The work to be completed shall consist of records of observations, videotapes, and photographs.

The Contractor shall notify the Engineer 48 hours prior to beginning the photo and crack monitoring work.

Each photograph is to be color and have a printed image size of at least 12.7 cm x 17.8 cm. All prints shall be on glossy photographic paper. Proof sheets, thumbnail prints, contract prints, or digital photos are not acceptable. All negatives shall be provided in protective sleeves. The negatives shall be indexed to facilitate expeditious reproduction. All photographs shall be identified by date, location, orientation, and labeled with a detailed description. All photographs shall be submitted in a 3-ring binder and shall include the following: protective photo sleeves, building layout, and summary sheet indexing all photographs.

The photo survey shall also include video tape recordings of the foundation, floor, walls, ceiling, roof, improvements, and all building elements inside and outside specified facilities. The video tapes shall show the condition of the facility, including but not limited to any and all deficiencies in the facility such as cracks, settlement, leakage, and the like. The video tape recordings shall be narrated contemporaneously by the camera operator, documenting the location, orientation, time and date of the scene. The videotapes shall be premium grade VHS color tapes and shall be recorded in the Standard Play (SP) mode. All video tape recordings shall be made to the highest quality standards. No more than one facility shall be recorded on a single videotape. The Contractor shall submit the original, unedited video recording to the Engineer.

A written report of the record of observations shall be submitted with the video tape. The written report shall include the time, date, and location of the video tape recording. The report shall also include a table listing any anomalies along with a videocassette counter for each anomaly recorded on the videotape.

The photographs, videotapes, and reports of all observations shall be prepared in triplicate by the Contractor and every document shall be signed by the authorized representatives of the State and of the Contractor. Videotapes and photographs, as deemed advisable by the Engineer will be made by the Contractor and signed in the manner specified above. One signed copy of every document and photograph will be kept on file by the Engineer.

The pre-construction survey records and documentation specified above shall be submitted to the Engineer prior to commencement of construction activities. The Engineer shall have 5 working days to review the submittal for adequacy. No work shall take place unless the Engineer approves the pre-construction survey records.

The post-construction survey documents shall be submitted with 10 working days after construction activities are completed.

The above-referenced records, videotapes, and photographs are intended for use as indisputable evidence in ascertaining the extent of any damage that may occur as a result of the Contractor's operations. The above-referenced records, videotapes, and photographs are for the protection of the adjacent property owners, the Contractor, and the State. These records will be used to determine any damage from the Contractor's operations during the work.

Attention is directed to Section 7-1.12, "Responsibility for Damage" of the Standard Specifications. The Contractor shall immediately inform the Engineer in writing of any damage to these and other facilities.

The contract lump sum price paid for photo survey of existing facilities shall include full compensation for furnishing all labor, materials, tools, equipment, and incidentals, and for doing all the work involved in photo survey and crack monitoring, as specified in these special provisions, and as directed by the Engineer.

The Engineer may order photo surveys, and crack monitoring of existing facilities other than those facilities listed under, "Vibration Monitoring and Photo Survey." Photo surveys and crack monitoring of existing facilities other than those facilities listed under "Vibration Monitoring and Photo Survey" will be paid for as extra work as provided in Section 4-1.03D of the Standard Specifications.

10-1.03 VIBRATION MONITORING

This work shall consist of furnishing, installing and maintaining vibration-monitoring instrumentation; collecting vibration data; and interpreting and reporting the results of vibration monitoring as specified herein. This work shall include the implementation by the Contractor of any required remedial and precautionary measures, using the vibration monitoring data, to protect the following properties from excess vibration during construction activities:

LOCATION OF VIBRATION MONITORING AND PHOTO SURVEY

1772 Market St.
1755 Market St.
155 McCoppin St.
1795 Market St.
12 Elgin Park
25 Elgin Park
31 Elgin Park
33 Elgin Park
47, 49 Elgin Park
51 Elgin Park
100 Valencia St. (U-Haul Truck and Equipment Rental)
150 Valencia St.
170 Valencia St.
Building between 177 Valencia St. & McCoppin St.
177 Valencia St.
84 Duboce Ave.
80 Duboce Ave.
1354 Stevensen St.
1367, 1369 Stevensen St.
1363, 1365 Stevensen St.
190 Otis St.
1695 Mission St. (Discount Builder’s Supply)
1710 Mission St
1700 Misson St.
1727 Mission St. (City Center Building)
15 Duboce Ave.
25 Duboce Ave.
31 Duboce Ave.
47 Duboce Ave.
170 South Van Ness Ave.

San Francisco Municipal Railway tunnel under Market St.
Bay Area Rapid Transit tunnels under Otis St.
205 13th Street

The Contractor shall obtain consent from property owners prior to performing any vibration monitoring. Refusal of a property owner to allow vibration monitoring shall be duly documented by the Contractor.

GENERAL

The Contractor shall be responsible for the following, including but not limited to:

A. Furnish and install vibration-monitoring instrumentation.
B. Protect from damage and maintain instruments installed by the Contractor and repair or replace damaged or inoperative instruments.
C. Collect, interpret and report data from instrumentation specified herein.
D. Implement response actions.

Caltrans is not responsible for the safety of the work based on vibration-monitoring data, and compliance with this Section does not relieve the Contractor of full responsibility for damage caused by the Contractor's operations.

VIBRATION MONITORING PERSONNEL

The Contractor's vibration-monitoring personnel shall have the qualifications specified herein. These personnel may be on the staff of the Contractor. However, they shall not be employed nor compensated by subcontractors, or by persons or entities hired by subcontractors, who will provide other services or material for the project.

The Contractor's vibration-monitoring personnel shall include a qualified Vibration Instrumentation Engineer who is a registered Professional Engineer in the State of California, and who has at least 4 years of experience in the installation and use of vibration-monitoring instrumentation and in interpreting instrumentation data. The Vibration Instrumentation Engineer shall:

1. Be on site and supervise the initial installation of each vibration-monitoring instrument.
2. Supervise interpretations of vibration-monitoring data.

The Contractor's vibration-monitoring personnel shall be subject to the review of the Engineer.

VIBRATION MONITORING SUBMITTALS

Prior to any bridge removal or significant impact work and prior to performing any vibration monitoring, the Contractor shall submit to the Engineer a written vibration monitoring plan, vibration monitoring equipment manufacturer's product data and the resumes of the Vibration Instrumentation Engineer and any vibration monitoring technical support personnel.

The vibration monitoring equipment manufacturer's data shall describe in detail all vibration-monitoring instruments. Requests for consideration of substitutions, if any, together with product data and instruction manuals for requested substitutions.

The resumes of the Vibration Instrumentation Engineer and any vibration monitoring technical support personnel shall be sufficient to define details of relevant experience.

The written vibration monitoring plan shall detail the procedures for vibration monitoring. Such details shall include, but not limited to:

1. The name of the Firm providing the vibration monitoring services.
2. Description of the instrumentation and equipment to be used.
3. Measurement locations and methods for mounting the vibration sensors.
4. Procedures for data collection and analysis.
5. Means and methods of providing warning when the particle velocity equals or exceeds specified limits.
6. Generalized plans of action to be implemented in the event is the particle velocity equals or exceeds specified limits. The generalized plans of action shall be positive measures by the Contractor to control vibrations (e.g. using alternative construction methods).
7. Name of the "responsible person" designated by the Contractor. The responsible person designated by the Contractor shall have the authority to stop the work causing the vibration.

Within 5 days of receipt of each instrument at the site, the Contractor shall submit to the Engineer a copy of the instruction manual and the laboratory calibration and test equipment certification.

In addition, the Contractor shall submit data and reports as specified in "Data Reduction, Processing, Plotting and Reporting" in these special Provisions.

The review period shall be the same as those set forth in Section 51-1.06A, Falsework Design and Drawings" of the Standard Specifications.

VIBRATION MONITORING EQUIPMENT

The Contractor shall provide portable seismographs for monitoring the velocities of ground vibrations resulting from construction activities. Seismographs shall be Model DS-477 Blastmate II as manufactured by Instantel Inc., Kanata (Ottawa), Ontario, Canada, Model VMS-500 as manufactured by Thomas Instruments, Inc., Spofford, NH, or Model NC5310/D, as manufactured by Nomis Inc., Birmingham, AL, or acceptable equivalent. The seismograph shall have the following minimum features:

1. Seismic range: 0.01 to 4 inches per second with an accuracy of +5 percent of the measured peak particle velocity or better at frequencies between 10 Hertz and 100 Hertz, and with a resolution of 0.01 inches per second or less.
2. Frequency response (+3 dB points): 2 to 200 Hertz.
3. Three channels for simultaneous time-domain monitoring of vibration velocities in digital format on three perpendicular axes.
4. Two power sources: internal rechargeable battery and charger and 115 volts AC. Battery must be capable of supplying power to monitor vibrations continuously for up to 24 hours.
5. Capable of internal, dynamic calibration.
6. Direct writing to printer and capability to transfer data from memory to 3-1/2 inch magnetic disk. Instruments must be capable of producing strip chart recordings of readings on site within one hour of obtaining the readings. Provide computer software to perform analysis and produce reports of continuous monitoring.
7. Continuous monitoring mode must be capable of recording single-component peak particle velocities, and frequency of peaks with an interval of one minute or less.

Whenever any product is specified by brand name and model number, such specifications shall be deemed to be used for the purpose of establishing a standard of quality and facilitating the description of the product desired. The term "acceptable equivalent" shall be understood to indicate a product that is the same or better than the product named in the specifications in function, quality, performance, reliability, and general configuration. This procedure is not to be construed as eliminating other manufacturers' suitable products of equal quality.

The Contractor may request to substitute an "acceptable equivalent" vibration monitoring equipment and shall submit complete comparative data to the Engineer for consideration of another product. Any request from the Contractor for consideration of a substitution shall clearly state the nature of the deviation from the product specified. Substitute products shall not be used in the work unless accepted by the Engineer in writing. The Engineer will be the sole judge of the suitability and equivalency of the proposed substitution.

The Contractor's instrumentation personnel shall conduct regular maintenance of seismograph installations.

All seismographs shall have been calibrated by the manufacturer or certified calibration laboratory within one year of their use on site. A current certificate of calibration shall be submitted to the Engineer with the Contractor's data.

A record of laboratory calibration shall be provided for all vibration-monitoring instruments to be used on site. Certification shall be provided to indicate that the instruments are calibrated and maintained in accordance with the equipment manufacturer's calibration requirements and that calibrations are traceable to the U. S. National Institute of Standards and Technology (NIST).

VIBRATION MONITORING

The Contractor shall furnish all installation tools, materials, and miscellaneous instrumentation components for vibration monitoring. At the above listed locations, vibration monitoring and recording shall be performed during the course of all construction activity, or other significant impact work, when that activity occurs within 26 meter of the said facilities. The 26 meter shall be measured from the edge of the construction activity.

The Contractor shall notify the Engineer at least 24 hours prior to starting a new vibration-producing construction task, and shall have the seismographs in place and functioning properly prior to any work within 26 meter as defined above. No work occurring within this zone shall occur unless monitoring equipment is functioning properly.

The equipment shall be set up in a manner such that an immediate warning is given when particle velocity equal to or exceeding 5 millimeter per second is produced. The warning emitted by the vibration-monitoring equipment shall be

instantaneously transmitted to the responsible person designated by the Contractor by means of warning lights, audible sounds or electronic transmission.

Monitoring equipment shall be stationed within 0.9 meter of the exterior of designated buildings on the side facing the Contractor's work site. For buildings whose frontage exceeds 60 meter, at least 2 monitors shall be utilized at that location.

When any reading on monitoring equipment equals or exceeds 5 millimeter per second, work shall immediately cease and the Contractor shall immediately notify the Engineer. If directed by the Engineer, the Contractor shall submit within 24 hours a detailed specific plan of action so that the vibration limits are not violated. The Contractor shall take whatever action is necessary to reduce and maintain the monitoring equipment reading below a particle velocity of 5 millimeter per second.

The seismograph vibration sensors shall be firmly mounted on the surface slab of concrete or asphalt, or firmly set in undisturbed soil.

DATA COLLECTION

Prior to any vibration-producing construction activity, the Contractor shall collect seismograph data to document background vibrations at each monitoring location. This monitoring shall consist of a continuous recording of the maximum single-component peak particle velocities for one-minute intervals, which shall be printed on a strip chart. The background monitoring shall be performed for a minimum of two non-consecutive workdays, spanning the hours during which construction activities will take place.

The Contractor shall monitor vibration during construction and other significant vibration-producing activities. This monitoring shall consist of a continuous recording of the maximum single-component peak particle velocities for one-minute intervals, which shall be printed on a strip chart. During the monitoring, the Contractor shall document all events that are responsible for the measured vibration levels, and submit the documentation to the Engineer with the data as specified in section "Data Reduction, Processing, Plotting and Reporting" in these Special Provisions. A record form for documenting these events is included herein as Figure 2.

All vibration monitoring data shall be recorded contemporaneously and plotted continuously on a graph by the data acquisition equipment. Each graph shall show time-domain wave traces (particle velocity versus time) for each transducer with the same vertical and horizontal axes scale.

DATA REDUCTION, PROCESSING, PLOTTING AND REPORTING

Within 10 working days after the completion of the background vibration monitoring, the Contractor shall submit to the Engineer a hard copy report documenting the results at each of the monitoring locations.

During bridge construction, the Contractor shall provide weekly, hard copy reports summarizing any vibration monitoring data collected at the specified vibration-monitoring locations. The reports for each week shall be submitted on or before the end of the following week.

All reports shall be signed by the approved Vibration Instrumentation Engineer, and shall include the following:

1. Project identification, including District, County, Route, Post Mile, Project Name and Bridge number as shown on the project plans.
2. Location of the monitoring equipment, including address of adjacent building.
3. Location of vibration sources (e.g. traffic, construction equipment, etc.)
4. Summary tables indicating the date, time and magnitude and frequency of maximum single-component peak particle velocity measured during each one-hour interval of the monitoring period.
5. Field data forms (construction vibration monitoring only).
6. Appendix graphs of the strip charts printed during the monitoring periods.

In addition to the hard copy data specified herein, the Contractor shall provide data on 3.5-inch diskettes with each report. Electronic data files for all instrument data shall be provided in dBASE IV (.DBF) format.

The Contractor shall not disclose any instrumentation data to third parties and shall not publish data without prior written consent of Caltrans.

PAYMENT

The contract lump sum price paid for vibration monitoring shall include full compensation for furnishing all labor, materials, tools, equipment, and incidentals and for performing all work involving vibration monitoring, as specified in the Standard Specifications and these special provisions, and as directed by the Engineer.

10-1.04 SEWER VIDEO SURVEY

This work shall consist of investigating, sewer cleaning as necessary to facilitate the survey, documenting, and reporting on the structural condition of the existing sewer lines both before and after construction from manhole to manhole at the following locations:

SEWER VIDEO SURVEY LOCATIONS

Otis St. from McCoppin St. to Duboce Ave.
Mission St. from Duboce Ave. to 14th St.
Duboce Ave. from Otis St. to Valencia St.
Valencia St. from Duboce Ave. to McCoppin St.
McCoppin St. from Valencia St. to Market St.
Market St. from Guerrero St. to Valencia St.
South Van Ness Ave. from 13th St. to 14th St.
13th St. from South Van Ness Ave. to Mission St.

The Contractor shall videotape with narration the condition of the sewer to show any and all structural deficiencies including cracks, holes, exposed aggregates and reinforcing bars, honey combed areas, damaged construction joints, deteriorated concrete surfaces, infiltrations, root intrusions and missing pieces. The locations of all deficiencies shall be shown by stationing with reference points agreed upon by the Contractor and the Engineer. The Contractor shall provide the dimensions of all major structural deficiencies and provide supplemental photographs of such deficiencies when requested by the Engineer.

For all the sewer locations as listed above and for all other sewer locations subjected to live loads exceeding AASHTO Standard HS-20, the Contractor shall investigate, document and report the sewer conditions before commencement and after final completion of the project.

At least 10 working days prior to investigation, the Contractor shall submit for acceptance 5 copies of the proposed operations and safety procedure to the Engineer.

The Engineer will either accept or reject such procedures within 5 working days of receipt. Approval will be contingent on such procedures being satisfactory to the City and County of San Francisco. Such procedures must comply with the Safety Procedures Section of this special provision.

The Contractor shall call the general foreman of the City and County of San Francisco Bureau of Street and Sewer Repair two days in advance at (415) 695-2095 for coordination and to gain access to the sewer.

The Contractor shall cooperate with local authorities relative to handling traffic through the area and shall make his own arrangements relative to keeping the working area clear of parked vehicles.

The Contractor shall prepare for the Engineer's approval, a written report documenting the results of his investigation. Approval of the report will be contingent on it being satisfactory to the City and County of San Francisco. In this report, the Contractor shall place emphasis on; first, the deficiencies discovered during the investigation; secondly; the proposed measures to remedy such deficiencies and; thirdly, the serviceability of the present sewer.

The Contractor shall: (a) after the pre-construction sewer investigation, deliver 2 copies of the report and 2 copies of the videotape 5 working days before actual start of construction and; (b) after post-construction sewer investigation, deliver 5 copies of the final report and 2 copies of the post-construction videotape to the Engineer.

The Contractor shall provide air ventilation and respiratory protection to workers and inspectors in accordance with an operation and safety procedures plan required by CAL-OSHA and accepted by the City and County of San Francisco.

The Contractor shall provide a plan for rescue of workers and investigators for review by the Engineer and for approval by the City and County of San Francisco.

The contract lump sum price paid for sewer video survey shall include full compensation for furnishing all labor, materials, tools, equipment, sewer cleaning as necessary to facilitate the survey, and incidentals, and for doing all the work involved in conducting the sewer video survey, including providing plans, reports and video tape, safety devices and precautions, as shown on the plans, as specified in the Standard Specifications and these special provisions, and as directed by the Engineer.

10-1.05 WATER POLLUTION CONTROL

Water pollution control work shall conform to the provisions in Section 7-1.01G, "Water Pollution," of the Standard Specifications and these special provisions.

This project lies within the boundaries of the San Francisco Bay Regional Water Quality Control Board (RWQCB).

The State Water Resources Control Board (SWRCB) has issued a permit to the Department which governs storm water and non-storm water discharges from its properties, facilities and activities. The Department's Permit is entitled: "Order No.

99-06-DWQ, NPDES No. CAS000003, National Pollutant Discharge Elimination System (NPDES) Permit, Storm Water Permit and Waste Discharge Requirements (WDRs) for the State of California, Department of Transportation Properties, Facilities, and Activities." Copies of the Department's Permit are available for review from the SWRCB, Storm Water Permit Unit, 1001 "I" Street, P.O. Box 1977, Sacramento, California 95812-1977, Telephone: (916) 341-5254, and may also be obtained from the SWRCB Internet website at: http://www.swrcb.ca.gov/stormwtr/caltrans.html.

The Department's Permit references and incorporates by reference the current Statewide General Permit issued by the SWRCB entitled "Order No. 99-08-DWQ, National Pollutant Discharge Elimination System (NPDES) General Permit No. CAS000002, Waste Discharge Requirements (WDRs) for Discharges of Storm Water Associated with Construction Activity," which regulates discharges of storm water and non-storm water from construction activities disturbing 0.4-hectare or more of soil in a common plan of development. Sampling and analysis requirements as specified in SWRCB Resolution No. 2001-46 are added to the Statewide General Permit. Copies of the Statewide General Permit and modifications thereto are available for review from the SWRCB, Storm Water Permit Unit, 1001 "I" Street, P.O. Box 1977, Sacramento, California 95812-1977, Telephone: (916) 341-5254 and may also be obtained from the SWRCB Internet website at: http://www.swrcb.ca.gov/stormwtr/construction.html.

The NPDES permit that regulate this project, as referenced above, are hereafter collectively referred to as the "Permits."

This project shall conform to the Permits and modifications thereto. The Contractor shall maintain copies of the Permits at the project site and shall make the Permits available during construction.

The Permits require the preparation of a Storm Water Pollution Prevention Plan (SWPPP). The SWPPP shall be prepared in conformance with the requirements of the Permits, the Department's "Storm Water Pollution Prevention Plan (SWPPP) and Water Pollution Control Program (WPCP) Preparation Manual," and the Department's "Construction Site Best Management Practices (BMPs) Manual," including addenda to those permits and manuals issued up to and including the date of advertisement of the project. These manuals are hereinafter referred to, respectively, as the "Preparation Manual" and the "Construction Site BMPs Manual," and collectively, as the "Manuals." Copies of the Manuals may be obtained from the Department of Transportation, Material Operations Branch, Publication Distribution Unit, 1900 Royal Oaks Drive, Sacramento, California 95815, Telephone: (916) 445-3520, and may also be obtained from the Department's Internet website at: http://www.dot.ca.gov/hq/construc/stormwater/stormwater1.htm.

The Contractor shall know and fully comply with applicable provisions of the Permits and all modifications thereto, the Manuals, and Federal, State, and local regulations and requirements that govern the Contractor's operations and storm water and non-storm water discharges from both the project site and areas of disturbance outside the project limits during construction. Attention is directed to Sections 7-1.01, "Laws to be Observed," and 7-1.12, "Indemnification and Insurance," of the Standard Specifications.

The Permits shall apply to storm water and certain permitted non-storm water discharges from areas outside the project site which are directly related to construction activities for this contract including, but not limited to, asphalt batch plants, material borrow areas, concrete plants, staging areas, storage yards and access roads. The Contractor shall comply with the Permits and the Manuals for those areas and shall implement, inspect and maintain the required water pollution control practices. The Engineer shall be allowed full access to these areas during construction to assure Contractor's proper implementation of water pollution control practices. Installing, inspecting and maintaining water pollution control practices on areas outside the highway right of way not specifically arranged and provided for by the Department for the execution of this contract, will not be paid for.

The Contractor shall be responsible for penalties assessed or levied on the Contractor or the Department as a result of the Contractor's failure to comply with the provisions in this section "Water Pollution Control" including, but not limited to, compliance with the applicable provisions of the Permits, the Manuals, and Federal, State and local regulations and requirements as set forth therein.

Penalties as used in this section, "Water Pollution Control," shall include fines, penalties and damages, whether proposed, assessed, or levied against the Department or the Contractor, including those levied under the Federal Clean Water Act and the State Porter-Cologne Water Quality Control Act, by governmental agencies or as a result of citizen suits. Penalties shall also include payments made or costs incurred in settlement for alleged violations of the Permits, the Manuals, or applicable laws, regulations, or requirements. Costs incurred could include sums spent instead of penalties, in mitigation or to remediate or correct violations.

RETENTION OF FUNDS

Notwithstanding any other remedies authorized by law, the Department may retain money due the Contractor under the contract, in an amount determined by the Department, up to and including the entire amount of Penalties proposed, assessed, or levied as a result of the Contractor's violation of the Permits, the Manuals, or Federal or State law, regulations or requirements. Funds may be retained by the Department until final disposition has been made as to the Penalties. The Contractor shall remain liable for the full amount of Penalties until such time as they are finally resolved with the entity seeking the Penalties.

Retention of funds for failure to conform to the provisions in this section, "Water Pollution Control," shall be in addition to the other retention amounts required by the contract. The amounts retained for the Contractor's failure to conform to provisions in this section will be released for payment on the next monthly estimate for partial payment following the date when an approved SWPPP has been implemented and maintained, and when water pollution has been adequately controlled, as determined by the Engineer.

When a regulatory agency identifies a failure to comply with the Permits and modifications thereto, the Manuals, or other Federal, State or local requirements, the Department may retain money due the Contractor, subject to the following:

A. The Department will give the Contractor 30 days notice of the Department's intention to retain funds from partial payments which may become due to the Contractor prior to acceptance of the contract. Retention of funds from payments made after acceptance of the contract may be made without prior notice to the Contractor.
B. No retention of additional amounts out of partial payments will be made if the amount to be retained does not exceed the amount being withheld from partial payments pursuant to Section 9-1.06, "Partial Payments," of the Standard Specifications.
C. If the Department has retained funds, and it is subsequently determined that the State is not subject to the entire amount of the Costs and Liabilities assessed or proposed in connection with the matter for which the retention was made, the Department shall be liable for interest on the amount retained for the period of the retention. The interest rate payable shall be 6 percent per annum.

During the first estimate period that the Contractor fails to conform to the provisions in this section, "Water Pollution Control," the Department may retain an amount equal to 25 percent of the estimated value of the contract work performed.

The Contractor shall notify the Engineer immediately upon request from the regulatory agencies to enter, inspect, sample, monitor, or otherwise access the project site or the Contractor's records pertaining to water pollution control work. The Contractor and the Department shall provide copies of correspondence, notices of violation, enforcement actions or proposed fines by regulatory agencies to the requesting regulatory agency.

STORM WATER POLLUTION PREVENTION PLAN PREPARATION, APPROVAL AND AMENDMENTS

As part of the water pollution control work, a Storm Water Pollution Prevention Plan (SWPPP) is required for this contract. The SWPPP shall conform to the provisions in Section 7-1.01G, "Water Pollution," of the Standard Specifications, the requirements in the Manuals, the requirements of the Permits, and these special provisions. Upon the Engineer's approval of the SWPPP, the SWPPP shall be considered to fulfill the provisions in Section 7-1.01G, "Water Pollution," of the Standard Specifications for development and submittal of a Water Pollution Control Program.

No work having potential to cause water pollution, shall be performed until the SWPPP has been approved by the Engineer. Approval shall not constitute a finding that the SWPPP complies with applicable requirements of the Permits, the Manuals and applicable Federal, State and local laws, regulations, and requirements.

The Contractor shall designate a Water Pollution Control Manager. The Water Pollution Control Manager shall be responsible for the preparation of the SWPPP and required modifications or amendments, and shall be responsible for the implementation and adequate functioning of the various water pollution control practices employed. The Contractor may designate different Water Pollution Control Managers to prepare the SWPPP and to implement the water pollution control practices. The Water Pollution Control Managers shall serve as the primary contact for issues related to the SWPPP or its implementation. The Contractor shall submit to the Engineer a statement of qualifications, describing the training, previous work history and expertise of the individual selected by the Contractor to serve as Water Pollution Control Manager. The Water Pollution Control Manager shall have a minimum of 24 hours of formal storm water management training or certification as a Certified Professional in Erosion and Sediment Control (CPESC). The Engineer will reject the Contractor's submission of a Water Pollution Control Manager if the submitted qualifications are deemed to be inadequate.

The SWPPP shall apply to the areas within and those outside of the highway right of way that are directly related to construction operations including, but not limited to, asphalt batch plants, material borrow areas, concrete plants, staging areas, storage yards, and access roads.

The SWPPP shall incorporate water pollution control practices in the following categories:

A. Soil stabilization.
B. Sediment control.
C. Wind erosion control.
D. Tracking control.
E. Non-storm water management.
F. Waste management and materials pollution control.

The following contract items of work shall be incorporated into the SWPPP as "Temporary Water Pollution Control Practices": Temporary Drainage Inlet Protection, Temporary Mulch, Temporary Concrete Washout, Temporary Cover and Temporary Construction Entrance. The Contractor's attention is directed to the special provisions provided for Temporary Water Pollution Control Practices.

The SWPPP shall include, but not be limited to, the items described in the Manuals, Permits and related information contained in the contract documents. The SWPPP shall also include a copy of the following: Notice of Construction.

The Contractor shall develop and include in the SWPPP the Sampling and Analysis Plan(s) as required by the Permits, and modifications thereto, and as required in "Sampling and Analytical Requirements" of this section.

The Contractor shall develop a Water Pollution Control Schedule that describes the timing of grading or other work activities that could affect water pollution. The Water Pollution Control Schedule shall be updated by the Contractor to reflect changes in the Contractor's operations that would affect the necessary implementation of water pollution control practices.

The Contractor shall complete the "Construction Site BMPs Consideration Checklist" presented in the Preparation Manual and shall incorporate water pollution control practices into the SWPPP. Water pollution control practices include the "Minimum Requirements" and other Contractor-selected water pollution control practices from the "Construction Site BMPs Consideration Checklist" and the "Project-Specific Minimum Requirements" identified in the Water Pollution Control Cost Break-Down of this section.

Within 20 working days after the approval of the contract, the Contractor shall submit 3 copies of the draft SWPPP to the Engineer. The Engineer will have 10 working days to review the SWPPP. If revisions are required, as determined by the Engineer, the Contractor shall revise and resubmit the SWPPP within 10 working days of receipt of the Engineer's comments. The Engineer will have 5 working days to review the revisions. Upon the Engineer's approval of the SWPPP, 4 approved copies of the SWPPP, incorporating the required changes, shall be submitted to the Engineer. In order to allow construction activities to proceed, the Engineer may conditionally approve the SWPPP while minor revisions are being completed. In the event the Engineer fails to complete the review within the time allowed, and if, in the opinion of the Engineer, completion of the work is delayed or interfered with by reason of the Engineer's delay in completing the review, the Contractor will be compensated for resulting losses, and an extension of time will be granted, in the same manner as provided for in Section 8-1.09, "Right of Way Delays," of the Standard Specifications.

The Contractor shall prepare an amendment to the SWPPP when there is a change in construction activities or operations which may affect the discharge of pollutants to surface waters, ground waters, municipal storm drain systems, or when the Contractor's activities or operations violate a condition of the Permits, or when directed by the Engineer. Amendments shall identify additional water pollution control practices or revised operations, including those areas or operations not identified in the initially approved SWPPP. Amendments to the SWPPP shall be prepared and submitted for review and approval within a time approved by the Engineer, but in no case longer than the time specified for the initial submittal and review of the SWPPP. At a minimum, the SWPPP shall be amended annually and submitted to the Engineer 25 days prior to the defined rainy season.

The Contractor shall keep one copy of the approved SWPPP and approved amendments at the project site. The SWPPP shall be made available upon request by a representative of the Regional Water Quality Control Board, State Water Resources Control Board, United States Environmental Protection Agency, or the local storm water management agency. Requests by the public shall be directed to the Engineer.

COST BREAK-DOWN

The Contractor shall include a Water Pollution Control Cost Break-Down in the SWPPP which itemizes the contract lump sum for water pollution control work. The Contractor shall use the Water Pollution Control Cost Break-Down provided in this section as the basis for the cost break-down submitted with the SWPPP. The Contractor shall use the Water Pollution Control Cost Break-Down to identify items, quantities and values for water pollution control work, excluding Temporary Water Pollution Control Practices for which there are separate bid items. The Contractor shall be responsible for the accuracy of the quantities and values used in the cost break-down submitted with the SWPPP. Partial payment for the item of water pollution control will not be made until the Water Pollution Control Cost Break-Down is approved by the Engineer.

Attention is directed to "Time-Related Overhead" of these special provisions regarding compensation for time-related overhead.

Line items indicated in the Water Pollution Control Cost Break-Down in this section with a specified Estimated Quantity shall be considered "Project-Specific Minimum Requirements." The Contractor shall incorporate Project-Specific Minimum Requirements with Contractor-designated quantities and values into the Water Pollution Control Cost Break-Down submitted with the SWPPP.

Line items indicated in the Water Pollution Control Cost Break-Down in this section without a specified Estimated Quantity shall be considered by the Contractor for selection to meet the applicable "Minimum Requirements" as defined in

the Manuals, or for other water pollution control work as identified in the "Construction Site BMPs Consideration Checklist" presented in the Preparation Manual. In the Water Pollution Control Cost Break-Down submitted with the SWPPP, the Contractor shall list only those water pollution control practices selected for the project, including quantities and values required to complete the work for those items.

The sum of the amounts for the items of work listed in the Water Pollution Control Cost Break-Down shall be equal to the contract lump sum price bid for water pollution control. Overhead and profit shall be included in the individual items listed in the cost break-down.

WATER POLLUTION CONTROL COST BREAK-DOWN

Contract No. 04-291004

ITEM	ITEM DESCRIPTION	UNIT	ESTIMATED QUANTITY	VALUE	AMOUNT
SC-1	Silt Fence	M			
SC-7	Street Sweeping and Vacuuming	LS			
SC-8	Sandbag Barrier	M			
WE-1	Wind Erosion Control	LS			
NS-3	Paving and Grinding Operations	LS			
NS-8	Vehicle and Equipment Cleaning	LS			
NS-9	Vehicle and Equipment Fueling	LS			
NS-10	Vehicle and Equipment Maintenance	LS			
WM-1	Material Delivery and Storage	LS			
WM-2	Material Use	LS			
WM-3	Stockpile Management	LS			
WM-4	Spill Prevention and Control	LS			
WM-5	Solid Waste Management	LS			
WM-6	Hazardous Waste Management	LS			
WM-7	Contaminated Soil Management	LS			
WM-9	Sanitary/Septic Waste Management	LS			

TOTAL _____

Adjustments in the items of work and quantities listed in the approved cost break-down shall be made when required to address amendments to the SWPPP, except when the adjusted items are paid for as extra work.

No adjustment in compensation will be made to the contract lump sum price paid for water pollution control due to differences between the quantities shown in the approved cost break-down and the quantities required to complete the work as shown on the approved SWPPP. No adjustment in compensation will be made for ordered changes to correct SWPPP work resulting from the Contractor's own operations or from the Contractor's negligence.

The approved cost break-down will be used to determine partial payments during the progress of the work and as the basis for calculating the adjustment in compensation for the item of water pollution control due to increases or decreases of quantities ordered by the Engineer. When an ordered change increases or decreases the quantities of an approved cost break-down item, the adjustment in compensation will be determined in the same manner specified for increases and decreases in the quantity of a contract item of work in conformance with the provisions in Section 4-1.03B, "Increased or Decreased Quantities," of the Standard Specifications. If an ordered change requires a new item which is not on the approved cost break-down, the adjustment in compensation will be determined in the same manner specified for extra work in conformance with Section 4-1.03D, "Extra Work," of the Standard Specifications.

If requested by the Contractor and approved by the Engineer, changes to the water pollution control practices listed in the approved cost break-down, including addition of new water pollution control practices, will be allowed. Changes shall be included in the approved amendment of the SWPPP. If the requested changes result in a net cost increase to the lump sum price for water pollution control, an adjustment in compensation will be made without change to the water pollution control item. The net cost increase to the water pollution control item will be paid for as extra work as provided in Section 4-1.03D, "Extra Work," of the Standard Specifications.

SWPPP IMPLEMENTATION

Unless otherwise specified, upon approval of the SWPPP, the Contractor shall be responsible throughout the duration of the project for installing, constructing, inspecting, maintaining, removing, and disposing of the water pollution control practices specified in the SWPPP and in the amendments. Unless otherwise directed by the Engineer, the Contractor's responsibility for SWPPP implementation shall continue throughout temporary suspensions of work ordered in conformance with the provisions in Section 8-1.05, "Temporary Suspension of Work," of the Standard Specifications. Requirements for installation, construction, inspection, maintenance, removal, and disposal of water pollution control practices shall conform to the requirements in the Manuals and these special provisions.

If the Contractor or the Engineer identifies a deficiency in the implementation of the approved SWPPP or amendments, the deficiency shall be corrected immediately unless requested by the Contractor and approved by the Engineer in writing, but shall be corrected prior to the onset of precipitation. If the Contractor fails to correct the identified deficiency by the date agreed or prior to the onset of precipitation, the project shall be in nonconformance with this section, "Water Pollution Control." Attention is directed to Section 5-1.01, "Authority of Engineer," of the Standard Specifications, and to "Retention of Funds" of this section for possible nonconformance penalties.

If the Contractor fails to conform to the provisions of this section, "Water Pollution Control," the Engineer may order the suspension of construction operations until the project complies with the requirements of this section.

Implementation of water pollution control practices may vary by season. The Construction Site BMPs Manual and these special provisions shall be followed for control practice selection of year-round, rainy season and non-rainy season water pollution control practices.

Year-Round Implementation Requirements

The Contractor shall have a year-round program for implementing, inspecting and maintaining water pollution control practices for wind erosion control, tracking control, non-storm water management, and waste management and materials pollution control.

The National Weather Service weather forecast shall be monitored and used by the Contractor on a daily basis. An alternative weather forecast proposed by the Contractor may be used if approved by the Engineer. If precipitation is predicted, the necessary water pollution control practices shall be deployed prior to the onset of the precipitation.

Disturbed soil areas shall be considered active whenever the soil disturbing activities have occurred, continue to occur or will occur during the ensuing 21 days. Non-active areas shall be protected as prescribed in the Construction Site BMPs Manual within 14 days of cessation of soil disturbing activities or prior to the onset of precipitation, whichever occurs first.

In order to provide effective erosion control, the Contractor may be directed by the Engineer to apply permanent erosion control in small or multiple units. The Contractor’s attention is directed to "Fiber Rolls and "Drainage Inlet Protection" of these special provisions.

The Contractor shall implement, maintain and inspect the following temporary sediment control practices on a year-round basis. The listed practices shall remain in place until their use is no longer needed, as determined by the Engineer.

YEAR-ROUND SEDIMENT CONTROL PRACTICES	LOCATION USED
Temporary Drainage Inlet Protection	EC-1
Temporary Mulch	EC-1

Rainy Season Implementation Requirements

Soil stabilization and sediment control practices shall be provided throughout the rainy season, defined as between October 15 and April 15.

An implementation schedule of required soil stabilization and sediment control practices for disturbed soil areas shall be completed no later than 20 days prior to the beginning of each rainy season. The implementation schedule shall identify the soil stabilization and sediment control practices and the dates when the implementation will be 25 percent, 50 percent and 100 percent complete, respectively. For construction activities beginning during the rainy season, the Contractor shall implement applicable soil stabilization and sediment control practices. The Contractor shall implement soil stabilization and sediment control practices a minimum of 10 days prior to the start of the rainy season.

Throughout the defined rainy season, the active disturbed soil area of the project site shall be not more than >0.4 hectares. The Engineer may approve, on a case-by-case basis, expansions of the active disturbed soil area limit. Soil stabilization and sediment control materials shall be maintained on site sufficient to protect disturbed soil areas. A detailed plan for the mobilization of sufficient labor and equipment shall be maintained to deploy the water pollution control practices required to protect disturbed soil areas prior to the onset of precipitation.

Non-Rainy Season Implementation Requirements

The non-rainy season shall be defined as days outside the defined rainy season. The Contractor's attention is directed to the Construction Site BMPs Manual for soil stabilization and sediment control implementation requirements on disturbed soil areas during the non-rainy season. Disturbed soil areas within the project shall be protected in conformance with the requirements in the Construction Site BMPs Manual with an effective combination of soil stabilization and sediment control.

MAINTENANCE

To ensure the proper implementation and functioning of water pollution control practices, the Contractor shall regularly inspect and maintain the construction site for the water pollution control practices identified in the SWPPP. The construction site shall be inspected by the Contractor as follows:

A. Prior to a forecast storm.
B. After a precipitation event which causes site runoff.
C. At 24 hour intervals during extended precipitation events.
D. Routinely, a minimum of once every two weeks outside of the defined rainy season.
E. Routinely, a minimum of once every week during the defined rainy season.

The Contractor shall use the Storm Water Quality Construction Site Inspection Checklist provided in the Preparation Manual or an alternative inspection checklist provided by the Engineer. One copy of each site inspection record shall be submitted to the Engineer within 24 hours of completing the inspection.

REPORTING REQUIREMENTS

Report of Discharges, Notices or Orders

If the Contractor identifies discharges into surface waters or drainage systems in a manner causing, or potentially causing, a condition of pollution, or if the project receives a written notice or order from a regulatory agency, the Contractor shall immediately inform the Engineer. The Contractor shall submit a written report to the Engineer within 7 days of the discharge event, notice or order. The report shall include the following information:

A. The date, time, location, nature of the operation, and type of discharge, including the cause or nature of the notice or order.

B. The water pollution control practices deployed before the discharge event, or prior to receiving the notice or order.
C. The date of deployment and type of water pollution control practices deployed after the discharge event, or after receiving the notice or order, including additional measures installed or planned to reduce or prevent reoccurrence.
D. An implementation and maintenance schedule for affected water pollution control practices.

Report of First-Time Non-Storm Water Discharge

The Contractor shall notify the Engineer at least 3 days in advance of first-time non-storm water discharge events, excluding exempted discharges. The Contractor shall notify the Engineer of the operations causing non-storm water discharges and shall obtain field approval for first-time non-storm water discharges. Non-storm water discharges shall be monitored at first-time occurrences and routinely thereafter.

Annual Certifications

By June 15 of each year, the Contractor shall complete and submit an Annual Certification of Compliance, as contained in the Preparation Manual, to the Engineer.

SAMPLING AND ANALYTICAL REQUIREMENTS

The Contractor is required to implement specific sampling and analytical procedures to determine whether BMPs implemented on the construction site are:

A. preventing pollutants that are known or should be known by permittees to occur on construction sites that are not visually detectable in storm water discharges, to cause or contribute to exceedances of water quality objectives, and
B. preventing further impairment by sediment in storm waters discharged into water bodies listed as impaired due to sediment, siltation or turbidity.

Non-Visible Pollutants

The project has the potential to discharge non-visible pollutants in storm water from the construction site. The project SWPPP shall contain a Sampling and Analysis Plan (SAP) that describes the sampling and analysis strategy and schedule to be implemented on the project for monitoring non-visible pollutants in conformance with this section.

The SAP shall identify potential non-visible pollutants that are known or should be known to occur on the construction site associated with the following: (1) construction materials, wastes or operations; (2) known existing contamination due to historical site usage; or (3) application of soil amendments, including soil stabilization products, with the potential to alter pH or contribute toxic pollutants to storm water. Planned material and waste storage areas, locations of known existing contamination, and areas planned for application of soil amendments shall be shown on the SWPPP Water Pollution Control Drawings.

The SAP shall identify a sampling schedule for collecting a sample down gradient from the applicable non-visible pollutant source and a sufficiently large uncontaminated control sample during the first two hours of discharge from rain events during daylight hours which result in a sufficient discharge for sample collection. If run-on occurs onto the non-visible pollutant source, a run-on sample that is immediately down gradient of the run-on to the Department's right of way shall be collected. A minimum of 72 hours of dry weather shall occur between rain events to distinguish separate rain events.

The SAP shall state that water quality sampling will be triggered when any of the following conditions are observed during the required storm water inspections conducted before or during a rain event:

A. Materials or wastes containing potential non-visible pollutants are not stored under watertight conditions.
B. Materials or wastes containing potential non-visible pollutants are stored under watertight conditions, but (1) a breach, leakage, malfunction, or spill is observed; and (2) the leak or spill has not been cleaned up prior to the rain event; and (3) there is the potential for discharge of non-visible pollutants to surface waters or drainage system.
C. Construction activities, such as application of fertilizer, pesticide, herbicide, methyl methacrylate concrete sealant, or non-pigmented curing compound have occurred during a rain event or within 24 hours preceding a rain event, and there is the potential for discharge of pollutants to surface waters or drainage system.
D. Soil amendments, including soil stabilization products, with the potential to alter pH levels or contribute toxic pollutants to storm water runoff have been applied, and there is the potential for discharge of pollutants to surface waters or drainage system (unless independent test data are available that demonstrate acceptable concentration levels of non-visible pollutants in the soil amendment).
E. Storm water runoff from an area contaminated by historical usage of the site is observed to combine with storm water, and there is the potential for discharge of pollutants to surface waters or drainage system.

The SAP shall identify sampling locations for collecting down gradient and control samples, and the rationale for their selection. The control sampling location shall be selected where the sample does not come into contact with materials, wastes or areas associated with potential non-visible pollutants or disturbed soil areas. Sampling locations shall be shown on the SWPPP Water Pollution Control Drawings. Only trained personnel shall collect water quality samples and be identified in the SAP. Qualifications of designated sampling personnel shall describe training and experience, and shall be included in the SWPPP. The SAP shall state monitoring preparation, sample collection procedures, quality assurance/quality control, sample labeling procedures, sample collection documentation, sample shipping and chain of custody procedures, sample numbering system, and reference the construction site health and safety plan.

The SAP shall identify the analytical method to be used for analyzing down gradient and control samples for potential non-visible pollutants on the project. For samples analyzed in the field by sampling personnel, collection, analysis, and equipment calibration shall be in conformance with the Manufacturer's specifications. For samples that will be analyzed by a laboratory, sampling, preservation, and analysis shall be performed by a State-certified laboratory in conformance with 40 CFR 136. The SAP shall identify the specific State-certified laboratory, sample containers, preservation requirements, holding times, and analysis method to be used. A list of State-certified laboratories that are approved by the Department is available at the following internet site: http://www.dhs.ca.gov/ps/ls/elap/html/lablist_county.htm.

Analytical Results and Evaluation

The Contractor shall submit a hard copy and electronic copy of water quality analytical results and quality assurance/quality control data to the Engineer within 5 days of sampling for field analyses and within 30 days for laboratory analyses. Analytical results shall be accompanied by an evaluation from the Contractor to determine if down gradient samples show elevated levels of the tested parameter relative to levels in the control sample. If down gradient or downstream samples, as applicable, show increased levels, the Contractor will assess the BMPs, site conditions, and surrounding influences to determine the probable cause for the increase. As determined by the assessment, the Contractor will repair or modify BMPs to address increases and amend the SWPPP as necessary. Electronic results (in one of the following file formats: .xls, .txt, .csv, .dbs, or .mdb) shall have at a minimum the following information: sample identification number, contract number, constituent, reported value, method reference, method detection limit, and reported detection limit. The Contractor shall document sample collection during rain events.

Water quality sampling documentation and analytical results shall be maintained with the SWPPP on the project site until a Notice of Completion has been submitted and approved.

If construction activities or knowledge of site conditions change, such that discharges or sampling locations change, the Contractor shall amend the SAP in conformance with this section, "Water Pollution Control."

PAYMENT

The contract lump sum price paid for prepare storm water pollution prevention plan shall include full compensation for furnishing all labor, materials, tools, equipment, and incidentals for doing all the work involved in developing, preparing, obtaining approval of, revising, and amending the SWPPP, as specified in the Standard Specifications and these special provisions, and as directed by the Engineer.

Attention is directed to Section 9-1.06, "Partial Payments," and Section 9-1.07, "Payment After Acceptance," of the Standard Specifications. Payments for prepare storm water pollution prevention plan will be made as follows:

A. After the SWPPP has been approved by the Engineer, 75 percent of the contract item price for prepare storm water pollution prevention plan will be included in the monthly partial payment estimate.
B. After acceptance of the contract in conformance with the provisions in Section 7-1.17, "Acceptance of Contract," of the Standard Specifications, payment for the remaining 25 percent of the contract item price for prepare storm water pollution prevention plan will be made in conformance with the provisions in Section 9-1.07.

The contract lump sum price paid for water pollution control shall include full compensation for furnishing all labor, materials, tools, equipment, and incidentals, and for doing all the work involved in installing, constructing, removing, and disposing of water pollution control practices, including non-storm water management, and waste management and materials pollution water pollution control practices, except those for which there is a contract item of work as specified in the Standard Specifications and these special provisions, and as directed by the Engineer.

Storm water sampling and analysis will be paid for as extra work as provided in Section 4-1.03D, "Extra Work," of the Standard Specifications. No payment will be made for the preparation, collection, analysis, and reporting of storm water samples required where appropriate BMPs are not implemented prior to a rain event, or if a failure of a BMP is not corrected prior to a rain event.

For items identified on the approved Water Pollution Control Cost Break-Down, the cost of maintaining the temporary water pollution control practices shall be divided equally by the State and the Contractor as follows:

Soil Stabilization

Temporary water pollution control practices except:
SS-1 Scheduling
SS-2 Preservation of Existing Vegetation

Sediment Control

Temporary water pollution control practices except:
SC-7 Street Sweeping and Vacuuming

Wind Erosion Control

No sharing of maintenance costs will be allowed.

Tracking Control

TC-1 Stabilized Construction Entrance/Exit.

Non-Storm Water Management

No sharing of maintenance costs will be allowed.

Waste Management & Materials Pollution Control

No sharing of maintenance costs will be allowed.

The division of cost will be made by determining the cost of maintaining water pollution control practices in conformance with the provisions in Section 9-1.03, "Force Account Payment," of the Standard Specifications and paying to the Contractor one-half of that cost. Cleanup, repair, removal, disposal, improper installation, and replacement of water pollution control practices damaged by the Contractor's negligence, shall not be considered as included in the cost for performing maintenance.

The provisions for sharing maintenance costs shall not relieve the Contractor from the responsibility for providing appropriate maintenance on items with no shared maintenance costs.

Full compensation for non-shared maintenance costs of water pollution control practices, as specified in this section, "Water Pollution Control," shall be considered as included in the contract lump sum price paid for water pollution control and no additional compensation will be allowed therefor.

Water pollution control practices for which there is a contract item of work, will be measured and paid for as that contract item of work.

10-1.06 TEMPORARY MULCH

Temporary mulch shall conform to the provisions for mulch in Section 20-4, "Highway Planting," of the Standard Specifications and these special provisions.

Temporary mulch shall consist of applying mulch at the rate specified herein to excavation slopes, embankment slopes and other areas shown on the plans. Temporary mulch shall extend to the edge of retaining walls, dikes and paving, and to within 1.2 m of the flow line of unpaved drainage ditches.

Attention is directed to "Water Pollution Control" of these special provisions.

MATERIALS

Materials shall conform to the provisions in Section 20-2, "Materials," of the Standard Specifications and the following:

Mulch

Mulch shall be woody material consisting of chipped, shredded or ground green materials such as shrubs, tree trimmings or clean processed wood products. Deleterious materials such as rocks, glass, plastics, metals, clods, weeds, weed seeds, coarse objects, sticks larger than the specified particle size, salts, paint, petroleum products, pesticides or other chemical residues that would be harmful to plant or animal life shall not exceed 0.1 percent of the mulch by volume. Chipping shall include shredding, grinding or any other method used to reduce mulch materials to the specified size. At least 85 percent of the mulch, by volume, shall conform to either the particle size specified for wood chips or to the particle size specified for

shredded bark in Section 20-2.08, "Mulch," of the Standard Specifications. Materials shall be composted and have reached an internal temperature of 56°C for a minimum of 15 consecutive days. During the composting process the compost shall have been turned a minimum of 5 times.

APPLICATION

Temporary mulch shall be applied as follows:

A. Mulch shall be applied at a uniform depth of 75 mm.

MEASUREMENT AND PAYMENT

Temporary mulch will be measured and paid for by the cubic meter in the same manner specified for mulch in Section 20-4.09, "Measurement," and Section 20-4.10, "Payment," of the Standard Specifications.

Temporary mulch placed at locations other than as shown on the project plans or directed by the Engineer, in conformance with the Contractor's Storm Water Pollution Prevention Plan, will not be measured and will be paid for as specified in "Water Pollution Control" of these special provisions.

No adjustment of compensation will be made for any increase or decrease in the quantities of temporary mulch required, regardless of the reason for the increase or decrease. The provisions in Section 4-1.03B, "Increased or Decreased Quantities," of the Standard Specifications shall not apply to temporary mulch.

10-1.07 TEMPORARY COVER

Temporary cover shall be furnished, installed, maintained, and later removed in conformance with the details as shown on the plans, as specified in these special provisions and as directed by the Engineer.

Attention is directed to "Water Pollution Control" of these special provisions. Temporary cover is used as a temporary soil stabilization control. Temporary cover used to cover materials other than exposed soil shall not be allowed unless approved in advance by the Engineer.

The Contractor shall use temporary cover as one of the various measures to prevent water pollution. The Storm Water Pollution Prevention Plan shall include the use of temporary cover.

MATERIALS

Temporary Cover Fabric

Temporary cover fabric shall be either a geomembrane (plastic sheeting) or a geotextile (engineering fabric) conforming to one of the following requirements:

A. Geotextile shall be a woven, slit film fabric which is also known as woven tape. The fabric shall be non-biodegradable, resistant to deterioration by sunlight, and inert to most soil chemicals. Edges of the film fabric shall be selvage or serge to prevent unraveling. The film fabric shall also conform to the following requirements:

Specification	Requirements
Grab tensile strength (25-mm grip), kilonewtons, minimum ASTM Designation: D4632*	0.89
Elongation at break, percent, minimum ASTM Designation: D4632*	15
Toughness, kilonewtons, minimum (percent elongation x grab tensile strength)	13.3
Permittivity, 1/sec, maximum, (liters per minute per square meter) ASTM Designation: D 4491	0.08 (244)
Ultraviolet light stability, percent tensile strength retained after 500 hours, minimum ASTM Designation: D 4355 (xenon arc lamp method)	70

* or appropriate test method for specific polymer

B. Geomembrane shall consist of 0.25-mm thick, single-ply material in conformance with the requirements in ASTM Designation: D 5199.

Temporary cover fabric shall be manufactured from polyethelene or polypropylene, or comparable polymers. The polymer materials may be virgin, recycled, or a combination of virgin and recycled materials. The polymer materials shall

not contain biodegradable filler materials that can degrade the physical or chemical characteristics of the finished fabric. The Engineer may order tests to confirm the absence of biodegradable filler materials in conformance with the requirements in ASTM Designation: E 204 (Fourier Transformed Infrared Spectroscopy-FTIR).

Restrainers

Restrainers for securing the temporary cover fabric on slopes and stockpiles shall consist of one or a combination of the following:

A. Gravel-filled bags used as restrainers shall be knotted, roped, and placed at a maximum of 2 m apart on the temporary cover fabric as shown on the plans. Gravel-filled bags shall be between 13 kg and 22 kg in mass, between 600 mm and 800 mm in length, and between 400 mm and 500 mm in width. Gravel bag fabric shall be non-woven polypropylene geotextile with a minimum unit weight of 235 g/m^2. The fabric shall have a minimum grab tensile strength (25-mm grip) of 0.89-kN in conformance with the requirements in ASTM Designation: D 4632, and an ultraviolet (UV) stability of 70 percent tensile strength retained after 500 hours in conformance to the requirements in ASTM Designation: D 4355, xenon arc lamp method. Gravel shall consist of non-cohesive material between 5 mm and 75 mm in diameter, free of clay balls, organic matter, and other deleterious material. The openings of filled gravel bags shall be secured to prevent escape of gravel.
B. Restrainers consisting of a steel anchor with a wooden lath shall be fabricated and placed as shown on the plans. Wooden lath shall conform to the provisions in Section 20-2.12, "Lumber," of the Standard Specifications and shall be fir or pine, 38 mm x 89 mm in size, and 2.4 m in length. The wooden lath shall be secured to the temporary cover with steel anchors placed 1.2 m apart along the lath.

The Contractor may use an alternative restrainer if approved by the Engineer in writing. The Contractor shall submit details for an alternative restrainer to the Engineer prior to installation. The alternative restrainer shall be installed and maintained in conformance with these special provisions.

INSTALLATION

Temporary cover shall be installed as follows:

A. Temporary cover fabric shall be placed and anchored as shown on the plans.
B. Abutting edges of the temporary cover fabric shall overlap a minimum of 0.6-m. Non-abutting edges shall be embedded in the soil a minimum of 150 mm.
C. Restrainers shall be placed at the overlap area and along the toe of the slope. Restrainers outside the overlap areas shall be placed at a maximum spacing of 2.4 m.
D. Steel anchors shall be installed to allow the leg of the steel anchor to pierce through the temporary cover fabric into the slope with the crown section securing the wooden lath firmly against the slope.
E. Earthen berm, a linear sediment barrier, shall be constructed adjacent to the toe of the slope with a minimum height of 200 mm and a minimum width of 940 mm. The earthen berms shall be hand or mechanically compacted. Alternative linear sediment barrier may be used at the Contractor's expense if approved by the Engineer in writing.

If the Contractor removes the temporary cover in order to facilitate other work, the temporary cover shall be replaced and secured by the Contractor at the Contractor's expense.

When no longer required as determined by the Engineer, temporary cover shall be removed and disposed of in conformance with the provisions in Section 7-1.13, "Disposal of Material Outside the Highway Right of Way" of the Standard Specifications.

MAINTENANCE

The Contractor shall maintain the temporary cover throughout the contract to prevent displacement or migration of the material on the slope or stockpiled.

Temporary cover shall be maintained to minimize exposure of the protected area. Restrainers shall be relocated and secured as needed to restrain the temporary cover fabric in place. Temporary cover that breaks free shall be immediately secured. Holes, tears, and voids in the temporary cover fabric shall be patched, repaired, or replaced. When patches or repairs are unacceptable as determined by the Engineer, the temporary cover shall be replaced.

MEASUREMENT AND PAYMENT

Temporary cover will be measured by the square meter along the slope.

The contract price paid per square meter for temporary cover shall include full compensation for furnishing all labor, materials, tools, equipment, and incidentals, and for doing all the work involved in placing, maintaining, and removing the temporary cover, complete in place, as shown on the plans, as specified in the Standard Specifications and these special provisions, and as directed by the Engineer.

The cost of maintaining the temporary cover will be borne equally by the State and the Contractor.

The division of cost will be made by determining the cost of maintaining temporary cover in conformance with the provisions in Section 9-1.03, "Force Account Payment," of the Standard Specifications and paying to the Contractor one-half of that cost. Clean-up, repair, removal, disposal, replacement because of improper installation, and replacement of temporary cover damaged as a result of the Contractor's negligence will not be considered as included in the cost for performing maintenance.

10-1.08 TEMPORARY CONCRETE WASHOUT FACILITY

Temporary concrete washout facilities shall be constructed, maintained, and later removed in conformance with the details as shown on the plans, as specified in these special provisions and as directed by the Engineer.

Attention is directed to "Water Pollution Control" of these special provisions.

Temporary concrete washout facilities shall be used as one of the various measures to prevent water pollution. The Storm Water Pollution Prevention Plan shall include the use of temporary concrete washout facilities.

MATERIALS

Plastic Liner

Plastic liner shall be single ply, new polyethylene sheeting, a minimum of 0.25-mm thick and shall be free of holes, punctures, tears or other defects that compromise the impermeability of the material. Plastic liner shall not have seams or overlapping joints.

Gravel-filled Bags

Gravel-filled bag fabric shall be non-woven polypropylene geotextile (or comparable polymer), with a minimum unit weight of 235 g/m^2. The fabric shall have a minimum grab tensile strength of 0.89-kilonewtons in conformance to the requirements in ASTM Designation: D 4632, 25-mm grip, and an ultraviolet (UV) stability of 70 percent tensile strength retained after 500 hours in conformance to the requirements in ASTM Designation: D 4355, xenon arc lamp method.

Gravel-filled bags shall be between 600 mm and 800 mm in length, and between 400 mm and 500 mm in width.

Gravel shall be between 5 mm and 75 mm in diameter, and shall be clean and free from clay balls, organic matter, and other deleterious materials. The opening of gravel-filled bags shall be secured such that gravel does not escape. Gravel-filled bags shall be between 13 kg and 22 kg in mass.

Straw Bales

Straw for straw bales shall conform to the provisions in Section 20-2.06, "Straw," of the Standard Specifications.

Straw bales shall be a minimum of 360 mm in width, 450 mm in height, 900 mm in length and shall have a minimum mass of 23 kg. The straw bale shall be composed entirely of vegetative matter, except for binding material.

Straw bales shall be bound by either wire, nylon or polypropylene string. Jute or cotton binding shall not be used. Wire shall be a minimum 1.57 mm (16-gage) baling wire. Nylon or polypropylene string shall be approximately 2 mm in diameter with 360 N of breaking strength.

Stakes

Stakes shall be 50 mm x 50 mm wood posts. Metal stakes may be used as an alternative, and shall be a minimum 13 mm in diameter. Stakes shall be a minimum 1200 mm in length. The tops of the metal stakes shall be bent at a 90-degree angle or capped with an orange or red plastic safety cap that fits snugly to the metal stake. The Contractor shall submit a sample of the metal stake and plastic cap, if used, to the Engineer prior to installation.

Staples

Staples shall be as shown on the plans.

Signs

Signs shall be constructed as shown on the plans. Wood posts shall conform to the provisions in Section 56-2.02B, "Wood Posts," of the Standard Specifications. Lag screws shall conform to the provisions in Section 56-2.02D, "Sign Panel Fastening Hardware," of the Standard Specifications.

Plywood shall be freshly painted for each installation with not less than 2 applications of flat white paint. Sign letters shown on the plans shall be stenciled with commercial quality exterior black paint. Testing of paint will not be required.

INSTALLATION

Temporary concrete washout facilities shall be installed on grade or below grade as shown on the plans and as follows:

A. Temporary concrete washout facilities shall be installed prior to beginning placement of concrete and located a minimum of 15 m from storm drain inlets, open drainage facilities, and water courses unless determined infeasible by the Engineer. Temporary concrete washout facilities shall be located away from construction traffic or access areas at a location determined by the Contractor and approved by the Engineer.
B. A sign shall be installed adjacent to each washout facility at a location determined by the Contractor and approved by the Engineer. Signs shall be installed in conformance with the provisions in Section 56-2.03, "Construction," and Section 56-2.04, "Sign Panel Installation," of the Standard Specifications and as shown on the plans.
C. The length and width of a temporary concrete washout facility may be increased from the minimum dimensions shown on the plans, at the Contractor's expense and upon approval of the Engineer.
D. Temporary concrete washout facilities shall be constructed in sufficient quantity and size to contain all liquid and concrete waste generated by washout operations for all concrete wastes. These facilities shall be constructed to contain all liquid and concrete waste without seepage, spillage or overflow.
E. Berms for below grade temporary concrete washout facilities shall be constructed from compacted native material. Gravel may be used in conjunction with compacted native material
F. Plastic liner shall be required in below grade temporary concrete washout facilities. No additional compensation will be allowed for the use of plastic liner in below grade temporary concrete washout facilities.

The Contractor may use an alternative temporary concrete washout facility if approved by the Engineer in writing. The Contractor shall submit details for an alternative temporary concrete washout facility to the Engineer at least 7 days prior to installation. Any increase in cost, including maintenance costs, for the alternative temporary concrete washout facility shall be borne by the Contractor. The alternative temporary concrete washout facility shall be installed and maintained in conformance with these special provisions.

When temporary concrete washout facilities are no longer required for the work, as determined by the Engineer, the hardened concrete and liquid residue shall be removed and disposed of in conformance with the provisions in Section 15-3.02, "Removal Methods," of the Standard Specifications. Material used to construct temporary concrete washout facilities shall become the property of the Contractor, shall be removed from the site of the work, and shall be disposed of in conformance with the provisions in Section 7-1.13, "Disposal of Material Outside the Highway Right of Way," of the Standard Specifications.

Holes, depressions or other ground disturbance caused by the installation and removal of the temporary concrete washout facilities shall be backfilled and repaired in conformance with the provisions in Section 15-1.02, "Preservation of Property," of the Standard Specifications.

MAINTENANCE

Temporary concrete washout facilities shall be maintained to provide adequate holding capacity with a minimum freeboard of 300 mm. Maintaining temporary concrete washout facilities shall include removing and disposing of hardened concrete and returning the facilities to a functional condition. Hardened concrete materials shall be removed and disposed of in conformance with the provisions in Section 15-3.02, "Removal Methods," of the Standard Specifications. Holes, rips, and voids in the plastic liner shall be patched and repaired by taping or the plastic liner shall be replaced. Plastic liner shall be replaced when patches or repairs compromise the impermeability of the material as determined by the Engineer.

MEASUREMENT AND PAYMENT

The contract unit price paid for temporary concrete washout facilities shall include full compensation for furnishing all labor, materials, tools, equipment and incidentals, and for doing all the work involved in constructing temporary concrete washout facilities, complete in place, including maintenance, removal of materials, and backfilling and repairing holes, depressions and other ground disturbance, as shown on the plans, as specified in the Standard Specifications and these special provisions, and as directed by the Engineer.

10-1.09 TEMPORARY FENCE

Temporary fence shall be furnished, constructed, maintained, and later removed as shown on the plans, as specified in these special provisions and as directed by the Engineer.

Except as otherwise specified in this section, temporary fence shall conform to the plan details and the specifications for permanent fence of similar character as provided in Section 80, "Fences," of the Standard Specifications.

Used materials may be installed provided the used materials are good, sound and are suitable for the purpose intended, as determined by the Engineer.

Materials may be commercial quality provided the dimensions and sizes of the materials are equal to, or greater than, the dimensions and sizes shown on the plans or specified herein.

Posts shall be metal.

Galvanizing and painting of steel items will not be required.

Concrete footings for metal posts will not be required.

Temporary fence that is damaged during the progress of the work shall be repaired or replaced by the Contractor at the Contractor's expense.

When no longer required for the work, as determined by the Engineer, temporary fence shall be removed. Removed facilities shall become the property of the Contractor and shall be removed from the site of the work, except as otherwise provided in this section.

Holes caused by the removal of temporary fence shall be backfilled in conformance with the provisions in the second paragraph of Section 15-1.02, "Preservation of Property," of the Standard Specifications.

The temporary fence (Type CL-1.8) will be measured and paid for in the same manner specified for permanent fence of similar character as provided in Section 80, "Fences," of the Standard Specifications.

Full compensation for maintaining, removing, and disposing of temporary fence (Type CL-1.8) shall be considered as included in the contract prices paid per meter for temporary fence (Type CL-1.8) and no additional compensation will be allowed therefor.

10-1.10 PRESERVATION OF PROPERTY

Attention is directed to Section 7-1.11, "Preservation of Property," of the Standard Specifications and these special provisions.

Existing trees that are not to be removed as shown on the plans or specified in these special provisions, and are injured or damaged by reason of the Contractor's operations, shall be replaced by the Contractor. The minimum size of tree replacement shall be No. 15 container. Replacement planting shall conform to the requirements in Section 20-4.07, "Replacement," of the Standard Specifications. The Contractor shall water replacement plants in conformance with the provisions in Section 20-4.06, "Watering," of the Standard Specifications.

Damaged or injured plants shall be removed and disposed of outside the highway right of way in conformance with the provisions in Section 7-l.13 of the Standard Specifications. At the option of the Contractor, removed trees and shrubs may be reduced to chips. The chipped material shall be spread within the highway right of way at locations designated by the Engineer.

Replacement planting of injured or damaged trees, shrubs, and other plants shall be completed prior to the start of the plant establishment period. Replacement planting shall conform to the provisions in Section 20-4.05, "Planting," of the Standard Specifications.

10-1.11 TEMPORARY CONSTRUCTION ENTRANCE

Temporary construction entrance shall be constructed, maintained, and later removed in conformance with the details as shown on the plans, as specified in these special provisions and as directed by the Engineer.

Attention is directed to "Water Pollution Control" of these special provisions. Temporary construction entrance is used as a temporary sediment tracking control.

The Contractor shall use temporary construction entrance as one of the various measures to prevent water pollution. The Storm Water Pollution Prevention Plan shall include the use of temporary construction entrance.

At the option of the Contractor, temporary construction entrance shall be either Type 1 or Type 2.

MATERIALS

Temporary Entrance Fabric

Temporary entrance fabric shall be manufactured from polyester, nylon or polypropylene material or any combination thereof. Temporary entrance fabric shall be a nonwoven, needle-punched fabric, free of any needles which may have broken off during the manufacturing process. Temporary entrance fabric shall be permeable and shall not act as a wicking agent.

Temporary entrance fabric shall be manufactured from virgin or recycled, or a combination of virgin and recycled, polymer materials. No virgin or recycled materials shall contain biodegradable filler materials that can degrade the physical or chemical characteristics of the finished fabric. The Engineer may order tests to confirm the absence of biodegradable

filler materials in conformance to the requirements in ASTM Designation: E 204 (Fourier Transformed Infrared Spectroscopy-FTIR).

Temporary entrance fabric shall conform to the following requirements:

Specification	Requirements
Mass per unit area, grams per square meter, minimum ASTM Designation: D 5261	235
Grab tensile strength (25-mm grip), kilonewtons, minimum ASTM Designation: D4632*	0.89
Elongation at break, percent, minimum, ASTM Designation: D4632*	50
Toughness, kilonewtons, minimum (percent elongation x grab tensile strength)	53

* or appropriate test method for specific polymer

Rocks

Rocks shall be angular to subangular in shape, and shall conform to the material quality requirements in Section 72-2.02, "Materials," of the Standard Specifications for apparent specific gravity, absorption, and durability index. Rocks used for the temporary entrance shall conform to the following sizes:

Square Screen Size (mm)	Percentage Passing
150	100
75	0-20

Corrugated Steel Panels

Corrugated steel panels shall be prefabricated and shall be pressed or shop welded as shown on the plans, with a slot or hooked section to facilitate coupling at the ends of the panels.

INSTALLATION

Temporary construction entrance shall be installed as follows:

A. Prior to placing the temporary entrance fabric, the areas shall be cleared of all trash and debris. Vegetation shall be removed to the ground level. Trash, debris, and removed vegetation shall be disposed of in conformance with the provisions in Section 7-1.13, "Disposal of Material Outside the Highway Right of Way", of the Standard Specifications.
B. A sump shall be constructed within 6 m of each temporary construction entrance as shown on the plans. The exact location of the sump will be determined by the Engineer.
C. Before placing the temporary entrance fabric, the ground shall be graded to a uniform plane. The relative compaction of the top 0.5-m shall be not less than 90 percent. The ground surface shall be free of sharp objects that may damage the temporary entrance fabric, and shall be graded to drain to the sump as shown on the plans.
D. Temporary entrance fabric shall be positioned longitudinally along the alignment of the entrance, as directed by the Engineer.
E. The adjacent ends of the fabric shall be overlapped a minimum length of 300 mm.
F. Rocks to be placed directly over the fabric shall be spread in the direction of traffic, longitudinally and along the alignment of the temporary construction entrance.
G. During spreading of the rocks, vehicles or equipment shall not be driven directly on the fabric. A layer of rocks of minimum 150 mm thick shall be placed between the fabric and the spreading equipment to prevent damage to the fabric.
H. For Type 2 temporary construction entrance, a minimum of 6 coupled panel sections shall be installed for each temporary construction entrance. Prior to installing the panels, the ground surface shall be cleared of all debris to ensure uniform contact with the ground surface.

Fabric damaged during rock placement shall be repaired by placing a new piece of fabric over the damaged area. The piece of fabric shall be large enough to cover the damaged area and provide a minimum 450-mm overlap on all edges.

The Contractor may use an alternative temporary construction entrance if approved by the Engineer in writing. The Contractor shall submit details for an alternative temporary construction entrance to the Engineer at least 7 days prior to

installation. The alternative temporary construction entrance shall be installed and maintained in conformance with these special provisions.

If buildup of soil and sediment deter the function of the temporary construction entrance, the Contractor shall immediately remove and dispose of the soil and sediment, and install additional corrugated steel panels and spread additional rocks to increase the capacity of the temporary construction entrance at the Contractor's expenses.

When the temporary construction entrances are no longer required, rocks, temporary entrance fabric, soil and collected sediment shall be removed and disposed of in conformance with the provisions in Section 7-1.13, "Disposal of Material Outside the Highway Right of Way," of the Standard Specifications. Corrugated steel panels used in the construction of temporary construction entrance shall become the property of the Contractor.

Holes, depressions or other ground disturbance caused by the removal of the temporary construction entrance, including the sumps, shall be backfilled and repaired in conformance with the provisions in Section 15-1.02, "Preservation of Property," of the Standard Specifications.

While the temporary construction entrance are in use, pavement shall be cleaned and sediment removed at least once a day, and as often as necessary when directed by the Engineer. Soil and sediment or other extraneous material tracked onto existing pavement shall not be allowed to enter drainage facilities.

MAINTENANCE

The Contractor shall maintain temporary construction entrance throughout the contract or until removed. The Contractor shall prevent displacement or migration of the rock surfacing or corrugated steel panels. Any significant depressions resulted from settlement or heavy equipment shall be repaired by the Contractor, as directed by the Engineer.

Temporary construction entrance shall be maintained to minimize tracking of soil and sediment onto existing public roads.

MEASUREMENT AND PAYMENT

The quantity of temporary construction entrance will be measured and paid for as units determined from actual count in place.

The contract unit price paid for temporary construction entrance shall include full compensation for furnishing all labor, materials, tools, equipment, and incidentals, and for doing all the work involved in constructing, maintaining, and removing the temporary construction entrance, complete in place, as shown on the plans, as specified in the Standard Specifications and these special provisions, and as directed by the Engineer.

The cost of maintaining the temporary construction entrance will be borne equally by the State and the Contractor.

The division of cost will be made by determining the cost of maintaining temporary construction entrance in conformance with the provisions in Section 9-1.03, "Force Account Payment," of the Standard Specifications and paying to the Contractor one-half of that cost. Clean-up, repair, removal, disposal, replacement because of improper installation, and replacement of temporary construction entrance damaged as a result of the Contractor's negligence will not be considered as included in the cost for performing maintenance.

10-1.12 TEMPORARY DRAINAGE INLET PROTECTION

Temporary drainage inlet protection shall be installed, maintained and later removed as shown on the plans, as specified in these special provisions, and as directed by the Engineer.

The Contractor shall select the appropriate drainage inlet protection shown on the plans to meet the field condition around the drainage inlet. For all other drainage inlets within the project limits that do not conform to the details shown on the plans, the Contractor shall submit to the Engineer for approval, provisions for providing temporary drainage inlet protection.

Special attention shall be given to existing and new drainage inlets adjacent to traffic. The Engineer shall review the need for drainage inlet protection at each location. Each proposed drainage inlet protection shall be approved by the Engineer to ensure safety.

Temporary drainage inlet protection types 2a and 4 shall have a continuous physical barrier separating the drainage inlet from traffic. Temporary drainage inlet protection types 2b and 3 do not require a barrier installed between the drainage inlet and traffic.

Throughout the duration of the Contract, the Contractor shall be required to provide protection to meet with the changing condition of the drainage inlet. It is recognized that the drainage inlet changes during the course of construction and the actual protection provided may require selecting the appropriate type or types of drainage inlet protection as it changes during the course of construction.

Some conditions may require combining materials outlined in the special provision to address conditions that cannot be anticipated in advance. The Contractor shall submit temporary drainage inlet protection drawings for such cases to the Engineer for approval prior to installation.

The Contractor shall use temporary drainage inlet protection as one of the various measures to prevent water pollution. The Storm Water Pollution Prevention Plan shall graphically show the use of temporary drainage inlet protection in relation to other water pollution control work specified elsewhere in these special provisions.

MATERIALS

Materials shall conform to the provisions in Section 20-2, "Materials," of the Standard Specifications and these special provisions.

A. SILT FENCE.—Sedimentation control fabric for temporary silt fence shall be a prefabricated silt fence with a minimum woven polypropylene fabric width of 900 mm and a minimum tensile strength of 0.44-kN, conforming to ASTM Designation: D 4632.

B. ROCK BAG.—Rock bag fabric shall be non-woven polypropylene, polyethylene or polyamide with a minimum unit weight of 135 250g/m^2. The fabric shall have a mullen burst strength of at least 2067 2500 kPa, per ASTM Designation D3786 and an ultraviolet (UV) stability exceeding 70 percent at 500 hours. Rock bags shall have a length of 600 mm to 800 mm, width of 400 mm to 450 500 mm, thickness of 150 mm to 200 mm, and capable of containing a shall be filled to a weighted mass of ranging from 13 kg to 22 kg. Rock bag fill material shall be non-cohesive, gravel, free from deleterious material. After filling, Rock bags shall be filled and the opening shall be secured such that rock shall not escape from the bag.

C. TEMPORARY FLEXIBLE DIKE.—Temporary flexible dike fabric cover and skirt shall be a woven polypropylene fabric with a minimum tensile strength of 0.44-kN, conforming to ASTM Designation: D 4632. The prefabricated fabric shall be high visibility orange in color that is integral to the fabric; painting shall not be allowed. The fabric shall have an ultraviolet (UV) stability exceeding 70 percent. Temporary flexible dike inner material shall be urethane foam and shall be shaped and dimensioned as shown on the plans. Adhesive for temporary flexible dike shall be a solvent free rubber modified asphalt emulsion. The color of the emulsion shall be brown when wet and shall have a drying period of not more than 3 hours.

D. EROSION CONTROL BLANKET.—Erosion control blanket shall consist of straw and coconut or wood excelsior blanket secured in place with wire staples and shall conform to one of the following:

E. EXCELSIOR BLANKET.—Excelsior blanket material shall consist of machine produced mats of curled wood excelsior with 80 percent of the fiber 150 mm or longer. The erosion control blanket shall be of consistent thickness and the wood fiber shall be evenly distributed over the entire area of the blanket. The top surface of the blanket shall be covered with an extruded plastic mesh. The blanket shall be smolder resistant without the use of chemical additives and shall be non-toxic and non-injurious to plant and animal life. Erosion control blanket shall be furnished in rolled strips, 1220 mm -2440 mm in width, and shall have an average mass of 0.5-kg/m^2, ± 10 percent, at the time of manufacture.

F. STRAW AND COCONUT BLANKET.—Straw and coconut blanket shall be machine produced mats of straw and coconut with a light weight netting on top. The straw and coconut shall be adhered to the netting with biodegradable thread or glue strip. The straw and coconut erosion control blanket shall be of consistent thickness with the straw and coconut evenly distributed over the entire area of the blanket. Straw and coconut erosion control blanket shall be furnished in rolled strips with a minimum width of 1.8 meters, minimum length of 20 meters (± 1 meter) and a minimum mass of 0.27-kg/m^2.

G. STAPLES.—Staples for erosion control blankets shall be made of 11-gage minimum steel wire and shall conform to the dimensions as shown on the plans.

H. SEDIMENT CONTROL BAG.—Sedimentation control fabric for sediment bags shall be a prefabricated sedimentation control fabric envelop with a woven polypropylene fabric and sewn with a double stitched seam using nylon thread. The fabric shall have a grab tensile strength of at least 120 kg and grab elongation of 20 percent, per ASTM Designation: D4632. The fabric shall have a mullen burst strength of at least 2895 kPa, per ASTM Designation: D3786 and an ultraviolet (UV) stability exceeding 90 percent. The sedimentation control fabric shall be capable of a flow rate of 70.3 L/minute/m2, per ASTM Designation: D4491. The sediment bag shall be sized to fit the catch basin or drainage inlet and be complete with lifting loops and dump straps attached at the

bottom to facilitate emptying of the sediment bag. The sediment bags shall have a restraint cord approximately halfway up the bag to keep the sides away from the catch basin walls.

INSTALLATION AND MAINTENANCE

Temporary flexible dike consists of individual sections of dike installed in conjunction with one another adjacent to existing drainage inlets as shown on the plans. The spacing and angle of placement shall be in accordance with the table shown on the plans. Temporary flexible dike shall be installed flush against the sides of concrete or asphalt curbs, dikes and pavement with the inner material and fabric cover cut smoothly and evenly to provide a tight flush joint.

Temporary flexible dike and rock bag dike installed as part of temporary drainage inlet protection shall be maintained to provide for adequate sediment holding capacity. Sediment deposits shall be removed when the deposit reaches one-half of the temporary flexible dike height. Removed sediment shall be deposited within the project in such a way that it is not subject to erosion by wind or water, or as directed by the Engineer.

Temporary rock bag dike consisting of filled rock bags placed in multiple layers shall be installed as shown on the plans.

When no longer required for the purpose, as determined by the Engineer, temporary drainage inlet protection facilities shall be removed. Removed facilities shall become the property of the Contractor and shall be removed from the site of the work.

Temporary drainage inlet protection damaged due to storms or as a result of the Contractors operations shall be replaced at the Contractor's expense.

Sediment bags shall be installed by removing the drainage inlet grate, placing the sediment bag in the opening, and replacing the grate to secure the sediment bag in place. Removal of the bag shall be facilitated by the use of 25 mm steel reinforcing bars placed through the lifting loops.

Sediment bags installed as part of temporary drainage inlet protection shall be emptied when the restraint cords are no longer visible. Emptying of the bag shall be facilitated by the use of 25mm steel reinforcing bars placed through the lifting loops. The sediment bag shall be emptied of material and rinsed before replacement in the catch basin or drainage inlet.

MEASUREMENT AND PAYMENT

The quantity of temporary drainage inlet protection to be paid for will be determined from each drainage inlet protected conforming to the details shown on the plans or as approved by the Engineer. The protection is measured one time only additional measurement is recognized and no additional compensation made if the temporary drainage inlet protection changes during the course of construction.

Temporary Drainage Inlet Protection Type 1A, 1B, 2A, 2B, 3 and 4 shall be measured and paid for as Temporary Drainage Inlet Protection.

The contract price paid per temporary drainage inlet protection shall include full compensation for furnishing all labor, materials, tools, equipment, and incidentals, and for doing all the work involved in installing temporary drainage inlet protection, complete in place, including excavation and backfill, all modifications occurring during the course of construction, and maintenance and removal of temporary drainage inlet protection, as shown on the plans, as specified in the Standard Specifications and these special provisions, and as directed by the Engineer.

Temporary drainage inlet protection for protection at drainage inlets shown on the project plans or directed by the Engineer will be paid for under this item of work. Payment for temporary drainage inlet protection that is required as part of the WPCP, and not paid for as above, will be paid for as specified in "Water Pollution Control" elsewhere in these special provisions.

No adjustment of compensation will be made for any increase or decrease in the quantities of temporary drainage inlet protection required, regardless of the reason for the increase or decrease. The provisions in Section 4-1.03B, "Increased or Decreased Quantities", shall not apply to temporary drainage inlet protection.

10-1.13 DAMAGE REPAIR

Attention is directed to Section 7-1.16, "Contractor's Responsibility for the Work and Materials," and Section 7-1.165, "Damage by Storm, Flood, Tsunami or Earthquake," of the Standard Specifications and these special provisions.

When as a result of freezing conditions (as defined herein) during the plant establishment period, plants have died or, in the opinion of the Engineer, have deteriorated to a point beyond which the plants will not mature as typical examples of their species, the Engineer may direct replacement of the affected plants. The total cost of ordered plant replacement work will be paid for as extra work as provided in Section 4-1.03D of the Standard Specifications. A freezing condition, for the purpose of this specification, occurs when the temperature at or near the affected area has been officially recorded below 0°C and plants have been killed or damaged to the degree described above.

When, as a result of drought conditions (as defined herein) during the plant establishment period, plants have died or, in the opinion of the Engineer, have deteriorated to a point beyond which the plants will not mature as typical examples of their species, the Engineer may direct replacement of the affected plants. The total cost of ordered plant replacements, after water

has been restricted or stopped, will be paid for as extra work as provided in Section 4-1.03D of the Standard Specifications. Restriction or shutoff of available water shall not relieve the Contractor from performing other contract work. A drought condition occurs when the Department, or its supplier, restricts or stops delivery of water to the Contractor to the degree that plants have died or deteriorated as described above.

When the provisions in Section 7-1.165, "Damage by Storm, Flood, Tsunami or Earthquake," of the Standard Specifications are applicable, the provisions above for payment of costs for repair of damage due to rain, freezing conditions and drought shall not apply.

10-1.14 RELIEF FROM MAINTENANCE AND RESPONSIBILITY

The Contractor may be relieved of the duty of maintenance and protection for those items not directly connected with plant establishment work in conformance with the provisions in Section 7-1.15, "Relief From Maintenance and Responsibility," of the Standard Specifications. Water pollution control, maintain existing planted areas, maintain existing irrigation facilities, transplant trees, and transplant palm trees shall not be relieved of maintenance.

10-1.15 SCAFFOLDING

Scaffolding shall be defined in accordance with and shall conform to the Construction Safety Orders of the Division of Occupational Safety and Health and these special provisions.

If scaffolding is constructed for this project over or adjacent to traffic, or suspended from the traveled way, the Contractor shall submit to the Engineer working drawings for scaffolding systems in conformance with Section 5-1.02, "Plans and Working Drawings'" of the Standard Specifications, and these special provisions.

Scaffolding working drawings shall include the following items:

A. Descriptions, calculations, and values for all loads anticipated during the erection, use, and removal of scaffolding.
B. Methods and equipment for erecting, moving, and removing scaffolding.
C. Design details including bolt layouts, welding details, and any connections to existing structures.
D. Stress sheets including a summary of computed stresses in the (1) scaffolding, (2) connections between scaffolding and any existing structures and (3) existing load supporting members. The computed stresses shall include the effects of erection, movement, and removal of the scaffolding.

The scaffolding manufacturer's name, address, and phone number shall be shown on the working drawings.

The working drawings shall be stamped and signed by an engineer who is registered as a Civil Engineer. In addition, prior to submitting the working drawings to the Engineer, the working drawings shall be stamped and signed by an independent reviewer who is registered as a Civil Engineer in the State of California. The independent reviewer shall not be employed by the same entity preparing the working drawings.

The Contractor shall allow 1 week for the review of a complete submittal for scaffolding working drawings. In the event the Engineer fails to complete the review within the time allowed, and if, in the opinion of the Engineer, completion of the work is delayed or interfered with by reason of the Engineer's delay in completing the review, the Contractor will be compensated for any resulting loss, and an extension of time will be granted, in the same manner as provided for in Section 8-1.09, "Right of Way Delays," of the Standard Specifications.

Welding for the manufacturing and erection of scaffolding shall conform to the requirements in AWS D1.1 or D1.2 for steel or aluminum construction respectively.

Full compensation for conforming to the above requirements shall be considered as included in the contract prices paid for the various contract items of work, and no additional compensation will be allowed therefor.

10-1.16 COOPERATION

Attention is directed to Section 7-1.14, "Cooperation," and Section 8-1.10, "Utility and Non-Highway Facilities," of the Standard Specifications and these special provisions.

It is anticipated that work by another contractor to construct a boulevard in San Francisco from Market Street to Hayes Street may be in progress adjacent to or within the limits of this project during progress of the work on this contract.

10-1.17 PROGRESS SCHEDULE (CRITICAL PATH METHOD)

The Contractor shall submit to the Engineer practicable critical path method (CPM) progress schedules in conformance with these special provisions. Whenever the term "schedule" is used in this section it shall mean CPM progress schedule.

Attention is directed to "Payments" of Section 5 of these special provisions.

The provisions in Section 8-1.04, "Progress Schedule," of the Standard Specifications shall not apply.

DEFINITIONS

The following definitions shall apply to this section:

A. ACTIVITY.—A task, event or other project element on a schedule that contributes to completing the project. Activities have a description, start date, finish date, duration and one or more logic ties.
B. BASELINE SCHEDULE.—The initial schedule representing the Contractor's work plan on the first working day of the project.
C. CONTRACT COMPLETION DATE.—The current extended date for completion of the contract shown on the weekly statement of working days furnished by the Engineer in conformance with the provisions in Section 8-1.06, "Time of Completion," of the Standard Specifications.
D. CRITICAL PATH.—The longest continuous chain of activities for the project that has the least amount of total float of all chains. In general, a delay on the critical path will extend the scheduled completion date.
E. CRITICAL PATH METHOD (CPM).—A network based planning technique using activity durations and the relationships between activities to mathematically calculate a schedule for the entire project.
F. DATA DATE.—The day after the date through which a schedule is current. Everything occurring earlier than the data date is "as-built" and everything on or after the data date is "planned."
G. EARLY COMPLETION TIME.—The difference in time between an early scheduled completion date and the contract completion date.
H. FLOAT.—The difference between the earliest and latest allowable start or finish times for an activity.
I. MILESTONE.—An event activity that has zero duration and is typically used to represent the beginning or end of a certain stage of the project.
J. NARRATIVE REPORT.—A document submitted with each schedule that discusses topics related to project progress and scheduling.
K. NEAR CRITICAL PATH.—A chain of activities with total float exceeding that of the critical path but having no more than 10 working days of total float.
L. SCHEDULED COMPLETION DATE.—The planned project finish date shown on the current accepted schedule.
M. STATE OWNED FLOAT ACTIVITY.—The activity documenting time saved on the critical path by actions of the State. It is the last activity prior to the scheduled completion date.
N. TIME IMPACT ANALYSIS.—A schedule and narrative report developed specifically to demonstrate what effect a proposed change or delay has on the current scheduled completion date.
O. TOTAL FLOAT.—The amount of time that an activity or chain of activities can be delayed before extending the scheduled completion date.
P. UPDATE SCHEDULE.—A current schedule developed from the baseline or subsequent schedule through regular monthly review to incorporate as-built progress and any planned changes.

GENERAL REQUIREMENTS

The Contractor shall submit to the Engineer baseline, monthly update and final update schedules, each consistent in all respects with the time and order of work requirements of the contract. The project work shall be executed in the sequence indicated on the current accepted schedule.

Schedules shall show the order in which the Contractor proposes to carry out the work with logical links between time-scaled work activities, and calculations made using the critical path method to determine the controlling operation or operations. The Contractor is responsible for assuring that all activity sequences are logical and that each schedule shows a coordinated plan for complete performance of the work.

The Contractor shall produce schedules using computer software and shall furnish compatible software for the Engineer's exclusive possession and use. The Contractor shall furnish network diagrams, narrative reports, tabular reports and schedule data as parts of each schedule submittal.

Schedules shall include, but not be limited to, activities that show the following that are applicable to the project:

A. Project characteristics, salient features, or interfaces, including those with outside entities, that could affect time of completion.
B. Project start date, scheduled completion date and other milestones.
C. Work performed by the Contractor, subcontractors and suppliers.
D. Submittal development, delivery, review and approval, including those from the Contractor, subcontractors and suppliers.
E. Procurement, delivery, installation and testing of materials, plants and equipment.
F. Testing and settlement periods.
G. Utility notification and relocation.

H. Erection and removal of falsework and shoring.
I. Major traffic stage switches.
J. Finishing roadway and final cleanup.
K. State-owned float as the predecessor activity to the scheduled completion date.

Schedules shall have not less than 50 and not more than 500 activities, unless otherwise authorized by the Engineer. The number of activities shall be sufficient to assure adequate planning of the project, to permit monitoring and evaluation of progress, and to do an analysis of time impacts.

Schedule activities shall include the following:

A. A clear and legible description.
B. Start and finish dates.
C. A duration of not less than one working day, except for event activities, and not more than 20 working days, unless otherwise authorized by the Engineer.
D. At least one predecessor and one successor activity, except for project start and finish milestones.
E. Required constraints.
F. Codes for responsibility, stage, work shifts, location and contract pay item numbers.

The Contractor may show early completion time on any schedule provided that the requirements of the contract are met. Early completion time shall be considered a resource for the exclusive use of the Contractor. The Contractor may increase early completion time by improving production, reallocating resources to be more efficient, performing sequential activities concurrently or by completing activities earlier than planned. The Contractor may also submit for approval a cost reduction incentive proposal in conformance with the provisions in Section 5-1.14, "Cost Reduction Incentive," of the Standard Specifications that will reduce time of construction.

The Contractor may show a scheduled completion date that is later than the contract completion date on an update schedule, after the baseline schedule is accepted. The Contractor shall provide an explanation for a late scheduled completion date in the narrative report that is included with the schedule.

State-owned float shall be considered a resource for the exclusive use of the State. The Engineer may accrue State-owned float by the early completion of review of any type of required submittal when it saves time on the critical path. The Contractor shall prepare a time impact analysis, when requested by the Engineer, to determine the effect of the action in conformance with the provisions in "Time Impact Analysis" specified herein. The Engineer will document State-owned float by directing the Contractor to update the State-owned float activity on the next update schedule. The Contractor shall include a log of the action on the State-owned float activity and include a discussion of the action in the narrative report. The Engineer may use State-owned float to mitigate past, present or future State delays by offsetting potential time extensions for contract change orders.

The Engineer may adjust contract working days for ordered changes that affect the scheduled completion date, in conformance with the provisions in Section 4-1.03, "Changes," of the Standard Specifications. The Contractor shall prepare a time impact analysis to determine the effect of the change in conformance with the provisions in "Time Impact Analysis" specified herein, and shall include the impacts acceptable to the Engineer in the next update schedule. Changes that do not affect the controlling operation on the critical path will not be considered as the basis for a time adjustment. Changes that do affect the controlling operation on the critical path will be considered by the Engineer in decreasing time or granting an extension of time for completion of the contract. Time extensions will only be granted if the total float is absorbed and the scheduled completion date is delayed one or more working days because of the ordered change.

The Engineer's review and acceptance of schedules shall not waive any contract requirements and shall not relieve the Contractor of any obligation thereunder or responsibility for submitting complete and accurate information. Schedules that are rejected shall be corrected by the Contractor and resubmitted to the Engineer within 5 working days of notification by the Engineer, at which time a new review period of one week will begin.

Errors or omissions on schedules shall not relieve the Contractor from finishing all work within the time limit specified for completion of the contract. If, after a schedule has been accepted by the Engineer, either the Contractor or the Engineer discover that any aspect of the schedule has an error or omission, it shall be corrected by the Contractor on the next update schedule.

COMPUTER SOFTWARE

The Contractor shall submit to the Engineer for approval a description of proposed software before delivery. The software shall be the current version of Primavera SureTrak Project Manager for Windows, or equal, and shall be compatible with Windows NT (version 4.0) operating system. If software other than SureTrak is proposed, it shall be capable of generating files that can be imported into SureTrak.

The Contractor shall furnish schedule software and all original software instruction manuals to the Engineer with submittal of the baseline schedule. The furnished schedule software shall become the property of the State and will not be returned to the Contractor. The State will compensate the Contractor in conformance with the provisions in Section 4-1.03, "Extra Work," of the Standard Specifications for replacement of software which is damaged, lost or stolen after delivery to the Engineer.

The Contractor shall instruct the Engineer in the use of the software and provide software support until the contract is accepted. Within 20 working days of contract approval, the Contractor shall provide a commercial 8-hour training session for 2 Department employees in the use of the software at a location acceptable to the Engineer. It is recommended that the Contractor also send at least 2 employees to the same training session to facilitate development of similar knowledge and skills in the use of the software. If software other than SureTrak is furnished, then the training session shall be a total of 16-hours for each Department employee.

NETWORK DIAGRAMS, REPORTS AND DATA

The Contractor shall include the following for each schedule submittal:

A. Two sets of originally plotted, time-scaled network diagrams.
B. Two copies of a narrative report.
C. Two copies of each of 3 sorts of the CPM software-generated tabular reports.
D. One 1.44-megabyte 90 mm (3.5 inch) floppy diskette containing the schedule data.

The time-scaled network diagrams shall conform to the following:

A. Show a continuous flow of information from left to right.
B. Be based on early start and early finish dates of activities.
C. Clearly show the primary paths of criticality using graphical presentation.
D. Be prepared on E-size sheets, 860 mm x 1120 mm (34 inch x 44 inch).
E. Include a title block and a timeline on each page.

The narrative report shall be organized in the following sequence with all applicable documents included:

A. Contractor's transmittal letter.
B. Work completed during the period.
C. Identification of unusual conditions or restrictions regarding labor, equipment or material; including multiple shifts, 6-day work weeks, specified overtime or work at times other than regular days or hours.
D. Description of the current critical path.
E. Changes to the critical path and scheduled completion date since the last schedule submittal.
F. Description of problem areas.
G. Current and anticipated delays:

    1. Cause of delay.
    2. Impact of delay on other activities, milestones and completion dates.
    3. Corrective action and schedule adjustments to correct the delay.

H. Pending items and status thereof:

    1. Permits
    2. Change orders
    3. Time adjustments
    4. Non-compliance notices

I. Reasons for an early or late scheduled completion date in comparison to the contract completion date.

Tabular reports shall be software-generated and provide information for each activity included in the project schedule. Three different reports shall be sorted by (1) activity number, (2) early start and (3) total float. Tabular reports shall be 215 mm x 280 mm (8 1/2 inch x 11 inch) in size and shall include, as a minimum, the following applicable information:

A. Data date

B. Activity number and description
C. Predecessor and successor activity numbers and descriptions
D. Activity codes
E. Scheduled, or actual and remaining durations (work days) for each activity
F. Earliest start (calendar) date
G. Earliest finish (calendar) date
H. Actual start (calendar) date
I. Actual finish (calendar) date
J. Latest start (calendar) date
K. Latest finish (calendar) date
L. Free float (work days)
M. Total float (work days)
N. Percentage of activity complete and remaining duration for incomplete activities.
O. Lags
P. Required constraints

Schedule submittals will only be considered complete when all documents and data have been provided as described above.

PRE-CONSTRUCTION SCHEDULING CONFERENCE

The Contractor shall schedule and the Engineer will conduct a pre-construction scheduling conference with the Contractor's project manager and construction scheduler within 10 working days of the approval of the contract. At this meeting the Engineer will review the requirements of this section of the special provisions with the Contractor.

The Contractor shall submit a general time-scaled logic diagram displaying the major activities and sequence of planned operations and shall be prepared to discuss the proposed work plan and schedule methodology that comply with the requirements of these special provisions. If the Contractor proposes deviations to the construction staging of the project, then the general time-scaled logic diagram shall also display the deviations and resulting time impacts. The Contractor shall be prepared to discuss the proposal.

At this meeting, the Contractor shall additionally submit the alphanumeric coding structure and the activity identification system for labeling the work activities. To easily identify relationships, each activity description shall indicate its associated scope or location of work by including such terms as quantity of material, type of work, bridge number, station to station location, side of highway (such as left, right, northbound, southbound), lane number, shoulder, ramp name, ramp line descriptor or mainline.

The Engineer will review the logic diagram, coding structure, and activity identification system, and provide any required baseline schedule changes to the Contractor for implementation.

BASELINE SCHEDULE

Beginning the week following the pre-construction scheduling conference, the Contractor shall meet with the Engineer weekly until the baseline schedule is accepted by the Engineer to discuss schedule development and resolve schedule issues.

The Contractor shall submit to the Engineer a baseline schedule within 20 working days of approval of the contract. The Contractor shall allow 3 weeks for the Engineer's review after the baseline schedule and all support data are submitted. In addition, the baseline schedule submittal will not be considered complete until the computer software is delivered and installed for use in review of the schedule.

The baseline schedule shall include the entire scope of work and how the Contractor plans to complete all work contemplated. The baseline schedule shall show the activities that define the critical path. Multiple critical paths and near-critical paths shall be kept to a minimum. A total of not more than 50 percent of the baseline schedule activities shall be critical or near critical, unless otherwise authorized by the Engineer.

The baseline schedule shall not extend beyond the number of working days specified in these special provisions. The baseline schedule shall have a data date of the first working day of the contract and not include any completed work to date. The baseline schedule shall not attribute negative float or negative lag to any activity.

If the Contractor submits an early completion baseline schedule that shows contract completion in less than 85 percent of the working days specified in these special provisions, the baseline schedule shall be supplemented with resource allocations for every task activity and include time-scaled resource histograms. The resource allocations shall be shown to a level of detail that facilitates report generation based on labor crafts and equipment classes for the Contractor and subcontractors. The Contractor shall use average composite crews to display the labor loading of on-site construction activities. The Contractor shall optimize and level labor to reflect a reasonable plan for accomplishing the work of the contract and to assure that resources are not duplicated in concurrent activities. The time-scaled resource histograms shall

show labor crafts and equipment classes to be utilized on the contract. The Engineer may review the baseline schedule activity resource allocations using Means Productivity Standards or equivalent to determine if the schedule is practicable.

UPDATE SCHEDULE

The Contractor shall submit an update schedule and meet with the Engineer to review contract progress, on or before the first day of each month, beginning one month after the baseline schedule is accepted. The Contractor shall allow 2 weeks for the Engineer's review after the update schedule and all support data are submitted, except that the review period shall not start until the previous month's required schedule is accepted. Update schedules that are not accepted or rejected within the review period will be considered accepted by the Engineer.

The update schedule shall have a data date of the twenty-first day of the month or other date established by the Engineer. The update schedule shall show the status of work actually completed to date and the work yet to be performed as planned. Actual activity start dates, percent complete and finish dates shall be shown as applicable. Durations for work that has been completed shall be shown on the update schedule as the work actually occurred, including Engineer submittal review and Contractor resubmittal times.

The Contractor may include modifications such as adding or deleting activities or changing activity constraints, durations or logic that do not (1) alter the critical path(s) or near critical path(s) or (2) extend the scheduled completion date compared to that shown on the current accepted schedule. The Contractor shall state in writing the reasons for any changes to planned work. If any proposed changes in planned work will result in (1) or (2) above, then the Contractor shall submit a time impact analysis as described herein.

TIME IMPACT ANALYSIS

The Contractor shall submit a written time impact analysis (TIA) to the Engineer with each request for adjustment of contract time, or when the Contractor or Engineer consider that an approved or anticipated change may impact the critical path or contract progress.

The TIA shall illustrate the impacts of each change or delay on the current scheduled completion date or internal milestone, as appropriate. The analysis shall use the accepted schedule that has a data date closest to and prior to the event. If the Engineer determines that the accepted schedule used does not appropriately represent the conditions prior to the event, the accepted schedule shall be updated to the day before the event being analyzed. The TIA shall include an impact schedule developed from incorporating the event into the accepted schedule by adding or deleting activities, or by changing durations or logic of existing activities. If the impact schedule shows that incorporating the event modifies the critical path and scheduled completion date of the accepted schedule, the difference between scheduled completion dates of the two schedules shall be equal to the adjustment of contract time. The Engineer may construct and utilize an appropriate project schedule or other recognized method to determine adjustments in contract time until the Contractor provides the TIA.

The Contractor shall submit a TIA in duplicate within 15 working days of receiving a written request for a TIA from the Engineer. The Contractor shall allow the Engineer 2 weeks after receipt to approve or reject the submitted TIA. All approved TIA schedule changes shall be shown on the next update schedule.

If a TIA submitted by the Contractor is rejected by the Engineer, the Contractor shall meet with the Engineer to discuss and resolve issues related to the TIA. If agreement is not reached, the Contractor will be allowed 15 days from the meeting with the Engineer to give notice in conformance with the provisions in Section 9-1.04, "Notice of Potential Claim," of the Standard Specifications. The Contractor shall only show actual as-built work, not unapproved changes related to the TIA, in subsequent update schedules. If agreement is reached at a later date, approved TIA schedule changes shall be shown on the next update schedule. The Engineer will withhold remaining payment on the schedule contract item if a TIA is requested by the Engineer and not submitted by the Contractor within 15 working days. The schedule item payment will resume on the next estimate after the requested TIA is submitted. No other contract payment will be retained regarding TIA submittals.

FINAL UPDATE SCHEDULE

The Contractor shall submit a final update, as-built schedule with actual start and finish dates for the activities, within 30 days after completion of contract work. The Contractor shall provide a written certificate with this submittal signed by the Contractor's project manager and an officer of the company stating, "To my knowledge and belief, the enclosed final update schedule reflects the actual start and finish dates of the actual activities for the project contained herein." An officer of the company may delegate in writing the authority to sign the certificate to a responsible manager.

RETENTION

The Department will retain an amount equal to 25 percent of the estimated value of the work performed during each estimate period in which the Contractor fails to submit an acceptable schedule conforming to the requirements of these special provisions as determined by the Engineer. Schedule retentions will be released for payment on the next monthly

estimate for partial payment following the date that acceptable schedules are submitted to the Engineer or as otherwise specified herein. Upon completion of all contract work and submittal of the final update schedule and certification, any remaining retained funds associated with this section, "Progress Schedule (Critical Path Method)", will be released for payment. Retentions held in conformance with this section shall be in addition to other retentions provided for in the contract. No interest will be due the Contractor on retention amounts.

PAYMENT

Progress schedule (critical path method) will be paid for at a lump sum price. The contract lump sum price paid for progress schedule (critical path method) shall include full compensation for furnishing all labor, material, tools, equipment, and incidentals, including computer software, and for doing all the work involved in preparing, furnishing, and updating schedules, and instructing and assisting the Engineer in the use of computer software, as specified in the Standard Specifications and these special provisions, and as directed by the Engineer.

Payments for the progress schedule (critical path method) contract item will be made progressively as follows:

A. A total of 25 percent of the item amount or a total of 25 percent of the amount listed for progress schedule (critical path method) in "Payments" of Section 5 of these special provisions, whichever is less, will be paid upon achieving all of the following:

   1. Completion of 5 percent of all contract item work.
   2. Acceptance of all schedules and TIAs required to the time when 5 percent of all contract item work is complete.
   3. Delivery of schedule software to the Engineer.
   4. Completion of required schedule software training.

B. A total of 50 percent of the item amount or a total of 50 percent of the amount listed for progress schedule (critical path method) in "Payments" of Section 5 of these special provisions, whichever is less, will be paid upon completion of 25 percent of all contract item work and acceptance of all schedules and TIAs required to the time when 25 percent of all contract item work is complete.
C. A total of 75 percent of the item amount or a total of 75 percent of the amount listed for progress schedule (critical path method) in "Payments" of Section 5 of these special provisions, whichever is less, will be paid upon completion of 50 percent of all contract item work and acceptance of all schedules and TIAs required to the time when 50 percent of all contract item work is complete.
D. A total of 100 percent of the item amount or a total of 100 percent of the amount listed for progress schedule (critical path method) in "Payments" of Section 5 of these special provisions, whichever is less, will be paid upon completion of all contract item work, acceptance of all schedules and TIAs required to the time when all contract item work is complete, and submittal of the certified final update schedule.

If the Contractor fails to complete any of the work or provide any of the schedules required by this section, the Engineer shall make an adjustment in compensation in conformance with the provisions in Section 4-1.03C, "Changes in Character of Work," of the Standard Specifications for the work not performed. Adjustments in compensation for schedules will not be made for any increased or decreased work ordered by the Engineer in furnishing schedules.

10-1.18 TIME-RELATED OVERHEAD

The Contractor will be compensated for time-related overhead in conformance with these special provisions.

Attention is directed to "Beginning of Work, Time of Completion and Liquidated Damages," "Force Account Payment," and "Progress Schedule (Critical Path Method)" of these special provisions.

The provisions in Section 9-1.08, "Adjustment of Overhead Costs," of the Standard Specifications shall not apply.

Time-related overhead shall consist of those overhead costs, including field and home office overhead, that are in proportion to the time required to complete the work. Time-related overhead shall not include costs that are not related to time, including but not limited to, mobilization, licenses, permits, and other charges incurred only once during the contract.

Field office overhead expenses include time-related costs associated with the normal and recurring operations of the construction project, and shall not include costs directly attributable to the work of the contract. Time-related costs of field office overhead include, but are not limited to, salaries, benefits, and equipment costs of project managers, general superintendents, field office managers and other field office staff assigned to the project, and rent, utilities, maintenance, security, supplies, and equipment costs of the project field office.

Home office overhead or general and administrative expenses refer to the fixed costs of operating the Contractor's business. These costs include, but are not limited to, general administration, insurance, personnel and subcontract administration, purchasing, accounting, and project engineering and estimating. Home office overhead costs shall exclude

expenses specifically related to other contracts or other businesses of the Contractor, equipment coordination, material deliveries, and consultant and legal fees.

The amount of time-related overhead associated with a reduction in contract time for cost reduction incentive proposals accepted and executed in conformance with the provisions in Section 5-1.14, "Cost Reduction Incentive," of the Standard Specifications shall be considered a construction cost attributable to the resultant estimated net savings due to the cost reduction incentive.

If the final increased amount of time-related overhead exceeds 149 percent of the contract lump sum price bid, the Contractor shall, within 60 days of the Engineer's written request, submit to the Engineer an audit examination and report performed by an independent Certified Public Accountant of the Contractor's actual overhead costs. The independent Certified Public Accountant's audit examination shall be performed in conformance with the requirements of the American Institute of Certified Public Accountants Attestation Standards. The audit examination and report shall depict the Contractor's project and company-wide financial records and shall specify the actual overall average daily rates for both field and home office overhead for the entire duration of the project, and whether the costs have been properly allocated. The rates of field and home office overhead shall exclude unallowable costs as determined in the Federal Acquisition Regulations, 48 CFR, Chapter 1, Part 31. The audit examination and report shall determine if the rates of field office overhead and home office overhead are:

A. Allowable in conformance with the requirements of the Federal Acquisition Regulations, 48 CFR, Chapter 1, Part 31.
B. Adequately supported by reliable documentation.
C. Related solely to the project under examination.

Within 20 days of the Engineer's written request, the Contractor shall make its financial records available for audit by the State for the purpose of verifying the actual rate of time-related overhead specified in the audit submitted by the Contractor. The actual rate of time-related overhead specified in the audit, submitted by the Contractor, will be subject to approval by the Engineer.

If the Engineer requests the independent Certified Public Accountant audit, or if it is requested in writing by the Contractor, the contract lump sum payment for time-related overhead, in excess of 149 percent of the lump sum price bid, will be adjusted to reflect the actual rate.

The cost of performing an independent Certified Public Accountant audit examination and submitting the report, requested by the Engineer, will be borne equally by the State and the Contractor. The division of the cost will be made by determining the cost of providing an audit examination and report in conformance with the provisions of Section 9-1.03B, "Work Performed by Special Forces or Other Special Services" of the Standard Specifications, and paying to the Contractor one-half of that cost. The cost of performing an audit examination and submitting the independent Certified Public Accountant audit report for overhead claims other than for the purpose of verifying the actual rate of time-related overhead shall be entirely borne by the Contractor.

Time-related overhead will be paid for at a lump sum price. The contract lump sum price bid for time-related overhead will be increased or decreased only as a result of suspensions or adjustments of contract time which revise the current contract completion date and which satisfy any of the following criteria:

A. Suspensions of work ordered in conformance with the provisions in Section 8-1.05, "Temporary Suspension of Work," of the Standard Specifications, except:

    1. Suspensions ordered due to weather conditions being unfavorable for the suitable prosecution of the controlling operation or operations.
    2. Suspensions ordered due to the failure on the part of the Contractor to carry out orders given, or to perform the provisions of the contract.
    3. Other suspensions that mutually benefit the State and the Contractor.

B. Extensions of contract time granted by the State in conformance with the provisions in the fifth paragraph in Section 8-1.07, "Liquidated Damages," of the Standard Specifications and set forth in approved contract change orders, in conformance with the provisions in Section 4-1.03, "Changes," of the Standard Specifications.
C. Reductions in contract time set forth in approved contract change orders, in conformance with the provisions in Section 4-1.03, "Changes," of the Standard Specifications.

For each day the number of working days bid to complete the contract, in conformance with the provisions in "Beginning Of Work, Time Of Completion And Liquidated Damages," of these special provisions, is increased or decreased due to suspensions or adjustments of contract time as specified above, the lump sum price for time-related overhead will be

increased or decreased by an amount equal to the contract lump sum price bid for time-related overhead divided by the number of working days bid to complete the contract.

In the event an early completion progress schedule, as defined in "Progress Schedule (Critical Path Method)" of these special provisions, is submitted by the Contractor and approved by the Engineer, the amount of time-related overhead eligible for payment will be based on the total number of working days for the project, in conformance with the provisions in "Beginning of Work, Time of Completion and Liquidated Damages" of these special provisions, rather than the Contractor's early completion progress schedule.

The contract lump sum price paid for time-related overhead shall include full compensation for time-related overhead, including the Contractor's share of costs of an independent Certified Public Accountant audit of overhead costs requested by the Engineer, as specified in these special provisions, and as directed by the Engineer.

The provisions in Sections 4-1.03B, "Increased or Decreased Quantities," and 4-1.03C, "Changes in Character of the Work," of the Standard Specifications shall not apply to the contract item of time-related overhead.

Full compensation for additional overhead costs incurred during days of inclement weather when the contract work is extended into additional construction seasons due to delays caused by the State shall be considered as included in the time-related overhead paid during the contract working days, and no additional compensation will be allowed therefor.

Full compensation for additional overhead costs involved in performing additional contract item work that is not a controlling operation shall be considered as included in the contract items of work involved, and no additional compensation will be allowed therefor.

Full compensation for overhead, other than time-related overhead measured and paid for as specified above, and other than overhead costs included in the markups specified in "Force Account Payment" of these special provisions, shall be considered as included in the various items of work and no additional compensation will be allowed therefor.

Overhead costs incurred by joint venture partners, subcontractors, suppliers or other parties associated with the Contractor shall be considered as included in the various overhead costs for which the Contractor is compensated, and no additional compensation will be allowed therefor.

For the purpose of making partial payments pursuant to the provisions in Section 9-1.06, "Partial Payments," of the Standard Specifications, the amount of time-related overhead in each monthly partial payment will be based on the number of working days that occurred during that monthly estimate period, including compensable suspensions and right of way delays. Working days granted by contract change order due to extra work or changes in character of work, will be compensated upon completion of the contract. The amount earned per working day for time-related overhead shall be the lesser of the following amounts:

A) The contract lump sum price for time-related overhead, divided by the number of working days bid to complete the contract, in conformance with the provisions in "Beginning Of Work, Time Of Completion And Liquidated Damages," of these special provisions.
B) Twenty percent of the original total contract amount, divided by the number of working days bid to compete the contract, in conformance with the provisions in "Beginning Of Work, Time Of Completion And Liquidated Damages," of these special provisions.

After the work has been completed, except plant establishment work, as provided in Section 20-4.08, "Plant Establishment Work," of the Standard Specifications, the amount of the total contract lump sum price for time-related overhead not yet paid will be included for payment in the first estimate made after completion of roadway construction work, in conformance with the provisions in Section 9-1.06, "Partial Payments," of the Standard Specifications.

10-1.19 OBSTRUCTIONS

Attention is directed to Section 8-1.10, "Utility and Non-Highway Facilities," and Section 15, "Existing Highway Facilities," of the Standard Specifications and these special provisions.

Attention is directed to the existence of certain underground facilities that may require special precautions be taken by the Contractor to protect the health, safety and welfare of workers and of the public. Facilities requiring special precautions include, but are not limited to: conductors of petroleum products, oxygen, chlorine, and toxic or flammable gases; natural gas in pipelines greater than 150 mm in diameter or pipelines operating at pressures greater than 415 kPa (gage); underground electric supply system conductors or cables, with potential to ground of more than 300 V, either directly buried or in a duct or conduit which do not have concentric grounded or other effectively grounded metal shields or sheaths.

The Contractor shall notify the Engineer and the appropriate regional notification center for operators of subsurface installations at least 2 working days, but not more than 14 calendar days, prior to performing any excavation or other work close to any underground pipeline, conduit, duct, wire or other structure. Regional notification centers include, but are not limited to, the following:

Notification Center	Telephone Number
Underground Service Alert-Northern California (USA)	1-800-642-2444 1-800-227-2600
Underground Service Alert-Southern California (USA)	1-800-422-4133 1-800-227-2600

It is anticipated that the following utility facilities will be relocated prior to the dates shown:

Utility	Location	Date
City of San Francisco - Sewer Line & MH	MC 14+88	11/1/03
City of San Francisco - 150 mm Water Line & Water Valve	MC 14+93	11/1/03
City of San Francisco - Fire Hydrant & Water Valve	MK 15+15	11/1/03
PG&E - 250 mm Gas Line	MC 14+82	11/1/03
PG&E - 100 mm Gas Line	MC 14+94	11/1/03
Pacific Bell Telephone Calif. Corp. - 6 Telephone Cables	MC 14+91	03/1/04

Installation of the following utility facilities will require coordination with the Contractor's operations. The Contractor shall make the necessary arrangements with the utility company, through the Engineer, and shall submit a schedule of work, verified by a representative of the utility company, to the Engineer. The schedule of work shall provide not less than the following number of working days, as defined in Section 8-1.06, "Time of Completion," of the Standard Specifications for the utility company to complete their work:

Utility (address)	Location	Working Days
City of San Francisco - "Path of Gold" Street Lighting	MK 15+11	12
PG&E - Guy Wire	T 11+83	8
City of San Francisco Municipal Railway - Overhead Muni Wire	T 11+25	10
PG&E - Gas Valve	MK 15+16	10
PG&E - Electrical Pull Boxes	MK 15+11	15
City of San Francisco Municipal Railway - Electrical Pull Boxes	MK 15+11	15
City of San Francisco - Electrical Pull Boxes	MK 15+11	15

On McCoppin Street between Valencia Street and Market Street, Pacific Bell Telephone California Corporation will be abandoning and relocating their facilities during this contract. The work is scheduled to be completed by March 1, 2004. The Contractor shall not schedule any work on McCoppin Street, including the retaining walls crossing McCoppin Street, until after the abandonment/relocation work is complete.

In the event that the utility facilities mentioned above are not removed or relocated by the date specified and, if in the opinion of the Engineer, the Contractor's operations are delayed or interfered with by reason of the utility facilities not being removed or relocated by the date specified, the State will compensate the Contractor for the delays to the extent provided in Section 8-1.09, "Right of Way Delays," of the Standard Specifications, and not otherwise, except as provided in Section 8-1.10, "Utility and Non-Highway Facilities," of the Standard Specifications.

The Contractor shall notify the Engineer in writing at least 30 days in advance of the date or dates that the interfering utility facilities are to be rearranged. The Engineer will, in turn, notify the owners of the utility facilities.

The utility facilities listed in the following table, and other utility facilities that possibly exist at locations which might interfere with the drilling operations or substructure construction, will not be rearranged in advance of or during construction operations. Should the Contractor desire to have any of the utility facilities rearranged or temporarily deactivated for his convenience, the Contractor shall make the necessary arrangements as provided in Section 8-1.10:

Utility Facility	Location
Telephone Lines	Central Viaduct (Replace) Bridge No. 34-0077 Retaining Walls at Abut 11

Full compensation for conforming to the requirements of this section, not otherwise provided for, shall be considered as included in the prices paid for the various contract items of work involved and no additional compensation will be allowed therefor.

10-1.20 DUST CONTROL

Dust control shall conform to the provisions in Section 10, "Dust Control," of the Standard Specifications and these special provisions.

AIR QUALITY REQUIREMENTS

A. Prior to starting work at the site, submit to the City for acceptance a dust control program to minimize potential public health impacts associated with visible dust emissions and air quality pollutants. Said dust control program shall include measures to minimize impacts to sensitive receptors associated with exposure to respirable nuisance dust (PM10) and the following requirements to achieve a goal of "No Visible Emissions".

B. Comply with the following requirements in accordance with San Francisco Department of Public Works Dust Control Order (DPW Order No. 171,378). Failure to comply with DPW Order No. 171,378 shall subject Contractor to fines of $1,000 per day for each day a violation is not corrected.

1. Minimize dust generation to reduce health risks to workers and the public.
2. Mist the immediate excavation area with a water spray to prevent airborne dust particles. Perform continuous water spraying during dust generating activities. Mist or spray in such a way as to prevent puddling or generation of runoff, which could potentially reach storm drains or catchbasins.
3. Minimize the amount of excavated material stored at the site. Remove excavated material from the site no later than the end of each workday. Remove such materials from the site as soon as possible for disposal or recycling in accordance with applicable laws and regulations.
4. Wet all exposed soil surfaces at least 3 times daily during dry weather or more frequently if dust is blowing or if required by the City.
5. Keep the site and adjacent areas clean and perform wet sweeping at the end of each shift.
6. Load haul trucks carrying excavated material so that the material does not extend above the walls or back of the truck bed. Wet before covering and tightly cover the surface of each load before the haul truck leaves the loading area.
7. Clean up spillage on City streets, whether directly or indirectly caused by Contractor's operations.

C. Comply with the requirements of the Bay Area Air Quality Management District (BAAQCD) regulation 6 (for particulate matter and visible emissions), regulation 7 "Odorous Substances," regulation 11 "Hazardous Pollutants," and the California Health and Safety Code division 26 "Air Resource", chapter 3 "Emission Limitations", section 41700 "Prohibited Conduct," and related regulations.

10-1.21 MOBILIZATION

Mobilization shall conform to the provisions in Section 11, "Mobilization," of the Standard Specifications.

10-1.22 BRIDGE CONSTRUCTION SURVEYING

This work shall consist of activities related to construction surveying performed by the Contractor to establish the lines and grades required for completion of the bridge as shown on the plans and as specified in the Standard Specifications and in these special provisions. The Contractor's bridge construction surveying shall include, but not limited to, providing the lines and grades for the bridge foundation, the concrete bridge elements, and the fabrication and erection of steel bridge members. The Contractor shall provide a surveyor licensed in the State of California who shall be responsible for establishing the lines and grades required for the completion of the bridge.

The Contractor's surveyor shall perform the bridge construction surveying to control the work with the accuracy to ensure that the completed work conforms to the lines, grades, and sections shown on the plans, including making allowances for camber, deflection, settlement, and any other factor that may affect the lines and grades of the bridge, and the quality of the ride of the bridge

The second paragraph of Section 51-1.17, "Finishing Bridge Decks," shall not apply. The Contractor shall be responsible for setting the deck elevation control points, which shall be used to establish the grade and cross section of the concrete deck surface.

Attention is directed to Section 55, "Steel Structure," of the Standard Specifications and Section "Steel Structures" elsewhere in these special provisions. The Contractor shall be responsible, through surveying and measurement, for ensuring that the bridge elements, including the steel girders and other steel bridge elements, conform to the tolerances specified in Section 55 of the Standard Specifications and Section "Steel Structures" elsewhere in these specifications.

The Contractor shall make all calculations necessary to establish the lines and grades of the bridge from the bridge control stakes provided by the Engineer. Calculations, survey notes, computer outputs, and other construction survey notes and records shall be neat, legible, accurate, and complete. Copies of all survey calculations, notes and other records shall be submitted to the Engineer two days prior to beginning the work that requires their use. Upon completion of all construction surveying and prior to acceptance of the contract, all computations, survey notes, and other data used to accomplish the work shall be furnished to the Engineer and shall become the property of the State.

The Contractor shall use surveying methods that incorporate surveying software specifically designed for precise positioning of structures to control the geometry of the bridge. The software shall also have user-defined reporting functions for quality control and as-built reporting. The records of the surveying work shall be submitted to the Engineer on a weekly basis and shall become the property of the State.

Before starting any bridge construction survey work, the Contractor shall submit a written Survey Plan for approval by the Engineer detailing the proposed procedures, methods, equipment, and typical stake markings to be used for all Contractor-furnished bridge construction surveying on the project. The Survey Plan shall include working drawings and supplements in conformance to "Working Drawings" of the Standard Specifications. The working drawing submittal shall include, at a minimum, the following:

A. Location of all bridge survey points
B. Bridge alignment
C. Grade sheet formats

The supplement to the working drawing shall show the Contractor's proposed methods of construction surveying and a quality control plan for surveying, and shall include the following:

A. A detailed narrative of the step-by-step surveying control process.
B. A listing of the types of methods and the related item(s) to be constructed.
C. Detailed calculation forms, and a set of calculation for each type of survey method, including sample input and output of computer programs.
D. Identifications of all measuring equipment, procedures.
E. Qualifications of personnel who will carry out construction surveying, and for the Land Surveyor of record.
F. Correlation between the data from geometric control for furnishing steel structures with data for erection and final line and grade.

Prior to submitting the Survey Plan, the Contractor and the Contractor’s Surveyor for this project shall hold a pre-survey meeting with the Engineer to discuss the proposed bridge construction surveying procedures. The pre-survey meeting shall be held within the San Francisco Bay Area.

The Contractor shall allow 15 working days for the Engineer to review the Survey Plan after a complete plan has been submitted. If revisions are required, as determined by the Engineer, the Contractor shall revise and resubmit the Survey Plan. The Contractors shall allow 10 working days for the Engineer to review the revisions. No bridge construction surveying shall begin until the Engineer approves the Survey Plan in writing.

The Survey Plan, and the calculations, survey notes, and other records submitted to establish the exact position of the work shall be completed under the direction of and signed by a Land Surveyor who is licensed by the State of California.

The Contractor shall build the bridge to the lines and grades established by the Contractor’s surveyor. The Engineer may perform quality assurance surveying as the Engineer determines to be necessary to verify the accuracy of the Contractor’s lines and grades. The Contractor shall be responsible that the bridge lines and grade conforms to the requirements shown on the plans and as specified in the Standard Plans and in these special provisions.

STATE FURNISHED SURVEY CONTROL STAKES

The Engineer will provide the bridge survey control stakes at the bridge abutments and bents in accordance with Section 12.5-12, "Major Structure Stakes", of the California Department of Transportation "Surveys Manual." All surveying

references indicated as to be provided by the Structure Representative for surveying, staking or providing line and grade in the "Survey s Manual shall not apply.

Caltrans bridge construction surveying practices outlined in any Caltrans publication shall not apply. For bridges and other structures on this project, other than providing the bridge survey control stakes as provided herein, the Engineer will not provide surveying for any portion of the bridge or structure, including, but not limited to, the bridge piles, pile driving, foundation, substructure, falsework, superstructure and bridge railing.

When the Contractor requires the bridge survey control stakes, the Contractor shall notify the Engineer of such request in accordance with the second paragraph of Section 5-1.07, "Lines and Grades," of the Standard Specifications.

Stakes provided by the Engineer will be marked in accordance with Chapter 12, "Construction Surveys," of the California Department of Transportation "Survey Manual." The Contractor shall be responsible for preserving the State-furnished stakes, in accordance with the third paragraph of Section 5-1.07, "Lines and Grades", of the Standard Specifications.

The Engineer will provide the Contractor a large format (50-scale) copy of the deck contour drawings as shown in the contract plans. The State-furnished deck contour sheets will not include any bridge element plotted therein. The Contractor shall be responsible for generating the bridge grades required for the completion of the bridge from the bridge deck contour sheet. The Contractor shall submit the grade sheets to the Engineer within a reasonable length of time prior to its use. In no event, shall a submittal of less than ten working days be considered a reasonable length of time.

The Contractor shall verify the accuracy of the bridge control stakes provided by the Engineer prior to initiating construction surveying and shall notify the Engineer immediately of any errors, deviations and inconsistencies that may affect the lines and grades of the bridge.

MEASUREMENT AND PAYMENT

The Contractor shall submit to the Engineer, a schedule of values detailing the cost breakdown of the contract lump sum item for bridge construction surveying. The schedule of values shall reflect the items, work, quantities and costs required to do the surveying required by these special provisions. The Contractor shall be responsible for the accuracy of the quantities and costs used in the schedule of values submitted for approval.

The sum of the amounts for the items and work listed in the schedule of values shall be equal to the contract lump sum price for bridge construction surveying. Changes in the schedule of values, due to changes by the Contractor in the items and work listed, shall not result in a change in the contract lump sum price for bridge construction surveying.

The schedule of values will be used only to determine progress payments for bridge construction surveying during the progress of the work. No payment for bridge construction surveying will be made until the Engineer approves the schedule of values in writing.

The contract lump sum price paid for bridge construction surveying shall include full compensation for furnishing all labor, materials, tools, equipment, and incidentals, and for doing all of the required survey work involved in constructing the bridge, as specified in these special provisions.

10-1.23 CONSTRUCTION AREA TRAFFIC CONTROL DEVICES

Flagging, signs, and all other traffic control devices furnished, installed, maintained, and removed when no longer required shall conform to the provisions in Section 12, "Construction Area Traffic Control Devices," of the Standard Specifications and these special provisions.

Category 1 traffic control devices are defined as those devices that are small and lightweight (less than 45 kg), and have been in common use for many years. The devices shall be known to be crashworthy by crash testing, crash testing of similar devices, or years of demonstrable safe performance. Category 1 traffic control devices include traffic cones, plastic drums, portable delineators, and channelizers.

If requested by the Engineer, the Contractor shall provide written self-certification for crashworthiness of Category 1 traffic control devices. Self-certification shall be provided by the manufacturer or Contractor and shall include the following: date, Federal Aid number (if applicable), expenditure authorization, district, county, route and kilometer post of project limits; company name of certifying vendor, street address, city, state and zip code; printed name, signature and title of certifying person; and an indication of which Category 1 traffic control devices will be used on the project. The Contractor may obtain a standard form for self-certification from the Engineer.

Category 2 traffic control devices are defined as those items that are small and lightweight (less than 45 kg), that are not expected to produce significant vehicular velocity change, but may otherwise be potentially hazardous. Category 2 traffic control devices include: barricades and portable sign supports.

Category 2 devices purchased on or after October 1, 2000 shall be on the Federal Highway Administration (FHWA) Acceptable Crashworthy Category 2 Hardware for Work Zones list. This list is maintained by FHWA and can be located at the following internet address: http://safety.fhwa.dot.gov/fourthlevel/hardware/listing.cfm?code=workzone. The Department maintains a secondary list at the following internet address: http://www.dot.ca.gov/hq/traffops/signtech/signdel/pdf.htm.

Category 2 devices that have not received FHWA acceptance, and were purchased before October 1, 2000, may continue to be used until they complete their useful service life or until January 1, 2003, whichever comes first. Category 2 devices in use that have received FHWA acceptance shall be labeled with the FHWA acceptance letter number and the name of the manufacturer by the start of the project. The label shall be readable. After January 1, 2003, all Category 2 devices without a label shall not be used on the project.

If requested by the Engineer, the Contractor shall provide a written list of Category 2 devices to be used on the project at least 5 days prior to beginning any work using the devices. For each type of device, the list shall indicate the FHWA acceptance letter number and the name of the manufacturer.

Full compensation for providing self-certification for crashworthiness of Category 1 traffic control devices and for providing a list of Category 2 devices used on the project and labeling Category 2 devices as specified shall be considered as included in the prices paid for the various contract items of work requiring the use of the Category 1 or Category 2 traffic control devices and no additional compensation will be allowed therefor.

10-1.24 CONSTRUCTION AREA SIGNS

Construction area signs shall be furnished, installed, maintained, and removed when no longer required in conformance with the provisions in Section 12, "Construction Area Traffic Control Devices," of the Standard Specifications and these special provisions.

Attention is directed to the provisions in "Prequalified and Tested Signing and Delineation Materials" of these special provisions. Type II retroreflective sheeting shall not be used on construction area sign panels.

The Contractor shall notify the appropriate regional notification center for operators of subsurface installations at least 2 working days, but not more than 14 calendar days, prior to commencing excavation for construction area sign posts. The regional notification centers include, but are not limited to, the following:

Notification Center	Telephone Number
Underground Service Alert-Northern California (USA)	1-800-642-2444 1-800-227-2600
Underground Service Alert-Southern California (USA)	1-800-422-4133 1-800-227-2600

Excavations required to install construction area signs shall be performed by hand methods without the use of power equipment, except that power equipment may be used if it is determined there are no utility facilities in the area of the proposed post holes.

Sign substrates for stationary mounted construction area signs may be fabricated from fiberglass reinforced plastic as specified under "Prequalified and Tested Signing and Delineation Materials" of these special provisions.

"Tow Away-No Stopping" signs shall be registered with the City of SF, DPT, at (415) 554-9928 and placed at least 72 hours prior to the effective date and time of the tow away-no stopping zone. The tow away-no stopping signs may be installed on existing poles, existing posts, or other supports (including barricades) approved by the Engineer. The tow away-no stopping signs shall be installed only in areas where the work is actively in progress.

Full compensation for "Tow Away-No Stopping" signs and other supports (including barricades) for mounting signs shall be considered as included in the contract lump sum price paid for construction area signs and no separate payment will be made therefor.

The Contractor may be required to cover certain signs during the progress of the work. Signs that are no longer required or that convey inaccurate information to the public shall be immediately covered or removed, or the information shall be corrected. Covers for construction area signs shall be of sufficient size and density to completely block out the complete face of the signs. The retroreflective face of the covered signs shall not be visible either during the day or at night. Covers shall be fastened securely so that the signs remain covered during inclement weather. Covers shall be replaced when they no longer cover the signs properly.

10-1.25 MAINTAINING TRAFFIC

Attention is directed to Sections 7-1.08, "Public Convenience," 7-1.09, "Public Safety," and 12, "Construction Area Traffic Control Devices," of the Standard Specifications and to the provisions in "Public Safety" of these special provisions and these special provisions. Nothing in these special provisions shall be construed as relieving the Contractor from the responsibilities specified in Section 7-1.09.

Lane closures shall conform to the provisions in section "Traffic Control System for Lane Closure" of these special provisions.

Openings shall be provided through bridge falsework for the use of public traffic at each location where falsework is constructed over the streets or routes listed in the following table. The type, minimum width, height, and number of

openings at each location shall conform to the requirements in the table. The width of vehicular openings shall be the clear width between temporary railings or other protective work.

Central Viaduct (Replace)
Bridge No. 34-0077
@ Bent 1, 13th Street

	Number	Width	Height
Vehicle Openings			
EB	1	9.6	4.6
WB	1	7.2	4.6

(Width and Height in meters)

Central Viaduct (Replace)
Bridge No. 34-0077
@ Bent 2, 13th Street

	Number	Width	Height
Vehicle Openings			
EB	1	8.1	4.6
WB	1	7.2	4.6

(Width and Height in meters)

Central Viaduct (Replace)
Bridge No. 34-0077
@ Bent 3, 13th Street

	Number	Width	Height
Vehicle Openings			
EB	1	6.6	4.6
WB	1	7.2	4.6

(Width and Height in meters)

Central Viaduct (Replace)
Bridge No. 34-0077
@ Bent 4, 13th Street

	Number	Width	Height
Vehicle Openings			
EB	1	8.1	4.6
WB	1	7.2	4.6

(Width and Height in meters)

Central Viaduct (Replace)
Bridge No. 34-0077
@ Bent 5, Duboce Avenue

	Number	Width	Height
Vehicle Openings			
EB	1	9.6	4.6
WB	1	9.6	4.6

(Width and Height in meters)

Central Viaduct (Replace)
Bridge No. 34-0077
@ Bent 6, Duboce Avenue

	Number	Width	Height
Vehicle Openings			
WB	1	9.6	4.6

(Width and Height in meters)

The exact location of openings will be determined by the Engineer.

Personal vehicles of the Contractor's employees shall not be parked within the right of way.

The Contractor shall notify local authorities of the Contractor's intent to begin work at least 5 days before work is begun. The Contractor shall cooperate with local authorities relative to handling traffic through the area and shall make arrangements relative to keeping the working area clear of parked vehicles.

Whenever vehicles or equipment are parked on the shoulder within 1.8 m of a traffic lane, the shoulder area shall be closed as shown on the plans.

Lanes shall be closed only during the hours shown on the charts included in this section "Maintaining Traffic." Except work required under Sections 7-1.08 and 7-1.09, work that interferes with public traffic shall be performed only during the hours shown for lane closures. The Contractor shall not close more lanes or area than is required to perform the work in one work period.

No lane closures, shoulder closures, or other traffic restrictions will be allowed on the following days: St. Patrick's Day (2nd Sunday in March), Bay to Breakers Run(3rd Sunday in May), Black & White Ball (1st Saturday in June), Gay Pride Parade (last weekend in June), Up Your Alley Fair (last Saturday in July), SF Marathon (last Sunday in July), Folsom St. Fair (last Sunday in September) and Veteran's Day Parade (1st Sunday in November).

On local streets within the City of San Francisco when construction is not actively in progress the full roadway shall be open to public traffic. The following table shows the lanes and lane widths that are to remain open on the streets listed:

CITY OF SAN FRANCISCO TRAFFIC LANE, PEDESTRIAN WALKWAY AND PARKING REQUIREMENTS

The Contractor shall provide the lanes listed to satisfactorily accommodate vehicular traffic. "Full Rdwy" indicates that all traffic lanes shall remain open. Vehicular/pedestrian access to properties along the project site shall be maintained at all times.

NUMBER OF LANES AND WIDTHS OF LANES TO BE LEFT OPEN					
Street	Time	North-bound	South bound	East-bound	West-bound
Market St	7 AM -10 AM (M-F) 3 PM – 6 PM (M-F) 9 AM – 6 PM (S-S) All Other Times			Full Rdwy Full Rdwy Full Rdwy 1 @ 4.3m	Full Rdwy Full Rdwy Full Rdwy 1 @ 4.3m
Elgin Park Stevenson St	7 AM – 6 PM (M-S) All Other Times	Rd Closed* Full Rdwy	Rd Closed* Full Rdwy		
Valencia St.	7 AM- 9 AM (M-F) 4 PM – 6 PM (M-F) All Other Times	Full Rdwy Full Rdwy 1@ 4.3m***	Full Rdwy Full Rdwy 1@ 4.3m***		
McCopppin St.	7 AM - 9 AM (M-F) 4 PM – 6 PM (M-F) All Other Times			Full Rdwy Full Rdwy 1 @ 3.4m	Full Rdwy Full Rdwy 2 @ 3.0m
Woodward St	7 AM – 6 PM (M-F) All Other Times	Rd Closed* Full Rdwy			
Duboce Ave (Valencia to Mission).	7 AM – 9 AM (M-F) 4 PM – 6 PM (M-F) All Other Times			Full Rdwy Full Rdwy 2 @ 3.0m	Full Rdwy Full Rdwy 2 @ 3.0m
Division St/13th St	7 AM – 9 AM (M-F) 4 PM – 6 PM (M-F) All Other Times			Full Rdwy Full Rdwy 2 @ 3.0m	Full Rdwy Full Rdwy 2 @ 3.0m
Mission St/Otis St (at Duboce)	7 AM – 10 AM (M-F) 3 PM – 6 PM (M-F) All Other Times	Full Rdwy Full Rdwy 2 @ 3.0m	Full Rdwy Full Rdwy 1 @ 3.6m		
So. Van Ness Ave. (at 13th St and at 14th)	7 AM – 10 AM (M-F) 3 PM – 6 PM (M-F) All Other Times	Full Rdwy Full Rdwy 1 @ 3.6m	Full Rdwy Full Rdwy 1 @ 3.6m		
14th St	7 AM – 9 AM (M-F) 4 PM – 6 PM (M-F) All Other Times			Full Rdwy Full Rdwy 1 @ 4.3m	
Otis St.	All times		2 at 3.0m		

* Street may be closed during times of actual work in the street with the Engineer's approval. "Road Closed" signs shall be removed or covered during non-working hours. The Contractor shall set up detour signs according to the approved traffic detour plans as deemed necessary. The Contractor shall comply with Note # 3 below. Provide local access at all times.

** The Contractor shall designate the lane for two-way traffic with flag person at each end of the two-way road segment.

*** Contractor is allowed to close the two-way left turn lane on Valencia Street during these hours.

NOTES:

1) Streets can be completely closed during active construction of structure with the Engineer's approval. Mission St., Valencia St. and Market St. can only be closed on weekends.
2) In addition to the above specified lanes for through traffic, the Contractor shall provide an additional left/right turn lane of 3.4 meter width at the intersection, when there is already an existing separate right/left turn lane.
3) The Contractor shall maintain the required travelway for vehicles in any public street or way and a minimum width of 1.8 meter of clear sidewalk for the pedestrians, at all times. The Contractor may be allowed to store materials and/or equipment for a limited time in the parking strip and/or portion of the sidewalk with written permission of the Engineer and appropriate permits from the Department of Parking and Traffic for use of the public right of way. The Contractor shall maintain adequate signing, barricades, lights etc. at all times. Permission to store the materials shall be limited to the unused materials during working hours or materials needed to resume the next day's work.
4) No work shall interfere with the access of emergency vehicles including those of Police and Fire Departments and ambulances. Local access shall be maintained at all times, by providing a 3.6 meter wide lane on all streets.
5) The Contractor shall notify the Engineer at least 10 days prior to each local street closure.
6) Advance information signs (with dates and time of closure) informing public traffic of future road closures shall be installed in locations to be determined by the Engineer, a minimum of 72 hours in advance of the intended closure.
7) At Market Street, only one sidewalk shall be closed at a time. In order to accomplish this, the Contractor shall coordinate Market Street sidewalk closures with the City of San Francisco's project to construct a boulevard between Market St and Hayes St. The Contractor shall attend weekly meetings with the contractor of this project in order to coordinate sidewalk closures and to avoid other conflicts.
8) In Stage 2, the pedestrian walkway on the south side of 13th Street between Mission Street and South Van Ness Avenue may not be closed between 7:00 AM and 7:00 PM Monday through Friday and on Saturday between 8:00 AM and 12:00 Noon in order to accommodate patrons of the Citi Center Building on Mission Street.
9) Temporary Towaway-No Stopping signs shall be placed no more than 6.1 meters apart.

Designated legal holidays are: January 1st, the third Monday in February, the last Monday in May, July 4th, the first Monday in September, November 11th, Thanksgiving Day, and December 25th. When a designated legal holiday falls on a Sunday, the following Monday shall be a designated legal holiday. When November 11th falls on a Saturday, the preceding Friday shall be a designated legal holiday.

Minor deviations from the requirements of this section concerning hours of work which do not significantly change the cost of the work may be permitted upon the written request of the Contractor, if in the opinion of the Engineer, public traffic will be better served and the work expedited. These deviations shall not be adopted by the Contractor until the Engineer has approved the deviations in writing. All other modifications will be made by contract change order.

Chart No. 1
Ramp Lane Requirements

Location: Southbound SF-101 – On the Mission/Van Ness on-ramp

	a.m.												p.m.												
FROM HOUR TO HOUR	12	1	2	3	4	5	6	7	8	9	10	11	12	1	2	3	4	5	6	7	8	9	10	11	12
Mondays through Thursdays	X	X	X	X	X	X																			
Fridays	X	X	X	X	X	X																			
Saturdays				X	X	X	X																		
Sundays				X	X	X	X	X																	
Day before designated legal holiday																									
Designated legal holidays																									

Legend:

X	Ramp may be closed and traffic detoured
	No work that interferes with public traffic will be allowed

REMARKS: This chart shall be used for restriping operations on the on-ramp and on the downstream connector at the 10th Street on-ramp and gore.

Chart No. 2
Ramp Lane Requirements

Location: Northbound Route 101 – On the connector from Northbound 101 to Northbound 101

	a.m.												p.m.												
FROM HOUR TO HOUR	12	1	2	3	4	5	6	7	8	9	10	11	12	1	2	3	4	5	6	7	8	9	10	11	12
Mondays through Thursdays		X	X	X	X																				
Fridays		X	X	X	X																				
Saturdays			X	X	X	X																			
Sundays			X	X	X	X	X																		
Day before designated legal holiday																									
Designated legal holidays																									

Legend:

X	Ramp may be closed
	No work that interferes with public traffic will be allowed

REMARKS: This chart shall be used for restriping the connector and the 9th Street off-ramp gore. Lane #1 may be closed on Northbound 101 in Hospital curve to support this closure during the same hours as the connector closure. Northbound 101 traffic should be directed to the 7th Street off-ramp.

Chart No. 3
Ramp Lane Requirements

Location: Northbound Route 101 – On the connector from Westbound SF-80 to Northbound 101

	a.m.												p.m.											
FROM HOUR TO HOUR	12	1	2	3	4	5	6	7	8	9	10	11	12	1	2	3	4	5	6	7	8	9	10	11	12
Mondays through Thursdays	1	1	1	1	1	1																			
Fridays	1	1	1	1	1	1																			
Saturdays	1	1	1	1	1	1	1																		
Sundays	1	1	1	1	1	1	1	1																	
Day before designated legal holiday																									
Designated legal holidays																									

Legend:

1	A minimum of one paved ramp lane, not less than 3 m wide, shall be open for use by public traffic
X	Ramp may be closed
	No work that interferes with public traffic will be allowed

REMARKS: This chart for support of striping operations.

Chart No. 4
Ramp Lane Requirements

Location: Northbound Route 101 – On the Mission/Van Ness off-ramp

	a.m.												p.m.											
FROM HOUR TO HOUR	12	1	2	3	4	5	6	7	8	9	10	11	12	1	2	3	4	5	6	7	8	9	10	11	12
Mondays through Thursdays	1	X	X	X	X	1																			1
Fridays	1	X	X	X	X	1																			
Saturdays	1	1	X	X	X	X	1																		
Sundays	1	1	X	X	X	X	1	1																	1
Day before designated legal holiday																									
Designated legal holidays																									

Legend:

1	A minimum of one paved ramp lane, not less than 3 m wide, shall be open for use by public traffic
X	Ramp may be closed
	No work that interferes with public traffic will be allowed

REMARKS: When the off-ramp to Mission/Van Ness is closed, the connector from Westbound SF-80 to Northbound 101 shall be closed, and the on-ramp from 7th Street at Harrison shall also be closed (detour to 10th Street on-ramp).

Pedestrian access facilities shall be provided through construction areas within the right of way as shown on the plans and as specified herein. Pedestrian walkways shall be surfaced with asphalt concrete, portland cement concrete or timber. The surface shall be skid resistant and free of irregularities. Hand railings shall be provided on each side of pedestrian walkways as necessary to protect pedestrian traffic from hazards due to construction operations or adjacent vehicular traffic. Protective overhead covering shall be provided as necessary to insure protection from falling objects and drip from overhead structures.

In addition to the required openings through falsework, pedestrian facilities shall be provided during pile driving, footing, wall, and other bridge construction operations. At least one walkway shall be available at all times. If the Contractor's operations require the closure of one walkway, then another walkway shall be provided nearby, off the traveled roadway.

Railings shall be constructed of wood, S4S, and shall be painted white. Railings and walkways shall be maintained in good condition. Walkways shall be kept clear of obstructions.

Full compensation for providing pedestrian facilities shall be considered as included in the prices paid for the various contract items of work involved and no additional compensation will be allowed therefor.

During steel girder erection, public traffic in the lanes over which girders are being placed shall be routed around the work area by means of a local detour as shown on the plans.

During falsework erection and removal, public traffic in the lanes over which falsework is being erected or removed shall be routed around the work area on adjacent streets by means of a local detour as shown on the plans. Erection shall include all adjustments or removal of falsework components prior to concrete placement that contribute to the horizontal stability of the falsework system**.** Removal shall include lowering falsework, blowing sand from sand jacks, turning screws on screw jacks, and removing wedges.

Rerouting traffic during erection or removal of girders and falsework shall be undertaken only during the hours shown on the lane closure charts.

Regardless of the construction procedure, methods and equipment selected, the Contractor shall have necessary materials and equipment on the site to erect or remove the girders and falsework in any span or over any opening prior to detouring public traffic, and shall erect or remove the girders and falsework in an expeditious manner in order that inconvenience to public traffic will be at a minimum.

The Contractor may occupy one 3-meter lane while placing or removing forms for the superstructure of bridges which are to remain open. Occupation of a traffic lane because of form work at a location will be permitted only during hours shown on the charts included in this section "Maintaining Traffic."

10-1.26 CLOSURE REQUIREMENTS AND CONDITIONS

Lane closures shall conform to the provisions in "Maintaining Traffic" of these special provisions and these special provisions.

The term closure, as used herein, is defined as the closure of a traffic lane or lanes, including ramp or connector lanes, within a single traffic control system.

CLOSURE SCHEDULE

By noon Monday, the Contractor shall submit a written schedule of planned closures for the following week period, defined as Friday noon through the following Friday noon.

The Closure Schedule shall show the locations and times when the proposed closures are to be in effect. The Contractor shall use the Closure Schedule request forms furnished by the Engineer. Closure Schedules submitted to the Engineer with incomplete, unintelligible or inaccurate information will be returned for correction and resubmittal. The Contractor will be notified of disapproved closures or closures that require coordination with other parties as a condition of approval.

Amendments to the Closure Schedule, including adding additional closures, shall be submitted to the Engineer, in writing, at least 3 working days in advance of a planned closure. Approval of amendments to the Closure Schedule will be at the discretion of the Engineer.

The Contractor shall confirm, in writing, all scheduled closures by no later than 8:00 a.m. 3 working days prior to the date on which the closure is to be made. Approval or denial of scheduled closures will be made no later than 4:00 p.m. 2 working days prior to the date on which the closure is to be made. Closures not confirmed or approved will not be allowed.

Confirmed closures that are cancelled due to unsuitable weather may be rescheduled at the discretion of the Engineer for the following working day.

CONTINGENCY PLAN

The Contractor shall prepare a contingency plan for reopening closures to public traffic. The Contractor shall submit the contingency plan for a given operation to the Engineer within one working day of the Engineer's request.

LATE REOPENING OF CLOSURES

If a closure is not reopened to public traffic by the specified time, work shall be suspended in conformance with the provisions in Section 8-1.05, "Temporary Suspension of Work," of the Standard Specifications. The Contractor shall not make any further closures until the Engineer has accepted a work plan, submitted by the Contractor, that will insure that future closures will be reopened to public traffic at the specified time. The Engineer will have 2 working days to accept or reject the Contractor's proposed work plan. The Contractor will not be entitled to any compensation for the suspension of work resulting from the late reopening of closures.

For each 10-minute interval, or fraction thereof past the time specified to reopen the closure, the Department will deduct $1300.00 per interval from moneys due or that may become due the Contractor under the contract.

LATE RE-OPENING OF LOCAL CITY STREET

The Contractor shall restore and maintain the traffic lane requirements in accordance with these Special Provisions. Unless authorized and directed by the Engineer in writing to do otherwise, the Contractor shall pay liquidated damages in the amount of $1000.00 per 10-minute period, or portion thereof per lane for failure to provide the lane requirements, up to a maximum of $20,000 for any 24-hour period.

In addition if the Contractor's failure to provide the required traffic lanes causes traffic congestion requiring immediate action by the City to provide Parking Control Officers or Police to control the traffic manually, the Contractor shall pay the city these costs. The Officers shall be paid at overtime rate for a minimum of two hours. The Officers shall be paid an additional one hour travel time.

COMPENSATION

The Contractor shall notify the Engineer of any delay in the Contractor's operations due to the following conditions, and if, in the opinion of the Engineer, the Contractor's controlling operation is delayed or interfered with by reason of those conditions, and the Contractor's loss due to that delay could not have been avoided by rescheduling the affected closure or by judicious handling of forces, equipment and plant, the delay will be considered a right of way delay within the meaning of Section 8-1.09, "Right of Way Delays," and compensation for the delay will be determined in conformance with the provisions in Section 8-1.09:

A. The Contractor's proposed Closure Schedule is denied and his planned closures are within the time frame allowed for closures in "Maintaining Traffic" of these special provisions, except that the Contractor will not be entitled to any compensation for amendments to the Closure Schedule that are not approved.
B. The Contractor is denied a confirmed closure.

Should the Engineer direct the Contractor to remove a closure prior to the time designated in the approved Closure Schedule, any delay to the Contractor's schedule due to removal of the closure will be considered a right of way delay within the meaning of Section 8-1.09, "Right of Way Delays," and compensation for the delay will be determined in conformance with the provisions in Section 8-1.09.

10-1.27 TRAFFIC CONTROL SYSTEM FOR LANE CLOSURE

A traffic control system shall consist of closing traffic lanes and ramps in conformance with the details shown on the plans, the provisions in Section 12, "Construction Area Traffic Control Devices," of the Standard Specifications, the provisions under "Maintaining Traffic" and "Construction Area Signs" of these special provisions, and these special provisions.

The provisions in this section will not relieve the Contractor of responsibility for providing additional devices or taking measures as may be necessary to comply with the provisions in Section 7-1.09, "Public Safety," of the Standard Specifications.

A portable changeable message sign shall be placed in advance of each traffic control system at locations as directed by the Engineer. The sign shall be in place and in operation before any other component of the traffic control system is placed and shall remain in operation until all other components of the traffic control system are removed. Portable changeable message signs shall conform to the provisions in "Portable Changeable Message Signs," elsewhere in these special provisions.

During traffic stripe operations and pavement marker placement operations using bituminous adhesive, traffic shall be controlled, at the option of the Contractor, with either stationary or moving lane closures. During other operations, traffic shall be controlled with stationary lane closures. Attention is directed to the provisions in Section 84-1.04, "Protection From Damage," and Section 85-1.06, "Placement," of the Standard Specifications.

If components in the traffic control system are displaced or cease to operate or function as specified, from any cause, during the progress of the work, the Contractor shall immediately repair the components to the original condition or replace the components and shall restore the components to the original location.

STATIONARY LANE CLOSURE

When lane and ramp closures are made for work periods only, at the end of each work period, components of the traffic control system, except portable delineators placed along open trenches or excavation adjacent to the traveled way, shall be removed from the traveled way and shoulder. If the Contractor so elects, the components may be stored at selected central locations, designated by the Engineer within the limits of the highway right of way.

Each vehicle used to place, maintain and remove components of a traffic control system on multilane highways shall be equipped with a Type II flashing arrow sign which shall be in operation when the vehicle is being used for placing, maintaining or removing the components. Vehicles equipped with Type II flashing arrow sign not involved in placing, maintaining or removing the components when operated within a stationary type lane closure shall only display the caution display mode. The sign shall be controllable by the operator of the vehicle while the vehicle is in motion. The flashing arrow sign shown on the plans shall not be used on the vehicles which are doing the placing, maintaining and removing of components of a traffic control system and shall be in place before a lane closure requiring the sign's use is completed.

MOVING LANE CLOSURE

Flashing arrow signs used in moving lane closures shall be truck-mounted. Changeable message signs used in moving lane closure operations shall conform to the provisions in Section 12-3.12, "Portable Changeable Message Signs," of the Standard Specifications, except the signs shall be truck-mounted and the full operation height of the bottom of the sign may be less than 2.1 m above the ground, but should be as high as practicable.

Truck-mounted attenuators (TMA) for use in moving lane closures shall be any of the following approved models, or equal:

A. Hexfoam TMA Series 3000, Alpha 1000 TMA Series 1000 and Alpha 2001 TMA Series 2001, manufactured by Energy Absorption Systems, Inc., One East Wacker Drive, Chicago, IL 60601-2076, Telephone (312) 467-6750.

   1. Distributor (Northern): Traffic Control Service, Inc., 8585 Thys Court, Sacramento, CA 95828, Telephone 1-800-884-8274, FAX (916) 387-9734.
   2. Distributor (Southern): Traffic Control Service, Inc., 1881 Betmor Lane, Anaheim, CA 92805, Telephone 1-800-222-8274.

B. Cal T-001 Model 2 or Model 3, manufacturer and distributor: Hexcel Corporation, 11711 Dublin Boulevard, P.O. Box 2312, Dublin, CA 94568, Telephone (510) 828-4200.
C. Renco Rengard Model Nos. CAM 8-815 and RAM 8-815, manufacturer and distributor: Renco Inc., 1582 Pflugerville Loop Road, P.O. Box 730, Pflugerville, TX 78660-0730, Telephone 1-800-654-8182.

Each TMA shall be individually identified with the manufacturer's name, address, TMA model number, and a specific serial number. The names and numbers shall each be a minimum 13 mm high and located on the left (street) side at the lower front corner. The TMA shall have a message next to the name and model number in 13 mm high letters which states, "The bottom of this TMA shall be _____ mm ± _____ mm above the ground at all points for proper impact performance." Any TMA which is damaged or appears to be in poor condition shall not be used unless recertified by the manufacturer. The Engineer shall be the sole judge as to whether used TMAs supplied under this contract need recertification. Each unit shall be certified by the manufacturer to meet the requirements for TMA in conformance with the standards established by the Transportation Laboratory.

Approvals for new TMA designs proposed as equal to the above approved models shall be in conformance with the procedures (including crash testing) established by the Transportation Laboratory. For information regarding submittal of new designs for evaluation contact: Transportation Laboratory, 5900 Folsom Boulevard, Sacramento, California 95819.

New TMAs proposed as equal to approved TMAs or approved TMAs determined by the Engineer to need recertification shall not be used until approved or recertified by the Transportation Laboratory.

PAYMENT

The contract lump sum price paid for traffic control system shall include full compensation for furnishing all labor, materials (including signs), tools, equipment, and incidentals, and for doing all the work involved in placing, removing, storing, maintaining, moving to new locations, replacing and disposing of the components of the traffic control system shown on the plans, as specified in the Standard Specifications and these special provisions, and as directed by the Engineer.

The adjustment provisions in Section 4-1.03, "Changes," of the Standard Specifications shall not apply to the item of traffic control system. Adjustments in compensation for traffic control system will be made only for increased or decreased traffic control system required by changes ordered by the Engineer and will be made on the basis of the cost of the increased or decreased traffic control necessary. The adjustment will be made on a force account basis as provided in Section 9-1.03, "Force Account Payment," of the Standard Specifications for increased work and estimated on the same basis in the case of decreased work.

Traffic control system required by work which is classed as extra work, as provided in Section 4-1.03D of the Standard Specifications, will be paid for as a part of the extra work.

10-1.28 TEMPORARY PAVEMENT DELINEATION

Temporary pavement delineation shall be furnished, placed, maintained, and removed in conformance with the provisions in Section 12-3.01, "General," of the Standard Specifications and these special provisions. Nothing in these special provisions shall be construed as reducing the minimum standards specified in the Manual of Traffic Controls published by the Department or as relieving the Contractor from the responsibilities specified in Section 7-1.09, "Public Safety," of the Standard Specifications.

GENERAL

Whenever the work causes obliteration of pavement delineation, temporary or permanent pavement delineation shall be in place prior to opening the traveled way to public traffic. Laneline or centerline pavement delineation shall be provided at all times for traveled ways open to public traffic. On multilane roadways (freeways and expressways) edgeline delineation shall be provided at all times for traveled ways open to public traffic.

The Contractor shall perform the work necessary to establish the alignment of temporary pavement delineation, including required lines or marks. Surfaces to receive temporary pavement delineation shall be dry and free of dirt and loose material. Temporary pavement delineation shall not be applied over existing pavement delineation or other temporary pavement delineation. Temporary pavement delineation shall be maintained until superseded or replaced with a new pattern of temporary pavement delineation or permanent pavement delineation.

Temporary pavement markers, including underlying adhesive, and removable traffic tape which are applied to the final layer of surfacing or existing pavement to remain in place or which conflicts with a subsequent or new traffic pattern for the area shall be removed when no longer required for the direction of public traffic, as determined by the Engineer.

TEMPORARY LANELINE AND CENTERLINE DELINEATION

Whenever lanelines or centerlines are obliterated and temporary pavement delineation to replace the lines is not shown on the plans, the minimum laneline and centerline delineation to be provided for that area shall be temporary pavement markers placed at longitudinal intervals of not more than 7.3 m. The temporary pavement markers shall be the same color as the laneline or centerline the pavement markers replace. Temporary pavement markers shall be, at the option of the Contractor, one of the temporary pavement markers listed for short term day/night use (14 days or less) or long term day/night use (6 months or less) in "Prequalified and Tested Signing and Delineation Materials" of these special provisions. The temporary pavement markers shall be placed in conformance with the manufacturer's instructions. Temporary pavement markers for long term day/night use (6 months or less) shall be cemented to the surfacing with the adhesive recommended by the manufacturer, except epoxy adhesive shall not be used to place the temporary pavement markers in areas where removal of the temporary pavement markers will be required.

Temporary laneline or centerline delineation consisting entirely of temporary pavement markers listed for short term day/night use (14 days or less), shall be placed on longitudinal intervals of not more than 7.3 m and shall be used for a maximum of 14 days on lanes opened to public traffic. Prior to the end of the 14 days the permanent pavement delineation shall be placed. If the permanent pavement delineation is not placed within the 14 days, the Contractor shall replace the temporary pavement markers and provide additional temporary pavement delineation and shall bear the cost thereof. The additional temporary pavement delineation to be provided shall be equivalent to the pattern specified for the permanent pavement delineation for the area, as determined by the Engineer.

Full compensation for furnishing, placing, maintaining, and removing the temporary pavement markers (including underlying adhesive, layout (dribble) lines to establish alignment of temporary pavement markers or used for temporary laneline and centerline delineation) for those areas where temporary laneline and centerline delineation is not shown on the plans and for providing equivalent patterns of permanent traffic lines for those areas when required, shall be considered as included in the contract prices paid for the items of work that obliterated the laneline and centerline pavement delineation and no separate payment will be made therefor.

TEMPORARY EDGELINE DELINEATION

On multilane roadways (freeways and expressways), whenever edgelines are obliterated and temporary pavement delineation to replace those edgelines is not shown on the plans, the edgeline delineation to be provided for those areas adjacent to lanes open to public traffic shall be as follows:

A. Temporary pavement delineation for right edgelines shall, at the option of the Contractor, consist of either a solid 100-mm wide traffic stripe of the same color as the stripe the temporary edgeline delineation replaces, or traffic cones, portable delineators or channelizers placed at longitudinal intervals not to exceed 30 m.
B. Temporary pavement delineation for left edgelines shall, at the option of the Contractor, consist of either solid 100-mm wide traffic stripe of the same color as the stripe the temporary edgeline delineation replaces, traffic cones, portable delineators or channelizers placed at longitudinal intervals not to exceed 30 m or temporary pavement markers placed at longitudinal intervals of not more than 1.8 m. Temporary pavement markers used for temporary left edgeline delineation shall be one of the types of temporary pavement markers listed for short term day/night use (14 days or less) or long term day/night use (6 months or less) in "Prequalified and Tested Signing and Delineation Materials" of these special provisions.

Traffic stripe (100-mm wide) placed as temporary edgeline delineation which will require removal shall conform to the provisions of "Temporary Traffic Stripe (Tape)" of these special provisions. Where removal of the 100-mm wide traffic stripe will not be required, painted traffic stripe conforming to the provisions of "Temporary Traffic Stripe (Paint)" of these special provisions may be used. The quantity of temporary traffic stripe (tape) or temporary traffic stripe (paint) used for this temporary edgeline delineation will not be included in the quantities of tape or paint to be paid for.

The lateral offset for traffic cones, portable delineators or channelizers used for temporary edgeline delineation shall be as determined by the Engineer. If traffic cones or portable delineators are used as temporary pavement delineation for edgelines, the Contractor shall provide personnel to remain at the project site to maintain the cones or delineators during the hours of the day that the portable delineators are in use.

Channelizers used for temporary edgeline delineation shall be the surface mounted type and shall be orange in color. Channelizer bases shall be cemented to the pavement in the same manner provided for cementing pavement markers to pavement in "Pavement Markers" of these special provisions, except epoxy adhesive shall not be used to place channelizers on the top layer of pavement. Channelizers shall be, at the Contractor's option, one of the surface mount types (900 mm) listed in "Prequalified and Tested Signing and Delineation Materials" of these special provisions.

Temporary edgeline delineation shall be removed when no longer required for the direction of public traffic as determined by the Engineer.

The quantity of channelizers used as temporary edgeline delineation will not be included in the quantity of channelizers to be paid for. Full compensation for furnishing, placing, maintaining and removing temporary edgeline delineation for those areas where temporary edgeline delineation is not shown on the plans shall be considered as included in the contract prices paid for the items of work that obliterated the edgeline pavement delineation and no separate payment will be made therefor.

TEMPORARY TRAFFIC STRIPE (PAINT)

Temporary traffic stripe consisting of painted traffic stripe shall be applied and maintained at the locations shown on the plans. The painted temporary traffic stripe shall be complete in place at the location shown prior to opening the traveled way to public traffic. Removal of painted temporary traffic stripe will not be required.

Temporary painted traffic stripe shall conform to the provisions in Section 84-3, "Painted Traffic Stripes And Pavement Markings," of the Standard Specifications, except for payment. At the option of the Contractor, either one or 2 coats shall be applied regardless of whether on new or existing pavement.

At the Contractor's option, temporary removable striping tape listed in "Prequalified and Tested Signing and Delineation Materials" of these special provisions may be used instead of painted temporary traffic stripes. When traffic stripe tape is used in place of painted temporary traffic stripes, the tape will be measured and paid for by the meter as temporary traffic stripe (paint).

When painted traffic stripe is specified for temporary left edgeline delineation, temporary pavement markers placed at longitudinal intervals of not more than 1.8 m may be used in place of the temporary painted traffic stripe. Temporary pavement markers shall be one of the types of temporary pavement markers listed for long term day/night use (6 months or less) in "Prequalified and Tested Signing and Delineation Materials" of these special provisions. When temporary reflective pavement markers are used in place of temporary painted traffic stripe, payment for those temporary pavement markers will be made on the basis of the theoretical quantity of temporary traffic stripe (paint) required for the left edgeline the temporary pavement markers replace.

TEMPORARY PAVEMENT MARKING (PAINT)

Temporary pavement marking consisting of painted pavement marking shall be applied and maintained at the locations shown on the plans. The painted temporary pavement marking shall be complete in place at the location shown prior to opening the traveled way to public traffic. Removal of painted temporary pavement marking will not be required.

Temporary painted pavement marking shall conform to the provisions in "Paint Traffic Stripes and Pavement Markings" of these special provisions, except for payment. At the option of the Contractor, either one or 2 coats shall be applied regardless whether on new or existing pavement.

At the Contractor's option, temporary removable pavement marking tape or permanent pavement marking tape listed in "Prequalified and Tested Signing and Delineation Materials" of these special provisions may be used instead of painted temporary pavement markings. When pavement marking tape is used, regardless of which type of tape is placed, the tape will be measured and paid for by the square meter as temporary pavement marking (paint).

TEMPORARY PAVEMENT MARKERS

Temporary pavement markers shall be applied at the locations shown on the plans. The pavement markers shall be applied complete in place at the locations shown prior to opening the traveled way to public traffic.

Temporary pavement markers shown on the plans shall be, at the option of the Contractor, one of the temporary pavement markers for long term day/night use (6 months or less) listed in "Prequalified and Tested Signing and Delineation Materials" of these special provisions.

Temporary pavement markers shall be placed in conformance with the manufacturer's instructions and shall be cemented to the surfacing with the adhesive recommended by the manufacturer, except epoxy adhesive shall not be used in areas where removal of the pavement markers will be required.

Where the temporary pavement delineation shown on the plans for lanelines or centerlines consists entirely of a pattern of broken traffic stripe and pavement markers, the Contractor may use groups of the temporary pavement markers for long term day/night use (6 months or less) in place of the temporary traffic stripe tape or painted temporary traffic stripe. The groups of pavement markers shall be spaced as shown on the plans for a similar pattern of permanent traffic line, except pavement markers shown to be placed in the gap between the broken traffic stripe shall be placed as part of the group to delineate the pattern of broken temporary traffic stripe. The kind of laneline and centerline delineation selected by the Contractor shall be continuous within a given location. Payment for those temporary pavement markers used in place of temporary traffic stripe will be made on the basis of the theoretical length of the patterns of temporary traffic stripe (tape) or temporary traffic stripe (paint).

Retroreflective pavement markers conforming to the provisions in "Pavement Markers" of these special provisions may be used in place of temporary pavement markers for long term day/night use (6 months or less) except to simulate patterns of broken traffic stripe. Placement of the retroreflective pavement markers used for temporary pavement markers shall conform to the provisions in "Pavement Markers" of these special provisions except the waiting period provisions before placing the pavement markers on new asphalt concrete surfacing as specified in Section 85-1.06, "Placement," of the Standard Specifications shall not apply and epoxy adhesive shall not be used to place pavement markers in areas where removal of the pavement markers will be required.

MEASUREMENT AND PAYMENT

Temporary traffic stripe (paint) and temporary pavement marking (paint) will be measured and paid for in the same manner specified for paint traffic stripe (1-coat) and paint pavement marking (1-coat) in Section 84-3.06, "Measurement," and Section 84-3.07, "Payment," of the Standard Specifications.

Temporary pavement markers, shown on the plans, will be measured and paid for by the unit in the same manner specified for retroreflective pavement markers in Section 85-1.08, "Measurement," and Section 85-1.09, "Payment," of the Standard Specifications. Temporary pavement markers used for temporary laneline and centerline delineation for areas which are not shown on the plans will not be included in the quantities of temporary pavement markers to be paid for. Full compensation for removing temporary pavement markers, when no longer required, shall be considered as included in the contract unit price paid for temporary pavement marker and no separate payment will be made therefor.

10-1.29 BARRICADE

Barricades shall be furnished, placed and maintained at the locations shown on the plans, specified in the Standard Specifications or in these special provisions or where designated by the Engineer. Barricades shall conform to the provisions in Section 12, "Construction Area Traffic Control Devices," of the Standard Specifications and these special provisions.

Attention is directed to "Prequalified and Tested Signing and Delineation Materials" of these special provisions regarding retroreflective sheeting for barricades.

At the time of completion of the project, certain barricades shall be left in place as directed by the Engineer. In addition to the contract unit price or prices paid for the type or types of barricades, the cost of leaving the barricades in place will be paid for at the contract unit price for barricade (left in place).

Construction area sign and marker panels conforming to the provisions in Section 12-3.06, "Construction Area Signs," of the Standard Specifications shall be installed on barricades in a manner determined by the Engineer at the locations shown on the plans.

Sign panels for construction area signs and marker panels installed on barricades shall conform to the provisions in Section 12-3.06A, "Stationary Mounted Signs," of the Standard Specifications.

Full compensation for furnishing, installing, maintaining, and removing construction area signs and marker panels on barricades shall be considered as included in the contract unit price paid for the type of barricade involved and no separate payment will be made therefor.

Barricades shown on the plans as part of a traffic control system will be paid for as provided in "Traffic Control System for Lane Closure" of these special provisions and will not be included in the count for payment of barricades.

10-1.30 PORTABLE CHANGEABLE MESSAGE SIGN

Portable changeable message signs shall be furnished, placed, operated, and maintained where designated by the Engineer in conformance with the provisions in Section 12, "Construction Area Traffic Control Devices," of the Standard Specifications and these special provisions.

Portable changeable message signs shall be placed in advance of each traffic control system as provided in "Traffic Control System for Lane Closure," elsewhere in these special provisions.

10-1.31 TEMPORARY RAILING

Temporary railing (Type K) shall be placed as shown on the plans, as specified in the Standard Specifications or these special provisions or where ordered by the Engineer and shall conform to the provisions in Section 12, "Construction Area Traffic Control Devices," of the Standard Specifications and these special provisions.

Reflectors on temporary railing (Type K) shall conform to the provisions in "Prequalified and Tested Signing and Delineation Materials" of these special provisions.

Temporary railing (Type K) shall conform to the details shown on Standard Plan T3. Temporary railing (Type K) fabricated prior to January 1, 1993, and conforming to 1988 Standard Plan B11-30 may be used, provided the fabrication date is printed on the required Certificate of Compliance.

Attention is directed to "Public Safety" and "Order of Work" of these special provisions.

Temporary railing (Type K) placed in conformance with the provisions in "Public Safety" of these special provisions will be neither measured nor paid for.

10-1.32 CHANNELIZER

Channelizers shall conform to the provisions in Section 12, "Construction Area Traffic Control Devices," of the Standard Specifications and these special provisions.

Channelizers shall conform to the provisions in "Prequalified and Tested Signing and Delineation Materials" of these special provisions.

When no longer required for the work as determined by the Engineer, channelizers and underlying adhesive used to cement the channelizer bases to the pavement shall be removed. Removed channelizers and adhesive shall become the property of the Contractor and shall be removed from the site of work.

10-1.33 PORTABLE DELINEATORS

Portable delineators shall be furnished, placed and maintained at the locations shown on the plans and shall conform to the provisions of Section 12, "Construction Area Traffic Control Devices," of the Standard Specifications and these special provisions.

Portable delineators shall conform to the provisions for channelizers in "Prequalified and Tested Signing and Delineation Materials" elsewhere in these special provisions.

Portable delineator posts shall be orange in color.

Portable delineators will be measured and paid for in the same manner specified for Channelizers (surface mounted) in Section 12-4.01 of the Standard Specifications.

10-1.34 TEMPORARY CRASH CUSHION MODULE

This work shall consist of furnishing, installing, and maintaining sand filled temporary crash cushion modules in groupings or arrays at each location shown on the plans, as specified in these special provisions or where designated by the

Engineer. The grouping or array of sand filled modules shall form a complete sand filled temporary crash cushion in conformance with the details shown on the plans and these special provisions.

Attention is directed to "Public Safety", and "Order of Work" of these special provisions.

Whenever the work or the Contractor's operations establishes a fixed obstacle, the exposed fixed obstacle shall be protected with a sand filled temporary crash cushion. The sand filled temporary crash cushion shall be in place prior to opening the lanes adjacent to the fixed obstacle to public traffic.

Sand filled temporary crash cushions shall be maintained in place at each location, including times when work is not actively in progress. Sand filled temporary crash cushions may be removed during a work period for access to the work provided that the exposed fixed obstacle is 4.6 m or more from a lane carrying public traffic and the temporary crash cushion is reset to protect the obstacle prior to the end of the work period in which the fixed obstacle was exposed. When no longer required, as determined by the Engineer, sand filled temporary crash cushions shall be removed from the site of the work.

At the Contractor's option, the modules for use in sand filled temporary crash cushions shall be either Energite III Inertial Modules, Fitch Inertial Modules or TrafFix Sand Barrels manufactured after March 31, 1997, or equal:

A. Energite III and Fitch Inertial Modules, manufactured by Energy Absorption Systems, Inc., One East Wacker Drive, Chicago, IL 60601-2076. Telephone 1-312-467-6750, FAX 1-800-770-6755

   1. Distributor (North): Traffic Control Service, Inc., 8585 Thys Court, Sacramento, CA 95828. Telephone 1-800-884-8274, FAX 1-916-387-9734
   2. Distributor (South): Traffic Control Service, Inc., 1881 Betmor Lane, Anaheim, CA 92805. Telephone 1-800-222-8274, FAX 1-714-937-1070

B. TrafFix Sand Barrels, manufactured by TrafFix Devices, Inc., 220 Calle Pintoresco, San Clemente, CA 92672. Telephone 1-949 361-5663, FAX 1-949 361-9205

1. Distributor (North): United Rentals, Inc., 1533 Berger Drive, San Jose, CA 95112. Telephone 1-408 287-4303, FAX 1-408 287-1929
2. Distributor (South): Statewide Safety & Sign, Inc., P.O. Box 1440, Pismo Beach, CA 93448. Telephone 1-800-559-7080, FAX 1-805 929-5786

Modules contained in each temporary crash cushion shall be of the same type at each location. The color of the modules shall be the standard yellow color, as furnished by the vendor, with black lids. The modules shall exhibit good workmanship free from structural flaws and objectionable surface defects. The modules need not be new. Good used undamaged modules conforming to color and quality of the types specified herein may be utilized. If used Fitch modules requiring a seal are furnished, the top edge of the seal shall be securely fastened to the wall of the module by a continuous strip of heavy duty tape.

Modules shall be filled with sand in conformance with the manufacturer's directions, and to the sand capacity in kilograms for each module shown on the plans. Sand for filling the modules shall be clean washed concrete sand of commercial quality. At the time of placing in the modules, the sand shall contain not more than 7 percent water as determined by California Test 226.

Modules damaged due to the Contractor's operations shall be repaired immediately by the Contractor at the Contractor's expense. Modules damaged beyond repair, as determined by the Engineer, due to the Contractor's operations shall be removed and replaced by the Contractor at the Contractor's expense.

Temporary crash cushion modules shall be placed on movable pallets or frames conforming to the dimensions shown on the plans. The pallets or frames shall provide a full bearing base beneath the modules. The modules and supporting pallets or frames shall not be moved by sliding or skidding along the pavement or bridge deck.

A Type R or P marker panel shall be attached to the front of the crash cushion as shown on the plans, when the closest point of the crash cushion array is within 3.6 m of the traveled way. The marker panel, when required, shall be firmly fastened to the crash cushion with commercial quality hardware or by other methods determined by the Engineer.

At the completion of the project, temporary crash cushion modules, sand filling, pallets or frames, and marker panels shall become the property of the Contractor and shall be removed from the site of the work. Temporary crash cushion modules shall not be installed in the permanent work.

Temporary crash cushion modules will be measured by the unit as determined from the actual count of modules used in the work or ordered by the Engineer at each location. Temporary crash cushion modules placed in conformance with the provisions in "Public Safety" of these special provisions and modules placed in excess of the number specified or shown will not be measured nor paid for.

Repairing modules damaged by public traffic will be paid for as extra work as provided in Section 4-1.03D of the Standard Specifications. Modules damaged beyond repair by public traffic, when ordered by the Engineer, shall be removed and replaced immediately by the Contractor. Modules replaced due to damage by public traffic will be measured and paid for as temporary crash cushion module.

If the Engineer orders a lateral move of the sand filled temporary crash cushions and the repositioning is not shown on the plans, moving the sand filled temporary crash cushion will be paid for as extra work as provided in Section 4-1.03D of the Standard Specifications and these temporary crash cushion modules will not be counted for payment in the new position.

The contract unit price paid for temporary crash cushion module shall include full compensation for furnishing all labor, materials (including sand, pallets or frames and marker panels), tools, equipment, and incidentals, and for doing all the work involved in furnishing, installing, maintaining, moving, and resetting during a work period for access to the work, and removing from the site of the work when no longer required (including those damaged by public traffic) sand filled temporary crash cushion modules, complete in place, as shown on the plans, as specified in the Standard Specifications and these special provisions, and as directed by the Engineer.

10-1.35 TEMPORARY CRASH CUSHION (QUADGUARD)

Temporary crash cushion (Quadguard QS9003Y) shall be furnished and installed as shown on the plans and in conformance with the provisions in the Standard Specifications and these special provisions.

Attention is directed to "Public Safety", and "Order of Work" of these special provisions.

The successful bidder can obtain the temporary crash cushion from the following sources:

1. Southern California: Traffic Control Service, Inc., 1881 Betmor Lane, Anaheim, California 92805, Telephone 1-800-222-8274, FAX 1-714-937-1070.
2. Northern California: Traffic Control Service, Inc., 8585 Thys Court, Sacramento, California 95828, Telephone 1-800-884-8274, FAX 1-916-387-9734.

The price quoted by the manufacturer for Temporary Crash Cushion (Quadguard QS9003Y), FOB Pell City, Alabama is $11,672, not including sales tax.

The above prices will be firm for orders placed within 30 days of contract award, and provided delivery is accepted within 90 days after the order is placed.

The monorail for the temporary crash cushion (Quadguard) shall be mounted and anchored directly to the existing pavement at the location shown on the plans. The monorail shall be mounted per manufacturer's recommendations, except that 254 mm steel studs shall be used and shall extend at least 140 mm into the concrete base of the existing structural section. The anchors shall be checked monthly and tightened if necessary. All other installation instructions shall be in conformance with the manufacturer's recommendations.

The W-Beam connections to barrier shall conform to the provisions in Section 83-1, "Railings," of the Standard Specifications.

High strength bolts and nuts for W-Beam connections to barrier shall conform to the requirements in ASTM Designation: A 325 or A 325M and A 563 or A 563M, respectively.

The Contractor shall furnish the Engineer five copies of the manufacturer's plans and instructions in accordance with Section 5-1.02 "Plans and Working Drawings" of the Standard Specifications. Plans and instructions shall be submitted not less than fifteen working days in advance of installation.

The Contractor shall provide the Engineer with a Certificate of Compliance from the manufacturer in conformance with the provisions in Section 6-1.07, "Certificates of Compliance," of the Standard Specifications. The Certificate of Compliance shall certify that the temporary crash cushion conforms to the contract plans and specifications; conforms to the prequalified design and material requirements, and was manufactured in accordance with a quality control program certified in accordance with the ISO 9000 series of Standards.

At the completion of the project the temporary crash cushion (Quadguard QS9003Y), shall be removed and salvaged. Salvaged temporary crash cushion (Quadguard QS9003Y) shall be hauled to the Maintenance Station at 110 Rickard Street, San Francisco and stockpiled. The Contractor shall notify the Engineer and Jon Stidman, telephone (415) 330-6541 a minimum of 48 hours prior to hauling salvaged material to the Maintenance Station.

Temporary crash cushion (Quadguard) will be measured by the unit as determined from actual count in place in the completed work.

The contract unit prices paid for temporary crash cushion (Quadguard) shall include full compensation for furnishing all labor, materials (anchor studs, nuts, washers, and marker panels), tools, equipment, and incidentals, and for doing all the work involved in furnishing, installing and removing and salvaging the temporary crash cushions, complete in place, including transition plate, W-beam connector, and for furnishing high strength bolts and plate washers, as shown on the plans, as specified in the Standard Specifications and these special provisions, and as directed by the Engineer.

10-1.36 EXISTING HIGHWAY FACILITIES

The work performed in connection with various existing highway facilities shall conform to the provisions in Section 15, "Existing Highway Facilities," of the Standard Specifications and these special provisions.

Except as otherwise provided in this section, all earthy material removed in connection with various existing highway facilities shall be disposed of outside the highway right of way in conformance with the provisions as provided in "Hazardous and Non-Hazardous Material Excavation," elsewhere in these special provisions.

Except as otherwise provided for damaged materials in Section 15-2.04, "Salvage," of the Standard Specifications, the materials to be salvaged shall remain the property of the State, and shall be cleaned, packaged, bundled, tagged, and hauled to the District Recycle Center at the San Francisco-Oakland Bay Bridge Toll Plaza Warehouse and stockpiled.

The Contractor shall notify the Engineer and the District Recycle Coordinator, telephone (510) 286-6100 a minimum of 48 hours prior to hauling salvaged material to the Recycle Center.

The recycle center is open from 8:00 AM to 12:00 Noon and from 1:00 PM to 2:30 PM Monday through Friday, except designated holidays.

Full compensation for the disposal of all earthy material in connection with various existing highway facilities outside the highway right of way in conformance with the provisions as provided in "Hazardous and Non-Hazardous Material Excavation," shall be considered as included in the contract prices paid for various existing highway facilities as shown in the Engineeer's Estimate and no additional compensation will be allowed therefore.

Plans of the existing bridges may be requested by fax from the Office of Structure Maintenance and Investigations, 1801 30th Street, Sacramento, CA, Fax (916) 227-8357.

Plans of the existing bridges available to the Contractor are reproductions of the original contract plans with significant changes noted and working drawings and do not necessarily show normal construction tolerances and variances. Where dimensions of new construction required by this contract are dependent on the dimensions of the existing bridges, the Contractor shall verify the controlling field dimensions and shall be responsible for adjusting dimensions of the work to fit existing conditions.

EXISTING PAINT SYSTEMS

The existing paint systems on Bent E-94 of Central Viaduct Bridge No. 34-0077 consist of lead. Any work that disturbs the existing paint system will expose workers to health hazards and will (1) produce debris containing heavy metal in amounts that exceed the thresholds established in Titles 8 and 22 of the California Code of Regulations or (2) produce toxic fumes when heated. All debris produced when the existing paint system is disturbed shall be contained.

Debris Containment and Collection Program

Prior to starting work, the Contractor shall submit a debris containment and collection program to the Engineer in conformance with the provisions in Section 5-1.02, "Plans and Working Drawings," of the Standard Specifications, for debris produced when the existing paint system is disturbed. The program shall identify materials, equipment, and methods to be used when the existing paint system is disturbed and shall include working drawings of containment systems, loads applied to the bridge by containment structures, and provisions for ventilation and air movement for visibility and worker safety.

If the measures being taken by the Contractor are inadequate to provide for the containment and collection of debris produced when the existing paint system is disturbed, the Engineer will direct the Contractor to revise the operations and the debris containment and collection program. The directions will be in writing and will specify the items of work for which the Contractor's debris containment and collection program is inadequate. No further work shall be performed on the items until the debris containment and collection program is adequate and, if required, a revised program has been approved for the containment and collection of debris produced when the existing paint system is disturbed.

The Engineer will notify the Contractor of the approval or rejection of the submitted or revised debris containment and collection program within 2 weeks of submittal of the Contractor's program or revised program.

The State will not be liable to the Contractor for failure to approve all or any portion of an originally submitted or revised debris containment and collection program, nor for delays to the work due to the Contractor's failure to submit an acceptable program.

Full compensation for the debris containment and collection program shall be considered as included in the contract price paid for the item of work causing the existing paint system to be disturbed, and no additional compensation will be allowed therefor.

Safety and Health Provisions

Attention is directed to Section 7-1.06, "Safety and Health Provisions," of the Standard Specifications. Work practices and worker health and safety shall conform to the California Code of Regulations, Title 8, Construction Safety Orders, including Section 1532.1, "Lead."

The Contractor shall furnish the Engineer a written Code of Safe Practices and shall implement an Injury and Illness Prevention Program and a Hazard Communication Program in conformance with the requirements of Construction Safety Orders, Sections 1509 and 1510.

Prior to starting work that disturbs the existing paint system, and when revisions to the program are required by Section 1532.1, "Lead," the Contractor shall submit the compliance programs required in subsection (e)(2), "Compliance Program," of Section 1532.1, "Lead," of the Construction Safety Orders to the Engineer in conformance with the provisions in Section 5-1.02, "Plans and Working Drawings," of the Standard Specifications. The compliance programs shall include the data specified in subsections (e)(2)(B) and (e)(2)(C) of Section 1532.1, "Lead." Approval of the compliance programs by the Engineer will not be required. The compliance programs shall be reviewed and signed by a Certified Industrial Hygienist (CIH) who is certified in comprehensive practice by the American Board of Industrial Hygiene (ABIH). Copies of all air monitoring or jobsite inspection reports made by or under the direction of the CIH in conformance with Section 1532.1, "Lead," shall be furnished to the Engineer within 10 days after the date of monitoring or inspection.

Full compensation for furnishing the Engineer with the submittals and for implementing the programs required by this safety and health section shall be considered as included in the contract price paid for the item of work causing the existing paint system to be disturbed, and no additional compensation will be allowed therefor.

Debris Handling

Debris produced when the existing paint system is disturbed shall not be temporarily stored on the ground. Debris accumulated inside the containment system shall be removed before the end of each work shift. Debris shall be stored in approved, leakproof containers and shall be handled in such a manner that no spillage will occur.

Disposal of debris produced when the existing paint system is disturbed shall be performed in conformance with all applicable Federal, State, and Local hazardous waste laws. Laws that govern this work include:

A. Health and Safety Code, Division 20, Chapter 6.5 (California Hazardous Waste Control Act).
B. Title 22; California Code of Regulations, Division 4.5, (Environmental Health Standards for the Management of Hazardous Waste).
C. Title 8, California Code of Regulations.

Except as otherwise provided herein, debris produced when the existing paint system is disturbed shall be disposed of by the Contractor at an approved Class 1 disposal facility in conformance with the requirements of the disposal facility operator. The debris shall be hauled by a transporter currently registered with the California Department of Toxic Substances Control using correct manifesting procedures and vehicles displaying current certification of compliance. The Contractor shall make all arrangements with the operator of the disposal facility and perform any testing of the debris required by the operator.

At the option of the Contractor, the debris produced when the existing paint system is disturbed may be disposed of by the Contractor at a facility equipped to recycle the debris, subject to the following requirements:

A. Copper slag abrasive blended by the supplier with a calcium silicate compound shall be used for blast cleaning.
B. The debris produced when the existing paint system is disturbed shall be tested by the Contractor to confirm that the solubility of the heavy metals is below regulatory limits and that the debris may be transported to the recycling facility as a non-hazardous waste.
C. The Contractor shall make all arrangements with the operator of the recycling facility and perform any testing of the debris produced when the existing paint system is disturbed that is required by the operator.

Full compensation for debris handling and disposal shall be considered as included in the contract price paid for the item of work causing the existing paint system to be disturbed, and no additional compensation will be allowed therefor.

Work Area Monitoring

The Contractor shall perform work area monitoring of the ambient air in and around the work area at the bridge site to verify the effectiveness of the containment system. The work area monitoring shall consist of collecting, analyzing, and reporting air test results and recommending the required corrective action when specified exposure levels are exceeded. The work area monitoring shall be carried out under the direction of a CIH. The samples shall be collected at locations designated by the Engineer.

Air samples shall be collected and analyzed in conformance with National Institute for Occupational Safety and Health (NIOSH) methods. Air samples for lead detection shall be collected and analyzed in conformance with NIOSH Method 7082, with a limit of detection of at least 0.5 $\mu g/m^3$. Air samples for detection of other metals shall be collected and analyzed in conformance with NIOSH Method 7300, with a limit of detection of at least one percent of the appropriate Permissible Exposure Limits (PELs) specified by the California/Occupational Safety and Health Administration (Cal/OSHA). Alternative methods of sample collection and analysis, with equivalent limits of detection, may be used at the option of the Contractor.

The airborne metals exposure, outside either the containment system or work areas, shall not exceed the lower of either: (1) 10 percent of the Action Level specified for lead by Section 1532.1, "Lead," of the Construction Safety Orders, or (2) 10 percent of the appropriate PELs specified for other metals by Cal/OSHA.

The air samples shall be collected at least once per week during progress of work that disturbs the existing paint system. All air samples shall be analyzed within 48 hours at a facility accredited by the Environmental Lead Laboratory Accreditation Program of the American Industrial Hygiene Association (AIHA). When corrective action is recommended by the CIH, additional samples may be required by the Engineer to be taken, at the Contractor's expense.

In areas where there is no exposed soil, there shall be no visible increase in the concentrations of heavy metal on the area affected when the existing paint system is disturbed. Any visible increase in the concentrations of heavy metal, after completion of work that disturbs the existing paint system, shall be removed at the Contractor's expense.

Air sample laboratory analysis results, including results of additional samples taken after corrective action as recommended by the CIH, shall be submitted to the Engineer. The results shall be submitted both verbally within 48 hours after sampling and in writing with a copy to the Contractor, within 5 days after sampling. Sample analysis reports shall be prepared by the CIH as follows:

A. For air sample laboratory analysis results, the date and location of sample collection, sample number, contract number, bridge number, full name of the structure as shown on the contract plans, and District-County-Route-Kilometer Post will be required.
B. For air sample laboratory analysis results, the following will be required:

    1. List of emission control measures in place when air samples were taken.
    2. Air sample results shall be compared to the appropriate PELs.
    3. Chain of custody forms.
    4. Corrective action recommended by the CIH to ensure airborne metals exposure, outside either the containment system or work areas, is within specified limits.

Work area monitoring will be paid for on the basis of a lump sum price.

The contract lump sum price paid for work area monitoring shall include full compensation for furnishing all labor, materials, tools, equipment, and incidentals, and for doing all the work involved in collecting and analyzing samples of ambient air for heavy metals, complete in place, including reporting the test results, as shown on the plans, as specified in the Standard Specifications and these special provisions, and as directed by the Engineer.

Containment System

At the option of the Contractor, the containment system shall consist of either (1) a ventilated containment structure, (2) vacuum shrouded surface preparation equipment and drapes, tarps, or other materials, or (3) an equivalent containment system. The containment system shall contain all water, resulting debris, and visible dust produced when the existing paint system is disturbed.

The containment system shall provide the clearances specified under "Maintaining Traffic" of these special provisions, except that when no clearances are specified, a vertical clearance of 4.6 m and a horizontal clearance of 9.8 m shall be provided for the passage of public traffic.

Falsework or supports for the ventilated containment structure shall not extend below the vertical clearance level nor to the ground line at locations within the roadbed.

The ventilated containment structure shall conform to the provisions for falsework in Section 51-1.06, "Falsework," of the Standard Specifications.

The minimum total design load of the ventilated containment structure shall consist of the sum of the dead and live vertical loads. Dead load shall consist of the actual load of the ventilated containment structure. Live loads shall consist of a uniform load of not less than 2160 Pa, which includes 960 Pa of sand load, applied over the area supported, and in addition, a moving 4.5 kN concentrated load shall be applied to produce maximum stress in the main supporting elements. Assumed horizontal loads need not be included in the design of the ventilated containment structure.

The ventilated containment structure shall be supported with either rigid or flexible supports. The rigid or flexible containment materials on the containment structure shall retain airborne particles but may allow airflow through the containment materials. Flexible materials shall be supported and fastened to prevent escape of abrasive and blast materials due to whipping from traffic or wind and to maintain clearances.

All mating joints between the ventilated containment structure and the bridge shall be sealed. Sealing may be by overlapping of seams when using flexible materials or by using tape, caulking, or other sealing measures.

Multiple flap overlapping door tarps shall be used at entry ways to the ventilated containment structure to prevent dust or debris from escaping.

Baffles, louvers, flapper seals, or ducts shall be used at make-up air entry points to the ventilated containment structure to prevent escape of abrasives and resulting surface preparation debris.

The ventilated containment structure shall be properly maintained while work is in progress and shall not be changed from the approved working drawings without prior approval of the Engineer.

The ventilation system in the ventilated containment structure shall be of the forced input airflow type with fans or blowers.

Negative air pressure shall be employed within the ventilated containment structure and will be verified by visual methods by observing the concave nature of the containment materials while taking into account wind effects or by using smoke or other visible means to observe airflow. The input airflow shall be properly balanced with the exhaust capacity throughout the range of operations.

The exhaust airflow of the ventilation system in the ventilated containment structure shall be forced into dust collectors (wet or dry) or bag houses.

Full compensation for the containment system shall be considered as included in the contract price paid for the item of work causing the existing paint system to be disturbed, and no additional compensation will be allowed therefor.

Protective Work Clothing and Hygiene Facilities

Wherever there is exposure or possible exposure to heavy metals or silica dust at the bridge site, the Contractor shall, for State personnel: (1) furnish, clean, and replace protective work clothing and (2) provide access to hygiene facilities. The furnishing, cleaning, and replacement of protective work clothing and providing access to hygiene facilities shall conform to the provisions of subsections (g), "Protective work clothing and equipment," and (i), "Hygiene facilities and practices," of Section 1532.1, "Lead," of the Construction Safety Orders, and will be required for no more than 3 people.

The protective work clothing and access to hygiene facilities shall be provided during exposure or possible exposure to heavy metals or silica dust at the bridge site and during the application of the undercoats of paint.

Protective work clothing and hygiene facilities shall be inspected and approved by the Engineer before being used by State personnel.

The protective work clothing shall remain the property of the Contractor at the completion of the contract.

Full compensation for protective work clothing and access to hygiene facilities for State personnel shall be considered as included in the contract price paid for the item of work causing the existing paint system to be disturbed, and no additional compensation will be allowed therefor.

ABANDON CULVERT

Existing culverts, where shown on the plans to be abandoned, shall be abandoned in place or, at the option of the Contractor, the culverts shall be removed and disposed of. Resulting openings into existing structures that are to remain in place shall be plugged with commercial quality concrete containing not less than 300 kg of cement per cubic meter.

Abandoning culverts in place shall conform to the following:

A. Culverts that intersect the side slopes shall be removed to a depth of not less than one meter measured normal to the plane of the finished side slope, before being abandoned.
B. Culverts 300 mm in diameter and larger, shall, at the Contractor's option, be backfilled with either sand, controlled low strength material or slurry cement backfill conforming to the provisions in Section 19-3.062, "Slurry Cement Backfill," of the Standard Specifications by any method acceptable to the Engineer that completely fills the pipe. Sand backfill material shall be clean, free draining, and free from roots and other deleterious substances.
C. The ends of culverts shall be securely closed by a 150 mm thick tight fitting plug or wall of commercial quality concrete.

Culverts shall not be abandoned until their use is no longer required. The Contractor shall notify the Engineer in advance of any intended culvert abandonment.

If the Contractor elects to remove and dispose of a culvert which is specified to be abandoned, as provided herein, backfill specified for the pipe will be measured and paid for in the same manner as if the culvert has been abandoned in place.

Full compensation for concrete plugs, pipe removal, structure excavation, and backfill (including sand, controlled low strength material or slurry cement backfill) shall be considered as included in the contract unit price paid for abandon culvert and no additional compensation will be allowed therefor.

ABANDON INLET

Existing drainage inlets, where shown on the plans to be abandoned, shall be abandoned.

The top portion of the inlets shall be removed to a depth of 0.3 m below finished grade.

Removed frames and grates shall be disposed of.

REMOVE FENCE

Existing chain link fence, where shown on the plans to be removed, shall be removed and disposed of.

Access control shall be maintained at all times. Before leaving any work area, all fencing necessary to ensure the integrity of the original fenced areas shall be provided such that there are no gaps left between the existing fence and the fence being installed. Whether permanent or temporary fencing is used, shall be at the Contractor's option.

Full compensation for providing access control shall be considered as included in the contract price paid per meter for remove fence and no additional compensation will be allowed therefor.

REMOVE CHANNELIZERS

Existing channelizers, when no longer required and as directed by the Engineer, shall be removed and disposed of.

REMOVE CRASH CUSHION (SAND FILLED)

Existing crash cushion (sand filled), where shown on the plans to be removed, shall be removed and disposed of.

Removing sand filled crash cushions, regardless of the number of modules in each sand filled crash cushion, will be measured and paid for by the unit as remove crash cushion (sand filled). The quantity to be paid for will be determined from actual count of the units in place.

REMOVE PAVEMENT MARKER

Existing pavement markers, including underlying adhesive, when no longer required for traffic lane delineation as determined by the Engineer, shall be removed and disposed of.

REMOVE TRAFFIC STRIPE AND PAVEMENT MARKING

Traffic stripe and pavement marking shall be removed at the locations shown on the plans and as directed by the Engineer.

Attention is directed to "Water Pollution Control" of these special provisions.

Waste from removal of yellow thermoplastic and yellow painted traffic stripe and pavement marking contains lead chromate in average concentrations greater than or equal to 5 mg/L Soluble Lead or 1000 mg/kg Total Lead. Yellow thermoplastic and yellow painted traffic stripe and pavement marking exist within the project limits as shown on the plans. Residue produced from when yellow thermoplastic and yellow paint are removed may contain heavy metals in concentrations that exceed thresholds established by the California Health and Safety Code and may produce toxic fumes when heated.

The removed yellow thermoplastic and yellow paint shall be disposed of at a Class 1 disposal facility in conformance with the requirements of the disposal facility operator within 15 days after accumulating 100 kg of residue and dust. The Contractor shall make necessary arrangements with the operator of the disposal facility to test the yellow thermoplastic and yellow paint residue as required by the facility and these special provisions. Testing shall include, at a minimum, (1) Total Lead and Chromium by EPA Method 7000 series and (2) Soluble Lead and Chromium by California Waste Extraction Test. From the first 3360 L of waste or portion thereof, if less than 3360 L of waste are produced, a minimum of four randomly selected samples shall be taken and analyzed. From each additional 840 L of waste or portion thereof, if less than 840 L are produced, a minimum of one additional random sample shall be taken and analyzed. The Contractor shall submit the name and location of the disposal facility and analytical laboratory along with the testing requirements to the Engineer not less than 5 days prior to the start of removal of yellow thermoplastic and yellow painted traffic stripe and pavement marking. The analytical laboratory shall be certified by the Department of Health Services Environmental Laboratory Accreditation Program. Test results shall be provided to the Engineer for review prior to signing a waste profile as requested by the disposal facility, prior to issuing an EPA identification number, and prior to allowing removal of the waste from the site.

The Contractor shall prepare a project specific Lead Compliance Plan to prevent or minimize worker exposure to lead while handling removed yellow thermoplastic and yellow paint residue. Attention is directed to Title 8, California Code of Regulations, Section 1532.1, "Lead," for specific Cal-OSHA requirements when working with lead.

The Lead Compliance Plan shall contain the elements listed in Title 8, California Code of Regulations, Section 1532.1(e)(2)(B). Before submission to the Engineer, the Lead Compliance Plan shall be approved by an Industrial Hygienist certified in Comprehensive Practice by the American Board of Industrial Hygiene. The Plan shall be submitted to the Engineer at least 7 days prior to beginning removal of yellow thermoplastic and yellow paint.

Prior to removing yellow thermoplastic and yellow painted traffic stripe and pavement marking, personnel who have no prior training, including State personnel, shall complete a safety training program provided by the Contractor that meets the requirements of Title 8, California Code of Regulations, Section 1532.1, "Lead," and the Contractor's Lead Compliance Program.

Personal protective equipment, training, and washing facilities required by the Contractor's Lead Compliance Plan shall be supplied to State personnel by the Contractor. The number of State personnel will be 3.

Where grinding or other methods approved by the Engineer are used to remove yellow thermoplastic and yellow painted traffic stripe and pavement marking, the removed residue, including dust, shall be contained and collected immediately. Sweeping equipment shall not be used. Collection shall be by a high efficiency particulate air (HEPA) filter equipped vacuum attachment operated concurrently with the removal operations or other equally effective methods approved by the Engineer. The Contractor shall submit a written work plan for the removal, storage, and disposal of yellow thermoplastic and yellow painted traffic stripe and pavement marking to the Engineer for approval not less than 7 days prior to the start of the removal operations. Removal operations shall not be started until the Engineer has approved the work plan.

The removed yellow thermoplastic and yellow painted traffic stripe and pavement marking residue shall be stored and labeled in covered containers. Labels shall conform to the provisions of Title 22, California Code of Regulations, Sections 66262.31 and 66262.32. Labels shall be marked with date when the waste is generated, the words "Hazardous Waste", composition and physical state of the waste (for example, asphalt grindings with thermoplastic or paint), the word "Toxic", the name and address of the Engineer, the Engineer's telephone number, contract number, and Contractor or subcontractor. The containers shall be a type approved by the United States Department of Transportation for the transportation and temporary storage of the removed residue. The containers shall be handled so that no spillage will occur. The containers shall be stored in a secured enclosure at a location within the project limits until disposal, as approved by the Engineer.

If the yellow thermoplastic and yellow painted traffic stripe and pavement marking residue is transported to a Class 1 disposal facility, a manifest shall be used, and the transporter shall be registered with the California Department of Toxic Substance Control. The Engineer will obtain the United States Environmental Protection Agency Identification Number and sign all manifests as the generator within 2 working days of receiving sample test results and approving the test methods.

The Contractor shall assume that the yellow paint removed is not regulated under the Federal Resource Conservation and Recovery Act (RCRA). Additional disposal costs for removal residue regulated under RCRA, as determined by test results required by the disposal facility, will be paid for as extra work as provided in Section 4-1.03D, "Extra Work," of the Standard Specifications.

Nothing in these special provisions shall relieve the Contractor of the Contractor's responsibilities as specified in Section 7-1.09, "Public Safety," of the Standard Specifications.

The contract lump sum price paid for Lead Compliance Plan (Remove Yellow Traffic Stripe) shall include full compensation for furnishing all labor, materials, tools, equipment, and incidentals and for doing all the work involved in preparing the Lead Compliance Plan, including paying the Certified Industrial Hygienist, and for providing personnel protective equipment, training, air monitoring, and medical surveillance, as specified in the Standard Specifications and these special provisions, and as directed by the Engineer.

Full compensation for providing a written work plan for the removal, storage, and disposal of yellow thermoplastic and yellow painted traffic stripe and pavement marking shall be considered as included in the contract items paid per meter for remove yellow thermoplastic traffic stripe and remove yellow painted traffic stripe or per square meter for remove yellow thermoplastic pavement marking and yellow painted pavement marking and no separate payment will be made therefor.

REMOVE DRAINAGE FACILITY

Existing culverts, inlets and manholes where shown on the plans to be removed, shall be completely removed and disposed of.

REMOVE ROADSIDE SIGN AND SIGN OVERLAY

Existing roadside signs and sign overlay, at those locations shown on the plans to be removed, shall be removed and disposed of.

Existing roadside signs or sign overlay shall not be removed until replacement signs have been installed or until the existing signs are no longer required for the direction of public traffic, unless otherwise directed by the Engineer.

RECONSTRUCT CHAIN LINK FENCE

Existing chain link fence, at the locations shown on the plans, shall be removed and reconstructed.

Fence removed in excess of that required for reconstructing chain link fence shall be disposed of.

Full compensation for removing and disposing of excess fence shall be considered as included in the contract price paid per meter for reconstruct chain link fence and no separate payment will be made therefor.

ADJUST MANHOLE

Adjust manhole shall be in accordance with the provisions in Section 15-2.05, "Reconstruction," of the Standard Specifications and these special provisions.

Portland cement concrete shall be minor concrete or may be produced from commercial quality concrete containing not less than 350 kilograms of cement per cubic meter.

Adjustment of manhole shall be performed prior to paving and shall be limited to the area to be paved or surfaced during the working day in which the adjustment is performed. The top of the manhole cover shall be protected from the asphalt concrete during paving operations by means of heavy plywood covers, steel plate covers or by other methods approved by the Engineer. Excess paving material shall be removed prior to rolling.

The contract unit price paid for adjust manhole shall include full compensation for furnishing all labor, materials, tools, equipment, and incidentals, and for doing all the work involved in adjusting manhole, complete in place, as shown on the plans, as specified in the Standard Specifications and these special provisions, and as directed by the Engineer.

REMOVE BASE AND SURFACING

Existing PCC base and bituminous surfacing shown on the plans to be removed, shall be removed to the bottom of the PCC base. Resulting holes and depressions shall be backfilled with earthy material selected from excavation to the lines and grade established by the Engineer.

The material removed shall be disposed of outside the highway right of way in conformance with the provisions as provided in "Hazardous and Non-Hazardous Material Excavation," elsewhere in these special provisions.

Removing PCC base and surfacing will be measured by the cubic meter in the same manner specified for roadway excavation in conformance with the provisions in Section 19, "Earthwork," of the Standard Specifications and will be paid for at the contract price per cubic meter for remove base and surfacing.

Full compensation for the disposal of PCC base and asphalt concrete surfacing outside the highway right of way in conformance with the provisions as provided in "Hazardous and Non-Hazardous Material Excavation," shall be considered as included in the contract price paid per cubic meter for remove base and surfacing and no additional compensation will be allowed therefore.

REMOVE ASPHALT CONCRETE SURFACING

Existing bituminous surfacing shown on the plans to be removed, shall be removed to a depth of the existing surfacing. Resulting holes and depressions shall be backfilled with earthy material to the lines and grade established by the Engineer.

The material removed shall be disposed of outside the highway right of way in conformance with the provisions as provided in "Hazardous and Non-Hazardous Material Excavation," elsewhere in these special provisions.

Removing asphalt concrete surfacing will be measured by the cubic meter in the same manner specified for roadway excavation in conformance with the provisions in Section 19, "Earthwork," of the Standard Specifications and will be paid for at the contract price per cubic meter for remove asphalt concrete surfacing.

Full compensation for the disposal of asphalt concrete surfacing outside the highway right of way in conformance with the provisions as provided in "Hazardous and Non-Hazardous Material Excavation," shall be considered as included in the contract price paid per cubic meter for remove asphalt concrete surfacing and no additional compensation will be allowed therefore.

COLD PLANE ASPHALT CONCRETE PAVEMENT

Existing asphalt concrete pavement shall be cold planed at the locations and to the dimensions shown on the plans.

Planing asphalt concrete pavement shall be performed by the cold planing method. Planing of the asphalt concrete pavement shall not be done by the heater planing method.

Cold planing machines shall be equipped with a cutter head not less than 750 mm in width and shall be operated so that no fumes or smoke will be produced. The cold planing machine shall plane the pavement without requiring the use of a heating device to soften the pavement during or prior to the planing operation.

The depth, width, and shape of the cut shall be as shown on the typical cross sections or as designated by the Engineer. The final cut shall result in a uniform surface conforming to the typical cross sections. The outside lines of the planed area shall be neat and uniform. Planing asphalt concrete pavement operations shall be performed without damage to the surfacing to remain in place.

Planed widths of pavement shall be continuous except for intersections at cross streets where the planing shall be carried around the corners and through the conform lines. Following planing operations, a drop-off of more than 45 mm will not be allowed between adjacent lanes open to public traffic.

Where transverse joints are planed in the pavement at conform lines no drop-off shall remain between the existing pavement and the planed area when the pavement is opened to public traffic. If asphalt concrete has not been placed to the level of existing pavement before the pavement is to be opened to public traffic a temporary asphalt concrete taper shall be constructed. Asphalt concrete for temporary tapers shall be placed to the level of the existing pavement and tapered on a slope of 1:30 (Vertical: Horizontal) or flatter to the level of the planed area.

Asphalt concrete for temporary tapers shall be commercial quality and may be spread and compacted by any method that will produce a smooth riding surface. Temporary asphalt concrete tapers shall be completely removed, including the removal of loose material from the underlying surface, before placing the permanent surfacing. The removed material shall be disposed of outside the highway right of way in conformance with the provisions in Section 7-1.13, "Disposal of Material Outside the Highway Right of Way," of the Standard Specifications.

Operations shall be scheduled so that not more than 7 days shall elapse between the time when transverse joints are planed in the pavement at the conform lines and the permanent surfacing is placed at the conform lines.

The material planed from the roadway surface, including material deposited in existing gutters or on the adjacent traveled way, shall be disposed of in conformance with the provisions in Section 7-1.13, "Disposal of Material Outside the Highway Right of Way," of the Standard Specifications. Removal operations of cold planed material shall be concurrent with planing operations and follow within 15 m of the planer, unless otherwise directed by the Engineer.

Cold plane asphalt concrete pavement will be measured by the square meter. The quantity to be paid for will be the actual area of surface cold planed irrespective of the number of passes required to obtain the depth shown on the plans.

The contract price paid per square meter for cold plane asphalt concrete pavement shall include full compensation for furnishing all labor, materials, tools, equipment, and incidentals, and for doing all the work involved in cold planing asphalt concrete surfacing and disposing of planed material, including furnishing the asphalt concrete for and constructing, maintaining, removing, and disposing of temporary asphalt concrete tapers, as specified in the Standard Specifications and these special provisions and as directed by the Engineer.

EXISTING HIGHWAY IRRIGATION FACILITIES

Existing irrigation facilities within the limits of work shall remain in place. Irrigation facilities that are damaged by the Contractor's operation shall be reported immediately to the Engineer.

Water shall be maintained in conformance with the provisions in Section 20-5.025, "Maintain Existing Water Supply," of the Standard Specifications.

BRIDGE REMOVAL

Removing bridges or portions of bridges shall conform to the provisions in Section 15-4, "Bridge Removal," of the Standard Specifications and these special provisions.

BRIDGE REMOVAL (PORTION)
CENTRAL VIADUCT (REPLACE)
Bridge No. 34-0077

Bridge removal (portion) shall consist of removing portions of existing concrete barriers. bridge decks, and footings as shown on the plans. At the locations where the new cast-in-drilled-hole concrete piling interferes with the existing piles as shown on the plans, the existing piles shall be completely removed and backfilled with slurry cement backfill. Slurry cement backfill shall conform to the provisions in Section 19-3.062, "Slurry Cement Backfill," of the Standard Specifications.

Removed materials that are not to be salvaged or used in the reconstruction shall become the property of the Contractor and shall be disposed of in conformance with the provisions in Section 7-1.13, "Disposal of Material Outside the Highway Right of Way," of the Standard Specifications.

Full compensation for slurry cement backfill shall be considered as included in the contract lump sum price paid for bridge removal (portion) and no additional compensation will be allowed therefor.

The Contractor shall submit a complete bridge removal plan to the Engineer for each bridge listed above, detailing procedures, sequences, and all features required to perform the removal in a safe and controlled manner.

The bridge removal plan shall include, but not be limited to the following:

A. The removal sequence, including staging of removal operations.
B. Equipment locations on the structure during removal operations.
C. Temporary support shoring or temporary bracing.
D. Locations where work is to be performed over traffic, utilities.
E. Details, locations, and types of protective covers to be used.
F. Measures to assure that people, property, utilities, and improvements will not be endangered.
G. Details and measures for preventing material, equipment, and debris from falling onto public traffic.

When protective covers are required for removal of portions of a bridge, or when superstructure removal works on bridges are involved, the Contractor shall submit working drawings, with design calculations, to the Engineer for the proposed bridge removal plan, and the bridge removal plan shall be prepared and signed by an engineer who is registered as a Civil Engineer in the State of California. The design calculations shall be adequate to demonstrate the stability of the structure during all stages of the removal operations. Calculations shall be provided for each stage of bridge removal and shall include dead and live load values assumed in the design of protective covers.

Temporary support shoring, temporary bracing, and protective covers, as required, shall be designed and constructed in conformance with the provisions in Section 51-1.06, "Falsework," of the Standard Specifications and these special provisions.

The assumed horizontal load to be resisted by the temporary support shoring and temporary bracing, for removal operations only, shall be the sum of the actual horizontal loads due to equipment, construction sequence or other causes, and an allowance for wind, but in no case shall the assumed horizontal load to be resisted in any direction be less than 5 percent of the total dead load of the structure to be removed.

The bridge removal plan shall conform to the provisions in Section 5-1.02, "Plans and Working Drawings," of the Standard Specifications. The number of sets of drawings, design calculations, and the time for reviewing bridge removal plans shall be the same as specified for falsework working drawings in Section 51-1.06A, "Falsework Design and Drawings," of the Standard Specifications.

The following additional requirements apply to the removal of bridges or portions of bridges whenever the removal work is to be performed over public traffic or railroad property:

A. A protective cover shall be constructed before beginning bridge removal work. The protective cover shall be supported by shoring, falsework, or members of the existing structure. The Contractor shall be responsible for designing and constructing safe and adequate protective covers, shoring, and falsework with sufficient strength and rigidity to support the entire load to be imposed.
B. The construction and removal of the protective cover, and the installation and removal of temporary railings shall conform to the provisions in "Maintaining Traffic," "Temporary Railings" of these special provisions.
C. Bridge removal methods shall be described in the working drawings, supported by calculations with sufficient details to substantiate live loads used in the protective cover design. Dead and live load values assumed for designing the protective cover shall be shown on the working drawings.
D. The protective cover shall prevent any materials, equipment, or debris from falling onto public traffic. The protective cover shall have a minimum strength equivalent to that provided by good, sound Douglas fir planking having a nominal thickness of 50 mm. Additional layers of material shall be furnished as necessary to prevent fine materials or debris from sifting down upon the traveled way and shoulders.
E. During the removal of bridge segments, and when portions of the bridge, such as deck slabs or box girder slabs, comply with the requirements for the protective cover, a separate protective cover need not be constructed.
F. At locations where only bridge railing is to be removed, the protective cover shall extend from the face of the exterior girder or at least 0.6-m inside of the bridge railing to be removed, whichever is less, to at least 1.2 m beyond the outside face of the bridge railing.
G. The protective cover shall provide the openings specified under "Maintaining Traffic" of these special provisions, except that when no openings are specified for bridge removal, a vertical opening of 4.6 m and a horizontal opening of 9.8 m shall be provided for the passage of public traffic.
H. Falsework or supports for protective covers shall not extend below the vertical clearance level nor to the ground line at any location within the roadbed.
I. The construction of the protective cover as specified herein shall not relieve the Contractor of responsibilities specified in Section 7-1.12A, "Indemnification," and Section 7-1.12B, "Insurance," of the Standard Specifications.
J. Before removal of the protective cover, the Contractor shall clean the protective cover of all debris and fine material.

For bridge removal that requires the Contractor's registered engineer to prepare and sign the bridge removal plan, the Contractor's registered engineer shall be present at all times when bridge removal operations are in progress. The Contractor's registered engineer shall inspect the bridge removal operation and report in writing on a daily basis the progress of the operation and the status of the remaining structure. A copy of the daily report shall be available at the site of the work at all times. Should an unplanned event occur or the bridge operation deviate from the approved bridge removal plan, the Contractor's registered engineer shall submit immediately to the Engineer for approval, the procedure of operation proposed to correct or remedy the occurrence.

REMOVE CONCRETE

Concrete, including brick sidewalk, granite curb and concrete base, where shown on the plans to be removed, shall be removed.

The pay quantities of concrete, including brick sidewalk, granite curb and concrete base, to be removed will be measured by the cubic meter, measured before and during removal operations.

Concrete, including brick sidewalk, granite curb and concrete base, removed shall be disposed of outside the highway right of way in conformance with the provisions in Section 7-1.13, "Disposal of Material Outside the Highway Right of Way," of the Standard Specifications.

Where no joint exists between concrete to be removed and concrete to remain in place, the concrete shall be cut on a neat line to a minimum depth of 50 mm with a power driven saw before the concrete is removed. This also includes the brick sidewalk, granite curb and concrete base.

Concrete, including brick sidewalk, granite curb and concrete base, to be removed which has portions of the same structure both above and below ground will be considered as concrete above ground for compensation.

REMOVE CONCRETE BARRIER (TYPE K)

Existing concrete barrier (Type K), where shown on the plans to be removed, shall be removed and disposed of.

Concrete barrier (Type K) shall consist of precast units conforming to the provisions for temporary railing (Type K) in Section 12-3.08, "Temporary Railing (Type K)," of the Standard Specifications.

Concrete barrier to be removed shall be disposed of in accordance with the provisions in Section 7-1.13, "Disposal of Material Outside the Highway Right of Way," of the Standard Specifications.

Remove concrete barrier will be measured and paid for by the meter.

10-1.37 CLEARING AND GRUBBING

Clearing and grubbing shall conform to the provisions in Section 16, "Clearing and Grubbing," of the Standard Specifications and these special provisions.

Vegetation shall be cleared and grubbed only within the excavation and embankment slope lines.

All earthy material removed in connection with clearing and grubbing shall be disposed of outside the highway right of way in conformance with the provisions as provided in "Hazardous and Non-Hazardous Material Excavation," elsewhere in these special provisions.

At locations where there is no grading adjacent to a bridge or other structure, clearing and grubbing of vegetation shall be limited to 1.5 m outside the physical limits of the bridge or structure.

Existing vegetation outside the areas to be cleared and grubbed shall be protected from injury or damage resulting from the Contractor's operations.

Activities controlled by the Contractor, except cleanup or other required work, shall be confined within the graded areas of the roadway.

Nothing herein shall be construed as relieving the Contractor of the Contractor's responsibility for final cleanup of the highway as provided in Section 4-1.02, "Final Cleaning Up," of the Standard Specifications.

Full compensation for the disposal of earthly material outside the highway right of way in conformance with the provisions as provided in "Hazardous and Non-Hazardous Material Excavation," shall be considered as included in the contract lump sum price paid for clearing and grubbing and no additional compensation will be allowed therefore.

10-1.38 EARTHWORK

Earthwork shall conform to the provisions in Section 19, "Earthwork," of the Standard Specifications and these special provisions.

Structure excavation (bridge) type H and structure excavation (retaining wall) type H as designated in the plans shall be considered hazardous material and shall be loaded, transported, and disposed of in conformance with the provisions in "Hazardous and Non-Hazardous Material Excavation" of these special provisions.

Difficult spread footing excavation at Abut 11 and Abut 11 retaining walls is anticipated due to the presence of hazardous materials, abundant rubble, subsurface concrete debris and underground utilities.

Surplus excavated material shall be handled as provided in "Hazardous and Non-Hazardous Material Excavation," elsewhere in these special provisions.

Where a portion of the existing surfacing is to be removed, the outline of the area to be removed shall be cut on a neat line with a power-driven saw to a minimum depth of 50 mm before removing the surfacing. Full compensation for cutting the existing surfacing shall be considered as included in the contract price paid per cubic meter for roadway excavation and no additional compensation will be allowed therefor.

The portion of imported borrow placed within 1.5 m of the finished grade shall have a Resistance (R-Value) of not less than 15.

Imported materials shall consist of clean soil, free of hazardous material as per California Code of Regulations (CCR) Title 22, Total Petroleum Hydrocarbons, BTEX (Benzene, Toluene, Ethylbenzene, Xylenes), and shall conform to the provisions in Sections 19-7.01, "Local Borrow" and 19-7.02, "Imported Borrow" of the Standard Specifications and these special provisions.

Reinforcement or metal attached to reinforced concrete rubble placed in embankments shall not protrude above the grading plane. Prior to placement within 0.6-m below the grading plane of embankments, reinforcement or metal shall be trimmed to no greater than 20 mm from the face of reinforced concrete rubble. Full compensation for trimming reinforcement or metal shall be considered as included in the contract prices paid per cubic meter for the types of excavation shown in the Engineer's estimate, or the contract prices paid for furnishing and placing imported borrow or embankment material, as the case may be, and no additional compensation will be allowed therefor.

At the locations and to the limits shown on the plans, material below the bottom of bridge retaining wall footings shall be removed and replaced with Class 2 aggregate base material in conformance with the placing and compacting requirements for structure backfill. The relative compaction shall be not less than 95 percent. Removal of the material will be measured and paid for by the cubic meter as structure excavation of the types listed in the Engineer's Estimate and furnishing, placing, and compacting the replacement material will be measured and paid for by the cubic meter as class 2 aggregate base.

10-1.39 HAZARDOUS AND NON-HAZARDOUS MATERIAL EXCAVATION

All hazardous and non-hazardous material to be excavated shall be transported to a disposal facility permitted to accept such material.

Excavated materials shall be handled and disposed of in conformance with the requirements in "Hazardous and Non-Hazardous Material, General" elsewhere in these special provisions.

Except as described in Table 1: HAZARDOUS AND NON-HAZARDOUS MATERIAL LIMITS, all excavated soil shall be classified as hazardous material and shall conform to the requirements in "Hazardous and Non-Hazardous Material, General" of these special provisions.

Hazardous materials shall be transferred directly from the excavation to a registered transport vehicle, or to an appropriate portable storage container approved for transport of hazardous waste by the United States Department of Transportation. There is insufficient room to store non-hazardous material on-site. Non-hazardous material shall be transferred directly from the excavation and placed into an appropriate portable storage container or loaded into an appropriate transport vehicle.

Hazardous and non-hazardous materials shall not be deposited on the pavement or on public roads.

All Hazardous material and non-hazardous material on exteriors of transport vehicles shall be removed and placed either into the current transport vehicle or the excavation prior to the vehicle leaving the exclusion zone. The Contractor shall indemnify the State from any costs due to spillage during the transport of hazardous or non-hazardous material to the disposal facility.

The Contractor shall monitor the air quality continuously during excavation operations at all locations containing hazardous material.

The Contractor shall implement a plan to prevent exposure of personnel working in hazardous material excavations. The Contractor’s plan to prevent exposure of personnel shall consist of a physical barrier. The barrier shall be maintained by the Contractor. When no longer required, as determined by the Engineer, the physical barrier shall be removed and either decontaminated or disposed of by the Contractor.

Upon completion of the hazardous material excavation, physical barrier and personal protective equipment, when no longer required, as determined by the Engineer, shall be removed from the job site.

Disposal of additional material resulting from the Contractor’s option to slope the excavations in lieu of shoring at locations where this is possible will be at the Contractor’s expense. All this additional material is designated as hazardous. At the Contractor’s option and expense, the Contractor may perform testing of this material, and if the material is non-hazardous, it may be handled and disposed of as non-hazardous material.

The locations and depths of hazardous and non-hazardous materials are shown in Table 1: "Hazardous and Non-Hazardous Material Limits" provided below.

TABLE 1: HAZARDOUS AND NON-HAZARDOUS MATERIAL LIMITS

Bent No.	Column Location	Level of Contaminants	Depth (meters) of Hazardous Material below Surface
1	1L	Hazardous	4.5
	1C	Hazardous	1.5
	1R	Non-Hazardous	N/A
2	2L	Hazardous	1.5
	2C	Hazardous	1.5
	2R	Hazardous	1.5
3	3L	Hazardous	1.5
	3C	Hazardous	1.5
	3R	Hazardous	1.5
4	4L	Hazardous	1.5
	4C	Hazardous	1.5
	4R	Hazardous	1.5
5	5L	Non-Hazardous	N/A
	5C	Hazardous	1.5
	5R	Hazardous	1.5
6	6L	Non-Hazardous	N/A
	6C	Hazardous	0.6
	6R	Non-Hazardous	N/A
7	7L	Hazardous	0.6
	7C	Hazardous	1.5
	7R	Hazardous	1.5
8	8L	Hazardous	0.6
	8C	Hazardous	1.5
	8R	Hazardous	3.0
9	9L	Hazardous	1.5
	9C	Hazardous	1.5
	9R	Hazardous	1.5
10	10L	Hazardous	1.5
	10C	Non-Hazardous	N/A
	10R	Hazardous	1.5
ABUTMENT AREA	AREA BOUNDED FOR TOUCH DOWN RAMP UP TO MARKET ST.	Hazardous	2.1

NOTE: Material below the depths of Hazardous Material (in the above Table) should be considered Non-Hazardous.
N/A : Not Applicable

MEASUREMENT AND PAYMENT

Quantities of Roadway Excavation, Structure Excavation (Retaining Wall), and Structure Excavation (Bridge) in hazardous materials will be measured and paid for as Roadway Excavation (Hazardous), Structure Excavation (Retaining Wall)(Type H) and Structure Excavation (Bridge)(Type H) respectively as shown in the Engineer's Estimate.

Full compensation for loading, transporting, and disposing of hazardous and non-hazardous material; providing storage containers, including handling and storage of such containers; furnishing, installing and removing physical barriers; incidentals and other items conforming to the requirements of this section shall be considered as included in the contract price paid per cubic meter for various items of excavation, the contract price paid per meter for various items of cast-in-

drilled-hole (CIDH) concrete piling, the contract prices paid per meter for various items of drainage and sewer pipe culverts of the types designated in the Engineer's Estimate; and the lump sum contract prices paid for various items of highway planting and irrigation systems, construction area signs and signal and lighting, and no additional compensation will be allowed therefor.

10-1.40 DEWATERING

Dewatering shall consist of work required for managing groundwater in this project, as shown on the plans, and as specified in these special provisions. Dewatering shall include labor and materials for operating and providing pumping equipment, settling tanks, monitoring, inspection, maintenance, and removal and disposal of materials. The Contractor shall provide a sealed excavation and prevent the flow of ground water, surface runoff, and tidal flow from entering any excavation including, but not limited to, footing excavations, pile foundation excavations, and excavations for storm drainage systems and their appurtenances. Well points and continuous pumping of excavations for dewatering purposes are not allowed. The Contractor may dewater an initial volume of water equivalent to the excavation pay limits for a particular excavation. The maximum seepage rate of the sealed excavation, after initial dewatering is complete, shall not exceed five gallons per square meter of the excavation area per eight hour period. The excavation area shall be measured at the top of the excavation as seen in plan view. A meter that has been approved by the Engineer shall be used to measure all excavation discharges.

The Contractor shall provide to the Engineer a schedule of planned dewatering activities at the contamination site at least 15 days prior to the commencement of dewatering activities.

The Contractor shall submit to the Engineer, as provided in Section 5-1.02, "Plans and Working Drawings," of the Standard Specifications, a plan which details the methods and measures that will be used to pump groundwater. The Plan shall at a minimum contain a graphic for the dewatering operation showing both a sectional plan and plan view that details the removal techniques. The graphic shall define the flow path and placement of pipes, hoses, pumps and other equipment used to convey the discharge. In addition the Contractor shall provide a drawing that depicts the general position of the dewatering measures relative to the excavations undergoing dewatering and the point of effluent discharge. The written descriptions of the dewatering operations shall include but are not limited to an estimate of the discharge volume, flow rate; location of the discharge; and inspection and monitoring procedures related to the discharge. The discharge plan shall also show the details of how and where the water will be discharged by the Contractor.

The Plan shall be submitted at least 3 weeks prior to beginning excavation operations. The Contractor shall allow 10 working days for the Engineer to review and approve the plan.

If the initial dewatering volume exceeds the volume of the structure excavation pay limits or the seepage rate exceeds the specified maximum rate, the Contractor shall immediately stop all work within the excavation not related to the control of water and submit a plan of corrective measures. The Contractor may not resume operations in that excavation until the plan is approved by the Engineer.

Discharge of excavation dewater into the drainage system of the City of San Francisco shall be conducted in accordance with Batch Waste Water Permit from the City and County of San Francisco. Dewatering shall conform Section7-1.01G, "Water Pollution" of the Standard Specifications, and these special provisions. Conformance with the requirements of this section shall in no way relieve the Contractor's responsibilities, as provided in Section 7-1.11, "Preservation of Property", Section 7-1.12, "Responsibility for Damage" and Section 7-1.16, "Contractor's Responsibility for the Work and Materials" of the Standard Specifications. A copy of the permit shall be provided to the Engineer fifteen days prior to disposal of excavation dewatering water. Penalties assessed against the State for permit non-compliance by the Contractor will be borne by the Contractor. Such penalties will be deducted from the monthly progress payments.

In the event the Contractor proposes to have the excavation dewatering water transported and discharged at a facility outside of the City of San Francisco, the Contractor shall submit to the Engineer, as provided in Section 5-1.02, "Plans and Working Drawings," of the Standard Specifications, a plan which details the methods and measures used to dewater the excavations and convey the discharge into transportable tanks or vessels. A copy of the plan shall be included as an amendment to the Water Pollution Control Plan (WPCP), as specified in "Water Pollution Control" of these special provisions. The plan shall include a graphic of the dewatering operation depicting both a sectional and plan view that details any pre-treatment techniques for the removal of suspended solids and other constituents of concern. The graphic shall define the flow path and placement of pipes, hoses, pumps, and other equipment used to convey the discharge. In addition, the Contractor shall provide a sketch that depicts the general position of the dewatering measures relative to the piles or excavations undergoing dewatering and the point of discharge into transportable tanks or vessels.

The written descriptions of the dewatering operation shall include, but not limited to, an estimate of the discharge volume, flow rate, frequency; location of discharge; and the inspection and monitoring procedures related to the discharge.

The Contractor shall conduct a daily inspection of the dewatering equipment when in use, to ensure that all components are functional and routinely maintained to prevent leakage during and prior to discharge. Should any component of the

dewatering apparatus be found to be damaged or to affect the performance of the apparatus, the dewatering operation shall be discontinued and the component shall be immediately repaired or replaced.

Observations, which indicate that the dewatering equipment is leaking, shall be immediately reported to the Engineer. The discharge activity shall immediately cease, so that corrective actions are undertaken to repair, modify, or replace the equipment. The commencement of discharge activities shall be allowed upon approval by the Engineer.

In addition the Contractor shall conduct inspections, at a minimum, one hour prior to discharge, during the first ten minutes of initiating discharge, every four hours during discharge, and upon cessation of discharge. The observations shall be recorded daily in a tabular format known as the monitoring report to be provided to the Engineer. The monitoring report shall be provided weekly to the Engineer, or as directed by the Engineer.

Upon completion of the dewatering activities, a letter report shall be prepared and signed by a California Registered Civil Engineer, Geologist or Engineering Geologist and include, at a minimum, the volume of removed groundwater, volume of contaminated groundwater and volume of groundwater discharged to the City of San Francisco collection systems, sampling procedures and analytical results.

MATERIALS

Materials shall conform to the provisions in Section 6, "Control of Materials," Section 7-1.16, "Contractor's Responsibility for the Work and Materials," and Section 74-2, "Drainage Pump Equipment" of the Standard Specifications and these special provisions.

The Contractor shall provide two (2) settling tanks on-site during dewatering activities with a minimum holding capacity of 7,570 L (2,000 gal) per individual tank and capable of connecting multiple tanks in series. Settling tanks shall be able to accommodate temporary installation of submersible pumps of such capability to discharge water at a rate of 150 L/min (40 gal/min). All tanks shall be of the same make and manufacturer and shall remain on the job site until dewatering operations are no longer necessary as determined by the Engineer.

Pumps shall be capable of being submerged in water and discharging water and other materials including, but not limited to small rocks, gravel, sand and sediments. Two (2) submersible pumps will be required for this project and shall be capable, at all times, of discharging at a flow rate necessary to remove the water in the excavation. In addition, a third submersible pump shall be provided by the Contractor that is capable of discharging treated effluent from the temporary holding container to the dedicated discharge location.

Plastic piping may be approved for use as determined by the Engineer in writing. If plastic piping is used, it shall conform to the provisions in section 20-5.03E, "Pipe" of the Standard Specifications. The Contractor shall be responsible for providing all piping required to convey the clean effluent from the temporary holding container to the point of release at the dedicated discharge location.

The Contractor shall be responsible for maintaining all of the equipment and materials outlined in this special provision to operational levels necessary to comply with provisions outlined in these special provisions and permits issued for this project. If the Contractor or the Engineer identifies a deficiency in the functioning of any equipment or material, the deficiency shall be immediately corrected by the Contractor.

MONITORING

The Contractor shall not allow discharge of water to the City of San Francisco drainage system exceeding the limits as shown in the table below:

Parameter	Limit (mg/l)	EPA Test Method
Chromium	0.05	6010
Nickel	0.1	6010
Thallium	0.002	6010
1,2 DiChloroethene (1,2 DCE)	0.006	8260B
Tetrachloroethene	0.005	8260B
Trichloroethene	0.005	8260B
Vinyl Chloride	0.0005	8260B

* Note: Metals shall be analyzed by a method with sufficient sensitivity to quantify metal concentration well below the regulatory limit.

The Contractor shall seek advance approval from the Engineer on use of a commercial laboratory prior to dewatering. Samples shall be obtained downstream of the flow meter, and just prior to the discharge point. Samples shall be obtained prior to the first discharge, and monthly thereafter. The Contractor shall submit a monitoring report that tabulates laboratory

results, describes sampling protocols, and includes laboratory documentation (chain of custodies, final laboratory analysis records, cover letters, etc.) weekly to the Engineer during the period that the permit is in effect even if there is no flow during the week. If there is no sampling performed due to the lack of discharge, then the Contractor shall submit a monitoring report explaining the discharge situation. The Engineer will have 10 days to review the monitoring report. If revisions are required as determined by the Engineer, the Contractor shall revise and resubmit the draft report within 5 days of receipt of the Engineer's comments. The Engineer will have 3 days to review the revisions. Upon the Engineer's approval of the monitoring report, the Contractor shall provide 3 copies of the monitoring report to the Engineer.

The Contractor shall record the flow-meter totalizer readings for every day of dewatering operations. The meter readings and the computed average daily volume (gal/day) shall be submitted to the Engineer as a Discharge Volume Report weekly.

MEASUREMENT AND PAYMENT

The contract lump sum price paid for dewatering shall include full compensation for furnishing all labor, materials, tools, equipment, including providing sealed excavation and measures to prevent the flow of water from entering the excavation; providing dewatering equipment; transportable tanks or vessels; conducting inspections and monitoring; obtaining discharge permits; disposal of excavation dewater including treatment to excavation dewater for removing suspended solids and other constituents of concern; and incidentals, and for doing all the work involved in dewatering as described, including placement, maintenance, and removal of equipment, complete in place, as shown in the plans, and this special provision, and no additional compensation will be allowed therefore.

Fees associated with discharge to the City of San Francisco will be paid by the Contractor.

10-1.41 CONTROLLED LOW STRENGTH MATERIAL

Controlled low strength material shall consist of a workable mixture of aggregate, cementitious materials, and water and shall conform to the provisions for slurry cement backfill in Section 19-3.062, "Slurry Cement Backfill," of the Standard Specifications and these special provisions.

At the option of the Contractor, controlled low strength material may be used as structure backfill for pipe culverts, except that controlled low strength material shall not be used as structure backfill for aluminum and aluminum-coated culverts nor for culverts having a diameter or span greater than 6.1 m.

When controlled low strength material is used for structure backfill, the width of the excavation shown on the plans may be reduced so that the clear distance between the outside of the pipe and the side of the excavation, on each side of the pipe, is a minimum of 300 mm. This minimum may be reduced to 150 mm when the height of cover is less than or equal to 6.1 m or the pipe diameter or span is less than 1050 mm.

Controlled low strength material in new construction shall not be permanently placed higher than the basement soil. For trenches in existing pavements, permanent placement shall be no higher than the bottom of the existing pavement permeable drainage layer. If a drainage layer does not exist, permanent placement in existing pavements shall be no higher than 25 mm below the bottom of the existing asphalt concrete surfacing or no higher than the top of base below the existing portland cement concrete pavement. The minimum height that controlled low strength material shall be placed, relative to the culvert invert, is 0.5 diameter or 0.5 height for rigid culverts and 0.7 diameter or 0.7 height for flexible culverts.

When controlled low strength material is proposed for use, the Contractor shall submit a mix design and test data to the Engineer for approval prior to excavating the trench for which controlled low strength material is proposed for use. The test data and mix design shall provide for the following:

A. A 28-day compressive strength between 345 kPa and 690 kPa for pipe culverts having a height of cover of 6.1 m or less and a minimum 28-day compressive strength of 690 kPa for pipe culverts having a height of cover greater than 6.1 m. Compressive strength shall be determined in conformance with the requirements in ASTM Designation: D 4832.
B. When controlled low strength material is used as structure backfill for pipe culverts, the sections of pipe culvert in contact with the controlled low strength material shall conform to the requirements of Chapter 850 of the Highway Design Manual using the minimum resistivity, pH, chloride content, and sulfate content of the hardened controlled low strength material. Minimum resistivity and pH shall be determined in conformance with the requirements of California Test 643. The chloride content shall be determined in conformance with the requirements of California Test 422 and the sulfate content shall be determined in conformance with the requirements of California Test 417.
C. Cement shall be any type of portland cement conforming to the requirements in ASTM Designation: C 150; or any type of blended hydraulic cement conforming to the requirements in ASTM Designation: C 595M or the physical requirements in ASTM Designation: C 1157M. Testing of cement will not be required.
D. Admixtures may be used in conformance with the provisions in Section 90-4, "Admixtures," of the Standard Specifications. Chemical admixtures containing chlorides as Cl in excess of one percent by mass of admixture, as determined in conformance with the requirements of California Test 415, shall not be used. If an air-entraining

admixture is used, the maximum air content shall be limited to 20 percent. Mineral admixtures shall be used at the Contractor's option.

Materials for controlled low strength material shall be thoroughly machine-mixed in a pugmill, rotary drum or other approved mixer. Mixing shall continue until the cementitious material and water are thoroughly dispersed throughout the material. Controlled low strength material shall be placed in the work within 3 hours after introduction of the cement to the aggregates.

When controlled low strength material is to be placed within the traveled way or otherwise to be covered by paving or embankment materials, the material shall achieve a maximum indentation diameter of 76 mm prior to covering and opening to public traffic. Penetration resistance shall be measured in conformance with the requirements in ASTM Designation: D 6024.

Controlled low strength material used as structure backfill for pipe culverts will be considered structure backfill for compensation purposes.

10-1.42 FIBER ROLLS

Fiber rolls shall conform to the details shown on the plans and these special provisions.

MATERIALS

Fiber rolls shall consist of one of the following:

A. Fiber rolls shall be constructed on the project site with manufactured blankets consisting of one or a combination of wood excelsior, rice, wheat or coconut fibers. The blanket shall measure approximately 3.5 m wide by 26 m to 29 m in length. Wood excelsior

material shall have individual fibers, 80 percent of which shall be 150 mm or longer in fiber length. The blanket shall have a photodegradable plastic netting. The blanket shall be rolled on the blanket's width and secured with jute twine spaced 2 m apart along the roll for the full length and 150 mm from each end of the individual rolls. The blanket shall be rolled so that the netting is on the outside of the finished roll. The finished roll diameter shall be a minimum of 175 mm and a maximum of 225 mm and shall weigh not less than 1.3 kg/m.

B. Fiber rolls shall be pre-manufactured rice or wheat straw, wood excelsior or coconut fiber rolls encapsulated within a photodegradable plastic netting. Each roll shall be a minimum of 175 mm and a maximum of 225 mm in diameter and 7 m to 9 m in length and shall weigh not less than 1.3 kg/m. The netting shall be ultraviolet (UV) degradable plastic. The netting shall have a minimum durability of one year after installation. The netting shall be secured tightly at each end of the individual rolls.

Stakes shall be fir or pine and shall be a minimum of 25 mm x 25 mm x 600 mm in length. Metal stakes may be used as an alternative. The Contractor shall submit a sample of the metal stake to the Engineer prior to installation. The tops of the metal stakes shall be bent over at a 90-degree angle. No additional compensation will be allowed for the use of a metal stake.

INSTALLATION

Fiber rolls shall be joined tightly together to form a single linear roll that is installed approximately parallel to the slope contour. Fiber rolls shall be installed prior to the application of other erosion control materials.

Furrows shall be constructed at a slight angle to the slope contour, to a depth of 50 mm to 100 mm, and at a sufficient width to hold the fiber rolls.

Rolls shall be installed at a maximum of 6 m apart (measured along the slope) in the furrows with the first row installed 1.5 m above the toe of slope. Individual rolls shall be placed with adjacent ends butted firmly to each other to create a continuous linear roll.

Stakes shall be installed 1.2 m apart along the total length of the rolls and 125 mm from the end of each individual roll. Stakes shall be driven flush or a maximum of 50 mm above the roll.

MEASUREMENT AND PAYMENT

Fiber rolls will be measured by the meter from end to end along the centerline of the installed rolls.

The contract price paid per meter for fiber rolls shall include full compensation for furnishing all labor, materials, tools, equipment, and incidentals, and for doing all the work involved in installing fiber rolls, complete in place, including stakes, as shown on the plans, as specified in the Standard Specifications and these special provisions, and as directed by the Engineer.

10-1.43 DRAIN INLET PROTECTION

Drain inlet protection shall be installed and maintained as shown on the plans, as specified in these special provisions, and as directed by the Engineer.

MATERIALS

Materials shall conform to the provisions in Section 20-2, "Materials," of the Standard Specifications and these special provisions.

Erosion Control Blanket

Erosion control blanket shall be secured in place with wire staples and shall conform to the following:

A. Erosion control blanket shall consist of 100 percent spun coir fiber and shall conform to the following:

Specification	Requirement
Weight, grams per square meter ASTM Designation: D 3776	400
Minimum Tensile Strength, kilonewtons, ASTM Designation: D 4595-86	0.23/0.14 (dry) 0.17/0.11 (wet)
Roll Width, meters, min.	2
Area/Roll, square meters, min.	200
Open Area, percent	63-70

B. Staples for erosion control blankets shall be as shown on plans.

Fiber Rolls

Fiber rolls shall conform to the provisions for fiber rolls elsewhere in these special provisions.

INSTALLATION

The bedding area shall be excavated and cleared of obstructions including, but not limited to, rocks, clods, and mulch prior to installation of the erosion control blanket. The edges of the erosion control blanket shall be keyed into trenches, stapled, backfilled, and tamped. Upon completion of the backfill and tamping, the resulting key trench shall have an indentation or furrow of 50 mm to 100 mm to accept the fiber roll. Fiber rolls shall be installed along the edges of the erosion control blanket, in the furrow, and secured as shown on plans. Excess soil from excavation of the key trenches shall be disposed of uphill of the installed fiber rolls.

Stakes shall be installed 600 mm apart along the total length of the rolls and 300 mm from the end of each individual roll. Stakes shall be driven flush or a maximum of 50 mm above the roll.

MEASUREMENT AND PAYMENT

Drainage inlet protection will be measured and paid for by actual count in place.

The contract unit price paid for drain inlet protection shall include full compensation for furnishing all labor, materials, tools, equipment, and incidentals, and for doing all the work involved in installing drain inlet protection, complete in place, including furnishing and installing fiber rolls and erosion control blanket as shown on the plans, as specified in the Standard Specifications and these special provisions, and as directed by the Engineer.

10-1.44 AGGREGATE SUBBASE

Aggregate subbase shall be Class 4 and shall conform to the provisions in Section 25, "Aggregate Subbases," of the Standard Specifications and these special provisions.

The restriction that the amount of reclaimed material included in Class 4 aggregate subbase not exceed 50 percent of the total volume of the aggregate used shall not apply. Aggregate for Class 4 aggregate subbase may include reclaimed glass. Aggregate subbase incorporating reclaimed glass shall not be placed at locations where surfacing will not be placed over the aggregate subbase.

The percentage composition by mass of Class 4 aggregate subbase shall conform to the following grading requirements:

Grading Requirements (Percentage Passing)

Sieve Sizes	Operating Range	Contract Compliance
63 mm	100	100
4.75-mm	35-65	25-70
75-µm	0-15	0-18

Class 4 aggregate subbase shall also conform to the following quality requirements:

Quality Requirements

Test	Operating Range	Contract Compliance
Sand Equivalent	21 Min.	18 Min.
Resistance (R-value)	----	50 Min.

The provisions of the last 4 paragraphs in Section 25-1.02A, "Class 1, Class 2, and Class 3 Aggregate Subbases," of the Standard Specifications shall apply to Class 4 aggregate subbase.

At the option of the Contractor, Class 2 aggregate subbase conforming to the grading and quality requirements in Section 25-1.02A, may be used in place of Class 4 aggregate subbase. The restriction that the amount of reclaimed material included in Class 2 aggregate subbase not exceed 50 percent of the total volume of the aggregate used shall not apply. Aggregate for Class 2 aggregate subbase may include reclaimed glass. Aggregate subbase incorporating reclaimed glass shall not be placed at locations where surfacing will not be placed over the aggregate subbase. Once a class of aggregate subbase is selected, the class shall not be changed without written approval of the Engineer.

Regardless of the class of aggregate subbase supplied under the provisions of this section, payment for all aggregate subbase will be made as Class 4 aggregate subbase.

10-1.45 AGGREGATE BASE (CLASS 2)

Aggregate base shall be Class 2 and shall conform to the provisions in Section 26, "Aggregate Bases," of the Standard Specifications and these special provisions.

The restriction that the amount of reclaimed material included in Class 2 aggregate base not exceed 50 percent of the total volume of the aggregate used shall not apply. Aggregate for Class 2 aggregate base may include reclaimed glass. Aggregate base incorporating reclaimed glass shall not be placed at locations where surfacing will not be placed over the aggregate base.

10-1.46 AGGREGATE BASE (CLASS 3)

Aggregate base shall be Class 3 and shall conform to the provisions in Section 26, "Aggregate Bases," of the Standard Specifications and these special provisions.

The restriction that the amount of reclaimed material included in Class 3 aggregate base not exceed 50 percent of the total volume of the aggregate used shall not apply. Aggregate for Class 3 aggregate base may include or consist of material processed from reclaimed asphalt concrete, portland cement concrete, lean concrete base, glass or combination of any of these materials. Aggregate base incorporating reclaimed glass shall not be placed at locations where surfacing will not be placed over the aggregate base.

Aggregate for Class 3 aggregate base shall conform to the following requirements:

Grading Requirements (Percentage Passing)

Sieve Sizes	19 mm Maximum	
	Operating Range	Contract Compliance
50-mm	-----	-----
37.5-mm	-----	-----
25-mm	100	100
19-mm	90-100	87-100
4.75-mm	35-60	30-65
600-µm	10-30	5-35
75-µm	2-11	0-14

Grading Requirements (Percentage Passing)

Sieve Sizes	37.5 mm Maximum	
	Operating Range	Contract Compliance
50-mm	100	100
37.5-mm	90-100	87-100
25-mm	---	---
19-mm	50-85	45-90
4.75-mm	25-45	20-50
600-µm	10-25	6-29
75-µm	2-11	0-14

Quality Requirements

Tests	Operating Range	Contract Compliance
Sand Equivalent	25 Min.	22 Min.
Resistance (R-value)	-----	78 Min.

A Durability Index with a minimum of 35 is required.

The aggregate shall not be treated with lime, cement or other chemical material before the Durability Index test is performed. Untreated reclaimed asphalt concrete and portland cement concrete will not be considered to be treated with lime, cement or other chemical material for purposes of performing the Durability Index test.

10-1.47 ASPHALT CONCRETE

Asphalt concrete shall be Type A and shall conform to the provisions in Section 39, "Asphalt Concrete," of the Standard Specifications and these special provisions.

The asphalt content of the asphalt mixture will be determined in conformance with the requirements in California Test 379, or in conformance with the requirements in California Test 382.

Paint binder (tack coat) shall be applied to existing surfaces to be surfaced and between layers of asphalt concrete, except when eliminated by the Engineer.

Paint binder (tack coat) shall be, at the option of the Contractor, either slow-setting type asphaltic emulsion, rapid setting asphaltic emulsion or paving asphalt. Slow-setting type asphaltic emulsion and rapid setting asphaltic emulsion shall conform to the provisions in Section 39-4.02, "Prime Coat and Paint Binder (Tack Coat)," and the provisions in Section 94, "Asphaltic Emulsions," of the Standard Specifications. When paving asphalt is used for paint binder, the grade will be determined by the Engineer. Paving asphalt shall conform to the provisions in Section 39-4.02, "Prime Coat and Paint Binder (Tack Coat)," and the provisions in Section 92, "Asphalts," of the Standard Specifications.

Paint binder (tack coat) shall be applied in the liter per square meter range limits specified for the surfaces to receive asphalt concrete in the tables below. The exact application rate within the range will be determined by the Engineer.

Application Rates for Asphaltic Emulsion Paint Binder (Tack Coat) for Asphalt Concrete (except Open Graded) and on Portland Cement Concrete Pavement		
Type of surface to receive paint binder (tack coat)	Slow-Setting Asphaltic Emulsion L/m^2(Note A)	Rapid-Setting Asphaltic Emulsion L/m^2(Note B)
Dense, compact surfaces, between layers, and on PCCP	0.20 – 0.35	0.10 – 0.20
Open textured, or dry, aged surfaces	0.35 – 0.90	0.20 – 0.40

Note A: Slow-setting asphaltic emulsion is asphaltic emulsion diluted with additional water. Water shall be added and mixed with the asphaltic emulsion (containing up to 43 percent water) so the resulting mixture contains one part asphaltic emulsion and not more than one part added water. The water shall be added by the emulsion producer or at a facility that has the capability to mix or agitate the combined blend.

Note B: Undiluted rapid-setting asphaltic emulsion.

If the Contractor selects the batch mixing method, asphalt concrete shall be produced by the automatic batch mixing method in conformance with the provisions in Section 39-3.03A(2), "Automatic Proportioning," of the Standard Specifications.

If the finished surface of the asphalt concrete on Route 101 and local street traffic lanes does not meet the specified surface tolerances, the surfacing shall be brought within tolerance by either (1) abrasive grinding (with fog seal coat on the

areas which have been ground), (2) removal and replacement or (3) placing an overlay of asphalt concrete. The method will be selected by the Engineer. The corrective work shall be at the Contractor's expense.

If abrasive grinding is used to bring the finished surface to the specified surface tolerances, additional grinding shall be performed, as necessary, to extend the area ground in each lateral direction so that the lateral limits of grinding are at a constant offset from, and parallel to, the nearest lane line or pavement edge, and in each longitudinal direction so that the grinding begins and ends at lines normal to the pavement centerline, within any ground area. Ground areas shall be neat rectangular areas of uniform surface appearance. Abrasive grinding shall conform to the provisions in the first paragraph and the last 4 paragraphs in Section 42-2.02, "Construction," of the Standard Specifications.

10-1.48 PORTLAND CEMENT CONCRETE BASE

Portland cement concrete base shall conform to the provisions for concrete pavement in Section 40, "Portland Cement Concrete Pavement," of the Standard Specifications and these special provisions.

The concrete for concrete base shall contain a minimum of 325 kg/m^3 of portland cement.

Weakened plane joints shall be constructed at 9-m intervals.

If the Contractor elects to place 2-lane monolithic base, a longitudinal joint will not be required in the center of such base.

Concrete shall be spread and shaped by suitably powered finishing machines, supplemented by hand work as necessary. Consolidation of concrete shall be performed by means of high-frequency internal vibrators within 15 minutes after the concrete is deposited on the subgrade. Vibrating shall be performed with care and in a manner that assures adequate consolidation across the full paving width. Use of vibrators for extensive shifting of the mass of concrete will not be permitted. Methods of spreading, shaping, and compacting that result in segregation, voids or rock pockets shall be discontinued and methods shall be adopted which will produce a dense homogeneous base conforming to the required cross section.

The finished surface shall not vary more than 6 mm from the undersurface of a straightedge, 3.6 m ± 0.06-m long, placed parallel with the center line.

Except as above provided, the finishing provided in Section 40-1.09, "Preliminary Finishing," and Section 40-1.10, "Final Finishing," of the Standard Specifications will not be required for the concrete base.

The surface of the base shall be broomed with a heavy broom to produce a uniform, rough surface. The surface shall not be broomed until the concrete has set sufficiently as determined by the Engineer.

Curing shall commence as soon as free water leaves the surface of the concrete base, but not later than 3 hours after depositing concrete base on the subgrade.

The base shall be cured by applying either a RS1 type or SS1 type asphaltic emulsion applied in conformance with the provisions in Section 94, "Asphaltic Emulsions," of the Standard Specifications. The curing seal shall be applied to the surface at a rate between 0.7-L/m^2 and 1.15 L/m^2. The exact rate of application will be determined by the Engineer. Areas of the curing seal that are damaged shall be covered immediately with additional seal at the Contractor's expense. The curing seal shall remain on the base to serve as paint binder when surfacing is placed thereon.

Furnishing and applying curing seal will be paid for at the contract price per tonne for asphaltic emulsion (curing seal) and shall include full compensation for furnishing all labor, materials, tools, equipment, and incidentals, and for doing all the work involved in applying the curing seal as specified in this section.

Portland cement concrete base will be measured and paid for by the cubic meter in the same manner specified for concrete pavement as provided in Section 40-1.13, "Measurement," Section 40-1.135, "Pavement Thickness," and Section 40-1.14, "Payment," of the Standard Specifications.

10-1.49 PILING

GENERAL

Piling shall conform to the provisions in Section 49, "Piling," of the Standard Specifications, and these special provisions.

Unless otherwise specified, welding of any work performed in conformance with the provisions in Section 49, "Piling," of the Standard Specifications, shall be in conformance with the requirements in AWS D1.1.

Foundation recommendations are included in the "Information Handout" available to the Contractor as provided for in Section 2-1.03, "Examination of Plans, Specifications, Contract, and Site of Work," of the Standard Specifications.

Attention is directed to "Welding" of these special provisions.

Difficult pile installation is anticipated due to the presence of high ground water, cobbles and boulders, caving soils, hazardous materials, existing reinforced concrete footing, existing piling, abundant rubble, subsurface concrete debris, underground utilities, overhead utilities, the requirements of pile embedment into rock, sound control, vibration monitoring and traffic control.

Load Test Piles

The Contractor shall notify the Engineer, in writing, not less than 10 days in advance of drilling the piles to be load tested.

Before the remaining piles at the control locations listed in the following table are drilled and cast, load testing of each load test pile shown on the plans for the corresponding control location shall be completed:

Bridge	Load Test Pile Location	Control Locations
Central Viaduct (Replace)	Bent 6	All Bents

The bottom of footing excavation shall be dewatered and made level before pile load testing. The excavation shall be kept dewatered during load testing.

Couplers shall be furnished at the top of each high strength threaded bar for connecting the State-Supplied William bar.

The high strength threaded bars and couplers shall conform to the requirements of ASTM Designation: A722.

The Engineer will require not more than 14 working days to perform pile load tests at each test location.

CAST-IN-DRILLED-HOLE CONCRETE PILES

Cast-in-drilled-hole concrete piling shall conform to the provisions in Section 49-4, "Cast-In-Place Concrete Piles," of the Standard Specifications and these special provisions.

Attention is directed to "Hazardous and Non-Hazardous Material Excavation" of these special provisions for hazardous material resulting from constructing the cast-in-drilled-hole concrete piling.

Cast-in-drilled-hole concrete piling (rock socket) shall consist of drilling or coring sockets in bedrock to the depths or lengths specified and filling with reinforced concrete in conformance with the details shown on the plans and these special provisions. Cored holes, if used, shall conform to the provisions of Section 49-4.03, "Drilled Holes," of the Standard Specifications.

The provisions of "Welding" of these special provisions shall not apply to temporary steel casings.

Cast-in-drilled-hole concrete piles 600 mm in diameter or larger may be constructed by excavation and depositing concrete under slurry.

Materials

Concrete deposited under slurry shall have a nominal penetration equal to or greater than 90 mm. Concrete shall be proportioned to prevent excessive bleed water and segregation.

Concrete deposited under slurry shall contain not less than 400 kg of cementitious material per cubic meter.

The combined aggregate grading used in concrete for cast-in-drilled-hole concrete piling shall be either the 25-mm maximum grading, the 12.5-mm maximum grading, or the 9.5-mm maximum grading and shall conform to the requirements in Section 90-3 "Aggregate Gradings," of the Standard Specifications.

Mineral Slurry

Mineral slurry shall be mixed and thoroughly hydrated in slurry tanks, and slurry shall be sampled from the slurry tanks and tested before placement in the drilled hole.

Slurry shall be recirculated or continuously agitated in the drilled hole to maintain the specified properties.

Recirculation shall include removal of drill cuttings from the slurry before discharging the slurry back into the drilled hole. When recirculation is used, the slurry shall be sampled and tested at least every 2 hours after beginning its use until tests show that the samples taken from the slurry tank and from near the bottom of the hole have consistent specified properties. Subsequently, slurry shall be sampled at least twice per shift as long as the specified properties remain consistent.

Slurry that is not recirculated in the drilled hole shall be sampled and tested at least every 2 hours after beginning its use. The slurry shall be sampled midheight and near the bottom of the hole. Slurry shall be recirculated when tests show that the samples taken from midheight and near the bottom of the hole do not have consistent specified properties.

Slurry shall also be sampled and tested prior to final cleaning of the bottom of the hole and again just prior to placing concrete. Samples shall be taken from midheight and near the bottom of the hole. Cleaning of the bottom of the hole and placement of the concrete shall not start until tests show that the samples taken from midheight and near the bottom of the hole have consistent specified properties.

Mineral slurry shall be tested for conformance to the requirements shown in the following table:

MINERAL SLURRY		
PROPERTY	REQUIREMENT	TEST
Density (kg/m^3) - before placement in the drilled hole - during drilling - prior to final cleaning - immediately prior to placing concrete	1030* to 1110* 1030* to 1200*	Mud Weight (Density) API 13B-1 Section 1
Viscosity (seconds/liter) bentonite attapulgite	29 to 53 29 to 42	Marsh Funnel and Cup API 13B-1 Section 2.2
pH	8 to 10.5	Glass Electrode pH Meter or pH Paper
Sand Content (percent) - prior to final cleaning - immediately prior to placing concrete	less than or equal to 4.0	Sand API 13B-1 Section 5
*When approved by the Engineer, slurry may be used in salt water, and the allowable densities may be increased up to 32 kg/m^3. Slurry temperature shall be at least 4 degrees Celsius when tested.		

Any caked slurry on the sides or bottom of hole shall be removed before placing reinforcement. If concrete is not placed immediately after placing reinforcement, the reinforcement shall be removed and cleaned of slurry, the sides of the drilled hole cleaned of caked slurry, and the reinforcement again placed in the hole for concrete placement.

Synthetic Slurry

Synthetic slurries shall be used in conformance with the manufacturer's recommendations and these special provisions. The following synthetic slurries may be used:

PRODUCT	MANUFACTURER
SlurryPro EXL	KB Technologies Ltd. 3648 FM 1960 West Suite 107 Houston, TX 77068 (800) 525-5237
Super Mud	PDS Company c/o Champion Equipment Company 8140 East Rosecrans Ave. Paramount, CA 90723 (562) 634-8180
Shore Pac GCV	CETCO Drilling Products Group 1350 West Shure Drive Arlington Heights, IL 60004 (847) 392-5800

Inclusion of a synthetic slurry on the above list may be obtained by meeting the Department's requirements for synthetic slurries. The requirements can be obtained from the Office of Structure Design, P.O. Box 942874, Sacramento, CA 94274-0001.

Synthetic slurries listed may not be appropriate for a given site.

Synthetic slurries shall not be used in holes drilled in primarily soft or very soft cohesive soils as determined by the Engineer.

A manufacturer's representative, as approved by the Engineer, shall provide technical assistance for the use of their product, shall be at the site prior to introduction of the synthetic slurry into a drilled hole, and shall remain at the site until released by the Engineer.

Synthetic slurries shall be sampled and tested at both mid-height and near the bottom of the drilled hole. Samples shall be taken and tested during drilling as necessary to verify the control of the properties of the slurry. Samples shall be taken and tested when drilling is complete, but prior to final cleaning of the bottom of the hole. When samples are in conformance with the requirements shown in the following tables for each slurry product, the bottom of the hole shall be cleaned and any loose or settled material removed. Samples shall be obtained and tested after final cleaning and immediately prior to placing concrete.

SlurryPro CDP synthetic slurries shall be tested for conformance to the requirements shown in the following table:

SLURRYPRO CDP KB Technologies Ltd.		
PROPERTY	REQUIREMENT	TEST
Density (kg/m^3) - during drilling - prior to final cleaning - just prior to placing concrete	 less than or equal to 1075* less than or equal to 1025*	Mud Weight (Density) API 13B-1 Section 1
Viscosity (seconds/liter) - during drilling -prior to final cleaning - just prior to placing concrete	 53 to 127 less than or equal to 74	Marsh Funnel and Cup API 13B-1 Section 2.2
pH	6 to 11.5	Glass Electrode pH Meter or pH Paper
Sand Content (percent) - prior to final cleaning - just prior to placing concrete	 less than or equal to 0.5	Sand API 13B-1 Section 5
*When approved by the Engineer, slurry may be used in salt water, and the allowable densities may be increased up to 32 kg/m^3. Slurry temperature shall be at least 4 degrees Celsius when tested.		

Super Mud synthetic slurries shall be tested for conformance to the requirements shown in the following table:

SUPER MUD PDS Company		
PROPERTY	REQUIREMENT	TEST
Density (kg/m^3) - prior to final cleaning - just prior to placing concrete	less than or equal to 1025*	Mud Weight (Density) API 13B-1 Section 1
Viscosity (seconds/liter) - during drilling - prior to final cleaning - just prior to placing concrete	34 to 64 less than or equal to 64	Marsh Funnel and Cup API 13B-1 Section 2.2
pH	8 to 10.0	Glass Electrode pH Meter or pH Paper
Sand Content (percent) - prior to final cleaning -just prior to placing concrete	less than or equal to 0.5	Sand API 13B-1 Section 5
*When approved by the Engineer, slurry may be used in salt water, and the allowable densities may be increased up to 32 kg/m^3. Slurry temperature shall be at least 4 degrees Celsius when tested.		

Shore Pac GCV synthetic slurries shall be tested for conformance to the requirements shown in the following table:

Shore Pac GCV CETCO Drilling Products Group		
PROPERTY	REQUIREMENT	TEST
Density (kg/m^3) - prior to final cleaning - just prior to placing concrete	less than or equal to 1025*	Mud Weight (Density) API 13B-1 Section 1
Viscosity (seconds/liter) - during drilling - prior to final cleaning - just prior to placing concrete	35 to 78 less than or equal to 60	Marsh Funnel and Cup API 13B-1 Section 2.2
pH	8.0 to 11.0	Glass Electrode pH Meter or pH Paper
Sand Content (percent) - prior to final cleaning -just prior to placing concrete	less than or equal to 0.5	Sand API 13B-1 Section 5
*When approved by the Engineer, slurry may be used in salt water, and the allowable densities may be increased up to 32 kg/m^3. Slurry temperature shall be at least 4 degrees Celsius when tested.		

Water Slurry

At the option of the Contractor water may be used as slurry when casing is used for the entire length of the drilled hole. Water slurry shall be tested for conformance to the requirements shown in the following table:

WATER SLURRY		
PROPERTY	REQUIREMENT	TEST

Density (kg/m^3) - prior to final cleaning - just prior to placing concrete	1017 *	Mud Weight (Density) API 13B-1 Section 1
Sand Content (percent) - prior to final cleaning -just prior to placing concrete	less than or equal to 0.5	Sand API 13B-1 Section 5
*When approved by the Engineer, salt water slurry may be used, and the allowable densities may be increased up to 32 kg/m^3.		

Construction

The Contractor shall submit a placing plan to the Engineer for approval prior to producing the test batch for cast-in-drilled-hole concrete piling and at least 10 working days prior to constructing piling. The plan shall include complete descriptions, details, and supporting calculations as listed below:

A. Requirements for all cast-in-drilled hole concrete piling:

1. Concrete mix design, certified test data, and trial batch reports.
2. Drilling or coring methods and equipment.
3. Proposed method for casing installation and removal when necessary.
4. Plan view drawing of pile showing reinforcement and inspection pipes, if required.
5. Methods for placing, positioning, and supporting bar reinforcement.
6. Methods and equipment for accurately determining the depth of concrete and actual and theoretical volume placed, including effects on volume of concrete when any casings are withdrawn.
7. Methods and equipment for verifying that the bottom of the drilled hole is clean prior to placing concrete.
8. Methods and equipment for preventing upward movement of reinforcement, including the Contractor's means of detecting and measuring upward movement during concrete placement operations.

B. Additional requirements when concrete is placed under slurry:

1. Concrete batching, delivery, and placing systems, including time schedules and capacities therefor. Time schedules shall include the time required for each concrete placing operation at each pile.
2. Concrete placing rate calculations. When requested by the Engineer, calculations shall be based on the initial pump pressures or static head on the concrete and losses throughout the placing system, including anticipated head of slurry and concrete to be displaced.
3. Suppliers' test reports on the physical and chemical properties of the slurry and any proposed slurry chemical additives, including Material Safety Data Sheet.
4. Slurry testing equipment and procedures.
5. Methods of removal and disposal of excavation, slurry, and contaminated concrete, including removal rates.
6. Methods and equipment for slurry agitating, recirculating, and cleaning.

In addition to compressive strength requirements, the consistency of the concrete to be deposited under slurry shall be verified before use by producing a test batch. The test batch shall be produced and delivered to the project under conditions and in time periods similar to those expected during the placement of concrete in the piles. Concrete for the test batch shall be placed in an excavated hole or suitable container of adequate size to allow for testing as specified herein. Depositing of test batch concrete under slurry will not be required. In addition to meeting the specified nominal penetration, the test batch shall meet the following requirements:

A. For piles where the time required for each concrete placing operation, as submitted in the placing plan, will be 2 hours or less, the test batch shall demonstrate that the proposed concrete mix design achieves either a penetration of at least 50 mm or a slump of at least 125 mm after twice that time has elapsed.
B. For piles where the time required for each concrete placing operation, as submitted in the placing plan, will be more than 2 hours, the test batch shall demonstrate that the proposed concrete mix design achieves either a penetration of at least 50 mm or a slump of at least 125 mm after that time plus 2 hours has elapsed.

The time period shall begin at the start of placement. The concrete shall not be vibrated or agitated during the test period. Penetration tests shall be performed in conformance with the requirements in California Test 533. Slump tests shall be performed in conformance with the requirements in ASTM Designation: C 143. Upon completion of testing, the concrete shall be disposed of in conformance with the provisions in Section 7-1.13, "Disposal of Material Outside the Highway Right of Way," of the Standard Specifications.

The concrete deposited under slurry shall be carefully placed in a compact, monolithic mass and by a method that will prevent washing of the concrete. Concrete deposited under slurry need not be vibrated. Placing concrete shall be a continuous operation lasting not more than the time required for each concrete placing operation at each pile, as submitted in the placing plan, unless otherwise approved in writing by the Engineer. The concrete shall be placed with concrete pumps and delivery tube system of adequate number and size to complete the placing of concrete in the time specified. The delivery tube system shall consist of one of the following:

A. A tremie tube or tubes, each of which are at least 250 mm in diameter, fed by one or more concrete pumps.
B. One or more concrete pump tubes, each fed by a single concrete pump.

The delivery tube system shall consist of watertight tubes with sufficient rigidity to keep the ends always in the mass of concrete placed. If only one delivery tube is utilized to place the concrete, the tube shall be placed near the center of the drilled hole. Multiple tubes shall be uniformly spaced in the hole. Internal bracing for the steel reinforcing cage shall accommodate the delivery tube system. Tremies shall not be used for piles without space for a 250-mm tube.

Spillage of concrete into the slurry during concrete placing operations shall not be allowed. Delivery tubes shall be capped with a watertight cap, or plugged above the slurry level with a good quality, tight fitting, moving plug that will expel the slurry from the tube as the tube is charged with concrete. The cap or plug shall be designed to be released as the tube is charged. The pump discharge or tremie tube shall extend to the bottom of the hole before charging the tube with concrete. After charging the delivery tube system with concrete, the flow of concrete through a tube shall be induced by slightly raising the discharge end. During concrete placement, the tip of the delivery tube shall be maintained as follows to prevent reentry of the slurry into the tube. Until at least 3 m of concrete has been placed, the tip of the delivery tube shall be within 150 mm of the bottom of the drilled hole, and then the embedment of the tip shall be maintained at least 3 m below the top surface of the concrete. Rapid raising or lowering of the delivery tube shall not be permitted. If the seal is lost or the delivery tube becomes plugged and must be removed, the tube shall be withdrawn, the tube cleaned, the tip of the tube capped to prevent entrance of the slurry, and the operation restarted by pushing the capped tube 3 m into the concrete and then reinitiating the flow of concrete.

When slurry is used, a fully operational standby concrete pump, adequate to complete the work in the time specified, shall be provided at the site during concrete placement. The slurry level shall be maintained within 300 mm of the top of the drilled hole.

A log of concrete placement for each drilled hole shall be maintained by the Contractor when concrete is deposited under slurry. The log shall show the pile location, tip elevation, dates of excavation and concrete placement, total quantity of concrete deposited, length and tip elevation of any casing, and details of any hole stabilization method and materials used. The log shall include a 215 mm x 280 mm sized graph of the concrete placed versus depth of hole filled. The graph shall be plotted continuously throughout placing of concrete. The depth of drilled hole filled shall be plotted vertically with the pile tip oriented at the bottom and the quantity of concrete shall be plotted horizontally. Readings shall be made at least at each 1.5 m of pile depth, and the time of the reading shall be indicated. The graph shall be labeled with the pile location, tip elevation, cutoff elevation, and the dates of excavation and concrete placement. The log shall be delivered to the Engineer within one working day of completion of placing concrete in the pile.

After placing reinforcement and prior to placing concrete in the drilled hole, if drill cuttings settle out of the slurry, the bottom of the drilled hole shall be cleaned. The Contractor shall verify that the bottom of the drilled hole is clean.

If temporary casing is used, concrete placed under slurry shall be maintained at a level at least 1.5 m above the bottom of the casing. The withdrawal of casings shall not cause contamination of the concrete with slurry.

Material resulting from using slurry shall be loaded, transported, and disposed of in conformance with the provisions in "Hazardous and Non-Hazardous Material Excavation" of these special provisions.

Acceptance Testing and Mitigation

Vertical inspection pipes for acceptance testing shall be provided in all cast-in-drilled-hole concrete piles that are 600 mm in diameter or larger, except when the holes are dry or when the holes are dewatered without the use of temporary casing to control ground water.

Inspection pipes shall be Schedule 40 polyvinyl chloride pipes with a nominal inside diameter of 50 mm. Each inspection pipe shall be capped top and bottom and shall have watertight couplers to provide a clean, dry and unobstructed 50-mm diameter clear opening from 1.0 m above the pile cutoff down to the bottom of the reinforcing cage.

If the Contractor drills the hole below the specified tip elevation, the reinforcement and the inspection pipes shall be extended to 75 mm clear of the bottom of the drilled hole.

Inspection pipes shall be placed around the pile, inside the outermost spiral or hoop reinforcement, and 75 mm clear of the vertical reinforcement, at a uniform spacing not exceeding 840 mm measured along the circle passing through the centers of inspection pipes. A minimum of 2 inspection pipes per pile shall be used. When the vertical reinforcement is not bundled and each bar is not more than 26 mm in diameter, inspection pipes may be placed 50 mm clear of the vertical reinforcement. The inspection pipes shall be placed to provide the maximum diameter circle that passes through the centers of the inspection pipes while maintaining the clear spacing required herein. The pipes shall be installed in straight alignment, parallel to the main reinforcement, and securely fastened in place to prevent misalignment during installation of the reinforcement and placing of concrete in the hole.

The Contractor shall log the location of the inspection pipe couplers with respect to the plane of pile cut off, and these logs shall be delivered to the Engineer upon completion of the placement of concrete in the drilled hole.

After placing concrete and before requesting acceptance tests, each inspection pipe shall be tested by the Contractor in the presence of the Engineer by passing a 48.3-mm diameter rigid cylinder 610 mm long through the complete length of pipe. If the 48.3-mm diameter rigid cylinder fails to pass any of the inspection pipes, the Contractor shall attempt to pass a 32.0-mm diameter rigid cylinder 1.375 m long through the complete length of those pipes in the presence of the Engineer. If an inspection pipe fails to pass the 32.0-mm diameter cylinder, the Contractor shall immediately fill all inspection pipes in the pile with water.

The Contractor shall replace each inspection pipe that does not pass the 32.0-mm diameter cylinder with a 50.8-mm diameter hole cored through the concrete for the entire length of the pile. Cored holes shall be located as close as possible to the inspection pipes they are replacing and shall be no more than 150 mm inside the reinforcement. Coring shall not damage the pile reinforcement. Cored holes shall be made with a double wall core barrel system utilizing a split tube type inner barrel. Coring with a solid type inner barrel will not be allowed. Coring methods and equipment shall provide intact cores for the entire length of the pile concrete. The coring operation shall be logged by an Engineering Geologist or Civil Engineer licensed in the State of California and experienced in core logging. Coring logs shall include complete descriptions of inclusions and voids encountered during coring, and shall be delivered to the Engineer upon completion. Concrete cores shall be preserved, identified with the exact location the core was recovered from within the pile, and made available for inspection by the Engineer.

Acceptance tests of the concrete will be made by the Engineer, without cost to the Contractor. Acceptance tests will evaluate the homogeneity of the placed concrete. Tests will include gamma-gamma logging. Tests may also include crosshole sonic logging and other means of inspection selected by the Engineer. The Contractor shall not conduct operations within 8.0 m of the gamma-gamma logging operations. The Contractor shall separate reinforcing steel as necessary to allow the Engineer access to the inspection pipes to perform gamma-gamma logging or other acceptance testing. After requesting acceptance tests and providing access to the piling, the Contractor shall allow 3 weeks for the Engineer to conduct these tests and make determination of acceptance if the 48.3-mm diameter cylinder passed all inspection pipes, and 4 weeks if only the 32.0-mm diameter cylinder passed all inspection pipes. Should the Engineer fail to complete these tests within the time allowance, and if in the opinion of the Engineer, the Contractor's controlling operation is delayed or interfered with by reason of the delay in inspection, the delay will be considered a right of way delay as specified in Section 8-1.09, "Right of Way Delays," of the Standard Specifications.

All inspection pipes and cored holes in a pile shall be dewatered and filled with grout after notification by the Engineer that the pile is acceptable. Placement and removal of water in the inspection pipes shall be at the Contractor’s expense. Grout shall conform to the provisions in Section 50-1.09, "Bonding and Grouting," of the Standard Specifications. The inspection pipes and holes shall be filled using grout tubes that extend to the bottom of the pipe or hole or into the grout already placed.

If acceptance testing performed by the Engineer determines that a pile does not meet the requirements of the specifications, then that pile will be rejected and all depositing of concrete under slurry or concrete placed using temporary casing for the purpose of controlling groundwater shall be suspended until written changes to the methods of pile construction are approved in writing by the Engineer.

The Contractor shall submit to the Engineer for approval a mitigation plan for repair, supplementation, or replacement for each rejected cast-in-drilled-hole concrete pile, and this plan shall conform to the provisions in Section 5-1.02, "Plans and

Working Drawings," of the Standard Specifications. Prior to submitting this mitigation plan, the Engineer will hold a repair feasibility meeting with the Contractor to discuss the feasibility of repairing rejected piling. The Engineer will consider the size of the defect, the location of the defect, and the design information and corrosion protection considerations for the pile. This information will be made available to the Contractor, if appropriate, for the development of the mitigation plan. If the Engineer determines that it is not feasible to repair the rejected pile, the Contractor shall not include repair as a means of mitigation and shall proceed with the submittal of a mitigation plan for replacement or supplementation of the rejected pile.

If the Engineer determines that a rejected pile does not require mitigation due to structural, geotechnical, or corrosion concerns, the Contractor may elect to 1) repair the pile per the approved mitigation plan, or 2) not repair anomalies found during acceptance testing of that pile. For such unrepaired piles, the Contractor shall pay to the State, $400 per cubic meter for the portion of the pile affected by the anomalies. The volume, in cubic meters, of the portion of the pile affected by the anomalies, shall be calculated as the area of the cross-section of the pile affected by each anomaly, in square meters, as determined by the Engineer, multiplied by the distance, in meters, from the top of each anomaly to the specified tip of the pile. If the volume calculated for one anomaly overlaps the volume calculated for additional anomalies within the pile, the calculated volume for the overlap shall only be counted once. In no case shall the amount of the payment to the State for any such pile be less than $400. The Department may deduct the amount from any moneys due, or that may become due the Contractor under the contract.

Pile mitigation plans shall include the following:

A. The designation and location of the pile addressed by the mitigation plan.
B. A review of the structural, geotechnical, and corrosion design requirements of the rejected pile.
C. A step by step description of the mitigation work to be performed, including drawings if necessary.
D. An assessment of how the proposed mitigation work will address the structural, geotechnical, and corrosion design requirements of the rejected pile.
E. Methods for preservation or restoration of existing earthen materials.
F. A list of affected facilities, if any, with methods and equipment for protection of these facilities during mitigation.
G. The State assigned contract number, bridge number, full name of the structure as shown on the contract plans, District-County-Route-Kilometer Post, and the Contractor's (and Subcontractor's if applicable) name on each sheet.
H. A list of materials, with quantity estimates, and personnel, with qualifications, to be used to perform the mitigation work.
I. The seal and signature of an engineer who is licensed as a Civil Engineer by the State of California.

For rejected piles to be repaired, the Contractor shall submit a pile mitigation plan that contains the following additional information:

A. An assessment of the nature and size of the anomalies in the rejected pile.
B. Provisions for access for additional pile testing if required by the Engineer.

For rejected piles to be replaced or supplemented, the Contractor shall submit a pile mitigation plan that contains the following additional information:

A. The proposed location and size of additional piling.
B. Structural details and calculations for any modification to the structure to accommodate the replacement or supplemental piling.

All provisions for cast-in-drilled-hole concrete piling shall apply to replacement piling.

The Contractor shall allow the Engineer 3 weeks to review the mitigation plan after a complete submittal has been received.

Should the Engineer fail to review the complete pile mitigation submittal within the time specified, and if, in the opinion of the Engineer, the Contractor's controlling operation is delayed or interfered with by reason of the delay in reviewing the pile mitigation plan, an extension of time commensurate with the delay in completion of the work thus caused will be granted in conformance with the provisions in Section 8-1.09, "Right of Way Delays," of the Standard Specifications.

When repairs are performed, the Contractor shall submit a mitigation report to the Engineer within 10 days of completion of the repair. This report shall state exactly what repair work was performed and quantify the success of the repairs relative to the submitted mitigation plan. The mitigation report shall be stamped and signed by an engineer that is licensed as a Civil Engineer by the State of California. The mitigation report shall show the State assigned contract number, bridge number, full name of the structure as shown on the contract plans, District-County-Route-Kilometer Post, and the Contractor (and Subcontractor if applicable) name on each sheet. The Engineer will be the sole judge as to whether a

mitigation proposal is acceptable, the mitigation efforts are successful, and to whether additional repairs, removal and replacement, or construction of a supplemental foundation is required.

MEASUREMENT AND PAYMENT (PILING)

Measurement and payment for the various types and classes of piles shall conform to the provisions in Sections 49-6.01, "Measurement," and 49-6.02, "Payment," of the Standard Specifications and these special provisions.

Payment for cast-in-place concrete piling shall conform to the provisions in Section 49-6.02, "Payment," of the Standard Specifications and these special provisions except that, when the diameter of cast-in-place concrete piling is shown on the plans as 600 mm or larger, reinforcement in the piling will be paid for by the kilogram as bar reinforcing steel (bridge).

Full compensation for slurry, depositing concrete under slurry, test batches, inspection pipes, filling inspection holes and pipes with grout, drilling oversized cast-in-drilled-hole concrete piling, filling cave-ins and oversized piles with concrete, and redrilling through concrete, shall be considered as included in the contract prices paid per meter for cast-in-drilled-hole concrete piling of the types and sizes listed in the Engineer's Estimate, and no additional compensation will be allowed therefor.

Full compensation for conforming to the handling, loading, transporting, and disposal of hazardous materials resulting from constructing the cast-in-drilled-hole concrete piling shall be considered as included in the contract price paid per meter for cast-in-drilled-hole concrete piling of the types and sizes listed in the Engineer's Estimate, and no separate payment will be made therefor.

The contract price paid per meter for cast-in-drilled-hole concrete piling (rock socket) of the sizes listed in the Engineer's Estimate shall include full compensation for furnishing all labor, materials, tools, equipment, and incidentals, and for doing all the work involved in drilling or coring holes, disposing of the material resulting from drilling or coring holes, and furnishing and placing concrete, complete in place, to the required penetration, as shown on the plans, as specified in the Standard Specifications and these special provisions, and as directed by the Engineer.

Additional cast-in-drilled-hole concrete piling, including inspection pipes, and bar reinforcing steel, required to extend the piling into bedrock and to maintain the length of cast-in-drilled-hole concrete piling (rock socket) into bedrock, as shown on the plans, will be paid for as extra work as provided in Section 4-1.03D, "Extra Work," of the Standard Specifications.

Test pile and anchor piles will be measured and paid for as cast-in-drilled-hole concrete piling.

Full compensation for dewatering during pile testing, for installing, protecting and removing the instruments from the test pile, and for furnishing and installing high strength threaded bars and couplers in the anchor piles shall be considered as included in the contract price paid per meter for cast-in-drilled-hole concrete piling of the types and sizes listed in the Engineer's Estimate, and no separate payment will be made therefor.

10-1.50 PRESTRESSING CONCRETE

Prestressing concrete shall conform to the provisions in Section 50, "Prestressing Concrete," of the Standard Specifications.

10-1.51 CONCRETE STRUCTURES

Portland cement concrete structures shall conform to the provisions in Section 51, "Concrete Structures," of the Standard Specifications and these special provisions.

GENERAL

Shotcrete shall not be used as an alternative construction method for reinforced concrete members unless otherwise specified.

Neoprene strip shall be furnished and installed at abutment backwall joint protection in conformance with the details shown on the plans, the provisions in the Standard Specifications, and these special provisions.

Furnishing and installing neoprene strip shall conform to the requirements for strip waterstops as provided in Section 51-1.145, "Strip Waterstops," of the Standard Specifications, except that the protective board will not be required.

The excavated material for inlets and manholes in existing original ground shall be disposed of outside the highway right of way in conformance with the provisions as provided in "Hazardous and Non-Hazardous Material Excavation," elsewhere in these special provisions.

Full compensation for imported material and the disposal of excavated material for inlets and manholes outside the highway right of way in conformance with the provisions as provided in "Hazardous and Non-Hazardous Material Excavation," shall be considered as included in the contract price paid per cubic meter for minor concrete (minor structure) and no additional compensation will be allowed therefore.

FALSEWORK

Falsework shall conform to the provisions in Section 51, "Concrete Structures," of the Standard Specifications and these special provisions.

Attention is directed to "Railroad Relations and Insurance" of these special provisions for additional requirements for falsework over railroads.

In addition to the provisions in Section 51-1.06A, "Falsework Design and Drawings," of the Standard Specifications, the time to be provided for the Engineer's review of the working drawings for specific structures, or portions thereof, shall be as follows:

Portion of Structure	Total Review Time - Weeks
Central Viaduct (Replace) Bridge No. 34-0077	
Bent 1	4
Bent 2	4
Bent 3	4
Bent 4	10
Bent 5	10
Bent 6	4
Bent 7	4
Bent 8	4
Bent 9	4
Bent 10	4

Temporary crash cushion modules, as shown on the plans and conforming to the provisions in "Temporary Crash Cushion Module" of these special provisions, shall be installed at the approach end of temporary railings which are located less than 4.6 m from the edge of a traffic lane. For 2-way traffic openings, temporary crash cushion modules shall be installed at the departing end of temporary railings which are located less than 1.8 m from the edge of a traffic lane.

Welding and Nondestructive Testing

Welding of steel members, except for previously welded splices and except for when fillet welds are used where load demands are less than or equal to 175 N/mm for each 3 mm of fillet weld, shall conform to AWS D1.1 or other recognized welding standard. The welding standard to be utilized shall be specified by the Contractor on the working drawings. Previously welded splices for falsework members are defined as splices made prior to the member being shipped to the project site.

Splices made by field welding of steel beams at the project site shall undergo nondestructive testing (NDT). At the option of the Contractor, either ultrasonic testing (UT) or radiographic testing (RT) shall be used as the method of NDT for each field weld and any repair made to a previously welded splice in a steel beam. Testing shall be performed at locations selected by the Contractor. The length of a splice weld where NDT is to be performed, shall be a cumulative weld length equal to 25 percent of the original splice weld length. The cover pass shall be ground smooth at the locations to be tested. The acceptance criteria shall conform to the requirements of AWS D1.1, Section 6, for cyclically loaded nontubular connections subject to tensile stress. If repairs are required in a portion of the weld, additional NDT shall be performed on the repaired sections. The NDT method chosen shall be used for an entire splice evaluation including any required repairs.

For all field welded splices, the Contractor shall furnish to the Engineer a letter of certification which certifies that all welding and NDT, including visual inspection, are in conformance with the specifications and the welding standard shown on the approved working drawings. This letter of certification shall be signed by an engineer who is registered as a Civil Engineer in the State of California and shall be provided prior to placing any concrete for which the falsework is being erected to support.

For previously welded splices, the Contractor shall determine and perform all necessary testing and inspection required to certify the ability of the falsework members to sustain the stresses required by the falsework design. This welding certification shall be in writing, shall be signed by an engineer who is registered as a Civil Engineer in the State of California, and shall be provided prior to placing any concrete for which the falsework is being erected to support.

The Contractor's engineer who signs the falsework drawings shall also certify in writing that the falsework is constructed in conformance with the approved drawings and the contract specifications prior to placing concrete. This certification shall include performing any testing necessary to verify the ability of the falsework members to sustain the stresses required by the falsework design. The engineer who signs the drawings may designate a representative to perform this certification. Where falsework contains openings for railroads, vehicular traffic, or pedestrians, the designated representative shall be qualified to

perform this work, shall have at least three years of combined experience in falsework design or supervising falsework construction, and shall be registered as a Civil Engineer in the State of California. For other falsework, the designated representative shall be qualified to perform this work and shall have at least three years of combined experience in falsework design or supervising falsework construction. The Contractor shall certify the experience of the designated representative in writing and provide supporting documentation demonstrating the required experience if requested by the Engineer.

DECK CRACK TREATMENT

The Contractor shall use all means necessary to minimize the development of shrinkage cracks.

The Contractor shall remove all equipment and materials from the deck and clean the surface as necessary for the Engineer to measure the surface crack intensity. Surface crack intensity will be determined by the Engineer after completion of concrete cure, prior to prestressing, and prior to the release of falsework. In any 50-m^2 portion of deck within the limits of the new concrete deck, should the intensity of cracking be such that there are more than 5 m of cracks whose width at any location exceeds 0.5-mm, the deck shall be treated with methacrylate resin. The area of deck to be treated shall have a width that extends for the entire width of new deck inside the concrete barriers and a length that extends at least 1.5 m beyond the furthest single continuous crack outside the 50-m^2 portion, measured from where that crack exceeds 0.5-mm in width, as determined by the Engineer.

Deck crack treatment shall consist of test sealing, and furnishing and applying methacrylate resin in conformance with the requirements of these special provisions. If grinding operation is required, deck treatment shall take place after grinding.

Prior to the start of deck treatment work, the Contractor shall submit for approval by the Engineer, a program for public safety associated with the use of methacrylate resin. The program shall identify materials, equipment, and methods to be used. The Contractor shall not perform deck treatment work, other than that specifically authorized in writing by the Engineer, until the program has been approved.

If the measures being taken by the Contractor are inadequate to provide for public safety associated with use of methacrylate resin, the Engineer will direct the Contractor to revise the operations and the public safety program. Directions for revisions will be in writing and will specify the items in which the Contractor's program is inadequate. No further deck treatment shall be performed until public safety measures are adequate, and a revised program for public safety has been approved.

The Engineer will notify the Contractor of the approval or rejection of any submitted or revised program for public safety associated with the use of methacrylate resin within 10 working days of receipt of the final submitted program.

The State will not be liable to the Contractor for failure to approve all or any portion of an originally submitted or revised program for public safety associated with the use of methacrylate resin, nor for any delays to the work due to the Contractor's failure to submit an acceptable program for public safety associated with the use of methacrylate resin. If the Engineer does not review or approve the program submitted by the Contractor within the time specified and if, in the opinion of the Engineer, the Contractor's controlling operation is delayed or interfered with by reason of the delay in reviewing the program for public safety, the delay will be considered a right of way delay in conformance with the provisions in Section 8-1.09, "Right of Way Delays," of the Standard Specifications.

The Contractor shall furnish an airborne emissions monitoring plan prepared by a certified industrial hygienist. Emissions will be monitored at a minimum of 4 points including the point of mixing, the point of application, and the point of nearest public contact, as determined by the Engineer. At the completion of work, a report by the certified industrial hygienist with results of the airborne emissions monitoring plan shall be furnished to the Engineer.

Materials

The material used for treating the deck shall be a low odor, high molecular weight methacrylate resin. Prior to adding initiator, the resin shall have a maximum volatile content of 30 percent when tested in conformance with the requirements in ASTM Designation: D 2369, and shall conform to the following:

PROPERTY	TEST METHOD	REQUIREMENT
Viscosity mPa·s, maximum, (Brookfield RVT with UL adaptor, 50 RPM at 25°C)	ASTM D 2196	0.025
Specific Gravity minimum, at 25°C	ASTM D 1475	0.90
Flash Point °C, minimum	ASTM D 3278	82
Vapor Pressure mm Hg, maximum, at 25°C	ASTM D 323	1.0
Tack-free time minutes, maximum at 25°C	California Test 551	400
PCC Saturated Surface-Dry Bond Strength MPa, minimum at 24 hours and 21±1°C	California Test 551	3.5
* Test shall be performed prior to adding initiator.		

A Material Safety Data Sheet shall be furnished prior to use for each shipment of high molecular weight methacrylate resin.

The promoter and initiator, if supplied separately from the resin, shall not be mixed directly with each other. Containers of promoters and initiators shall not be stored together in a manner that will allow leakage or spillage from one to contact the containers or material of the other.

Testing

The Contractor shall allow 14 days for sampling and testing by the Engineer of the high molecular weight methacrylate resin prior to proposed use.

The Contractor shall treat a test area within the project limits of approximately 50 m^2 at a location approved by the Engineer. Conditions during the test treatment shall be similar to those expected on the deck. Equipment used in the test shall be similar to those used for the deck treating operations. If the test area is on the traveled way, traffic shall not be allowed on the treated test area until (1) the treated surface is tack free (non-oily), (2) the sand cover adheres sufficiently to resist brushing by hand, and (3) the coefficient of friction of the deck is at least 0.35 when tested in conformance with the requirements in California Test 342.

Should the above requirements for traffic use not be met, the Contractor shall suspend treating of bridge decks until another test area is treated and complies with the requirements.

Construction

Prior to deck treatment with methacrylate resin, the bridge deck surface shall be cleaned by abrasive blasting and all loose material shall be blown from visible cracks using high-pressure air. Concrete curing seals shall be cleaned from the deck surface to be treated, and the deck shall be dry when blast cleaning is performed. If the deck surface becomes contaminated at any time prior to placing the penetrating sealer, the deck surface shall be cleaned by abrasive blasting.

Equipment shall be fitted with suitable traps, filters, drip pans, or other devices as necessary to prevent oil or other deleterious material from being deposited on the deck.

Where abrasive blasting is being performed within 3 m of a lane occupied by public traffic, the residue including dust shall be removed immediately after contact between the abrasive and the surface being treated. The removal shall be by a vacuum attachment operating concurrently with the abrasive blasting operation.

The relative humidity shall be less than 90 percent at time of treatment.

A compatible promoter/initiator system shall be capable of providing a resin gel time of not less than 40 minutes nor more than 1.5 hours at the temperature of application. Gel time shall be adjusted to compensate for the changes in temperature throughout treatment application.

The quantity of resin mixed with promoter and initiator shall be limited to 20 L at a time for manual application.

Machine application of the resin shall be performed by using a two-part resin system using a promoted resin for one part and an initiated resin for the other part. This two-part resin system shall be combined at equal volumes to the spray bars through separate positive displacement pumps. Combining of the 2 components shall be by either static in-line mixers or by external intersecting spray fans. The pump pressure at the spray bars shall not be great enough to cause appreciable atomization of the resin. Compressed air shall not be used to produce the spray. A shroud shall be used to enclose the spray bar apparatus. Hand held spray apparatus shall not be used.

The Contractor shall allow methacrylate resin to be applied only to the specified area. Barrier rails, joints, and drainage facilities shall be adequately protected to prevent contamination by the treatment material. Contaminated items shall be repaired at the Contractor's expense.

The prepared area shall be dry and the surface temperature shall be less than or equal to 38°C when the resin is applied. The rate of application of promoted/initiated resin shall be approximately 2.5 square meters per liter, ± 0.1 square meter per liter.

The deck surfaces to be treated shall be flooded with resin, allowing penetration into the concrete and filling of all cracks. The treatment shall be applied within 5 minutes after complete mixing. A significant increase in viscosity shall be cause for rejection. Excess material shall be redistributed by squeegees or brooms within 10 minutes after application.

After the resin has been applied, at least 20 minutes shall elapse before applying sand. The sand shall be commercial quality dry blast sand. Ninety-five percent of the sand shall pass the 2.36-mm sieve, and 95 percent shall be retained on the 850-µm sieve. The sand shall be applied at a rate of one kilogram per square meter, ± 0.1 kilogram per square meter.

Excess sand shall be removed from the deck surface by vacuuming or sweeping prior to opening to traffic.

Traffic shall not be allowed on the treated area until (1) the treated surface is tack free (non-oily), (2) the sand cover adheres sufficiently to resist brushing by hand, and (3) the coefficient of friction of the deck is at least 0.35 when tested in conformance with the requirements in California Test 342.

MEASUREMENT AND PAYMENT

Measurement and payment for concrete in structures shall conform to the provisions in Section 51-1.22, "Measurement," and Section 51-1.23, "Payment," of the Standard Specifications and these special provisions.

Full compensation for forming blockouts for joint seal assemblies shall be considered as included in the contract price paid per cubic meter for structural concrete, bridge and no separate payment will be made therefor.

Full compensation for deck crack treatment, including a program for public safety and airborne monitoring, shall be considered as included in the contract price paid per cubic meter for structural concrete (bridge) and no additional compensation will be allowed therefor.

10-1.52 PTFE BEARING

PTFE bearings, consisting of steel reinforced elastomeric bearing pads, polytetrafluoroethylene (PTFE) surfacing, anchors, stainless steel and steel plates, shall conform to the details shown on the plans, the provisions in Section 51, "Concrete Structures," of the Standard Specifications, and these special provisions.

The Contractor shall submit working drawings for the PTFE bearings to the Office of Structure Design, (OSD) for approval in conformance with the provisions in Section 5-1.02, "Plans and Working Drawings," of the Standard Specifications. For initial review, 4 sets shall be submitted for bridge structures. After review, between 6 and 12 sets, as requested by the Engineer, shall be submitted to OSD for final approval and for use during construction.

Working drawings shall be 279 mm x 432 mm in size, and each drawing and calculation sheet shall include the name of the structure as shown on the contract plans, District-County-Route, bridge number, and contract number.

Working drawings shall be submitted sufficiently in advance of the start of the affected work to allow time for review by the Engineer and correction by the Contractor of the drawings without delaying the work. The time shall be proportional to the complexity of the work but in no case shall the time be less than 6 weeks for bridge structures after complete drawings and all support data are submitted. The location of match marks on plate edges shall be shown on the working drawings.

At the completion of each structure on the contract, one set of prints on 75-g/m^2 (minimum) bond paper, 279 mm x 432 mm in size, of the corrected original tracings of all working drawings for each structure shall be furnished to the Engineer. Prints of drawings which are common to more than one structure shall be submitted for each structure. An index prepared specifically for the drawings for each structure containing sheet numbers and titles shall be included on the first print in the set for each structure. Prints for each structure shall be arranged in the order of drawing numbers shown in the index.

The edge of the corrected original tracing image shall be clearly visible and visually parallel with the edges of the page. A clear, legible symbol shall be provided as near to the upper left side of each page as is feasible within the original print to show the amount of reduction and a horizontal and vertical scale shall be provided on each reduced print to facilitate enlargement to original scale.

The manufacturer shall furnish Certificates of Compliance in conformance with the provisions in Section 6-1.07, "Certificates of Compliance," of the Standard Specifications, for all material used in the PTFE bearings.

The shear modulus of the elastomer in the elastomeric bearing pads shall be 750±75 kPa.

PTFE sheet shall be made from unfilled PTFE resin and shall conform to the following requirements:

Test	Test Method	Requirements
Tensile strength (Minimum)	ASTM D 4894 or D 4895	19.3 MPa
Elongation (Minimum)	ASTM D 4894 or D 4895	200 %

The PTFE resin shall be virgin material (not reprocessed) meeting the requirements of ASTM Designation: D 4894 or D 4895, with a minimum thickness of 6 mm. Specific gravity shall be from 2.13 to 2.19. Melting point shall be 327±10°C.

The PTFE sliding surface shall be provided with lubricant dimples with a maximum diameter of 8 mm, a minimum depth of 2 mm, and a maximum depth of one half of the PTFE sheet thickness. The dimples shall be uniformly distributed within the area 6 mm from the edges of the PTFE sheet and occupy between 20 percent and 30 percent of the PTFE sheet area.

Stainless steel plates shall conform to the requirements of ASTM Designation: A 240, Type 304, with a minimum thickness of 3 mm.

Steel plates, except stainless steel, shall conform to the requirements of ASTM Designation: A 36/A 36M.

Bearing anchors shall conform to the requirements in Section 75, "Miscellaneous Metal," of the Standard Specifications.

Welding of structural steel shall conform to the requirements of AWS D1.1. Welding of structural steel to stainless steel shall conform to the requirements of AWS D1.6.

The PTFE sheet shall be adhesive bonded in the recess of steel plate under controlled factory conditions. The adhesive material shall be an epoxy resin conforming to the requirements of Federal Specification: MMM-A-134.

Contact surfaces of PTFE sheet and steel plate to be bonded shall be uniformly roughened to a minimum roughness height value of 6.3 µm.

The side of the PTFE sheet to be bonded shall be factory treated by the sodium naphthalene or sodium ammonia process, after the contact surface is roughened.

After completion of the bonding operation the PTFE surface shall be smooth and free from bubbles. The PTFE sheet shall show no signs of delamination and shall be fully bonded within the recess.

The stainless steel plate shall be attached by perimeter welding using Type 309L electrodes. After completion of the weld operation, the stainless steel plate shall be smooth and free from waves.

The flatness of the bearing elements shall be controlled such that upon completion of the bearing assembly, the PTFE/stainless steel sliding interface shall be in full bearing.

The mating surface of the stainless steel plate with the PTFE surfacing shall have a minimum #8 mirror finish determined according to ANSI Standard B46.1. The sliding element of the production bearings shall have a first movement static coefficient of friction not exceeding 0.06 when tested without the coating of silicone grease.

Steel reinforced elastomeric bearing pads shall be fully vulcanized to the steel plates under factory controlled conditions, and the bond shall have a peel-strength of at least 5.3 Newtons per millimeter as determined by California Test 663.

Metal surfaces of bearings exposed to the atmosphere and in contact with the structure in the completed work, except stainless steel surfaces, shall be cleaned and painted in conformance with the provisions in Sections 59-2, "Painting Structural Steel," and 91, "Paint" of the Standard Specifications, and these special provisions.

Certification in conformance with the requirements in SSPC-QP 1, SSPC-QP 2, and SSPC-QP 3 of the "SSPC: The Society for Protective Coatings" will not be required for cleaning and painting PTFE bearings.

Prior to performing any painting or paint removal, the Contractor shall submit to the Engineer, in conformance with the provisions in Section 5-1.02, "Plans and Working Drawings," of the Standard Specifications, 3 copies of a separate Painting Quality Work Plan (PQWP) for each item of work for which painting or paint removal is to be performed. As a minimum, each PQWP shall include the following:

A. The name of each Contractor or subcontractor to be used.
B. One copy each of all current "SSPC: The Society for Protective Coatings" specifications or qualification procedures which are applicable to the painting or paint removal to be performed. These documents shall become the permanent property of the Department.
C. Proposed methods and equipment to be used for any paint application.

The Engineer shall have 2 weeks to review the PQWP submittal after a complete plan has been received. No painting or paint removal shall be performed until the PQWP for that work is reviewed by the Engineer. Should the Engineer fail to complete the review within this time allowance and if, in the opinion of the Engineer, the Contractor's controlling operation is delayed or interfered with by reason of the delay in reviewing the PQWP, the delay will be considered a right of way delay in conformance with the provisions in Section 8-1.09, "Right of Way Delays," of the Standard Specifications.

CLEANING

Exposed new metal surfaces shall be dry blast cleaned in conformance with the requirements in Surface Preparation Specification No. 10, "Near White Blast Cleaning," of the "SSPC: The Society for Protective Coatings." Blast cleaning shall leave surfaces with a dense, uniform, angular anchor pattern of not less than 40 µm nor more than 86 µm as measured in conformance with the requirements in ASTM Designation: D 4417.

Mineral and slag abrasives used for blast cleaning steel shall conform to the requirements in Abrasive Specification No. 1, "Mineral and Slag Abrasives," of the "SSPC: The Society for Protective Coatings" and shall not contain hazardous material. Mineral and slag abrasives shall comply with the requirements for Class A, Grade 2 to 3 as defined therein.

A Certificate of Compliance conforming to the provisions in Section 6-1.07, "Certificates of Compliance," of the Standard Specifications and a Material Safety Data Sheet shall be furnished prior to use for each shipment of blast cleaning material for steel.

PAINTING

Blast cleaned surfaces shall receive a single undercoat, and a final coat where specified, consisting of a waterborne inorganic zinc coating conforming to the requirements in AASHTO Designation M 300, Type II, except that: 1) the first 3 sentences of Section 4.7, "Primer Field Performance Requirements," and the entire Section 4.7.1 shall not apply, and 2) zinc dust shall be Type II in conformance with the requirements in ASTM Designation: D 520. The inorganic zinc coating shall be listed on the qualified products list which may be obtained from the Transportation Laboratory.

The color of the final application of inorganic zinc coating shall match Federal Standard 595B No. 36373.

Inorganic zinc coating shall be used within 12 hours of initial mixing.

Application of inorganic zinc coating shall conform to the provisions for applying zinc-rich coating in Section 59-2.13, "Application of Zinc-Rich Primer," of the Standard Specifications.

Inorganic zinc coating shall not be applied when the atmospheric or surface temperature is less than 7°C or more than 29°C, nor when the relative humidity exceeds 85 percent.

The single undercoat of inorganic zinc coating shall be applied to the required dry film thickness in 2 or more applications within 4 hours after blast cleaning.

The total dry film thickness of all applications of the inorganic zinc undercoat shall be not less than 100 µm nor more than 200 µm.

Areas where mudcracking occurs in the inorganic zinc coating shall be blast cleaned and repainted with inorganic zinc coating to the specified thickness.

Dry spray, or overspray, as defined in the Steel Structures Painting Manual, Volume 1, "Good Painting Practice," of the "SSPC: The Society for Protective Coatings," shall be removed prior to application of subsequent coats or final acceptance. Removal of dry spray shall be by screening or other methods that minimize polishing of the inorganic zinc surface. The dry film thickness of the coating after removal of dry spray shall be in conformance with the provisions for applying the single undercoat, as specified herein.

The inorganic zinc coating shall be tested for adhesion and cure. The locations of the tests will be determined by the Engineer. The sequence of the testing operations shall be determined by the Contractor. The testing for adhesion and cure will be performed no sooner than 72 hours after application of the single undercoat of inorganic zinc coating. At the Contractor's expense, satisfactory access shall be provided to allow the Engineer to determine the location of the tests and to test the inorganic zinc coating cure. The inorganic zinc coating shall pass the following tests:

Adhesion

1. The inorganic zinc coating shall have a minimum adhesion to steel of 4 MPa when measured at no more than 6 locations per bearing using a self-aligning adhesion tester in conformance with the requirements in ASTM Designation: D 4541. The Contractor, at the Contractor's expense, shall: (1) verify compliance with the adhesion requirements, (2) furnish test results to the Engineer, and (3) repair the coating after testing.

Cure

1. The inorganic zinc coating, when properly cured, shall exhibit a solid, hard, and polished metal surface when firmly scraped with the knurled edge of a quarter. Inorganic zinc coating that is powdery, soft, or does not exhibit a polished

metal surface, as determined by the Engineer, shall be repaired by the Contractor, at the Contractor's expense, by blast cleaning and repainting with inorganic zinc coating to the specified thickness.

Finish coats will not be required on the bearings.

After installation, the top of the assembly shall be removed and a 1.5 mm thick coating of silicone grease shall be applied to the entire PTFE surface and the bearing reassembled without damage to the mating sliding surfaces. Silicone grease shall conform to the requirements in Military Specification: MIL-S-8660.

Damaged bearings and bearings with scratched mating surfaces shall be returned to the factory for replacement or resurfacing.

Prior to proof testing or painting, all individual components shall be permanently die-stamped on 2 of 4 sides with markings consisting of bearing number and contract number. Each bearing shall have a unique bearing number and match marks on plate edges to insure correct assembly at the job site.

Full sized PTFE bearings shall be proof tested and evaluated for compression and coefficient of initial static friction in the presence of the Engineer. The proof tests shall be performed on samples randomly selected by the Engineer from the production bearings to be used in the work. Proof testing shall be performed by the Contractor at the manufacturer's plant or at an approved laboratory. If proof tests can not be performed at the specified load, the Contractor shall submit to the Engineer for review and approval a testing plan listing additional physical tests. These tests shall be performed in the presence of the Engineer, and shall demonstrate that the requirements for proof testing at the specified load are satisfied. The Contractor shall give the Engineer at least 7 days notice before beginning proof testing. Proof testing of PTFE bearings shall conform to the following requirements:

A. One bearing per lot of production PTFE bearings shall be proof tested. A lot is defined as 25 PTFE bearings or fraction thereof of the same type, within a load category.
B. A load category shall consist of bearings of differing vertical load capacity within a range defined as follows:

    1. Bearings with less than or equal to 2225 kN maximum vertical load capacity.
    2. Bearings with greater than 2225 kN but less than or equal to 8900 kN maximum vertical load capacity.
    3. Bearings with greater than 8900 kN maximum vertical load capacity.

C. Bearings shall be proof tested for compression and coefficient of friction.
D. Proof tests for compression: The bearing shall be held for one hour at 1.5 times the maximum vertical load shown on the plans for the bearing.
E. Proof tests for coefficient of friction: The tests shall be performed at the minimum dead load shown on the plans for the bearing with the test load applied for 12 hours continuously and the test load shall not be reduced or removed prior to friction measurement and the following:

    1. The tests shall be arranged to allow measurement of the static coefficient of friction on the first movement of the bearing.
    2. The first movement static and dynamic coefficients of friction shall be measured at a sliding speed not exceeding 25 millimeters per minute and shall not exceed the specified coefficient of initial static friction.
    3. The test bearings shall be subjected to a minimum of 100 movements of at least 25 mm of relative movement at a sliding speed not exceeding 300 millimeters per minute. After cycling, the first movement static and dynamic coefficients of friction shall be measured again at a sliding speed not exceeding 25 millimeters per minute and shall not exceed the specified coefficient of initial static friction.

F. The bearing surfaces shall be cleaned prior to testing.
G. Proof testing of bearings shall be done after conditioning specimens for 12 hours at 24°±3°C.
H. The proof tested bearings shall show no visible sign of: (1) bond failure of bearing surfaces, (2) separation or lift-off of plates from each other or from PTFE surfaces, (3) excessive transfer of PTFE to the stainless steel surface, or (4) other defects. When a proof tested bearing fails to comply with these specifications, all bearings in that lot shall be individually tested for acceptance.
I. Proof test results shall be certified correct and signed by the testing laboratory personnel who conducted the test and interpreted the test results. Proof test results shall include the bearing numbers of the bearings tested.

One sample of elastomeric bearing pad, 57±3 mm high and not less than 200 mm x 300 mm in plan, shall be cut by the manufacturer from one of the thickest production elastomeric bearing pads, as directed by the Engineer, and furnished to the Transportation Laboratory. The Contractor shall allow 3 weeks for testing and obtaining satisfactory results after the sample elastomeric bearing pad has been received.

A test specimen taken from the sample furnished to the Transportation Laboratory will be tested in conformance with the requirements in California Test 663 for 10,000 cycles at the design load and 1/2 T (T = total thickness of elastomer) translation. The testing speed shall not exceed 115 millimeters per minute. Specimens tested shall show no indication of deterioration of elastomer or loss of bond between the elastomer and steel laminates.

PTFE bearing sole plates shall be temporarily supported during concrete placement. Temporary supports shall prevent the rotation or displacement of the bearings during concrete placing operations. Temporary supports shall not inhibit the functioning of the PTFE bearings after concrete is placed. Temporary supports shall not restrict the movement at bridge joints due to temperature changes and shortening from prestress forces. Materials for temporary supports within the limits for placing concrete shall conform to the requirements for form fasteners.

PTFE and stainless steel surfaces shall be protected from contamination and weather damage.

Quantities of PTFE bearings will be determined as units from actual count in the completed work. A PTFE bearing with more than one disc shall be considered a single PTFE bearing.

The contract unit price paid for PTFE bearing shall include full compensation for furnishing all labor, materials, tools, equipment, and incidentals, and for doing all the work involved in constructing the bearing, complete in place, including temporary supports, proof testing, and cleaning and painting of PTFE bearings, as shown on the plans, as specified in the Standard Specifications and these special provisions, and as directed by the Engineer.

Full compensation for furnishing the sample of elastomeric bearing pad shall be considered as included in the contract unit price paid for PTFE bearing, and no separate payment will be made therefor.

If a portion or all of PTFE bearings are either fabricated or tested at a site more than 480 air line kilometers from both Sacramento and Los Angeles, additional shop inspection expenses will be sustained by the State. Whereas it is and will be impractical and extremely difficult to ascertain and determine the actual increase in such expenses, it is agreed that payment to the Contractor for PTFE bearings will be reduced $5,000 for each fabrication or testing site located more than 480 air line kilometers from both Sacramento and Los Angeles and an additional $10,000 ($15,000 total) for each fabrication or testing site located more than 4800 air line kilometers from both Sacramento and Los Angeles.

10-1.53 PTFE SPHERICAL BEARING

PTFE spherical bearings, consisting of polytetrafluoro-ethylene (PTFE) and stainless steel bearing surfaces, structural steel plates and anchors shall conform to the details shown on the plans and these special provisions.

PTFE spherical bearings shall be of 2 types:

A. Expansion type with spherical and sliding bearing surfaces.

The manufacturer of the PTFE spherical bearings shall show evidence that PTFE spherical bearings furnished by the same manufacturer and used in conditions similar to this application have had at least 3 years of satisfactory service at each of 2 projects.

A qualified representative of the manufacturer shall be present during installation of the first bearing and shall be available for advice during any remaining installations.

The Contractor shall submit working drawings of the PTFE spherical bearings to the Office of Structure Design (OSD) for approval in conformance with the provisions in Section 5-1.02, "Plans and Working Drawings," of the Standard Specifications. For initial review, 4 sets shall be submitted for bridge structures. After review, between 6 and 12 sets, as requested by the Engineer, shall be submitted to OSD for final approval and for use during construction.

The working drawings for PTFE spherical bearings shall include a description of the method of mechanical interlocking of the PTFE fabric to the metallic substrate and details of temporary support for the PTFE bearing sole plate during concrete placement.

Working drawings shall be 279 mm x 432 mm or 559 mm x 864 mm in size and each drawing and calculation sheet shall include the name of the structure as shown on the contract plans, District-County-Route, bridge number, and contract number.

Working drawings shall be submitted sufficiently in advance of the start of the affected work to allow time for review by the Engineer and correction by the Contractor of the drawings without delaying the work. The time shall be proportional to the complexity of the work but in no case shall the time be less than 6 weeks for bridge structures after complete drawings and all support data are submitted.

At the completion of each structure on the contract, one set of reduced prints on 75-g/m^2 (minimum) bond paper, 279 mm x 432 mm in size, of the corrected original tracings of all working drawings for each structure shall be furnished to the Engineer. Reduced prints of drawings which are common to more than one structure shall be submitted for each structure. An index prepared specifically for the drawings for each structure containing sheet numbers and titles shall be included on the first reduced print in the set for each structure. Reduced prints for each structure shall be arranged in the order of drawing numbers shown in the index.

The edge of the corrected original tracing image shall be clearly visible and visually parallel with the edges of the page. A clear, legible symbol shall be provided as near to the upper left side of each page as is feasible within the original print to show the amount of reduction and a horizontal and vertical scale shall be provided on each reduced print to facilitate enlargement to original scale.

PTFE spherical bearings shall be installed on surfaces prepared in conformance with the provisions in Section 55-3.19, "Bearings and Anchorages," of the Standard Specifications.

The manufacturer shall furnish Certificates of Compliance in conformance with the provisions in Section 6-1.07, "Certificates of Compliance," of the Standard Specifications for all material used in the PTFE spherical bearings. The certification shall be supported by a copy of the results of all proof tests performed on the bearings.

PTFE surfaces of PTFE spherical bearings shall be unfilled PTFE fabric made from virgin PTFE oriented multifilament and other fibers. The resin in the filaments shall be virgin PTFE material (not reprocessed) in conformance with the requirements of ASTM Designation: D 4441.

At the highest point of substrate and after compression, the PTFE fabric shall have a minimum thickness of 1.6 mm and a maximum thickness of 3.2 mm.

Flat stainless steel surfaces shall be a weld overlay on structural steel plate, or solid or sheet stainless steel conforming to the requirements of ASTM Designation: A 240, Type 304 with a minimum thickness of 3.2 mm.

Curved stainless steel surfaces shall be solid stainless steel conforming to the requirements of ASTM Designation: A 240, Type 304.

Curved stainless steel surfaces with dimensions shown on the plans exceeding 101.6 mm in thickness shall be either a weld overlay on structural steel plate or solid stainless steel conforming to the requirements of ASTM Designation: A 240, Type 304. Stainless steel sheet will not be allowed.

When a weld overlay is used for stainless steel surfacing, the overlay shall be placed by submerged arc welding using Type 309L electrodes. The finished overlay shall have a 2.38 mm minimum thickness after welding, grinding and polishing. Prior to welding, the manufacturer must submit a complete weld procedure to the Engineer for approval.

When stainless steel sheets are used for stainless steel surfacing, the sheets shall be attached by perimeter arc welding using Type 309L electrodes. After completion of the weld operation, the stainless steel surface shall be smooth and free from waves.

Steel plates, except stainless steel, shall conform to the requirements of ASTM Designation: A 709/A 709, Grade 36 [250], 50 [345], or 50W [345W].

Bearing anchors shall conform to the requirements in Section 75, "Miscellaneous Metal," of the Standard Specifications.

Welding of structural steel shall conform to the requirements of AWS D1.1. Welding of structural steel to stainless steel shall conform to the requirements of AWS D1.6.

Convex plate radius dimension tolerances shall be 0.000 to -250 µm. Concave plate radius dimensions shall be +250 to 0.000 µm.

The bearing manufacturer shall have full size convex and concave metal templates for the 2 spherical surfaces of each bearing radius. The templates shall be available to the inspector during all bearing inspections.

The PTFE fabric on spherical or sliding bearing surfaces shall be epoxy bonded and mechanically interlocked to the steel substrate. All bonding shall be done under controlled factory conditions. The mechanical interlock on the spherical concave surface must be integrally machined into the steel substrate. Welded retention grids will not be allowed on the concave surface. Any edges, other than the selvage shall be oversown or recessed so that no cut fabric edges are exposed.

After completion of the bonding operation the PTFE surface shall be smooth and free from bubbles.

The surface of the bearing elements shall be controlled such that upon completion of the bearing assembly the PTFE to stainless steel interface shall be in full bearing.

The mating surface of the flat stainless steel with the PTFE surfacing shall have a minimum #8 mirror finish as determined in conformance with the requirements in ANSI Standard B46.1. The mating surface of the curved stainless steel with the PTFE surfacing shall have a finish of less than 0.4 µm root-mean-square (rms), as determined in conformance with the requirements in ANSI Standard B46.1.

Metal surfaces of bearings exposed to the atmosphere and in contact with the structure of the completed work, except stainless steel surfaces, shall be cleaned and painted in conformance with the provisions in Sections 59-2, "Painting Structural Steel," and 91, "Paint" of the Standard Specifications, and "PTFE Bearing" of these special provisions.

Certification in conformance with the requirements in SSPC-QP 1, SSPC-QP 2, and SSPC-QP 3 of the "SSPC: The Society for Protective Coatings" will not be required for PTFE spherical bearings.

Finish coats will not be required on the bearings.

PTFE spherical bearing assemblies shall be assembled at the factory. Each assembly shall have a minimum of 4 temporary steel straps which are bolted to threaded holes in the masonry and sole plates so that the entire assembly is shipped as a unit and remains intact when uncrated and installed. Welding of the steel straps will not be allowed. Straps must be adequate for vertical lifting purposes. Bearing dismantling will only be allowed under the direction and in the presence of the Engineer.

During fabrication, the maximum temperature of bonded PTFE surfaces shall be 150°C.

Damaged bearings and bearings with scratched mating surfaces shall be returned to the factory for replacement or resurfacing.

PTFE spherical bearing sole plates shall be temporarily supported during concrete placement. Temporary supports shall prevent the rotation or displacement of the bearing during concrete placing operations. Temporary supports shall not inhibit the functioning of the PTFE spherical bearing after concrete is placed. Temporary supports shall not restrict the movement at bridge joints due to temperature changes and shortening from prestress forces. Materials for temporary supports within the limits for placing concrete shall conform to the requirements for form fasteners.

PTFE spherical bearings shall have a first movement static coefficient of friction not exceeding 0.06.

Prior to proof testing, all bearings shall be permanently die-stamped on 2 of 4 sides with markings consisting of bearing number and contract number. Each bearing shall have a unique bearing number and match marks on plate edges to insure correct assembly at the job site.

Full sized PTFE spherical bearings shall be proof tested and evaluated for compression and coefficient of friction in the presence of the Engineer. The proof tests shall be performed on samples randomly selected by the Engineer from the production bearings to be used in the work. Proof testing shall be performed by the Contractor at the manufacturer's plant or at an approved laboratory. If proof tests can not performed at the specified load, the Contractor shall submit to the Engineer for review and approval a testing plan listing additional physical tests. These tests shall be performed in the presence of the Engineer and shall demonstrate that the requirements for proof testing at the specified load are satisfied. The Contractor shall give the Engineer at least 7 days notice before beginning proof testing. Proof testing of PTFE spherical bearings shall conform to the following requirements:

A. One bearing per lot of production bearings shall be proof tested. A lot is defined as 25 bearings or fraction thereof of the same type, within a load category. Bearings in two load categories with vertical load capacities within 800 kN of each other will be considered in one load category for testing.
B. The bearing types and proof tests required for each type shall be as follows:

    1. Expansion type bearings shall be proof tested for compression and coefficient of friction.

C. A load category shall consist of bearings of differing vertical load capacity within a range defined as follows:

    1. Bearings with less than or equal to 2225 kN maximum vertical load capacity.
    2. Bearings with greater than 2225 kN but less than or equal to 8900 kN maximum vertical load capacity.
    3. Bearings with more than 8900 kN maximum vertical load capacity.

D. Proof tests for compression: The bearing shall be held at the design rotation or 0.02 radians whichever is greater for one hour at 1.5 times the maximum vertical load shown on the plans for the bearing. The device shall be in a rotated position during the test. The rotation may be imposed on the bearing by inserting a beveled plate between the bearing and the restraining surface prior to loading.
E. Proof tests for coefficient of friction: The tests shall be performed at the minimum vertical load shown on the plans for the bearing with the test load applied for 12 hours prior to friction measurement and the following:

    1. The tests shall be arranged to allow measurement of the static coefficient of friction on the first movement of the bearing.
    2. The first movement static and dynamic coefficients of friction shall be measured at a sliding speed not exceeding 25 millimeters per minute and shall not exceed the specified coefficient of initial static friction.
    3. The test bearings shall be subjected to a minimum of 100 movements of at least 25 mm of relative movement at a sliding speed not exceeding 300 millimeters per minute. After cycling, the first movement static and dynamic coefficients of friction shall be measured again at a sliding speed not exceeding 25 millimeters per minute and shall not exceed the specified coefficient of initial static friction.

F. The bearing surfaces shall be cleaned prior to proof testing.
G. Proof testing of bearings shall be done after conditioning specimens for 12 hours at 21°±8°C.
H. The proof tested bearings shall show no visible sign of: (1) bond failure of bearing surfaces, (2) separation or lift-off of plates from each other or from PTFE surfaces, or (3) other defects. When a proof tested bearing fails to comply with these specifications, all bearings in that lot shall be individually tested for acceptance.
I. Proof test results shall be certified correct and signed by the testing laboratory personnel who conducted the test and interpreted the test results. Proof test results shall include the bearing numbers of the bearings tested.

Quantities of PTFE spherical bearings will be determined as units from actual count in the completed work. A PTFE spherical bearing with more than one PTFE surface shall be considered a single PTFE spherical bearing.

The contract unit price paid for PTFE spherical bearing shall include full compensation for furnishing all labor, materials, tools, equipment, and incidentals, and for doing all the work involved in constructing the bearing, complete in place, including masonry and sole plates, anchor bolts and sleeves, mortaring of bolts, temporary supports, proof testing, and cleaning and painting of PTFE spherical bearings, as shown on the plans, as specified in the Standard Specifications and these special provisions, and as directed by the Engineer.

If a portion or all of PTFE spherical bearings are either fabricated or tested at a site more than 480 air line kilometers from both Sacramento and Los Angeles, additional shop inspection expenses will be sustained by the State. Whereas it is and will be impractical and extremely difficult to ascertain and determine the actual increase in such expenses, it is agreed that payment to the Contractor for PTFE spherical bearings will be reduced $5,000 for each fabrication or testing site located more than 480 air line kilometers from both Sacramento and Los Angeles and an additional $10,000 ($15,000 total) for each fabrication or testing site located more than 4800 air line kilometers from both Sacramento and Los Angeles.

10-1.54 STRUCTURE APPROACH SLABS (Type N)

This work shall consist of constructing reinforced concrete approach slabs, structure approach drainage system, and treated permeable base at structure approaches in conformance with the details shown on the plans, the provisions in Section 51, "Concrete Structures," of the Standard Specifications, and these special provisions.

GENERAL

Attention is directed to "Engineering Fabrics" of these special provisions.

STRUCTURE APPROACH DRAINAGE SYSTEM

Geocomposite Drain

Geocomposite drain shall consist of a manufactured core not less than 6.35 mm thick nor more than 50 mm thick with one or both sides covered with a layer of filter fabric that will provide a drainage void. The drain shall produce a flow rate, through the drainage void, of at least 25 liters per minute per meter of width at a hydraulic gradient of 1.0 and a minimum externally applied pressure of 168 kPa.

A Certificate of Compliance conforming to the provisions in Section 6-1.07, "Certificates of Compliance," of the Standard Specifications shall be furnished for the geocomposite drain certifying that the drain produces the required flow rate and complies with these special provisions. The Certificate of Compliance shall be accompanied by a flow capability graph for the geocomposite drain showing flow rates and the externally applied pressures and hydraulic gradients. The flow capability graph shall be stamped with the verification of an independent testing laboratory.

Filter fabric for the geocomposite drain shall conform to the provisions for fabric for underdrains in Section 88, "Engineering Fabrics," of the Standard Specifications.

The manufactured core shall be either a preformed grid of embossed plastic, a mat of random shapes of plastic fibers, a drainage net consisting of a uniform pattern of polymeric strands forming 2 sets of continuous flow channels, or a system of plastic pillars and interconnections forming a semirigid mat.

The core material and filter fabric shall be capable of maintaining the drainage void for the entire height of geocomposite drain. Filter fabric shall be integrally bonded to the side of the core material with the drainage void. Core material manufactured from impermeable plastic sheeting having nonconnecting corrugations shall be placed with the corrugations approximately perpendicular to the drainage collection system.

The geocomposite drain shall be installed with the drainage void and the filter fabric facing the embankment. The fabric facing the embankment side shall overlap a minimum of 75 mm at all joints and wrap around the exterior edges a minimum of 75 mm beyond the exterior edge. If additional fabric is needed to provide overlap at joints and wrap-around at edges, the added fabric shall overlap the fabric on the geocomposite drain at least 150 mm and be attached thereto.

Should the fabric on the geocomposite drain be torn or punctured, the damaged section shall be replaced completely or repaired by placing a piece of fabric that is large enough to cover the damaged area and provide a 150-mm overlap.

Plastic Pipe

Plastic pipe shall conform to the provisions for pipe for edge drains and edge drain outlets in Section 68-3, "Edge Drains," of the Standard Specifications.

Treated Permeable Base At Bottom Of Geocomposite Drains

Treated permeable base to be placed around the slotted plastic pipe at the bottom of geocomposite drains shall conform to the provisions in "Treated Permeable Base Under Approach Slabs." If asphalt treated permeable base is used, it shall be placed at a temperature of not less than 82°C nor more than 110°C.

The filter fabric to be placed over the treated permeable base at the bottom of geocomposite drains shall conform to the provisions for filter fabric for edge drains in Section 88, "Engineering Fabrics," of the Standard Specifications.

ENGINEERING FABRICS

Filter fabric to be placed between the structure approach embankment material and the treated permeable base shall conform to the provisions for filter fabric for edge drains in Section 88, "Engineering Fabrics," of the Standard Specifications and these special provisions.

The subgrade to receive the filter fabric, immediately prior to placing, shall conform to the compaction and elevation tolerance specified for the material involved.

Filter fabric shall be aligned, handled, and placed in a wrinkle-free manner in conformance with the manufacturer's recommendations.

Adjacent borders of the filter fabric shall be overlapped from 300 to 450 mm or stitched. The preceding roll shall overlap the following roll in the direction the material is being spread or shall be stitched. When the fabric is joined by stitching, it shall be stitched with yarn of a contrasting color. The size and composition of the yarn shall be as recommended by the fabric manufacturer. The number of stitches per 25 mm of seam shall be 5 to 7.

Equipment or vehicles shall not be operated or driven directly on the filter fabric.

TREATED PERMEABLE BASE UNDER APPROACH SLAB

Treated permeable base under structure approach slabs shall consist of constructing either an asphalt treated permeable base or a cement treated permeable base in accordance with Section 29, "Treated Permeable Bases," of the Standard Specifications and these special provisions.

The type of treatment, asphalt or cement, to be used shall be at the option of the Contractor.

The Contractor shall notify the Engineer in writing, not less than 30 days prior to the start of placing the treated permeable base, which type of treated permeable base will be furnished. Once the Contractor has notified the Engineer of the selection, the type to be furnished shall not be changed without a prior written request to do so and approval thereof in writing by the Engineer.

Asphalt treated permeable base shall be placed at a temperature of not less than 93°C nor more than 121°C. Material stored in excess of 2 hours shall not be used in the work.

Asphalt treated permeable base material may be spread in one layer. The base material shall be compacted with a vibrating shoe type compactor or rolled with a roller weighing at least 1.3 tonnes but no more than 4.5 tonnes. Rolling shall begin as soon as the mixture has cooled sufficiently to support the weight of the rolling equipment without undue displacement.

Cement treated permeable base material may be spread in one layer. The base material shall be compacted with either a vibrating shoe type compactor or with a steel-drum roller weighing at least 1.3 tonnes but no more than 4.5 tonnes. Compaction shall follow within one-half hour after the spreading operation and shall consist of 2 complete coverages of the treated material.

APPROACH SLABS

Concrete for use in approach slabs shall contain not less than 400 kilograms of cementitious material per cubic meter.

The steel angle at the concrete barrier joint shall conform to the provision in Section 75-1.03, "Miscellaneous Metal," of the Standard Specifications.

Structure approach slabs shall be cured for not less than 5 days prior to opening to public traffic, unless, at the option of the Contractor, the structure approach slabs are constructed using concrete with a non-chloride Type C chemical admixture conforming to these special provisions.

Portland cement for use in concrete using a non-chloride Type C chemical admixture shall be Type II Modified, Type II Prestress, or Type III. Type II Modified and Type III cement shall conform to the provisions in Section 90-2.01, "Cement," of the Standard Specifications. Type II Prestress cement shall conform to the requirements of Type II Modified cement, except the mortar containing the portland cement to be used and Ottawa sand, when tested in conformance with California Test 527, shall not contract in air more than 0.053-percent.

The non-chloride Type C chemical admixture, approved by the Engineer, shall conform to the requirements in ASTM Designation: C 494 and Section 90-4, "Admixtures," of the Standard Specifications.

The concrete with non-chloride Type C chemical admixture shall be prequalified prior to placement in conformance with the provisions for prequalification of concrete specified by compressive strength in Section 90-9.01, "General," of the Standard Specifications and the following:

A. Immediately after fabrication of the 5 test cylinders, the cylinders shall be stored in a temperature medium of 21 ± 1.5°C until the cylinders are tested.
B. The 6-hour average strength of the 5 test cylinders shall not be less than 5.85 MPa. No more than 2 test cylinders shall have a strength of less than 5.5 MPa.

The top surface of approach slabs shall be finished in conformance with the provisions in Section 51-1.17, "Finishing Bridge Decks," of the Standard Specifications. Edges of slabs shall be edger finished.

Approach slabs shall be cured with pigmented curing compound (1) in conformance with the provisions for curing structures in Section 90-7.01B, "Curing Compound Method," of the Standard Specifications.

Structure approach slabs constructed using concrete with a non-chloride Type C chemical admixture shall be cured for not less than 6 hours prior to opening to public traffic. The curing period shall be considered to begin at the start of discharge of the last truck load of concrete to be used in the slab.

If the ambient temperature is below 18°C during the curing period for approach slabs using concrete with a non-chloride Type C chemical admixture, an insulating layer or blanket shall be used to cover the surface. The insulating layer or blanket shall have an R-value rating given in the table below. At the Contractor's option, a heating tent may be used in lieu of or in combination with the insulating layer or blanket.

Temperature range during curing period	R-value, minimum
13°C to 18°C	1
7°C to 13°C	2
4°C to 7°C	3

JOINTS

Hardboard and expanded polystyrene shall conform to the provisions in Section 51-1.12D, "Sheet Packing, Preformed Pads and Board Fillers," of the Standard Specifications.

Type AL joint seals shall conform to the provisions in Section 51-1.12F, "Sealed Joints" of the Standard Specifications. The sealant may be mixed by hand-held power-driven agitators and placed by hand methods.

The pourable seal between the steel angle and concrete barrier shall conform to the requirements for Type A and AL seals in Section 51-1.12F(3), "Materials and Installation," of the Standard Specifications. The sealant may be mixed by hand-held power-driven agitators and placed by hand methods. Immediately prior to placing the seal, the joint shall be thoroughly cleaned, including abrasive blast cleaning of the concrete surfaces, so that all foreign material and concrete spillage are removed from all joint surfaces. Joint surfaces shall be dry at the time the seal is placed.

MEASUREMENT AND PAYMENT

Structural concrete, approach slab (Type N)will be measured and paid for in conformance with the provisions in Section 51-1.22, "Measurement," and Section 51-1.23, "Payment," of the Standard Specifications and these special provisions.

Full compensation for the structure approach drainage system including geocomposite drain, plastic pipe, treated permeable base, filter fabric, miscellaneous metal, pourable seals, shall be considered as included in the contract price paid per cubic meter for structural concrete, approach slab of the type shown in the Engineer's Estimate, and no additional compensation will be allowed therefor.

10-1.55 SEALING JOINTS

Joints in concrete bridge decks and joints between concrete structures and concrete approach slabs shall be sealed in conformance with the details shown on the plans, the provisions in Section 51, "Concrete Structures," of the Standard Specifications, and these special provisions.

Where polyurethane seals are shown on the plans, a silicone sealant conforming to the provisions in Section 51–1.12F, "Sealed Joints," of the Standard Specifications may be used.

When ordered by the Engineer, a joint seal larger than called for by the Movement Rating shown on the plans shall be furnished and installed. Payment to the Contractor for furnishing the larger seal and for saw cutting the increment of additional depth of groove required will be determined as provided in Section 4-1.03, "Changes," of the Standard Specifications.

10-1.56 JOINT SEAL ASSEMBLIES (MAXIMUM MOVEMENT RATING, 100 mm)

Joint seal assemblies shall conform to the details shown on the plans, the provisions in Section 51, "Concrete Structures," of the Standard Specifications, and these special provisions.

All metal parts of the joint seal assembly shall conform to the provisions in Section 75-1.03, "Miscellaneous Bridge Metal," of the Standard Specifications. Bolts, nuts, and washers shall conform to the requirements in ASTM Designation: A 325 or A 325M.

At the Contractor's option, cleaning and painting of all new metal surfaces of the joint seal assembly, except stainless steel and anchorages embedded in concrete, may be substituted for galvanizing. Cleaning and painting shall be in conformance with these special provisions.

Certification in conformance with the requirements in SSPC-QP 1, SSPC-QP 2, and SSPC-QP 3 of the "SSPC: The Society for Protective Coatings" will not be required for cleaning and painting joint seal assemblies.

Prior to performing any painting or paint removal, the Contractor shall submit to the Engineer, in conformance with the provisions in Section 5-1.02, "Plans and Working Drawings," of the Standard Specifications, 3 copies of a separate Painting Quality Work Plan (PQWP) for each item of work for which painting or paint removal is to be performed. As a minimum, each PQWP shall include the following:

A. The name of each Contractor or subcontractor to be used.
B. One copy each of all current "SSPC: The Society for Protective Coatings" specifications or qualification procedures which are applicable to the painting or paint removal to be performed. These documents shall become the permanent property of the Department.
C. Proposed methods and equipment to be used for any paint application.

The Engineer shall have 2 weeks to review the PQWP submittal after a complete plan has been received. No painting or paint removal shall be performed until the PQWP for that work is reviewed by the Engineer. Should the Engineer fail to complete the review within this time allowance and if, in the opinion of the Engineer, the Contractor's controlling operation is delayed or interfered with by reason of the delay in reviewing the PQWP, the delay will be considered a right of way delay in conformance with the provisions in Section 8-1.09, "Right of Way Delays," of the Standard Specifications.

CLEANING

Exposed new metal surfaces shall be dry blast cleaned in conformance with the requirements in Surface Preparation Specification No. 10, "Near White Blast Cleaning," of the "SSPC: The Society for Protective Coatings." Blast cleaning shall leave surfaces with a dense, uniform, angular anchor pattern of not less than 40 µm nor more than 86 µm as measured in conformance with the requirements in ASTM Designation: D 4417.

Mineral and slag abrasives used for blast cleaning steel shall conform to the requirements in Abrasive Specification No. 1, "Mineral and Slag Abrasives," of the "SSPC: The Society for Protective Coatings" and shall not contain hazardous material. Mineral and slag abrasives shall comply with the requirements for Class A, Grade 2 to 3 as defined therein.

A Certificate of Compliance conforming to the provisions in Section 6-1.07, "Certificates of Compliance," of the Standard Specifications and a Material Safety Data Sheet shall be furnished prior to use for each shipment of blast cleaning material for steel.

PAINTING

Blast cleaned surfaces shall receive a single undercoat, and a final coat where specified, consisting of a waterborne inorganic zinc coating conforming to the requirements in AASHTO Designation M 300, Type II, except that: 1) the first 3 sentences of Section 4.7, "Primer Field Performance Requirements," and the entire Section 4.7.1 shall not apply, and 2) zinc dust shall be Type II in conformance with the requirements in ASTM Designation: D 520. The inorganic zinc coating shall be listed on the qualified products list which may be obtained from the Transportation Laboratory.

The color of the final application of inorganic zinc coating shall match Federal Standard 595B No. 36373.

Inorganic zinc coating shall be used within 12 hours of initial mixing.

Application of inorganic zinc coating shall conform to the provisions for applying zinc-rich coating in Section 59-2.13, "Application of Zinc-Rich Primer," of the Standard Specifications.

Inorganic zinc coating shall not be applied when the atmospheric or surface temperature is less than 7°C or more than 29°C, nor when the relative humidity exceeds 85 percent.

The single undercoat of inorganic zinc coating shall be applied to the required dry film thickness in 2 or more applications within 4 hours after blast cleaning.

The total dry film thickness of all applications of the inorganic zinc undercoat shall be not less than 100 µm nor more than 200 µm.

Areas where mudcracking occurs in the inorganic zinc coating shall be blast cleaned and repainted with inorganic zinc coating to the specified thickness.

Dry spray, or overspray, as defined in the Steel Structures Painting Manual, Volume 1, "Good Painting Practice," of the "SSPC: The Society for Protective Coatings," shall be removed prior to application of subsequent coats or final acceptance. Removal of dry spray shall be by screening or other methods that minimize polishing of the inorganic zinc surface. The dry film thickness of the coating after removal of dry spray shall be in conformance with the provisions for applying the single undercoat, as specified herein.

The inorganic zinc coating shall be tested for adhesion and cure. The locations of the tests will be determined by the Engineer. The sequence of the testing operations shall be determined by the Contractor. The testing for adhesion and cure will be performed no sooner than 72 hours after application of the single undercoat of inorganic zinc coating. At the Contractor's expense, satisfactory access shall be provided to allow the Engineer to determine the location of the tests and to test the inorganic zinc coating cure. The inorganic zinc coating shall pass the following tests:

Adhesion

The inorganic zinc coating shall have a minimum adhesion to steel of 4 MPa when measured at no more than 6 locations per assembly using a self-aligning adhesion tester in conformance with the requirements in ASTM Designation: D 4541. The Contractor, at the Contractor's expense, shall: (1) verify compliance with the adhesion requirements, (2) furnish test results to the Engineer, and (3) repair the coating after testing.

Cure

The inorganic zinc coating, when properly cured, shall exhibit a solid, hard, and polished metal surface when firmly scraped with the knurled edge of a quarter. Inorganic zinc coating that is powdery, soft, or does not exhibit a polished metal surface, as determined by the Engineer, shall be repaired by the Contractor, at the Contractor's expense, by blast cleaning and repainting with inorganic zinc coating to the specified thickness.

Finish coats will not be required on joint seal assemblies.

Sheet neoprene shall conform to the provisions for neoprene in Section 51-1.14, "Waterstops," of the Standard Specifications. The sheet neoprene shall be fabricated to fit the joint seal assembly accurately.

Metal parts of the joint seal assembly shall be pre-assembled before installation to verify the geometry of the completed seal.

The bridge deck surface shall conform to the provisions in Section 51-1.17, "Finishing Bridge Decks," of the Standard Specifications prior to placing and anchoring the joint seal assembly.

The assembly shall be placed in a blocked out recess in the concrete deck surface. The depth and width of the recess shall permit the installation of the assembly anchorage components or anchorage bearing surface to the lines and grades shown on the plans.

Sheet neoprene shall be installed at such time and in such manner that the sheet neoprene will not be damaged by construction operations. The joint shall be cleaned of all dirt, debris and other foreign material immediately prior to installation of the sheet neoprene.

ALTERNATIVE JOINT SEAL ASSEMBLY

At the Contractor's option, an alternative joint seal assembly may be furnished and installed provided: (1) that the quality of the alternative and its suitability for the intended application are at least equal to that of the joint seal assembly shown on the plans, (2) that acceptable working drawings and a Certificate of Compliance are furnished as specified herein and (3) that the alternative conforms to the following requirements:

A. The determination as to the quality and suitability of a joint seal assembly will be made in the same manner as provided in Section 6-1.05, "Trade Names and Alternatives," of the Standard Specifications. The factors to be considered will include: the ability of the assembly to resist the intrusion of foreign material and water throughout the full range of movement for the application, and the ability to function without distress to any component.
B. Joint seal assemblies will not be considered for approval unless it can be proven that the assembly has had at least one year of satisfactory service under conditions similar to this application.
C. The Contractor shall submit complete working drawings for each joint seal assembly to the Division of Structure Design (DSD) in conformance with the provisions in Section 5-1.02, "Plans and Working Drawings," of the Standard Specifications. The working drawings shall show complete details of the joint seal assembly and anchorage components and the method of installation to be followed, including concrete blockout details and additions or rearrangements of the reinforcing steel from that shown on the plans. For initial review, 5 sets of

working drawings shall be submitted. After review, between 6 and 12 sets of working drawings, as requested by the Engineer, shall be submitted to DSD for final approval and use during construction.

D. The working drawings shall be supplemented with calculations for each proposed joint seal assembly, as requested by the Engineer. Working drawings shall be either 279 mm x 432 mm or 559 mm x 864 mm in size. Each drawing and calculation sheet shall include the State assigned designations for the contract number, bridge number, full name of the structure as shown on the contract plans, and District-County-Route-Kilometer Post. The design firm's name, address, and telephone number shall be shown on the working drawings. Each sheet shall be numbered in the lower right hand corner and shall contain a blank space in the upper right hand corner for future contract sheet numbers.

E. Calculations, when requested, and working drawings, shall be stamped and signed by an engineer who is registered as a Civil Engineer. The Contractor shall allow the Engineer 4 weeks to review the drawings after a complete set has been received.

F. Within 3 weeks after final working drawing approval, one set of the corrected good quality prints on 75 g/m^2 (minimum) bond paper (559 mm x 864 mm in size) of all working drawings prepared by the Contractor for each joint seal assembly shall be furnished to DSD.

G. Each shipment of joint seal materials shall be accompanied by a Certificate of Compliance in conformance with the provisions in Section 6-1.07, "Certificates of Compliance," of the Standard Specifications. The certificate shall state that the materials and fabrication involved comply in all respects to the specifications and data submitted in obtaining the approval.

H. The elastomer portion of the joint seal assembly shall be neoprene conforming to the requirements in Table 1 of ASTM Designation: D 2628 and the following, except that no recovery tests or compression-deflection tests will be required:

Property	Requirement	ASTM Test Method
Hardness, Type A Durometer, points	55-70	D 2240 (Modified)
Compression set, 70 hours at 100°C, maximum, percent	40	D 395 Method B (Modified)

I. All metal parts of an alternative joint seal assembly shall conform to the requirements above for the joint seal assembly shown on the plans. At the Contractor's option, metal parts may conform to the requirements in ASTM Designation: A 572/A 572M.

J. The assembly and its components shall be designed to support the AASHTO HS20-44 loading with 100 percent impact. The tire contact area used to distribute the tire loads shall be 244 mm, measured normal to the longitudinal axis of the assembly, by 508 mm wide. The assembly shall provide a smooth riding joint without slapping of components or wheel tire rumble.

K. The Movement Rating of the assembly shall be measured normal to the longitudinal axis of the assembly. The dimensions for positioning the assembly within the Movement Rating during installation shall be measured normal to the longitudinal axis, disregarding any skew of the deck expansion joint.

L. The assembly shall have cast-in-place anchorage components forming a mechanical connection between the joint components and the concrete deck.

M. The maximum depth and width of the recess shall be such that the primary reinforcement to provide the necessary strength of the structural members is outside the recess. The maximum depth of the recess at bent 1 shall be 250 mm. The maximum width of the recess on each side of the expansion joint shall be 300 mm.

N. All reinforcement other than the primary reinforcement shall continue through the recess construction joint into the recess and engage the anchorage components of the assembly.

O. Horizontal angle points and vertical corners at curbs in assemblies shall consist of either pre-molded sections or standard sections of the joint seal assembly that have been specially miter cut or bent to fit the structure.

P. The elastomer portion of the assembly shall be installed in conformance with the manufacturer's recommendations at such time and in such a manner that the elastomer portion will not be damaged by construction operations. The joint and blockout shall be cleaned of all dirt, debris, and other foreign material immediately prior to the installation of the elastomer.

Full compensation for additional materials or work required because of the application of the optional cleaning and painting or the use of an alternative type joint seal assembly, shall be considered as included in the contract price paid per meter for the joint seal assembly involved and no additional compensation will be allowed therefor.

10-1.57 SEISMIC JOINT ASSEMBLY (MOVEMENT RATING EXCEEDING 100 mm)

Seismic joint assemblies with movement rating greater than 100 mm shall consist of steel deck plate, steel slide plate, steel channel and anchorage assemblies and shall conform to the details shown on the plans, the provisions in Section 51, "Concrete Structures," and Section 55, "Steel Structures," of the Standard Specifications and to these special provisions.

A qualified representative of the manufacturer shall be present during installation of the seismic joint assembly and shall be available for advice during any remaining installations.

The Contractor shall submit complete working drawings for each seismic joint assembly to the Division of Structure Design (DSD) in conformance with the provisions in Section 5-1.02, "Plans and Working Drawings," of the Standard Specifications. The working drawings shall show complete details of the seismic joint assembly and anchorage components, the method of installation to be followed, including concrete blockout details and any additions or rearrangements of the reinforcing steel from that shown on the plans, and equipment to be used during installation. For initial review, 5 sets of drawings shall be submitted. After review, between 6 and 12 sets, as requested by the Engineer, shall be submitted to DSD for final approval and use during construction.

The working drawings shall be supplemented with complete calculations for the particular seismic joint assembly, when requested by the Engineer. Working drawings shall be either 279 mm x 432 mm or 559 mm x 864 mm in size and each drawing and calculation sheet shall include the State assigned designations for the contract number, bridge number, full name of the structure as shown on the contract plans, and District-County-Route-Kilometer Post. The design firm's name, address, and phone number shall be shown on the working drawings. Each sheet shall be numbered in the lower right hand corner and shall contain a blank space in the upper right hand corner for future contract sheet numbers.

Calculations, when requested, and working drawings shall be stamped and signed by an engineer who is registered as a Civil Engineer. The Contractor shall allow the Engineer 4 weeks to review the drawings after a complete set has been received.

Within 3 weeks after final working drawing approval, one set of the corrected good quality prints on 75-g/m^2 (minimum) bond paper (559 mm x 864 mm in size) of all working drawings prepared by the Contractor for each joint seal assembly shall be furnished to OSD.

Each shipment of seismic joint assembly materials shall be accompanied by a Certificate of Compliance in conformance with the provisions in Section 6-l.07, "Certificates of Compliance," of the Standard Specifications. The certificate shall state that the materials and fabrication involved comply in all respects to the specifications and data submitted in obtaining approval.

Attention is directed to "Welding Quality Control" of these special provisions.

Sheet neoprene shall conform to the provisions for neoprene in Section 51-1.14, "Waterstops," of the Standard Specifications. The sheet neoprene shall be fabricated to fit the joint seal assembly accurately.

Metal plates and built-up channels shall conform to the requirements of ASTM Designation: A 709 or A 709M Grade 50. Bolts, nuts and washers shall conform to the requirements of ASTM Designation: A 325 or A 325M. Anchor studs shall conform to the requirements of ASTM Designation: A 307 or A 307M. Drain pipes shall conform to the provisions in Section 75-1.03, "Miscellaneous Bridge Metal," of the Standard Specifications.

Spring rubber tubes shall conform to the provisions of elastomer in Section 51-1.12H(1), "Plain and Fabric Reinforced Elastomeric Bearing Pads" of the Standard Specifications.

Welding shall conform to the requirements in AWS D1.5.

Metal surfaces of seismic joints exposed to the atmosphere and in contact with the structure in the completed work shall be clean and pained in conformance with the provisions in Sections 59-2, "Painting Structural Steel," and 91, "Paint," of the Standard Specifications, and these special provisions.

Certification in conformance with the requirements in SSPC-QP 1, SSPC-QP 2, and SSPC-QP 3 of the "SSPC: The Society for Protective Coatings" will not be required for cleaning and painting seismic joint assemblies.

Prior to performing any painting, the Contractor shall submit to the Engineer, in conformance with the provisions in Section 5-1.02, "Plans and Working Drawings," of the Standard Specifications, 3 copies of a separate Painting Quality Work Plan (PQWP) for each item of work for which painting or paint removal is to be performed. As a minimum, each PQWP shall include the following:

A. The name of each Contractor or subcontractor to be used.
B. One copy each of all current "SSPC: The Society for Protective Coatings" specifications or qualification procedures which are applicable to the painting or paint removal to be performed. These documents shall become the permanent property of the Department.
C. Proposed methods and equipment to be used for any paint application.

The Engineer shall have 2 weeks to review the PQWP submittal after a complete plan has been received. No painting or paint removal shall be performed until the PQWP for that work is reviewed by the Engineer. Should the Engineer fail to

complete the review within this time allowance and if, in the opinion of the Engineer, the Contractor's controlling operation is delayed or interfered with by reason of the delay in reviewing the PQWP, the delay will be considered a right of way delay in conformance with the provisions in Section 8-1.09, "Right of Way Delays," of the Standard Specifications.

CLEANING

Metal surfaces of seismic joints exposed to the atmosphere and in contact with the structure in the completed work shall be dry blast cleaned in conformance with the requirements in Surface Preparation Specification No. 10, "Near White Blast Cleaning," of the "SSPC: The Society for Protective Coatings." Blast cleaning shall leave surfaces with a dense, uniform, angular anchor pattern of not less than 40 µm nor more than 86 µm as measured in conformance with the requirements in ASTM Designation: D 4417.

Mineral and slag abrasives used for blast cleaning steel shall conform to the requirements in Abrasive Specification No. 1, "Mineral and Slag Abrasives," of the "SSPC: The Society for Protective Coatings" and shall not contain hazardous material. Mineral and slag abrasives shall comply with the requirements for Class A, Grade 2 to 3 as defined therein.

A Certificate of Compliance conforming to the provisions in Section 6-1.07, "Certificates of Compliance," of the Standard Specifications and a Material Safety Data Sheet shall be furnished prior to use for each shipment of blast cleaning material for steel.

PAINTING

Blast cleaned surfaces shall receive a single undercoat, and a final coat where specified, consisting of a waterborne inorganic zinc coating conforming to the requirements in AASHTO Designation M 300, Type II, except that: 1) the first 3 sentences of Section 4.7, "Primer Field Performance Requirements," and the entire Section 4.7.1 shall not apply, and 2) zinc dust shall be Type II in conformance with the requirements in ASTM Designation: D 520. The inorganic zinc coating shall be listed on the qualified products list which may be obtained from the Transportation Laboratory.

The color of the final application of inorganic zinc coating shall match Federal Standard 595B No. 36373.

Inorganic zinc coating shall be used within 12 hours of initial mixing.

Application of inorganic zinc coating shall conform to the provisions for applying zinc-rich coating in Section 59-2.13, "Application of Zinc-Rich Primer," of the Standard Specifications.

Inorganic zinc coating shall not be applied when the atmospheric or surface temperature is less than 7°C or more than 29°C, nor when the relative humidity exceeds 85 percent.

The single undercoat of inorganic zinc coating shall be applied to the required dry film thickness in 2 or more applications within 4 hours after blast cleaning.

The total dry film thickness of all applications of the inorganic zinc undercoat shall be not less than 100 µm nor more than 200 µm.

Areas where mudcracking occurs in the inorganic zinc coating shall be blast cleaned and repainted with inorganic zinc coating to the specified thickness.

Dry spray, or overspray, as defined in the Steel Structures Painting Manual, Volume 1, "Good Painting Practice," of the "SSPC: The Society for Protective Coatings," shall be removed prior to application of subsequent coats or final acceptance. Removal of dry spray shall be by screening or other methods that minimize polishing of the inorganic zinc surface. The dry film thickness of the coating after removal of dry spray shall be in conformance with the provisions for applying the single undercoat, as specified herein.

The inorganic zinc coating shall be tested for adhesion and cure. The locations of the tests will be determined by the Engineer. The sequence of the testing operations shall be determined by the Contractor. The testing for adhesion and cure will be performed no sooner than 72 hours after application of the single undercoat of inorganic zinc coating. At the Contractor's expense, satisfactory access shall be provided to allow the Engineer to determine the location of the tests and to test the inorganic zinc coating cure. The inorganic zinc coating shall pass the following tests:

Adhesion

The inorganic zinc coating shall have a minimum adhesion to steel of 4 MPa when measured at no more than 6 locations per assembly using a self-aligning adhesion tester in conformance with the requirements in ASTM Designation: D 4541. The Contractor, at the Contractor's expense, shall: (1) verify compliance with the adhesion requirements, (2) furnish test results to the Engineer, and (3) repair the coating after testing.

Cure

The inorganic zinc coating, when properly cured, shall exhibit a solid, hard, and polished metal surface when firmly scraped with the knurled edge of a quarter. Inorganic zinc coating that is powdery, soft, or does not exhibit a

polished metal surface, as determined by the Engineer, shall be repaired by the Contractor, at the Contractor's expense, by blast cleaning and repainting with inorganic zinc coating to the specified thickness.

Finish coats will not be required on seismic joint assemblies.

The bridge deck surface shall conform to the provisions in Section 51-1.17 "Finishing Bridge Deck," of the Standard Specifications prior to placing seismic joint assemblies and anchorage.

The assembly shall be completely shop-assembled and placed in a blocked out recess in the concrete deck surface. The depth and width of the recess shall permit the installation of the assembly anchorage components or anchorage bearing surface to the planned line and grade.

The maximum depth of the recess at abutment 11 end diaphragm shall be 520 mm and at approach slab shall be 300 mm. The maximum width of recess at abutment 11 end diaphragm shall be 680 mm and at approach slab shall be 1200 mm.

The vertical expansion joint in barrier shall be available for inspection after placement of the recess concrete around the anchorage components of the assembly.

The assembly shall make a watertight, continuous return 150 mm up into the barrier at the low side of the deck joint. Neoprene glands shall be continuous without field splices or joints, including the return up into barrier.

Seismic Joint assemblies will be measured by the meter from end to end along the centerline of the completed joint as shown on the plans.

The contract price paid per meter for seismic joint assembly shall include full compensation for furnishing all labor, materials, tools, equipment, and incidentals, and for doing all the work involved in constructing the seismic joint assemblies, complete in place, including protecting, repairing, cleaning, and painting, as shown on the plans, as specified in the Standard Specifications and these special provisions, and as directed by the Engineer.

10-1.58 REFINISHING BRIDGE DECKS

Surfaces of bridge decks that are exposed when existing railings, curbs, or sidewalks are removed shall be prepared and refinished flush with the adjoining deck surface with portland cement concrete or rapid setting concrete, at the option of the Contractor, in conformance with these special provisions.

The exact area to be refinished will be designated by the Engineer.

Attention is directed to "Public Safety" of these special provisions.

When work is being performed within 3 m of a traffic lane or performed over traffic, dust and residue from deck preparation and cleaning shall be removed or controlled by vacuum, water spray, or shield methods approved by the Engineer.

Concrete shall be removed without damage to concrete that is to remain in place. Damage to concrete which is to remain in place shall be repaired to a condition satisfactory to the Engineer.

The concrete in deck areas to be refinished shall be removed to a depth of approximately 20 mm below the adjoining deck surface. A 20 mm deep saw cut shall be made along the perimeter of areas prior to removing the concrete.

Existing areas of the deck more than 20 mm below the adjoining deck surface shall be prepared by removing not less than 6 mm of surface material to expose sound aggregates.

Concrete removal may be done by abrasive blast cutting, abrasive sawing, impact tool cutting, machine rotary abrading, or by other methods, all to be approved by the Engineer. Cut areas shall be cleaned free of dust and all other loose and deleterious materials by brooming, abrasive blast cleaning, and high pressure air jets. Equipment shall be fitted with suitable traps, filters, drip pans or other devices to prevent oil or other deleterious matter from being deposited on the deck.

Existing reinforcement, exposed during the removal of concrete, that is to remain in place shall be protected from damage.

Steel dowels shall be cut off flush with the existing concrete or cut off at the bottom of concrete removal, whichever is lower. Patching around or over dowels in sound concrete will not be required. Existing voids around dowels, where refinishing is not required, shall be chipped back to sound concrete, the dowels removed 25 mm below the finished surface, and the hole filled with rapid setting concrete.

Refinishing isolated high areas in the existing deck may be accomplished by cutting the concrete down to be flush with the plane of the adjoining deck surface by abrasive sawing, grinding, impact tool cutting, or by other methods to be approved by the Engineer. When grinding is performed to bring the deck concrete flush with the adjoining deck surface, the resulting surface shall have a coefficient of friction of not less than 0.35 as determined by California Test 342.

PORTLAND CEMENT CONCRETE

An epoxy adhesive shall be applied to the surfaces to be refinished before placing the portland cement concrete. Immediately prior to applying the adhesive, the area to receive the adhesive shall be cleaned by abrasive blasting and blown clean by compressed air to remove dust and any other loose material. The area to be covered shall be surface dry and the ambient temperature shall be 10°C or above when the adhesive is applied.

The epoxy adhesive shall be furnished and applied in conformance with the provisions in Section 95-1, "General," and Section 95-2.03, "Epoxy Resin Adhesive for Bonding New Concrete to Old Concrete," of the Standard Specifications. Whenever the ambient temperature is below 18°C, Type II epoxy shall be used. The exact rate of applying epoxy adhesive will be as determined by the Engineer. The adhesive shall be worked onto the surface with stiff brushes or equal.

Portland cement concrete used to fill the prepared areas shall conform to the provisions in Section 90, "Portland Cement Concrete," of the Standard Specifications and the following:

A. The concrete shall contain a minimum of 400 kilograms of portland cement per cubic meter.
B. The amount of free water used in concrete shall not exceed 166 kg/m^3.
C. The aggregate shall contain between 50 and 55 percent fine aggregate and the remainder shall be pea gravel. The grading of pea gravel shall be such that 100 percent passes the 12.5 mm screen and not more than 5 percent passes the 1.18 mm sieve, unless a larger size is ordered by the Engineer.
D. Admixtures shall be furnished and used if directed by the Engineer.
E. Immediately after depositing on the newly placed adhesive, the portland cement concrete shall be thoroughly consolidated until all voids are filled and free mortar appears on the surface and then struck off to the required grade.
F. Concrete shall be cured as provided in Section 90-7.03, "Curing Structures," of the Standard Specifications.
G. No loads of any kind shall be applied to the portland cement concrete for at least 7 days after placing, unless otherwise permitted by the Engineer.

RAPID SETTING CONCRETE

The concrete used to fill the prepared areas shall be a high-strength material consisting of either magnesium phosphate concrete, modified high alumina based concrete, or portland cement based concrete. Magnesium phosphate concrete shall conform to the requirements for magnesium phosphate concrete in Section 83-2.02D(1), "General," of the Standard Specifications and these special provisions. Modified high alumina based concrete and portland cement based concrete shall be water activated and shall conform to the requirements for single component (water activated) magnesium phosphate concrete in Section 83-2.02D(1), "General," of the Standard Specifications and the following:

A. A clean uniform rounded aggregate filler may be used to extend the concrete. The moisture content of the aggregate shall not exceed 0.5 percent. Grading of the aggregate shall conform to the following:

Sieve Size	Percentage Passing
12.5 mm	100
1.18 mm	0-5

B. The amount of aggregate filler shall conform to the manufacturer's recommendation, but in no case shall the concrete strengths be less than that specified for magnesium phosphate concrete in Section 83-2.02D(1), "General," of the Standard Specifications.
C. Mixing of components of dual component (with a prepackaged liquid activator) magnesium phosphate shall be by complete units, supplied by the manufacturer. Portions of units shall not be used. Water shall not be added to dual component magnesium phosphate.
D. Immediately prior to applying the rapid setting concrete, the surface shall be dry and blown clean by compressed air to remove accumulated dust and any other loose material. If the surface becomes contaminated at any time prior to placing the concrete, the surface shall be cleaned by abrasive blasting. The surface temperature of the areas to be covered shall be 4°C or above when the concrete is applied. Methods proposed to heat said surfaces are subject to approval by the Engineer. The surface for the magnesium phosphate concrete shall be dry. The surfaces for modified high alumina based concrete or portland cement based concrete may be damp but not saturated.
E. Magnesium phosphate concrete shall not be mixed in containers or worked with tools containing zinc, cadmium, aluminum or copper. Modified high alumina based concrete shall not be mixed in containers or worked with tools containing aluminum.
F. Concrete shall not be retempered. Finishing tools that are cleaned with water shall be thoroughly dried before working the concrete.
G. When placing concrete on slopes exceeding 5 percent, the Engineer may require the Contractor to provide a flow controlled modified material.
H. Modified high alumina based concrete and portland cement based concrete shall be cured in conformance with the provisions in Section 90-7.01B, "Curing Compound Method," of the Standard Specifications. Magnesium phosphate concrete shall not be cured.

I. Unless otherwise permitted in writing by the Engineer, public traffic shall not be permitted on the new concrete until at least 24 hours after final set.

FINISHING REQUIREMENTS

In advance of the curing operations, the surface of the concrete shall be textured by brooming with a stiff bristled broom or by other suitable devices which will result in uniform scoring. Brooming shall be performed transversely. The operation shall be performed at a time and in a manner that to produces a hardened surface having a uniform texture and a coefficient of friction of not less than 0.35 as determined by California Test 342.

Refinished surfaces that are found to have a coefficient of friction less than 0.35 shall be ground or grooved by the Contractor at his expense in conformance with the applicable provisions in Section 42, "Groove and Grind Pavement," of the Standard Specifications.

In the longitudinal direction, refinished surfaces shall not vary more than 6 mm from the lower edge of a 3.6 m straightedge. The refinished surface shall be flush with the existing adjoining surface.

MEASUREMENT AND PAYMENT

No adjustment of compensation will be made for any increase or decrease in the quantity of refinish bridge deck, regardless of the reason for the increase or decrease. The provisions in Section 4-1.03B, "Increased or Decreased Quantities," of the Standard Specifications shall not apply to the contract item of refinish bridge deck.

The quantity in square meters of refinish bridge deck to be paid for will be determined from the lengths and widths of the refinished areas, measured horizontally, plus 0.02-m^2 for patching around each dowel.

The contract price paid per square meter for refinish bridge deck shall include full compensation for furnishing all labor, materials, tools, equipment, and incidentals, and for doing all the work involved in refinishing areas of the existing bridge deck (including cutting steel dowels), complete in place, as shown on the plans, as specified in the Standard Specifications and these special provisions, and as directed by the Engineer.

10-1.59 ARCHITECTURAL FINISH (EXPOSED AGGREGATE)

Exposed aggregate architectural finish on concrete surfaces shall conform to the details shown on the plans and in conformance with the provisions in Section 51, "Concrete Structures," of the Standard Specifications and these special provisions.

Coarse aggregate for exposed aggregate finish for cast-in-place concrete surfaces shall be river gravel, exclusive of crushed gravel and rock, conforming to the provisions in Section 90-2, "Materials," of the Standard Specifications for the 37.5-mm x 19-mm primary aggregate size. The matrix of cement and fine aggregate shall be removed from the surface of the concrete by water jetting, coarse brooming, abrasive blasting, or a combination of these procedures to expose coarse aggregates to a depth of approximately 6 mm to 12 mm from the formed or floated surface. Removal methods shall not dislodge or loosen the coarse aggregate from embedment in the concrete matrix. At the option of the Contractor, a commercial quality, water-resistant set retarder manufactured for the intended use may be used. Exposed aggregate finish shall have cement film, discoloring agents, dirt, dust, grease, loose concrete and other foreign material removed and shall be uniform in appearance.

TEST PANEL

A test panel at least 1.25 m x 1.25 m in size shall be successfully completed at a location approved by the Engineer before beginning work on architectural finishes. The test panel shall be constructed and finished with the materials, tools, equipment and methods to be used in constructing the architectural finish. If ordered by the Engineer, additional test panels shall be constructed and finished until the specified finish, texture and color are obtained, as determined by the Engineer.

The test panel approved by the Engineer shall be used as the standard of comparison in determining acceptability of architectural finish applied to concrete surfaces.

CURING

Cast-in-place concrete surfaces with architectural finish shall be cured by the water method. Seals and curing compounds shall not be used.

MEASUREMENT AND PAYMENT

Exposed aggregate architectural finish will be measured and paid for by the square meter.

The contract price paid per square meter for exposed aggregate finish shall include full compensation for furnishing all labor, materials, tools, equipment, and incidentals and for doing all the work involved in architectural finish, complete in

place, including test panels, as shown on the plans, as specified in the Standard Specifications and these special provisions, and as directed by the Engineer.

10-1.60 ARCHITECTURAL SURFACE (TEXTURED CONCRETE)

Architectural texture for concrete surfaces shall conform to the details shown on the plans and the provisions in Section 51, "Concrete Structures," of the Standard Specifications and these special provisions.

Architectural textures listed below are required at concrete surfaces shown on the plans:

A. Random cut stone texture

TEST PANEL

A test panel at least 1.25 m x 1.25 m in size shall be successfully completed at a location approved by the Engineer before beginning work on architectural textures. The test panel shall be constructed and finished with the materials, tools, equipment and methods to be used in constructing the architectural texture. If ordered by the Engineer, additional test panels shall be constructed and finished until the specified finish, texture and color are obtained, as determined by the Engineer.

The test panel approved by the Engineer shall be used as the standard of comparison in determining acceptability of architectural texture for concrete surfaces.

FORM LINERS

Form liners shall be used for textured concrete surfaces and shall be installed in conformance with the manufacturer's recommendations, unless other methods of forming textured concrete surfaces are approved by the Engineer. Form liners shall be manufactured from an elastomeric material or a semi-elastomeric polyurethane material by a manufacturer of commercially available concrete form liners. No substitution of other types of formliner material will be allowed. Form liners shall leave crisp, sharp definition of the architectural surface. Recurring textural configurations exhibited by repeating, recognizable shadow patterns shall be prevented by proper casting of form liner patterns. Textured concrete surfaces with such recurring textural configurations shall be reworked to remove such patterns as approved by the Engineer or the concrete shall be replaced.

Form liners shall have the following properties:

Description	ASTM Designation:	Range
Elastomeric material		
Shore A hardness	D 2240	20 to 65
Tensile strength (MPa)	D 412	0.9 to 6.2
Semi-elastomeric polyurethane		
Shore D hardness	D 2240	55 to 65
Tensile strength (MPa)	D 2370	18 minimum

Cuts and tears in form liners shall be sealed and repaired in conformance with the manufacturer's recommendations. Form liners that are delaminated from the form shall not be used. Form liners with deformations to the manufactured surface caused by improper storage practices or any other reason shall not be used.

Form liners shall extend the full length of texturing with transverse joints at 2.5 m minimum spacing. Small pieces of form liners shall not be used. Grooves shall be aligned straight and true. Grooves shall match at joints between form liners. Joints in the direction of grooves in grooved patterns shall be located only in the depressed portion of the textured concrete. Adjoining liners shall be butted together without distortion, open cracks or offsets at the joints. Joints between liners shall be cleaned before each use to remove any mortar in the joint.

Adhesives shall be compatible with the form liner material and with concrete. Adhesives shall be approved by the liner manufacturer. Adhesives shall not cause swelling of the liner material.

RELEASING FORM LINERS

Products and application procedures for form release agents shall be approved by the form liner manufacturer. Release agents shall not cause swelling of the liner material or delamination from the forms. Release agents shall not stain the concrete or react with the liner material. For reliefs simulating fractured concrete or wood grain surfaces the application method shall include the scrubbing method using a natural bristle scrub brush in the direction of grooves or grain The release agent shall coat the liner with a thin film. Following application of form release agent, the liner surfaces shall be cleaned of excess amounts of agent using compressed air. Buildup of form release agent caused by the reuse of a liner shall be removed at least every 5 uses.

Form liners shall release without leaving particles or pieces of liner material on the concrete and without pulling or breaking concrete from the textured surface. The concrete surfaces exposed by removing forms shall be protected from damage.

CURING

Concrete surfaces with architectural texture shall be cured only by the forms-in-place or water methods. Seals and curing compounds shall not be used.

MEASUREMENT AND PAYMENT

Architectural texture will be measured and paid for by the square meter.

The contract price paid per square meter for architectural texture of the types listed in the Engineer's Estimate shall include full compensation for furnishing all labor, materials, tools, equipment, and incidentals and for doing all the work involved in architectural texture, complete in place, including test panels, as shown on the plans, as specified in the Standard Specifications and these special provisions, and as directed by the Engineer.

10-1.61 COLORED CONCRETE

Colored concrete shall conform to the provisions in Section 51, "Concrete Structures," and Section 90, "Portland Cement Concrete," of the Standard Specifications and these special provisions.

The color of bent caps, columns, abutment wall stems, retaining wall stems, concrete barriers Type 736, 736A, 60A, 60C of Central Viaduct (Replace), Bridge No. 34-0077 shall be integrally pigmented colored concrete. The color shall conform to Color No. 23619 of Federal Standard 595B.

Color pigments shall be of high quality iron oxides conforming to ASTM C979, "Standard Specification for Pigments for Integrally Colored Concrete." The manufacturer of the color pigments shall specify the dosage rate for achieving the specified color. The dosage shall not exceed 10 percent by weight of cementitious materials in the concrete mix design.

The Contractor shall submit technical data and manufacturer's specifications for colored concrete components and a proposed plan for mixing, delivery, placement, finishing, and curing of the colored concrete. This plan shall be submitted to the Engineer for approval at least 15 days prior to constructing the test panel as specified herein.

At the Contractor's option air-entraining admixtures may be used in conformance with Section 90-4.07, "Optional Use of Air-entraining Admixtures," of the Standard Specifications.

In addition to the requirements for the use of admixtures in Section 90-4, "Admixtures," of the Standard Specifications and these special provisions, admixtures used in colored concrete shall be certified by both the color additive manufacturer and the concrete supplier. The Contractor shall submit these written certifications to the Engineer at least 15 days prior to constructing the test panel.

Test Panel

A test panel of at least 1.25 m x 1.25 m in size, with a depth of 150 mm, shall be successfully completed, at a location approved by the Engineer, at least 30 days before placing colored concrete. The test panel shall be constructed, finished, and cured with the same materials, tools, equipment, and methods that will be used in placing the colored concrete. At the completion of the curing period, the test panel shall exhibit a color that closely matches the specified color. If ordered by the Engineer, additional test panels shall be constructed, finished, and cured until the specified color is obtained.

The approved test panel shall be the standard of comparison in determining the acceptability of colored concrete. Upon successful completion of all colored concrete, all test panels shall become property of the Contractor and shall be disposed of in conformance with the provisions in Section 7-1.13, "Disposal of Material Outside the Highway Right of Way," of the Standard Specifications.

Samples of cementitious materials and aggregates used in the approved test panel shall be retained. Cementitious materials and aggregates from the same sources used in the approved test panel shall be used for the colored concrete and sampled in conformance with California Test 201 for comparison of color and gradation with the material used for the approved test panel.

Construction

The Contractor shall monitor the water content, weight of cement, and size, weight, and color of aggregate to maintain consistency and accuracy of the mixed colored concrete. The Contractor shall schedule delivery of concrete to provide consistent mix times from batching until discharge. No water shall be added after a portion of the batch has been discharged.

When more than one concrete pump is used to place concrete, the Contractor shall designate which pumps shall receive colored concrete. The designated pumps shall receive only colored concrete throughout the concrete placement operation.

Consistent finishing practices shall be used to ensure uniformity of texture and color. Surrounding exposed surfaces shall be protected from discoloring during placement and finishing operations of colored concrete.

Unless otherwise specified, curing of colored concrete shall be by the forms-in-place method or the curing compound method only and shall conform to Section 90-7.03, "Curing Structures," of the Standard Specifications and these special provisions. The curing compound used for curing colored concrete surfaces shall be clear or match the color of the colored concrete and shall be manufactured specifically for colored concrete. Curing compounds containing calcium chloride shall not be used. Curing compound shall be applied at a consistent time period after concrete finishing operations. Surrounding exposed surfaces shall be protected from discoloring during curing operations of colored concrete.

Measurement and Payment

Colored concrete of bent caps, columns, abutment wall stems, and retaining wall stems will be measured and paid for as structural concrete, bridge (colored) and structural concrete, retaining wall (colored).

The contract price paid per cubic meter for structural concrete, bridge (colored) and structural concrete, retaining wall (colored) shall include full compensation for furnishing all labor, materials, tools, equipment and incidentals, and for doing all the work involved in constructing the colored concrete work, complete in place, including test panels, as shown on the plans, as specified in the Standard Specifications and these special provisions, and as directed by the Engineer.

Full compensation for colored concrete used in concrete barriers Type 736, 736A, 60A, 60C shall be considered as included in the contract price paid per meter for concrete barriers of the types listed in the Engineer's Estimate and no separate payment will be made therefor.

10-1.62 MINOR CONCRETE (PIPE COVER)

Concrete for Minor Concrete (Pipe Cover) shall conform to the provisions in Section 90-10 "Minor Concrete" of the Standard Specifications and these special provisions

Minor concrete shall contain not less than 400 Kg of cement per cubic meter.

Calcium chloride conforming to the provisions of Section 90-4.04 of the Standard Specifications shall be added to the minor concrete (pipe cover).

The concrete shall be placed in the trench against undisturbed material at the sides of the trench. Foreign material which falls into the trench, prior to or during placing of the concrete, shall be immediately removed. Where necessary, earth plugs shall be constructed and compacted at the ends of the planned concrete to contain the concrete within the trench.

The surface of the minor concrete (pipe cover) shall be broomed with a heavy broom to produce a uniform rough surface.

Minor concrete (pipe cover) shall be placed and compacted without segregation and the finished surface shall not vary more than 15-mm above or below the grade established by the Engineer.

Minor concrete (pipe cover) shall be cured by applying SS1 type asphaltic emulsion applied in conformance with the provisions in Section 94, "Asphaltic Emulsions", of the Standard Specifications. The curing seal shall be applied at a rate between 0.70 and 1.15 L per square meter of surface. The exact rate of application will be determined by the Engineer. Any areas of the curing seal that are damaged shall be covered immediately with additional seal by the Contractor at his expense. The curing seal shall be allowed to remain on the minor concrete (pipe cover) to serve as a paint binder when surfacing is placed thereon.

Minor concrete (pipe cover) will be measured and paid for by the cubic meter in the same manner specified for minor concrete (backfill) in Section 65-1.10 "Payment" of the Standard Specifications.

Full compensation for curing seal and calcium chloride shall be considered as included in the contract price paid per cubic meter for minor concrete (pipe cover) and no separate payment will be made therefor.

10-1.63 REINFORCEMENT

Reinforcement shall conform to the provisions in Section 52, "Reinforcement," of the Standard Specifications and these special provisions.

ULTIMATE BUTT SPLICES

Ultimate butt splices shall be either welded or mechanical splices, shall be used at the locations shown on the plans, and shall conform to the provisions in Section 52, "Reinforcement," of the Standard Specifications and these special provisions.

General Requirements

The Contractor shall designate in writing an ultimate butt splicing Quality Control Manager (QCM). The QCM shall be responsible directly to the Contractor for 1) the quality of all ultimate butt splicing including the inspection of materials and workmanship performed by the Contractor and all subcontractors; and 2) submitting, receiving, and approving all correspondence, required submittals, and reports regarding ultimate butt splicing to and from the Engineer.

The QCM shall not be employed or compensated by any subcontractor, or by other persons or entities hired by subcontractors, who will provide other services or materials for the project. The QCM may be an employee of the Contractor.

The length of any type of ultimate mechanical butt splice shall not exceed 10 times the bar diameter of the larger bar to be spliced.

All ultimate prejob, production, and job control sample splices shall be 1) a minimum length of 1.5 meters for reinforcing bars No. 25 or smaller and 2 meters for reinforcing bars No. 29 or larger, with the splice located at mid-point, and 2) suitably identified prior to shipment with weatherproof markings that do not interfere with the Engineer's tamper-proof markings or seals. Any splice that shows signs of tampering will be rejected.

A minimum of one control bar shall be removed from the same bar as, and adjacent to, all ultimate prejob, production, and job control sample splices. Control bars shall be 1) a minimum length of one meter for reinforcing bars No. 25 or smaller and 1.5 meters for reinforcing bars No. 29 or larger, and 2) suitably identified prior to shipment with weatherproof markings that do not interfere with the Engineer's tamper-proof markings or seals. The portion of adjacent bar remaining in the work shall also be identified with weatherproof markings that correspond to its adjacent control bar.

Shorter length sample splice and control bars may be furnished if approved in writing by the Engineer.

Each sample splice and its associated control bar shall be identified and marked as a set. Each set shall be identified as representing a prejob, production, or job control sample splice.

The portion of hoop reinforcing bar, removed to obtain a sample splice and control bar, shall be replaced using a prequalified ultimate mechanical butt splice, or the hoop shall be replaced in kind.

Reinforcing bars, other than hoops, from which sample splices are removed, shall be repaired using ultimate mechanical butt splices conforming to the provisions in "Prejob Test Requirements for Ultimate Butt Splices" specified herein, or the bars shall be replaced in kind. These bars shall be repaired or replaced such that no splices are located in the "No Splice Zone" shown on the plans.

Section 52-1.08E, "Job Control Tests," of the Standard Specifications shall not apply.

The provisions for total slip shall not apply to any ultimate splices that are welded or that are used on hoops.

The independent qualified testing laboratory used to perform the testing of all ultimate butt sample splices and control bars shall not be employed or compensated by any subcontractor, or by other persons or entities hired by subcontractors who will provide other services or materials for the project, and shall have the following:

A. Proper facilities, including a tensile testing machine capable of breaking the largest size of reinforcing bar to be tested.
B. A device for measuring the total slip of the reinforcing bars across the splice to the nearest 25 µm, that, when placed parallel to the longitudinal axis of the bar is able to simultaneously measure movement across the splice, at 2 locations, 180 degrees apart.
C. Operators who have received formal training for performing the testing requirements of ASTM Designation: A 370/A 370M and California Test 670.
D. A record of annual calibration of testing equipment performed by an independent third party that has 1) standards that are traceable to the National Institute of Standards and Technology, and 2) a formal reporting procedure, including published test forms.

Ultimate Butt Splice Test Criteria

Ultimate prejob, production, and job control sample splices shall be tensile tested in conformance with the requirements described in ASTM Designation: A 370/A 370M and California Test 670.

Ultimate prejob and production sample splices shall rupture in the reinforcing bar either: 1) outside of the affected zone or 2) within the affected zone, provided that the sample has achieved at least 95 percent of the ultimate tensile strength of the control bar associated with the sample. In addition, necking of the bar shall be visibly evident at rupture regardless of whether the bar breaks inside or outside the affected zone.

The affected zone is the portion of the reinforcing bar where any properties of the bar, including the physical, metallurgical, or material characteristics, have been altered by fabrication or installation of the splice.

The ultimate tensile strength of each control bar shall be determined by tensile testing the bar to rupture and shall be determined for all control bars, regardless of where each sample splice ruptures. If 2 control bars are tested for one sample splice, the bar with the lower ultimate tensile strength shall be considered the control bar.

Testing to determine the minimum tensile strength, in conformance with the provisions in the ninth paragraph of Section 52-1.08, "Splicing," of the Standard Specifications, will not be required.

Prejob Test Requirements for Ultimate Butt Splices

Prior to use in the work, all ultimate butt splices shall conform to the following prejob test requirements:

A. Eight prejob sample splices for each bar size of each splice type including ultimate mechanical butt splices, ultimate complete joint penetration butt welded splices, and ultimate resistance butt welded splices, that will be used in the work, shall be fabricated by the Contractor. For deformation-dependent types of couplers, 8 sample prejob splices shall also be fabricated for each reinforcing bar size and deformation pattern that will be used in the work.
B. The sample splices shall be fabricated using the same splice materials, position, operators, location, and equipment, and following the same procedures as will be used to make the splices in the work.
C. At the option of the Contractor, operator qualification tests may be performed simultaneously with the preparation of prejob sample splices.
D. If different diameters of hoops are shown on the plans, prejob sample splices, as described above, will only be required for the smallest hoop diameter. In addition, these splices shall be fabricated using the same radius as shown on the plans for these hoops.
E. Unless otherwise directed in writing by the Engineer, 4 prejob sample splices and control bar sets shall be shipped to the Transportation Laboratory and the remaining 4 sets shall be tested by the Contractor's independent qualified testing laboratory.
F. Each group of 4 sets from a prejob test shall be securely bundled together and identified by location and contract number with weatherproof markings prior to shipment. Bundles containing fewer than 4 sets will not be tested by the Transportation Laboratory, nor shall they be tested by the independent laboratory.
G. All 8 sample splices from each prejob test shall conform to the provisions in "Ultimate Butt Splice Test Criteria" specified herein.
H. Prior to performing any tensile tests on prejob test sample splices, one of the 4 samples shall be tested for, and shall conform to, the provisions for total slip. Should this sample not meet these requirements, one retest, in which the 3 remaining samples are tested for total slip, will be allowed. All 3 of these remaining samples tested shall conform to the aforementioned slip requirements.
I. For each bundle of 4 sets, a Prejob Test Report shall be prepared by the independent testing laboratory performing the testing. The report shall 1) be signed by an engineer who represents the laboratory and is registered as a Civil Engineer in the State of California; 2) include, as a minimum, the following information for each set: contract number, bridge number, bar size, type of splice, length of mechanical splice, physical condition of test sample splice and control bar, any notable defects, limits of affected zone, total measured slip, location of visible necking area, ultimate strength of each splice, ultimate strength and 95 percent of this ultimate strength for each control bar, and a comparison between 95 percent of the ultimate strength of each control bar and the ultimate strength of its associated splice; and 3) be submitted to the QCM for review and approval, and then to the Engineer.
J. Test results for each bundle of 4 sets will be reported in writing to the Contractor within 10 working days after receipt of the bundle by the Transportation Laboratory. In the event that more than one bundle is received on the same day, 2 additional working days shall be allowed for providing test results for each additional bundle received. A test report will be made for each bundle received.
K. Should the Engineer fail to provide the test results within this time allowance and if, in the opinion of the Engineer, the Contractor's controlling operation is delayed or interfered with by reason of the delay in providing the test results, the delay will be considered a right of way delay in conformance with the provisions in Section 8-1.09, "Right of Way Delays," of the Standard Specifications.

Production Test Requirements for Ultimate Butt Splices

Production tests shall be performed for all ultimate butt splices used in the work. A production test shall consist of 4 sets of sample splices and control bars removed from each lot of completed splices, except when quality assurance tests are performed.

A lot of ultimate butt splices is defined as 1) 150, or fraction thereof, of the same type of ultimate mechanical butt splices used for each bar size and each bar deformation pattern that is used in the work or 2) 150, or fraction thereof, of ultimate complete joint penetration butt welded splices, or ultimate resistance butt welded splices for each bar size used in the work. If different diameters of hoop reinforcement are shown on the plans, separate lots shall be used for each different hoop diameter.

After all splices in a lot have been completed, the QCM shall notify the Engineer in writing that all couplers in this lot conform to the specifications and are ready for testing. The sample splices will either be selected by the Engineer at the job site or a fabrication facility, provided the facility is located within an 80-km radius of the jobsite.

At the option of the Contractor, sample splices for vertical and hook reinforcement at the 1.8 m and 2.1 m diameter cast-in-drilled-hole concrete piling may be either 1) removed from the completed lot, or 2) prepared in the same manner as specified herein for ultimate prejob sample splices and control bars.

After notification has been received, the Engineer will randomly select the 4 sample splices to be removed from the lot and place tamper-proof markings or seals on them. The Contractor or QCM shall select the adjacent control bar for each sample splice bar, and the Engineer will place tamper-proof markings or seals on them. These ultimate production sample splices and control bars shall be removed by the Contractor, and tested by an independent qualified testing laboratory, in the presence of either the Engineer or the Engineer's authorized representative.

The Engineer or the Engineer's authorized representative will be at the independent qualified testing laboratory within a maximum of 5 working days after receiving written notification that the samples are at the laboratory and ready for testing. Should the Engineer or the Engineer's authorized representative fail to be at the laboratory within this time allowance, and if, in the opinion of the Engineer, the Contractor's controlling operation is delayed or interfered with by reason of this action, the delay will be considered a right of way delay in conformance with the provisions in Section 8-1.09, "Right of Way Delays," of the Standard Specifications.

A sample splice or control bar from any set will be rejected if any tamper-proof marking or seal is disturbed prior to testing.

The 4 sets from each production test shall be securely bundled together and identified with a completed sample identification card prior to shipment to the independent laboratory. The card will be furnished by the Engineer. Bundles of samples containing fewer than 4 sets of splices shall not be tested.

A Production Test Report for all testing performed on each lot shall be prepared by the independent testing laboratory performing the testing and submitted to the QCM for review and approval. The report shall be signed by an engineer who represents the laboratory and is registered as a Civil Engineer in the State of California. The report shall include, as a minimum, the following information for each set: contract number, bridge number, lot number and location, bar size, type of splice, length of mechanical splice, physical condition of test sample splice and control bar, any notable defects, limits of affected zone, total measured slip, location of visible necking area, ultimate strength of each splice, ultimate strength and 95 percent of this ultimate strength for each control bar, and a comparison between 95 percent of the ultimate strength of each control bar and the ultimate strength of its associated splice.

The QCM must review, approve, and forward each Production Test Report to the Engineer for review before any splices represented by the report are encased in concrete. The Engineer shall have 3 working days to review each Production Test Report and respond in writing after a complete report has been received. Should the Contractor elect to encase any splices prior to receiving notification from the Engineer, it is expressly understood that the Contractor will not be relieved of the Contractor's responsibility for incorporating material in the work that conforms to the requirements of the plans and specifications. Any material not conforming to these requirements will be subject to rejection. Should the Contractor elect to wait to encase any splices pending notification by the Engineer, and should the Engineer fail to complete the review and provide notification within this time allowance, and if, in the opinion of the Engineer, the Contractor's controlling operation is delayed or interfered with by reason of the delay in notification, the delay will be considered a right of way delay in conformance with the provisions in Section 8-1.09, "Right of Way Delays," of the Standard Specifications.

At the option of the Contractor, any splices at the locations listed below may be encased in concrete prior to having the QCM review, approve, and forward each Production Test Report to the Engineer. Should the Contractor exercise this option, it is expressly understood that the Contractor will not be relieved of the Contractor's responsibility for incorporating material in the work that conforms to the requirements of the plans and specifications. Any material not conforming to these requirements will be subject to rejection.

A. 1.8 m diameter cast-in-drilled-hole concrete piling
B. 2.1 m diameter cast-in-drilled-hole concrete piling

Prior to performing any tensile tests on production test sample splices, one of the 4 samples shall be tested for, and shall conform to, the provisions for total slip. Should this sample not meet these requirements, one retest, in which the 3 remaining samples are tested for total slip, will be allowed. Should any of the 3 remaining samples not conform to these requirements, all splices in the lot represented by this production test will be rejected.

If 3 or more sample splices from any production test conform to the provisions in "Ultimate Butt Splice Test Criteria" specified herein, all splices in the lot represented by this production test will be considered acceptable.

Should only 2 sample splices from any production test conform to the provisions in "Ultimate Butt Splice Test Criteria" specified herein, one additional production test shall be performed on the same lot of splices. Should any of the 4 sample splices from this additional test fail to conform to these provisions, all splices in the lot represented by these production tests will be rejected.

If only one sample splice from any production test conforms to the provisions in "Ultimate Butt Splice Test Criteria" specified herein, all splices in the lot represented by this production test will be rejected.

If a production test for any lot fails, the Contractor will be required to repair or replace all reinforcing bars from which sample splices were removed, complete in place, before the Engineer selects any additional splices from this lot for further testing.

Whenever any lot of ultimate butt splices is rejected, additional ultimate butt splices shall not be used in the work until 1) the QCM performs a complete review of the Contractor's quality control process for these splices, 2) a written report is submitted to the Engineer describing the cause of failure for the splices in this lot and provisions for correcting these failures in future lots, and 3) the Engineer has provided the Contractor with written notification that the report is acceptable. The Engineer shall have 3 working days after receipt of the report to provide notification to the Contractor. Should the Engineer not provide notification within this time allowance, and if, in the opinion of the Engineer, the Contractor's controlling operation is delayed or interfered with by reason of this action, the delay will be considered a right of way delay in conformance with the provisions in Section 8-1.09, "Right of Way Delays," of the Standard Specifications.

Production tests will not be required on any repaired splice from a lot, regardless of the type of prequalified ultimate mechanical butt splice used to make the repair.

Should an additional production test be required, the Engineer may select any repaired splice for use in the additional production test.

Quality Assurance Test Requirements for Ultimate Butt Splices

For the first production test performed, and for at least one, randomly selected by the Engineer, of every 5 additional production tests, or portion thereof, performed thereafter, the Contractor shall concurrently prepare 4 additional ultimate job control sample splices along with associated control bars. These ultimate job control samples shall be prepared in the same manner as specified herein for ultimate prejob sample splices and control bars.

Each time 4 additional ultimate job control sample splices are prepared, 2 of these job control sample splice and associated control bar sets and 2 of the production sample splice and associated control bar sets, together, shall conform to the requirements for ultimate production sample splices in "Production Test Requirements for Ultimate Butt Splices" specified herein.

The 2 remaining job control sample splice and associated control bar sets, along with the 2 remaining production sample splice and associated control bar sets shall be shipped, unless otherwise directed in writing by the Engineer, to the Transportation Laboratory for quality assurance testing. The 4 sets shall be securely bundled together and identified by location and contract number with weatherproof markings prior to shipment. Bundles containing fewer than 4 sets will not be tested.

Quality assurance testing will be performed in conformance with the requirements for ultimate production sample splices in "Production Test Requirements for Ultimate Butt Splices" specified herein.

Test results for each bundle of 4 sets will be reported in writing to the Contractor within 3 working days after receipt of the bundle by Transportation Laboratory. In the event that more than one bundle is received on the same day, 2 additional working days shall be allowed for providing test results for each additional bundle received. A test report will be made for each bundle received. Should the Contractor elect to encase any splices prior to receiving notification from the Engineer, it is expressly understood that the Contractor will not be relieved of the Contractor's responsibility for incorporating material in the work that conforms to the requirements of the plans and specifications. Any material not conforming to these requirements will be subject to rejection. Should the Contractor elect to wait to encase any splices pending notification by the Engineer, and should the Engineer fail to complete the review and provide notification within this time allowance, and if, in the opinion of the Engineer, the Contractor's controlling operation is delayed or interfered with by reason of the delay in notification, the delay will be considered a right of way delay in conformance with the provisions in Section 8-1.09, "Right of Way Delays," of the Standard Specifications.

SERVICE BUTT SPLICES

Service butt splices shall be used at the locations shown on the plans, and shall conform to the provisions in Section 52, "Reinforcement," of the Standard Specifications and these special provisions. Service butt splices shall be either welded or mechanical splices. Unless otherwise specified, mechanical lap splices shall be treated as service butt splices as specified herein.

General Requirements

The Contractor shall designate in writing a service butt splicing Quality Control Manager (QCM). The QCM shall be responsible directly to the Contractor for 1) the quality of all service butt splicing including the inspection of materials and workmanship performed by the Contractor and all subcontractors; and 2) submitting, receiving, and approving all correspondence, required submittals, and reports regarding service butt splicing to and from the Engineer.

The QCM shall not be employed or compensated by any subcontractor, or by other persons or entities hired by subcontractors, who will provide other services or materials for the project. The QCM may be an employee of the Contractor.

All service prejob and production sample splices shall be 1) a minimum length of 1.5 meters for reinforcing bars No. 25 or smaller, and 2 meters for reinforcing bars No. 29 or larger, with the splice located at mid-point; and 2) suitably identified prior to shipment with weatherproof markings that do not interfere with the Engineer's tamper-proof markings or seals. Any splice that shows signs of tampering will be rejected.

Shorter length sample splice bars may be furnished if approved in writing by the Engineer.

Each set shall be identified as representing either a prejob or production test sample splice.

Section 52-1.08E, "Job Control Tests," of the Standard Specifications shall not apply.

When joining new reinforcing bars to existing reinforcement, the prejob sample splices shall be made using only the deformation pattern of the new reinforcement to be joined.

The provisions for total slip shall not apply to any service splices that are welded.

The independent qualified testing laboratory used to perform the testing of all service butt sample splices shall not be employed or compensated by any subcontractor, or by other persons or entities hired by subcontractors who will provide other services or materials for the project, and shall have the following:

A. Proper facilities, including a tensile testing machine capable of breaking the largest size of reinforcing bar to be tested.
B. A device for measuring the total slip of the reinforcing bars across the splice to the nearest 25 µm, that, when placed parallel to the longitudinal axis of the bar is able to simultaneously measure movement across the splice, at 2 locations, 180 degrees apart.
C. Operators who have received formal training for performing the testing requirements of ASTM Designation: A 370/A 370M and California Test 670.
D. A record of annual calibration of testing equipment performed by an independent third party that has 1) standards that are traceable to the National Institute of Standards and Technology, and 2) a formal reporting procedure, including published test forms.

Service Butt Splice Test Criteria

Service prejob sample splices and production sample splices shall be tensile tested in conformance with the requirements described in ASTM Designation: A 370/A 370M and California Test 670.

Service prejob sample splices and production sample splices shall develop a minimum tensile strength of not less than 550 Mpa.

Prejob Test Requirements for Service Butt Splices

Prior to use in the work, all service butt splices shall conform to the following prejob test requirements:

A. Four prejob sample splices for each bar size of each splice type including service mechanical butt splices, service complete joint penetration butt welded splices, and service resistance butt welded splices, that will be used in the work, shall be fabricated by the Contractor. For deformation-dependent types of couplers, 4 sample prejob splices shall also be fabricated for each reinforcing bar size and deformation pattern that will be used in the work.
B. The sample splices shall be fabricated using the same splice materials, position, operators, location, and equipment, and following the same procedures as will be used to make the splices in the work.
C. At the option of the Contractor, operator qualification tests may be performed simultaneously with the preparation of prejob sample splices.

D. Unless otherwise directed in writing by the Engineer, the 4 sample splices shall be tested by the Contractor's independent qualified testing laboratory.
E. Each group of 4 samples from a prejob test shall be securely bundled together and identified by location and contract number with weatherproof markings prior to shipment. Bundles containing fewer than 4 samples shall not be tested by the independent laboratory.
F. All 4 sample splices from each prejob test shall conform to the provisions in "Service Butt Splice Test Criteria" specified herein.
G. Prior to performing any tensile tests on prejob test sample splices, one of the 4 samples shall be tested for, and shall conform to, the provisions for total slip. Should this sample not meet these requirements, one retest, in which the 3 remaining samples are tested for total slip, will be allowed. All 3 of these remaining samples tested shall conform to the aforementioned slip requirements.
H. For each bundle of 4 samples, a Prejob Test Report shall be prepared by the independent testing laboratory performing the testing. The report shall 1) be signed by an engineer who represents the laboratory and is registered as a Civil Engineer in the State of California; 2) include, as a minimum, the following information for each sample: contract number, bridge number, bar size, type of splice, length of mechanical splice, physical condition of test sample splice, any notable defects, total measured slip, and ultimate strength of each splice; and 3) be submitted to the QCM for review and approval, and then to the Engineer.

Production Test Requirements for Service Butt Splices

Production tests shall be performed by the Contractor's independent laboratory for all service butt splices used in the work. Unless otherwise specified, a production test shall consist of 4 sample splices prepared for each lot of completed splices. The samples shall be prepared by the Contractor in the same manner as specified herein for service prejob sample splices, and then tested by the independent laboratory in the presence of either the Engineer or the Engineer's authorized representative.

A lot of service butt splices is defined as 1) 150, or fraction thereof, of the same type of service mechanical butt splices used for each bar size and each bar deformation pattern that is used in the work or 2) 150, or fraction thereof, of service complete joint penetration butt welded splices, or service resistance butt welded splices for each bar size used in the work.

The Engineer or the Engineer's authorized representative will be at the independent qualified testing laboratory within a maximum of 5 working days after receiving written notification that the samples are at the laboratory and ready for testing. Should the Engineer or the Engineer's authorized representative fail to be at the laboratory within this time allowance, and if, in the opinion of the Engineer, the Contractor's controlling operation is delayed or interfered with by reason of this action, the delay will be considered a right of way delay in conformance with the provisions in Section 8-1.09, "Right of Way Delays," of the Standard Specifications.

The 4 samples from each production test shall be securely bundled together and identified with a completed sample identification card prior to shipment to the independent laboratory. The card will be furnished by the Engineer. Bundles of samples containing fewer than 4 samples of splices shall not be tested.

A Production Test Report for all testing performed on each lot shall be prepared by the independent testing laboratory performing the testing and submitted to the QCM for review and approval. The report shall be signed by an engineer who represents the laboratory and is registered as a Civil Engineer in the State of California. The report shall include, as a minimum, the following information for each sample: contract number, bridge number, lot number and location, bar size, type of splice, length of mechanical splice, physical condition of test sample splice, any notable defects, total measured slip, ultimate strength of each splice.

The QCM must review, approve, and forward each Production Test Report to the Engineer for review before any splices represented by the report are encased in concrete. The Engineer shall have 3 working days to review each Production Test Report and respond in writing after a complete report has been received. Should the Contractor elect to encase any splices prior to receiving notification from the Engineer, it is expressly understood that the Contractor will not be relieved of the Contractor's responsibility for incorporating material in the work that conforms to the requirements of the plans and specifications. Any material not conforming to these requirements will be subject to rejection. Should the Contractor elect to wait to encase any splices pending notification by the Engineer, and should the Engineer fail to complete the review and provide notification within this time allowance, and if, in the opinion of the Engineer, the Contractor's controlling operation is delayed or interfered with by reason of the delay in notification, the delay will be considered a right of way delay in conformance with the provisions in Section 8-1.09, "Right of Way Delays," of the Standard Specifications.

Prior to performing any tensile tests on production test sample splices, one of the 4 samples shall be tested for, and shall conform to, the provisions for total slip. Should this sample not meet the slip requirements, one retest, in which the 3 remaining samples are tested for total slip, will be allowed. Should any of the 3 remaining samples not conform to the slip requirements, all splices in the lot represented by this production test will be rejected.

If 3 or more sample splices from any production test conform to the provisions in "Service Butt Splice Test Criteria" specified herein, all splices in the lot represented by this production test will be considered acceptable, provided all 4 samples develop a minimum tensile strength of not less than 420 Mpa.

Should only 2 sample splices from any production test conform to the provisions in "Service Butt Splice Test Criteria" specified herein, one additional production test shall be performed on the same lot of splices. This additional production test shall consist of testing 4 samples splices that have been randomly selected by the Engineer and removed by the Contractor from the actual completed lot of splices. Should any of the 4 splices from this additional test fail to conform to these provisions or to develop a minimum tensile strength of not less than 550 Mpa, all splices in the lot represented by these production tests will be rejected.

If only one sample splice from any production test conforms to the provisions in "Service Butt Splice Test Criteria" specified herein, all splices in the lot represented by this production test will be rejected.

If a production test for any lot fails, the Contractor will be required to repair or replace all reinforcing bars from which sample splices were removed, complete in place, before the Engineer selects any additional splices from this lot for further testing.

Whenever any lot of service butt splices is rejected, additional service butt splices shall not be used in the work until 1) the QCM performs a complete review of the Contractor's quality control process for these splices, 2) a written report is submitted to the Engineer describing the cause of failure for the splices in this lot and provisions for correcting these failures in future lots, and 3) the Engineer has provided the Contractor with written notification that the report is acceptable. The Engineer shall have 3 working days after receipt of the report to provide notification to the Contractor. Should the Engineer not provide notification within this time allowance, and if, in the opinion of the Engineer, the Contractor's controlling operation is delayed or interfered with by reason of this action, the delay will be considered a right of way delay in conformance with the provisions in Section 8-1.09, "Right of Way Delays," of the Standard Specifications.

MEASUREMENT AND PAYMENT

Measurement and payment for reinforcement in structures shall conform to the provisions in Section 52-1.10, "Measurement," and Section 52-1.11, "Payment," of the Standard Specifications and these special provisions.

Full compensation for conforming to the provisions of "Ultimate Butt Splices," of these special provisions shall be considered as included in the contract prices paid for the various contract items of work involved and no additional compensation will be allowed therefor.

Full compensation for conforming to the provisions of "Service Butt Splices," of these special provisions shall be considered as included in the contract prices paid for the various contract items of work involved and no additional compensation will be allowed therefor.

10-1.64 STEEL STRUCTURES

Construction of steel structures shall conform to the provisions in Section 55, "Steel Structures," of the Standard Specifications and these special provisions.

GENERAL

Fabrication of grade HPS 70W steel shall conform to the requirements in ASTM A 709/A 709M, the latest edition of the ASSHTO "Guide Specifications for Highway Bridge Fabrication with HPS 70W Steel," and these special provisions.

Structural steel (bridge) shall include column shear pins.

Attention is directed to "Welding" in Section 8, "Materials," of these special provisions.

The following substitutions of high-strength steel fasteners shall be made:

METRIC SIZE SHOWN ON THE PLANS	SIZE TO BE SUBSTITUTED
ASTM Designation: A 325M (Nominal bolt diameter (mm or mm x thread pitch))	ASTM Designation: A 325 (Nominal bolt diameter (inch))
13 or 12.70, M12, M12 x 1.75	1/2
16 or 15.88, M16, M16 x 2	5/8
19 or 19.05, M20, M20 x 2.5	3/4
22 or 22.22, M22, M22 x 2.5	7/8
24, 25, or 25.40, M24, M24 x 3	1
29 or 28.58, M27, M24 x 3	1 1/8
32 or 31.75, M30, M30 x 3.5	1 1/4
38 or 38.10, M36, M36 x 4	1 1/2

MATERIALS

Structural steel rolled shapes used in the intermediate crossframes shall conform to the Charpy V-notch impact values specified for steel plate in Section 55-2, "Materials," of the Standard Specifications.

TEMPORARY FALSEWORK TOWERS

Temporary falsework towers used to support the steel girders and splice girders in their final position shall conform to the provisions in Section 55-1.05, "Falsework," of the Standard Specifications and these special provisions. Openings shall be provided through temporary falsework towers for the use of public traffic. The temporary falsework towers shall have the same minimum width, height, and number of openings as the adjacent bent cap falsework specified under "Maintaining Traffic" of these special provisions.

Temporary falsework towers shall not be allowed at Mission and Duboce intersection.

CHECK TESTING

Structural steel shall conform to the designated ASTM Standard and the check testing requirements of this section.

Check samples shall be furnished for each heat of maximum thickness of:

Tension flanges and webs of curved girders.

Steel plates, shapes, or bars containing check samples shall be furnished from the mill with extra length in order to provide for removal of material for check samples at the point of fabrication. Check samples may be cut from either end of the designated plate, shape, or bar.

At the option of the Contractor, check samples may be removed at the rolling mill rather than at the point of fabrication. The sample will be removed from the mill plate that will be stripped by the fabricator to produce the designated plate and may be taken from any location within that plate. The mill plate from which samples are removed shall be marked with the same identifying numbers as are used on the samples.

Material for check samples shall be removed by the Contractor in the presence of the Engineer. Check samples for plates wider than 610 mm shall be 355 mm wide and 460 mm long with the long dimension transverse to the direction of rolling. Check samples for all other products shall be 460 mm long, taken in the direction of rolling, and the width shall be the product width. Check samples shall be removed and delivered to the Engineer before the material is fabricated into components. The direction of rolling, heat numbers, and plate numbers shall be marked on the samples with paint or other indelible marking material or may be steel stamped in one corner of the plate.

Check samples shall be delivered to the Transportation Laboratory at the Contractor's expense. The check samples will be tested by the Transportation Laboratory for compliance with the requirements specified in ASTM and these special provisions. Check sample test results will be reported to the Contractor within 3 weeks of delivery to the Transportation Laboratory. In the event several samples are submitted on the same day, an additional day will be added for every 2 samples submitted. The test report will be made for the group of samples.

The results of the tensile and impact tests shall not vary more than 5 percent below the specified minimum or 5 percent above the specified maximum requirements. If the initial check test results vary more than 5 percent but not more than 10 percent from the specified requirements, a retest may be performed on another sample from the same heat and thickness. The results of the retest shall not vary more than 5 percent from the original specified requirements. If the results of check tests exceed these permissible variations, material planned for use from the heat represented by said check samples shall be subject to rejection.

ROTATIONAL CAPACITY TESTING PRIOR TO SHIPMENT TO JOB SITE

Rotational capacity tests shall be performed on all lots of high-strength fastener assemblies prior to shipment of these lots to the project site. Zinc-coated assemblies shall be tested after all fabrication, coating, and lubrication of components has been completed. One hardened washer shall be used under each nut for the tests.

Each combination of bolt production lot, nut lot, and washer lot shall be tested as an assembly.

A rotational capacity lot number shall be assigned to each combination of lots tested. Each shipping unit of fastener assemblies shall be plainly marked with the rotational capacity lot number.

Two fastener assemblies from each rotational capacity lot shall be tested.

The following equipment, procedure, and acceptance criteria shall be used to perform rotational capacity tests on and determine acceptance of long bolts. Fasteners are considered to be long bolts when full nut thread engagement can be achieved when installed in a bolt tension measuring device:

A. Long Bolt Test Equipment:

1. Calibrated bolt tension measuring device with adequate tension capacity for the bolts being tested.
2. Calibrated dial or digital torque wrench. Other suitable tools will be required for performing Steps 7 and 8 of the Long Bolt Test Procedure. A torque multiplier may be required for large diameter bolts.
3. Spacer washers or bushings. When spacer washers or bushings are required, they shall have the same inside diameter and equal or larger outside diameter as the appropriate hardened washers conforming to the requirements in ASTM Designation: F436.
4. Steel beam or member, such as a girder flange or cross frame, to which the bolt tension measuring device will be attached. The device shall be accessible from the ground.

B Long Bolt Test Procedure:

1. Measure the bolt length. The bolt length is defined as the distance from the end of the threaded portion of the shank to the underside of the bolt head.
2. Install the nut on the bolt so that 3 to 5 full threads of the bolt are located between the bearing face of the nut and the underside of the bolt head. Measure and record the thread stickout of the bolt. Thread stickout is determined by measuring the distance from the outer face of the nut to the end of the threaded portion of the shank.
3. Insert the bolt into the bolt tension measuring device and install the required number of washers, and additional spacers as needed, directly beneath the nut to produce the thread stickout measured in Step 2 of this procedure.
4. Tighten the nut using a hand wrench to a snug-tight condition. The snug tension shall not be less than the Table A value but may exceed the Table A value by a maximum of 2 kips.

Table A

High-Strength Fastener Assembly Tension Values to Approximate Snug-Tight Condition	
Bolt Diameter (inches)	Snug Tension (kips)
1/2	1
5/8	2
3/4	3
7/8	4
1	5
1 1/8	6
1 1/4	7
1 3/8	9
1 1/2	10

5. Match-mark the assembly by placing a heavy reference start line on the face plate of the bolt tension measuring device which aligns with 1) a mark placed on one corner of the nut, and 2) a radial line placed across the flat on the end of the bolt, or on the exposed portions of the threads of tension control bolts. Place an additional mark on the outside of the socket that overlays the mark on the nut corner such that this mark will be visible while

turning the nut. Make an additional mark on the face plate, either 2/3 of a turn, one turn, or 1 1/3 turn clockwise from the heavy reference start line, depending on the bolt length being tested as shown in Table B.

Table B

Required Nut Rotation for Rotational Capacity Tests[a,b]	
Bolt Length (measured in Step 1)	Required Rotation (turn)
4 bolt diameters or less	2/3
Greater than 4 bolt diameters but no more than 8 bolt diameters	1
Greater than 8 bolt diameters, but no more than 12 bolt diameters[c]	1 1/3
(a) Nut rotation is relative to bolt, regardless of the element (nut or bolt) being turned. For bolts installed by 1/2 turn and less, the tolerance shall be plus or minus 30 degrees; for bolts installed by 2/3 turn and more, the tolerance shall be plus or minus 45 degrees. (b) Applicable only to connections in which all material within grip of the bolt is steel. (c) When bolt length exceeds 12 diameters, the required rotation shall be determined by actual tests in a suitable tension device simulating the actual conditions.	

6. Turn the nut to achieve the applicable minimum bolt tension value listed in Table C. After reaching this tension, record the moving torque, in foot-pounds, required to turn the nut, and also record the corresponding bolt tension value in pounds. Torque shall be measured with the nut in motion. Calculate the value, T (in ft-lbs), where T=[(the measured tension in pounds) x (the bolt diameter in inches) / 48 in/ft].

Table C

Minimum Tension Values for High-Strength Fastener Assemblies	
Bolt Diameter (inches)	Minimum Tension (kips)
1/2	12
5/8	19
3/4	28
7/8	39
1	51
1 1/8	56
1 1/4	71
1 3/8	85
1 1/2	103

7. Turn the nut further to increase bolt tension until the rotation listed in Table B is reached. The rotation is measured from the heavy reference line made on the face plate after the bolt was snug-tight. Record this bolt tension.
8. Loosen and remove the nut and examine the threads on both the nut and bolt.

C. Long Bolt Acceptance Criteria:

1. An assembly shall pass the following requirements to be acceptable: 1) the measured moving torque (Step 6) shall be less than or equal to the calculated value, T (Step 6), 2) the bolt tension measured in Step 7 shall be greater than or equal to the applicable turn test tension value listed in Table D, 3) the nut shall be able to be removed from the bolt without signs of thread stripping or galling after the required rotation in Step 7 has been achieved, 4) the bolt does not shear from torsion or fail during the test, and 5) the assembly does not seize before the final rotation in Step 7 is reached. Elongation of the bolt in the threaded region between the bearing face of the nut and the underside of the bolt head is expected and will not be considered a failure. Both fastener assemblies tested from one rotational capacity lot shall pass for the rotational capacity lot to be acceptable.

Table D

Turn Test Tension Values	
Bolt Diameter (inches)	Turn Test Tension (kips)
1/2	14
5/8	22
3/4	32
7/8	45
1	59
1 1/8	64
1 1/4	82
1 3/8	98
1 1/2	118

The following equipment, procedure, and acceptance criteria shall be used to perform rotational capacity tests on and determine acceptance of short bolts. Fasteners are considered to be short bolts when full nut thread engagement cannot be achieved when installed in a bolt tension measuring device:

A. Short Bolt Test Equipment:

1. Calibrated dial or digital torque wrench. Other suitable tools will be required for performing Steps 7 and 8 of the Short Bolt Test Procedure. A torque multiplier may be required for large diameter bolts.
2. Spud wrench or equivalent.
3. Spacer washers or bushings. When spacer washers or bushings are required, they shall have the same inside diameter and equal or larger outside diameter as the appropriate hardened washers conforming to the requirements in ASTM Designation: F436.
4. Steel plate or girder with a hole to install bolt. The hole size shall be 1.6 mm greater than the nominal diameter of the bolt to be tested. The grip length, including any plates, washers, and additional spacers as needed, shall provide the proper number of threads within the grip, as required in Step 2 of the Short Bolt Test Procedure.

B. Short Bolt Test Procedure:

1. Measure the bolt length. The bolt length is defined as the distance from the end of the threaded portion of the shank to the underside of the bolt head.
2. Install the nut on the bolt so that 3 to 5 full threads of the bolt are located between the bearing face of the nut and the underside of the bolt head. Measure and record the thread stickout of the bolt. Thread stickout is determined by measuring the distance from the outer face of the nut to the end of the threaded portion of the shank.
3. Install the bolt into a hole on the plate or girder and install the required number of washers and additional spacers as needed between the bearing face of the nut and the underside of the bolt head to produce the thread stickout measured in Step 2 of this procedure.
4. Tighten the nut using a hand wrench to a snug-tight condition. The snug condition shall be the full manual effort applied to the end of a 305 mm long wrench. This applied torque shall not exceed 20 percent of the maximum allowable torque in Table E.

Table E

Maximum Allowable Torque for High-Strength Fastener Assemblies	
Bolt Diameter (inches)	Torque (ft-lbs)
1/2	145
5/8	285
3/4	500
7/8	820
1	1220
1 1/8	1500
1 1/4	2130
1 3/8	2800
1 1/2	3700

5. Match-mark the assembly by placing a heavy reference start line on the steel plate or girder which aligns with 1) a mark placed on one corner of the nut and 2) a radial line placed across the flat on the end of the bolt or on the exposed portions of the threads of tension control bolts. Place an additional mark on the outside of the socket that overlays the mark on the nut corner such that this mark will be visible while turning the nut. Make 2 additional small marks on the steel plate or girder, one 1/3 of a turn and one 2/3 of a turn clockwise from the heavy reference start line on the steel plate or girder.
6. Using the torque wrench, tighten the nut to the rotation value listed in Table F. The rotation is measured from the heavy reference line described in Step 5 made after the bolt was snug-tight. A second wrench shall be used to prevent rotation of the bolt head during tightening. Measure and record the moving torque after this rotation has been reached. The torque shall be measured with the nut in motion.

Table F

Nut Rotation Required for Turn-of-Nut Installation[a,b]	
Bolt Length (measured in Step 1)	Required Rotation (turn)
4 bolt diameters or less	1/3
(a) Nut rotation is relative to bolt, regardless of the element (nut or bolt) being turned. For bolts installed by 1/2 turn and less, the tolerance shall be plus or minus 30 degrees. (b) Applicable only to connections in which all material within grip of the bolt is steel.	

7. Tighten the nut further to the 2/3-turn mark as indicated in Table G. The rotation is measured from the heavy reference start line made on the plate or girder when the bolt was snug-tight. Verify that the radial line on the bolt end or on the exposed portions of the threads of tension control bolts is still in alignment with the start line.

Table G

Required Nut Rotation for Rotational Capacity Test	
Bolt Length (measured in Step 1)	Required Rotation (turn)
4 bolt diameters or less	2/3

8. Loosen and remove the nut and examine the threads on both the nut and bolt.

C. Short Bolt Acceptance Criteria:

1. An assembly shall pass the following requirements to be acceptable: 1) the measured moving torque from Step 6 shall be less than or equal to the maximum allowable torque from Table E, 2) the nut shall be able to be

removed from the bolt without signs of thread stripping or galling after the required rotation in Step 7 has been achieved, 3) the bolt does not shear from torsion or fail during the test, and 4) the assembly shall not seize before the final rotation in Step 7 is reached. Elongation of the bolt in the threaded region between the bearing face of the nut and the underside of the bolt head will not be considered a failure. Both fastener assemblies tested from one rotational capacity lot shall pass for the rotational capacity lot to be acceptable.

INSTALLATION TENSION TESTING AND ROTATIONAL CAPACITY TESTING AFTER ARRIVAL ON THE JOB SITE

Installation tension tests and rotational capacity tests on high-strength fastener assemblies shall be performed by the Contractor prior to acceptance or installation and after arrival of the fastener assemblies on the project site. Installation tension tests and rotational capacity tests shall be performed at the job-site, in the presence of the Engineer, on each rotational capacity lot of fastener assemblies.

Installation tension tests shall be performed on 3 representative fastener assemblies in conformance with the provisions in Section 8, "Installation," of the RCSC Specification. For short bolts, Section 8.2, "Pretensioned Joints," of the RCSC Specification shall be replaced by the "Pre-Installation Testing Procedures," of the "Structural Bolting Handbook," published by the Steel Structures Technology Center, Incorporated.

The rotational capacity tests shall be performed in conformance with the requirements for rotational capacity tests in "Rotational Capacity Testing Prior to Shipment to Job Site" of these special provisions.

At the Contractor's expense, additional installation tension tests, tests required to determine job inspecting torque, and rotational capacity tests shall be performed by the Contractor on each rotational capacity lot, in the presence of the Engineer, if 1) any fastener is not used within 3 months after arrival on the jobsite, 2) fasteners are improperly handled, stored, or subjected to inclement weather prior to final tightening, 3) significant changes are noted in original surface condition of threads, washers, or nut lubricant, or 4) the Contractor's required inspection is not performed within 48 hours after all fasteners in a joint have been tensioned.

Failure of a job-site installation tension test or a rotational capacity test will be cause for rejection of unused fasteners that are part of the rotational capacity lot.

When direct tension indicators are used, installation verification tests shall be performed in conformance with Appendix Section X1.4 of ASTM Designation: F959, except that bolts shall be initially tensioned to a value 5 percent greater than the minimum required bolt tension.

SURFACE PREPARATION

For all bolted connections, the 1) contact surfaces, 2) outer surfaces of existing members that are within the grip and will be hidden by surfaces of outside existing members within the grip under bolt heads, nuts, and washers, shall be cleaned and coated before assembly in conformance with the provisions for cleaning and painting structural steel of these special provisions.

SEALING

When zinc-coated tension control bolts are used, the sheared end of each fastener shall be completely sealed with non-silicone type sealing compound conforming to the provisions in Federal Specification TT-S-230, Type II. The sealant shall be gray in color and shall have a minimum thickness of 1.3 mm. The sealant shall be applied to a clean sheared surface on the same day that the splined end is sheared off.

WELDING

Dimensional details and workmanship for welded joints in tubular and pipe connections shall conform to the provisions in Part A, "Common Requirements of Nontubular and Tubular Connections," and Part D, "Specific Requirements for Tubular Connections," in Section 2 of AWS D1.1.

CURVED GIRDERS

Cold bending to achieve curvature for curved girders shall not be used.

Heat-curving of girders for the Central Viaduct (Replace), Bridge No. 34-0077 may be used subject to the requirements in this section.

Girders may be curved by either continuous or V-type heating.

For the continuous method, a strip along the edge of the top and bottom flange shall be heated simultaneously. The strip shall be of sufficient width and temperature to obtain the required curvature.

For V-type heating, the top and bottom flanges shall be heated in truncated triangular or wedge-shaped areas having their bases along the flange edge and spaced at regular intervals along each flange. The spacing and temperature shall be as

required to obtain the required curvature, and heating shall progress along the top and bottom flange at approximately the same rate. For V-type heating, the apex of the truncated triangular area applied to the inside flange surface shall terminate just before the juncture of the web and the flange is reached. Heat shall not be applied directly to the web. When the radius of curvature is 300 m or more, the apex of the truncated triangular heating pattern applied to the outside flange surface shall extend to the juncture of the flange and web. When the radius of curvature is less than 300 m, the apex of the truncated triangular heating pattern applied to the outside flange surface shall extend past the web for a distance equal to 1/8 of the flange width or 75 mm, whichever is less. The truncated triangular pattern shall have an included angle of approximately 15 to 30 degrees, but the base of the triangle shall not exceed 250 mm. Variations in the patterns prescribed above may be made with the approval of the Engineer.

For both types of heating, the flange edges to be heated are those that will be on the inside of the horizontal curve after cooling. Heating both inside and outside flange surfaces concurrently shall be performed when the flange thickness is 30 mm or greater.

The heat-curving operation shall be conducted in such a manner that the temperature of the steel does not exceed 590°C as measured by temperature indicating crayons or other suitable means. Methods of artificial cooling shall be subject to the approval of the Engineer.

The girder may be heat-curved with the web in either a vertical or a horizontal position. When curved with the web in the vertical position, the girder shall be braced or supported in such a manner that the tendency of the girder to deflect laterally during the heat-curving process will not cause the girder to overturn.

When curved with the web in the horizontal position, the girder shall be supported near its end and at intermediate points, if required, to obtain a uniform curvature. The bending stress in the flanges due to the mass of the girder shall not exceed the allowable design stress. When the girder is positioned horizontally for heating, intermediate safety catch blocks shall be maintained at the midlength of the girder within 50 mm of the flanges at all times during the heating process to guard against a sudden sag due to plastic flange buckling.

The girder shall be heat-curved prior to cleaning and painting. The heat-curving operation may be conducted either before or after all the required welding of transverse intermediate stiffeners is completed. However, unless provisions are made for girder shrinkage, connection plates and bearing stiffeners shall be located and attached after heat-curving. If longitudinal stiffeners are required, they shall be heat-curved or torch-cut separately and then welded to the curved girder.

Girders shall be cambered before heat-curving. Girder webs shall be cut to the prescribed camber with suitable allowance for shrinkage due to cutting, welding and heat-curving.

Horizontal curvature and vertical camber shall be measured for final acceptance after all welding and heating operations are completed and the flanges have cooled to a uniform temperature. Horizontal curvature shall be checked with the girder in the vertical position by measuring offsets from a string line or wire attached to both flanges or by using other suitable means.

In addition to the provisions in Section 55-3.16, "Assembly," of the Standard Specifications, curved girders shall be shop assembled in pairs in an upright position supported in a similar manner and at the same points that will be used during field erection. Sufficient lateral and sway bracing shall be connected to ensure stability of the girders before establishing the geometry of field connections.

MEASUREMENT AND PAYMENT

If a portion of or all check samples are removed at a mill more than 480 air line kilometers from both Sacramento and Los Angeles, shop inspection expenses will be sustained by the State which are in addition to expenses incurred for fabrication site inspection. Payment to the Contractor for furnishing structural steel will be reduced $2,000 for each mill located more than 480 air line kilometers from both Sacramento and Los Angeles.

Full compensation for detaching and reattaching existing restrainer brackets shall be considered as included in the contract price paid per kilogram for erect structural steel (bridge) and no separate payment will be made therefor.

10-1.65 ROADSIDE SIGNS

Roadside signs shall be installed at the locations shown on the plans or where designated by the Engineer and in conformance with the provisions in Section 56-2, "Roadside Signs," of the Standard Specifications and these special provisions.

Wood posts shall be pressure treated after fabrication in conformance with the provisions in Section 58, "Preservative Treatment of Lumber, Timber and Piling," of the Standard Specifications with creosote, creosote coal tar solution, creosote petroleum solution (50-50), pentachlorophenol in hydrocarbon solvent, copper naphthenate, ammoniacal copper arsenate, or ammoniacal copper zinc arsenate. In addition to the preservatives listed above, Southern yellow pine may also be pressure treated with chromated copper arsenate. When other than one of the creosote processes is used, blocks shall have a minimum retention of 6.4 kg/m^3, and need not be incised.

Type N marker panels mounted on a post with a roadside sign shall be considered to be sign panels and will not be paid for as markers.

All earthy material removed in connection with placing roadside signs shall be disposed of outside the highway right of way in conformance with the provisions as provided in "Hazardous and Non-Hazardous Material Excavation," elsewhere in these special provisions.

Full compensation for the disposal of earthy material outside the highway right of way in conformance with the provisions as provided in "Hazardous and Non-Hazardous Material Excavation," shall be considered as included in the contract unit price paid for roadside sign of the type shown in the Engineer's Estimate and no additional compensation will be allowed therefore.

10-1.66 INSTALL SIGN PANEL ON EXISTING FRAME

Sign panels shall be installed on existing frames at the locations shown on the plans or where designated by the Engineer and in conformance with the provisions in Section 56-1.06, "Sign Panels and Fastening Hardware," of the Standard Specifications and these special provisions.

The contract unit price paid for install sign panel on existing frame shall include full compensation for furnishing all labor, materials (except State-furnished sign panels and mounting bolts, but including removable sign frames), tools, equipment, and incidentals, and for doing all the work involved in installing sign panels on existing frames, complete in place (including repositioning existing sign panels and their removable sign frames, to accommodate new sign panels and their new removable sign frames), as shown on the plans, as specified in the Standard Specifications and these special provisions, and as directed by the Engineer.

10-1.67 CLEAN AND PAINT STRUCTURAL STEEL

Exposed new metal surfaces and connections to existing steel, except where galvanized, shall be cleaned and painted in conformance with the provisions in Section 59-2, "Painting Structural Steel," and Section 91, "Paint," of the Standard Specifications and these special provisions.

Where bridge deck drains are to be located over structural steel girders, the top and edges of the top flange under the drain and for 50 mm on each side of the drain shall be cleaned and painted, as specified in this section, before the drains are installed.

Whenever the Standard Specifications refer to "Steel Structures Painting Council," the reference shall be replaced with "SSPC: The Society for Protective Coatings."

Prior to performing any painting or paint removal, the Contractor shall submit to the Engineer, in conformance with the provisions in Section 5-1.02, "Plans and Working Drawings," of the Standard Specifications, 3 copies of a separate Painting Quality Work Plan (PQWP) for each item of work for which painting or paint removal is to be performed. As a minimum, each PQWP shall include the following:

A. The name of each Contractor or subcontractor to be used.
B. One copy each of all current "SSPC: The Society for Protective Coatings" specifications or qualification procedures which are applicable to the painting or paint removal to be performed. These documents shall become the permanent property of the Department.
C. Proposed methods and equipment to be used for any paint application.
D. Proof of each of any required certifications, SSPC-QP 1, SSPC-QP 2, SSPC-QP 3.
    1. In lieu of certification in conformance with the requirements in SSPC-QP 2 for this project, the Contractor may submit written documentation showing conformance with the requirements in Sections 4.2 through 4.6 of SSPC-QP 2.

The Engineer shall have 2 weeks to review the PQWP submittal after a complete plan has been received. No painting or paint removal shall be performed until the PQWP for that work is reviewed by the Engineer. Should the Engineer fail to complete the review within this time allowance and if, in the opinion of the Engineer, the Contractor's controlling operation is delayed or interfered with by reason of the delay in reviewing the PQWP, the delay will be considered a right of way delay in conformance with the provisions in Section 8-1.09, "Right of Way Delays," of the Standard Specifications.

The existing paint systems consist of materials listed in "Existing Highway Facilities" of these special provisions.

CLEANING

Exposed new metal surfaces and areas of connections to existing steel, except where galvanized, shall be dry blast cleaned and dry spot blast cleaned, respectively, in conformance with the requirements in Surface Preparation Specification No. 10, "Near White Blast Cleaning," of the "SSPC: The Society for Protective Coatings." Blast cleaning shall leave

surfaces with a dense, uniform, angular anchor pattern of no less than 40 µm nor more than 86 µm as measured in conformance with the requirements in ASTM Designation: D 4417.

The areas of connections to existing steel to be dry spot blast cleaned shall consist of, as a minimum: (1) new and existing contact surfaces and existing member surfaces under bolt heads, nuts or washers of high-strength bolted connections, (2) exposed bare surfaces of existing steel remaining after trimming, cutting, drilling or reaming, and (3) areas of existing steel within a 100-mm radius measured in any direction from the point of application of heat for welding or flame cutting.

Mineral and slag abrasives used for blast cleaning steel shall conform to the requirements in Abrasive Specification No. 1, "Mineral and Slag Abrasives," of the "SSPC: The Society for Protective Coatings" and shall not contain hazardous material. Mineral and slag abrasives shall comply with the requirements for Class A, Grade 2 to 3 as defined therein.

A Certificate of Compliance conforming to the provisions in Section 6-1.07, "Certificates of Compliance," of the Standard Specifications and a Material Safety Data Sheet shall be furnished prior to use for each shipment of blast cleaning material for existing steel.

PAINTING

Blast cleaned surfaces shall receive a single undercoat consisting of a waterborne inorganic zinc coating conforming to the requirements in AASHTO Designation M 300, Type II, except that: 1) the first 3 sentences of Section 4.7, "Primer Field Performance Requirements," and the entire Section 4.7.1 shall not apply, and 2) zinc dust shall be Type II in conformance with the requirements in ASTM Designation: D 520. The inorganic zinc coating shall be listed on the qualified products list which may be obtained from the Transportation Laboratory.

Inorganic zinc coating shall be used within 12 hours of initial mixing.

Application of inorganic zinc coating shall conform to provisions for applying zinc-rich coating in Section 59-2.13, "Application of Zinc-Rich Primer," of the Standard Specifications.

Inorganic zinc coating shall not be applied when the atmospheric or surface temperature is less than 7°C nor more than 29°C, nor when the relative humidity exceeds 85 percent.

The single undercoat of inorganic zinc coating shall be applied to the required dry film thickness in 2 or more applications within 4 hours after blast cleaning.

The total dry film thickness of all applications of the inorganic zinc undercoat, including the surfaces of outside existing members within the grip under bolt heads, nuts and washers, shall be not less than 100 µm nor more than 200 µm, except that the total dry film thickness on each faying (contact) surface of high strength bolted connections shall be between 25 µm and the maximum allowable dry film thickness for Class B coatings as determined by certified testing in conformance with Appendix A of the "Specification for Structural Joints Using ASTM A325 or A490 Bolts" of the Research Council on Structural Connections (RCSC Specification). Unless otherwise stated, all inorganic zinc coatings used on faying surfaces shall meet the slip coefficient requirements for a Class B coating on blast-cleaned steel, as specified in the RCSC Specification. The Contractor shall provide results of certified testing showing the maximum allowable dry film thickness for the Class B coating from the qualifying tests for the coating he has chosen, and shall maintain the coating thickness on actual faying surfaces of the structure at or below this maximum allowable coating thickness.

Areas where mudcracking occurs in the inorganic zinc coating shall be blast cleaned and repainted with inorganic zinc coating to the specified thickness.

Dry spray, or overspray, as defined in the Steel Structures Painting Manual, Volume 1, "Good Painting Practice," of the "SSPC: The Society for Protective Coatings," shall be removed prior to application of subsequent coats or final acceptance. Removal of dry spray shall be by screening or other methods that minimize polishing of the inorganic zinc surface. The dry film thickness of the coating after removal of dry spray shall be in conformance with the provisions for applying the single undercoat, as specified herein.

The inorganic zinc coating shall be tested for adhesion and cure. The locations of the tests will be determined by the Engineer. The sequence of the testing operations shall be determined by the Contractor. The testing for adhesion and cure will be performed no sooner than 72 hours after application of the single undercoat of inorganic zinc coating. At the Contractor's expense, satisfactory access shall be provided to allow the Engineer to determine the location of the tests and to test the inorganic zinc coating cure. The inorganic zinc coating shall pass the following tests:

Adhesion

The inorganic zinc coating shall have a minimum adhesion to steel of 4 MPa when measured at no more than 6 locations per span on each girder using a self-aligning adhesion tester in conformance with the requirements in ASTM Designation: D 4541. The Contractor, at the Contractor's expense, shall: (1) verify compliance with the adhesion requirements, (2) furnish test results to the Engineer, and (3) repair the coating after testing.

Cure

The inorganic zinc coating, when properly cured, shall exhibit a solid, hard, and polished metal surface when firmly scraped with the knurled edge of a quarter. Inorganic zinc coating that is powdery, soft, or does not exhibit a polished metal surface, as determined by the Engineer, shall be repaired by the Contractor, at the Contractor's expense, by blast cleaning and repainting with inorganic zinc coating to the specified thickness.

The surface pH of the inorganic zinc primer shall be checked in conformance with ASTM Designation: D4262 by wetting the surface with deionized water and applying pH paper with a capability of measuring in increments of 0.5 pH units. Application of finish coats will not be permitted until the surface pH is less than 8.

Except as approved by the Engineer, a minimum curing time of 72 hours shall be allowed between application of inorganic zinc coating and water rinsing.

Exposed areas of inorganic zinc coating shall be thoroughly water rinsed.

Exposed areas of inorganic zinc coating shall receive a minimum of 2 finish coats of a Caltrans Waterborne Formula PWB-165B (Coronado Blue) paint. The formulation is available from the Caltrans Transportation Laboratory.

The first finish coat shall be applied within 48 hours following the water rinsing.

The first finish coat shall be applied in 2 applications. The first application shall consist of a spray applied mist application. The second application shall be applied after the mist application has dried to a set to touch condition as determined by the procedure described in Section 7 of ASTM Designation: D1640. The first finish coat color shall match Caltrans color chip number PWB-110. The total dry film thickness of both applications of the first finish coat shall be not less than 50 µm.

Except as approved by the Engineer, a minimum drying time of 12 hours shall be allowed between finish coats.

The second finish coat color shall match Caltrans color chip number PWB-111. The total dry film thickness of all applications of the second finish coat shall be not less than 50 µm.

The 2 finish coats shall be applied in 3 or more applications to a total dry film thickness of not less than 100 µm nor more than 200 µm.

The total dry film thickness of all applications of inorganic zinc coating and finish coat paint shall be not less than 200 µm nor more than 350 µm.

MEASUREMENT AND PAYMENT

Dry spot blast cleaning and undercoat painting of blast cleaned areas of existing surfaces will be measured by the square meter of spot blast cleaned areas, and will be paid for as spot blast clean and paint undercoat.

The contract price paid per square meter for spot blast clean and paint undercoat shall include full compensation for furnishing all labor, materials, tools, equipment, and incidentals, and for doing all the work involved in dry spot blast cleaning and painting undercoat on the existing surfaces complete in place, as shown on the plans, as specified in the Standard Specifications and these special provisions, and as directed by the Engineer.

The contract lump sum price paid for clean and paint structural steel shall include full compensation for furnishing all labor, materials, tools, equipment, and incidentals, and for doing all the work involved in cleaning and painting the exposed surfaces of the new structural steel and finish coat on undercoated areas of existing metal, complete in place, including water rinsing, as shown on the plans, as specified in the Standard Specifications and these special provisions, and as directed by the Engineer.

10-1.68 ALTERNATIVE PIPE

Alternative pipe culverts shall conform to the provisions in Section 62, "Alternative Culverts," of the Standard Specifications and these special provisions.

The excavated material shall be disposed of outside the highway right of way in conformance with the provisions as provided in "Hazardous and Non-Hazardous Material Excavation," elsewhere in these special provisions.

Full compensation for imported material and the disposal of excavated material outside the highway right of way in conformance with the provisions as provided in "Hazardous and Non-Hazardous Material Excavation," shall be considered as included in the contract price paid per meter for 300 mm alternative pipe culvert and no additional compensation will be allowed therefore.

10-1.69 PLASTIC PIPE

Plastic pipe shall conform to the provisions in Section 64, "Plastic Pipe," of the Standard Specifications.

10-1.70 REINFORCED CONCRETE PIPE

Reinforced concrete pipe shall conform to the provisions in Section 65, "Reinforced Concrete Pipe," of the Standard Specifications and these special provisions.

Where embankment will not be placed over the top of the pipe, a relative compaction of not less than 85 percent shall be required below the pipe spring line for pipe installed using Method 1 backfill in trench, as shown on Standard Plan A62D. Where the pipe is to be placed under the traveled way, a relative compaction of not less than 90 percent shall be required unless the minimum distance between the top of the pipe and the pavement surface is the greater of 1.2 m or one half of the outside diameter of the pipe.

Except as otherwise designated by classification on the plans or in the specifications, joints for culvert and drainage pipes shall conform to the plans or specifications for standard joints.

When reinforced concrete pipe is installed in conformance with the details shown on Revised Standard Plan A62DA, the fifth paragraph of Section 19-3.04, "Water Control and Foundation Treatment," of the Standard Specifications shall not apply.

When solid rock or other unyielding material is encountered at the planned elevation of the bottom of the bedding, the material below the bottom of the bedding shall be removed to a depth of 1/50 of the height of the embankment over the top of the culvert, but not less than 150 mm nor more than 300 mm. The resulting trench below the bottom of the bedding shall be backfilled with structure backfill material in conformance with the provisions in Section 19-3.06, "Structure Backfill," of the Standard Specifications.

The excavation and backfill below the planned elevation of the bottom of the bedding will be paid for as extra work as provided in Section 4-1.03D, "Extra Work," of the Standard Specifications.

The Outer Bedding shown on Revised Standard Plan A62DA shall not be compacted prior to placement of the pipe.

10-1.71 PLASTIC PIPE

Plastic pipe for approach slab drain outlet as shown on the plans shall conform to the provisions in Section 68-3, "Edge Drains," of the Standard Specifications.

The excavated material shall be disposed of outside the highway right of way in conformance with the provisions as provided in "Hazardous and Non-Hazardous Material Excavation," elsewhere in these special provisions.

Full compensation for imported material and the disposal of excavated material outside the highway right of way in conformance with the provisions as provided in "Hazardous and Non-Hazardous Material Excavation," shall be considered as included in the contract price paid per meter for 80 mm plastic pipe (approach slab drain outlet) and no additional compensation will be allowed therefore.

10-1.72 WELDED STEEL PIPE

Welded steel pipe shall conform to the provisions in Section 70, "Miscellaneous Facilities," of the Standard Specifications and these special provisions.

Coating and wrapping will not be required.

The excavated material shall be disposed of outside the highway right of way in conformance with the provisions as provided in "Hazardous and Non-Hazardous Material Excavation," elsewhere in these special provisions.

Full compensation for imported material and the disposal of excavated material outside the highway right of way in conformance with the provisions as provided in "Hazardous and Non-Hazardous Material Excavation," shall be considered as included in the contract price paid per meter for welded steel pipe of the sizes shown in the Engineer's Estimate and no additional compensation will be allowed therefore.

10-1.73 MISCELLANEOUS CONCRETE CONSTRUCTION

Curbs, curb ramps, sidewalks and island paving shall conform to the provisions in Section 73, "Concrete Curbs and Sidewalks," of the Standard Specifications and these special provisions.

Curb ramp detectable warning surface shall conform to the details shown on the plans and shall not be constructed or installed on curb ramps with a slope that exceeds 6.67 percent. The finished surfaces of the detectable warning surface shall be free from blemishes.

Curb ramp detectable warning surface shall consist of raised truncated domes constructed or installed on curb ramps. Detectable warning surface, at the option of the Contractor, shall be either cast-in-place or stamped into the surface of the curb ramp, or shall be a prefabricated surface installed on the curb ramp. The color of the detectable warning surface shall be yellow conforming to Federal Standard No. 595B, Color No. 33538. Detectable warning surface, either cast-in-place or stamped into the surface of the curb ramp, shall be painted yellow in conformance with the provisions in Section 59-6, "Painting Concrete," of the Standard Specifications.

Prior to constructing curb ramps with a cast-in-place or stamped detectable warning surface, a test panel shall be constructed on the project site and shall be of a size not less than 600 mm by 600 mm. The test panel shall be constructed, finished and cured with the same materials, tools, equipment, and methods to be used in constructing the proposed permanent work. Additional test panels shall be constructed as necessary until a panel is produced which demonstrates, to the satisfaction of the Engineer, the ability of the selected procedure to produce a detectable warning surface that meets all of the specified requirements.

Full compensation for constructing or installing a curb ramp detectable warning surface shall be considered as included in the contract price paid per cubic meter for minor concrete (miscellaneous construction) and no separate payment will be made therefor.

10-1.74 MISCELLANEOUS IRON AND STEEL

Miscellaneous iron and steel shall conform to the provisions in Section 75, "Miscellaneous Metal," of the Standard Specifications.

10-1.75 MISCELLANEOUS METAL (BRIDGE)

Miscellaneous metal (bridge) shall conform to the provisions for miscellaneous bridge metal in Section 75, "Miscellaneous Metal," of the Standard Specifications and these special provisions.

Miscellaneous metal (bridge) shall consist of the miscellaneous bridge metal items listed in Section 75-1.03, "Miscellaneous Bridge Metal," of the Standard Specifications, and the following:

A. Expansion coupling for deck drains
B. Pipe hangers for deck drains
C. Column eyebolts

Self-tapping screws used for sleeve connections shall be hex-head stainless steel, installed in holes drilled to fit the self-tapping screws, conforming to the requirements of ASTM Designation: A 276, Type 304.

At the Contractor's option, fiberglass pipes and fittings with the same diameter and minimum bend radius as those shown on the plans, may be substituted for welded steel pipe in deck drain systems.

Fiberglass pipe and fittings shall conform to the requirements in ASTM Designation: D 2996, and shall have a minimum short-term rupture strength of 207 MPa. The adhesive type recommended by the manufacturer shall be used for joining pipe and fittings. Fiberglass pipe not enclosed in a box girder cell or encased in concrete shall be manufactured from ultraviolet-resistant resin pigmented with concrete-gray color, or be coated with a concrete-gray resin-rich exterior coating. Paint shall not be used. Fiberglass pipe treated with ultraviolet protection shall withstand a minimum of 2500 hours of accelerated weathering when tested in conformance with the requirements in ASTM Designation: G 154. Lamps shall be UV-B (313 nm wavelength). The resting cycle shall be 4 hours of ultraviolet (UV) exposure at 60°C, and then 4 hour of condensate exposure at 50°C. After testing, the surface of the pipe shall exhibit no fiber exposure, crazing, or checking, and only a slight chalking or color change.

Support spacing for fiberglass pipe shall be the same as shown on the plans for welded steel pipe. Pipe supports shall have a width of not less than 38 mm.

A Certificate of Compliance for fiberglass pipe and fittings shall be furnished to the Engineer in conformance with the provisions in Section 6-1.07, "Certificates of Compliance," of the Standard Specifications. The Certificate of Compliance shall include all laboratory test results conforming to the provisions specified herein.

Couplings used to connect fiberglass pipe to steel shall be threaded or flanged. The sleeve connections shown on the plans shall not be used for either PVC plastic pipe or fiberglass pipe.

If fiberglass pipe is substituted for welded steel pipe, the quantity of drainage piping will be computed on the basis of the dimensions and details shown on the plans, and no change in the quantities to be paid for will be made because of the use of fiberglass pipe.

10-1.76 CONCRETE BARRIER

Concrete barriers shall conform to the provisions in Section 83-2, "Barriers," of the Standard Specifications and these special provisions.

The provisions of the third paragraph in Section 83-2.02D(4), "Finishing," of the Standard Specifications shall not apply.

If reinforcement is encountered during drilling before the specified depth is attained, the Engineer shall be notified. Unless the Engineer approves coring through the reinforcement, the hole will be rejected and a new hole, in which reinforcement is not encountered, shall be drilled adjacent to the rejected hole to the depth shown on the plans.

Concrete barriers Type 736, 736A, 60A, 60C shall be colored concrete and shall conform to "Colored Concrete" of these special provisions.

Concrete barrier (Type 736A) will be measured and paid for as concrete barrier (Type 736).

10-1.77 CRASH CUSHION (ADIEM)

Crash cushion shall be furnished and installed as shown on the plans and in conformance with the provisions in the Standard Specifications and these special provisions.

Crash cushion shall be an ADIEM II-350 as manufactured by Trinity Industries, Inc., and shall include the items detailed for crash cushion shown on the plans.

The successful bidder can obtain the crash cushion from the manufacturer, Trinity Industries, Inc., P.O. Box 99, 950 West 400S, Centerville, Utah 84014, telephone 1-800-772-7976.

The price quoted by the manufacturer for ADIEM II-350, FOB Centerville, Utah is $11,500.00, not including sales tax.

The above price will be firm for orders placed on or before December 31, 2003, provided delivery is accepted within 90 days after the order is placed.

The Contractor shall furnish the Engineer one copy of the manufacturer's plan and parts list.

The Contractor shall provide the Engineer with a Certificate of Compliance from the manufacturer in conformance with the provisions in Section 6-1.07, "Certificates of Compliance," of the Standard Specifications. The Certificate of Compliance shall certify that the crash cushion conforms to the contract plans and specifications, conforms to the prequalified design and material requirements, and was manufactured in conformance with the approved quality control program.

Crash cushion shall be installed in conformance with the manufacturer's installation instructions.

Surplus excavated material remaining after the crash cushion has been installed shall be disposed of in a uniform manner along the adjacent roadway where designated by the Engineer.

Crash cushion (ADIEM) will be measured by the unit as determined from actual count in place in the completed work.

The contract unit price paid for crash cushion (ADIEM) shall include full compensation for furnishing all labor, materials (including anchor bolts, nuts, washers, and marker panels), tools, equipment, and incidentals, and for doing all the work involved in furnishing and installing the ADIEM type crash cushion, complete in place, including structure excavation, structure backfill, and disposing of surplus material, as shown on the plans, as specified in the Standard Specifications and these special provisions, and as directed by the Engineer.

10-1.78 CRASH CUSHION, SAND FILLED

Sand filled crash cushions shall be furnished and installed as shown on the plans and in conformance with these special provisions.

A sand filled crash cushion shall consist of a grouping of sand filled modules.

Crash cushions shall be installed at the following locations:

E 8+00.

At the Contractor's option, modules for use in sand filled crash cushions shall be either Energite III Inertial Modules, Fitch Inertial Modules or TrafFix Sand Barrels manufactured after March 31, 1997, or equal:

A. Energite III and Fitch Inertial Modules, manufactured by Energy Absorption Systems, Inc., One East Wacker Drive, Chicago, IL 60601-2076. Telephone 1-312-467-6750, FAX 1-800-770-6755

   1. Distributor (North): Traffic Control Service, Inc., 8585 Thys Court, Sacramento, CA 95828. Telephone 1-800-884-8274, FAX 1-916-387-9734
   2. Distributor (South): Traffic Control Service, Inc., 1881 Betmor Lane, Anaheim, CA 92805. Telephone 1-800-222-8274, FAX 1-714-937-1070

B. TrafFix Sand Barrels, manufactured by TrafFix Devices, Inc., 220 Calle Pintoresco, San Clemente, CA 92672. Telephone 1-949 361-5663, FAX 1-949 361-9205

   1. Distributor (North): United Rentals, Inc., 1533 Berger Drive, San Jose, CA 95112. Telephone 1-408 287-4303, FAX 1-408 287-1929
   2. Distributor (North): Statewide Safety & Sign, Inc., P.O. Box 1440, Pismo Beach, CA 93448. Telephone 1-800-559-7080, FAX 1-805 929-5786

Modules contained in the crash cushion shall be of the same type at each location. The color of the modules shall be the standard yellow color as furnished by the vendor, with black lids. The exterior components of the modules shall be formulated or processed to resist deterioration from ambient ultraviolet rays. The modules shall exhibit good workmanship free from structural flaws and objectionable surface defects.

The Contractor shall provide the Engineer with a Certificate of Compliance from the manufacturer in conformance with the provisions in Section 6-1.07, "Certificates of Compliance," of the Standard Specifications. The Certificate of Compliance shall certify that the crash cushions comply with the contract plans and specifications, conform to the prequalified design and material requirements, and were manufactured in conformance with the approved quality control program.

Sand for filling the modules shall be clean washed concrete sand of commercial quality. At the time of placing in the modules, the sand shall contain not more than 7 percent water, as determined by California Test 226.

Modules placed on bridge decks shall be provided with positioning blocks fastened to the deck surface. Positioning blocks shall be shaped as segments of a ring and placed along the inner or outer periphery of the module wall. A minimum of 2 blocks, a minimum of one-sixth of a ring in length shall be provided for each module. Positioning blocks and fasteners shall be of a material that is corrosion and water resistant.

Module cylinders shall be filled with sand in conformance with the manufacturer's directions and to the sand capacity in kilograms for each module shown on the plans.

Lids shall be securely attached as recommended by the manufacturer.

A Type R or Type P marker panel shall be attached to the front of the crash cushion as shown on the plans, when the closest point of the crash cushion array is within 3.6 m of the traveled way. The marker panel, when required, shall be firmly fastened to the crash cushion with commercial quality hardware or by other methods approved by the Engineer.

Sand filled crash cushions, regardless of the number of modules required in each sand filled crash cushion, will be measured and paid for by the unit as crash cushion, sand filled. The quantity to be paid for will be determined from actual count of the units in place in the completed work.

The contract unit price paid for crash cushion, sand filled shall include full compensation for furnishing all labor, materials (including sand and marker panels), tools, equipment, and incidentals, and for doing all the work involved in furnishing and installing crash cushions, complete in place, as shown on the plans, as specified in the Standard Specifications and these special provisions, and as directed by the Engineer.

10-1.79 THERMOPLASTIC TRAFFIC STRIPE AND PAVEMENT MARKING

Thermoplastic traffic stripes (traffic lines) and pavement markings shall be applied in conformance with the provisions in Section 84, "Traffic Stripes and Pavement Markings," of the Standard Specifications and these special provisions.

Thermoplastic material shall be free of lead and chromium, and shall conform to the requirements in State Specification PTH-02ALKYD.

Retroreflectivity of the thermoplastic traffic stripes and pavement markings shall conform to the requirements in ASTM Designation: D 6359-99. White thermoplastic traffic stripes and pavement markings shall have a minimum initial retroreflectivity of 250 $mcd \cdot m^{-2} \cdot lx^{-1}$. Yellow thermoplastic traffic stripes and pavement markings shall have a minimum initial retroreflectivity of 150 $mcd \cdot m^{-2} \cdot lx^{-1}$.

Where striping joins existing striping, as shown on the plans, the Contractor shall begin and end the transition from the existing striping pattern into or from the new striping pattern a sufficient distance to ensure continuity of the striping pattern.

Thermoplastic traffic stripes shall be applied at the minimum thickness and application rate as specified below. The minimum application rate is based on a solid stripe of 100 mm in width.

Minimum StripeThickness (mm)	Minimum Application Rate (kg/m)
2.0	0.4

Thermoplastic traffic stripes and pavement markings shall be free of runs, bubbles, craters, drag marks, stretch marks, and debris.

At the option of the Contractor, permanent traffic striping and pavement marking tape conforming to the provisions in "Prequalified and Tested Signing and Delineation Materials" of these special provisions may be placed instead of the thermoplastic traffic stripes and pavement markings specified herein. Permanent tape, if used, shall be installed in conformance with the manufacturer's specifications.

If permanent tape is placed instead of thermoplastic traffic stripes and pavement markings, the tape will be measured and paid for by the meter as thermoplastic traffic stripe and by the square meter as thermoplastic pavement marking.

10-1.80 PAINT TRAFFIC STRIPE AND PAVEMENT MARKING

Painted traffic stripes (traffic lines) and pavement markings shall be applied in conformance with the provisions in Section 84, "Traffic Stripes and Pavement Markings," of the Standard Specifications and these special provisions.

Traffic stripe and pavement marking paint shall conform to the requirements in State Specification No. PTWB-01.

The color of the painted traffic stripes and pavement markings shall conform to the requirements in ASTM Designation: D 6628-01.

Retroreflectivity of the paint traffic stripes and pavement markings shall conform to the requirements in ASTM Designation: D 6359-99. White painted traffic stripes and pavement markings shall have a minimum initial retroreflectivity of 250 $mcd \cdot m^{-2} \cdot lx^{-1}$. Yellow painted traffic stripes and pavement markings shall have a minimum initial retroreflectivity of 150 $mcd \cdot m^{-2} \cdot lx^{-1}$.

At the option of the Contractor, permanent traffic striping and pavement marking tape conforming to the provisions in "Prequalified and Tested Signing and Delineation Materials" of these special provisions may be placed instead of painted traffic stripes and pavement markings. Permanent tape, if used, shall be placed in conformance with the manufacturer's specifications.

If permanent tape is placed instead of painted traffic stripes and pavement markings, the tape will be measured and paid for by the meter as paint traffic stripe and by the square meter as paint pavement marking of the number of coats designated in the Engineer's Estimate.

10-1.81 PAVEMENT MARKERS

Pavement markers shall be placed in conformance with the provisions in Section 85, "Pavement Markers," of the Standard Specifications and these special provisions.

Attention is directed to "Traffic Control System For Lane Closure" of these special provisions regarding the use of moving lane closures during placement of pavement markers with bituminous adhesive.

The Contractor shall furnish the Engineer certificates of compliance for the pavement markers in conformance with the provisions in Section 6-1.07, "Certificates of Compliance," of the Standard Specifications.

Retroreflective pavement markers shall be marked as abrasion resistant on the body of the markers.

SECTION 10-2. HIGHWAY PLANTING AND IRRIGATION SYSTEMS

10-2.01 GENERAL

The work performed in connection with highway planting and irrigation systems shall conform to the provisions in Section 20, "Erosion Control and Highway Planting," of the Standard Specifications and these special provisions.

All earthly material removed in connection with highway planting and irrigation systems shall be disposed of outside the highway right of way in conformance with the provisions as provided in "Hazardous and Non-Hazardous Material Excavation," elsewhere in these special provisions.

When fluctuations of water pressure and water supply are encountered during normal working hours, plants shall be watered at other times, as often, and in sufficient amounts as conditions may require to keep the soil and plant roots moist during the life of the contract.

Full compensation for watering plants outside normal working hours shall be considered as included in the contract lump sum prices paid for highway planting and plant establishment work and no additional compensation will be allowed therefor.

PROGRESS INSPECTIONS

Progress inspections will be performed by the Engineer for completed highway planting and irrigation system work at designated stages during the life of the contract.

Progress inspections will not relieve the Contractor of responsibility for installation in conformance with the special provisions, plans and Standard Specifications. Work within an area shall not progress beyond each stage until the inspection has been completed, corrective work has been performed, and the work is approved, unless otherwise permitted by the Engineer.

The requirements for progress inspections will not preclude additional inspections of work by the Engineer at other times during the life of the contract.

The Contractor shall notify the Engineer, in writing, at least 4 working days prior to completion of the work for each stage of an area and shall allow a minimum of 3 working days for the inspection.

Progress inspections will be performed at the following stages of work:

A. During pressure testing of the pipelines on the supply side of control valves.
B. During testing of low voltage conductors.
C. Before planting begins and after completion of the work specified for planting in Section 20-4.03, "Preparing Planting Areas," of the Standard Specifications.
D. Before plant establishment work begins and after completion of the work specified for planting in Section 20-4.05, "Planting," of the Standard Specifications.
E. At intervals of one month during the plant establishment period.

Full compensation for imported material and the disposal outside the highway right of way of all earthly material removed in connection with highway planting and irrigation systems work shall be considered as included in the contract lump sum prices paid for highway planting and irrigation systems and no additional compensation will be allowed therefore.

COST BREAK-DOWN

The Contractor shall furnish the Engineer a cost break-down for the contract lump sum items of highway planting and irrigation system. Cost break-down tables shall be submitted to the Engineer for approval within 15 working days after the contract has been approved. Cost break-down tables shall be approved, in writing, by the Engineer before any partial payment will be made for the applicable items of highway planting and irrigation system involved.

Attention is directed to "Time-Related Overhead" of these special provisions regarding compensation for time-related overhead.

Cost break-downs shall be completed and furnished in the format shown in the samples of the cost break-downs included in this section. Line item descriptions of work shown in the samples are the minimum to be submitted. Additional line item descriptions of work may be designated by the Contractor. If the Contractor elects to designate additional line item descriptions of work, the quantity, value and amount for those line items shall be completed in the same manner as for the unit descriptions shown in the samples. The line items and quantities given in the samples are to show the manner of preparing the cost break-downs to be furnished by the Contractor.

The Contractor shall determine the quantities required to complete the work shown on the plans. The quantities and their values shall be included in the cost break-downs submitted to the Engineer for approval. The Contractor shall be responsible for the accuracy of the quantities and values used in the cost break-downs submitted for approval.

The sum of the amounts for the line items of work listed in each cost break-down table for highway planting and for irrigation system work shall be equal to the contract lump sum price bid for Highway Planting and Irrigation System, respectively. Overhead and profit, except for time-related overhead, shall be included in each individual line item of work listed in a cost break-down table.

No adjustment in compensation will be made in the contract lump sum prices paid for highway planting and irrigation system due to differences between the quantities shown in the cost break-downs furnished by the Contractor and the quantities required to complete the work as shown on the plans and as specified in these special provisions.

Individual line item values in the approved cost break-down tables will be used to determine partial payments during the progress of the work and as the basis for calculating an adjustment in compensation for the contract lump sum items of highway planting and irrigation system due to changes in line items of work ordered by the Engineer. When the total of ordered changes to line items of work increases or decreases the lump sum price bid for either Highway Planting or Irrigation System by more than 25 percent, the adjustment in compensation for the applicable lump sum item will be determined in the same manner specified for increases and decreases in the total pay quantity of an item of work in Section 4-1.03B, "Increased or Decreased Quantities," of the Standard Specifications.

HIGHWAY PLANTING COST BREAK-DOWN

Contract No. 04-291004

UNIT DESCRIPTION	UNIT	APPROXIMATE QUANTITY	VALUE	AMOUNT
PREPARE HOLE (SOIL AMENDMENT)	EA	285		
ROADSIDE CLEARING	LS	LUMP SUM		
PLANT (GROUP A)	EA	52		
PLANT (GROUP B)	EA	193		
PLANT (GROUP F)	EA	5,487		
PLANT (GROUP U)	EA	38		
PLANT (GROUP K)	EA	2		
PLANT (GROUP Z)	EA	3		
MULCH	M3	68		
COMMERCIAL FERTILIZER	KG	50		
COMMERCIAL FERTILIZER (PACKET)	EA	109		

IRRIGATION SYSTEM COST BREAK-DOWN

Contract No. 04-291004

UNIT DESCRIPTION	UNIT	APPROXIMATE QUANTITY	VALUE	AMOUNT
40 mm ELECTRIC REMOTE CONTROL VALVES	EA	5		
12 STATION IRRIGATION CONTROLLER	EA	1		
50 mm GALVANIZED STEEL PIPE (SUPPLY LINE)	M	12		
20 mm PVC PLASTIC PIPE (PR 200) (SUPPLY LINE)	M	583		
25 mm PVC PLASTIC PIPE (PR 200) (SUPPLY LINE)	M	75		
32 mm PVC PLASTIC PIPE (PR 200) (SUPPLY LINE)	M	72		
40 mm PVC PLASTIC PIPE (PR 200) (SUPPLY LINE)	M	36		
50 mm PVC PLASTIC PIPE (PR 200) (SUPPLY LINE)	M	920		
SPRINKLER (TYPEA-6)	EA	1		
SPRINKLER (TYPE A-7)	EA	49		
SPRINKLER (TYPE A-8)	EA	8		
SPRINKLER (TYPE C-2)	EA	109		
40 mm GATE VALVE	EA	2		
40 mm WYE STRAINER	EA	2		
20 mm QUICK COUPLING VALVE	EA	1		
75 mm PVC PLASTIC PIPE (PR 315) IRRIGATION CONDUIT	M	140		
CONTROL AND NEUTRAL CONDUCTORS	LS	LUMP SUM		
IRRIGATION SYSTEMS FUNCTIONAL TEST	LS	LUMP SUM		
50 mm BACKFLOW PREVENTER ASSEMBLY	EA	2		
BACKFLOW PREVENTER ASSEMBLY ENCLOSURE	EA	2		
TESTING BACKFLOW PREVENTERS	LS	LUMP SUM		

10-2.02 (BLANK)

10-2.03 (BLANK)

10-2.04 HIGHWAY PLANTING

The work performed in connection with highway planting shall conform to the provisions in Section 20-4, "Highway Planting," of the Standard Specifications and these special provisions.

HIGHWAY PLANTING MATERIALS

Mulch

Mulch shall be wood chips.

Commercial Fertilizer (Slow Release)

Commercial fertilizer (slow release) shall be a pelleted or granular form, shall be slow or controlled release with a nutrient release over an 8- to 12-month period, and shall fall within the following guaranteed chemical analysis range:

Ingredient	Percentage
Nitrogen	14-21
Phosphoric Acid	5-8
Water Soluble Potash	4-15

Commercial Fertilizer (Packets)

Commercial fertilizer (packet) shall be slow or controlled release and shall be in a biodegradable packet form. The packet shall gradually release nutrients over a 12-month period. Each packet shall have a mass of 10 g ± 1 g and shall have the following guaranteed chemical analysis:

Ingredient	Percentage
Nitrogen	20
Phosphoric Acid	10
Water Soluble Potash	5

ROADSIDE CLEARING

Prior to preparing planting areas, or commencing irrigation trenching operations for planting areas, trash and debris shall be removed from these areas and a distance of 3 m beyond the edges of those areas. At locations where proposed planting areas are 3.6 m or more from the edges of dikes, curbs, sidewalks, fences, walls, paved shoulders and existing planting to remain or to be maintained, the clearing limit shall be 2 m beyond the outer limits of the proposed planting area.

In addition to removing trash and debris, the project area shall be cleared as specified herein:

A. Weeds shall be killed and removed within proposed mulch areas and within the area extending beyond the outer limits of the proposed mulch areas to the adjacent edges of shoulders, dikes, curbs, sidewalks, walls, existing planting and fences. At those locations where proposed mulch areas are 3.6 m or more from the adjacent edges of shoulders, dikes, curbs, sidewalks, walls, and fences, the clearing limit shall be 2 m beyond the outer limits of the proposed mulch areas.

After the initial roadside clearing is complete, additional roadside clearing work shall be performed as necessary to maintain the areas, as specified above, in a neat appearance until the start of the plant establishment period. This work shall include the following:

A. Trash and debris shall be removed.
B. Rodents shall be controlled.
C. Weed growth shall be killed before the weeds reach the seed stage of growth or exceed 150 mm in length.
D. Weeds in plant basins, including basin walls, shall be removed by hand pulling, after the plants have been planted.

Weed Control

Weed control shall also conform to the following:

A. Stolon type weeds shall be killed with glyphosate.

Roadside clearing work shall not include work required to be performed as clearing and grubbing as specified in Section 16, "Clearing and Grubbing," of the Standard Specifications.

PESTICIDES

Pesticides used to control weeds shall conform to the provisions in Section 20-4.026, "Pesticides," of the Standard Specifications. Except as otherwise provided in these special provisions, pesticide use shall be limited to the following materials:

Cacodylic Acid
Diquat
Fluazifop-butyl
Glyphosate
Sethoxydim
Ammonium Sulfate
Magnesium Chloride

Glyphosate shall be used to kill stolon type weeds.

Ammonium sulfate and magnesium chloride shall be used only in areas planted to Carpobrotus or Delosperma. Ammonium sulfate and magnesium chloride shall not be applied in a manner that allows the pesticides to come in contact with trees or shrubs.

If the Contractor elects to request the use of other pesticides on this project, the request shall be submitted, in writing, to the Engineer not less than 15 days prior to the intended use of the other pesticides. Except for the pesticides listed in these special provisions, no pesticides shall be used or applied without prior written approval of the Engineer.

Pesticides shall not be applied within the limits of the plant basins. Pesticides shall not be applied in a manner that allows the pesticides to come in contact with the foliage and woody parts of the plants.

PREPARING PLANTING AREAS

Plants adjacent to drainage ditches shall be located so that after construction of the basins, no portion of the basin walls shall be less than the minimum distance shown on the plans for each plant involved.

PREPARE HOLES

Holes for plants shall be excavated to the minimum dimensions shown on the plans.

Backfill material for plant holes shall be a mixture of soil and other materials shown on the Plant List. Backfill material shall be thoroughly mixed and uniformly distributed throughout the entire depth of the plant hole without clods and lumps.

PLANTING

Commercial fertilizer shall be applied or placed at the time of planting and at the rates shown on the plans.

Mulch placed in areas outside of plant basins shall be spread to a uniform depth of 50 mm.

Mulch shall not be placed within one meter of the center line of earthen drainage ditches, within one meter of the edge of paved ditches, and within one meter of the center line of drainage flow lines.

Attention is directed to "Irrigation Systems Functional Test" of these special provisions regarding functional tests of the irrigation systems. Planting shall not be performed in an area until the functional test has been completed for the irrigation system serving that area.

Commercial fertilizer packets shall be placed next to the plant to within 150 to 200 mm of the soil surface and approximately 22 mm from the roots.

PALM TREE PLANTING

MATERIALS

Palms Trees

Palm trees shall be of the species and height shown on the plans. The Contractor shall provide a Certificate of Compliance from the Nursery indicating approval of palm trees.

Fungicide

Fungicide shall be "Cleary's 3336" or approved equal.

Subsurface Drains

Subsurface drains shall consist of aeration and monitoring drain pipe, filter fabric, and gravel. A gravel-filled drain pipe shall be provided in the planting hole as shown on the plans. Aeration and monitoring drain pipe shall be 100 mm diameter, Schedule 40, polyvinyl chloride (PVC) perforated plastic pipe. Filter fabric shall conform to "subsurface drains" of the Standard Provisions, Section 68-1.028, "Filter Fabric." Gravel shall be 19 mm aggregate base rock conforming to "Subsurface Drains" of the Standard Provisions, Section 68-1.025, "Permeable Material", Class 2.

Backfill Material

Backfill material for the planting holes shall be 100% pure plaster sand.

Foliar Water Retention Polymer

Foliar water retention polymer shall be of a type manufactured specifically for the purpose of preventing desiccation in living plants.

Decomposed Granite

Decomposed granite shall be "Fenton Gold," 10 mm fines, or approved equal.

PLANTING

Rooted palm trees shall be planted between April 1 and October 31 during daylight hours with temperatures ranging from 18 degrees C to 29 degrees C, or as directed by Engineer. Do not plant palm trees when wind velocity exceeds 108 kilometers per hour. Notify the Engineer 72 hours prior to the beginning of palm tree planting operations.

Prior to delivery of palm trees to project site, skin trunk and spray entire terminal shoot with fungicide in accordance with manufacturer's instructions.

Apply a drenching of 57 liters of diluted fungicide to each root ball in 3 separate applications:

A. Immediately after planting.
B. Six weeks after planting.
C. As directed by the Engineer.

After each fungicide application, spray palm trees with foliar water retention polymer in accordance with manufacturer's instructions.

Planting holes and palm tree fronds shall be saturated with clean water immediately prior to planting.

Prior to the planting of palm trees in the planting holes, install subsurface drains, cap with removable slotted cap, and wrap drain pipe with filter fabric.

Backfill with plaster sand and jet backfill to eliminate all voids around root ball.

Install filter fabric below decomposed granite and spread to a uniform depth of 75 mm as shown on the plans.

If work is not completed by end of day, securely cover all open pits with plywood of minimum thickness to bear pedestrian traffic.

Immediately after planting palm trees, remove all loose and damaged growth, including broken and severed fronds, and fruiting stems. When removing loose and damaged growth, consideration shall be made for radial symmetry and smoothness of trunk and shall be completed as directed by the Engineer.

Full compensation for fungicide, subsurface drains, backfill material, foliar water retention polymer, filter fabric, and decomposed granite, shall be considered as included in the contract lump sum price paid for highway planting and no additional compensation will be allowed therefor.

STREET TREE PLANTING

MATERIALS

Street Trees

Street trees, plant (Group K), shall be of species and size shown on the plans. The Contractor shall provide a Certification of Compliance from the Nursery indicating approval of street trees.

Subsurface Drains

Subsurface drains shall conform to the provisions of “Palm Tree Planting,” of these special provisions.

Decomposed Granite

Decomposed granite shall be "Fenton Gold," 10 mm fines, or approved equal.

Plant Stakes

Plant stakes shall be "The Reddy Stake System" or approved equal.

PLANTING

Do not plant street trees when wind velocity exceeds 108 kilometers per hour. Notify the Engineer 72 hours prior to the planting of street trees.

Prior to the planting of street trees in planting holes, install subsurface drains, cap with removable slotted cap, and wrap drain pipe with filter fabric.

Planting holes tree foliage and trunk shall be saturated with clean water immediately prior to planting.

Install filter fabric below decomposed granite and spread decomposed granite to a uniform depth of 50 mm as shown on the plans.

Plant stakes shall be installed as shown on the plans.

Full compensation for subsurface drains, filter fabric, decomposed granite, and plant stakes shall be considered as included in the contract lump sum price paid for highway planting and no additional compensation will be allowed therefor.

PLANT ESTABLISHMENT WORK

The plant establishment period shall be Type 2 and shall not be less than 250 working days.

Attention is directed to "Relief From Maintenance and Responsibility" in these special provisions regarding relief from maintenance and protection.

Commercial fertilizer (slow release) shall be applied to trees, shrubs, vines, and ground covers 15 days prior to the completion of the plant establishment period. In addition to the commercial fertilizer application required before the completion of the plant establishment period, commercial fertilizer (slow release) shall be applied to the palm trees at a 3 month interval during the plant establishment period. Commercial fertilizer shall be applied at the rates shown on the plans and shall be spread with a mechanical spreader wherever possible.

The center to center spacing of replacement plants for unsuitable ground cover plants shall be determined by the number of completed plant establishment working days at the time of replacement and the original spacing in conformance with the following:

ORIGINAL SPACING (Millimeters)	SPACING OF REPLACEMENT GROUND COVER PLANTS (Millimeters)		
	Number of Completed Plant Establishment Working Days		
	1-125	126-190	191-End of Plant Establishment
500	500	350	300

Weeds within plant basins, including basin walls and ground cover, shall be controlled by hand pulling.

Weeds within mulched areas and outside of plant basins shall be controlled by killing.

Weeds within median areas, pavement, curbs, sidewalk, and other surfaced areas shall be controlled by killing.

Vines shall be trained onto fences and walls.

At the option of the Contractor, plants of a larger container size than those originally specified may be used for replacement plants during the first 125 working days of the plant establishment period. The use of plants of a larger container size than those originally specified for replacement plants shall be at the Contractor's expense.

After 125 working days of the plant establishment period have been completed, replacement of plants, except for ground cover plants, shall be No. 1 size for seedlings, pot and liner size plants; No. 5 size for No. 1 size plants; No. 15 size for No. 5 size plants; and other plant replacement plants shall be the same size as originally specified.

Wye strainers shall be cleaned at least 15 days prior to the completion of the plant establishment period.

The final inspection shall be performed in conformance with the provisions in Section 5-1.13, "Final Inspection," of the Standard Specifications and shall be completed a minimum of 20 working days before the estimated completion of the contract.

10-2.05 IRRIGATION SYSTEMS

Irrigation systems shall be furnished and installed in conformance with the provisions in Section 20-5, "Irrigation Systems," of the Standard Specifications, except materials containing asbestos fibers shall not be used.

Attention is directed to the provisions in "Obstructions" of these special provisions, regarding work over or adjacent to existing underground facilities. Excavation for proposed irrigation facilities shall not be started until the existing underground facilities have been located.

VALVE BOXES

Valve boxes shall conform to the provisions in Section 20-2.24, "Valve Boxes," of the Standard Specifications, except as otherwise provided herein.

Valve boxes shall be precast portland cement concrete.

Covers for concrete valve boxes shall be glass fiber reinforced plastic, plastic.

Valve boxes shall be identified on the top surface of the covers by branding the appropriate abbreviations for the irrigation facilities contained in the valve boxes as shown on the plans. Valve boxes that contain remote control valves shall be identified by the appropriate letters and numbers (controller and station numbers). The letters and numbers shall be 50 mm in height.

ELECTRIC AUTOMATIC IRRIGATION COMPONENTS

Irrigation Controllers

Irrigation controllers shall be single, solid-state independent controllers conforming to the following:

A. Irrigation controllers shall be fully automatic and shall operate a complete 14-day or longer irrigation program.
B. A switch or switches shall be provided on the face of the control panel that will turn the irrigation controller "on" or "off" and provide for automatic or manual operation. Manual operation shall allow cycle start at the desired station and shall allow activation of a single station.
C. The watering time of each station shall be displayed on the face of the control panel.
D. The irrigation controller and the low voltage output source shall be protected by fuses or circuit breakers.
E. The irrigation controller mechanism, panel and circuit board shall be connected to the low voltage control and neutral conductors by means of plug and receptacle connectors located in the irrigation controller enclosure.
F. Each station shall have a variable or incremental timing adjustment with a range of 0-120 minutes to a minimum of one minute.
G. Irrigation controllers shall be capable of a minimum of 2 program schedules.
H. Irrigation controllers shall have an output that can energize a pump start circuit or a remote control valve (master).
I. Irrigation controllers shall be manufactured by the same company.
J. Where direct burial conductors are to be connected to the terminals strip, the conductors shall be connected with the proper size open-end crimp-on wire terminals. No exposed wire shall extend beyond the crimp of the terminal and the wires shall be parallel on the terminal strip.

Attention is directed to the provisions in Section 10-3, "Signals, Lighting and Electrical Systems," of these special provisions, regarding electrical power for irrigation controllers and irrigation controller enclosure cabinets.

Electric Remote Control Valves

Electric remote control valves shall conform to the provisions in Section 20-2.23, "Control Valves," of the Standard Specifications and the following:

A. Valves shall be brass or cast iron construction.
B. Valves shall be angle pattern (bottom inlet) or straight pattern (side inlet) as shown on the plans.

Pull Boxes

Pull box installations shall conform to the provisions in Section 20-5.027I, "Conductors, Electrical Conduits and Pull Boxes," of the Standard Specifications.

Conductors

Low voltage, as used in this section "Conductors," shall mean 36 V or less.

Low voltage control and neutral conductors in pull boxes and valve boxes, at irrigation controller terminals, and at splices shall be marked as follows:

A. Conductor terminations and splices shall be marked with adhesive backed paper markers or adhesive cloth wrap-around markers, with clear, heat-shrinkable sleeves sealed over the markers.
B. Non-spliced conductors in pull boxes and valve boxes shall be marked with clip-on, "C" shaped, white extruded polyvinyl chloride sleeves. Marker sleeves shall have black, indented legends of uniform depth with transparent overlays over the legends and "chevron" cuts for alignment of 2 or more sleeves.

Markers for the control conductors shall be identified with the appropriate number or letter designations of irrigation controllers and station numbers. Markers for neutral conductors shall be identified with the appropriate number or letter designations of the irrigation controllers.

The color of low voltage neutral and control conductor insulation, except for the striped portions, shall be homogeneous throughout the entire thickness of the insulation.

Insulation for conductors may be UL listed polyethylene conforming to UL44 test standards with a minimum insulation thickness of 1.05 mm for wire sizes 10AWG and smaller.

At the option of the Contractor, other types of splice sealing materials and methods may be used provided other materials and methods have been approved in writing by the Engineer prior to installation of the connectors.

ARMOR-CLAD CONDUCTORS

Armor-clad conductors shall be used in direct burial applications from pull boxes adjacent to irrigation controller to remote control valves and other irrigation facilities in conformance with the details shown on the plans and these special provisions.

Armor-clad conductors shall conform to the following:

A. Conductors shall be the proper size for the application, and shall be solid, uncoated copper with a conductor size not less than 90 percent of the AWG diameter required.
B. At the Contractor's option, conductor insulation coverings shall be either of the following:

    1. Polyvinyl chloride (PVC) conforming to UL style, Type UF 60°C, 600 V. Average thickness of insulation shall be not less than 1.52 mm, with a minimum thickness of 1.37 mm, or
    2. UL listed polyethylene conforming to UL44 test standards with a minimum insulation thickness of 1.05 mm for wire sizes 10AWG and smaller.

C. Armor shall be a minimum 0.13-mm thick by 12.7 mm wide Type 304 stainless steel tape that is helically wrapped over each conductor with a 33 percent minimum overlap.
D. Outer jacket for conductors shall be sunlight resistant PVC and shall conform to the Insulated Power Cable Engineer's Association (ICEA) S-61-402, NEMA Standard WC5, and UL Listing 1263. Nominal thickness of the outer jacket shall be 0.76-mm with a minimum thickness of 0.61-mm.

At the option of the Contractor, conductors conforming to the provisions in Section 20-2.31D, "Conductors," of the Standard Specifications may be used when the conductors are installed in an electrical conduit.

IRRIGATION SYSTEMS FUNCTIONAL TEST

Functional tests for the irrigation controllers and associated automatic irrigation systems shall conform to the provisions in Section 20-5.027J, "Testing," of the Standard Specifications and these special provisions.

Tests shall demonstrate to the Engineer, through one complete cycle of the irrigation controllers in the automatic mode, that the associated automatic components of the irrigation systems operate properly. If automatic components of the

irrigation systems fail a functional test, these components shall be repaired at the Contractor's expense and the testing repeated until satisfactory operation is obtained.

Associated automatic components shall include, but not be limited to, remote control valves.

Upon completion of work on an irrigation system, including correction of deficiencies and satisfactory functional tests for the systems involved, the plants to be planted in the area watered by the irrigation system may be planted provided the planting areas have been prepared as specified in these special provisions.

PIPE

Steel Pipe

Galvanized steel pipe supply lines installed between water meters and backflow preventer assemblies shall be installed not less than 300 mm below finished grade, measured to the top of the pipe.

Plastic Pipe

Plastic pipe supply lines shall be polyvinyl chloride (PVC) 1120 or 1220 pressure rated pipe with the minimum pressure rating of (PR 200).

Plastic pipe supply lines less than 100 mm in diameter shall have solvent cemented type joints. Primers shall be used on the solvent cemented type joints.

A nonhardening joint compound shall be used in place of the pipe thread sealant tape conforming to the provisions in Section 20-5.03E, "Pipe," of the Standard Specifications. Joint compounds shall be applied in conformance with the manufacturer's recommendations.

Fittings for plastic pipe supply lines with a pressure rating (PR) of 315 shall be Schedule 80.

IRRIGATION CONDUIT

Irrigation conduit shall be polyvinyl chloride (PVC) plastic pipe, (PR 315), and shall conform to Section 20-2.15B(1), "Plastic Pipe Supply Line," of the Standard Specifications and these special provisions.

Irrigation conduit shall be installed where shown on the plans.

Irrigation conduit shall be installed a minimum of 450 mm below finished grade and shall extend 300 mm beyond all paving. The ends of the conduit shall be capped.

WATER METER

Water meters for the irrigation systems will be furnished and installed by the serving utility at the locations shown on the plans.

The Contractor shall make the arrangements and pay the costs and fees required by the serving utility.

The San Francisco Water District has established a fee of $35,000 for furnishing and installing a water meter. If, at the time of installation, this fee has been changed, the State will take a credit for the reduction in the fee, or the State will pay the difference for the increase in the fee. The credit or payment will be taken or paid on the first monthly progress payment made after the meter is installed. The Contractor shall furnish the Engineer with a copy of the invoice for the installation fee.

Attention is directed to Section 20-4.06, "Watering," of the Standard Specifications. The Contractor shall make the arrangements for furnishing and applying water until the water meters have been installed by the serving utility.

The quantity of water meters will be measured by the unit as determined from actual count in place.

The contract unit price paid for water meter shall include full compensation for furnishing all labor, materials, tools, equipment, and incidentals, and for doing all the work involved in furnishing and installing water meters, complete in place, as shown on the plans, as specified in the Standard Specifications and these special provisions, and as directed by the Engineer.

BACKFLOW PREVENTER ASSEMBLIES

Backflow preventers shall conform to the provisions in Section 20-2.25, "Backflow Preventers," of the Standard Specifications and these special provisions.

Pressure loss through the backflow preventers shall not exceed the following:

BACKFLOW PREVENTER SIZE (millimeters)	FLOW RATE (Liters per minute)	PRESSURE LOSS (kPa)
50	200	96

Backflow preventer assemblies shall be painted with a minimum of 2 applications of a commercial quality enamel paint. The color of the paint shall be light brown.

BACKFLOW PREVENTER ASSEMBLY ENCLOSURE

Enclosures shall be fabricated of structural steel angles and flattened expanded metal and shall be installed over backflow preventer assemblies on a portland cement concrete pad as shown on the plans and in conformance with these special provisions.

Expanded metal for sides, ends and top panels shall be fabricated from 1.9 mm (14-gage), minimum thickness, sheet steel. The flattened expanded metal openings shall be approximately 20 mm by 45 mm in size.

Expanded metal panels shall be attached to the steel frames by a series of welds, not less than 6.4 mm in length and spaced not more than 100 mm on centers, along the edges of the enclosure.

Enclosure door handles shall have provisions for padlocking in the latched position. Padlocks will be State-furnished. Attention is directed to "State-furnished Materials" of these special provisions.

Enclosures shall be galvanized, after fabrication, in conformance with the provisions in Section 75-1.05, "Galvanizing," of the Standard Specifications.

Concrete for the concrete pad shall conform to the provisions in Section 20-2.26, "Concrete," of the Standard Specifications.

Hold down bolt assemblies shall be galvanized and shall be installed when the portland cement concrete pad is still plastic. Nuts shall be hexagonal and washers shall be the lock type.

Enclosures shall be painted with one application of a commercial quality pre-treatment, vinyl wash primer and a minimum of one application of a commercial quality, exterior enamel for metal. The finish color shall be light brown.

All parts of the backflow preventer assembly enclosure, including hold down assemblies, may be constructed of stainless steel instead of standard steel materials specified above. Stainless steel enclosures shall conform to the provisions herein except galvanizing, priming and painting shall not be required. Stainless steel enclosures shall be powder coated a light brown color by the manufacturer.

The minimum clearance between the backflow preventer assembly and the backflow preventer assembly enclosure shall be 150 mm. The concrete pad shall extend a minimum of 50 mm beyond the outer limits of the backflow preventer assembly enclosure, unless otherwise shown on the plans or specified in these special provisions.

TESTING BACKFLOW PREVENTERS

New backflow preventers installed by the Contractor shall be tested for proper operation in conformance with the provisions in Section 20-5.03J, "Check and Test Backflow Preventers," of the Standard Specifications and these special provisions.

Tests for new backflow preventers shall be satisfactorily completed after installation of the backflow preventer assembly and before operation of the irrigation systems.

New backflow preventers shall be retested one year after the satisfactory completion of the previous test or 10 days prior to completion of the plant establishment period, whichever occurs first.

SPRINKLERS

Sprinklers shall conform to the type, pattern, material, and operating characteristics listed in the "Sprinkler Schedule" shown on the plans.

Flexible risers shall be ultraviolet (UV) resistant, brown in color and shall conform to the details shown on the plans.

Full compensation for the 50 mm diameter x 300 mm polyvinyl chloride (PVC) plastic pipe, Schedule 80, with removable threaded cap for the Type C-2 flood bubbler sprinklers required to irrigate the palm trees and street trees as shown on the plans shall be considered as included in the contract lump sum price paid for irrigation system and no additional compensation will be allowed therefor.

WYE STRAINERS

Wye strainers shall be installed on the upstream side of the electric remote control valves as shown on the plans.

When garden valves are opened, discharge shall be up and out of the valve box.

FINAL IRRIGATION SYSTEM CHECK

A final check of new irrigation facilities shall be performed not more than 20 working days prior to acceptance of the contract.

The length of watering cycles using potable water measured by water meters for the final check of irrigation facilities will be determined by the Engineer.

Remote control valves connected to new irrigation controllers shall be checked for automatic performance when the controllers are in automatic mode.

Unsatisfactory performance of irrigation facilities installed or modified by the Contractor shall be repaired and rechecked at the Contractor's expense until satisfactory performance is obtained, as determined by the Engineer.

Nothing in this section "Final Irrigation System Check" shall relieve the Contractor of full responsibility for making good or repairing defective work or materials found before the formal written acceptance of the entire contract by the Director.

Full compensation for checking the irrigation systems prior to the acceptance of the contract shall be considered as included in the contract lump sum price paid for plant establishment work and no additional compensation will be allowed therefor.

SECTION 10-3. SIGNALS, LIGHTING AND ELECTRICAL SYSTEMS

10-3.01 DESCRIPTION

Modify lighting (City), signal and lighting (City), lighting and sign illumination, traffic operations system, and irrigation controller enclosure cabinet shall conform to the provisions in Section 86, "Signals, Lighting and Electrical Systems," of the Standard Specifications and these special provisions.

All earthly material removed in connection with signals, lighting and electrical systems shall be disposed of outside the highway right of way in conformance with the provisions as provided in "Hazardous and Non-Hazardous Material Excavation," elsewhere in these special provisions.

Traffic operations system shall consist of:

1. CCTV camera system.
2. Extinguishable message sign system.
3. Traffic monitoring station.

Work to be performed within the City of San Francisco's right of way shall conform to the additional or different requirements described in "City of San Francisco Electrical Special Provisions," elsewhere in these special provisions. In the event the special provisions for the City or the Standard Specifications Department of Public Works San Francisco do not cover a particular item the Standard Specifications and these special provisions shall be applicable.

Lighting equipment is included in the following structure:

A. Central Viaduct (Bridge No. 34-0077).

Traffic signal work shall be performed at the following location:

A. Route 101 on/off ramps and Market Street.

Full compensation for imported material and the disposal of all earthly material in connection with signals, lighting and electrical systems outside the highway right of way in conformance with the provisions as provided in "Hazardous and Non-Hazardous Material Excavation," shall be considered as included in the contract prices paid for various signals, lighting and electrical systems items as shown in the Engineeer's Estimate and no additional compensation will be allowed therefore.

10-3.02 COST BREAK-DOWN

Cost break-downs shall conform to the provisions in Section 86-1.03, "Cost Break-Down," of the Standard Specifications and these special provisions.

The Engineer shall be furnished a cost break-down for each contract lump sum item of work described in this Section 10-3.

The cost break-down shall be submitted to the Engineer for approval within 15 days after the contract has been approved. The cost break-down shall be approved, in writing, by the Engineer before any partial payment for the items of electrical work will be made.

10-3.03 ABBREVIATIONS

CTSS	Caltrans Standard Specifications (July 1999)
CTSP	Caltrans Standard Plans (July 1999)
SPDPWSF	Standard Plans Department of Public Works San Francisco (September 1987)
SSDPWSF	Standard Specifications Department of Public Works San Francisco (July 1986)

The following applicable City Standard Plans are contained in the project plans:

File Number and Change Number	Sheet Title
43,665, Ch.2	Typical: Details of Splicing of 600-Volt Multi-Conductor Cable; Details of Splicing of 600-Volt and 5,000-Volt Thermoplastic Insulated Single Conductor Wiring
49,093, Ch. 1	Pull Box Details
49,092	Street Light Service and Circuit Requirements
STR-7025	Signal Head Mountings

The City Standard Plans listed above are also contained in the Standard Plans Book of the City and County of San Francisco, Department of Public Works, Bureau of Engineering, dated September 1987.

Additional copies of the City of San Francisco's Standard Plans may be obtained at the office of the City Engineer, Room 420, 875 Stevenson St., San Francisco, California, 94102, telephone (415) 554-6229, on payment of the prescribed purchase price.

10-3.04 FOUNDATIONS

Sleeve nuts shall be used on Type 1-B standard. Foundations for Type 1-B standards shall conform to the details on Standard Plan ES-7B, "Anchor Bolts With Sleeve Nuts", except that the bottom of the base plate shall be flush with the finished grade.

10-3.05 STANDARDS, STEEL PEDESTALS AND POSTS

The sign mounting hardware shall be installed at the locations shown on the plans.

Type 1 standards shall be assembled and set with the handhole on the downstream side of the pole in relation to traffic or as shown on the plans.

10-3.06 CONDUIT

Conduit to be installed underground shall be Type 1 or Type 3 unless otherwise specified.

The conduit in a foundation and between a foundation and the nearest pull box shall be Type 1.

Conduit sizes shown on the plans and specified in the Standard Specifications and these special provisions are referenced to metallic type conduit. When rigid non-metallic conduit is required or allowed, the nominal equivalent industry size shall be used as shown in the following table:

Size Designation for Metallic Type Conduit	Equivalent Size for Rigid Non-metallic Conduit
21	20
27	25
41	40
53	50
63	65
78	75
103	100

When Type 3 conduit is placed in a trench (not in pavement or under portland cement concrete sidewalk), after the bedding material is placed and the conduit is installed, the trench shall be backfilled with commercial quality concrete, containing not less than 250 kg of portland cement per cubic meter, to not less than 100 mm above the conduit before additional backfill material is placed.

Conduit runs shown on the plans to be located behind curbs may be installed in the street, within 0.9-m of, and parallel with the face of the curb, by the "Trenching in Pavement Method" in conformance with the provisions in Section 86-2.05C, "Installation," of the Standard Specifications. Pull boxes shall be located behind the curb or at the locations shown on the plans.

After conductors have been installed, the ends of conduits terminating in pull boxes, service equipment enclosures, and controller cabinets shall be sealed with an approved type of sealing compound.

At those locations where conduit is required to be installed under pavement and existing underground facilities require special precautions in conformance with the provisions in "Obstructions" of these special provisions, conduit shall be placed by the "Trenching in Pavement Method" in conformance with the provisions in Section 86-2.05C, "Installation," of the Standard Specifications.

At other locations where conduit is required to be installed under pavement and if a delay to vehicles will not exceed 5 minutes, conduit may be installed by the "Trenching in Pavement Method."

At the option of the Contractor, the final 0.6-m of conduit entering a pull box in a reinforced concrete structure may be Type 4.

Conduit between irrigation controller enclosure and adjacent service pull box shall be metric trade Size 41.

10-3.07 PULL BOXES

Grout shall not be placed in the bottom of new or existing pull boxes.

10-3.08 CABLES, CONDUCTORS AND WIRING

Splices shall be insulated by "Method B".

The minimum insulation thickness, at any point, for Type USE, RHH or RHW wire shall be 1.0 mm for conductor sizes No. 14 to No. 10, inclusive, and 1.3 mm for No. 8 to No. 2, inclusive. The minimum insulation thickness, at any point, for Type THW and TW wires shall be 0.69 mm for conductor sizes No. 14 to No. 10, inclusive, 1.02 mm for No. 8, and 1.37 mm for No. 6 to No. 2, inclusive.

Signal cable shall not be used.

Splices for cables will not be allowed, except where shown on the plans.

10-3.09 CLOSED CIRCUIT TELEVISION CABLES

Television control (TVC) cable shall consist of 15 No. 18 conductors, unshielded and with an outer jacket. Each conductor shall have a minimum of 16 tinned copper stands with a minimum of 400 µm insulation. Individual conductor insulation shall be chrome PVC with a nominal thickness of 1 mm. The outside diameter of the jacket shall not exceed 14 mm.

Color code for TVC cable shall be:

1. Black
2. White
3. Red
4. Green
5. Orange
6. Blue
7. White/ Black
8. Red/ Black
9. Green/ Black
10. Orange/ Black
11. Blue/ Black
12. Black/ White
13. Red/ White
14. Green/ White
15. Blue/ White

Television power (TVP) conductors shall be 3 No. 14 (120 VAC, AC-, equipment ground) individually insulated, stranded copper conductors in conformance with Section 86-2.08, "Conductors" of the Standard Specifications. The conductors shall be color coded black, white, and green respectively.

Television control power (TVCP) cable shall consist of 12 No. 18 conductors, unshielded and with an outer jacket. Each conductor shall have a minimum of 16 tinned copper strands with a minimum of 400 µm insulation. Individual conductor insulation shall be polyvinyl chloride (PVC), rated for 300 V (see color code below). The jacket shall be chrome PVC with a nominal thickness of 1 mm. The outside diameter of the jacket shall not exceed 12 mm.

Color code for TVCP cable shall be:

1. Black

2. White
3. Red
4. Green
5. Orange
6. Blue
7. White/ Black
8. Red/ Black
9. Green/ Black
10. Orange/ Black
11. Blue/ Black
12. Black/ White

Television video (TVL) cable shall consist of an RG-6/U coaxial cable. Each cable shall be provided with a solid No. 18 copper clad steel center conductor and shall conform to the following requirements:

Electrical	TVL
Capacitance (picofarads/m nominal)	54.1
Impedance (ohms-nominal)	75
Velocity of propagation (nominal)	84%
D.C. loop resistance (ohms/100 m)	11.7

Attenuation at 20˚C:

Frequency (MHz)	TVL (Nominal dB/ 100 m)
5.0	1.90
30	3.64
108	6.40

Physical Specifications	TVL Nominal O.D. (mm)
Copper-clad steel center conductor	1.00
Foam polyethylene dielectric	4.57
Sealed APA tape with 1.6 mm overlap	4.75
Woven aluminum braid	5.39
Sealed APA tape with 1.6 mm overlap	5.49
Woven aluminum braid	6.12
Flooding compound	
PVC outer jacket	7.55

(APA = Aluminum polyolefin and aluminum with adhesive)

TVL cable shall be terminated with BNC plug connector at both ends.

COAXIAL CABLE CONNECTORS (TVL COAXIAL CABLES)

Coaxial cable connectors for attaching Type TVL coaxial cable shall meet the following requirements:

1. **Electrical:**

Impedance	75 Ω nominal
Return loss	30 dB minimum (5 MHz to 300 MHz)
Rated working voltage	500 V rms

2. **Mechanical:**

Type of construction	Integral sleeve BNC
Method of attachment	Crimp-crimp
Composition	Bodies - alloy Finish - chromate conversion, silver plating, or other corrosion resistant metal

3. **Environmental:**

Temperature	-10˚C to +50˚C
Moisture	Weather resistance design

The mating connector for TVL cable in junction box shall be provided. The center contact of this jack shall be beryllium copper.

TESTING

Testing of TVL cables and connectors shall be performed in accordance with provisions in Section 86-2.14B, "Field Testing" of the Standard Specifications and these special provisions.

Cable lengths found to have faults shall be replaced and retested. The removed faulty cable shall be disposed of by the Contractor.

Prior to the beginning of work, each length of coaxial cable shall be tested for attenuation and faults to ensure compliance with specifications contained herein using a time domain reflectometer (TDR). For the purpose of these special provisions, a fault in a long length of cable is defined by one or more of the following:

a. Return loss measurements indicating that attenuation exceeds 3 dB at 5 MHz to 30 MHz in a portion of cable less than 3 m long.
b. A return loss measurement indicating that there is a short in the cable.
c. A return loss measurement indicating a cut or open circuit in the cable.
d. A visual inspection which reveals exposure of or damage to the cable shielding.

10-3.10 TELEPHONE CABLE

The telephone cable (TC) shall consist of 6 pairs of No. 19 solid copper conductors. Conductors shall be twisted in pairs. Each conductor shall be insulated with a high molecular weight, heat stabilized, color coded polyethylene material. The insulation shall be 440 µm nominal.

Color code for TC cable shall be as follows:

1. White/Blue
2. White/Orange
3. White/Green
4. White/Brown
5. White/Gray
6. Red/Blue

The core shall be protected by a non-hygroscopic polyester film with a single longitudinally applied 120 µm thick corrugated copper shield (or 190 µm thick plastic coated aluminum shield). A moisture barrier of petrolatum-polyethylene compound shall be applied over the core tape and over and under the cable shield to fill all cable interstices.

The cable shall be provided with an outer jacket of extruded, black, high molecular weight, heat stabilized polyethylene material. The outer jacket shall have a thickness of 1.5 mm nominal. The outer diameter of the cable shall be 15.25 mm maximum.

All conductors shall be terminated inside the telephone demarcation cabinet and the controller cabinet as shown on the plans. All connections from the TBO terminal block to the 8-position connecting block shall be via a cable consisting of 2 pairs of No. 22 solid conductors and shall meet the same specifications as the TC cable.

10-3.11 BONDING AND GROUNDING

Bonding and grounding shall conform to the provisions in Section 86-2.10, "Bonding and Grounding," of the Standard Specifications and these special provisions.

Bonding jumpers in standards with handholes and traffic pull box lid covers shall be attached by a UL listed lug using 4.5-mm diameter or larger brass or bronze bolts and shall run to the conduit or bonding wire in the adjacent pull box. The grounding jumper shall be visible after the standard has been installed and the mortar pad and cap have been placed on the foundation.

Standards without handholes shall have bonding accomplished by jumpers attached to UL listed ground clamps on each anchor bolt.

For slip base standards or slip base inserts, bonding shall be accomplished by jumpers attached to UL listed ground clamps on each anchor bolt, or a UL listed lug attached to the bottom slip base plate with a 4.5-mm diameter or larger brass or bronze bolt.

Equipment bonding and grounding conductors are required in conduits, except when the conduits contain combinations of loop lead-in cable, fiber optic cable, or signal interconnect cable. A No. 8 minimum, bare copper wire shall run continuously in circuits, except for series lighting circuits, where No. 6 bare copper wire shall run continuously. The bonding wire size shall be increased to match the circuit breaker size in conformance with the Code, or shall be as shown on the plans. Conduits to be installed for future conductors, may omit the copper wire.

Bonding of metallic conduits in metal pull boxes shall be by means of bonding bushings and bonding jumpers connected to the bonding wire running in the conduit system.

10-3.12 SERVICE

Type III service equipment enclosures shall be the aluminum type.

Circuit breakers shall be the cable-in/cable-out type, mounted on non-energized clips. All circuit breakers shall be mounted vertically with the up position of the handle being the "ON" position.

Type H service shall consist of a conduit and conductors with length and size as required by the serving utility company.

The neutral conductor shall run from the service equipment enclosure to the controller cabinet without splicing to any other neutral conductor.

The clearance between the bottom of the lowest circuit breaker and the bottom of the service equipment enclosure for a Type III-A series shall be 600 mm minimum.

Installation of a barrier type terminal block in service equipment enclosures is not required.

ELECTRIC SERVICE (IRRIGATION)

Electric service (irrigation) shall be from the service points to the irrigation controllers (IC) and to the spaces provided in the irrigation controller enclosure cabinets (CEC) for irrigation controllers as shown on the plans.

Irrigation Controller (IC) 'A' : Electric service (irrigation) shall be a metered 120/240 V(ac), single-phase service in a Type III service equipment enclosure.

10-3.13 NUMBERING ELECTRICAL EQUIPMENT

The placement of numbers on electrical equipment will be done by others.

10-3.14 STATE-FURNISHED CONTROLLER ASSEMBLIES

The Model 170 controller assemblies, including controller unit, completely wired controller cabinet and inductive loop detector sensor units, but without anchor bolts, will be State-furnished as provided under "Materials" of these special provisions.

The Contractor shall construct each controller cabinet foundation as shown on the plans for Model 332 and 334 cabinets (including furnishing and installing anchor bolts), shall install the controller cabinet on the foundation, and shall make field wiring connections to the terminal blocks in the controller cabinet.

A listing of field conductor terminations, in each State-furnished controller cabinet, will be furnished free of charge to the Contractor at the site of the work.

State forces will maintain controller assemblies. The Contractor's responsibility for controller assemblies shall be limited to conforming to the provisions in Section 6-1.02, "State-Furnished Materials," of the Standard Specifications.

The Contractor shall furnish and install one rackmount surge power strip with a switch in each Model 334 controller cabinet. The power strip shall be plugged into the non-GFCI duplex outlet normally labeled with "Controller Unit Recp." in the back of the PDA unit. The power strip shall be mounted at the top of the standard EIA-310 rack cage and across the two vertical back rails with four stainless steel EIA mounting screws, two on each side. The power strip shall not hinder the accessibility to the back of all existing electrical equipment. All power cords for permanently field installed electrical equipment shall be plugged into the power strip.

The power strip, at a minimum, shall meet the following requirements:

1. It shall have a maximum rating of 15 A, 120 VAC, 60 Hz.
2. It shall have a surge protection with UL 1449 Clamping Level of 400 V, an IEEE Let-Through Voltage rating of less than 336 V, a single -pulse energy rating of 210 J and EMI/RFI noise protection rating of 40 dB.
3. It shall be 46 mm (H) x 483 mm (W) x 70 mm (D) maximum and shall not weigh more than 2.0 kg.
4. The front plate of the power strip shall have four cut-off EIA mounting screw holes, two on each side.
5. It shall have six rear outlets with 38 mm minimum apart center to center. The power cord shall enter from the rear with a length of 2 meters minimum. The clearance between the power cord entrance and the nearest outlet shall be 90 mm minimum.
6. It shall have a 15 Amp circuit breaker and an internally illuminated switch to cut off power to all outlets. Both the circuit breaker and the switch shall be front mounted.

10-3.15 IRRIGATION CONTROLLER ENCLOSURE CABINET

Irrigation controller enclosure cabinets (CEC) shall be constructed and the equipment within the cabinets shall be installed in conformance with the details shown on the plans, the provisions in the Standard Specifications, and these special provisions.

Irrigation controller enclosure cabinets shall be of metal construction conforming to the details for empty Type P signal cabinets shown on Standard Plans ES-3A and ES-3C, except that the fluorescent interior light, police panels, and shelves shall not be provided, unless otherwise shown on the plans. Cabinets shall be provided with cross ventilation, roof ventilation or a combination of both. The anchorage arrangement shall be inside the cabinet as shown on the plans. Dimensions of the cabinet shall be suitable for the equipment to be installed as shown on the plans and specified in these special provisions.

Irrigation controller enclosure cabinets shall be a minimum of 1.2 m high, fabricated in conformance with the provisions in Section 86-3.04A, "Cabinet Construction," of the Standard Specifications.

Irrigation controller enclosure cabinets shall be fabricated of stainless steel.

Irrigation controller enclosure cabinet doors shall not be furnished with integral door locks. Irrigation controller enclosure cabinet door handles shall have provisions for padlocking in the latched position. Padlocks will be State-furnished as provided under "Materials" of these special provisions.

Irrigation controller enclosure cabinets shall be furnished with a 304 grade stainless steel or plywood mounting panel.

Mounting panels made of plywood shall be 19-mm exterior AC grade veneer plywood. The panel shall be painted with one application of an exterior, latex based, wood primer and 2 applications of an exterior, vinyl acrylic enamel, white in color. The plywood panel shall be painted on all sides and edges prior to installation of the panel in the cabinet and equipment on the panel.

Inside of the doors shall have provisions for storage of the irrigation plans.

Duplex convenience receptacles shall have ground-fault circuit interruption as defined by the Code. Circuit interruption shall occur on 6 mA of ground-fault current and shall not occur on less than 4 mA. Receptacles shall be installed in a weatherproof housing with rainproof lift covers.

Equipment, except for field wiring, shall be installed in the cabinet in a shop prior to field installation.

Irrigation controller enclosure cabinets will be measured by the unit as determined from actual count in place.

The contract unit price paid for irrigation controller enclosure cabinet shall include full compensation for furnishing all labor, materials, tools, equipment and incidentals, and for doing all the work involved in fabricating and installing irrigation controller enclosure cabinets, complete in place, including constructing foundations, pads and conduits to pull box adjacent to cabinets, and installing equipment within the cabinets, except controllers, as shown on the plans, as specified in the Standard Specifications and these special provisions, and as directed by the Engineer.

10-3.16 TELEPHONE DEMARCATION CABINET

The Contractor shall furnish and install all cable assemblies, punch block, and connecting blocks inside the TDC, except those that are provided by the telephone company (TELCO), as shown on the plans and as directed by the Engineer.

Ground rod shall meet the requirements of NEC Article 250-84.

Padlockable drawer latch shall be padlock hasp.

Backboard C shall be secured by a retaining screw.

Duplex outlet and GFCI duplex outlet shall be separately connected to the main circuit breaker.

The bottom plate for TDC shall be 3.2 mm aluminum.

10-3.17 FLASHING BEACONS

Incandescent lamps for flashing beacon units will be State-furnished in conformance with the provisions in "Materials" of these special provisions.

10-3.18 DETECTORS

Loop detector sensor units will be State-furnished in conformance with the provisions in "Materials" of these special provisions.

Where one traffic signal detector consists of a sequence of 4 loops in a single lane, the front loop closest to the limit line or crosswalk shall be located 0.3 m from the line. All 4 loops in each lane shall be connected in series.

PREFORMED INDUCTIVE LOOPS

Preformed inductive loops shall be the type shown on the plans.

The loop shall be 1.8 m square unless otherwise shown. The loop shall consist of 4 turns of No. 16, or larger, wire with Type THWN or TFFN insulation.

The loop wires shall be encased in Size 10, minimum, Schedule 40 or Schedule 80 PVC or polypropylene conduit. The conduit shall be sealed to prevent the entrance of water and the movement of wires within the conduit.

The loop wires from the preformed loop to the adjacent pull box shall be twisted together into a pair (at least 7 turns per meter) and encased in Schedule 40 or Schedule 80 PVC or polypropylene conduit between the preformed loop and the adjacent pull box or detector handhole. The lead-in conduit shall be sealed to prevent the entrance of water at the pull box or handhole end.

In new roadways, the preformed loops and lead-in conduits shall be placed in the base course, with the top of the conduit flush with the top of the base, and then covered with asphalt concrete or portland cement concrete pavement. Preformed loops and lead-in conduits shall be protected from damage prior to and during pavement placement.

In new reinforced concrete structure decks, the preformed loops shall be secured to the top of the uppermost layer of reinforcing steel using nylon wire ties. The loop shall be held parallel to the structure deck by using PVC or polypropylene spacers where necessary. Conduit for lead-in conductors shall be placed between the uppermost 2 layers of reinforcing steel.

Preformed inductive loops shall not be fabricated at the job site.

10-3.19 LUMINAIRES

Ballasts shall be the lag or lead regulator type.

10-3.20 PHOTOELECTRIC CONTROLS

Contactors shall be the mechanical mercury type.

10-3.21 EXTINGUISHABLE MESSAGE SIGN

Each extinguishable message sign shall be an internally illuminated weathertight and dust tight unit which will produce a clearly visible message only when internally illuminated and shall conform to these special provisions.

The design of each sign shall be as shown on the plans. Minor details of construction shown are typical and may be modified subject to approval by the Engineer.

Six sets of shop drawings shall be submitted to the Engineer for review prior to performing work on the signs.

HOUSING

The housing shall be ruggedly constructed, shall be rigid, weathertight, dust tight and corrosion resistant, and shall be made of durable materials.

Provisions shall be made for ease of maintenance of components.

Sign panels and housing window shall be made of acrylic plastic which, including painted portions, shall be highly resistant to crazing, staining, discoloration, creep, warping, and the long range deleterious effects of vehicle fumes, direct sunlight, heat (up to 90°C), water, oils and aging.

The housing skin shall be made of Type 5052-H32 aluminum alloy sheet with clad finish. The housing reinforcing and miscellaneous parts shall be made of suitable gages and types of aluminum, except external fasteners, machine screw parts, lock washers, hinge pins, and other mechanical parts, which shall be made of Type 316 stainless steel.

Interior metal parts shall be made of suitable gages and types of plated steel or aluminum, except fasteners, machine screw parts, lock washers and other miscellaneous parts shall be made of corrosion resistant metals other than aluminum.

The separable hinge for mounting the reflector shall be brass as shown on the plans or shall be stainless steel.

Gaskets shall be uniform and even textured, and shall be highly resistant to stiffening and setting and the long range deleterious effects of vehicle fumes, direct sunlight, heat (up to 70°C), water, oils and aging.

Terminal strips shall be used for input, output and tie point connections and shall be of the molded phenolic, barrier type.

BALLASTS, CONTROL RELAYS AND TERMINAL BLOCKS

Ballast inductors shall meet the requirements in ANSI Standard: C82.1, "Fluorescent Lamp Ballasts."

The inductors shall have the inductance noted on the plans (±10 percent), losses not exceeding 15 percent of lamp watts at rated current of inductor and a maximum current crest factor of 1.5 at rated current of inductor. The maximum temperature rise of the inductor coils shall be limited to 40°C above an ambient temperature of 40°C.

Heater transformers shall produce the rated secondary voltage (±10 percent) at full load and at one-third load. The maximum temperature rise of the transformer coils shall not exceed 40°C above an ambient temperature of 40°C.

Inductors and transformers shall have cores made of a suitable grade of silicon steel lamination material and shall have thorough resin impregnation.

Each mounting chassis shall be fabricated of 3 mm, Type 5052-H32 aluminum alloy sheet. Units shall be mounted on the chassis with plated brass or steel hardware, except for lock washers which shall be beryllium copper, externally toothed.

Capacitors shall be rated 660 V (ac), 60 Hz, for operation down to -20°C with capacity as shown on the plans and shall be oil filled, paper type, hermetically sealed with solder lug terminals. Capacitance shall be within ±10 percent of rating at 25°C. Each capacitor shall withstand a limited direct current, 15-second breakdown test at 25°C of 3000 V (ac) from each terminal to case. Minimum insulation leakage resistance from terminal to terminal, in megohms, shall be not less than 1500 divided by capacitance in microfarads.

Each magnetic control relay shall be of the heavy-duty, power type with 120-V (ac) coil and double-pole, double–throw contacts with a minimum rating of 2 A at 480 V (ac), 60 Hz. The coil shall consume not more than 10 VA with sealed armature.

The relay coil shall be designed to provide reliable service under the following conditions:

A. Maximum operating voltage: 10 percent over rated volts.
B. Ambient temperature: 60°C.

The relay coil shall meet NEMA requirements for temperature rise and voltage breakdown.

Maximum dimensions of the relay shall be: mounting base, 63.5 mm by 102 mm; overall height, 63.5 mm.

Fuseholders shall be the panel mounting type rated at 250 V (ac), complete with a 10.3-mm diameter by 38-mm length, slow blowing, cartridge type fuse.

Surge limiting and ballast resistors shall be ceramic coated, 20-watt, wirewound units. Resistor leads shall have plastic insulation rated 600 V (ac), for operation at 200°C.

Wiring connections from components shall be terminated on 2 molded phenolic, barrier type, terminal block assemblies rated at 15 A, 600 V (ac). Terminal designations shall be marked as indicated on the plans.

LAMPHOLDERS AND LAMPS

Lampholders shall have silver plated contacts.

Lamps shall be the extra-high output, rapid-start type with T-12 bulb of the length shown on the plans, cool-white color and plated contacts for operation up to 1500 mA.

CONDUCTORS AND WIRING

Ballast and sign conductors shall be No. 16 stranded copper wire and shall be labeled by UL as 105°C appliance wiring material (AWM) for use at 600 V (ac). Ballast conductors shall be secured with easily removable, spring cross straps (not clamped, cabled or served) on the underside of the chassis. Color coding and terminal markings shall be as shown on the plans.

Lead ends shall be fitted with spade lugs.

LUG DISCONNECT

Each plug disconnect shall consist of molded nylon plug and receptacle housings containing plug pins and individual sockets designed to be crimped to conductors and snapped into the housings. Housings shall have integral, molded, polarizing and locking devices. Minimum UL electrical rating shall be 10 A, 600 V (ac). Pins and sockets shall be tin plated phosphor bronze secured to conductors using a ratchet type precision crimping tool.

TESTING

Tests shall verify that the following conditions exist:

A. Transformer output voltage: 480 V (ac) ± 10 percent.
B. Sign input current (daytime level): 4 A maximum.

C. Lamp current each (daytime level): 1.4 A ± 15 percent (nighttime level) 30 mA ± 15 percent.
D. Cathode filament voltage: 3.6 V (ac) ± 10 percent and shall be supplied from a steady (non-flashing) source.

SIGN OPERATION

The sign shall operate as follows:

A. During daytime, the lamps shall operate at full rated brightness.
B. During nighttime, the lamps shall be dimmed to approximately one-thirty-fifth of daytime brightness.
C. Starting and flashing shall be positive, without flickering, during daytime and nighttime levels.

10-3.22 CAMERA UNIT

Each camera unit shall consist of a camera, lens, environmental housing and camera unit cable assembly. The camera, lens and environmental housing, combined, shall not weigh more than 6.8 kg. Each camera unit shall be interchangeable with the existing camera units already installed on various traffic operations system (TOS) projects without changes or adjustments to either the system or the camera unit.

Each camera unit shall be assembled, inspected, and tested in accordance with these special provisions prior to delivery to the job site. Installation, operations and maintenance manuals shall also be submitted at the time of delivery.

Applicable Documents - The following documents of the U.S. Military Specification (MIL-SPEC), Underwriters' Laboratory, Inc. (UL), Electronics Industries Association (EIA) Standards, and other Standards form parts of the specification to the extent specified in these standards. In the event of a conflict between the content of this section and the content of the specification, the standards defined in this section shall supersede.

Military Specification Documents	
MIL-I-45208A	Inspection System Requirements, Dec. 16, 1963
MIL-C-45662	Calibration System Requirements, June 10, 1980
MIL-STD-416A	Electromagnetic Interface Characteristics Requirements for Equipment, Subsystems & Systems, Aug. 1, 1968
MIL-E-5400T	Electronic Equipment, Airborne General Specification
MIL-STD-810	Environmental Test Methods, 19 July 1983
MIL-C-5541	Chemical Conversion Coatings on Aluminum Alloys, June 3, 1970

Underwriters' Laboratory, Inc. and other documents	
UL-796	Printed Circuit Boards
EIA-170A	Electrical Performance Standards Color Television Studio Facilities
EIA RS-330	Electrical Performance Standards for Closed Circuit Television (CCTV) Camera 525/60 Interlaced

CAMERA

Approved Camera - The cameras listed below have been approved by the Engineer. Further information such as the source of the cameras can be provided upon demand. Any camera submitted by the Contractor that is not one of the approved cameras listed below shall be stringently compared to the specifications set forth in these special provisions before it is approved by the Engineer.

Approved Cameras:

Cohu 8240
Sony SSC-C374
Burle/Philips TC293C-Z0P2X596

1. General -

a. Each camera shall be self-contained and designed for continuous unattended 24-hour operation.
b. Camera performance shall meet or exceed EIA-170A standards.
c. Each camera shall have automatic sensitivity and black level control so that it operates without further adjustment when illumination ranges from the minimum specified herein to that of full daylight.
d. Each active electronic device within the camera shall be solid-state.

e. Each camera shall have a switch selectable electronic shutter. The shutter speed shall range from 1/60 of a second (off) to 1/10,000 of a second in 8 steps. The control of the electronic shutter rate shall be accessible through a side panel opening. Remote on/off control of the shutter shall be accomplished via an output connector on the rear of the environmental housing.

2. Light sensitivity - At a scene with 50 percent light reflectivity and with light level on the scene measured to be 10 lux and greater, each camera with its 10:1 zoom lens shall generate a picture on the monitor specified in these special provisions which resolves all 10 shades of gray on the EIA Television Test Chart. Not every camera shall be required to resolve the same gray scale when the light level on the same scene is measured to be less than one lux.

3. Electrical Power - Each camera shall operate when the applied voltage is between 95 to 130 VAC, 60 Hz ±0.3 Hz, single phase. The power consumption of camera shall not exceed 10 W. All camera circuitry shall be powered by a regulated, over-voltage protected DC power supply contained in the camera.

4. Synchronization -

a. Each camera shall generate synchronization signals by means of a single integrated circuit.
b. Each camera shall operate with the internal EIA-170A crystal as the sync reference source with the field rate of 59.94 Hz.
c. Each camera shall have the capability of synchronizing to an external input source.
d. The synchronization signal at the video output shall conform to EIA-170A.

5. Scanning - Each camera's mode of scanning shall be two-to-one interlaced at 525 lines, 60 fields per second, as specified by EIA-170A.

6. Video Processing -

a. The video output level shall be maintained to within 3 dB for changes in scene brightness of 0.17 to 109 600 cd/m^2 using a motorized iris lens having a transmission range of F/1.2 to F/1200.
b. Each camera shall have a black-level control system.
c. Each camera shall have an automatic white (color) balance control to maintain proper color rendition by automatically referencing to white areas of the scene. Manual control of the white balance shall be accessible through side panel or remotely controlled via the rear connector on the environmental enclosure.
d. Automatic gain control (AGC). The switch selectable fixed gain response shall maintain the output video level to 90 percent video when the light level on the image sensor falls too low to maintain full video output. The video out will be maintained at 90 percent peak-average setting to optimize video output under varying lighting conditions. The controls for the on/off and peak average adjustments shall be accessible through the side panel of the camera.
e. One 75 Ω (±1 percent) source-terminated, single-ended video output jack shall be provided.
f. An adjustable white clipper shall be provided to limit highlight brightness.
g. The video output level shall be 1.0 V peak-to-peak composite (0.7 V video, 0.3 V sync) signal, polarity black negative, across a 75 Ω load impedance.
h. The minimum signal-to-noise ratio shall be 50 dB at 25°C.

7. Imager -

a. Each camera shall be designed to use a 12.7 or 16.9 mm format solid-state, color, interline transfer charged-coupled device (CCD) imager.
b. The imager shall have a minimum resolution of 768 horizontal by 493 vertical active picture elements.
c. When provided with 6.89 lux of highlight illumination on the environmental housing window, the camera shall provide the following resolution with AGC off:

   i. Horizontal center resolution shall be 460 TV lines minimum.
   ii. Vertical resolution shall be 350 TV lines minimum in the center and all corners simultaneously.

8. Mechanical -

a. All camera circuitry shall be on a printed circuit board which shall be removable and replaceable using no more than common hand tools.

b. Test points and adjustment identifications shall be etched or silk-screened on the boards.
c. Each camera shall be self-supporting and operable when removed from the environmental housing and shall have a lens adapter ring which accommodates a standard 16 mm C-mount. A back focal distance adjustment shall be provided.
d. Each camera shall utilize the rigidity of the environmental housing for strength against shock and vibration.

9. Environmental Operation -

a. Each camera within its environmental housing shall withstand the following requirements:

i. Operate over an ambient temperature range on -10°C to +50°C with the use of heaters.
ii. Peak random vibration of 5 g from 60 to 1000 Hz, with camera in operation.
iii. Shock up to 15 g in all axes under non-operating conditions.
iv. Exposure to sand, dust, fungus, and salt atmosphere as per MIL-E-5400T paragraphs 3.2.24.7, 3.2.24.8, 3.2.24.9, and 3.2.24.10.
v. Up to 100 percent relative humidity as per MIL-E-5400T, paragraph 3.2.24.2.

10. Picture Quality -

a. The quality of the picture shall be such that most objects in low light levels can be distinguished without excess interference from undesirable picture attributes.
b. Undesirable picture attributes include blooming, transfer smear, vertical register shifting.

LENS

1. General -

a. Each lens shall be fully compatible with the camera provided.
b. Each lens shall have a maximum aperture of no less than F/1.2, and a minimum range of F/1.2 to F/1200.
c. Each lens shall be a 16 mm C-mount.
d. Each lens shall have a minimum zoom range of 10 to 1. The lens focal length for a 16.9-mm CCD camera shall be shall be 10-100 mm, 10.5-105 mm or 11-110 mm. The lens focal length for a 12.7 mm. CCD camera shall be shall be 8-80 mm. A 1.5-X extender shall be included with the lens.
e. Each lens shall be equipped with a motorized zoom and focus control.
f. Each lens shall have an automatic, motor-driven iris with manual override. The iris shall be controlled directly through the camera in automatic mode and from the camera control unit in the manual mode. The automatic iris shall provide continuous aperture adjustments of the lens as determined by the amount of light reaching the camera imager. The power supply and electronics for iris motor shall be contained within the environmental housing.
g. Each lens shall be fitted with an intra-spot neutral density filter.
h. Each lens must be able to respond to the following inputs from camera control unit (CCU) for lens control:

Focus near	+9.0VDC @ 100 mA
Focus far	-9.0VDC @ 100 mA
Zoom in	+9.0VDC @ 100 mA
Zoom out	-9.0VDC @ 100 mA
Iris closed	+9.0VDC @ 100 mA
Iris open	-9.0VDC @ 100 mA

i. The travel time for the upper limit stop to the lower limit stop for zoom and focus shall be from 5 seconds minimum to 10 seconds maximum.
j. Each lens shall have the capability of at least 10 pre-positioning positions.

2. Environmental Operation -

a. Each lens within its pressurized environmental enclosure shall withstand the following requirements:

i. Operate over an ambient temperature range on -10°C to +50°C with the use of heaters.

ii. Peak random vibration of 5 g from 60 to 1000 Hz, with lens in operation.
iii. Shock up to 15 g in all axes under non-operating conditions.
iv. Exposure to sand, dust, fungus, and salt atmosphere as per MIL-E-5400T paragraphs 3.2.24.7, 3.2.24.8, 3.2.24.9, and 3.2.24.10.
v. Up to 100 percent relative humidity as per MIL-E-5400T, paragraph 2.24.2.

ENVIRONMENTAL HOUSING

1. General -

a. Each camera and lens shall be mounted in a sealed, cylindrical, environmental housing which shall not exceed 165 mm in diameter and 560 mm in length.
b. The housing shall be fabricated of seamless aluminum tubing Type 6061-T6 and shall be finished with heat reflecting, weather resisting enamel. The rear plate shall be fabricated of Type 6061-T6 aluminum.
c. The front of the housing shall be closed with a clear optically flat glass or Lexan window.
d. The housing shall include a sun shroud which shall be strapped to the housing bindings in such a manner as to minimize heat conduction by maintaining air space between shroud and housing. The shroud shall shield the entire top portion of the housing from the sun, and shall extend a minimum of 76 mm in front of the housing's glass plate.
e. The housing shall not interfere with the widest viewing angle of the lens.
f. The housing shall include a thermostatically controlled heating pad rated at 115 VAC, 100 W maximum.
g. The backplate, which is an integral part of the housing, shall have a nameplate attached bearing the manufacturer's camera assembly model number and serial number.
h. Camera connector -

i. The camera connector shall be designed to MIL-C-28462 Series 1 specifications with solder contacts. It shall be PT-07C-20-39 P, the male counterpart to PT-06A-20-39 S SR.
ii. The connector shall be made of the same shell material and pin arrangement as the PT-06A-20-39 S SR connector on the end of the wiring harness.
iii. The pinout of the connector shall be as shown on the plans.
iv. Each camera connector shall be mounted on the rear plate with an airtight connection and a watertight seal for each conductor on its connecting cable.

i. Each camera shall be designed for operating with the housing purged of air and filled with dry nitrogen to 35 kPa.
j. Valves -

i. The housing shall have two valves, both on the rear end plate of the housing.
ii. One valve shall be a standard Schrader valve. It shall have a tube running from the valve to the front end of the housing.
iii. The other valve shall be an air escape/pressure relief valve preset to 140 kPa.
iv. The two valves shall be arranged such that filling with dry nitrogen from the Schrader valve will force gas to flow from front end of the housing to the rear end and vent through the air escape valve.
v. The leakage rate with both valves closed and the housing pressurized to 70 kPa, shall leak less than 7 kPa per year, and less than 0.7 kPa per month.

k. The enclosure shall be factory pressurized to 35 kPa with dry nitrogen.
l. The notation "CAUTION PRESSURIZED" shall be printed on the rear plate of the enclosed.
m. A safety pressure release bolt shall be incorporated such that the enclosure may not be opened without first releasing the internal pressure.
n. A low-pressure (LP) sensor with related circuitry shall be provided to send an LP alarm (dry contact closure) via the camera connector. The LP sensor threshold shall be preset to activate the LP alarm at 14 kPa.
o. Two units of desiccant shall be placed inside the housing but will not obstruct the camera view or operation.
p. A humidity level indicator strip with discrete indications for 10, 20 and 30 percent humidity, shall be installed inside the housing in a position that allows inspection, while facing directly, through the window without obstructing the view of the camera at the widest viewing angle of the lens.

2. Mounting Base -

a. A mounting base shall surround the enclosure to provide a tamper-resistant attachment of the environmental housing to the pan/tilt unit and securely hold the housing in either an upright or inverted position. The combined height of camera housing and mounting base shall be less than 254 mm. The mounting base attachment shall be as shown on the plans.
b. All fasteners and nuts used in attaching the mounting base to the environmental housing shall be of grade 18-8 stainless steel.
c. Each camera unit shall be provided with three stainless steel hex head bolts to secure the camera unit to the pan/tilt unit.

CAMERA UNIT CABLE ASSEMBLY

1. General - Each camera unit cable assembly shall consist of box mounting socket connector and a wiring harness.

2. Box Mounting Socket Connector -

a. Each box mounting socket connector shall be MS-3102E-28-21S-F80.
b. One full set of crimp contacts shall be provided with each box mounting socket connector.
c. The pinout of the connector shall be as shown on the plans.

3. Wiring Harness -

a. The camera unit cable assembly wiring harness shall be 3 m long and shall be COHU AC27E or other cable approved by the Engineer. The coaxial cables' impedance shall be 75 Ω. One end of each wiring harness shall be type PT06A-20-39S (SR) and shall mate with the camera connector. It shall have a 90-degree end bell, Bendix 10-25997-203 or equal, for strain relief. The end bell shall be positioned such that the opening is 180 degrees from the main key on the connector. The other end of each wiring harness shall be type MS-3106E-28-21P and shall mate with the box mounting socket connector.
b. All connectors shall be potted with an appropriate potting compound for environmental sealing.
c. All connectors' pinout shall be as shown on the plans.

10-3.23 PAN/TILT UNIT

General

a. Each pan/tilt unit, with camera unit attached, shall pan 355 degrees minimum in either direction, and tilt 60 degrees minimum from horizontal position to either up or down positions.
b. Each pan/tilt unit shall be capable of minimum ten preset positions for each pan and tilt operation.

Electrical

a. Each pan/tilt unit shall operate with input voltage of 115 VAC, 60 Hz ±0.3 Hz.
b. Each pan/tilt unit shall not exceed 200 W power consumption.
c. The motors shall be impedance overload protected, two phase induction type, rated for continuous duty and shall be instantaneous reversing.
d. The limit switches shall be rated 5 A, 10 million cycles and with external adjustments.
e. Each pan/tilt unit shall be provided with box-mounting type connector.
f. One mating connector with full set of crimp contacts and strain relief shall be provided with the box-mounting connector.

Mechanical

a. The maximum load shall be 45 kg at 127 mm from tilt table to center of gravity in both upright and inverted position.
b. Each pan/tilt unit shall have maximum dimensions of 400 mm high, 355 mm wide and 230 mm deep.
c. Each pan/tilt unit shall not exceed the maximum weight of 27 kg.
d. Each pan/tilt unit shall be constructed in aluminum casting and plate. All internal parts shall be corrosion protected.
e. Each pan/tilt shall have textured semi-gloss beige enamel finish.
f. All bearings shall be heavy duty ball or roller bearing.

g. All gears shall be hardened steel.
h. All gasket seals shall be designed for all weather protection.
i. Each pan/tilt unit shall have a mounting hole pattern as shown on the plans.
j. Each pan/tilt unit shall have a minimum pan torque rating of 34 N·m and an instantaneous minimum tilt torque of 68 N·m.
k. The pan speed at no load shall be 6 to 8 degrees per second, nominal.
l. The tilt speed at no load shall be 3 to 4 degrees per second, nominal.

Environmental

a. Ambient operating temperature shall be from -10°C to 50°C.
b. It shall be able to withstand vibration of 760 µm total excursion from 5 to 30 Hz and a peak random vibration of 5 g from 30 to 1000 Hz.
c. It shall be able to withstand shock up to 15 g in all axes under non-operating conditions, conforming to MIL-E-5400R, Para. 3.2.24.6.
d. It shall be able to operate in atmospheres up to 95 percent relative humidity, conforming to MIL-E-5400R, Para 3.2.24.4.
e. It shall be able to withstand exposure to sand, dust, fungus, and salt atmosphere, conforming to MIL-E-5400R, Para 3.2.24.7, 3.2.24.8 and 3.2.24.9.

Pan and tilt unit mounting

The nuts and bolts securing the pan and tilt unit to the camera platform shall be hex head and made of stainless steel. Before each bolt is fastened, a locking type coating shall be applied to the threads. The coating shall lock the bolts and nuts in place making it impossible to turn bolt or nut without tools. This coating shall last and be effective through at least 10 insertions and withdrawals of the bolt or nut.

10-3.24 CAMERA JUNCTION BOX

The camera junction box (JCB) shall be constructed as shown on the plans and described in these special provisions. All seams shall be continuously welded. All JCB mounting Hex head stainless steel nuts and bolts shall be 6 mm ∅-20 x 25 mm. Steel surfaces on which JCB is to be mounted shall be drilled and tapped 6 mm ∅-20 thread. Each JCB shall be fabricated from 14 gauge sheet steel. Two 8-32 threaded studs for terminal strip mounting shall be welded on the bottom of the box as shown on the plans. After fabrication the JCB shall be hot-dip galvanized.

A twenty position terminal block with No. 8 lugs and cover shall be mounted on the bottom of the box. Permanent terminal position markings shall be used. A laminated wiring schematic shall be permanently attached to the inside of box cover showing wiring from the camera unit box mounting connector to the terminal block.

10-3.25 CAMERA CONTROL UNIT

General

Each part of each camera control unit (CCU) shall be electrically and physically interchangeable with the like part in any other CCU furnished under this contract.

Mechanical

a. Each CCU shall mount in 133 mm of EIA-310 rack space with a maximum depth of 356 mm.
b. The front panel shall be white gloss color Number 17886 as per Federal Standard Color Chart 595B.
c. The front and rear panel lettering shall be black color Number 17986 as per Federal Standard Color Chart 595B.
d. A high-impedance panel jack BNC (Bayonet Nut connector) connector shall be installed on the front panel as shown on the plans. This connector shall provide video input to a test monitor without affecting the remainder of the CCTV system. This connector shall be directly connected to the video input on the rear panel.
e. A glass type, size 6.35 mm x 31.75 mm (AG) slow blow fuse shall be installed on the front panel. The fuse shall be replaceable from the outside of the front panel.
f. Switches shall protrude no more than 25 mm from the front panel and shall be mounted as shown on the plans.
g. The rear panel connectors shall be mounted as shown on the plans and shall meet the following requirements:

i. Connectors C1-C3 shall be of the following type or equivalent:

C1	AMP 206430-1
C2	AMP 206043-1
C3	AMP 206306-1

ii. The pin and socket contacts for connectors C1-C3 shall be constructed with brass contact body material and with stainless steel spring that are sub-plated with 1.27 µm nickel and plated with 0.762 µm gold. Pin diameter shall be 1.575 mm. Contact size shall be 16.

iii. Each C1, C2 and C3 connector shall use the AMP No. 601105-1 or No. 91002-1 contact insertion and the AMP No. 305183 contact extraction tool.

iv. One mating connector with a full set crimp contacts and strain relief shall be supplied with connectors C1, C2 and C3.

v. The connectors C4 and C5 shall be a DB-25 socket connector.

h. Serial cable assemblies (SCA1 and SCA2) with length of 3 m shall be provided to mate with C4 and C5, respectively.

i. Pin and socket contacts for DB-25 connectors shall be copper alloy body; finished with 0.762 µm gold over 1.27 µm nickel.

j. The rear and front panel BNC connectors shall be of copper material with bright nickel (tarnish resistant) finish for the body and silver finish for the contact.

k. Each printed circuit board shall be vertically installed.

l. Each LED shall be equal to Hewlett Packard High Intensity Red Untinted, Non-diffused LED (Part Number HLMP-D105). Each LED shall be mounted as shown on the plans.

m. A front panel on/off switch shall turn the CCU on/off and shall also control AC power to the rear panel power output connector (C1). The indicator used for AC power shall be green when energized.

n. One coaxial cable labeled "AVO" (Analog Video Output) terminated with BNC plug connectors on each end shall be provided. This cable shall be RG-59/U with overall length of one meter.

Electrical

a. Each CCU shall have auto-iris override.

b. Each CCU shall have circuitry to detect the absence and presence of video sync on its video input. Each CCU shall also have circuitry to monitor the low-pressure alarm contact closure from the camera unit. A local/remote control switch shall be provided to override the lens and pan/tilt controls through C4 when the switch is in local mode. When in local mode, the local control alarm shall be active. Alarm status shall be constantly monitored and updated. Upon receipt of a "status query" message, the CCU shall send alarm status message with data as follows:

"0"	None of the alarms active.
"1"	Local Control (LC) alarm active.
"2"	Low Pressure (LP) alarm active.
"3"	LP/LC alarms active.
"4"	Video Sync Absence (VSA) alarm active.
"5"	VSA/LC alarms active.
"6"	VSA/LP alarms active.
"7"	VSA/LP/LC alarms active.

The front panel alarm light shall be lit if any the alarms are active.

c. Each CCU shall have circuitry for a source character generator. The source character generator shall display 16 alphanumeric characters superimposed on the video image. Each character shall be 28 TV lines high and shall be derived from a standard 5 x 7 dot matrix. The programmed characters shall be stored in a non-volatile memory. Upon receipt of "Set ID" message, the CCU shall position from the camera ID in the video image as follows:

"1"	Upper 15% limit of the left viewing area
"2"	Upper 15% limit of the right viewing area
"3"	Lower 15% limit of the left side viewing area
"4"	Lower 15% limit of the right side viewing area

The characters shall be superimposed on the video signal using non-additive mixing techniques.

d. Each CCU shall be designed to prevent simultaneous operation of pan right/left, tilt up/down, zoom in/out, focus near/far or iris open/close.

e. Each CCU shall have power supply(ies) for camera zoom, focus, motors, control and interface circuits. The voltage for zoom, focus and iris shall be selectable internally by one jumper for 12.0 VDC, 9.0 VDC or 5.0 VDC at 100 mA. The CCU shall be pre-configured with the voltage jumper select set to 9.0 VDC. The operation of zoom, focus and iris shall be as follows:

Zoom in	+VDC
Zoom out	-VDC
Focus near	+VDC
Focus far	-VDC
Iris close	+VDC
Iris open	-VDC

f. The maximum power consumption for the CCU shall not exceed 450 W. Power consumption of equipment attached to pin 1 of connector C1 shall not exceed 100 W. Power consumption of equipment attached to pin 12 of connector C2 shall not exceed 200 W.

g. Each CCU shall have eight independently operating 24 VDC relays (options 1 to 8). Each relay shall be single pole, double throw (SPDT), with contacts rated 1.25 A at 120 VAC.

h. Each CCU shall be capable of a minimum of ten presets and capable of controlling camera units and pan/tilt units equipped with pre-positioning feedback potentiometers. Each CCU shall have circuitry to filter out any electrical noise interference on each of the pre-positioning feedback voltage signal for the camera unit and pan/tilt unit.

i. A system reset switch shall be a momentary-pushbutton type and be mounted on the front panel to function as external reset input to the microprocessor. System reset shall not cause existing pan/tilt and lens positions to change. System reset shall be executed without requiring the operator to hold the momentary-pushbutton for more than one second.

j. The front panel of the camera control unit shall have LEDs and switches to provide the following control functions as shown on the plans.

Function	Hardware	Indicator
Zoom (In/Off/Out)	(ON)-OFF-(ON)	2 LED
Focus (Near/Off/Far)	(ON)-OFF-(ON)	2 LED
Pan (Left/Off/Right)	(ON)-OFF-(ON)	2 LED
Tilt (Up/Off/Down)	(ON)-OFF-(ON)	2 LED
Iris (Open/Off/Close)	(ON)-OFF-(ON)	2 LED
Iris override (Manual/Auto)	ON-OFF	1 LED
Option 1 (On/Off)	ON-OFF	1 LED
Option 2 (On/Off)	ON-OFF	1 LED
Option 3 (On/Off)	ON-OFF	1 LED
Option 4 (On/Off)	ON-OFF	1 LED
Option 5 (On/Off)	ON-OFF	1 LED
Option 6 (On/Off)	ON-OFF	1 LED
Option 7 (On/Off)	ON-OFF	1 LED
Option 8 (On/Off)	ON-OFF	1 LED
Alarm (On/Off)	ON-OFF	1 LED
Control (Local/Remote)	ON-OFF	
Reset	(ON)-OFF (momentary pushbutton)	

k.

CCU connector assignments	
C1	4 contact connector
C2	14 contact connector
C3	37 contact connector
C4, C5	DB-25 connectors

C1 -- AC Power	
Position	Function
1	AC +
2	AC -
3	Equipment Ground
4	NA

C2 -- Pan/Tilt			
Pos.	Function	Pos.	Function
1	Pan right	8	Pan feedback
2	Pan left	9	Tilt feedback
3	AC-	10	Preset -VDC
4	Tilt up	11	NA
5	Tilt down	12	AC+
6	AC-	13	AC-
7	Preset +VDC	14	Ground

C3 -- Camera			
Pos.	Function	Pos.	Function
1	Zoom	20	Option 3 N.O.
2	Z/F/I Common	21	Option 3 Common
3	Focus	22	Option 3 N.C.
4	Iris	23	Option 4 N.O.
5	Iris Override Common	24	Option 4 Common
6	Iris Override	25	Option 4 N.C.
7	Preset +VDC	26	Option 5 N.O.
8	Zoom Preset feedback	27	Option 5 Common
9	Focus Preset feedback	28	Option 5 N.C.
10	Preset -VDC	29	Option 6 N.O.
11	LP alarm	30	Option 6 Common
12	LP alarm	31	Option 6 N.C.
13	NA	32	Option 7 N.O.
14	Option 1 N.O.	33	Option 7 Common
15	Option 1 Common	34	Option 7 N.C.
16	Option 1 N.C.	35	Option 8 N.O.
17	Option 2 N.O.	36	Option 8 Common
18	Option 2 Common	37	Option 8 N.C.
19	Option 2 N.C.		

Note:
N.O. = Normally open
N.C. = Normally closed
NA = Not Available

C4, C5 -- Serial communication ports to and from external device.			
Pos.	Function	Pos.	Function
1	NA	14	NA
2	Transmit Data	15	NA
3	Receive Data	16	NA
4	NA	17	NA
5	NA	18	NA
6	NA	19	NA
7	Signal Ground	20	NA
8	NA	21	NA
9	NA	22	NA
10	NA	23	NA
11	NA	24	NA
12	NA	25	NA
13	NA		

Serial cables			
SCA1		SCA2	
DB-25 Pin	DB-25 Pin	DB-25 Pin	DB-25 Socket
2	2	2	2
3	3	3	3
7	7	7	7

Environmental

a. Each CCU shall operate in an ambient temperature environment of -10°C to 50°C.
b. Each CCU shall conform to MIL-STD-810D-516.1 and MIL-STD-810D-514.1 shock and vibration test.

CCU messages

a. Each CCU shall communicate through the C4 serial port with the following communication message codes:

DIREC-TION	MESSAGE	CHARACTER		DATA
		1ST CODE	2ND CODE	
Transmit	Alarm status	A	space	"0"-"7"
Receive	Status query	Q	space	NONE
Receive	Pan stop	p	space	NONE
Receive	Tilt stop	t	space	NONE
Receive	Zoom stop	z	space	NONE
Receive	Focus stop	f	space	NONE
Receive	Iris stop	i	space	NONE
Receive	Pan left	L	space	NONE
Receive	Pan right	R	space	NONE
Receive	Tilt up	U	space	NONE
Receive	Tilt down	D	space	NONE
Receive	Zoom in	I	space	NONE
Receive	Zoom out	O	space	NONE
Receive	Focus near	N	space	NONE
Receive	Focus Far	F	space	NONE
Receive	Iris open	J	space	NONE
Receive	Iris close	K	space	NONE
Receive	Iris manual	M	space	NONE
Receive	Iris auto	m	space	NONE
Receive	Set ID word	C	"1"-"4"	16-ASCII char.
Receive	Home position 0-9	H	"0"-"9"	NONE
Receive	Home position program 0-9	P	"0"-"9"	NONE
Receive	Option on 1-8	S	"1"-"8"	NONE
Receive	Option off 1-8	s	"1"-"8"	NONE
Receive	Enter Echo mode	E	space	NONE
Receive	Exit Echo mode	^]C	This sequence is not in a communication packet	

b. After receiving the "enter echo" command the CCU shall pass all characters from C5 to C4 and C4 to C5. The CCU shall disable all camera movement.
c. When the "exit echo" mode sequence is received on C4, the CCU shall return to normal operation.

Serial communications protocol

a. The communication protocol shall consist of 8 data bits, 1 stop bit and no parity.
b. Communication handshaking shall use XON/XOFF.
c. The communication packet shall contain the following items: ADDRESS, CODE, DATA, CHECKSUM, CR. The packet is sent as a string of ASCII printable characters. The ADDRESS, which has its $80 bit set in order to signal the start of the packet. The CHECKSUM is generated by Exclusive-ORing the ADDRESS, CODE, and DATA. The communication byte count shall be as follows:

ADDRESS	1
CODE	2
DATA	≥0
CHECKSUM	2
CR	1

d. The receiver will compute the CHECKSUM. If the computed CHECKSUM is correct the receiver will send ACK, otherwise the receiver will send NAK.

10-3.26 VIDEO ENCODER UNIT

General

a. A prototype of the video encoder unit (VEU) is not acceptable.
b. All equipment shall be off the shelf production units.
c. All equipment shall be new and not previously used.
d. The Contractor shall provide a manual per each unit ordered.

Acceptable equipment

The VEU shall be compatible and interoperable with the existing video decoder unit (VDU), Enerdyne Technologies Model DEC1000R5. No other VEU/VDU pairs shall be different or deviate from other pairs.

Qualifying specifications

a. Video encoding --

i. The VEU shall replicate the adaptive digital video standard (ADVS) for digital compression and transmission of video images.
ii. The VEU shall implement frame sensitive algorithms, joint photograhic experts group (JPEG) to perform frame updating. Motion sensitive algorithms motion picture experts group (MPEG) shall not be allowed.
iii. The VEU shall be compatible with integrated services digital network (ISDN) basic rate interface at 128 kbps and shall comply with bandwidth on demand interoperability group (BONDING) protocol.
iv. The VEU shall be compatible with Switched-56 digital service at 56 kbps.
v. The VEU shall be compatible with advanced digital network (ADN) service at 56 kbps.
vi. The VEU shall be compatible with T1 service at 1.544 Mbps.

b. Physical -- The physical size of the VEU shall be as follows:

Weight	9 kg, maximum
Height	135 mm, maximum
Width	483 mm, maximum
Depth	300 mm, maximum

c. Mounting --

i. The VEU shall be mountable in a standard EIA-310 equipment rack.
ii. Each VEU shall be designed and mounted in such a way that it is easily accessible for maintenance.

d. Primary power input and output requirements --

i. All electrical power distribution, service and wiring components shall be UL listed or equivalent and meet the requirements of the national electric code as well as these special provisions.
ii. Power input shall be 100 to 130 VAC at 60 Hz ±3 Hz.
iii. Maximum power requirement shall be 25 W at 120 VAC.

e. Local control facilities --

i. Local operator control of all essential features of the VEU shall be accomplished by the use of necessary discrete front panel controls and/or switches. Each VEU shall have a front panel status display.
ii. The VEU shall store operator set default parameters in EEPROM to retain system configuration after loss of power. These parameters shall be loaded into volatile RAM during operation where they may be modified by operator set operational parameters.
iii. The VEU shall have a front panel status display.

f. Remote control facilities --

i. The control/status ports shall be EIA-232 with selectable data rates of 1200 to 9600 bps and the connector shall be a DB-25 type.
ii. The control/status ports shall provide telephone dialing, remote and local diagnostics testing, and system configuration.
iii. The control/status port shall provide selection of any of the video inputs.
iv. The control/status port shall provide in-band dialing for all interfaces using the AT and/or V.25 bis command set.
v. The control/status port of the VEU shall override in-band control of the VEU via the VDU.
vi. The control/status port shall provide selection of all network interface data rates and/or services.
vii. The control/status port shall provide user selectable video resolution. Minimum resolution settings shall be 560 (high), 280 (standard), and 140 (low) pixels per line.
viii. The control/status port shall provide user selection of 480 lines interlaced (frame mode) or 240 lines non-interlaced (field mode).
ix. The control/status port shall provide user selection of the compression algorithm quantization levels (Q-factor).
x. The control/status port shall provide cropping of the encoded video image at minimum of 104 percent (overscan), 100 percent, 85 percent, and 63 percent.
xi. The control/status port shall provide control over image attributes including, but not limited to, color hue, tint, and saturation. Section of monochrome or color of the VEU digitized video stream shall also be possible.

g. Video interface requirements --

i. The VEU shall be capable of both color and black/white video operation without modification to the hardware. Minimum motion video resolution shall be 560 pixels x 240 lines for the 525 lines, National Television Systems Committee (NTSC) standard, 60 Hz, composite input. Motion handling capability shall be up to 30 frames per second.
ii. The video interface formats shall be the following:

Composite	525 line NTSC 60 Hz
Component	Y/C: Luminance / Chrominance

iii. The video input for the VEU shall be compatible with EIA-170 at 75 Ω impedance with Bayonet Nut Connector (BNC) type connectors and shall be provided as a minimum the following:

3 video inputs composite
3 video input Y/C

iv. All video inputs shall be software selectable from the front panel on the VEU and from the control/status port.

h. Network interface requirements --

i. The VEU shall have hardware and software selectable network bit rates with the following as a minimum: 56 kbps, 64 kbps, 112 kbps, 128 kbps, 384 kbps, 768 kbps and 1.544 Mbps (T1).
ii. The VEU shall have three network interfaces: EIA-530A, DS-1 (T1 service), and V.35.
iii. The VEU shall transmit compressed and digitized video at a minimum of 95 percent of the available channel bandwidth, whenever bandwidth is not used by telephone, camera controls and or remote diagnostics.

i. Diagnostic and alarm requirements --

i. The VEU shall have self-diagnostic features display on the front panel.
ii. The VEU shall blank video on loss of video input.
iii. The VEU shall regain video lost due to excessive temperature when the temperature has reduced to 69°C.

j. Telephone interface --

i. The VEU shall provide an RJ11 telephone jack for voice communication.

ii. The VEU shall provide 16 kbps bandwidth for telephony within the bandwidth allocated for video only when bandwidth is needed for telephone.

k. Camera control interface --

i. The camera control interface shall provide a half-duplex clear channel for camera control and status user data with the following requirements:

The port shall communicate at a user selectable data rate from 1200 to 9600 bps, asynchronous.
The port shall be EIA-232, and the connector shall be a DB-25 type.

ii. The VEU shall provide bandwidth for camera control within the bandwidth allocated for video only when bandwidth is needed for camera control/status data transmission.

l. Environmental --

i. Minimum operating temperature range shall be from -40°C to 70°C ambient, with guaranteed start up at -10°C. An environmental housing with air conditioning will not be allowed.
ii. Operating humidity shall be from 0 to 95 percent, non-condensing.

Accessory items

The following VEU equipment accessory items shall be supplied by the Contractor as specified in these special provisions:

a. Service and Operations manual describing the video VEU as ordered and in accordance with these special provisions.
b. EIA-530A cable assembly shall be provided to connect the VEU to the integrated services digital network terminal adapter (ISDN TA) unit with basic rate interface that is specified elsewhere in these special provisions.

10-3.27 INTEGRATED SERVICES DIGITAL NETWORK TERMINAL ADAPTER UNIT

General

a. Each integrated services digital network terminal adapter (ISDN TA) unit shall provide an interface between data terminal equipment (DTE) such as the video encoder unit (VEU) or video decoder unit (VDU) and ISDN.
b. Each ISDN TA unit shall include an internal network termination Type 1 device (NT1) interface and include Terminal Adapter functionality. No external NT1 shall be allowed.
c. A prototype unit is not acceptable.
d. Each ISDN TA unit shall be of the current standard production units.
e. Each ISDN TA unit shall be new and not previously used.
f. The Contractor shall provide a manual for each unit supplied.

Qualifying specifications

a. Operation --

i. Each ISDN TA shall support ISDN basic rate interface (BRI) service and shall provide three digital channels capable of simultaneous data and voice transmission via a standard telephone line. The three channels shall include two Bearer (B) channels at 64 kbps and one Data (D) channel at 16 kbps (2B+D).
ii. Leased operation shall support 1B (64 kbps) or 2B (128 kbps) clear channel synchronous configurations.
iii. At data rates over 64 kbps, the BONDING delay equalization protocol shall synchronize data over the two B channels.

b. Data rates --

i. Synchronous: 2.4, 4.8, 9.6, 19.2, 38.4, 48, 56, 64, 112, 128 kbps; selectable.
ii. Asynchronous: 0.3, 1.2, 2.4, 4.8, 9.6, 19.2, 38.4, 57.6, 115.2 kbps; selectable.

c. Interoperability -- The ISDN TA unit shall support communications with public switched 56 kbps services and switched 56 kbps channel service unit/data service unit (CSU/DSU) as well as other ISDN TA, ISDN terminal equipment, and BONDING compatible inverse multiplexers.
d. D-Channel switch compatibility -- AT&T 5ESS, NTI DMS-100, National ISDN-1.
e. Dialing --Dialing shall be supported in the following ways:

i. Manually from a front panel keypad.
ii. Automatically from up to ten stored numbers.
iii. Automatically through an RS-366 parallel dial port.
iv. Dialing over the DTE interface using the asynchronous AT command set.
v. V.25 bis in-band dialing over the DTE interface using V.25 bis commands.

f. DTE interface -- The ISDN TA shall provide both EIA-530A and V.35 interfaces. The interface to be used shall be selectable. A three meter male/female EIA-530 interface cable shall be provided with each ISDN TA.
g. Network interface -- Network termination shall be designed into the ISDN unit thereby eliminating the need for an external NT1. Connection to the network shall be made by a telephone company provided 2-wire and/or 4-wire 2B1Q U-interface which is connected directly to an eight-pin RJ45 modular jack on the rear panel of the ISDN TA unit. The ISDN TA unit shall provide two RJ45 modular jacks, where one jack shall be designated for dial-up ISDN and the other jack designated for leased ISDN. The dial-up ISDN and leased ISDN operational modes maybe integrated on a single RJ45 jack if the operational modes are user selectable.
h. Local control facilities --Local operator control of all essential features of the ISDN TA unit shall be accomplished by the use of necessary discrete front panel controls.
i. Remote control facilities -- Remote configuration and control of the ISDN TA unit shall be possible using the AT command set in-band over the DTE interface. Remote call setup and termination shall also be possible using V.25 bis in-band dialing.
j. Diagnostics requirements -- Each ISDN TA unit shall be able to perform a variety of tests that allow problems to be identified and isolated. Testing shall be supported manually from the front panel, or in-band from either the network provider or distant end unit. Internal error checking shall be available for both the local and a remote activated digital loopback.
k. Physical --

i. Each ISDN TA unit shall be secured and mounted on a shelf assembly.
ii. Each shelf assembly shall provide for a minimum of four mounting screws in order to mount the shelf assembly in 89 mm (2 rack units) of EIA-310 rack space.

l. Electrical --

i. Power input voltage shall be 115 VAC ±10 percent, 60 Hz.
ii. Power dissipation shall not be greater than 8 W.

m. Environmental --

i. Operating temperature: 0°C to 50°C, minimum.
ii. Storage temperature: -20°C to 70°C, minimum.
iii. Relative humidity: 0 to 95 percent, non-condensing.

10-3.28 CAMERA STATION

GENERAL

The Contractor shall furnish and install the following closed circuit television (CCTV) equipment at each camera station as described in these special provisions and as shown on the plans:

1. One camera unit.
2. One pan/tilt unit.
3. One CCTV pole.
4. One camera junction box (JCB).
5. One camera control unit (CCU).

6. One video encoder unit (VEU).
7. One integrated services digital network terminal adapter (ISDN TA).
8. Connectors and fittings as required.
9. Cable and conductors as required.

CABLES AND CONNECTORS

The camera unit cable assembly box mounting connector shall be mounted on one side of the JCB and shall be prewired to the 20 position terminal block as shown on the plans. The video signal pins of the camera unit cable assembly box mounting connector shall be terminated to a Bayonet Nut Connector (BNC) jack connector via Type RG-59/U coaxial cable stub.

The television control cable (TVC) and television power conductors (TVP) shall be wired to the 20 position terminal block as shown on the plans. The television control power cable (TVCP) cable shall go through but does not terminate inside the JCB. A watertight strain-relief box connector shall installed at the JCB hole for the TVCP cable.

INSTALLATION OF CAMERA STATION

The work to be done at each camera station, as shown on the plans, as a minimum, shall consist of the following:

1. Attach pan/tilt unit to the mounting plate.
2. Attach camera unit to the pan/tilt unit.
3. Install JCB junction box.
4. Terminate TVC and TVP inside JCB junction box.
5. Terminate television video cable (TVL) inside JCB junction box with a BNC plug connector.
6. Install camera unit cable assembly wiring harness (Type JC).
7. Terminate TVCP with pan/tilt mating connector.
8. Connect TVCP to the pan/tilt unit.
9. Terminate TVL inside controller cabinet with BNC plug connector.
10. Terminate TVP, TVCP and TVC with CCU mating connectors C1, C2 and C3, respectively.
11. Adjust limit stops of the pan/tilt unit as directed by the Engineer.
12. Adjust camera unit to provide the optimum picture for the full range of daylight and night time conditions as directed by the Engineer.

CAMERA UNIT MOUNTING

The camera unit shall be secured to the pan/tilt unit using the stainless steel bolts provided with the camera unit. Before each bolt is fastened, a locking type coating shall be applied to the threads. The coating shall lock the bolt and nut in place, making it impossible to turn the bolt or nut without tools. This coating shall last through and be effective through at least ten insertions and withdrawals of the bolt or nut.

The work to be done between the camera mount and the controller cabinet, as shown on the plans, as a minimum, shall consist of the following:

1. Install conduits and pull boxes as required up to the controller cabinet.
2. Install and terminate TVL, TVC, TVCP, and TVP as shown on the plans.

The work to be done at each CCTV controller cabinet, as shown on the plans, as a minimum, shall consist of the following:

1. Install CCU.
2. Connect TVC, TVCP, TVP and TVL to CCU via their respective connectors.
3. Install VEU.
4. Install ISDN TA.
5. Connect CCU to VEU.
6. Connect ISDN TA to VEU.
7. Install 8-position connecting block.
8. Connect ISDN TA to the 8-position connecting block.

The Contractor shall furnish all materials necessary to provide a complete and functional camera station in accordance with these special provisions. Miscellaneous equipment, and materials not mentioned but necessary to provide a complete and fully operational camera station shall be furnished by the Contractor as incidental to the work for which no additional

compensation will be allowed therefor.

All items furnished under this contract shall be new and shall be the latest version.

The Contractor shall be responsible for demonstrating proper operation of the camera station using test software and diagnostics which shall be provided to the Engineer as incidental items at no additional cost. Testing procedures are described elsewhere in these special provisions.

CAMERA STATION TESTING

Upon completion of work, each camera station shall be subjected to post-installation tests as outlined herein. All testing shall be performed by the District Electrical Systems Branch personnel, arranged by the Engineer and in the presence of the Contractor. The Contractor shall notify the Engineer in writing fifteen days prior to the scheduled testing. Upon receipt of the notification, the Engineer shall contact the Electrical Systems Branch at (510) 286-6142. The Contractor shall provide all necessary equipment required to access the CCTV equipment for testing.

The testing shall consist of five consecutive days of continuous satisfactory operation of each camera station. If any material and equipment furnished and installed by the Contractor in this project is found defective or otherwise unsuitable, or the workmanship does not conform with the accepted standards, the Contractor shall replace such defective material and equipment at no cost to the State.

Rejected material or equipment may be offered again by the Contractor for consideration provided all non-compliance has been corrected and pretested by the Contractor. After all defects have been corrected, the camera station shall be re-tested until five consecutive days of continuous satisfactory operation is obtained.

The post-installation tests shall consist of, but not be limited to, inspection and functional testing in accordance with these special provisions.

Inspection shall consist of, but not be limited to, verification of correct wiring terminations, correct cable interconnections, good workmanship and compliance with these special provisions.

Functional testing shall include, but not be limited to, the following:

a. Verification of all local mode CCTV operations using the CCU front panel controls.
b. Verify video signal output from CCU with a National Television Systems Committee (NTSC) monitor.
c. Verify the correct operation of the auto/manual iris and power zoom.
d. Verify the correct operation of the pan/tilt unit. The pan/tilt unit shall be functionally tested over 355 degrees in the horizontal plane and ±60 degrees in the vertical plane. The pan/tilt unit limit stops shall then be adjusted to optimize the camera viewing coverage of the freeway as directed by the Engineer.
e. Verify the correct operation of the preset positions.

10-3.29 CAMERA POLES

Camera poles shall conform to the provisions in Section 86-2.04, "Standards, Steel Pedestals and Posts," of the Standard Specifications.

10-3.30 CELLULAR DIGITAL PACKET DATA WIRELESS MODEM

The cellular digital packet data (CDPD) wireless modem shall be configured with the following major components:

A. Modem.
B. Power supply.
C. Modem mounting bracket and hardware.
D. Serial communication cable.
E. Antenna.

MODEM

All modems shall be configurable remotely through the wireless network and through the modem serial port. The Contractor shall configure all modems prior to acceptance. The Contractor shall provide the Engineer with the modem serial and security numbers 30 days prior to requiring the IP address. The Engineer will make available the service provider IP address and configuration parameters (if different from those listed below) after the serial and security numbers are provided to the Engineer by the Contractor. All modems shall be complete with all cables, conductors, hardware, antenna, and other equipment as required to make the system completely operational. Location and mounting of the equipment shall be as directed by the Engineer and details shown on the plans. The modem shall be fully compliant with PCCA STD-101.

Environmental Requirements

The operating temperature range of the modem shall range from -30°C to +70°C, with humidity from 5 percent to 95 percent (non-condensing) and have transmissions at 10 percent duty cycle above 60°C.

Physical Characteristics

The modem shall weigh less than 1 kg and have overall dimensions of less than 180 mm x 90 mm x 30 mm. The housing shall be constructed of anodized aluminum.

The modem shall have the following status indicators:

1. Power (on).
2. Channel Acquired.
3. Link Status.
4. Network Registration.
5. Received Signal Strength Indicator.
6. Transmit and Receive data.
7. Block Errors.

Operational parameters

The modem shall meet the following operational parameters:

Integrated TCP/IP	Full duplex
Transmit power	600 mW
Transmit frequency	824-849 MHz
Receive frequency	869-894 MHz
RF protocol	CDPD 1.1
Raw Data rate	19.2 kbps
Serial protocols	AT commands, SLIP, PPP
Transmit load	0.28 A at 12 V(dc) typical
Receive load	0.05 A at 12 V(dc) typical
Nominal operating load	4 W maximum
RF Antenna connector	50 Ω TNC
Serial interface	RS-232 DB-9F (1,200 to 38,000 bps)
Certification	Class I Division 2 (CSA)

Application Interfaces

The modem shall have the following standard interfaces:

1. The AT command serial character stream (uses TCP/IP stack).
2. Host TCP/IP stack communicates the modem using SLIP.
3. Computer terminal platform using Windows 98/2000/NT and Dial-Up Networking communicates with the modem using PPP.

Features

The modem shall have the following features:

1. 19.2 kbps raw data transfer rate minimum.
2. Full duplex transceiver.
3. 600 mW transmit power.
4. Integrated TCP/IP protocol stack with UDP.
5. Security such to prevent unauthorized access.
6. Includes a DC power cable at least 1 meter in length with a connector compatible with the modem power connector.
7. Packet buffering and forwarding feature that provides discipline to the output of the serial port. The packet forwarding time interval shall be configurable from a rate of 0 (undisciplined) to 400ms in increments of 100ms or less.
8. "Friends Only" access mode.

Configuration parameters
The modem shall be configured with the following parameters (major divisions separated by a blank line):

Parameter Name	Current Value
[\N] Side Preference	1: A Side only
[S110] Device IP Address	###,###,###,###
[S110] Device Port	12345
[S116] Service ID Preference	3: Don't Care
[S111] Service ID	1000/1000/1000
[S112] Channel List Mode	2: Hot Channel List
[S113] Channel List	0,0,0,0…
[3W] 3Watt Booster support	0:No Booster Attached
[*DSIDE] Disable Side Switch	0:Switch back to preferred side (default)
[#X] Debug Output	0:No Serial Debug Output
[#ZZ] Sleep Mode	0
[S0]TCP Auto Answer Mode	1:Enable TCP Server
[S7] TCP Establishment Timeout	20
[S50] Data Forwarding Timeout	1
[S51] Data Forwarding Character	0
[S53] Destination IP Address	0.0.0.0
[S53]Destination TCP/UDP Port	12345
[S53] Destination Connect Mode	T
[S210] AT Command Compatibility	1: Standard Modem Compatibility
[211] Ignore DTR	1: Ignore DTR
[MD]Startup Mode Default	0: AT Startup Mode [normal]
[MD] UDP Mode Default	0: Normal UDP
[S60] Telnet Echo Mode	0: No Telnet Echo
[S82] UDP Half Open Mode	2: Enable UDP Half Open
[S83] UDP Half Open Timeout	10
[AIP] Allow Any UDP IP	1: Allow Any UDP IP
[HOR] UDP Half Open Response	0: No RING Connect
[S220] Break on TCP connect	0
[S221] Delay Connect Response	1
[E] Command Echo	1: AT Command Echo On
[V] Command Response Mode	1: Verbose AT Responses
[Q] Quiet Mode	1: Quiet Mode On (No Result Codes)
[X] Call Progress Result Mode	0
[TCPT] TCP Inactive Timeout	1
[TCPS] Specify TCPT in Seconds	0: TCPT Units are Minutes
[TCPX] Allow TCP Suspension	0: No TCP Suspension
[*DATZ] Disable Reset on ATZ	0: Normal Reset [recommended]
[DAE] Disable AT Esc Sequence	0: Enable AT Escape Sequence

[RKEY] Radio Transceiver Keying	0: Disable Transceiver Keying
[\Q] Flow Control	0: No Flow Control
[S23] Baud Rate	9600
[S23] Data Bits	8
[S23] Parity	N
[MVOFF] Modbus-Variant Offset	1
[MVLEN] Modbus-Variant Length	0
[MVTYP] Modbus -Variant Type	0
[MVOPT] Modbus-Variant Option	0
[MVMSK] Modbus-Variant ID Mask	0
[FM] Friends Mode	0: Allow Any

System Compliance

The modem and associated firmware, software, hardware, protocol, and other features shall be fully and completely compatible with the existing CDPD network currently in use. The existing CDPD network utilizes the AT&T Wireless Services cellular system (band compatible with this modem) the AirLink Raven II wireless modem, and the AirLink Gateway. The Contractor shall demonstrate the compatibility to the Engineer by actual installation demonstration or by other means approved by the Engineer.

Installation

The installation of the modem shall be according to the plans, the manufacturer's instructions, and adjusted per field conditions with the Engineers approval.

Certificate of Compliance

The Contractor shall provide the Engineer with a Certificate of Compliance from the manufacturer in accordance with the provisions of Section 6-1.07, "Certificates of Compliance" of the Standard Specifications for all of the modems furnished for the project.

Warranty

The manufacturer shall provide a written warranty against defects in materials and workmanship for modems for a period of 12 months after installation for parts and labor. Replacement modems shall be provided within 5 days after receipt of failed modem at no cost to the State, except the cost of shipping the failed modem. All warranty documentation shall be given to the Engineer prior to installation. Replacement modems shall be delivered to Caltrans Maintenance Electrical Shop at 30 Rickard Street, San Francisco, CA 94134.

The software warranty shall be for one (1) year, including upgrades and feature enhancements.

POWER SUPPLY

The power supply shall be vertically mountable on a 483-mm standard rack rail using existing mounting hardware. An existing mounting hardware sample is available upon request; the Contractor may pick it up at 111 Grand Avenue, Oakland. The Contractor shall return the sample if it is not used in the installation. The power supply shall have provision to attach the modem power cable securely without the need for modifying the modem power cable.

The power supply shall meet the following requirements:

Power Cord	Standard 120 V(ac), 3 prong cord, at least 1 meter in length (may be added by Contractor)
Type	Switching mode type
Power Rated	40 W minimum with no minimum load required
Operating Temperature Range	From -30°C to +70°C
Operating Humidity Range	From 5 percent to 95 percent non-condensing
Input Voltage	From 85 V (ac) to 264 V (ac) or 120 V (dç) to 370 V (dc)
Input Frequency	From 47 Hz to 63 Hz
Inrush Current	Cold start, 25 A at 115 V
Output Voltage	12 V (dc), adjustable over a ±10 percent range
Overload Protection	From 105 percent to 150 percent in output pulsing mode
Over Voltage Protection	From 115 percent to 135 percent of output voltage
Setup, Rise, Hold Up Time	800 ms, 50 ms,15 ms at 115 V (ac)
Withstand Voltage	I/P-0/P:3 kV, I/P-FG:1.5 kV, for 60 seconds
Working Temperature*	70°C@30%
Safety Standards	UL 1012, TUV EN60950
EMC Standards	EN55022 Class B, EN61000-4-2, 3, 4, 5 and EN61000-3-2, 3

* Note: A substitute may be proposed by the Contractor which meets the 70°C environmental rating at a lower load percentage as long as the temperature rating is maintained at the maximum modem load and all other electrical specifications are met.

Certificate of Compliance

The Contractor shall provide the Engineer with a Certificate of Compliance from the manufacturer in accordance with the provisions of Section 6-1.07, "Certificates of Compliance" of the Standard Specifications for all of the power supplies furnished for the project.

Warranty

The manufacturer shall provide a written warranty against defects in materials and workmanship for power supplies for a period of 12 months after installation for parts and labor. Replacement power supplies shall be provided within 5 days after receipt of failed power supply at no cost to the State, except the cost of shipping the failed power supply. All warranty documentation shall be given to the Engineer prior to installation. Replacement power supplies shall be delivered to Caltrans Maintenance Electrical Shop at 30 Rickard Street, San Francisco, CA 94134.

MODEM MOUNTING BRACKET AND HARDWARE

The mounting bracket and hardware shall be stainless steel. The mounting bracket shall securely hold the modem in a vertical attitude with all cables and conductors installed. The mounting bracket shall contain the modem using a method that allows the removal of the modem without tools or without removing the bracket from its attachment to the cabinet frame.

D SERIAL COMMUNICATION CABLE

Where the modem is designed to interface with a Model 170E controller, the Contractor shall provide a communication cable known as the C2 cable. The C2 cable shall interface the Model 170E controller C2 connector and the CDPD modem and include all conductors and connectors required for that purpose. The CDPD modem connector shall meet EIA RS-232 standard using a DB-9 connector. The Model 170E controller end connector shall comply with AMP 201360-2-ND or equivalent. All pins in both connectors shall be gold plated. The cable shall have four No. 20 AWG conductors with (UL) Type CM shielded or AWM 2464 80C 300 Volts – C (UL) CMG. The cable shall be at least 1 meter long. The cable wiring shall comply with the following:

AMP 201360-2-ND -L to DB9-P - 2
AMP 201360-2-ND -K to DB9-P - 3
AMP 201360-2-ND -N to DB9-P - 5
AMP 201360-2-ND -D to AMP 201360-2-ND - H
AMP 201360-2-ND -J to AMP 201360-2-ND - M

ANTENNA

The antenna shall be the low profile type, and shall adhere to the cabinet using a factory installed double-sided waterproof acrylic foam adhesive. The coax cable shall be at least 1 meter in length and shall have a 50 Ω TNC connector on the modem end. In addition, the antenna shall meet the following requirements:

VSWR (at resonant point)	1.5:1 or less
Frequency	824-896 M Hz
Nominal Impedance	50 Ω
Gain	3 dB
Radiation Pattern	Omni-directional
Polarization	Vertical
Ground Plane Required	Yes, see note below

Ground plane requirements: The antenna shall require a reflective ground plane to function properly. The required ground plane shall extend beyond the antenna at least 20 cm in all directions.

10-3.31 SERVICE MANUAL REQUIREMENTS

The Contractor shall provide to the Engineer a minimum of one copy of service manuals for the camera unit, pan/tilt unit, camera control unit (CCU), video encoder unit (VEU), and integrated services digital network terminal adapter (ISDN TA) unit under this special provisions. Each manual shall contain the following sections and sub-sections.

General information section

a. A list of applicable subassemblies that comprise the specified equipment.
b. Overall description of the equipment design features (including all enhance features if applicable), performance, and applications.
c. Equipment specifications summary.
d. Equipment installation instructions.

Theory of operations section

a. Theory of operation of the standard equipment, with unique or unusual circuitry described in detail.
b. Theory of operation reflecting any modifications to the standard equipment.

Maintenance section

a. Recommended test equipment and fixtures, or minimum operational and performance requirements for appropriate test equipment.
b. Trouble shooting information and charts.
c. Removal and installation procedures for replacing assemblies and subassemblies, if not obvious or if improper sequencing of steps may result in component damage.

Replacement parts section

a. Each manual shall contain an equipment replacement parts list including electrical parts, mechanical parts and assemblies.
b. All semiconductors shall be identified by the supplier's numbers and by JEDEC numbers if applicable.

Diagram section

a. Schematic diagrams(s) identifying all circuit components and showing normal test voltages and levels.
b. An overall functional block diagram.
c. Detailed interconnecting diagram(s) showing wiring between modules, circuit boards and major components.
d. Pictorial circuit board layout diagram(s) showing both component placement and printed wiring detail.
e. Diagram(s) showing location of circuit boards and other subassemblies.

f. Exploded view diagram(s) of complex mechanical assemblies.

Physical requirements

a. All pages, including latest revisions, shall be securely fastened together between protective covers (loose-leaf ring binding is acceptable).
b. No page shall be subject to fading from exposure to any normal source of ambient lighting (ozalid reproduced pages are not acceptable).

10-3.32 TRAFFIC OPERATIONS SYSTEM EQUIPMENT TESTING

Prior to shipping to the project, the Contractor shall submit the following items to the State of California, Department of Transportation Laboratory, 5900 Folsom Blvd., Sacramento, CA 95819 for acceptance testing:

1. Camera unit
2. Pan/tilt unit
3. Camera control unit (CCU)
4. Video encoder unit (VEU)
5. Integrated services digital network terminal adapter (ISDN TA)
6. Extinguishable Message Sign Panels

Approximately 30 days will be required for the testing. The Contractor will be notified upon completion of the testing and shall arrange for delivery of the equipment to a storage location designated by the Contractor. The costs of such testing and the transportation to and from the Laboratory shall be borne by the Contractor.

10-3.33 CITY OF SAN FRANCISCO ELECTRICAL SPECIAL PROVISIONS

MAINTAINING EXISTING CITY TRAFFIC SIGNAL AND STREET LIGHTING SYSTEMS

The Contractor shall notify the Engineer and the Bureau of Light, Heat and Power of the City and County of San Francisco, Phone (415) 554-0730, at least five days prior to performing any work on their existing street lighting system. All splicing of new to existing conductors or disconnection of existing conductors shall be done in the presence of the Engineer and as directed.

Disconnection of any existing street lighting shall not be permitted except as directed by the Engineer.

The Contractor shall notify the Engineer and the Traffic Signal Division, 901 Rankin Street, San Francisco, (415) 550-2736, at least 24 hours in advance of removing, disconnecting or doing any work on any existing traffic signal equipment, wiring or conduit, or placing in service any traffic signal equipment installed under this contract. In this contract, the Contractor shall install all new traffic signal conductors but the City personnel shall splice and connect new traffic signal conductors to the existing phase conductors from the controller in pull box as shown on the plans.

The Contractor shall notify the Engineer and the Bureau of Light, Heat and Power, (415) 554-0730, at least 24 hours prior to performing any work on the existing lighting. Prior to starting work for electrolier foundation on South Van Ness, the Contractor shall contact the Engineer and the City Engineer at (415) 554-1688 and verify that the base plate of the City-furnished electrolier is compatible with the foundation anchor-bolt dimensions shown in the plan. The Contractor shall make arrangements to purchase anchor bolts and to pick up the City-furnished electrolier from the Yard on 69 Bryant Street to the construction site when needed.

Traffic signal system shutdowns shall be limited to periods between the hours of 9 a.m. and 4 p.m. The Contractor shall install or reinstall temporary wiring, at his own expense, in the event it is foreseen that the Contractor cannot complete the work to restore any existing traffic signal to normal service before 4 p.m. Street lighting system shall be in continuous service from 4 p.m. of each day to 9 a.m. of the following day.

The Contractor shall furnish and install whatever temporary or permanent conduit, overhead and other wiring and equipment, as necessary, shall make all connections and do other work necessary to maintain normal signal and street lighting operation and at the conclusion of the need therefor, shall remove all temporary facilities from the site.

The Contractor shall be completely responsible for the maintenance and continuity of operation of any temporary electrical facility installed.

Lamps in traffic signal heads installed or relocated by the Contractor that burn out during the life of contract will be replaced by the City.

Lamps in street lighting luminaries installed, relocated or worked on by the Contractor that burn out during the life of the contract shall be replaced at the Contractor's expense with new, approved equal lamps.

The cost of electrical energy for any temporary facility will be borne by the City but the Contractor shall bear all costs of any temporary service connections.

Vehicular and pedestrian signals shall be covered until activated for operation.

Full compensation for maintaining existing traffic signal and street lighting in operation shall be considered as included in the contract lump sum price paid for modify signal and lighting (city) at the various locations and no additional compensation will be allowed therefor.

All the work for maintaining existing traffic signal and street lighting in operation shall be done as incidental work to traffic signal work.

FOUNDATIONS

Concrete for foundations for city street signal and light poles shall conform to "Classes of Concrete," of these special provisions. No pre-cast foundations shall be allowed.

Concrete for foundations shall conform to CTSS Section 90-10, "Minor Concrete" and these special provisions, shall contain not less than 669 Tonne per cubic meter, unless noted otherwise on the plans.

Foundations for street light pole shall be installed as per SFPDW drawing A—27,029 CH 2.

CONDUIT

The conduit for city street lighting and traffic signal work shall be of rigid steel hot dip galvanized after fabrication. The conduit shall comply with these special provisions and shall meet the requirements from: ANSI C80, NEMA FBI, UL, and NEC,

Zinc primer paint on conduit threads and damaged conduit surfaces shall conform to Section 86-2.05C, "Installation," of CTSS, except that the use of spray cans will be permitted.

Conduits shall not be installed at a depth greater than one meter below pavement surface, nor 760 mm below ground surface in unpaved areas; and minimum depth of conduit shall be 610 mm in roadway areas and 460 mm in sidewalk and unpaved areas.

Rigid Steel Conduit, Galvanized

General.--The Contractor shall furnish and install galvanized rigid steel conduit complete with fittings and appurtenances, where and as shown on the plans or where required, including all excavating, backfilling, restoring pavement, and other incidental work necessary or required for a complete, legal and satisfactory installation.

Material.--Rigid steel conduit, including couplings, elbows, and nipples, shall be new, first quality, standard weight, wrought steel, galvanized on the exterior and interior surfaces and furnished with plastic thread protectors. Galvanizing shall be by hot-dipping, electroplating, sherardizing, or metallizing process, and shall meet the latest requirements of the National Electric Code. Each length shall bear the label of the Underwriters' Laboratories, Inc., and the name of the manufacturer.

All surfaces of conduit and fittings shall be free of obstructions, projections, roughness, blisters, scale, sharp edges and rust.

All conduit fittings, such as couplings, elbows, outlet boxes, junction boxes, caps and locknuts, shall be threaded fittings, and, together with covers therefor, shall be galvanized ferrous material.

Covers shall be furnished with neoprene gaskets cemented thereto and stainless steel screws. Gasket cement shall be of the type approved for automotive engine application. Non-cemented surfaces of gaskets shall be coated with a lubricant containing silicon and of the type approved for application on rubber-like materials.

Hot dipped galvanized rigid steel conduit shall be used for all installation underground, outdoors above ground, and cast in concrete.

Installation.--Rigid steel conduit shall not be cut with pipe cutters but shall in all cases be cut with a hack saw. Both ends of every length and piece of conduit shall be carefully reamed open to the full diameter, and all burrs and sharp edges shall be removed. Threads shall be cut clean and true with sharp dies. No connections shall be made with defective threads. No pipe fittings, except caps, shall be used. Three piece union couplings shall be used at each point of conduit union. All conduit and screwed fittings shall be securely tightened and installation made in a workmanlike manner.

The external threads only of all steel conduit and fittings, except at grounding bushings, shall be well painted with conductive pipe joint compound before assembly, so that the compound will not be forced into the conduit in tightening the joints. The heating of any metallic conduits for the purpose of bending is prohibited.

All conduit, including existing conduit intended for reuse, damaged on the job, before and during installation, shall not be used in the work, and shall be removed from the job site immediately.

If an existing pipe, duct or duct bank is in the path of, or obstructs the laying of the underground conduit at normal depth, and if such obstacle extends more than 1.2 m, the conduit shall be installed as directed by the Engineer. If such obstacle extends only to a depth of 1.2 m or less, the conduit shall cross 300 mm below the obstacle.

Conduit shall be brought into pull boxes and junction boxes in such a manner that sufficient space is allowed for proper bonding of the conduits. All conduit shall be installed so that the cable or wire will not be damaged in pulling.

After installation, the Contractor shall clean out all new and reused conduits by pulling a mandrel or steel brush, approved by the Engineer, through each run. At all stages of the work, everything possible shall be done to prevent foreign material from entering conduits.

All ends of conduit not immediately connected or used shall be capped. After conductors have been installed, the ends of conduits terminating in pull boxes shall be sealed with an approved type of sealing compound.

Conduit fittings shall be installed with the cover facing the installer and so that the cover screws are accessible and not obstructed.

Where existing conduits are shown on the plans to be reused and any portions thereof are damaged or the ends and terminal elbows thereof are rusted or lack threads, the Contractor shall furnish and install conduit, elbows and nipples to replace the existing conduit. Such conduit replacement will be paid for as extra work. Such extra work will be approved only if, in the opinion of the Engineer, the Contractor has made every reasonable effort, including the use of compressed air and approved lubricants and solvents, to use the existing conduits. The extra work will be subject to the limitation that work to the extent specified to be alterations shall be done as incidental work.

Underground.--The Contractor shall lay underground conduit in open trench.

If jacking of conduit is employed, inspection holes shall be opened, as required, for the Engineer to determine compliance with the requirements for depth and line.

Except as hereinafter specified, conduit shall not be installed at a depth greater than one meter below pavement surface, nor 760 mm below ground surface in unpaved areas; and minimum depth of conduit shall be 610 mm in roadway areas and 460 mm in sidewalk.

Where parallel runs of conduits are installed in a common trench, such conduits shall have a minimum separation of 50 mm.

Where underground conduit changes direction, long radius sweeps shall be used instead of short bends, and in no case, except at foundations or where otherwise specified, shall a bend radius of less than 760 mm be used. Bends at foundations or other underground structures shall be of maximum possible radius, in no case less than 12 times the internal diameter of the conduit. Conduit shall not be flattened in bending, and shall be free of kinks and indentations. In addition, unless otherwise directed, the maximum number of bends in any conduit run shall be as follows: a run of conduit between the bases of standards and controller pedestals shall not contain more than the equivalent of two 90 degree and one 45 degree bends; a run of conduit between pull or junction boxes shall not contain more than the equivalent of three 45 degree bends; a run of conduit between the base of a standard or controller pedestal and pull or junction box shall not contain more than the equivalent of one 90 degree and one 45 degree bend.

PULL BOXES

Pull boxes and covers for city street lighting and signals shall be precast reinforced concrete. All details and dimensions shall be per details shown on E-23 on the plans. Crushed rock pad and grout in the bottom of the pull boxes shall not be allowed. Fuse and fuse holder shall be installed in the lighting circuit as per E-24and E-25.

Pull box covers for city lighting and traffic signals shall not have the "CALTRANS" cover marking.

CONDUCTORS AND WIRING

Conductors for city street traffic signal shall be Type UF. Conductors for street lighting shall be Type THW. No. 8 and shall be stranded copper; No. 14 through No. 10 shall be solid copper. Wiring from the luminaire to the nearest pull box shall be the same size.

Traffic signal wires for city street signal shall be color coded and tagged in accordance with the following schedule:

	Phase	Base Color	Stripe and Tag
Vehicle Signal	A or (2,6)	Red, Yellow, Brown	None
Vehicle Signal	B or (4,8)	Red, Yellow, Brown	White
Signal Common		White	None
Spare		Black	None

All field wires shall be grouped according to phase and labeled according to signal location and movement. The labels shall be weather resistant nylon type.

Installation.--The installation of any wiring in the conduit shall not take place until the Contractor has demonstrated to the Engineer's satisfaction and received approval that the Contractor and the Contractor's employees have all means necessary to clean and prepare the conduits for the installation of wiring therein.

If the existing strapping or lacing of wiring is disturbed in the course of work, the Contractor shall replace or restrap as applicable.

Splicing.--All splicing devices shall be UL approved. All splicing devices of the correct size range for the wire being used. All splices shall be wrapped with one wrap of rubber splicing tape (Scotch 130C or equal), taped with four wraps of plastic electrical tape(Scotch 33+ or equal), and coated with a waterproofing coating (Scotchkote or equal). Splicing shall conform to the details per SPDPWSF, No. 43665.

The Contractor shall install the specified wiring in the conduit without splicing in the adjacent pull box and as noted on the plans. The wiring once connected to the relative signal head, shall form a continuous run from the signal head to the splicing pull box. The Contractor shall pull new wiring, at the Contractors expense, when it is determined that the unnecessary splicing has occurred.

BONDING AND GROUNDING

Steel standards with hand holes providing access to the conduit ends shall be bonded to the conduit with a grounding conductor terminated in a screw- type copper box- shaped terminal.

The bonding and grounding jumpers shall be a continuous length of No 6 AWG bare stranded copper wire.

In multiface signal heads bonding conductor shall be run to one face only.

The bonding conductor shall be attached the bottom section of the signal face, using screw- type copper box-shaped terminal, secured to the housing of the signal face with round head stainless steel machine screw, a stainless steel internal tooth lockwasher and stainless steel nut.

SIGNAL MOUNTING ASSEMBLIES

Signal mounting shall be constructed as per applicable details shown on E-26 and California Transportation Standard Plans (CTSP): ES-4A, ES-4B, ES-4C, ES-4D and ES-4E, as applicable; except as superseded by other contract plans or as needed to accommodate special mounting configurations. All signal frames shall consist of 41 GRC standard steel pipe and fittings, shall be hot-dip galvanized before assembly, with the exception of bronze terminal compartment, bronze slip fitter, and bronze pole clamps, and shall be watertight and free of sharp edges or protrusions which might damage conductor insulation. Before assembly any cut pipe threads shall be coated with zinc primer paint as specified in Section 86-2.05C, "Installation," of CTSS.

Each U-bolt type pole clamp shall consist of a cast bronze pole plate drilled and tapped for 41 GRC pipe thread, a galvanized 13 mm U-bolt to fit the perimeter of the pole and stainless steel nuts and shake proof washers. Portions of the pole plate shall be hinged for adapting the plate to various pole contours and shall be equipped with bolt openings through which the ends of the U-bolt shall be installed.

Elbows, trees, crosses and slip fitters at the bottom of signal faces shall have 72 equally spaced serrations on the upward facing outlet to match serrations on the bottom of the signal housing. A galvanized steel washer (70 mm O.D., 50 mm I.D., 18 GA) and a neoprene washer (70 mm O.D., 50 mm I.D., 3.2 mm thick) shall be furnished and installed at the top of each signal. The neoprene washer shall be next to the signal housing with the galvanized steel washer above. Signal housings shall be attached to fittings by use of hex head lock nipples. When tops of signal housings are not attached to framework, the hole shall be closed with an ornamental cap, locknut, metal washer and neoprene washer. After all adjustments have been made and all connections are fully tightened, duct sealing compound shall be applied externally to all joints at the top of the signal to make it watertight.

The Contractor shall drill a wiring entry hole on pole to the bottom clamp of each side-mounted signal bracket and to each pedestrian push button station for all internal wired poles without such suitable entry holes. Core drill shall be used for all hole drilling on concrete poles. Care shall be taken not to damage or cut the existing reinforcing steel inside the concrete standard. Part of reinforcing steel exposed during drilling shall be painted with corrosion resistant paint as soon as possible and on the same day. The height for pedestrian signal is 2.14 m and for traffic signal is 3.2 m from the bottom of framework to grade unless otherwise noted. The vertical axis of each signal shall be truly vertical when installation is complete. The Contractor's attention is directed to the need for different length horizontal 38 mm pipe nipples top and bottom on poles that are tapered, raked or are otherwise non-vertical at the signal mounting places. It is expected that one horizontal nipple, top or as appropriate, shall be, in the field, shortened and rethreaded as needed to get a tight rigid vertical installation.

Set screws in slip fitters shall have square heads.

SIGNAL POLES

The traffic signal poles shall be installed as per CTSS Section 86-2.04 and CTSP ES-7B, ES-7M, ES-11 as applicable.

STREET LIGHTING

The lamp for the luminaire shall be clear high pressure sodium vapor with mogul bases manufactured by General Electric, Philips, Sylvania, or equal. Align, mount and level lighting fixtures uniformly.

Steel street light standard only shall be Ameron Series Catalog No. PL 286, Union Metal Catalog No. 5809-B, Velmont Catalog No. DS36800A286 or approved equal.

Street light pole heights shall conform to the applicable standard plans. Street light bracket arm lengths shall conform to the applicable standard plans. Alternate bracket arm lengths shall require specific approval of Bureau of Light, Heat and Power (BLHP) by variance. The concrete footing requirements shall conform to the requirements of E-28 SFDPW, No. A27,029.2 Ch 4 for steel standards. The class of concrete used for foundation shall be Class 7-4000-11/2 with 102 mm maximum slump. The base leveling requirements shall conform to the requirements of E-28 SFDPW, No. A27,029.2 Ch.4 for steel street light standards.

Cut off lenses and devices shall require specific approval of BLHP by variance.

Install lighting fixture at location indicated and in accordance with manufacturer's instructions, complete with lamps, hangers, brackets, fittings, and accessories, ready for operation as indicated. Each street light shall have a fuse holder in its base and shall conform to E-25 SPDWSF, No. 49092, Ch. 1, "Street Light Service and Circuit Requirements". The wiring for the street light shall conform to the requirements of E-25 SPDPWSF, No. 49092, Ch. 1, "Street Light Service and Circuit Requirements". Align, mount, and level lighting fixtures uniformly. All splices for street lighting shall be made in accordance with E-24 SPDPWSF, No. 43665, Ch. 2.

The Contractor shall notify (BLHP), (415) 554-0730, at least 24 hours prior to performing any work on existing lighting.

Prior to completion of street lighting work, the Contractor shall notify BLHP for final inspection before acceptance of newly installed street lights for maintenance. The Contractor shall submit as–built drawings to BLHP.

Photoelectric Controls.--

For street lights equipped with photoelectric control, the photocell shall be Type IV consisting of a photoelectric unit which plugs into an EEI-NEMA twist lock receptacle integral with the luminaire. The photoelectric controls shall be operable within a minimum voltage range between 105 and 280 volts. All photoelectric controls shall be oriented to the north. Photoelectric controls for luminaires shall be Dark To Light Model #D124 or approved equal having an instantaneous turn on at 0.10 to 0.15 +.03 lux 1 to 1.5 +0.3 foot-candles and having a turn off/on ratio below 3:1.

DELIVERY OF SALVAGED EQUIPMENT TO CITY YARDS

Removing, reinstalling or salvaging electrical equipment shall be in accordance with Section 86-7 of CTSS, "Removing, Reinstalling or Salvaging Electrical Equipment," and these special provisions.

The Contractor shall deliver the street lighting pole specified to be salvaged as City property to the Bureau of Light, Heat and Power, 639 Bryant Street, San Francisco, CA 94107 and stockpiled.

The Contractor shall furnish the Engineer with a receipt dated and signed by City Yard personnel stating the number, description and condition of materials delivered.

Appointments for the delivery of salvaged equipment shall be made twenty-four (24) hours in advance:

Traffic Equipment -The Traffic Signal Division
Tel. No. (415) 550-2736
Street Lighting Equipment
Tel. No. (415)495-5576

If existing equipment, required to be salvaged, is damaged by the Contractor or by others when such equipment is within the Contractor's control, repairs shall be made in accordance with "Damage to Work or Property" of these special provisions.

If repairs, required to be made by this Section of these special provisions, are not approved by the Engineer, the respective equipment shall be considered as lost. Deduction from final contract payment shall be made as determined by the Engineer.

The listing of the above equipment and payment adjustments does not prelude the City from making claims or adjustments for other existing equipment which may be lost or damaged by the Contractor.

DAMAGE TO WORK OR PROPERTY

The Contractor shall be responsible for the safekeeping of, and shall protect, the work and materials from damage due to the nature of the work, the action of the elements, the carelessness of other contractors, or from any other cause whatsoever, until acceptance of the work. Should any such damage occur, the Contractor shall repair and leave the work in a condition satisfactory to the Engineer in every particular at the Contractor's expense.

Neither the City nor any of its officers, employees or agent assumes any responsibility for collecting indemnity from the person or persons causing damage to the work of the Contractor.

Any damage, arising from or in consequence of the performance of the contract, to tracks, pavements, curbs, landscaping, sidewalks, footings, walls, stairs, fences, sewerage and drainage structures, mains, pipes, valves, conduits, poles, wires, transformers, to adjoining work, or to any other improvement or property above or below the surface of the ground, whether private or public, shall be repaired at once at the Contractor's expense, or upon the occurrence of such damage the Contractor shall obtain from the owner of the damaged property a release from liability for such damage. If the Engineer requires such repair to be made prior to the execution of any part of the work included in the contract, the Engineer will so notify the Contractor who shall delay or discontinue the performance of that part of the work until the necessary repair has been made. Such delay shall not be considered unavoidable, and no extension of time for completion of the contract will be granted therefor. When ordered by the Engineer to make any such repair, the Contractor shall start work thereon within forty-eight hours and shall prosecute the same with diligence to completion. Failure to comply with such order or failure to make immediate emergency repairs which are necessary in the best interest of the City or of the public shall give the Engineer the authority to cause such repair to be made and to deduct the cost thereof from any money due, or which may become due, to the Contractor.

Repair or replacement of damaged work or property by the Contractor shall return such work or property to at least the condition before the damage, with respect to quality, strength, appearance, serviceability for use intended, and finish.

The Contractor shall promptly report to the Engineer and to the Contractor's Insurance Carrier with copies to the Engineer, all claims submitted by third parties for damages to property alleged to have been caused by project work, and shall submit monthly status reports listing all of these claims until all claims are settled or withdrawn.

The Contractor shall take immediate action to mitigate or correct any damages when in the opinion of the Engineer these damages present a hazard to persons or property. When no emergency exists, corrections shall be made as soon as the Engineer has determined that progress of the work will not cause further damage.

The Engineer may withhold sufficient funds to cover 125 percent of the estimate of the cost of repairs. These funds shall be released after receipt of a statement signed by the claimant indicating that the damage has been repaired or other settlement made to the satisfaction of the property owner.

CORRECTION OF DEFECTS AFTER ACCEPTANCE

All necessary repairs and replacements to remedy in a satisfactory manner any and all defects in the work, or damages resulting from such defects, due to faulty materials or workmanship, or due to disturbance of or damage to City improvements by the Contractor's operations under the contract and contrary to the specifications, or due to other failure to comply with the specifications shall be at the Contractors expense, these defects are defined as:

a) in any part of the surface work done under the contract, or in surface improvements of the City such as pavements, curbs, walks, tracks, walls, stairways, poles, mechanical and electrical equipment, materials, appurtenances and accessories, or other surface structures provided that such defect or defects be detected within the period of this contract;
b) in any part of the subsurface work done under the contract, or in subsurface improvements of the City not included in the work under the contract, such as sewers, side sewers, culverts, other drainage structures, pipes, valves, conduits, conductors, or other subsurface structures, provided that such defects in such subsurface work, or disturbance of or damage to, said other improvements be detected within the period of this contract.

Should the Contractor, after written notification by the Engineer, fail to remedy promptly any such defect occurring as set forth hereinbefore under a) or b), or should the best interest of the City require an immediate remedy without the delay incident to such notification, the Engineer may cause such repairs, replacements or other remedy to be made, and the expenses so incurred, limited in case b) as provided hereinafter, shall be chargeable to, and shall be paid by, the Contractor, provided that such expense so incurred by the Contractor, or incurred by the City and paid by the Contractor, on account of disturbance of or damage to City improvements occurring as set forth under b) next hereinbefore, shall not exceed an amount equal to 50 percent of the contract cost of all work to be done under the terms of the specifications, or such other amount as may be set forth in the special provisions, and further provided that the liability of the surety on the faithful performance bond, on account of such disturbance of or damage to City improvements occurring as set forth under b) next hereinbefore,

shall likewise not exceed 50 percent of the contract cost of all work to be done under the terms of the specifications, or such other amount as may be set forth in the special provisions.

Nothing in this Section shall be construed as a waiver, or impairment of any of the City's rights under the contract, or of any other recourse provided by law.

PROGRESS SCHEDULE

General.--Prior to starting the work, the Contractor shall submit to the Engineer two (2) copies of a progress schedule showing his proposed sequence of operations in the performance of the work, and the estimated dates of starting and finishing the various major parts of the work. The progress schedule shall conform to the specified time for the completion of the work; shall show a reasonable and orderly work sequence that will preclude excessive times for completion of any part thereof; shall show and be in accordance with the order and delivery dates for equipment and materials requiring special fabrication or otherwise not readily available for purchase and affecting, or critical with respect to, such time of completion; and shall be subject to the approval of, and modification by, the Engineer.

The submission of an amended schedule shall not relieve the Contractor of the responsibility for the notification required by Section 6.8 of the San Francisco Administrative Code which Section is included in "Extensions of Time Allowed for Completion of Work," in these special provisions.

Format for Progress Schedule.--The format to be used for the submission of progress schedules shall be the applicable of the following:

I: IF THE TIME ALLOWED FOR COMPLETION IS LESS THAN 41 WORKING DAYS, THE FOLLOWING IS APPLICABLE.--The progress schedule and any subsequent revised schedule may be submitted in the form of a written statement outlining the proposed operations.

II: IF THE TIME ALLOWED FOR COMPLETION IS MORE THAN 40 AND LESS THAN 201 WORKING DAYS, THE FOLLOWING IS APPLICABLE.--Within 10 calendar days after the official commencement date, the Contractor shall submit to the Engineer for approval 3 copies of his proposed progress schedule prepared on a City-furnished standard form. Copies of this form are available from the Construction Management Division.

The progress schedule shall show the order in which the Contractor proposes to carry out the work, and the dates on which the Contractor shall start and complete the salient features thereof, including procurement of materials, plant, and equipment.

A revised schedule shall be submitted when one or more of the following conditions occur:

a. Progress falls behind schedule and the Engineer requests in writing, a revised schedule;
b. A Change Order significantly affects the contract completion date or the sequence of activities;
c. The Contractor requests an extension of time of 15 working days or more.

EXTENSIONS OF TIME ALLOWED FOR COMPLETION OF WORK

Extensions of the time allowed in the special provisions for completion off the work shall be in accordance with and pursuant to the provisions of Section 6.8 of the San Francisco Administrative Code as follows:

"SECTION 6.8. CONTRACTOR TO GIVE NOTICE OF DELAY; NOTICE TO CONSTITUTE APPLICATION FOR EXTENSION.--The Contractor shall promptly notify the awarding officer, board or commission in writing of all anticipated delays in the prosecution of the work and, in any event, promptly upon the occurrence of a delay, the notice shall constitute an application for an extension of time only if the notice requests such extension and sets forth the Contractor's estimate of the additional time required together with a full recital of the causes of unavoidable delays relied upon. The awarding officer, board or commission may take steps to prevent the occurrence or continuance of the delay, may classify the delay as avoidable or unavoidable, and may determine to what extent the completion of the work is delayed thereby.

WORK AT UTILITY FACILITIES

The Contractor shall conduct work in manholes, vaults, handholes, and pull boxes of the Pacific Bell Company, the Pacific Gas and Electric Company, the Public Utilities Commission of the City and County of San Francisco, the Department of Electricity, and in all other such facilities not owned by the Department of Public Works, in strict accordance with the requirements of the owners thereof. The Contractor shall notify the owners of manholes, vaults, handholes, and pull boxes at least 48 hours before commencing work therein.

The Contractor shall not commence the installation of conduit into any manhole, vault, handhole, or pull box until an authorized representative of the owner thereof has designated the point of entry of the conduit. The Contractor shall install the conduit where designated.

Conduit installed to utility company manholes or handholes shall terminate within the wall thereof at a point 19 mm from the inside face of wall. The manhole or handhole wall shall be refinished and rounded off with Class B mortar to conform to the interior surface.

The Contractor shall not connect or disconnect any wire or cable, except that exclusively for traffic signal control, in any such manhole or vault.

All persons entering or leaving manholes or vaults shall do so only by ladders, so as to avoid damage to cables and other facilities.

Suitable barricades shall be placed around each open manhole, handhole, or pull box, and a flagman shall be stationed at the manhole during the entire time the manhole cover is off, in accordance with the applicable requirements of "Flagman," of these special provisions.

FLAGMAN

In order to avoid danger and delay to the public, the Contractor shall, during the entire time of any approved temporary use of any part of the roadway specified to remain open for traffic, provide competent flagmen, whose sole duty shall be to direct and control the movement of traffic through or past the work, as applicable.

The flagmen shall be provided with appropriate apparel and equipment and shall use hand signals and equipment in accordance with the California Department of Transportation "Manual of Traffic Controls, Warning Signs, Lights and Devices for Use in Performance of Work Upon Highways."

CLASSES OF CONCRETE

Portland cement concrete shall be composed of Portland cement, fine aggregate, coarse aggregate, admixtures if used, and water, proportioned and mixed as specified, and the various classes of concrete shall conform to the following limiting requirements:

Class	Min. kg/m^3 of concrete	Min. strength MPa at 28 days (f'c)	Max. size of coarse aggregates in mm	Slump in mm
7-4000-3/4	390	27.6	19	100
6-3000- 3/4	334	20.7	19	100
5.5-2500-3/4	306	17.2	19	100

The class of concrete used shall be as specified. If the concrete class is not specified, Class 6-3000-3/4 shall be used.

Where concrete containing 280 maximum size aggregate is specified, but reinforcement clearances or structural dimensions will not permit the use of 280 aggregate, the Contractor, with the approval of the Engineer, may substitute concrete of like strength with 19 maximum size aggregate. Any additional cost will be paid for by the State as extra work.

The weigh master's certificate, delivered to the Engineer with each load of concrete, shall state the number of kilogram of cement per cubic meter.

Should the quantities of ingredients designed to produce a cubic meter of concrete result in a volume (yield) greater or less than one cubic meter, the amounts of fine and coarse aggregate shall be changed as necessary to maintain the required quantity of Portland cement in each cubic meter of concrete.

The slump of concrete shall be determined in accordance with the requirements of the ASTM "Standard Method of Test for Slump of Portland Cement Concrete, " Designation C 143, which is a slump cone test, or by the "Kelly Ball" method of test. For any batch of concrete, the results of the "Kelly Ball" method of test will be approved equivalent of the required slump. Any concrete not meeting the slump requirements tabulated in the table set forth herein before shall be immediately removed from the site of the work.

10-3.34 REMOVING, REINSTALLING OR SALVAGING ELECTRICAL EQUIPMENT

Salvaged State electrical materials shall be hauled to Caltrans Electrical Maintenance Station, 30 Rickard Street, San Francisco, CA 94134, (415) 330-6509 and stockpiled.

The Contractor shall provide the equipment, as necessary, to safely unload and stockpile the material. A minimum of 2 working days' notice shall be given prior to delivery.

10-3.35 PAYMENT

Full compensation for hauling and stockpiling electrical materials shall be considered as included in the contract price paid for the item requiring the material to be salvaged and no additional compensation will be allowed therefor.

Full compensation for flashing beacon system, City lighting standards shown on E-3, and electrical service (irrigation) shall be considered as included in the contract lump sum price paid for lighting and sign illumination and no separate payment will be made therefor.

The contract lump sum price paid for traffic operations system shall include full compensation for furnishing all labor, materials (except items covered by other bid items), tools, equipment, and incidentals, and for doing all the work involved in installing traffic operations system, complete in place, including all the poles, manuals and testing, as shown on the plans, as specified in the Standard Specifications and these special provisions, and as directed by the Engineer.

Full compensation for each of the following items shall be considered as included in the contract lump sum price paid for the work being done and no separate payment will be made therefor.

1. Camera unit.
2. Pan/tilt unit.
3. Camera control unit (CCU).
4. Video encoder unit. (VEU)
5. Integrated services digital network terminal adapter (ISDN TA).
6. Cellular digital packet data wireless modem (CDPD)

SECTION 10-4. CITY OF SAN FRANCISCO SPECIAL PROVISIONS

10-4.01 TRAFFIC CONTROL BY UNIFORMED OFF-DUTY SAN FRANCISCO POLICE OFFICER

The Contractor shall provide a minimum of 2 uniformed off-duty San Francisco Police Officers (herein referred to as officers) at each of the following intersections when closed and traffic is being detoured through these intersections:

1. During McCoppin Street Closure – McCoppin/Valencia, Duboce/Valencia
2. During Valencia Street Closure – Duboce/Valencia, Duboce/Guerrero, Market/Guerrero, Market/McCoppin, McCoppin/Valencia
3. During Duboce Avenue Closure – Gough/Mission/Otis, Valencia/McCoppin, Duboce/Valencia, 14th/Valencia, 15th/Valencia, 15th/Mission, 14th/Mission, Mission/Otis/Duboce/13th, Mission/South Van Ness
4. During Mission/Otis/Duboce/13th Intersection Closure – same as 6 plus 15th/South Van Ness, 14th/South Van Ness, 13th/South Van Ness, South Van Ness/Howard, 11th/Mission, 11th/Howard
5. During 13th Street Closure – Duboce/Valencia, 14th/Valencia, 14th/Mission, 13th/Duboce/Mission/Otis, 13th/South Van Ness, 14th/South Van Ness

The officers may be required at other locations, during different phases of work, or as requested by the Engineer. The Contractor shall provide officers for the time required by the Engineer, and as specified above.

The final locations of the officers will be determined by the City of San Francisco Traffic Engineer, through the Engineer. The City of San Francisco Traffic Engineer through the Engineer shall make the determination whether any officers are required in addition to the flag persons provided by the Contractor as part of the traffic routing.

The Contractor shall prepare instruction sheets for use by the officers. The Contractor shall submit the instructions to the City of San Francisco Traffic Engineer through the Engineer for approval, as a part of the traffic control plans. These sheets will be for specific duties the officers will be required to perform, at specific locations. The Contractor shall give a copy of the approved instruction sheets to each officer and to Sgt. Tobin of the San Francisco Police Department (SFPD), Fax (415) 553-1637, Phone (415) 553-1638, for their use.

The officers will more than likely perform the following duties:

1. Direct vehicular traffic.
2. Direct pedestrian traffic.
3. Cite motorists or pedestrians violating traffic regulations.
4. Other traffic control duties as directed by Engineer through the Contractor.

The officers shall be paid a minimum of four hours per day. If the number of work hours exceeds four hours, the officers shall be paid for one additional hour for travel time. For a twelve-hour shift, the officers shall be paid thirteen hours per ordinance.

The Contractor should contact Sgt. Tobin of the SFPD at (415) 553-1638 for any additional details. The Contractor shall enter into an agreement with the SFPD to provide officers, within 30 days of the official date for commencement of the work. The Contractor shall make a deposit to the SFPD. The deposit will be a minimum of $2,000 or equal to the amount required for providing officers for a period of 2 weeks, whichever is more. The Contractor shall pay the SFPD the amount of each invoice within 30 calendar days of the date of the invoice.

The Contractor shall notify Sgt. Tobin of the SFPD at (415) 553-1638, Fax (415) 553-1637, Cellular Phone (415) 819-2007 regarding the schedule and number of officers required at least 4 calendar days in advance of the scheduled date. The minimum time to cancel the need of the officers is 24 hours.

Traffic control by uniformed off-duty San Francisco Police Officers will be paid for as extra work as provided in Section 4-1.03D, "Extra Work," of the Standard Specifications.

10-4.02 VITRIFIED CLAY PIPE

This work shall consist of furnishing and constructing vitrified clay pipe culvert including excavating, lagging, backfilling, and other incidental work, necessary or required for a complete installation as shown on the plans, or as directed by the Engineer, and as specified in these special provisions.

Vitrified clay pipe (VCP) shall conform to the ASTM "Standard Specification for Extra Strength Clay Pipe," Designation C700, except as modified by the plans and these special provisions. The minimum thickness of the pipe barrel shall conform to the Regional Western Standard of the Clay Pipe Institute.

Joints shall be made up in the field in accordance with the manufacturer's recommendations. All joints shall be tight fitting, watertight, and without imperfections. Only factory recommended lubricants shall be used. Joints connecting pipes to manhole structures shall be made with a short stub. The straight segment of stub barrel may not exceed 150mm maximum from face of structure. Joints for VCP plain-end pipe may be rubber compression couplings with stainless steel bands and shall be in accordance with the requirements of ASTM Designation: C425.

All vitrified clay pipe installed shall be field tested for leakage of each joint by performing an air pressure test is accordance with the requirements of ASTM Designation: C1103.

The Contractor shall furnish to the Engineer for approval six copies of the certified report of actual test results meeting ASTM C700. The pipes shall be handled and stored so as to prevent damage thereto, or to existing improvements, pipe, when stored, shall be secured to prevent rolling.

Excavation and backfill shall conform to the provisions in section 19-3, "Structure Excavation and Backfill," of the Standard Specifications.

The excavated material shall be disposed of outside the highway right of way in conformance with the provisions as provided in "Hazardous and Non-Hazardous Material Excavation," elsewhere in these special provisions.

Sand bedding, as shown on the plans, shall conform to Section 19-3.025B, "Sand Bedding" of the Standard Specifications.

VCP shall be so constructed and the sections so installed that the sections of pipe laid together form a continuous uniform line of pipe with a smooth regular interior surface. Pipe shall be laid uphill from structure to structure with the bell end upgrade. Each pipe shall be laid in the proper position, on a firm 100mm deep sand bed and shall have uniform support and bearing for its entire length. Bells shall be cleaned before the spigot of the succeeding pipe is inserted. A bell hole shall be dug at the end of each pipe to accommodate the bell and facilitate the making of joint.

Pipe shall be laid in conformity to the prescribed lines and grades, which shall be obtained for each pipe by measuring from a tightly stretched line running parallel with the grade and supported over the center line of the pipe by bars placed across the trench. The pipe sections shall be tightly fitted together. All adjustments of pipe to line and grade shall be made by scraping away of filling in and tamping the earth under the body of the pipe, not by blocking or wedging up. Supporting blocks shall not be under the pipe. Pipe shall not be laid within 100mm of any rock or other rigid object.

The Contractor shall not lay pipe in water and shall use permeable material, subdrains, or some other method approved by the Engineer to maintain an appropriately dry trench.

Pipes on foundation shall have the bottom reinforcing steel of the foundation run continuously through all sewerage structures constructed along or at the end of such sewers.

Horizontal and vertical bends in side sewer runs shall not exceed 45 degrees (1/8 bend), using approved mitered joints.

The length of vitrified clay pipe will be measured by the meter horizontally along the centerline of the culvert, between the outside surfaces of sewerage and drainage structures, or to the limits as constructed if the culvert does not terminate in sewerage or drainage structures.

The contract price paid per meter for vitrified clay pipe of the sizes listed in the Engineer's Estimate shall include full compensation for furnishing all labor, materials, tools, equipment, and incidentals, and for doing all the work involved in constructing the vitrified clay pipe, complete in place, including structure excavation and structure backfill, sand bedding and connecting new pipe to new or existing facilities, including concrete collars, and reinforcement complete in place, as shown on the plans, and specified in these special provisions, and as directed by the Engineer.

Full compensation for imported material and the disposal of excavated material outside the highway right of way in conformance with the provisions as provided in "Hazardous and Non-Hazardous Material Excavation," shall be considered as included in the contract price paid per meter for vitrified clay pipe of the sizes shown in the Engineeer's Estimate and no additional compensation will be allowed therefore.

10-4.03 SAN FRANCISCO CATCH BASIN

San Francisco catch basins shall be constructed as shown on the plans, and in accordance with the specifications in Section 51-1.02, "Minor Structures," of the Standard Specifications, and these special provisions.

San Francisco catch basins, at the option of the Contractor, may be furnished and installed as precast units, or units may be combined precast and cast-in-place structures.

Excavation and backfill shall conform to the provisions in section 19-3, "Structure Excavation and Backfill," of the Standard Specifications. Except the excavated material shall be disposed of outside the highway right of way in conformance with the provisions as provided in "Hazardous and Non-Hazardous Material Excavation," elsewhere in these special provisions.

Portland cement concrete shall conform to the provisions in Section 90-10, "Minor Concrete", of the Standard Specifications, or may be produced from commercial quality aggregates and cement containing not less than 350 kilograms of cement per cubic meter.

Metal water traps, and frames and grates used in the San Francisco catch basins shall conform to the provisions in Section 75-1.02, "Miscellaneous Iron and Steel", of the Standard Specifications and the provisions as shown on the plans.

The quantity of the San Francisco catch basins will be measured by the unit as determined from actual count.

The contract unit price paid for San Francisco catch basin shall include full compensation for furnishing all labor, materials, tools, equipment, and incidentals and for doing all the work involved in constructing San Francisco catch basin, including metal water trap, and frames and grate, bar reinforcing steel, structure excavation and structure backfill, completed in place, as shown on the plans, as specified in the Standard Specifications and these special provisions, and as directed by the Engineer.

Full compensation for imported material and the disposal of excavated material outside the highway right of way in conformance with the provisions as provided in "Hazardous and Non-Hazardous Material Excavation," shall be considered as included in the contract unit price paid for San Francisco catch basin and no additional compensation will be allowed therefore.

10-4.04 SAN FRANCISCO MANHOLE

San Francisco manholes shall be constructed in accordance with the details shown on the plans, as specified in Section 51-1.02, "Minor Structures," of the Standard Specifications, and these special provisions.

San Francisco manholes, at the option of the Contractor, may be furnished and installed as precast units, or units may be combined precast and cast-in-place structures.

Excavation and backfill shall conform to the provisions in section 19-3, "Structure Excavation and Backfill," of the Standard Specifications. Except the excavated material shall be disposed of outside the highway right of way in conformance with the provisions as provided in "Hazardous and Non-Hazardous Material Excavation," elsewhere in these special provisions.

Portland cement concrete shall conform to the provisions in Section 90-10, "Minor Concrete", of the Standard Specifications, or may be produced from commercial quality aggregates and cement containing not less than 350 kilograms of cement per cubic meter.

Metal frames and covers used in the San Francisco manholes shall conform to the provisions in Section 75-1.02, "Miscellaneous Iron and Steel", of the Standard Specifications and the provisions as shown on the plans.

The precast concrete components and steps in the San Francisco manhole shall conform to the provisions as shown on the plans.

The quantity of the San Francisco manhole will be determined as units from actual count.

The contract unit price paid for San Francisco manhole shall include full compensation for furnishing all labor, materials, tools, equipment, and incidentals and for doing all the work involved in constructing San Francisco manhole, including metal frame and cover, metal steps, bar reinforcing steel, structure excavation and structure backfill, completed in place, as shown on the plans, as specified in the Standard Specifications and these special provisions, and as directed by the Engineer.

Full compensation for imported material and the disposal of excavated material outside the highway right of way in conformance with the provisions as provided in "Hazardous and Non-Hazardous Material Excavation," shall be considered as included in the contract unit price paid for San Francisco manhole and no additional compensation will be allowed therefore.

10-4.05 GRANITE CURB

PART 1 - GENERAL

This work shall consist of furnishing and installing granite curb. It includes but is not limited to granite, mortar, concrete base, expansion joint material, dowels and epoxy, as shown on the plans and as provided in these special provisions and as directed by the Engineer.

RELATED CITY OF SAN FRANCISCO SECTIONS

Section 02050 Demolition
Section 02510 Asphalt Concrete Paving
Section 02518 Brick Paving
Section 03300 Cast-In-Place Concrete

REFERENCES

A. American Society for Testing and Materials (ASTM):

1. ASTM A666
2. ASTM C97 - Test Methods for Absorption and Bulk Specific Gravity of Dimension Stone.
3. ASTM C99 - Test Method for Modulus of Rupture of Dimension Stone.
4. ASTM C170 - Test Method for Compression Strength of Dimension.
5. ASTM C241 - Test Method for Abrasion Resistance of Stone Subjected to Foot Traffic.
6. ASTM C270 - Mortar for Unit Masonry.
7. ASTM C615 - Granite Dimension Stone.
8. ASTM C880 - Flexural Strength of Dimensional Stone.

SUBMITTALS

A. Coordination Drawings and Documents:

1. Verify field conditions and furnish coordination drawings showing location, arrangement, dimensions, jointing, anchorage, profiles and connections.

2. Under direction of Engineer and prior to removal, assess condition of existing granite sections and benefits to salvaging and preserving for re-use on the project. Provide schedule of salvaged pieces, description of condition, requirements for reinstallation, and cleaning. See also 2.03 Stone Fabrication and Reuse.

B. Samples:

1. Mortar samples shall be dry and thoroughly set.
2. Expansion joint materials and color sample of joint sealant.
3. Granite curb representation 305mm (1’-0") square and at least 19mm (3/4") thick; 3 identical samples.

C. Mock-up:

1. Furnish and erect a full-size mock-up of the stone work.
2. Materials and execution shall comply with requirements of the Specifications.
3. Mock-up shall serve as a control for judging subsequent work on the Contract.

D. Product Data: Submit manufacturer's product data confirming requirements of specified materials.

QUALITY ASSURANCE

A. Qualifications:

1. Stone Supplier:

    a. Company specializing in quarrying types of granite required herein.

    b. Company shall have adequate capacity and facilities to meet requirements as specified.

2. Fabricator: Fabricator shall have equipment for cutting and finishing to produce finished stone as specified.
3. Stone Setter: Stone Setter shall have been regularly engaged in setting dimensional stone for not less than five years.

DELIVERY, STORAGE, AND HANDLING

A. Storage: Stack granite on timbers or platforms at least 102mm (4") above the ground. Extreme precautions shall be taken to prevent staining, marring and breakage.

B. Handling: Pieces of granite over 45 kg (100 pounds) shall have Lewis holes for lifting. Lewis holes shall not be permitted on the exposed face of stone and shall not come closer than 51mm (2") from the finished face. Holes for other trades shall be cut in accordance with this Section of the Specifications. Holes and depths for anchors, details, etc. shall be in accordance with approved shop drawings.

PART 2 - PRODUCTS

MATERIALS

A. Granite:

1. Produced by Cold Springs Granite Company, Madera, CA or equal.
2. Specified colors supplied from the same quarry batch.
3. Granite color, types and finishes shall match existing as directed.
4. Granite properties as a minimum:

Property	Test Method	Value
Absorption	ATSM C97	0.40% (by weight)
Density	ATSM C97	2563 kg/m^3
Modular of Rupture	ATSM C99	10.3 Mpa (average)
Compressive Strength	ATSM C170	131 Mpa

5. Comply with requirements of ASTM C615.

B. Mortar:

1. The standard of quality for all latex Portland cement and adhesives, and grouting materials specified herein shall be as manufactured by LATICRETE International, Inc. Alternate manufacturers must be approved by the Engineer. Equivalent product manufacturers: Custom Building Products, MAPEL Corp. HYDROMENT (Bostik).
2. Portland Cement Mixes: As manufactured by LATICRETE International. Provide LATICRETE 211 Crete Filler Powder and LATICRETE 226 Thick Bed Mortar Mix for leveling/scratch coat and LATICRETE Grout and Joint Filler for grouting as required.
3. Latex Additives: As manufactured by LATICRETE International. Provide LATICRETE 4237 Thin Set Mortar Additive, LATICRETE 3701 Mortar Admix and LATICRETE 1776 Grout Admix Plus. Installation shall be in strict accordance with manufacturer's instructions. The use of polyvinyl acetate, natural rubber or resin latex emulsions shall not be permitted.

Note: LATICRETE is a proprietary product.

4. Latex Portland cement bedding and grout mortar shall be weather, frost, shock resistant and shall meet the following physical requirements:

    a. Compressive Strength: Thick bed mortar 27.6 MPa (4000 lbs/in^2) min.
    b. Compressive Strength: Thin bed bonding grouting mortars 35.6 MPa (5000 lbs/in^2) min.
    c. Tensile strength: Thin bed, bonding grouting mortars 3.5 MPa (500 lbs/in^2) min.
    d. Bond strength: Thin bed, bonding, grouting mortars .5 MPa (500 lbs/in^2) min.
    e. Water absorption: 4% max.
    f. Ozone Resistance: 200 hours @ 200 ppm with no loss of strength
    g. Smoke and Flame contribution factors: 0

5. Cement bed and grout mortar shall achieve full strength in twenty eight (28) days and fifty percent of its required 28 day strength within the initial 72 hours.
6. Provide color sample for Engineer's approval.

C. Expansion Joint Material: Conform to expansion joint material specified under Section 02518 Brick Paving.

D. Concrete Base: The concrete base shall conform to the section "Portland Cement Concrete Base," elsewhere in these special provisions.

ACCESSORIES

A. Stainless steel dowels as shown on the plans.

STONE FABRICATION AND REUSE

A. General: Cut granite to conform to shape of utility castings. Salvaged granite curbs for reuse are subject to Engineer's approval prior to installation. Salvaged granite damaged during construction shall be rejected and replaced with new matching pieces.
B. Granite Curb:

1. Straight granite curb sections shall typically be 1.83 m (6'-0") long, center to center of joints. Minimum length of granite curb as required to meet curb return sections shall be 1.22 m (4'-0").
2. Granite curb finish: All surfaces except bottom wire cut. Bottom surface shall be split face or wire cut.
3. Color: Sierra White

C. Granite Curb at Sidewalk Curb Ramp:

1. Dimensions: As shown on Drawings. Submit shop drawings for approval.
2. Finish: Wire Cut and sanded
3. Color: Sierra White

D. Scored Band Around Curb Ramps:

1. Dimensions: Submit shop drawings for approval
2. Finish: Thermal finish with sachets one inch on center, size to match existing or as indicated on the Drawings
3. Color: Carnelian

PART 3 - EXECUTION

MIXES

A. Mortar and Grout Mixes:

Slurry Coats

1. LATEX SLURRY BOND COAT

   - 200 lbs./90.0 kg. (4 bags) LATICRETE 211 Crete Filler Powder.
   - 5 Gal./19 L (1 pail) LATICRETT; 4237 Latex Thin Set Mortar Additive or LATICRETE 3701 Latex Admixture or LATICRETE 4237 (top mortar bed slurry). Adjust quality of liquid to obtain proper consistency.

2. LATEX THIN BED MORTAR MIX

   - 165 lbs./75 kg. (3 bags) LATICRETE 211 Crete Filler Powder.
   - 6 Gal./22.8 L (1 pail) LATICRETE 4237 Latex Thin Set Mortar Additive (Adjust quality of liquid to obtain proper consistency).

Screed Bed

3. LATEX PORTLAND CEMENT LEVELING BED AND SCRATCH COATS (Up to 25 mm (½") +/- # thick 146 kg./300 lbs.(5 bags) LATICRETE 226 Thick Bed Mortar Mix.

   - 5 gal./19 L (1 pail) LATICRETE 3701 Mortar Mix (Adjust quality of liquid to obtain proper consistency).

Mortar Thick Bed

4. LATEX PORTLAND CEMENT THICK BED MORTAR (31.25 millimeters [1 1/4"] min. thick).

   - 360 lbs./163 kg. (6 bags) LATICRETE 226 Thick Bed Mortar Mix.
   - 5 Gal./19 L (1 pail) LATICRETE 3701 Mortar Admix (Adjust quantity of liquid to obtain proper consistency).

Grout Joints

5. LATEX GROUT

   - 50 lbs./22.7 kg (1 bag) LATICRETE Dry Set Wall Grout and Joint Filler (custom color).
   - 1 Gal./3.8 L (2 jars) LATICRETE 1776 Grout Admix Plus (adjust quality of liquid to obtain proper consistency).

B. Mixing:

1. Machine Mixing: Mixer shall be a rotating blade type mortar mixer. Place LATICRETE liquid in mixer, start machine and add dry material. Mix only long enough to wet out the batch. DO NOT OVERMIX. Stop mixer and dump mortar from mixer promptly. Clean out mixer promptly with water.
2. Hand Mixing: Place LATICRETE liquid in clean container or mixing box, add dry material and mix. Adjust amount of liquid or dry material to obtain proper consistency.

SETTING

A. Clean and dry each granite piece before being setting. Place each piece in full bed of mortar not less than one inch thick and tapped home with rawhide mallet to full and solid bearing. Completely fill vertical joints with mortar, 10 mm (3/8") wide, unless noted otherwise.
B. Keep granite surfaces free of mortar at all times.
C. Rake joints to depth of at least 19 mm (3/4-inch). Brush clean raked joints. Point joints in two stages, attaining a flat cut joint in last stage with thumbprint hard tool having a round jointer 3 mm (1/8") larger in diameter than the joint.

D. Exercise professional care and methods and utilize protective materials to safeguard the granite work until Final Acceptance from damage and discoloration by construction operations, adjacent work, vehicular and pedestrian traffic.
E. Expansion joint material placed between granite curbs and brick sidewalks shall be placed to the depth of the adjacent brick and mortar bed.

DOWELS

A. Dowel granite work according to the Drawings and as specified; and as directed.
B. Dowels shall be of stainless steel inserted in mortar-filled holes in the granite, as indicated on the Drawings and as directed by the Engineer.

CLEANING

A. After completion of the granite work and after liability of staining from other operations has passed, clean the granite, removing dirt, mortar, stains, and other defacements.
B. The use of wire brushes, acid, or solutions which may cause discoloration is prohibited. Exercise special care to prevent discoloration and stain from washing and cleaning operations.
C. Cleaning shall start at the horizontal surface and continue vertically until completed.

PROTECTION OF FINISHED WORK

A. All granite work shall be protected from damage. Protective crates or other suitable means shall be employed whenever required. No lumber or material liable to stain or deface the granite shall be used. All nails used shall be galvanized.
B. All granite work shall be protected from water at the all times during construction by weighted tarpaulins.
C. All granite work shall be protected during the asphalt paving operation from oil stains, compaction of asphalt, etc. Replace stained or damaged granite at no extra cost to the City.

DEFECTIVE WORK

A. No patching or hiding of defects will be permitted. New granite showing flaws or imperfections upon receipt at the site shall be rejected or redressed for use under Engineer's direction. Reused granite damaged under construction shall be rejected and replaced at no extra cost to the City.

MEASUREMENT AND PAYMENT

Quantities of granite curb to be paid for will be by the meter.

The contract price paid per meter for granite curb shall include full compensation for furnishing all labor, materials, tools, equipment, and incidentals, and for doing all the work involved furnishing and installing granite curb (including concrete base), complete in place, as specified in the Standard Specifications and these special provisions, and as directed by the Engineer.

10-4.06 MANUFACTURED STONE PAVING

PART 1 - GENERAL

This work shall consist of furnishing and installing manufactured stone paving as shown on the plans and as provided in the Standard Specifications and these special provisions and as directed by the Engineer. The work includes, but is not limited to:

1. Minimum 10.16 cm sub-slab (sub-slab is also shown as a "Concrete Base Slab" but the latter includes welded wire fabric reinforcement).
2. Mortar leveling bed.
3. Manufactured Stone Pavers (also indicated on Drawings as "Cobblestone").
4. Expansion joints.
5. Replacement of unsatisfactory work.
6. Clean-up and acceptance.

RELATED CITY OF SAN FRANCISCO SECTIONS

Section 03300 Cast-in-Place Concrete
Standard Specifications, Department Of Public Works, Bureau Of Engineering, Sections 207 and 416.

REFERENCE

A. UBC Standard No. 26-10, Parts I and IV - Compressive Strength of Manufactured Units - Cultured Stone.
B. American Society for Testing and Materials (ASTM) Standards. Comply with applicable provisions of the following:

1. ASTM C 33 - Concrete Aggregates
2. ASTM C91 - Specification for Masonry Cement
3. ASTM C144 - Aggregate for Masonry Mortar
4. ASTM C150 - Portland Cement
5. ASTM C207 - Specification for Hydrated Lime for Masonry
6. ASTM C39 - Compressive Strength of Cylindrical Concrete Specimens
7. ASTM C270 - Mortar for Unit Masonry
8. ASTM C260 - Air Entraining Agent

SUBMITTALS

A. General: Submittals in accordance with Section 01300.
B. Samples:

1. Pavers: Submit 20 samples of full-size pavers and 10 samples of half-size pavers, illustrating: style, size, range of color and surface texture of units to be installed.
2. Color range shall demonstrate a minimum of 2 variants of dark gray and 2 variants of light gray.
3. Mortar: Custom color = "medium gray" 15.25 cm square panel.
4. Elastomeric joint sealant with color chart.

C. Manufacturer's Data and installation recommendations

1. Paving units
2. Cleaning solution

QUALITY ASSURANCE

A. Installer Qualifications: The Contractor, personally or through an authorized representative shall supervise the work constantly, and shall keep the same foreman and workmen on the job from commencement to completion. The foreman is to be present on the job site whenever work is in progress. Only qualified and competent workmen with a minimum five (5) years work experience of same paving type installation shall work on the job.

PROJECT SITE CONDITIONS

A. Maintain cementitious materials and substrate surface to a minimum of 50 degrees F, prior to, during, and 48 hours after installation.
B. Protect materials from rain and moisture. At end of working day or during rainy weather, cover unfinished or uncured work exposed to weather with waterproof coverings, securely anchored.

MOCK-UP

A. General: The Contractor shall construct to scale, a "mock-up" of manufactured stone paving, as specified herein. The "mock-up" shall be representative of all work necessary to complete the job, including cleaning agents, curing compounds and will be reviewed at the end of specified curing time for this type of concrete/masonry work.

B. Mock-up: The "mock-up" is to be no less than 14 meters squared and the installation is to include, but is not limited to the following:

1. Representation of the dark gray paver band to align with black trackway.
2. Representation of the light gray paver band to align with red trackway.
3. Concrete curbs with a corner angles equal to 90 degree.
4. Concrete corner at curb greater than 90 degree.
5. Concrete corner at curb less than 90 degree.
6. Manufactured full and half-size pavers.
7. A minimum three examples to demonstrate conditions that require: field cut and special pre-cast pavers to fit odd angles and areas requiring less than full or half sized manufactured pavers.
8. Expansion joint sealant.

C. The "mock-up" shall be prepared as many as five (5) times as necessary to obtain approval from the Engineer. All pavers cut in field for odd angles are subject to approval by the Engineer.
D. The "Mock-up" may remain as part of completed work.
E. The "Mock-up", as reviewed and accepted by the Engineer, will remain on site until the entire project is complete, and will become the standard to which the remainder of material furnished on the job shall conform

WARRANTY

A. The Contractor shall furnish a two (2) year Warranty for all work covered by this Section per the requirements of Section 01740.

PRODUCT DELIVERY, STORAGE AND HANDLING

A. All stone pavers shall be delivered and unloaded at job site on pallets and bound in such a manner that no damage occurs to the product during hauling, handling, or unloading at the job site.

MAINTENANCE

A. Extra Materials: The Contractor shall provide five (5) pallets of the approved and accepted manufactured stone paver. All materials are to be delivered and stored to a location as directed by the Engineer.

COORDINATION

A. Contractor is to verify location and coordinate installation of all utility poles and other structures to include but not limited to: signs; utility boxes; manholes; equipment block-outs and pads; and track way paving colors prior to commencement of work in this Section.

PART 2 - PRODUCTS

STONE PAVERS

A. General: All manufactured stone pavers shall be as manufactured by Cultured Stone – A Division of Owens Corning, 1 800-255-1727, no known equal. Manufactured stone pavers may be obtained from Pacific Supply, 61 Jordan Street, San Rafael, Ca. 94912-2274; telephone (415) 453-9531. The price quoted by the manufacturer for the San Francisco Cobblestone is $7.58 per square foot with a minimum order of 186m2 (2,000 square feet), not including sales tax. Delivery to the job site in San Francisco is an additional $100.00. Prices are valid through December 31, 2003.
B. Manufactured stone paver:

1. Full -size: length = 204mm (8"), width = 153mm (6"), height = 64mm (2 1/2")
2. Half -size: length = 102mm (4"), width = 153mm (6"), height = 64mm (2 ½")
3. Color: Custom integral color with a range of to demonstrate a minimum of 2 variants of dark gray and 2 variants of light gray. as per accepted and approved samples.

4. Pavers shall have a minimum compressive strength of 27.58 Mpa (megapascals), as noted on Drawings and herein in accordance with testing procedures ASTM C-140.
5. Pavers shall have cobble texture on top side and all four sides, no exceptions.

C. Materials used to manufacture stone pavers shall conform to the following:

CAUTION: Do not use Calcium chloride in any form.

1. Masonry cement - ASTM C-150 (Portland Cement), or ASTM C91 type, custom gray color, as approved and accepted sample.
2. Sand: ASTM C144 and ASTM C33; sharp, coarse, clean, screened and free of organic material; gray color.
3. Lime: ASTM C207.
4. Water: Potable, not detrimental to Mix.
5. Admixtures: Pozzolan; ASTM C618, Type N or F.
6. Color: Mineral type, non-fading, gray color, devoid of iron oxide, custom type to be selected.

D. Accessories:

1. Fiber expansion joint, bituminous material, non-extruding, conforming to ASTM D 1751, thickness as shown on the Drawings.
2. Backer rod: Extruded closed-cell polyethylene foam rod -- Sonofoam, as manufactured by: Chemrex/Sonneborn, 2359 Lincoln Ave, Hayward, CA, (510) 732-9101; or ICEL backer rod - manufactured by: Industrial Systems Dept., Plastic Products Group of Hercules Inc., Middletown, Delaware; or W.R. Meadows Inc., Elgin, IL., (312) 683-4500; or equal. The rod shall be 1/8 inch larger in diameter than the joint width.
3. Elastomeric Joint Sealant: Color of the sealant shall be gray to match the color of the joint mortar. Sikaflex 425 or 427 - Sika Chemical Co., Lyndhurst, NJ; or PRC 230 or PRC 210/220 - Products Research and Chemical Corp. Foster City, CA; or W.R. Meadows Inc., Elgin, IL, (312) 683-4500; or equal.
4. Cleaning Solution: Consult the paving manufacturer for recommended cleaning solution type or technique, which will not harm pavers, joint materials or adjacent surface.

E. Mixes:

1. Cementitious Bed: Portland cement mix conforming to the following:

Property	Value
Compressive Strength (28 Days)	20.68 MPa
Slump	7.62 to 10.16 cm
Admixture: Efflorescence Reducing Agent	10% Pozzolan Agent Type N or F
Air Entrainment	5 to 7% by volume

2. Joint Mortar: Portland cement mix conforming to the following:

Property	Value
Compressive Strength (28 Days)	20.68 MPa
Slump	2.54 to 5.08 cm
Color Admixture	Gray without iron oxide
Admixture: Efflorescence Reducing Agent	Pozzolan Agent Type N or F
Air Entrainment	5 to 7% by volume

3. Thoroughly mix ingredients in quantities needed for immediate use in accordance to ASTM C279, Type S.
4. Use within two hours after mixing. Do not re-temper.

F. Aggregates - ASTM C-33 (washed, graded sand and rock, no expanded shale or lightweight aggregates).

PART 3 - EXECUTION

FIELD QUALITY CONTROL

A. Inspection of sub-slab: Inspect the sub-slab on which the pavers are to be installed. Be sure the sub-slab is clean and free of any deleterious materials and that grades provide for positive drainage. Where Contractor feels that the sub-slab condition is not acceptable for installation of the pavers, report to the Engineer in writing and obtain the Engineer's instructions prior to proceeding with the work affected.

INSTALLATION

A. Installation of Paver and Mortar Bed

1. Dampen concrete surface.
2. Set paver units in full cementitious mortar bed of 2.54 cm minimum, covering a maximum 1.9 meters square at one time. Press paver firmly into position in soft mortar bed; position each paver to bond firmly.
3. Place expansion joint material perpendicular to the trackway and spaced at a minimum of 6.1 meters to a maximum of 9.1 meters, see Drawings.
4. Place manufactured half pavers to create running bond pattern, do not use cut pavers to create running bond pattern.
5. All field cut pavers are subject to approval by the Engineer.
6. Perform necessary cutting with proper tools to provide uniform edges.
7. Maintain uniform joint width of 19 mm between pavers and at abutting vertical surfaces and protrusions. To accommodate mortar, rake out joints to required depth.
8. Fill joints with mortar. Pack and work into voids. Neatly tool surface to concave joint with a 13 mm rake. Wet cure.

B. Pavers shall be clean and free of foreign materials before installation.
C. Installation should start from a corner or straight edge and proceed forward, over the mortar setting bed.
D. Pattern: Running Bond Pattern place perpendicular to main flow of traffic and align with trackway pavement colors. See Drawings for pattern direction and track way paving colors.

1. Selectively place pavers such that the 2 variants of dark gray pavers are randomly mixed and align with black track way pavement.
2. Selectively place pavers such that the 2 variants of light gray pavers are randomly mixed and align with red track way pavement.
3. Place manufactured half pavers, do not use cut pieces to create running bond pattern.

E. Paving work shall be plumb, level and true to line and grade; shall be installed to properly coincide and align with adjacent work and elevations.
F. Cleaning: Clean soiled surfaces using the cleaning solution and technique as recommended by the paving manufacturer.

1. Use non-metallic tools during the cleaning operation.
2. Clean-up each work day as per manufacturer's instructions.
3. Sweep with broom to clean paving surface before the close of each workday.
4. Cleaning operation is to be considered complete as approved by the Engineer.

PROTECTION

A. The Contractor shall take all necessary steps to protect pavers as installed. Do not permit traffic over unprotected surfaces.

REPAIR AND REPLACEMENT

A. Repair all defective work. Where a paver unit is replaced, select a unit to blend in the color range of the surrounding units. Replace with unit having same color.

MEASUREMENT AND PAYMENT

For payment purposes, the area in square meter of manufactured stone paving will be determined from horizontal measurements of the finished paving.

The contract price paid per square meter for manufactured stone paving shall include full compensation for furnishing all labor, materials, tools, equipment, and incidentals, and for doing all the work involved in constructing manufactured stone paving, complete in place, as shown on the plans, as specified in these special provisions, and as directed by the Engineer.

10-4.07 BRICK SIDEWALK

PART 1 - GENERAL

The work consists of providing brick paving for sidewalks and curb ramps. The work includes but is not limited to brick pavers, mortar, expansion joint materials, and slip sheet; cleaning; and adjustment of frames and castings; and bronze street name plaques as shown on the plans, as provided in these special provisions and as directed by the Engineer.

RELATED CITY OF SAN FRANCISCO SECTIONS

Section 02050 Demolition
Section 02607 Adjustment of City-Owned Frames and Castings
Section 02608 Adjustment of SFWD-Owned Frames and Castings
Section 02609 Adjustment of Non-Government-Owned Frames and Castings
Section 02900 Landscape Work
Section 02952 Palm Planting
Section 03300 Cast-in-Place Concrete
Section 04465 Granite Masonry

REFERENCES

A. ASTM C67 - Test Methods of Sampling and Testing Brick and Structural Clay Tile
B. ASTM C109 - Test Method for Compressive Strength of Hydraulic Cement Mortars (Using two inches or 50-mm. Cube Specimens).
C. ASTM C144 - Aggregate for Masonry Mortar.
D. ASTM - C150 - Portland Cement.
E. ASTM C207 - Hydrated Lime for Masonry Purposes.
F. ASTM C216 - Facing Brick (Solid Masonry Units made from Clay or Shale).
G. ASTM C270 - Mortar for Unit Masonry.
H. ASTM D1752 - Preformed Sponge Rubber and Cork Expansion Joint Fillers for Concrete Paving and Structural Construction.
I. UBC Standard No. 24-28, Method of Sampling and Testing Grout.
J. AASTM C1028 – Standard Test Method for Evaluating the Static Coefficient of Friction of Ceramic Tile and Other Like Surfaces by the Horizontal Dynamometer Pull Meter Method
K. SFDPW Standard Curb Ramps:

    1. CR-1 Standard Curb Ramp Plans and General Notes
    2. CR-2 Detectable Surface Layout, Details and Notes

SUBMITTALS

A. Brick:

    1. Three full-size brick samples for each type.
    2. Manufacturer's material specifications and installation recommendations.

3. Certificates of Compliance.

B. Expansion Joint Materials: Joint filler, sealant back-up and polyethylene slip sheet:

1. Three material samples of each.
2. Manufacturer's material specifications and installation recommendations for each.
3. Certificates of Compliance for each.

C. Mortar:

1. Proposed pre-mixed product.
2. Color sample for Engineer's approval.

D. Cast Bronze Street Name Plaque:

1. See Drawings for details.
2. Provide plaques for streets intersecting Market Street. Verify names prior to fabrication.

MOCK-UPS

A. General: Construct to scale, a "Mock-up" of brick paving for each brick type and pattern for each location. The "Mock-up" shall be representative of all work necessary to complete the job at each location, including saw- cut removal of existing work; brick cutting and fitting, mortaring, curing; and expansion joints' bronze street name plaque; and adjustments of castings to meet finished grade.
B. Market Street and Adjacent Mock-ups: Provide full scale extension of new work to match existing patterns, starting at the existing double soldier course band along granite or concrete curb, approximately 18 square feet, and including the following:

1. Herringbone field, radiating border around tree pit and utility covers; and soldier course patterns.
2. Mortar joint size, color and finish to match existing.
3. Removal of all partial units of existing brick at starting point and replacement with whole brick units; and removal and replacement of all missing, broken, cracked, and chipped bricks within the public-right-of-way within 5 foot radius from edge of new work.
4. Expansion joint materials.
5. Bronze street name plaque.
6. Adjustment of castings.

C. Prepare mock-ups as many times as necessary to obtain approval from the Engineer. All bricks cut in field are subject to approval by the Engineer.
D. Mock-ups may remain as part of completed work.
E. Mock-ups reviewed and accepted by the Engineer shall serve as the standard conformance for materials and workmanship for subsequent work.

QUALITY ASSURANCE

A. Installer Qualifications: The Contractor, personally or through an authorized representative shall supervise the work constantly and keep the same foreman and workmen on the job from beginning to completion. The foreman shall be present on the job site whenever work is in progress. Only qualified and competent workmen with a minimum five years work experience installing same paving type shall work on the job.
B. Certificates:

1. Provide certificates stating that the grout, setting materials, and admixtures are compatible with themselves and the bricks. Have the certificate signed by the brick supplier, manufacturer and installer.

C. Single source for setting products: Provide mortar, grout, and latex admixtures from a single source or manufacturer, unless otherwise approved by Engineer.

D. The supplier of adhesives, grouts and mortars shall have been regularly engaged in the manufacture of these materials a minimum of 10 years, and shall submit to the Engineer a list of three similar installations, each having a minimum 10 years service.

MAINTENANCE

A. Protect, clean and maintain brick to preserve original color and texture throughout the duration of the Contract.

PART 2 - PRODUCTS

BRICKS

A. Bricks shall match existing brick type for various locations and conform to the requirements of ASTM C216, Grade "SW", Type "FBS", "Standard Specification for Facing Brick" and ASTM C902-92 Pedestrian Paving and Light Vehicular, Class SX, Type 1; and to the following specifications:

1. Brick Size: Field verify dimensions of existing bricks on sidewalk and curbramp of contrasting color. Common size is 92mm x 194mm x 51mm (3-5/8" by 7-5/8" by 2") actual dimensions laid flat. Curbramp brick varies slightly.
2. Size Variation: 3mm (1/8") maximum in any dimensions.
3. Color: Match existing sidewalk and curbramps of Pacific Rose color and verify proposed manufacturers and colors for different existing locations.

    a. Market Street sidewalk: Muddox Company #890, dark red or equal.
    b. Market Street curb ramp: Pacific Clay Brick Products, 909-674-2131; Pacific Rose.

4. Texture: Die face free from concave indentations, having rough texture and color, and shall have eased edges on the long sides.
5. Wire cut face for curb ramp brick must be essentially free of concave indentations normal to typical wire cut faces. Fire flashed brick is not acceptable.
6. A minimum compressive strength of 2.07 x 10^4 kPa (3,000 pounds per square inch) when based on an average of five bricks.
7. 24-hour absorption (%) - 4.5 minimum.
8. Maximum water absorption by 5 hour boiling (%) - 8.0 minimum.
9. Saturation co-efficient - 0.55 minimum.

B. All brick shall be sampled, tested and accepted in accordance with ASTM C216, ASTM C67 and ASTM 902-92.

1. Curb ramp brick shall be slip resistant, tested and approved in accordance with ASTM C1028, based on passing the friction coefficient of 0.8 minimum under all conditions.

EXPANSION JOINT MATERIALS

A. Expansion joint: Conform to ASTM D1752-67 Type II, Grace standard cork expansion joint filler, Code 4323, or equal; no known equal. Provide filler equal to the full depth of brick and mortar bed less depth of the sealant and back-up.
B. Joint sealant: Sonneborn-DeSota "Sonoclastic" elastomeric paving joint sealant, or Grace "Daraseal U," Traffic Grades, two component urethane base sealant, or equal. Apply in accordance with the manufacturer's specifications and instructions, complete with priming material, bond breaker and back-up. The sealant material shall comply with Federal Specification TT-S-00227e, Type I, Class A. The sealant joint width shall be 10mm x 10mm (3/8" x 3/8") deep. Sealant color shall match the mortar color.
C. Back-up of butyl rubber rod: Percora "Back-Up" No. 89, or Sonneborn No. 94, Sonaform Backer Rod, or equal.
D. Polyethylene slip sheet: "GER-PAK" Seamless Polyethylene Slip Sheeting 10-mil (0.010) manufactured by Gering Plastics Company, Kenilworth, New Jersey; no known equal.

MORTAR

A. The standard of quality for all latex Portland cement and epoxy adhesives, and grouting materials specified herein shall be manufactured by Laticrete International, Inc., Bethany, CT 06524-3423. Alternate manufacturers must be approved by the Engineer in accordance with provisions of Section 01630.

   1. Equivalent Product Manufacturers: Custom Building Products, Seal Beach, CA; Mapel Corp., Elk Grove Village, ILL.; Hydroment (Bostik), Middleton, MA.

B. Portland Cement Mixes: As manufactured by Laticrete International. Provide Laticrete 211 Crete Filler Powder and Laticrete 226 Thick Bed Mortar Mix for leveling/scratch coat or Laticrete Floor Grout and Joint Filler (specify color) for grouting as required.

C. Latex Additives: As manufactured by Laticrete International. Provide Laticrete 4237 Thin Set Mortar Additive, Laticrete 3701 Mortar Admix and Laticrete 1776 Grout Admix Plus. Installation shall be in strict accordance with manufacturer's instructions. The use of polyvinyl acetate, natural rubber or resin latex emulsions shall not be permitted.

   1. Latex Portland cement bedding and grouting mortar shall be weather, frost, shock resistant and shall meet the following physical requirements.

      a. Compressive Strength: Thick bed mortar: 4000 lbs per square inch (27.6 MPa) min.
      b. Compressive Strength: Thin bed bonding grouting mortars: 5000 lbs per square inch (35.6 MPa) min.
      c. Tensile Strength: Thin bed bonding grouting mortars; 500 lbs per square inch (3.5 MPa) min.
      d. Bond Strength: Thin bed, bonding grouting mortars 500 lbs per square inch (3.5 MPa) min.
      e. Water Absorption 4% max.
      f. Ozone Resistance: 200 hours @ 200 ppm and no loss of strength
      g. Smoke and Flame contribution factors: 0
      h. Non-conductive; infinitely resistant to conductivity

CONCRETE BASE

The concrete base shall conform to the section "Portland Cement Concrete Base," elsewhere in these special provisions.

PART 3 - EXECUTION

FIELD QUALITY CONTROL

A. Inspect the depth and workmanship of the concrete sub-slab for the finished brick work. Verify that the sub-slab is clean and free of any deleterious materials and that grades provide for positive drainage. Sub-slab conditions not acceptable for brick installation shall be reported to the Engineer in writing. Obtain the Engineer's instructions prior to proceeding with the work affected.

INSTALLATION

A. Wet bricks until they attain absorption rates of not over 1.4 oz. per minute in accordance with ASTM C67. When being laid, the brick shall have suction sufficient to hold the mortar and to delete the excess water from the grout, but shall be sufficiently damp so that the mortar will remain plastic enough to permit the brick to be leveled and plumbed immediately after being laid.
B. Brick work shall be plumb level, and true to line. All corners and angles shall be square unless otherwise indicated on the Drawings.
C. Brick shall be clean and free of dust, dirt, or other foreign materials before laying.
D. Lay brick to match existing pattern unless otherwise directed. Adjust the double soldier course and contiguous herringbone pattern to conform to all horizontally curved granite curbs.
E. All pattern work shall be accurately and uniformly done.
F. Lay bricks in a full mortar bed over a concrete base slab. The full mortar bed shall vary in thickness to conform with existing brick edge, concrete sidewalk paving and to attain minimum slope for drainage.

G. Mortar joints shall match existing or be 10mm (3/8 inch) nominal tooled to a shallow smooth, dense, concave joint. Bricks shall be solid, butted and shoved in place. Excess mortar shall be removed immediately from brick pavers. The centerline of all mortar joints shall be straight and aligned in each direction. Brick paving, mortar joint center lines shall conform to a horizontal four 102mm (4 inch) module in each direction, except as noted otherwise, and all joint relationships and control points shall be maintained.

H. At completion of the brick paving, all masonry surfaces shall be thoroughly cleaned in accordance with the Structural Clay Products Institute - Technical Notes on Brick and Tile Construction, No. 20 Revised, latest edition. Sandblasting will not be permitted. The method of cleaning must be approved in writing by the Engineer prior to proceeding with laying brick, but such approval will not relieve the Contractor of the responsibility for having the brick work cleaned satisfactorily.

I. Brick Paving at Street Furniture, Equipment and Pole Foundations: Provide continuous radiating soldier course around base plates, frames and castings; and poles. Locate expansion joints at least 1 foot from poles.

MIXES

A. Mortar and Grout Mixes:

1. Latex Slurry Bond Coat

   a. 200 lbs./90.0 kg. (4 bags) Laticrete 211 Crete Filler Power.
   b. 5 Gal/19 L (1 pail) Laticrete; 4237 Latex Thin Set Mortar Additive or Laticrete 3701 Latex Admixture or Laticrete 4237 (top mortar bed slurry). Adjust liquid amount to obtain proper consistency.

2. Latex Thin Bed Mortar Mix

   a. 165 lbs/75 kg. (3 bags) Laticrete 211 Crete Filler Powder.
   b. 6 Gal./22.8 L (1 pail) Laticrete 4237 Latex Thin Set Mortar Additive. Adjust liquid amount to obtain proper consistency.

3. Latex Grout

   a. 50 lbs/22.7 kg (1 bag) Laticrete Floor Grout and Joint Filler 500 Series. Provide color.
   b. 1 Gal./3.8 L (2 jars) Laticrete 1776 Grout Admix Plus. Adjust liquid amount to obtain proper consistency.

4. Latex Portland Cement Leveling Bed to 1 inch (25 mm)

   a. 300 lbs./146 kg. (5 bags) Laticrete 226 Thick Bed Mortar Mix.
   b. 5 Gal./19 L (1 pail) Laticrete 3701 Mortar Mix. Adjust liquid amount to obtain proper consistency.

EXPANSION JOINT LOCATIONS

A. At juncture of brick paving and concrete curb or driveway.
B. Around street equipment and furnishings; utility and trolley poles. Provide expansion joint around the one brick course around said features.
C. On centerline of Market Street "Path of Gold" street light or other lights, parallel to curb and through brick sidewalk.
D. Expansion joints shall be inconspicuous and appear identical in size, shape and color to the adjacent mortar joints. Conform expansion joint to brick pattern.
E. At property or building line parallel to curb.
F. Install not more than 9.20m (30’-0") on center to nearest joint.

EXPANSION JOINT INSTALLATION

A. Construct expansion joint materials to the full depth of the brick and mortar bed at all expansion joint locations.
B. Install a polyethylene slip sheet, 10 mil thick and 914mm (3 feet) wide, centered on the joint between the brick mortar and the concrete base slab on grade at the herein before specified expansion joint locations.

MORTAR PROPORTIONING AND MIXING

A. Accurately measure all materials; shovel measurements are not acceptable. Use a mechanical mixer of at least one cubic foot capacity. Mix materials for a minimum of three minutes, but in no case less than the time required to secure a uniform mass. The drum must be completely emptied before the next batch of materials is placed therein.
B. Stir and mix at frequent intervals to prevent separation of the materials.
C. Adjust mortar consistency to the satisfaction of the mason. The amount of water added shall not exceed industry standards. The mortar shall not be used after the cement has begun its final set and in no case shall it be used more than one hour after the completion of the original mixing. Retempering of mortar will not be permitted.
D. When partial batches are mixed, extreme care shall be used in measuring all ingredients.
E. The color shall be a standard commercial brand of chemically inert coloring material accurately measured by weight in a definite manner for each batch of mortar to produce a consistently even medium grey color. The mortar for the mortar joints shall be integrally colored with Conrad Sovig "Permatint" color mix, in a ratio of2 pounds of 1339 brown with 8 pounds of 110l black.

    1. Use 4 pounds of said color mixture per sack of cement or their equal in color and quality. Proportion and mix according to manufacturer's directions. Mortar color shall match the approved color sample at the Engineer's office.

FRAMES AND CASTINGS

A. At areas where brick pavement is constructed, all frames and castings, including covers, gratings, boxes shall be adjusted to conform with final grades. The adjustment of frames and castings is incidental to the brick paving work and be in accordance with the requirements of SFDPW Standard Specifications, Section 217.
B. Prior to the start of this work, the Contractor shall locate and show all frames and castings on a set of drawings.
C. Provide adjusting rings for resetting the low pressure and high pressure hydrant valve castings.
D. The San Francisco Water Department (SFWD) will supply the required adjusting rings for the 152 mm (6-inch) and 203 mm (8-inch) valve box castings at the City Distribution Division Corporation Yard, 1990 Newcomb Avenue, San Francisco, at no cost to the Contractor.
E. Adjustment of SFWD frames larger than 203 mm (8 inches) in diameter shall be done by the SFWD, at no cost to the Contractor. Contractor shall notify the SFWD Distribution Division, 4 calendar days in advance of scheduled work that requires resetting of valve castings larger than 203 mm (8 inches) in diameter.
F. Place brick pavement around each casting no later than two calendar days after said casting has been adjusted and concrete has been placed.
G. Existing manholes and valves shall be accessible at all times.

MEASUREMENT AND PAYMENT

For payment purposes, the area in square meter of brick sidewalk will be determined from horizontal measurements of the finished brick sidewalk.

The contract price paid per square meter for brick sidewalk shall include full compensation for furnishing all labor, materials, tools, equipment, and incidentals, and for doing all the work involved in constructing brick sidewalk, mortar bed, and concrete base (including "path of gold", tree, traffic signal, sign, and pedestrian signal cast iron frames and bronze street name plaque), complete in place, as shown on the plans, as specified in these special provisions, and as directed by the Engineer.

10-4.08 WROUGHT IRON FENCE

Wrought iron fence, vehicular gates and pedestrian gates shall conform to the provisions in Section 75, "Miscellaneous Metal" and Section 55, "Steel Structures," of the Standard Specifications and these special provisions. Fence and gates shall be fabricated in accordance with the details shown on the plans and as directed by the Engineer.

All earthly material removed in connection with placing wrought iron fence shall be disposed of outside the highway right of way in conformance with the provisions as provided in "Hazardous and Non-Hazardous Material Excavation," elsewhere in these special provisions.

MATERIALS

Wrought iron fence and gates shall be furnished and installed at the locations as shown on the plans.

Wrought iron fence shall be finished with a fused coating of electrostatically applied polyester powder paint. The color of polyester powder paint shall be black.

Fence posts shall be installed in pre-set sleeves in accordance with the manufacturers instructions.

Hinges, hasps, locks, closing and locking hardware and rolling gate device shall be pre-approved by Engineer and installed per manufacturer's instructions.

For metal fabrications exposed to view in the completed work, provide materials with smooth, flat surfaces without blemishes. Do not use materials with exposed pitting, seam marks, roller marks, rolled trade names or roughness.

Hardware: All bolts and nuts shall be hot-dip galvanized or stainless steel.

Grout: Erosion control anchoring cement; factory-packaged, non-shrink, non-staining,

hydraulic-controlled expansion cement formulation for mixing with water at a Project site to create pourable anchoring, patching and grouting compound. Provide formulation that is resistant to erosion from water exposure without needing protection by a sealer or waterproof coating and that is recommended by manufacturer for exterior use.

Concrete footings shall conform to the provisions in Section 51, "Concrete Structures", of the Standard Specification and these special provisions.

INSTALLATION

The Contractor shall require a single installer to perform the work of this Section, having no less than five years of successful experience in installation of metal fencing and gates similar to those required for this project.

Contractor shall verify metal work dimensions by field measurements before fabrication and indicated measurements on plans. Coordinate fabrication schedule with construction progress to avoid delaying the work.

The fencing shall be erected as shown on the plans with fence posts in holes formed by sleeves provided in the concrete footings to receive the fence posts.

The wrought iron fence shall be carefully erected, true to line and grade. Posts shall be vertical with the deviation from the vertical not exceeding 3mm at the top.

Cutting, Fitting and Placement: Perform cutting, drilling and fitting required for installing metalwork. Set metal work accurately in location, alignment and elevation; with edges and surfaces level, plumb, true and free of rack and measured from established lines and levels.

When welding, use materials and methods that minimize distortion and develop strength and corrosion resistance of base materials.

Obtain fusion without undercut or overlap.

Remove welding flux immediately.

At exposed connections, finish exposed welds and surfaces smooth and blending so roughness shows after finishing and contour of welding surface matched that of adjacent surface.

After erecting all metal work, any abrasions of the galvanized or exposed steel shall be repaired in accordance to the provisions in Section 83-1, "Railings," of the Standard Specifications.

Apply polyester powder paint in accordance with the provisions in Section 59, "Painting", of the Standard Specifications and these special provisions.

Metal fence shall be fabricated in accordance with the details shown on the plans and as directed by Engineer.

MEASUREMENT AND PAYMENT

Quantities of wrought iron fence to be paid for will be determined by the meter from actual measurements, the measurements to be made parallel to the ground slope along the line of completed fence, deducting the widths of openings.

Quantities of wrought iron gates of the type shown in the Engineer's Estimate will be determined from actual count. A gate unit complete in place shall include one gate with all necessary fittings, hardware and gate latch posts.

The contract price paid per linear meter for wrought iron fence and for wrought iron gates of the type shown in the Engineer's Estimate shall include full compensation for furnishing all labor, materials, tools, equipment, and incidentals and for doing all the work involved in installing wrought iron fence and for wrought iron gates, complete in place, including polyester powder paint, as shown on the plans, as specified in the Standard Specifications and these special provisions and as directed by Engineer.

Full compensation for the disposal of earthly material outside the highway right of way in conformance with the provisions as provided in "Hazardous and Non-Hazardous Material Excavation," shall be considered as included in the contract price paid per meter for wrought iron fence and the contract unit price paid for wrought iron pedestrian gate and wrought iron vehicular gate and no additional compensation will be allowed therefore.

SECTION 11. (BLANK)

SECTION 12. (BLANK)

SECTION 13: RAILROAD RELATIONS AND INSURANCE REQUIREMENTS

13-1: RELATIONS WITH RAILROAD COMPANY

13-1.01 GENERAL

The term "Railroad" shall mean the San Francisco Bay Area Rapid Transit District (BART) and the San Francisco Municipal Railway (MUNI).

It is expected that the Railroad will cooperate with the Contractor to the end that the work may be handled in an efficient manner. However, except for the additional compensation provided for hereinafter for delays in completion of specific unit of work to be performed by the Railroad, and except as provided in Public Contracts Code Section 7102, the Contractor shall have no claim for damages, extension of time, or extra compensation in the event his work is held up by work performed by the Railroad.

The Contractor must understand the Contractor's right to enter Railroad's property is subject to the absolute right of Railroad to cause the Contractor's work on Railroad's property to cease if, in the opinion of Railroad, Contractor's activities create a hazard to Railroad's property, employees, and operations.

The Contractor shall sign and submit to the Railroad the Contractor's Endorsement, in the form attached hereto.

13-1.02 RAILROAD REQUIREMENTS

The Contractor shall notify Mr. Edwin Kung, Manager Special Services Engineering, BART 101 8th Street Oakland, CA 94607, telephone (510) 464-6445, fax (510) 464-6470, Mr. John Katz, Senior Project Planner, MUNI, 1145 Market Street 5th Floor San Francisco, CA 94103, telephone (415) 554-3124, fax (415) 554-3127, and the Engineer, in writing, at least 10 working days before performing any work on, or adjacent to the property, tracks or subway structure of the Railroad.

The Contractor shall cooperate with the Railroad where work is over the Railroad tracks or subway structure, or within the limits of Railroad property, to expedite the work and avoid interference with the operation of railroad equipment.

The Contractor shall comply with the rules and regulations of Railroad or the instructions of its representatives in relation to protecting the tracks, subway structure and property of Railroad and the traffic moving on such tracks and inside such subway structure, as well as the wires, signals and other property of Railroad, its tenants or licensees, at and in the vicinity of the work during the period of construction.

The Contractor shall perform work to not endanger or interfere with the safe operation of the tracks, subway structure and property of Railroad and traffic moving on such tracks and inside such subway structure, as well as wires, signals and other property of Railroad, its tenants or licensees, at or in the vicinity of the work.

The Contractor shall take protective measures to keep railroad facilities free of sand or debris resulting from his operations. Damage to railroad facilities resulting from Contractor's operations will be repaired or replaced by Railroad and the cost of such repairs or replacement shall be deducted from the Contractor's progress and final pay estimates.

The Contractor shall contact the Railroad's "Call Before You Dig" at least 48 hours prior to commencing work, at BART (510) 464-6445, MUNI (415) 554-3124 to determine location of fiber optics. If a telecommunications system is buried anywhere on or near railroad property, the Contractor will coordinate with the Railroad and the Telecommunication Company(ies) to arrange for relocation or other protection of the system prior to beginning any work on or near Railroad Property.

The Contractor shall not pile nor store any materials nor park any equipment over the subway structure closer than 2.28-meter (7'-6") to the exterior face of subway structure, unless directed by Railroad's representative.

The Contractor shall also abide by the following general guidelines for design and construction over or adjacent to Railroad's subway structures during the course of construction:

> Structures over or adjacent to Railroad's subway structures shall be designed and constructed so as not to impose any temporary or permanent adverse effects on subway. The minimum clearance between any part of the adjacent structures to exterior face of substructures shall be 2.28-meter (7'-6"). Minimum cover of 2.44-meter (8 feet) shall be maintained wherever possible.

Allowable additional average vertical loading over cut-and-cover subways shall be in accordance with the following:

D (ft)	Allowable Additional Average Vertical Loading (psf)
D>20	0
5<D<20	800-40D
D<5	600

Where D is the vertical distance from the top of the tunnel roof to the ground surface.
Allowable additional average vertical loading over steel-lined tunnels shall be in accordance with the following:

D (ft)	Allowable Additional Average Vertical Loading (psf)
D=35	0
D<35	120x(35-D)

Where D is the vertical distance from the top of tunnel roof to the ground surface.
Where basements are excavated, the allowable additional average vertical loading stated above can be increased to the extent that it is balanced by the weight of the removed material. The effects of soil rebound in such cases shall be fully analyzed.

Shoring is required for excavations in the Zone of Influence. Zone influence is defined as the area above a Line of Influence which is a line from the critical point of substructure at a slope of 1 ½ horizontal to 1 vertical (line sloping towards ground level).

Shoring shall be required to maintain at-rest soil condition and monitored for movement.
Soil redistribution caused by temporary shoring or permanent foundation system shall be analyzed.

Dewatering shall be monitored for changes in groundwater level. Recharging will be required if existing groundwater level is expected to drop more than 2 feet.

Piles shall be pre-drilled to a minimum of 10 feet below the Line of Influence. Piles shall be driven in a sequence away from Railroad structure. No pile will be allowed between steel-lined tunnels.

Subway structures shall be monitored for vibration during pile driving operations for all piles within 100 feet of the structures. Steel-lined tunnels shall also be monitored for movement and deformation. Requirements for monitoring will be provided upon request.

The above shall be considered as general information only and is not intended to cover all situations. The net effect of equipment load over the Railroad's subway structure shall be calculated and submitted to Railroad for review and approval.

Notwithstanding these guidelines, pertinent design and construction documents shall be submitted to the Railroad for review and approval. In addition, the following shall be submitted as applicable:

Geologic Hazards Evaluation and Geotechnical Investigation reports.

The reports shall include engineering geology map, site plan showing the location of subway structures, Railroad easement, soil reworking plan and the geological conclusion and recommendations.

Dewatering monitoring and recharging plans.

Vibration monitoring plan and/or movements and deformation monitoring plans for steel-lined tunnels. Plans shall include locations and details of instruments in subway.
Foundation plan showing the anticipated total foundation loads.
Excavation plan for area within the Zone of Influence showing excavation slope or shoring system.

Procedures and control of soil compaction operation.

Walkways with railing shall be constructed by Contractor over open excavation areas when in close proximity of subway structures, and railings shall not be closer than 2.28-meter (7'-6") horizontally from exterior face of subway structure.

Infringement on the above temporary construction clearances by the Contractor's operations shall be submitted to the Railroad through the Engineer, and shall not be undertaken until approved by the Railroad, and until the Engineer has obtained any necessary authorization from any governmental body or bodies having jurisdiction thereover.

No extension of time or extra compensation will be allowed in the event that the Contractor's work is delayed pending Railroad approval and governmental authorization.

Four sets of plans, in 279mm x 432mm (11" x 17") format, and two sets of calculations showing details of construction affecting the Railroad's subway structure and property not included in the contract plans, including but not limited to shoring and falsework, shall be submitted to the Engineer for review prior to submittal to Railroad (Les Freligh, District Real Estate Surveyor, BART, 1330 Broadway Suite 1800, Oakland, CA 94612) for final approval. Shoring shall be designed in accordance with Railroad's shoring requirements. All plans and calculations shall be prepared and signed by a professional civil engineer registered in the State of California. The review and approval by Railroad may take up to 6 weeks after receipt of all necessary information. No work shall be undertaken until such time as the Railroad has given such approval.

Heavy equipment crossing over subway structure of Railroad for the purpose of hauling abandoned material, earth, rock, paving or other materials will not be permitted. If the Contractor, for the purpose of constructing highway structures, desires to move equipment or materials across Railroad's subway structure, the Contractor shall first obtain permission from Railroad. Should Railroad approve the crossing, the Contractor shall bear the cost of the warning devices that might be required. The Contractor shall furnish the Contractor's own employees as flagmen to control movements of vehicles.

Blasting shall not be permitted.

The Contractor shall, upon completion of the work covered by this contract to be performed by Contractor upon the premises or over or adjacent to the tracks and subway structure of Railroad, promptly remove from the premises of Railroad the Contractor's tools, implements and other materials, whether brought upon said premises by the Contractor or his subcontractor, and cause said premises to be left in a clean and presentable condition.

13-1.03 PROTECTION OF RAILROAD FACILITIES

Upon advance notification of not less than 10 working days by the Contractor, Railroad representatives, conductors, flagmen or watchmen will be provided by Railroad to protect its facilities, property and movements of its trains or engines. Notice shall be made to Mr. Edwin Kung, Manager Special Services Engineering, BART 101 8th Street Oakland, CA 94607, telephone (510) 464-6445.

At the time of notification, the Contractor shall provide Railroad with a schedule of dates that construction activities will be held, as well as times, if outside normal working hours. Subsequent deviation from the schedule shall require 10 working days advance notice from the first affected date. The Railroad will furnish such personnel or other protective devices:

(a) For any excavation below elevation of street surface if, in the opinion of Railroad's representative, subway structure or other Railroad facilities may be subject to overloading, damage or movement.

(b) During any clearing, grubbing, grading or blasting in proximity to Railroad which, in the opinion of Railroad's representative, may endanger Railroad facilities or operations.

(c) During any of Contractor's operations when, in the opinion of Railroad's representatives, Railroad facilities, including, but not limited to, tracks, subway structures, buildings, signals, wire lines or pipe lines, may be endangered.

The cost of inspection provided by Railroad during the period of constructing or demolishing that portion of the project located on or near Railroad property, as deemed necessary for the protection of Railroad's facilities and trains, will be borne by the State for a period of 60 working days, beginning on the date work commences on or near property of Railroad. The Contractor shall pay to the State liquidated damages in the sum of $500 per day for each day in excess of the above-referenced 60 working days the Contractor works on or near Railroad property, and which requires protection of Railroad's facilities and trains.

13-1.04 WORK BY RAILROAD

Railroad will furnish or cause to be furnished as necessary due to construction, labor materials, tools and equipment to perform certain works including relocation of telephone, telegraphy and signal lines and appurtenances and will perform any other work in connection therewith.

The following work by Railroad will be performed by Railroad forces and is not a part of the work under this contract.

(a) The Railroad will perform preliminary engineering inspection as specified in Section 13-1.03, “Protection of Railroad Facilities,” of these special provisions.

13-1.05 DELAYS DUE TO WORK BY RAILROAD

No delay due to work by the Railroad is anticipated.

If delays due to work by the Railroad occur, and the Contractor sustains loss which, in the opinion of the Engineer, could not have been avoided by the judicious handling of forces, equipment and plant, the amount of said loss shall be determined as provided in Section 8-1.09, "Right of Way Delays," of the Standard Specifications.

If a delay due to work by Railroad occurs, an extension of time determined pursuant to the provisions in Section 8-1.07, "Liquidated Damages," of the Standard Specifications will be granted.

13-1.06 LEGAL RELATIONS

The provisions of Section 13-1, "Relations with Railroad Company," and the provisions of Section 13-2, "Railroad Protective Insurance," of these special provisions shall inure directly to the benefit of Railroad.

13-1.07 INDEMNIFICATION

As between the Railroad as one party, and the Contractor as the other party, the Contractor is deemed to assume responsibility and liability for all damage, loss or injury of any kind or nature whatever to persons or property, public utilities and non-transit facilities, caused by or resulting from or in connection with any action or omission on the part of the Contractor or any of Contractor’s officers, agents, directors, employees or subcontractors or their performance of the work.

The Contractor shall indemnify, defend and hold harmless the Railroad, and any and all of its directors, officers, agents or employees to the maximum extent permitted by law from and against any and all claims, liabilities, losses, damages, or expenses (including attorneys’ fees and related costs), whether direct or indirect, for loss of or damage to any property (including the property of the Railroad), for injury to or death of any person (including an employee of the Railroad, public utilities and non-transit facilities, or the contractor or its subcontractors), or otherwise arising out of or relating to the performance of the work and the contract.

This duty on the part of the Contractor to indemnify, defend and hold harmless the Railroad shall expressly include all claims and lawsuits brought against the Railroad where the Railroad is named as a defendant but is not the real party in interest, including, without limitation, all actions on stop notices brought by subcontractors on this contract.

13-2 RAILROAD PROTECTIVE INSURANCE

The term "Railroad" shall mean the San Francisco Bay Area Rapid Transit District (BART) and the San Francisco Municipal Railway (MUNI).

In addition to any other form of insurance or bonds required under the terms of the contract and specifications, the Contractor will be required to carry insurance of the kinds and in the amounts hereinafter specified.

Such insurance shall be approved by the Railroad before any work is performed on Railroad's property and shall be carried until all work required to be performed on or adjacent to the Railroad's property under the terms of the contract is satisfactorily completed as determined by the Engineer, and thereafter until all tools, equipment and materials have been removed from Railroad's property and such property is left in a clean and presentable condition.

The insurance herein required shall be obtained by the Contractor, who shall furnish the Railroad with completed certificates, in the form attached hereto, signed by the insurance company or its authorized agent or representative, reflecting the existence of each of the policies required by 1 and 2 below including coverage for X, C and U and completed operations hazards, and the original policy of insurance (or a certified duplicate original policy) required by 3 below, to the address shown in the item No. 2 under “Insurance” elsewhere in these special provisions.

Certificate of insurance shall guarantee that the policy under 1 and 2 will not be amended, altered, modified or canceled insofar as the coverage contemplated hereunder is concerned, without at least thirty (30) days notice mailed by registered mail to the Railroad.

Full compensation for all premiums which the Contractor is required to pay on all the insurance described hereinafter shall be considered as included in the prices paid for the various items of work to be performed under the contract, and no additional allowance will be made therefor or for additional premiums which may be required by extensions of the policies of insurance.

The approximate ratio of the estimated cost of the work over or under or within 50 feet of Railroad's subway structure to the total estimated cost is 0.1. Railroad traffic is inside the underground structure.

1. Contractor's Public Liability and Property Damage Liability Insurance

The Contractor shall, with respect to the operations he performs within or adjacent to Railroad's property, carry regular Contractor's Public Liability and Property Damage Liability Insurance providing for the same limits as specified for Railroad's Protective Public Liability and Property Damage Liability insurance to be furnished for and in behalf of Railroad as hereinafter provided.

If any part of the work within or adjacent to Railroad's property is subcontracted, the Contractor in addition to carrying the above insurance shall provide the above insurance on behalf of the subcontractors to cover their operations.

2. Contractor's Protective Public Liability and Property Damage Liability Insurance.

The Contractor shall, with respect to the operations performed for him by subcontractors who do work within or adjacent to Railroad's property, carry in his own behalf regular Contractor's Protective Public Liability and Property Damage Liability Insurance providing for the same limits as specified for Railroad's Protective Public Liability and Property Damage Liability Insurance to be furnished for and on behalf of Railroad as hereinafter provided.

3. Railroad's Protective Public Liability and Property Damage Liability Insurance

The Contractor shall, with respect to the operations he performs within or adjacent to Railroad's property or that of any of his subcontractors who do work within or adjacent to Railroad's property perform, have issued and furnished in favor of Railroad, Policy or policies of insurance in the Railroad Protective Liability Form as hereinafter specified.

INSURANCE

At all times during the life of this Permit, or as may further be required by this Permit, Permittee at its own cost and expense, shall provide the insurance specified as follows:

1. Evidence Required

At or before execution of this Permit, Permittee shall provide BART with a certificate of insurance executed by an authorized representative of the insurer(s) evidencing that Permittee's insurance complies with this Article, including a copy of all required endorsements.

2. Notice of Cancellation, Reduction or Material Change in Coverage.

Policies shall be endorsed to provide thirty (30) days prior written notice of any cancellation, reduction or material change in coverage. Notices, including evidence of insurance, shall be forwarded to:

San Francisco Bay Area Rapid Transit District
Attention: Manager of Insurance
P. O. Box 12688
Oakland, California 94604-2688

3. Qualifying Insurers

All policies shall be issued by California admitted companies which hold a current policy holders alphabetic and financial size category rating of not less than A:VIII according to Best's Insurance Reports.

4. Insurance Required

A. Commercial General Liability Insurance for bodily injury (including death) and property damage which provides limits of not less than Ten Million Dollars ($10,000,000) per occurrence and Ten Million Dollars ($10,000,000) annual aggregate as applicable.

1. Coverage included shall include:

a) Premises and Operations;
b) Products/Completed Operations;
c) Broad Form Property Damage;
d) Contractual liability;
e) Personal Injury liability; and
f) Cross-Liability and Severability of Interests.
g) Explosion, Collapse and Underground (XCU)
h) Independent Contractors Liability.

2. Such insurance shall include the following endorsements, copies of which shall be provided to BART:

a) Inclusion of BART, its directors, officers, representatives, agents and employees as additional insured as respects to Permittee's operations in connection with this Permit;
b) Stipulation that the insurance is primary insurance and that no insurance or self-insurance of BART will be called upon to contribute to a loss.

B. Automobile Liability for bodily injury (including death) and property damage which provides a coverage limit of at least One Million Dollars ($1,000,000) combined single limit per occurrence applicable for all owned, non-owned and hired vehicles.

C. Statutory Workers' Compensation and Employer's Liability Insurance for not less than One Million Dollars ($1,000,000) per accident applicable to Employer's Liability coverage for all employees engaged in services or operations under this Permit. The policy shall include broad form all-states/other states coverage. Coverage shall be specifically endorsed to include the insurer's waiver of subrogation in favor of Railroad, its directors, officers, representatives, agents and employees, a copy of which shall be provided to Railroad. Should any such work be subcontracted, Contractor shall require each subcontractor of any tier to similarly comply with this article, all in strict compliance with federal and state law.

D. Railroad Protective Liability with respect to the operations of Permittee and any of its contractors or subcontractors above the railroad tracks or within fifty (50) feet horizontally of the railroad tracks, Railroad Protective Liability Insurance with a policy form acceptable to BART, including pollution coverage for job site fuels and lubricants in an amount not less that Ten ($10,000,000) million dollars per occurrence, combined single limit, for Coverages A and B, for losses arising out of injury to or death of any person and for physical loss of or damage to or destruction of property , including loss of use thereof. Prior to commencing work or entering onto the Property, Permittee shall file the original copy of the policy with the BART Insurance Department. This policy is to be kept in effect until the entire project is completed. If the $10 million limit is diminished at any time during the Project, Permittee will be obligated to restore the Railroad Protective Liability Insurance limit to the full $10 million.

5. Special Provisions

The foregoing requirements as to the types and limits of insurance coverage to be maintained by Permittee and any approval of said insurance by District is not intended to and shall not in any manner limit or qualify the liabilities and obligations otherwise assumed by Permittee pursuant to this Permit, including but not limited to the provisions concerning indemnification. Should any of the work be contracted, Permittee shall require each of its contractors of any tier to provide the aforementioned insurance.

* (Note: XCU coverage (Section 4.A.1.g) is only required under certain circumstances (excavation, borings, etc.). General liability limits may be increased relative to risk involved).

CERTIFICATE OF INSURANCE

Exhibit "C"

This is to certify to:

RAILROAD FILE NO.
04-291001
Central Viaduct Reconstruction

(1) Railroad Agreements Branch, Room # 102
Division of Engineering Services
California Department of Transportation
1801 30th Street, Sacramento, California 95816

(2) and to the following Railroad Company

that such insurance as is afforded by the policy or policies described below for bodily injury liability and property damage liability is in full force and effect as of the date of this certificate and covers the following contractor as a named insured with respect to liability for damages arising out of operations performed by or for the named insured in connection with the contract or work described below.

1. Named Insured and Address

This is to certify that policies of insurance listed below have been issued to the insured named above and are in force at this time. Notwithstanding any requirement, term or condition of any contract or other document with respect to which this certificate may be issued or may pertain, the insurance afforded by the policies described herein is subject to all the terms, exclusions and conditions of such policies.

2. Description of Work
Contract No. 04-291001

Coverages	Policy Expiration Date	Limits of Liability Each Occurrence	Aggregate
Contractor's Bodily Injury Liability and Property Damage Liability			
Umbrella or Excess Liability			

All of the coverages include coverage for the completed operations hazard, and X, C and U exposures.

Name of Insurance Company by Coverage

Coverages	Company	Policy Number
Bodily Injury Liability		
Property Damage Liability		
Umbrella or Excess Liability		

4. The policy or policies described above will not be amended, altered, modified or cancelled until thirty (30) days after written notice thereof has been given by registered mail to the Railroad named as certificate holder in this certificate.

Certificate Date:

For _____
(Insurance Company)

By _____
(Authorized Agent or Representative)

State of California
Department of Transportation
DH-0S-A104(8-10-00)

CONTRACTOR'S ENDORSEMENT

As a condition to entering upon Railroad's right-of-way to perform work pursuant to this agreement, Licensee's contractor, _____, whose address is _____ (hereinafter "Contractor), agrees to comply with and be bound by all the terms and provisions of this agreement relating to the work to be performed and the insurance requirements set forth in Section 13 of the Contract Special Provisions.

Before the Contractor commences any work, the Contractor will provide the Railroad with (1) a binder of insurance for the Railroad Protective Liability Insurance described in Section 13.2 of the Contract Special Provisions, and the original policy (or a certified duplicate original policy), and (2) a certificate issued by its insurance carrier providing the other insurance coverage required pursuant to Section 13.2 of the Contract Special Provisions in a policy or policies which contain the following type endorsement:

San Francisco Bay Area Rapid Transit District is named as an additional insured with respect to all liabilities arising out of Insured's performance of work on behalf of the State.

This endorsement shall be completed and directed to:

San Francisco Bay Area Rapid Transit District
Attention: Manager of Insurance
P. O. Box 12688
Oakland, California 94604-2688

_____
CONTRACTOR (print name on above line)

By: _____

Title: _____

SECTION 14. FEDERAL REQUIREMENTS FOR FEDERAL-AID CONSTRUCTION PROJECTS

GENERAL.—The work herein proposed will be financed in whole or in part with Federal funds, and therefore all of the statutes, rules and regulations promulgated by the Federal Government and applicable to work financed in whole or in part with Federal funds will apply to such work. The "Required Contract Provisions, Federal-Aid Construction Contracts, "Form FHWA 1273, are included in this Section 14. Whenever in said required contract provisions references are made to "SHA contracting officer", "SHA resident engineer", or "authorized representative of the SHA", such references shall be construed to mean "Engineer" as defined in Section 1-1.18 of the Standard Specifications.

PERFORMANCE OF PREVIOUS CONTRACT.—In addition to the provisions in Section II, "Nondiscrimination," and Section VII, "Subletting or Assigning the Contract," of the required contract provisions, the Contractor shall comply with the following:

The bidder shall execute the CERTIFICATION WITH REGARD TO THE PERFORMANCE OF PREVIOUS CONTRACTS OR SUBCONTRACTS SUBJECT TO THE EQUAL OPPORTUNITY CLAUSE AND THE FILING OF REQUIRED REPORTS located in the proposal. No request for subletting or assigning any portion of the contract in excess of $10,000 will be considered under the provisions of Section VII of the required contract provisions unless such request is accompanied by the CERTIFICATION referred to above, executed by the proposed subcontractor.

NON-COLLUSION PROVISION.—The provisions in this section are applicable to all contracts except contracts for Federal Aid Secondary projects.

Title 23, United States Code, Section 112, requires as a condition precedent to approval by the Federal Highway Administrator of the contract for this work that each bidder file a sworn statement executed by, or on behalf of, the person, firm, association, or corporation to whom such contract is to be awarded, certifying that such person, firm, association, or corporation has not, either directly or indirectly, entered into any agreement, participated in any collusion, or otherwise taken any action in restraint of free competitive bidding in connection with the submitted bid. A form to make the non-collusion affidavit statement required by Section 112 as a certification under penalty of perjury rather than as a sworn statement as permitted by 28, USC, Sec. 1746, is included in the proposal.

PARTICIPATION BY MINORITY BUSINESS ENTERPRISES IN SUBCONTRACTING.—Part 23, Title 49, Code of Federal Regulations applies to this Federal-aid project. Pertinent sections of said Code are incorporated in part or in its entirety within other sections of these special provisions.

Schedule B—Information for Determining Joint Venture Eligibility

(This form need not be filled in if all joint venture firms are minority owned.)

1. Name of joint venture _____
2. Address of joint venture _____
3. Phone number of joint venture _____
4. Identify the firms which comprise the joint venture. (The MBE partner must complete Schedule A.) _____
   _____

   a. Describe the role of the MBE firm in the joint venture. _____
      _____
   b. Describe very briefly the experience and business qualifications of each non-MBE joint venturer: _____
      _____

5. Nature of the joint venture's business _____
   _____
6. Provide a copy of the joint venture agreement.
7. What is the claimed percentage of MBE ownership? _____
8. Ownership of joint venture: (This need not be filled in if described in the joint venture agreement, provided by question 6.).

   a. Profit and loss sharing.
   b. Capital contributions, including equipment.

c. Other applicable ownership interests.

9. Control of and participation in this contract. Identify by name, race, sex, and "firm" those individuals (and their titles) who are responsible for day-to-day management and policy decision making, including, but not limited to, those with prime responsibility for:

a. Financial decisions _____

b. Management decisions, such as:

(1) Estimating _____

(2). Marketing and sales _____

(3). Hiring and firing of management personnel _____

_____

(4) Purchasing of major items or supplies _____

_____

c. Supervision of field operations _____

Note.—If, after filing this Schedule B and before the completion of the joint venture's work on the contract covered by this regulation, there is any significant change in the information submitted, the joint venture must inform the grantee, either directly or through the prime contractor if the joint venture is a subcontractor.

Affidavit

"The undersigned swear that the foregoing statements are correct and include all material information necessary to identify and explain the terms and operation of our joint venture and the intended participation by each joint venturer in the undertaking. Further, the undersigned covenant and agree to provide to grantee current, complete and accurate information regarding actual joint venture work and the payment therefor and any proposed changes in any of the joint venture arrangements and to permit the audit and examination of the books, records and files of the joint venture, or those of each joint venturer relevant to the joint venture, by authorized representatives of the grantee or the Federal funding agency. Any material misrepresentation will be grounds for terminating any contract which may be awarded and for initiating action under Federal or State laws concerning false statements."

Name of Firm	Name of Firm
Signature	Signature
Name	Name
Title	Title
Date	Date

Date _____

State of _____

County of _____

On this ____ day of _____, 19 __, before me appeared (Name) _____, to me personally known, who, being duly sworn, did execute the foregoing affidavit, and did state that he or she was properly authorized by (Name of firm) _____ to execute the affidavit and did so as his or her free act and deed.

Notary Public _____

Commission expires _____

[Seal]

Date _____

State of _____

County of _____

On this ___ day of _____, 19 __, before me appeared (Name) _____ to me personally known, who, being duly sworn, did execute the foregoing affidavit, and did state that he or she was properly authorized by (Name of firm) _____ to execute the affidavit and did so as his or her free act and deed.

Notary Public _____

Commission expires _____

[Seal]

REQUIRED CONTRACT PROVISIONS
FEDERAL-AID CONSTRUCTION CONTRACTS

I. GENERAL

1. These contract provisions shall apply to all work performed on the contract by the contractor's own organization and with the assistance of workers under the contractor's immediate superintendence and to all work performed on the contract by piecework, station work, or by subcontract.

2. Except as otherwise provided for in each section, the contractor shall insert in each subcontract all of the stipulations contained in these Required Contract Provisions, and further require their inclusion in any lower tier subcontract or purchase order that may in turn be made. The Required Contract Provisions shall not be incorporated by reference in any case. The prime contractor shall be responsible for compliance by any subcontractor or lower tier subcontractor with these Required Contract Provisions.

3. A breach of any of the stipulations contained in these Required Contract Provisions shall be sufficient grounds for termination of the contract.

4. A breach of the following clauses of the Required Contract Provisions may also be grounds for debarment as provided in 29 CFR 5.12:

   Section I, paragraph 2;
   Section IV, paragraphs 1, 2, 3, 4, and 7;
   Section V, paragraphs 1 and 2a through 2g.

5. Disputes arising out of the labor standards provisions of Section IV (except paragraph 5) and Section V of these Required Contract Provisions shall not be subject to the general disputes clause of this contract. Such disputes shall be resolved in accordance with the procedures of the U.S. Department of Labor (DOL) as set forth in 29 CFR 5, 6, and 7. Disputes within the meaning of this clause include disputes between the contractor (or any of its subcontractors) and the contracting agency, the DOL, or the contractor's employees or their representatives.

6. **Selection of Labor:** During the performance of this contract, the contractor shall not:

   a. discriminate against labor from any other State, possession, or territory of the United States (except for employment preference for Appalachian contracts, when applicable, as specified in Attachment A), or

   b. employ convict labor for any purpose within the limits of the project unless it is labor performed by convicts who are on parole, supervised release, or probation.

II. NONDISCRIMINATION

(Applicable to all Federal-aid construction contracts and to all related subcontracts of $10,000 or more.)

1. **Equal Employment Opportunity:** Equal employment opportunity (EEO) requirements not to discriminate and to take affirmative action to assure equal opportunity as set forth under laws, executive orders, rules, regulations (28 CFR 35, 29 CFR 1630, and 41 CFR 60) and orders of the Secretary of Labor as modified by the provisions prescribed herein, and imposed pursuant to 23 U.S.C. 140 shall constitute the EEO and specific affirmative action standards for the contractor's project activities under this contract. The Equal Opportunity Construction Contract Specifications set forth under 41 CFR 60-4.3 and the provisions of the American Disabilities Act of 1990 (42 U.S.C. 12101 et seq.) set forth under 28 CFR 35 and 29 CFR 1630 are incorporated by reference in this contract. In the execution of this contract, the contractor agrees to comply with the following minimum specific requirement activities of EEO:

   a. The contractor will work with the State highway agency (SHA) and the Federal Government in carrying out EEO obligations and in their review of his/her activities under the contract.

   b. The contractor will accept as his operating policy the following statement:

"It is the policy of this Company to assure that applicants are employed, and that employees are treated during employment, without regard to their race, religion, sex, color, national origin, age or disability. Such action shall include: employment, upgrading, demotion, or transfer; recruitment or recruitment advertising; layoff or termination; rates of pay or other forms of compensation; and selection for training, including apprenticeship, preapprenticeship, and/or on-the-job training."

2. **EEO Officer:** The contractor will designate and make known to the SHA contracting officers an EEO Officer who will have the responsibility for and must be capable of effectively administering and promoting an active contractor program of EEO and who must be assigned adequate authority and responsibility to do so.

3. **Dissemination of Policy:** All members of the contractor's staff who are authorized to hire, supervise, promote, and discharge employees, or who recommend such action, or who are substantially involved in such action, will be made fully cognizant of, and will implement, the contractor's EEO policy and contractual responsibilities to provide EEO in each grade and classification of employment. To ensure that the above agreement will be met, the following actions will be taken as a minimum:

   a. Periodic meetings of supervisory and personnel office employees will be conducted before the start of work and then not less often than once every six months, at which time the contractor's EEO policy and its implementation will be reviewed and explained. The meetings will be conducted by the EEO Officer.

   b. All new supervisory or personnel office employees will be given a thorough indoctrination by the EEO Officer, covering all major aspects of the contractor's EEO obligations within thirty days following their reporting for duty with the contractor.

   c. All personnel who are engaged in direct recruitment for the project will be instructed by the EEO Officer in the contractor's procedures for locating and hiring minority group employees.

   d. Notices and posters setting forth the contractor's EEO policy will be placed in areas readily accessible to employees, applicants for employment and potential employees.

   e. The contractor's EEO policy and the procedures to implement such policy will be brought to the attention of employees by means of meetings, employee handbooks, or other appropriate means.

4. **Recruitment:** When advertising for employees, the contractor will include in all advertisements for employees the notation: "An Equal Opportunity Employer." All such advertisements will be placed in publications having a large circulation among minority groups in the area from which the project work force would normally be derived.

   a. The contractor will, unless precluded by a valid bargaining agreement, conduct systematic and direct recruitment through public and private employee referral sources likely to yield qualified minority group applicants. To meet this requirement, the contractor will identify sources of potential minority group employees, and establish with such identified sources procedures whereby minority group applicants may be referred to the contractor for employment consideration.

   b. In the event the contractor has a valid bargaining agreement providing for exclusive hiring hall referrals, he is expected to observe the provisions of that agreement to the extent that the system permits the contractor's compliance with EEO contract provisions. (The DOL has held that where implementation of such agreements have the effect of discriminating against minorities or women, or obligates the contractor to do the same, such implementation violates Executive Order 11246, as amended.)

   c. The contractor will encourage his present employees to refer minority group applicants for employment. Information and procedures with regard to referring minority group applicants will be discussed with employees.

5. **Personnel Actions:** Wages, working conditions, and employee benefits shall be established and administered, and personnel actions of every type, including hiring, upgrading, promotion, transfer, demotion, layoff, and termination, shall be taken without regard to race, color, religion, sex, national origin, age or disability. The following procedures shall be followed:

a. The contractor will conduct periodic inspections of project sites to insure that working conditions and employee facilities do not indicate discriminatory treatment of project site personnel.

b. The contractor will periodically evaluate the spread of wages paid within each classification to determine any evidence of discriminatory wage practices.

c. The contractor will periodically review selected personnel actions in depth to determine whether there is evidence of discrimination. Where evidence is found, the contractor will promptly take corrective action. If the review indicates that the discrimination may extend beyond the actions reviewed, such corrective action shall include all affected persons.

d. The contractor will promptly investigate all complaints of alleged discrimination made to the contractor in connection with his obligations under this contract, will attempt to resolve such complaints, and will take appropriate corrective action within a reasonable time. If the investigation indicates that the discrimination may affect persons other than the complainant, such corrective action shall include such other persons. Upon completion of each investigation, the contractor will inform every complainant of all of his avenues of appeal.

6. Training and Promotion:

a. The contractor will assist in locating, qualifying, and increasing the skills of minority group and women employees, and applicants for employment.

b. Consistent with the contractor's work force requirements and as permissible under Federal and State regulations, the contractor shall make full use of training programs, i.e., apprenticeship, and on-the-job training programs for the geographical area of contract performance. Where feasible, 25 percent of apprentices or trainees in each occupation shall be in their first year of apprenticeship or training. In the event a special provision for training is provided under this contract, this subparagraph will be superseded as indicated in the special provision.

c. The contractor will advise employees and applicants for employment of available training programs and entrance requirements for each.

d. The contractor will periodically review the training and promotion potential of minority group and women employees and will encourage eligible employees to apply for such training and promotion.

7. **Unions:** If the contractor relies in whole or in part upon unions as a source of employees, the contractor will use his/her best efforts to obtain the cooperation of such unions to increase opportunities for minority groups and women within the unions, and to effect referrals by such unions of minority and female employees. Actions by the contractor either directly or through a contractor's association acting as agent will include the procedures set forth below:

a. The contractor will use best efforts to develop, in cooperation with the unions, joint training programs aimed toward qualifying more minority group members and women for membership in the unions and increasing the skills of minority group employees and women so that they may qualify for higher paying employment.

b. The contractor will use best efforts to incorporate an EEO clause into each union agreement to the end that such union will be contractually bound to refer applicants without regard to their race, color, religion, sex, national origin, age or disability.

c. The contractor is to obtain information as to the referral practices and policies of the labor union except that to the extent such information is within the exclusive possession of the labor union and such labor union refuses to furnish such information to the contractor, the contractor shall so certify to the SHA and shall set forth what efforts have been made to obtain such information.

d. In the event the union is unable to provide the contractor with a reasonable flow of minority and women referrals within the time limit set forth in the collective bargaining agreement, the contractor will, through

independent recruitment efforts, fill the employment vacancies without regard to race, color, religion, sex, national origin, age or disability; making full efforts to obtain qualified and/or qualifiable minority group persons and women. (The DOL has held that it shall be no excuse that the union with which the contractor has a collective bargaining agreement providing for exclusive referral failed to refer minority employees.) In the event the union referral practice prevents the contractor from meeting the obligations pursuant to Executive Order 11246, as amended, and these special provisions, such contractor shall immediately notify the SHA.

8. **Selection of Subcontractors, Procurement of Materials and Leasing of Equipment:** The contractor shall not discriminate on the grounds of race, color, religion, sex, national origin, age or disability in the selection and retention of subcontractors, including procurement of materials and leases of equipment.

   a. The contractor shall notify all potential subcontractors and suppliers of his/her EEO obligations under this contract.

   b. Disadvantaged business enterprises (DBE), as defined in 49 CFR 23, shall have equal opportunity to compete for and perform subcontracts which the contractor enters into pursuant to this contract. The contractor will use his best efforts to solicit bids from and to utilize DBE subcontractors or subcontractors with meaningful minority group and female representation among their employees. Contractors shall obtain lists of DBE construction firms from SHA personnel.

   c. The contractor will use his best efforts to ensure subcontractor compliance with their EEO obligations.

9. **Records and Reports:** The contractor shall keep such records as necessary to document compliance with the EEO requirements. Such records shall be retained for a period of three years following completion of the contract work and shall be available at reasonable times and places for inspection by authorized representatives of the SHA and the FHWA.

   a. The records kept by the contractor shall document the following:

      (1) The number of minority and non-minority group members and women employed in each work classification on the project;

      (2) The progress and efforts being made in cooperation with unions, when applicable, to increase employment opportunities for minorities and women;

      (3) The progress and efforts being made in locating, hiring, training, qualifying, and upgrading minority and female employees; and

      (4) The progress and efforts being made in securing the services of DBE subcontractors or subcontractors with meaningful minority and female representation among their employees.

   b. The contractors will submit an annual report to the SHA each July for the duration of the project, indicating the number of minority, women, and non-minority group employees currently engaged in each work classification required by the contract work. This information is to be reported on Form FHWA-1391. If on-the-job training is being required by special provision, the contractor will be required to collect and report training data.

III. NONSEGREGATED FACILITIES

(Applicable to all Federal-aid construction contracts and to all related subcontracts of $10,000 or more.)

   a. By submission of this bid, the execution of this contract or subcontract, or the consummation of this material supply agreement or purchase order, as appropriate, the bidder, Federal-aid construction contractor, subcontractor, material supplier, or vendor, as appropriate, certifies that the firm does not maintain or provide for its employees any segregated facilities at any of its establishments, and that the firm does not permit its employees to perform their services at any location, under its control, where segregated facilities are maintained. The firm agrees that a breach of this certification is a violation of the EEO provisions of this contract. The firm further certifies that no employee will be denied access to adequate facilities on the basis of sex or disability.

b. As used in this certification, the term "segregated facilities" means any waiting rooms, work areas, restrooms and washrooms, restaurants and other eating areas, time clocks, locker rooms, and other storage or dressing areas, parking lots, drinking fountains, recreation or entertainment areas, transportation, and housing facilities provided for employees which are segregated by explicit directive, or are, in fact, segregated on the basis of race, color, religion, national origin, age or disability, because of habit, local custom, or otherwise. The only exception will be for the disabled when the demands for accessibility override (e.g. disabled parking).

c. The contractor agrees that it has obtained or will obtain identical certification from proposed subcontractors or material suppliers prior to award of subcontracts or consummation of material supply agreements of $10,000 or more and that it will retain such certifications in its files.

IV. PAYMENT OF PREDETERMINED MINIMUM WAGE

(Applicable to all Federal-aid construction contracts exceeding $2,000 and to all related subcontracts, except for projects located on roadways classified as local roads or rural minor collectors, which are exempt.)

1. General:

a. All mechanics and laborers employed or working upon the site of the work will be paid unconditionally and not less often than once a week and without subsequent deduction or rebate on any account [except such payroll deductions as are permitted by regulations (29 CFR 3)] issued by the Secretary of Labor under the Copeland Act (40 U.S.C. 276c) the full amounts of wages and bona fide fringe benefits (or cash equivalents thereof) due at time of payment. The payment shall be computed at wage rates not less than those contained in the wage determination of the Secretary of Labor (hereinafter "the wage determination") which is attached hereto and made a part hereof, regardless of any contractual relationship which may be alleged to exist between the contractor or its subcontractors and such laborers and mechanics. The wage determination (including any additional classifications and wage rates conformed under paragraph 2 of this Section IV and the DOL poster (WH-1321) or Form FHWA-1495) shall be posted at all times by the contractor and its subcontractors at the site of the work in a prominent and accessible place where it can be easily seen by the workers. For the purpose of this Section, contributions made or costs reasonably anticipated for bona fide fringe benefits under Section 1(b)(2) of the Davis-Bacon Act (40 U.S.C. 276a) on behalf of laborers or mechanics are considered wages paid to such laborers or mechanics, subject to the provisions of Section IV, paragraph 3b, hereof. Also, for the purpose of this Section, regular contributions made or costs incurred for more than a weekly period (but not less often than quarterly) under plans, funds, or programs, which cover the particular weekly period, are deemed to be constructively made or incurred during such weekly period. Such laborers and mechanics shall be paid the appropriate wage rate and fringe benefits on the wage determination for the classification of work actually performed, without regard to skill, except as provided in paragraphs 4 and 5 of this Section IV.

b. Laborers or mechanics performing work in more than one classification may be compensated at the rate specified for each classification for the time actually worked therein, provided, that the employer's payroll records accurately set forth the time spent in each classification in which work is performed.

c. All rulings and interpretations of the Davis-Bacon Act and related acts contained in 29 CFR 1, 3, and 5 are herein incorporated by reference in this contract.

2. Classification:

a. The SHA contracting officer shall require that any class of laborers or mechanics employed under the contract, which is not listed in the wage determination, shall be classified in conformance with the wage determination.

b. The contracting officer shall approve an additional classification, wage rate and fringe benefits only when the following criteria have been met:

(1) the work to be performed by the additional classification requested is not performed by a classification in the wage determination;

(2) the additional classification is utilized in the area by the construction industry;

(3) the proposed wage rate, including any bona fide fringe benefits, bears a reasonable relationship to the wage rates contained in the wage determination; and

(4) with respect to helpers, when such a classification prevails in the area in which the work is performed.

c. If the contractor or subcontractors, as appropriate, the laborers and mechanics (if known) to be employed in the additional classification or their representatives, and the contracting officer agree on the classification and wage rate (including the amount designated for fringe benefits where appropriate), a report of the action taken shall be sent by the contracting officer to the DOL, Administrator of the Wage and Hour Division, Employment Standards Administration, Washington, D.C. 20210. The Wage and Hour Administrator, or an authorized representative, will approve, modify, or disapprove every additional classification action within 30 days of receipt and so advise the contracting officer or will notify the contracting officer within the 30-day period that additional time is necessary.

d. In the event the contractor or subcontractors, as appropriate, the laborers or mechanics to be employed in the additional classification or their representatives, and the contracting officer do not agree on the proposed classification and wage rate (including the amount designated for fringe benefits, where appropriate), the contracting officer shall refer the questions, including the views of all interested parties and the recommendation of the contracting officer, to the Wage and Hour Administrator for determination. Said Administrator, or an authorized representative, will issue a determination within 30 days of receipt and so advise the contracting officer or will notify the contracting officer within the 30-day period that additional time is necessary

e. The wage rate (including fringe benefits where appropriate) determined pursuant to paragraph 2c or 2d of this Section IV shall be paid to all workers performing work in the additional classification from the first day on which work is performed in the classification.

3. Payment of Fringe Benefits:

a. Whenever the minimum wage rate prescribed in the contract for a class of laborers or mechanics includes a fringe benefit which is not expressed as an hourly rate, the contractor or subcontractors, as appropriate, shall either pay the benefit as stated in the wage determination or shall pay another bona fide fringe benefit or an hourly case equivalent thereof.

b. If the contractor or subcontractor, as appropriate, does not make payments to a trustee or other third person, he/she may consider as a part of the wages of any laborer or mechanic the amount of any costs reasonably anticipated in providing bona fide fringe benefits under a plan or program, provided, that the Secretary of Labor has found, upon the written request of the contractor, that the applicable standards of the Davis-Bacon Act have been met. The Secretary of Labor may require the contractor to set aside in a separate account assets for the meeting of obligations under the plan or program.

4. Apprentices and Trainees (Programs of the U.S. DOL) and Helpers:

a. Apprentices:

(1) Apprentices will be permitted to work at less than the predetermined rate for the work they performed when they are employed pursuant to and individually registered in a bona fide apprenticeship program registered with the DOL, Employment and Training Administration, Bureau of Apprenticeship and Training, or with a State apprenticeship agency recognized by the Bureau, or if a person is employed in his/her first 90 days of probationary employment as an apprentice in such an apprenticeship program, who is not individually registered in the program, but who has been certified by the Bureau of Apprenticeship and Training or a State apprenticeship agency (where appropriate) to be eligible for probationary employment as an apprentice.

(2) The allowable ratio of apprentices to journeyman-level employees on the job site in any craft classification shall not be greater than the ratio permitted to the contractor as to the entire work force under the registered program. Any employee listed on a payroll at an apprentice wage rate, who is not registered or otherwise employed as stated above, shall be paid not less than the applicable wage rate listed in the wage determination for the classification of work actually performed. In addition, any apprentice performing

work on the job site in excess of the ratio permitted under the registered program shall be paid not less than the applicable wage rate on the wage determination for the work actually performed. Where a contractor or subcontractor is performing construction on a project in a locality other than that in which its program is registered, the ratios and wage rates (expressed in percentages of the journeyman-level hourly rate) specified in the contractor's or subcontractor's registered program shall be observed.

(3) Every apprentice must be paid at not less than the rate specified in the registered program for the apprentice's level of progress, expressed as a percentage of the journeyman-level hourly rate specified in the applicable wage determination. Apprentices shall be paid fringe benefits in accordance with the provisions of the apprenticeship program. If the apprenticeship program does not specify fringe benefits, apprentices must be paid the full amount of fringe benefits listed on the wage determination for the applicable classification. If the Administrator for the Wage and Hour Division determines that a different practice prevails for the applicable apprentice classification, fringes shall be paid in accordance with that determination.

(4) In the event the Bureau of Apprenticeship and Training, or a State apprenticeship agency recognized by the Bureau, withdraws approval of an apprenticeship program, the contractor or subcontractor will no longer be permitted to utilize apprentices at less than the applicable predetermined rate for the comparable work performed by regular employees until an acceptable program is approved.

b. Trainees:

(1) Except as provided in 29 CFR 5.16, trainees will not be permitted to work at less than the predetermined rate for the work performed unless they are employed pursuant to and individually registered in a program which has received prior approval, evidenced by formal certification by the DOL, Employment and Training Administration.

(2) The ratio of trainees to journeyman-level employees on the job site shall not be greater than permitted under the plan approved by the Employment and Training Administration. Any employee listed on the payroll at a trainee rate who is not registered and participating in a training plan approved by the Employment and Training Administration shall be paid not less than the applicable wage rate on the wage determination for the classification of work actually performed. In addition, any trainee performing work on the job site in excess of the ratio permitted under the registered program shall be paid not less than the applicable wage rate on the wage determination for the work actually performed.

(3) Every trainee must be paid at not less than the rate specified in the approved program for his/her level of progress, expressed as a percentage of the journeyman-level hourly rate specified in the applicable wage determination. Trainees shall be paid fringe benefits in accordance with the provisions of the trainee program. If the trainee program does not mention fringe benefits, trainees shall be paid the full amount of fringe benefits listed on the wage determination unless the Administrator of the Wage and Hour Division determines that there is an apprenticeship program associated with the corresponding journeyman-level wage rate on the wage determination which provides for less than full fringe benefits for apprentices, in which case such trainees shall receive the same fringe benefits as apprentices.

(4) In the event the Employment and Training Administration withdraws approval of a training program, the contractor or subcontractor will no longer be permitted to utilize trainees at less than the applicable predetermined rate for the work performed until an acceptable program is approved.

c. Helpers**:**

Helpers will be permitted to work on a project if the helper classification is specified and defined on the applicable wage determination or is approved pursuant to the conformance procedure set forth in Section IV.2. Any worker listed on a payroll at a helper wage rate, who is not a helper under an approved definition, shall be paid not less than the applicable wage rate on the wage determination for the classification of work actually performed.

5. Apprentices and Trainees (Programs of the U.S. DOT):

Apprentices and trainees working under apprenticeship and skill training programs which have been certified by the Secretary of Transportation as promoting EEO in connection with Federal-aid highway construction programs are not subject to the requirements of paragraph 4 of this Section IV. The straight time hourly wage rates for apprentices and trainees under such programs will be established by the particular programs. The ratio of apprentices and trainees to journeymen shall not be greater than permitted by the terms of the particular program.

6. **Withholding:**
The SHA shall upon its own action or upon written request of an authorized representative of the DOL withhold, or cause to be withheld, from the contractor or subcontractor under this contract or any other Federal contract with the same prime contractor, or any other Federally-assisted contract subject to Davis-Bacon prevailing wage requirements which is held by the same prime contractor, as much of the accrued payments or advances as may be considered necessary to pay laborers and mechanics, including apprentices, trainees, and helpers, employed by the contractor or any subcontractor the full amount of wages required by the contract. In the event of failure to pay any laborer or mechanic, including any apprentice, trainee, or helper, employed or working on the site of the work, all or part of the wages required by the contract, the SHA contracting officer may, after written notice to the contractor, take such action as may be necessary to cause the suspension of any further payment, advance, or guarantee of funds until such violations have ceased.

7. **Overtime Requirements:**
No contractor or subcontractor contracting for any part of the contract work which may require or involve the employment of laborers, mechanics, watchmen, or guards (including apprentices, trainees, and helpers described in paragraphs 4 and 5 above) shall require or permit any laborer, mechanic, watchman, or guard in any workweek in which he/she is employed on such work, to work in excess of 40 hours in such workweek unless such laborer, mechanic, watchman, or guard receives compensation at a rate not less than one-and-one-half times his/her basic rate of pay for all hours worked in excess of 40 hours in such workweek.

8. **Violation:**
Liability for Unpaid Wages; Liquidated Damages: In the event of any violation of the clause set forth in paragraph 7 above, the contractor and any subcontractor responsible thereof shall be liable to the affected employee for his/her unpaid wages. In addition, such contractor and subcontractor shall be liable to the United States (in the case of work done under contract for the District of Columbia or a territory, to such District or to such territory) for liquidated damages. Such liquidated damages shall be computed with respect to each individual laborer, mechanic, watchman, or guard employed in violation of the clause set forth in paragraph 7, in the sum of $10 for each calendar day on which such employee was required or permitted to work in excess of the standard work week of 40 hours without payment of the overtime wages required by the clause set forth in paragraph 7.

9. **Withholding for Unpaid Wages and Liquidated Damages:**
The SHA shall upon its own action or upon written request of any authorized representative of the DOL withhold, or cause to be withheld, from any monies payable on account of work performed by the contractor or subcontractor under any such contract or any other Federal contract with the same prime contractor, or any other Federally-assisted contract subject to the Contract Work Hours and Safety Standards Act, which is held by the same prime contractor, such sums as may be determined to be necessary to satisfy any liabilities of such contractor or subcontractor for unpaid wages and liquidated damages as provided in the clause set forth in paragraph 8 above.

V. STATEMENTS AND PAYROLLS

(Applicable to all Federal-aid construction contracts exceeding $2,000 and to all related subcontracts, except for projects located on roadways classified as local roads or rural collectors, which are exempt.)

1. Compliance with Copeland Regulations (29 CFR 3):

   The contractor shall comply with the Copeland Regulations of the Secretary of Labor which are herein incorporated by reference.

2. Payrolls and Payroll Records:

a. Payrolls and basic records relating thereto shall be maintained by the contractor and each subcontractor during the course of the work and preserved for a period of 3 years from the date of completion of the contract for all laborers, mechanics, apprentices, trainees, watchmen, helpers, and guards working at the site of the work.

b. The payroll records shall contain the name, social security number, and address of each such employee; his or her correct classification; hourly rates of wages paid (including rates of contributions or costs anticipated for bona fide fringe benefits or cash equivalent thereof the types described in Section 1(b)(2)(B) of the Davis Bacon Act); daily and weekly number of hours worked; deductions made; and actual wages paid. In addition, for Appalachian contracts, the payroll records shall contain a notation indicating whether the employee does, or does not, normally reside in the labor area as defined in Attachment A, paragraph 1. Whenever the Secretary of Labor, pursuant to Section IV, paragraph 3b, has found that the wages of any laborer or mechanic include the amount of any costs reasonably anticipated in providing benefits under a plan or program described in Section 1(b)(2)(B) of the Davis Bacon Act, the contractor and each subcontractor shall maintain records which show that the commitment to provide such benefits is enforceable, that the plan or program is financially responsible, that the plan or program has been communicated in writing to the laborers or mechanics affected, and show the cost anticipated or the actual cost incurred in providing benefits. Contractors or subcontractors employing apprentices or trainees under approved programs shall maintain written evidence of the registration of apprentices and trainees, and ratios and wage rates prescribed in the applicable programs.

c. Each contractor and subcontractor shall furnish, each week in which any contract work is performed, to the SHA resident engineer a payroll of wages paid each of its employees (including apprentices, trainees, and helpers, described in Section IV, paragraphs 4 and 5, and watchmen and guards engaged on work during the preceding weekly payroll period). The payroll submitted shall set out accurately and completely all of the information required to be maintained under paragraph 2b of this Section V. This information may be submitted in any form desired. Optional Form WH-347 is available for this purpose and may be purchased from the Superintendent of Documents (Federal stock number 029-005-0014-1), U.S. Government Printing Office, Washington, D.C. 20402. The prime contractor is responsible for the submission of copies of payrolls by all subcontractors.

d. Each payroll submitted shall be accompanied by a "Statement of Compliance," signed by the contractor or subcontractor or his/her agent who pays or supervises the payment of the persons employed under the contract and shall certify the following:

(1) that the payroll for the payroll period contains the information required to be maintained under paragraph 2b of this Section V and that such information is correct and complete;

(2) that such laborer or mechanic (including each helper, apprentice, and trainee) employed on the contract during the payroll period has been paid the full weekly wages earned, without rebate, either directly or indirectly, and that no deductions have been made either directly or indirectly from the full wages earned, other than permissible deductions as set forth in the Regulations, 29 CFR 3;

(3) that each laborer or mechanic has been paid not less that the applicable wage rate and fringe benefits or cash equivalent for the classification of worked performed, as specified in the applicable wage determination incorporated into the contract.

e. The weekly submission of a properly executed certification set forth on the reverse side of Optional Form WH-347 shall satisfy the requirement for submission of the "Statement of Compliance" required by paragraph 2d of this Section V.

f. The falsification of any of the above certifications may subject the contractor to civil or criminal prosecution under 18 U.S.C. 1001 and 31 U.S.C. 231.

g. The contractor or subcontractor shall make the records required under paragraph 2b of this Section V available for inspection, copying, or transcription by authorized representatives of the SHA, the FHWA, or the DOL, and shall permit such representatives to interview employees during working hours on the job. If the contractor or subcontractor fails to submit the required records or to make them available, the SHA, the FHWA, the DOL, or all may, after written notice to the contractor, sponsor, applicant, or owner, take such actions as may be necessary to cause the suspension of any further payment, advance, or guarantee of funds. Furthermore, failure

to submit the required records upon request or to make such records available may be grounds for debarment action pursuant to 29 CFR 5.12.

VI. RECORD OF MATERIALS, SUPPLIES, AND LABOR

1. On all Federal-aid contracts on the National Highway System, except those which provide solely for the installation of protective devices at railroad grade crossings, those which are constructed on a force account or direct labor basis, highway beautification contracts, and contracts for which the total final construction cost for roadway and bridge is less than $1,000,000 (23 CFR 635) the contractor shall:

   a. Become familiar with the list of specific materials and supplies contained in Form FHWA-47, "Statement of Materials and Labor Used by Contractor of Highway Construction Involving Federal Funds," prior to the commencement of work under this contract.

   b. Maintain a record of the total cost of all materials and supplies purchased for and incorporated in the work, and also of the quantities of those specific materials and supplies listed on Form FHWA-47, and in the units shown on Form FHWA-47.

   c. Furnish, upon the completion of the contract, to the SHA resident engineer on Form FHWA-47 together with the data required in paragraph 1b relative to materials and supplies, a final labor summary of all contract work indicating the total hours worked and the total amount earned.

2. At the prime contractor's option, either a single report covering all contract work or separate reports for the contractor and for each subcontract shall be submitted.

VII. SUBLETTING OR ASSIGNING THE CONTRACT

1. The contractor shall perform with its own organization contract work amounting to not less than 30 percent (or a greater percentage if specified elsewhere in the contract) of the total original contract price, excluding any specialty items designated by the State. Specialty items may be performed by subcontract and the amount of any such specialty items performed may be deducted from the total original contract price before computing the amount of work required to be performed by the contractor's own organization (23 CFR 635).

   a. "Its own organization" shall be construed to include only workers employed and paid directly by the prime contractor and equipment owned or rented by the prime contractor, with or without operators. Such term does not include employees or equipment of a subcontractor, assignee, or agent of the prime contractor.

   b. "Specialty Items" shall be construed to be limited to work that requires highly specialized knowledge, abilities, or equipment not ordinarily available in the type of contracting organizations qualified and expected to bid on the contract as a whole and in general are to be limited to minor components of the overall contract.

2. The contract amount upon which the requirements set forth in paragraph 1 of Section VII is computed includes the cost of material and manufactured products which are to be purchased or produced by the contractor under the contract provisions.

3. The contractor shall furnish (a) a competent superintendent or supervisor who is employed by the firm, has full authority to direct performance of the work in accordance with the contract requirements, and is in charge of all construction operations (regardless of who performs the work) and (b) such other of its own organizational resources (supervision, management, and engineering services) as the SHA contracting officer determines is necessary to assure the performance of the contract.

4. No portion of the contract shall be sublet, assigned or otherwise disposed of except with the written consent of the SHA contracting officer, or authorized representative, and such consent when given shall not be construed to relieve the contractor of any responsibility for the fulfillment of the contract. Written consent will be given only after the SHA has assured that each subcontract is evidenced in writing and that it contains all pertinent provisions and requirements of the prime contract.

VIII. SAFETY: ACCIDENT PREVENTION

1. In the performance of this contract the contractor shall comply with all applicable Federal, State, and local laws governing safety, health, and sanitation (23 CFR 635). The contractor shall provide all safeguards, safety devices and protective equipment and take any other needed actions as it determines, or as the SHA contracting officer may determine, to be reasonably necessary to protect the life and health of employees on the job and the safety of the public and to protect property in connection with the performance of the work covered by the contract.

2. It is a condition of this contract, and shall be made a condition of each subcontract, which the contractor enters into pursuant to this contract, that the contractor and any subcontractor shall not permit any employee, in performance of the contract, to work in surroundings or under conditions which are unsanitary, hazardous or dangerous to his/her health or safety, as determined under construction safety and health standards (29 CFR 1926) promulgated by the Secretary of Labor, in accordance with Section 107 of the Contract Work Hours and Safety Standards Act (40 U.S.C. 333).

3. Pursuant to 29 CFR 1926.3, it is a condition of this contract that the Secretary of Labor or authorized representative thereof, shall have right of entry to any site of contract performance to inspect or investigate the matter of compliance with the construction safety and health standards and to carry out the duties of the Secretary under Section 107 of the Contract Work Hours and Safety Standards Act (40 U.S.C. 333).

IX. FALSE STATEMENTS CONCERNING HIGHWAY PROJECTS

In order to assure high quality and durable construction in conformity with approved plans and specifications and a high degree of reliability on statements and representations made by engineers, contractors, suppliers, and workers on Federal-aid highway projects, it is essential that all persons concerned with the project perform their functions as carefully, thoroughly, and honestly as possible. Willful falsification, distortion, or misrepresentation with respect to any facts related to the project is a violation of Federal law. To prevent any misunderstanding regarding the seriousness of these and similar acts, the following notice shall be posted on each Federal-aid highway project (23 CFR 635) in one or more places where it is readily available to all persons concerned with the project:

Notice To All Personnel Engaged On Federal-Aid Highway Projects

18 U.S.C. 1020 READS AS FOLLOWS:

"Whoever being an officer, agent, or employee of the United States, or any State or Territory, or whoever, whether a person, association, firm, or corporation, knowingly makes any false statement, false representation, or false report as to the character, quality, quantity, or cost of the material used or to be used, or the quantity or quality of the work performed or to be performed, or the cost thereof in connection with the submission of plans, maps, specifications, contracts, or costs of construction on any highway or related project submitted for approval to the Secretary of Transportation; or

Whoever knowingly makes any false statement, false representation, false report or false claim with respect to the character, quality, quantity, or cost of any work performed or to be performed, or materials furnished or to be furnished, in connection with the construction of any highway or related project approved by the Secretary of Transportation; or

Whoever knowingly makes any false statement or false representation as to material fact in any statement, certificate, or report submitted pursuant to provisions of the Federal-aid Roads Act approved July 1, 1916, (39 Stat. 355), as amended and supplemented;

Shall be fined not more that $10,000 or imprisoned not more than 5 years or both."

X. IMPLEMENTATION OF CLEAN AIR ACT AND FEDERAL WATER POLLUTION CONTROL ACT

(Applicable to all Federal-aid construction contracts and to all related subcontracts of $100,000 or more.)

By submission of this bid or the execution of this contract, or subcontract, as appropriate, the bidder, Federal-aid construction contractor, or subcontractor, as appropriate, will be deemed to have stipulated as follows:

1. That any facility that is or will be utilized in the performance of this contract, unless such contract is exempt under the Clean Air Act, as amended (42 U.S.C. 1857 et seq., as amended by Pub.L. 91-604), and under the Federal Water

Pollution Control Act, as amended (33 U.S.C. 1251 et seq., as amended by Pub.L. 92-500), Executive Order 11738, and regulations in implementation thereof (40 CFR 15) is not listed, on the date of contract award, on the U.S. Environmental Protection Agency (EPA) List of Violating Facilities pursuant to 40 CFR 15.20.

2. That the firm agrees to comply and remain in compliance with all the requirements of Section 114 of the Clean Air Act and Section 308 of the Federal Water Pollution Control Act and all regulations and guidelines listed thereunder.

3. That the firm shall promptly notify the SHA of the receipt of any communication from the Director, Office of Federal Activities, EPA, indicating that a facility that is or will be utilized for the contract is under consideration to be listed on the EPA List of Violating Facilities.

4. That the firm agrees to include or cause to be included the requirements of paragraph 1 through 4 of this Section X in every nonexempt subcontract, and further agrees to take such action as the government may direct as a means of enforcing such requirements.

XI. CERTIFICATION REGARDING DEBARMENT, SUSPENSION, INELIGIBILITY AND VOLUNTARY EXCLUSION

1. Instructions for Certification - Primary Covered Transactions:

(Applicable to all Federal-aid contracts - 49 CFR 29)

a. By signing and submitting this proposal, the prospective primary participant is providing the certification set out below.

b. The inability of a person to provide the certification set out below will not necessarily result in denial of participation in this covered transaction. The prospective participant shall submit an explanation of why it cannot provide the certification set out below. The certification or explanation will be considered in connection with the department or agency's determination whether to enter into this transaction. However, failure of the prospective primary participant to furnish a certification or an explanation shall disqualify such a person from participation in this transaction.

c. The certification in this clause is a material representation of fact upon which reliance was placed when the department or agency determined to enter into this transaction. If it is later determined that the prospective primary participant knowingly rendered an erroneous certification, in addition to other remedies available to the Federal Government, the department or agency may terminate this transaction for cause of default.

d. The prospective primary participant shall provide immediate written notice to the department or agency to whom this proposal is submitted if any time the prospective primary participant learns that its certification was erroneous when submitted or has become erroneous by reason of changed circumstances.

e. The terms "covered transaction," "debarred," "suspended," "ineligible," "lower tier covered transaction," "participant," "person," "primary covered transaction," "principal," "proposal," and "voluntarily excluded," as used in this clause, have the meanings set out in the Definitions and Coverage sections of rules implementing Executive Order 12549. You may contact the department or agency to which this proposal is submitted for assistance in obtaining a copy of those regulations.

f. The prospective primary participant agrees by submitting this proposal that, should the proposed covered transaction be entered into, it shall not knowingly enter into any lower tier covered transaction with a person who is debarred, suspended, declared ineligible, or voluntarily excluded from participation in this covered transaction, unless authorized by the department or agency entering into this transaction.

g. The prospective primary participant further agrees by submitting this proposal that it will include the clause titled "Certification Regarding Debarment, Suspension, Ineligibility and Voluntary Exclusion-Lower Tier Covered Transaction," provided by the department or agency entering into this covered transaction, without modification, in all lower tier covered transactions and in all solicitations for lower tier covered transactions.

h. A participant in a covered transaction may rely upon a certification of a prospective participant in a lower tier covered transaction that is not debarred, suspended, ineligible, or voluntarily excluded from the covered transaction, unless it knows that the certification is erroneous. A participant may decide the method and frequency by which it determines the eligibility of its principals. Each participant may, but is not required to, check the nonprocurement portion of the "Lists of Parties Excluded From Federal Procurement or Nonprocurement Programs" (Nonprocurement List) which is compiled by the General Services Administration.

i. Nothing contained in the foregoing shall be construed to require establishment of a system of records in order to render in good faith the certification required by this clause. The knowledge and information of participant is not required to exceed that which is normally possessed by a prudent person in the ordinary course of business dealings.

j. Except for transactions authorized under paragraph f of these instructions, if a participant in a covered transaction knowingly enters into a lower tier covered transaction with a person who is suspended, debarred, ineligible, or voluntarily excluded from participation in this transaction, in addition to other remedies available to the Federal Government, the department or agency may terminate this transaction for cause or default.

Certification Regarding Debarment, Suspension, Ineligibility and Voluntary Exclusion — Primary Covered Transactions

1. The prospective primary participant certifies to the best of its knowledge and belief, that it and its principals:

   a. Are not presently debarred, suspended, proposed for debarment, declared ineligible, or voluntarily excluded from covered transactions by any Federal department or agency;

   b. Have not within a 3-year period preceding this proposal been convicted of or had a civil judgement rendered against them for commission of fraud or a criminal offense in connection with obtaining, attempting to obtain, or performing a public (Federal, State or local) transaction or contract under a public transaction; violation of Federal or State antitrust statutes or commission of embezzlement, theft, forgery, bribery, falsification or destruction of records, making false statements, or receiving stolen property;

   c. Are not presently indicted for or otherwise criminally or civilly charged by a governmental entity (Federal, State or local) with commission of any of the offenses enumerated in paragraph 1b of this certification; and

   d. Have not within a 3-year period preceding this application/proposal had one or more public transactions (Federal, State or local) terminated for cause or default.

2. Where the prospective primary participant is unable to certify to any of the statements in this certification, such prospective participant shall attach an explanation to this proposal.

2. Instructions for Certification - Lower Tier Covered Transactions:

(Applicable to all subcontracts, purchase orders and other lower tier transactions of $25,000 or more - 49 CFR 29)

a. By signing and submitting this proposal, the prospective lower tier is providing the certification set out below.

b. The certification in this clause is a material representation of fact upon which reliance was placed when this transaction was entered into. If it is later determined that the prospective lower tier participant knowingly rendered an erroneous certification, in addition to other remedies available to the Federal Government, the department or agency with which this transaction originated may pursue available remedies, including suspension and/or debarment.

c. The prospective lower tier participant shall provide immediate written notice to the person to which this proposal is submitted if at any time the prospective lower tier participant learns that its certification was erroneous by reason of changed circumstances.

d. The terms "covered transaction," "debarred," "suspended," "ineligible," "primary covered transaction," "participant," "person," "principal," "proposal," and "voluntarily excluded," as used in this clause, have the

meanings set out in the Definitions and Coverage sections of rules implementing Executive Order 12549. You may contact the person to which this proposal is submitted for assistance in obtaining a copy of those regulations.

e. The prospective lower tier participant agrees by submitting this proposal that, should the proposed covered transaction be entered into, it shall not knowingly enter into any lower tier covered transaction with a person who is debarred, suspended, declared ineligible, or voluntarily excluded from participation in this covered transaction, unless authorized by the department or agency with which this transaction originated.

f. The prospective lower tier participant further agrees by submitting this proposal that it will include this clause titled "Certification Regarding Debarment, Suspension, Ineligibility and Voluntary Exclusion-Lower Tier Covered Transaction," without modification, in all lower tier covered transactions and in all solicitations for lower tier covered transactions.

g. A participant in a covered transaction may rely upon a certification of a prospective participant in a lower tier covered transaction that is not debarred, suspended, ineligible, or voluntarily excluded from the covered transaction, unless it knows that the certification is erroneous. A participant may decide the method and frequency by which it determines the eligibility of its principals. Each participant may, but is not required to, check the Nonprocurement List.

h. Nothing contained in the foregoing shall be construed to require establishment of a system of records in order to render in good faith the certification required by this clause. The knowledge and information of participant is not required to exceed that which is normally possessed by a prudent person in the ordinary course of business dealings.

i. Except for transactions authorized under paragraph e of these instructions, if a participant in a covered transaction knowingly enters into a lower tier covered transaction with a person who is suspended, debarred, ineligible, or voluntarily excluded from participation in this transaction, in addition to other remedies available to the Federal Government, the department or agency with which this transaction originated may pursue available remedies, including suspension and/or debarment.

Certification Regarding Debarment, Suspension, Ineligibility and Voluntary Exclusion — Lower Tier Covered Transactions

1. The prospective lower tier participant certifies, by submission of this proposal, that neither it nor its principals is presently debarred, suspended, proposed for debarment, declared ineligible, or voluntarily excluded from participation in this transaction by any Federal department or agency.

2. Where the prospective lower tier participant is unable to certify to any of the statements in this certification, such prospective participant shall attach an explanation to this proposal.

XII. CERTIFICATION REGARDING USE OF CONTRACT FUNDS FOR LOBBYING

(Applicable to all Federal-aid construction contracts and to all related subcontracts which exceed $100,000 - 49 CFR 20)

1. The prospective participant certifies, by signing and submitting this bid or proposal, to the best of his or her knowledge and belief, that:

   a. No Federal appropriated funds have been paid or will be paid, by or on behalf of the undersigned, to any person for influencing or attempting to influence an officer or employee of any Federal agency, a Member of Congress, an officer or employee of Congress, or an employee of a Member of Congress in connection with the awarding of any Federal contract, the making of any Federal grant, the making of any Federal loan, the entering into of any cooperative agreement, and the extension, continuation, renewal, amendment, or modification of any Federal contract, grant, loan, or cooperative agreement.

   b. If any funds other than Federal appropriated funds have been paid or will be paid to any person for influencing or attempting to influence an officer or employee of any Federal agency, a Member of Congress, an officer or employee of Congress, or an employee of a Member of Congress in connection with this Federal contract, grant, loan, or cooperative agreement, the undersigned shall complete and submit Standard Form-LLL, "Disclosure Form to Report Lobbying," in accordance with its instructions.

2. This certification is a material representation of fact upon which reliance was placed when this transaction was made or entered into. Submission of this certification is a prerequisite for making or entering into this transaction imposed by 31 U.S.C. 1352. Any person who fails to file the required certification shall be subject to a civil penalty of not less than $10,000 and not more than $100,000 for each such failure.

3. The prospective participant also agrees by submitting his or her bid or proposal that he or she shall require that the language of this certification be included in all lower tier subcontracts, which exceed $100,000 and that all such recipients shall certify and disclose accordingly.

FEDERAL-AID FEMALE AND MINORITY GOALS

In accordance with Section II, "Nondiscrimination," of "Required Contract Provisions Federal-aid Construction Contracts" the following are the goals for female utilization:

Goal for Women (applies nationwide).....(percent) 6.9

The following are goals for minority utilization:

CALIFORNIA ECONOMIC AREA

		Goal (Percent)
174	**Redding, CA:**	
	Non-SMSA Counties	6.8
	CA Lassen; CA Modoc;CA Plumas;CA Shasta; CA Siskiyou; CA Tehama.	
175	**Eureka, CA**	
	Non-SMSA Counties	6.6
	CA Del Norte; CA Humboldt; CA Trinity.	
176	**San Francisco-Oakland-San Jose, CA:**	
	SMSA Counties:	
	7120 Salinas-Seaside-Monterey, CA	28.9
	CA Monterey.	
	7360 San Francisco-Oakland	25.6
	CA Alameda; CA Contra Costa; CA Marin; CA San Francisco; CA San Mateo.	
	7400 San Jose, CA	19.6
	CA Santa Clara.	
	7485 Santa Cruz, CA.	14.9
	CA Santa Cruz.	
	7500 Santa Rosa, CA	9.1
	CA Sonoma.	
	8720 Vallejo-Fairfield- Napa, CA	17.1
	CA Napa; CA Solano	
	Non-SMSA Counties	23.2
	CA Lake; CA Mendocino; CA San Benito	
177	**Sacramento, CA**:	
	SMSA Counties:	
	6920 Sacramento, CA	16.1
	CA Placer; CA Sacramento; CA Yolo.	
	Non-SMSA Counties	14.3
	CA Butte; CA Colusa; CA El Dorado; CA Glenn; CA Nevada; CA Sierra; CA Sutter; CA Yuba.	
178	**Stockton-Modesto, CA:**	
	SMSA Counties:	
	5170 Modesto, CA	12.3
	CA Stanislaus.	
	8120 Stockton, CA	24.3
	CA San Joaquin.	
	Non-SMSA Counties	19.8
	CA Alpine; CA Amador; CA Calaveras; CA Mariposa;CA Merced; CA Tuolumne.	

		Goal (Percent)
179	**Fresno-Bakersfield, CA**	
	SMSA Counties:	
	0680 Bakersfield, CA	19.1
	CA Kern.	
	2840 Fresno, CA	26.1
	CA Fresno.	
	Non-SMSA Counties	23.6
	CA Kings; CA Madera; CA Tulare.	
180	**Los Angeles, CA:**	
	SMSA Counties:	
	0360 Anaheim-Santa Ana-Garden Grove, CA	11.9
	CA Orange.	
	4480 Los Angeles-Long Beach, CA	28.3
	CA Los Angeles.	
	6000 Oxnard-Simi Valley-Ventura, CA	21.5
	CA Ventura.	
	6780 Riverside-San Bernardino-Ontario, CA.	19.0
	CA Riverside; CA San Bernardino.	
	7480 Santa Barbara-Santa Maria-Lompoc, CA	19.7
	CA Santa Barbara.	
	Non-SMSA Counties	24.6
	CA Inyo; CA Mono; CA San Luis Obispo.	
181	**San Diego, CA:**	
	SMSA Counties	
	7320 San Diego, CA.	16.9
	CA San Diego.	
	Non-SMSA Counties	18.2
	CA Imperial.	

In addition to the reporting requirements set forth elsewhere in this contract the Contractor and subcontractors holding subcontracts, not including material suppliers, of $10,000 or more, shall submit for every month of July during which work is performed, employment data as contained under Form FHWA PR-1391 (Appendix C to 23 CFR, Part 230), and in accordance with the instructions included thereon.