

**DEPARTMENT OF TRANSPORTATION**  
**DIVISION OF ENGINEERING SERVICES**  
OFFICE ENGINEER, MS 43  
1727 30<sup>TH</sup> STREET  
P.O. BOX 168041  
SACRAMENTO, CA 95816-8041  
FAX (916) 227-6214  
TTY (916) 227-8454



*Flex your power!  
Be energy efficient!*

**\*\* WARNING \*\* WARNING \*\* WARNING \*\* WARNING \*\***  
**This document is intended for informational purposes only.**

Users are cautioned that California Department of Transportation (Department) does not assume any liability or responsibility based on these electronic files or for any defective or incomplete copying, excerpting, scanning, faxing or downloading of the contract documents. As always, for the official paper versions of the bidders packages and non-bidder packages, including addenda write to the California Department of Transportation, Plans and Bid Documents, Room 0200, P.O. Box 942874, Sacramento, CA 94272-0001, telephone (916) 654-4490 or fax (916) 654-7028. Office hours are 7:30 a.m. to 4:15 p.m. When ordering bidder or non-bidder packages it is important that you include a telephone number and fax number, P.O. Box and street address so that you can receive addenda.

August 28, 2006

08-SBd-40-R129.4/R157.2  
08-0J1014  
ACBRIM-040-2(052)E

Addendum No. 2

Dear Contractor:

This addendum is being issued to the contract for construction on State highway in SAN BERNARDINO COUNTY NEAR BARSTOW AND NEEDLES ON ROUTE 40 FROM MARBLE WASH BRIDGE TO MUSTANG WASH BRIDGE.

Submit bids for this work with the understanding and full consideration of this addendum. The revisions declared in this addendum are an essential part of the contract.

Bids for this work will be opened on August 31, 2006.

This addendum is being issued to revise the Notice to Contractors and Special Provisions and the Proposal and Contract.

In the Special Provisions, Section 10-1.10, "STRUCTURE DEMOLITION ASBESTOS-CONTAINING MATERIAL," the last paragraph is revised as follows:

"Full compensation for conforming to the requirements of this section shall be considered as included in the contract lump sum prices paid for bridge removal (Locations A, B, C, D, E, and F) and no additional compensation will be allowed therefor."

In the Special Provisions, Section 10-1.18, "EXISTING HIGHWAY FACILITIES," subsection "BRIDGE REMOVAL," the following paragraph is added after the third paragraph:

"The existing timber and steel girder temporary support shoring system including all cross bracing, timber columns, timber bent caps, timber support pads and concrete support pads shall be removed at all six existing bridge locations. Support pads consist of approximately 72 reinforced concrete pads 1.22 m by 1.83 m by 0.61 m in size. The temporary railing to be removed consists of approximately 70 pieces of railing 6.10 m in length. Full compensation for removing the temporary support shoring system and temporary railing shall be considered as included in the contract lump sum prices paid for bridge removal (Locations A, B, C, D, E, and F) and no additional compensation will be allowed therefor."

In the Proposal and Contract, the Engineer's Estimate Item 26 is deleted as attached.

Addendum No. 2  
Page 2  
August 28, 2006

08-SBd-40-R129.4/R157.2  
08-0J1014  
ACBRIM-040-2(052)E

To Proposal and Contract book holders:

Replace page 4 of the Engineer's Estimate in the Proposal with the attached revised page 4 of the Engineer's Estimate. The revised Engineer's Estimate is to be used in the bid.

Inquiries or questions in regard to this addendum must be communicated as a bidder inquiry and must be made as noted in the NOTICE TO CONTRACTORS section of the Notice to Contractors and Special Provisions.

Indicate receipt of this addendum by filling in the number of this addendum in the space provided on the signature page of the proposal.

Submit bids in the Proposal and Contract book you now possess. Holders who have already mailed their book will be contacted to arrange for the return of their book.

Inform subcontractors and suppliers as necessary.

This office is sending this addendum by confirmed facsimile to Proposal and Contract book holders to ensure that each receives it. A copy of this addendum is available for the contractor's use on the Internet Site:

**[http://www.dot.ca.gov/hq/esc/oe/weekly\\_ads/addendum\\_page.html](http://www.dot.ca.gov/hq/esc/oe/weekly_ads/addendum_page.html)**

If you are not a Proposal and Contract book holder, but request a book to bid on this project, you must comply with the requirements of this letter before submitting your bid.

Sincerely,

ORIGINAL SIGNED BY

REBECCA D. HARNAGEL, Chief  
Office of Plans, Specifications & Estimates  
Office Engineer

Attachment

**ENGINEER'S ESTIMATE****08-0J1014**

Item No.	Item Code	Item Description	Unit of Measure	Estimated Quantity	Unit Price	Item Total
21	170101	DEVELOP WATER SUPPLY	LS	LUMP SUM	LUMP SUM	
22	190185	SHOULDER BACKING	STA	23		
23 (F)	192003	STRUCTURE EXCAVATION (BRIDGE)	M3	1590		
24 (F)	193003	STRUCTURE BACKFILL (BRIDGE)	M3	820		
25 (S)	010086	EROSION CONTROL (TYPE PSFM)	M2	24 500		
26	BLANK					
27	010087	ASPHALT CONCRETE (TYPE C)	TONN	3200		
28	390106	ASPHALT CONCRETE (OPEN GRADED)	TONN	830		
29	394002	PLACE ASPHALT CONCRETE (MISCELLANEOUS AREA)	M2	5		
30	394048	PLACE ASPHALT CONCRETE DIKE (TYPE E)	M	120		
31	394049	PLACE ASPHALT CONCRETE DIKE (TYPE F)	M	150		
32 (F)	510051	STRUCTURAL CONCRETE, BRIDGE FOOTING	M3	295		
33 (F)	510053	STRUCTURAL CONCRETE, BRIDGE	M3	1420		
34 (F)	510086	STRUCTURAL CONCRETE, APPROACH SLAB (TYPE N)	M3	419		
35 (S)	512231	FURNISH PRECAST PRESTRESSED CONCRETE GIRDER (15 M - 20 M)	EA	53		
36 (S)	512233	FURNISH PRECAST PRESTRESSED CONCRETE GIRDER (25 M - 30 M)	EA	6		
37 (S)	512234	FURNISH PRECAST PRESTRESSED CONCRETE GIRDER (30 M - 35 M)	EA	12		
38 (S)	512500	ERECT PRECAST PRESTRESSED CONCRETE GIRDER	EA	71		
39 (S)	040440	JOINT SEAL (MR 30 MM) (TYPE A SILICONE ONLY)	M	27		
40 (S)	519117	JOINT SEAL (MR 30 MM)	M	31		