

DEPARTMENT OF TRANSPORTATION

DES-OE MS #43
1727 30TH Street, 2ND Floor
Sacramento, CA 95816



**** WARNING ** WARNING ** WARNING ** WARNING ****

This document is intended for informational purposes only.

Users are cautioned that California Department of Transportation (Department) does not assume any liability or responsibility based on these electronic files or for any defective or incomplete copying, excerpting, scanning, faxing or downloading of the contract documents. As always, for the official paper versions of the bidders packages and non-bidder packages, including addenda write to the California Department of Transportation, Plans and Bid Documents, Room 0200, P.O. Box 942874, Sacramento, CA 94272-0001, telephone (916) 654-4490 or fax (916) 654-7028. Office hours are 7:30 a.m. to 4:15 p.m. When ordering bidder or non-bidder packages it is important that you include a telephone number and fax number, P.O. Box and street address so that you can receive addenda.

May 19, 2004

08-Riv-60-24.3/24.7

08-486204

Addendum No. 2

Dear Contractor:

This addendum is being issued to the contract for construction on State highway in RIVERSIDE COUNTY IN MORENO VALLEY FROM 0.3 KM WEST TO 0.1 KM EAST OF HEACOCK STREET OVERCROSSING.

Submit bids for this work with the understanding and full consideration of this addendum. The revisions declared in this addendum are an essential part of the contract.

Bids for this work will be opened on June 3, 2004. The original bid opening date was previously postponed indefinitely under Addendum No. 1, dated March 24, 2004.

This addendum is being issued to set a new bid opening date as shown herein and revise the Project Plans, the Notice to Contractors and Special Provisions, and the Proposal and Contract.

Project Plan Sheets 1, 2, 3, 5, 6, 8, 9, 10, 11, 13 and 15 are revised. Half-sized copies of the revised sheets are attached for substitution for the like-numbered sheets.

In the Special Provisions, "STANDARD PLANS LIST," the following item is added:

"A77G Concrete Barrier – Type 60"

In the Special Provisions, Section 10-1.26, "TYPE 6 RETAINING WALL," is deleted.

In the Special Provisions, Section 10-1.39, "CONCRETE BARRIER," is added as attached.

In the Proposal and Contract, the Engineer's Estimate Items 41, 42, 43 and 44 are added and Items 22, 23, 24 and 40 are deleted.

To Proposal and Contract book holders:

Replace page 4 and add page 4A of the Engineer's Estimate in the Proposal with the attached revised page 4 and added page 4A of the Engineer's Estimate. The revised Engineer's Estimate is to be used in the bid.

Indicate receipt of this addendum by filling in the number of this addendum in the space provided on the signature page of the proposal.

Submit bids in the Proposal and Contract book you now possess. Holders who have already mailed their book will be contacted to arrange for the return of their book.

Inform subcontractors and suppliers as necessary.

Addendum No. 2
Page 2
May 19, 2004

08-Riv-60-24.3/24.7
08-486204

This office is sending this addendum by UPS overnight mail to Proposal and Contract book holders to ensure that each receives it. A copy of this addendum and the modified wage rates are available for the contractor's use on the Internet Site:

http://www.dot.ca.gov/hq/esc/oe/weekly_ads/addendum_page.html

If you are not a Proposal and Contract book holder, but request a book to bid on this project, you must comply with the requirements of this letter before submitting your bid.

Sincerely,

ORIGINAL SIGNED BY

REBECCA D. HARNAGEL, Chief
Office of Plans, Specifications & Estimates
Office Engineer

Attachments

10-1.39 CONCRETE BARRIER

Concrete barriers shall conform to the provisions in Section 83-2, "Barriers," of the Standard Specifications and these special provisions.

Concrete barriers shall be constructed on a layer of Class 2 Aggregate Base as shown on the plans. Aggregate base shall conform to the provisions in "Aggregate Base" of these special provisions. When concrete barriers are to be constructed on aggregate base, the height of the barriers shall be adjusted to compensate for irregularities in the surface of the finished aggregate base. The amount of adjustment will be determined by the Engineer and will be ordered before the concrete is placed.

The provisions of the third paragraph in Section 83-2.02D(4), "Finishing," of the Standard Specifications shall not apply.

Concrete barrier markers shall conform to the provisions in "Prequalified and Tested Signing and Delineation Materials" of these special provisions. At those locations shown on the plans, concrete barrier markers shall be cemented to the barrier in conformance with the manufacturer's recommendations.

ENGINEER'S ESTIMATE
08-486204

Item	Item Code	Item	Unit of Measure	Estimated Quantity	Unit Price	Item Total
21 (F)	510502	MINOR CONCRETE (MINOR STRUCTURE)	M3	3		
22	BLANK					
23	BLANK					
24	BLANK					
25	566011	ROADSIDE SIGN - ONE POST	EA	4		
26	566012	ROADSIDE SIGN - TWO POST	EA	8		
27	650069	450 MM REINFORCED CONCRETE PIPE	M	16		
28	705222	450 MM CONCRETE FLARED END SECTION	EA	1		
29	727901	MINOR CONCRETE (DITCH LINING)	M3	4		
30	731627	MINOR CONCRETE (CURB, SIDEWALK AND CURB RAMP)	M3	21		
31	032387	FRAME AND GRATE (TYPE G-1)	EA	1		
32	820107	DELINEATOR (CLASS 1)	EA	12		
33 (S)	832003	METAL BEAM GUARD RAILING (WOOD POST)	M	23		
34 (S)	839565	TERMINAL SYSTEM (TYPE SRT)	EA	1		
35	839568	TERMINAL ANCHOR ASSEMBLY (TYPE SFT)	EA	1		
36 (S)	840515	THERMOPLASTIC PAVEMENT MARKING	M2	87		
37	840560	THERMOPLASTIC TRAFFIC STRIPE (SPRAYABLE)	M	840		
38	850111	PAVEMENT MARKER (RETROREFLECTIVE)	EA	46		
39 (S)	861501	MODIFY SIGNAL AND LIGHTING	LS	LUMP SUM	LUMP SUM	
40	BLANK					

ENGINEER'S ESTIMATE
08-486204

Item	Item Code	Item	Unit of Measure	Estimated Quantity	Unit Price	Item Total
41	839712	CONCRETE BARRIER (TYPE 60 SC)	M	100		
42	120143	TEMPORARY PAVEMENT DELINEATION	M	800		
43	120154	TEMPORARY MARKER	EA	35		
44	999990	MOBILIZATION	LS	LUMP SUM	LUMP SUM	

TOTAL BID: _____