

DEPARTMENT OF TRANSPORTATION
DIVISION OF ENGINEERING SERVICES
OFFICE ENGINEER, MS 43
1727 30TH STREET
P.O. BOX 168041
SACRAMENTO, CA 95816-8041
FAX (916) 227-6214
TTY (916) 227-8454



*Flex your power!
Be energy efficient!*

**** WARNING ** WARNING ** WARNING ** WARNING ****
This document is intended for informational purposes only.

Users are cautioned that California Department of Transportation (Department) does not assume any liability or responsibility based on these electronic files or for any defective or incomplete copying, excerpting, scanning, faxing or downloading of the contract documents. As always, for the official paper versions of the bidders packages and non-bidder packages, including addenda write to the California Department of Transportation, Plans and Bid Documents, Room 0200, P.O. Box 942874, Sacramento, CA 94272-0001, telephone (916) 654-4490 or fax (916) 654-7028. Office hours are 7:30 a.m. to 4:15 p.m. When ordering bidder or non-bidder packages it is important that you include a telephone number and fax number, P.O. Box and street address so that you can receive addenda.

September 9, 2005

08-SBd-10-14.5/32.2
08-493704
ACIM-010-2(253)56E

Addendum No. 1

Dear Contractor:

This addendum is being issued to the contract for construction on State highway in SAN BERNARDINO COUNTY IN ONTARIO, FONTANA AND RIALTO FROM 0.3 KM WEST OF MILLIKEN AVENUE OVERCROSSING TO RIVERSIDE AVENUE OVERCROSSING.

Submit bids for this work with the understanding and full consideration of this addendum. The revisions declared in this addendum are an essential part of the contract.

Bids for this work will be opened on September 22, 2005, instead of the original date of September 15, 2005.

This addendum is being issued to revise the Notice to Contractors and Special Provisions.

In the Special Provisions, Section 10-1.23, "REPLACE CONCRETE PAVEMENT (RAPID STRENGTH CONCRETE)," the subsection "REPLACEMENT TIE BARS," the title is revised to read "TIE BARS."

In the Special Provisions, Section 10-1.23, "REPLACE CONCRETE PAVEMENT (RAPID STRENGTH CONCRETE)," the subsection "TIE BARS," the first paragraph is revised as follows:

"Tie bars shall be installed at longitudinal contact joints and longitudinal weakened plane joints as shown on the plans. Tie bars at transverse contact joints shall not be required."

In the Special Provisions, Section 10-1.23, "REPLACE CONCRETE PAVEMENT (RAPID STRENGTH CONCRETE)," the subsection "MEASUREMENT AND PAYMENT," the sixth paragraph is revised as follows:

"Full compensation for removing and disposing of existing concrete pavement, constructing trial slabs, furnishing and placing bond breaker, furnishing and disposing of standby materials for temporary roadway structural section, and constructing, maintaining, removing and disposing of temporary roadway structural section, and quality control program shall be considered as included in the contract price paid per cubic meter for replace concrete pavement (Rapid Strength Concrete), and no additional compensation will be allowed therefor."

In the Proposal and Contract, the Engineer's Estimate Item 16 is revised as attached.

Addendum No. 1
Page 2
September 9, 2005

08-SBd-10-14.5/32.2
08-493704
ACIM-010-2(253)56E

To Proposal and Contract book holders:

Replace page 3 of the Engineer's Estimate in the Proposal with the attached revised page 3 of the Engineer's Estimate. The revised Engineer's Estimate is to be used in the bid.

Inquiries or questions in regard to this addendum must be communicated as a bidder inquiry and must be made as noted in the NOTICE TO CONTRACTORS section of the Notice to Contractors and Special Provisions.

Indicate receipt of this addendum by filling in the number of this addendum in the space provided on the signature page of the proposal.

Submit bids in the Proposal and Contract book you now possess. Holders who have already mailed their book will be contacted to arrange for the return of their book.

Inform subcontractors and suppliers as necessary.

This office is sending this addendum by confirmed facsimile to all book holders to ensure that each receives it. A copy of this addendum and the modified wage rates are available for the contractor's use on the Internet Site:

http://www.dot.ca.gov/hq/esc/oe/weekly_ads/addendum_page.html

If you are not a Proposal and Contract book holder, but request a book to bid on this project, you must comply with the requirements of this letter before submitting your bid.

Sincerely,

ORIGINAL SIGNED BY

REBECCA D. HARNAGEL, Chief
Office of Plans, Specifications & Estimates
Office Engineer

Attachments

ENGINEER'S ESTIMATE**04-162514**

Item No.	Item Code	Item Description	Unit of Measure	Estimated Quantity	Unit Price	Item Total
1	070012	PROGRESS SCHEDULE (CRITICAL PATH METHOD)	LS	LUMP SUM	LUMP SUM	
2	070018	TIME-RELATED OVERHEAD	LS	LUMP SUM	LUMP SUM	
3	074017	PREPARE WATER POLLUTION CONTROL PROGRAM	LS	LUMP SUM	LUMP SUM	
4	074020	WATER POLLUTION CONTROL	LS	LUMP SUM	LUMP SUM	
5	074042	TEMPORARY CONCRETE WASHOUT (PORTABLE)	LS	LUMP SUM	LUMP SUM	
6 (S)	120090	CONSTRUCTION AREA SIGNS	LS	LUMP SUM	LUMP SUM	
7 (S)	120100	TRAFFIC CONTROL SYSTEM	LS	LUMP SUM	LUMP SUM	
8 (S)	128650	PORTABLE CHANGEABLE MESSAGE SIGN	EA	1		
9	150662	REMOVE METAL BEAM GUARD RAILING	M	130		
10	150722	REMOVE PAVEMENT MARKER	EA	40 500		
11	260210	AGGREGATE BASE (APPROACH SLAB)	M3	77		
12	034832	REPLACE ASPHALT CONCRETE SURFACING (TYPE A)	M3	15 200		
13	397001	ASPHALTIC EMULSION (PAINT BINDER)	TONN	61		
14	401108	REPLACE CONCRETE PAVEMENT (RAPID STRENGTH CONCRETE)	M3	1690		
15	404092	SEAL PAVEMENT JOINT	M	3100		
16	406003	TIE BAR (DRILL AND BOND)	EA	72		
17	420201	GRIND EXISTING CONCRETE PAVEMENT	M2	523 000		
18	510087	STRUCTURAL CONCRETE, APPROACH SLAB (TYPE R)	M3	760		
19	510800	PAVING NOTCH EXTENSION	M3	9		
20 (S)	519117	JOINT SEAL (MR 30 MM)	M	42		