


4" x 6 1/2" ROUNDED RECTANGLE HANDHOLE REINFORCED WITH RING WELDED TO OUTSIDE OF POLE. SEE NOTE 4, 1/8" COVER PLATE

AFTER PLUMBING STANDARD, PLACE MORTAR ALL AROUND BOLTS. FINISH WITH SLOPE RANGING FROM 45° TO 90° INCLUDES DRAIN HOLES

4 SIDES ES-6B Det N




**HANDHOLE AND ANCHORAGE**  
DETAIL A

**IDENTIFICATION NUMBER**

1. Attach a stamped metal tag with pole's identification number above the handhole. 1/4" high number, minimum.
2. Attach a stamped metal tag with mast arm's identification number to the bottom of the signal mast arm near the pole plate. 1/4" high number, minimum.

Type  
Load case (Use SL for special load case)  
Design wind velocity (mph)  
Signal mast arm length (ft)  
Standard plan year  
Only for poles or mast arms using Detail F  
Only for poles or mast arms using ES-70


**SAMPLE IDENTIFICATION NUMBER**




**SECTION A-A**

**NOTES:**


1. Provide a Hex nut, leveling nut and 2 washers for each bolt.
2. Luminaire mast arms shall be round, tapered steel tubes, taper of 0.1375" to 0.143-inch per foot with an end section 2 3/8" OD for mounting hardware. Extensions of 2 NPS Standard pipe and 7" long may be used at the option of the manufacturer. When low pressure sodium luminaires are required, the extension shall be 1'-3".
3. Signal mast arms shall be round, tapered steel tubes, maximum taper 0.143-inch per foot.
4. Handhole reinforcement ring shall be 1/4" x 2" for 0.1196" to 0.2391" thick poles, 3/8" x 2" for 0.3125" thick poles.
5. Handholes shall be located on the downstream side of traffic.
6. Detail F, fatigue resistant weld, is required at socket welded signal mast arm plate and pole base plate.
7. Cap screws shall be tightened by the turn-of-nut method 1/3 turn from a snug tight condition. No washer will be required.
8. Outside diameter, wall thickness, and corresponding section properties of poles and mast arms as shown in the Standard Plans are minimums. Unless otherwise specified, alternative sections shall require approval by the Engineer.
9. Wind Loading (3 seconds gust): 100 mph
10. Unit Stresses (Structural steel):  
fy = 55,000 psi (tapered steel tube and anchor bolts)  
fy = 50,000 psi (unless otherwise noted)
11. Unit Stresses (Reinforced concrete):  
f'c = 3,625 psi  
fy = 60,000 psi



**TYPICAL DETAIL**  
DETAIL B-1



**ALTERNATIVE DETAIL**  
DETAIL B-2




**SIDE TENON**  
DETAIL S-1

**PIPE TENONS**  
DETAIL S


WELD SIZE	WALL THICKNESS
1/8"	0.1196"
3/16"	0.1793"
1/4"	0.2391"

2 NPS PIPE, CHASED FOR WIRE PROTECTION SEE NOTE 2




**TIP TENON**  
DETAIL TS


WELD SIZE	WALL THICKNESS
3/16"	0.1196"
1/4"	0.1793"
5/16"	0.2391"
3/8"	0.3125"




**TAMPER RESISTANT HANDHOLE COVER**  
DETAIL B



**TIP TENON**  
DETAIL TL  
This detail supersedes Detail S when so designated



**DETAIL F**  
Fatigue resistant weld at socket type connection see Elevation A for inner weld



**ELEVATION A**

STATE OF CALIFORNIA  
DEPARTMENT OF TRANSPORTATION

**ELECTRICAL SYSTEMS**  
**(SIGNAL AND LIGHTING STANDARD,**  
**DETAIL No. 1)**

NO SCALE

RSP ES-7M DATED OCTOBER 30, 2015 SUPERSEDES STANDARD PLAN ES-7M DATED MAY 20, 2011 - PAGE 474 OF THE STANDARD PLANS BOOK DATED 2010.

**REVISED STANDARD PLAN RSP ES-7M**

TO ACCOMPANY PLANS DATED **06-27-16**

Dist	COUNTY	ROUTE	POST MILES TOTAL PROJECT	SHEET No.	TOTAL SHEETS
12	Ora	405	2.6/6.5	401	431


October 30, 2015  
PLANS APPROVAL DATE

Stanley P. Johnson  
REGISTERED CIVIL ENGINEER  
No. C57793  
Exp. 3-31-16  
CIVIL  
STATE OF CALIFORNIA

THE STATE OF CALIFORNIA OR ITS OFFICERS OR AGENTS SHALL NOT BE RESPONSIBLE FOR THE ACCURACY OR COMPLETENESS OF SCANNED COPIES OF THIS PLAN SHEET.

2010 REVISED STANDARD PLAN RSP ES-7M


2010 REVISED STANDARD PLAN RSP ES-7N




REAR VIEW

SIDE VIEW


SIGN MOUNTING DETAILS  
DETAIL U



STANDARD TOP  
DETAIL B-1




MOUNTING ADAPTER FOR  
PHOTOELECTRIC UNIT  
DETAIL B-2



ALTERNATIVE  
MOUNTING ADAPTER  
DETAIL B-3


POLE TOP DETAILS  
DETAIL B

TO ACCOMPANY PLANS DATED 06-27-16



SECTION A-A


SECTION B-B




INSPECTION TUBE PLACEMENT  
DETAIL I

CIDH DIAMETER	VERTICAL BARS	HOOPS (WELDED)	INSPECTION TUBE
2 ft	8-#5	#4 AT 6	2
2.5 ft	10-#6		4*
3 ft	12-#7	#5 AT 6	4
3.5 ft	14-#8		5
4 ft	18-#9	2-#4 AT 7	6
5 ft	22-#10	2-#5 AT 7	7
6 ft	26-#11	2-#6 AT 7	

\* FOR SLIP BASE VERSIONS WITH 3 ANCHOR BOLTS USE 3 INSPECTION TUBES.



DETAIL C-1



DUAL PHOTOELECTRIC UNIT MOUNTING DETAIL  
DETAIL C


STATE OF CALIFORNIA  
DEPARTMENT OF TRANSPORTATION

**ELECTRICAL SYSTEMS  
(SIGNAL AND LIGHTING STANDARD,  
DETAIL No. 2)**

NO SCALE

RSP ES-7N DATED OCTOBER 30, 2015 SUPERSEDES STANDARD PLAN ES-7N DATED MAY 20, 2011 - PAGE 475 OF THE STANDARD PLANS BOOK DATED 2010.


**REVISED STANDARD PLAN RSP ES-7N**




ELEVATION

CAST-IN-DRILLED-HOLE PILE FOUNDATION,  
REINFORCED PILE  
DETAIL A

FOR POLES TO BE INSTALLED ON EXISTING FOUNDATION:  
Verify bolt circles, anchor bolt sizes and dependent dimensions for poles to be installed on existing foundations before fabricating the poles.




FOR UNIFORM TUBE THICKNESS  
DETAIL T-1



AT TUBE THICKNESS CHANGE  
DETAIL T-2

POLE SPLICES  
DETAIL T


TO ACCOMPANY PLANS DATED 06-27-16




**INSTALLATION DETAILS**  
**DETAIL A**

**NOTES:**


1. The nominal dimensions of the opening in which the cover sets shall be the same as the cover dimensions except the length and width dimensions shall be 1/8" greater.
2. Covers and boxes shall be interchangeable with California standard male and female gages. When interchanged with a standard male or female gage, the top surfaces shall be flush within 1/8". Top outside radius of covers and pull boxes shall have a 1/8" radius.
3. Dimensions for the cover for non-traffic pull box are nominal values.



**COVER TOP VIEW**



**TYPICAL COVER CAPTIVE BOLT**  
**OR SIMILAR**



**TYPICAL THREADED INSERT**  
**OR SIMILAR**

DIMENSION TABLE										
PULL BOX	PULL BOX			COVER						
	MINIMUM DEPTH BOX	MINIMUM DEPTH EXTENSION	MINIMUM WEIGHT	LI Min	WI Min	TE	D	L	W	MINIMUM WEIGHT
No. 3 1/2	12"	N/A	40 lb	1' - 3"	9"	1 3/4"	1 3/4"	1'-3 1/4" - 1'-3 3/8"	10" - 10 1/8"	30 lb
No. 5	12"	10"	55 lb	1' - 8"	11"	2"	1 3/4"	1'-11 1/4"	1'-1 3/4"	60 lb
No. 6	12"	10"	70 lb	2' - 4 1/4"	1' - 3 1/4"	2"	2"	2'-6 1/2"	1'-5 1/2"	85 lb

STATE OF CALIFORNIA  
DEPARTMENT OF TRANSPORTATION  
**ELECTRICAL SYSTEMS**  
**(NON-TRAFFIC PULL BOX)**  
NO SCALE

RSP ES-8A DATED APRIL 15, 2016 SUPERSEDES RSP ES-8A DATED OCTOBER 30, 2015 AND RSP ES-8A DATED JULY 19, 2013 AND RSP ES-8A DATED JANUARY 20, 2012 THAT SUPPLEMENTS THE STANDARD PLANS BOOK DATED 2010.


2010 REVISED STANDARD PLAN RSP ES-8A

DIST	COUNTY	ROUTE	POST MILES TOTAL PROJECT	SHEET NO.	TOTAL SHEETS
12	Ora	405	2.6/6.5	404	431

*Theresa Gabriel*  
 REGISTERED ELECTRICAL ENGINEER  
 April 15, 2016  
 PLANS APPROVAL DATE

THE STATE OF CALIFORNIA OR ITS OFFICERS OR AGENTS SHALL NOT BE RESPONSIBLE FOR THE ACCURACY OR COMPLETENESS OF SCANNED COPIES OF THIS PLAN SHEET.

TO ACCOMPANY PLANS DATED 06-27-16



SECTION A-A  
**No. 3 1/2(T), No. 5(T) AND  
 No. 6(T) TRAFFIC PULL BOX**

**NOTES:**

- Traffic pull box shall be provided with steel cover and special concrete footing. Steel cover shall have embossed non-skid pattern.
- Steel reinforcing shall be as regularly used in the standard products of the respective manufacturer.
- Bonding jumper for metal covers shall be 3' long, minimum.
- The nominal dimensions of the opening in which the cover sets shall be the same as the cover dimensions except the length and width dimensions shall be 1/8" greater.
- Covers and boxes shall be interchangeable with California standard male and female gages. When interchanged with a standard male or female gage, the top surfaces shall be flush within 1/8".

DIMENSION TABLE								
PULL BOX	PULL BOX				COVER			
	MINIMUM * THICKNESS	MINIMUM DEPTH BOX AND EXTENSION	LO	LI	WO	WI	L **	W **
No. 3 1/2(T)	1 1/2"	1'-0"	1'-10" - 1'-11"	1'-5" - 1'-6 1/2"	1'-3" - 1'-4"	10" - 1'-0"	1'-8" - 1'-8 1/2"	1'-1" - 1'-2"
No. 5(T)	1 3/4"	1'-0"	2'-5" - 2'-6"	2'-0" - 2'-1"	1'-6" - 1'-7"	1'-1" - 1'-2"	2'-3" - 2'-3 1/2"	1'-4" - 1'-4 1/2"
No. 6(T)	2"	1'-0"	2'-11" - 3'-1"	2'-6" - 2'-7"	1'-10" - 2'-0"	1'-5" - 1'-6"	2'-9" - 2'-9 1/2"	1'-8" - 1'-8 1/2"

\* EXCLUDING CONDUIT WEB      \*\* TOP DIMENSION

STATE OF CALIFORNIA  
 DEPARTMENT OF TRANSPORTATION  
**ELECTRICAL SYSTEMS  
 (TRAFFIC PULL BOX)**  
 NO SCALE

RSP ES-8B DATED APRIL 15, 2016 SUPERSEDES RSP ES-8B  
 DATED OCTOBER 30, 2015 AND RSP ES-8B DATED JULY 19, 2013 AND RSP ES-8B  
 DATED JANUARY 20, 2012 THAT SUPPLEMENTS THE STANDARD PLANS BOOK DATED 2010.

2010 REVISED STANDARD PLAN RSP ES-8B

DIST	COUNTY	ROUTE	POST MILES TOTAL PROJECT	SHEET No.	TOTAL SHEETS
12	Ora	405	2.6/6.5	405	431


*Theresa Gabriel*  
 REGISTERED ELECTRICAL ENGINEER  
 Theresa Aziz Gabriel  
 No. E15129  
 Exp. 6-30-16  
 ELECTRICAL  
 STATE OF CALIFORNIA

October 30, 2015  
 PLANS APPROVAL DATE


THE STATE OF CALIFORNIA OR ITS OFFICERS OR AGENTS SHALL NOT BE RESPONSIBLE FOR THE ACCURACY OR COMPLETENESS OF SCANNED COPIES OF THIS PLAN SHEET.

TO ACCOMPANY PLANS DATED 06-27-16


**NOTE:**  
Curves represent the minimum footcandle (FC).




**LED LUMINAIRE 165 W**  
34' Mounting Height




**LED LUMINAIRE 235 W**  
40' Mounting Height



**LED LUMINAIRE 235 W**  
40' Mounting Height  
with back side control



**LED LUMINAIRE 300 W**  
40' Mounting Height



**LOW-PRESSURE SODIUM LUMINAIRE 180 W**  
40' Mounting Height  
Lamp operated at 33,000 lm

STATE OF CALIFORNIA  
DEPARTMENT OF TRANSPORTATION

**ELECTRICAL SYSTEMS  
(ISOFOOTCANDLE CURVES)**

NO SCALE

RSP ES-10A DATED OCTOBER 30, 2015 SUPERSEDES RSP ES-10A DATED JULY 19, 2013 THAT SUPPLEMENTS THE STANDARD PLANS BOOK DATED 2010.

**REVISED STANDARD PLAN RSP ES-10A**


2010 REVISED STANDARD PLAN RSP ES-10A

DIST	COUNTY	ROUTE	POST MILES TOTAL PROJECT	SHEET No.	TOTAL SHEETS
12	Ora	405	2.6/6.5	406	431


*Theresa Gabriel*  
 REGISTERED ELECTRICAL ENGINEER  
 October 30, 2015  
 PLANS APPROVAL DATE  
THE STATE OF CALIFORNIA OR ITS OFFICERS OR AGENTS SHALL NOT BE RESPONSIBLE FOR THE ACCURACY OR COMPLETENESS OF SCANNED COPIES OF THIS PLAN SHEET.

TO ACCOMPANY PLANS DATED 06-27-16


**NOTE:**  
Curves represent the minimum footcandle (FC).




**HIGH-PRESSURE SODIUM  
WALL-MOUNTED LUMINAIRE 70 W**  
 15' Mounting Height  
 ANSI Designation S62  
 Lamp operated at 5,800 lm




**HIGH-PRESSURE SODIUM  
WALL-MOUNTED LUMINAIRE 100 W**  
 15' Mounting Height  
 ANSI Designation S54  
 Lamp operated at 9,500 lm




**HIGH-PRESSURE SODIUM  
PENDANT SOFFIT LUMINAIRE 70 W  
TYPE III SHORT**  
 17' Mounting Height  
 ANSI Designation S62  
 Lamp operated at 5,800 lm



**HIGH-PRESSURE SODIUM  
PENDANT SOFFIT LUMINAIRE 70 W**  
 17' Mounting Height  
 ANSI Designation S62  
 Lamp operated at 5,800 lm



**HIGH-PRESSURE SODIUM  
FLUSH-MOUNTED SOFFIT LUMINAIRE 70 W**  
 17' Mounting Height  
 ANSI Designation S62  
 Lamp operated at 5,800 lm



**INDUCTION SIGN  
LIGHTING FIXTURE 85 W**

STATE OF CALIFORNIA  
DEPARTMENT OF TRANSPORTATION


**ELECTRICAL SYSTEMS  
(ISOFOOTCANDLE CURVES)**

NO SCALE

RSP ES-10B DATED OCTOBER 30, 2015 SUPERSEDES RSP ES-10B DATED JULY 20, 2012 THAT SUPPLEMENTS THE STANDARD PLANS BOOK DATED 2010.


**REVISED STANDARD PLAN RSP ES-10B**

2010 REVISED STANDARD PLAN RSP ES-10B




TO ACCOMPANY PLANS DATED 06-27-16


STANDARD TYPE	SETBACK (DIMENSION A)
32	30'-0" (Min)
31	20'-0" (Min)
15, 15D, 15-SB, 21, 21D, 30	ARM LENGTH (Min)



**CUT SLOPES  
STEEPER THAN 4:1,  
LESS THAN 2:1  
DETAIL A-1**  
See Note 2 and 3



**FILL SLOPES  
STEEPER THAN 4:1,  
LESS THAN 2:1  
DETAIL A-2**  
See Note 2 and 3




**FLAT SECTIONS, CUT OR FILL SLOPES  
4:1 OR FLATTER  
DETAIL A-3**  
See Note 2


**FOUNDATIONS ADJACENT TO ALL ROADWAYS EXCEPT  
IN SIDEWALK, MEDIAN AND ISLAND AREAS  
DETAIL A**

**NOTES:**

1. Where a portion of the foundation is above grade, the top edges shall have a 1" chamfer.
2. Slopes shall be horizontal to vertical ratio (Horizontal : Vertical).
3. Horizontal setbacks on cut and fill slopes steeper than 4:1 shall not exceed the distance shown for flat sections.
4. CIDH embedment depth shall be increased beyond standard depths by the diameter of the CIDH.



**MEDIAN, ISLAND  
OR WIDE SIDEWALK  
DETAIL B-1**  
7' Wide and wider



**NARROW SIDEWALK  
DETAIL B-2**  
Less than 7' wide

**FOUNDATIONS IN SIDEWALK, MEDIAN AND ISLAND AREAS  
DETAIL B**

STATE OF CALIFORNIA  
DEPARTMENT OF TRANSPORTATION  
**ELECTRICAL SYSTEMS  
(FOUNDATION INSTALLATIONS)**  
NO SCALE





RSP ES-11 DATED JULY 19, 2013 SUPERSEDES STANDARD PLAN ES-11 DATED MAY 20, 2011 - PAGE 488 OF THE STANDARD PLANS BOOK DATED 2010.

Dist	COUNTY	ROUTE	POST MILES TOTAL PROJECT	SHEET No.	TOTAL SHEETS
12	Ora	405	2.6/6.5	408	431

Theresa Gabriel  
 REGISTERED ELECTRICAL ENGINEER  
 April 15, 2016  
 PLANS APPROVAL DATE  
THE STATE OF CALIFORNIA OR ITS OFFICERS OR AGENTS SHALL NOT BE RESPONSIBLE FOR THE ACCURACY OR COMPLETENESS OF SCANNED COPIES OF THIS PLAN SHEET.






TO ACCOMPANY PLANS DATED 06-27-16



**NOTES:**

1. Dimensions are minimum.
2. Rubber tapes shall be rolled after application.
3. Between 1 free-end and 1 through conductor.
4. Between 2 free-end conductors.
5. Between 3 free-end conductors.

**TYPICAL SPLICE INSULATION METHOD B**



**TYPICAL SPLICE INSULATION HEAT-SHRINK TUBING**

STATE OF CALIFORNIA  
 DEPARTMENT OF TRANSPORTATION  
**ELECTRICAL SYSTEMS**  
**(SPLICE INSULATION METHODS DETAILS)**

NO SCALE

RSP ES-13A DATED APRIL 15, 2016 SUPERSEDES RSP ES-13A DATED OCTOBER 30, 2015 AND STANDARD PLAN ES-13A DATED MAY 20, 2011 - PAGE 491 OF THE STANDARD PLANS BOOK DATED 2010.

**REVISED STANDARD PLAN RSP ES-13A**



2010 REVISED STANDARD PLAN RSP ES-13A

TO ACCOMPANY PLANS DATED 06-27-16

CIRCUIT VOLTAGE	FUSE VOLTAGE RATING	FUSE CURRENT RATING						
		HPS LAMP BALLAST		LOW PRESSURE SODIUM BALLAST	INDUCTION SIGN LIGHTING	SINGLE PHASE (TWO WIRE) TRANSFORMERS (PRIMARY SIDE)		
		70 W	100 W	180 W	85 W	1 KVA	2 KVA	3 KVA
120 V	250 V	5 A	5 A	5 A	5 A	10 A	20 A	30 A
240 V	250 V	5 A	5 A	5 A	5 A	6 A	10 A	20 A
480 V	500-600 V	5 A	5 A	3 A	1 A (SEE NOTE 2)	3 A	6 A	10 A

- NOTES:**
1. Primary lines of multiple ballasts shall be provided with fused connectors. Fuse ratings shall be as noted above.
  2. See Revised Standard Plan RSP ES-15D, Type SC3 control.

**FUSE RATINGS FOR FUSED CONNECTORS**



STATE OF CALIFORNIA  
 DEPARTMENT OF TRANSPORTATION  
**ELECTRICAL SYSTEMS  
 (FUSE RATING, KINKING AND  
 BANDING DETAIL)**  
 NO SCALE

RSP ES-13B DATED APRIL 15, 2016 SUPERSEDES STANDARD PLAN ES-13B DATED MAY 20, 2011 - PAGE 492 OF THE STANDARD PLANS BOOK DATED 2010.


2010 REVISED STANDARD PLAN RSP ES-13B

Dist	COUNTY	ROUTE	POST MILES TOTAL PROJECT	SHEET No.	TOTAL SHEETS
12	Ora	405	2.6/6.5	410	431
<i>Theresa Gabriel</i> REGISTERED ELECTRICAL ENGINEER October 30, 2015 PLANS APPROVAL DATE					
<small>THE STATE OF CALIFORNIA OR ITS OFFICERS OR AGENTS SHALL NOT BE RESPONSIBLE FOR THE ACCURACY OR COMPLETENESS OF SCANNED COPIES OF THIS PLAN SHEET.</small>					

TO ACCOMPANY PLANS DATED 06-27-16


**NOTES:**

1. Type 4 conduit shall be secured to the nearest walkway bracket using one-hole galvanized malleable iron or steel straps and brass machine screws tapped into the bracket.
2. See Overhead Signs Standard Plans for overhead signs and frame juncture details for photoelectric unit installation.
3. Enclosures and straps shall be secured by 3/8" maximum size screws.
4. The Contactor and test switch enclosures shall be readily accessible from the sign walkway.




**TYPICAL SIGN ILLUMINATION EQUIPMENT  
INSTALLATION FOR OVERHEAD SIGNS TUBULAR**

DETAIL A




**TYPICAL SIGN ILLUMINATION EQUIPMENT  
INSTALLATION FOR OVERHEAD SIGNS ROUND POST**


DETAIL B



SIDE VIEW



FRONT VIEW



ISOMETRIC VIEW

**TYPICAL SIGN ILLUMINATION EQUIPMENT  
INSTALLATION FOR OVERHEAD SIGNS  
BRIDGE MOUNTED**

DETAIL C  
See Note 4

STATE OF CALIFORNIA  
DEPARTMENT OF TRANSPORTATION  
**ELECTRICAL SYSTEMS  
(SIGN ILLUMINATION EQUIPMENT)**

NO SCALE

RSP ES-15C DATED OCTOBER 30, 2015 SUPERSEDES STANDARD PLAN ES-15C DATED MAY 20, 2011 - PAGE 498 OF THE STANDARD PLANS BOOK DATED 2010.

**REVISED STANDARD PLAN RSP ES-15C**

2010 REVISED STANDARD PLAN RSP ES-15C

Dist	COUNTY	ROUTE	POST MILES TOTAL PROJECT	SHEET No.	TOTAL SHEETS
12	Ora	405	2.6/6.5	411	431


Theresa Gabriel  
 REGISTERED ELECTRICAL ENGINEER  
 October 30, 2015  
 PLANS APPROVAL DATE  
THE STATE OF CALIFORNIA OR ITS OFFICERS OR AGENTS SHALL NOT BE RESPONSIBLE FOR THE ACCURACY OR COMPLETENESS OF SCANNED COPIES OF THIS PLAN SHEET.

TO ACCOMPANY PLANS DATED 06-27-16

2010 REVISED STANDARD PLAN RSP ES-15D


**NOTE:**

Type SC1A, SC2A, SC3A controls are similar to Types SC1, SC2 and SC controls respectively except test switch and wiring are not required.




**TYPE LC1 CONTROL**

For 120 V unswitched circuit with no more than 1000 W load.




**TYPE LC2 CONTROL**

For 120 V unswitched circuit




**TYPE LC3 CONTROL**

For 240 V unswitched circuits




**TYPE LC4 CONTROL**

For 480 V unswitched circuits




**TYPE SC1 CONTROL**

For 120 V switched circuit, see Note 1 for Type SC1A



**TYPE SC2 CONTROL**

For 240 V switched circuit, see Note 1 for Type SC2A



**TYPE SC3 CONTROL**

For 480 V switched sign circuit, see Note 1 for Type SC3A

**ELECTRICAL SYSTEMS (LIGHTING AND SIGN ILLUMINATION CONTROL)**

STATE OF CALIFORNIA DEPARTMENT OF TRANSPORTATION

NO SCALE

RSP ES-15D DATED OCTOBER 30, 2015 SUPERSEDES STANDARD PLAN ES-15D DATED MAY 20, 2011 - PAGE 499 OF THE STANDARD PLANS BOOK DATED 2010.

**REVISED STANDARD PLAN RSP ES-15D**

Dist	COUNTY	ROUTE	POST MILES TOTAL PROJECT	SHEET No.	TOTAL SHEETS
12	Ora	405	2.6/6.5	412	431


Stanley P. Johnson  
 REGISTERED CIVIL ENGINEER  
 October 30, 2015  
 PLANS APPROVAL DATE  
 No. C57793  
 Exp. 3-31-16  
 CIVIL  
 STATE OF CALIFORNIA  
 REGISTERED PROFESSIONAL ENGINEER

THE STATE OF CALIFORNIA OR ITS OFFICERS OR AGENTS SHALL NOT BE RESPONSIBLE FOR THE ACCURACY OR COMPLETENESS OF SCANNED COPIES OF THIS PLAN SHEET.


POLE TYPE	POLE DATA				BASE PLATE DATA				CIDH	
	HEIGHT "h"	Min OD		THICKNESS	"c"	THICKNESS	ANCHOR BOLT SIZE	BC = BOLT CIRCLE	Dia	"d"
		BASE	TOP							
CCTV 25	25'	7 <sup>3</sup> / <sub>8</sub> "			1'-1"			11 <sup>1</sup> / <sub>2</sub> "		7'-0"
CCTV 30	30'	8"			1'-1 <sup>1</sup> / <sub>2</sub> "			1'-0"		7'-6"
CCTV 35	35'	8 <sup>5</sup> / <sub>8</sub> "	3 <sup>3</sup> / <sub>4</sub> "	0.1793"	1'-2"	1"	1/2" $\phi$ x 36"	1'-1"	2'-6"	8'-0"
CCTV 40	40'	9 <sup>3</sup> / <sub>8</sub> "			1'-1 <sup>1</sup> / <sub>2</sub> "			1'-1 <sup>1</sup> / <sub>2</sub> "		8'-0"
CCTV 45	45'	10"			1'-3"			1'-2"		8'-6"

TO ACCOMPANY PLANS DATED 06-27-16


CCTV MOUNTING ADAPTER DETAIL SHALL BE SUBMITTED BY THE CONTRACTOR FOR THE ENGINEER'S APPROVAL, SEE DETAIL C




ELEVATION A




BASE PLATE  
DETAIL A




TOP PLATE  
DETAIL B




BOX ENCLOSURE  
DETAIL D




J HOOK  
DETAIL E



SECTION A-A



SAFETY CHAIN BRACKET  
DETAIL F



CLOSED CIRCUIT TELEVISION MOUNTING ADAPTER  
DETAIL C

NOTES:

1. Verify controlling field dimensions before ordering or fabricating any material.
2. During pole installation, the post shall be raked as necessary with the use of leveling nuts to provide a plumb pole axis.
3. Wind Loadings (3-second gust): 100 mph
4. Unit Stresses (Structural Steel):
  - a.  $f_y = 55,000$  psi (tapered steel tube and anchor bolts)
  - b.  $f_y = 50,000$  psi (unless otherwise noted)
5. Unit Stresses (Reinforced Concrete):
  - a.  $f'_c = 3,625$  psi
  - b.  $f_y = 60,000$  psi

STATE OF CALIFORNIA  
 DEPARTMENT OF TRANSPORTATION  
**ELECTRICAL SYSTEMS  
 (CLOSED CIRCUIT TELEVISION,  
 25' TO 45' POLE)**  
 NO SCALE

RSP ES-16B DATED OCTOBER 30, 2015 SUPERSEDES STANDARD PLAN ES-16B DATED MAY 20, 2011 - PAGE 501 OF THE STANDARD PLANS BOOK DATED 2010.

**REVISED STANDARD PLAN RSP ES-16B**

2010 REVISED STANDARD PLAN RSP ES-16B

DIST	COUNTY	ROUTE	POST MILES TOTAL PROJECT	SHEET No.	TOTAL SHEETS
12	Ora	405	2.6/6.5	413	431


  

REGISTERED CIVIL ENGINEER	DATE
6-27-16	06-10-16
PLANS APPROVAL DATE	


  

REGISTERED PROFESSIONAL ENGINEER
Gabriel J. Galo
No. 52288
Exp. 12-31-16
CIVIL

The State of California or its officers or agents shall not be responsible for the accuracy or completeness of scanned copies of this plan sheet.




**PROFILE GRADE - TOP OF WALL**  
NO SCALE



**DEVELOPED ELEVATION**  
1" = 20'-0"

- NOTES:
- For Temporary Railing (Type K), see "ROADWAY PLANS".
  - For Structural Details, see "STRUCTURAL DETAILS No. 1" through "STRUCTURAL DETAILS No. 8" sheets.
  - For Geocomposite Drain and Filter Fabric, see "DRAINAGE DETAILS No. 1, No. 2, and No. 3" sheets.
  - For "TYPICAL SECTION" see "GENERAL PLAN No. 2" sheet.
  - Concrete Surface Texture, (Fractured Rib Triangular Pattern) not shown for clarity.

- LEGEND:
- Indicates limits of existing Culver Drive OC Slope Paving to be removed. See "ROADWAY PLANS".
  - Indicates existing structure



**PLAN**  
1" = 20'-0"

QUANTITIES

STRUCTURE EXCAVATION (SOIL NAIL WALL)	176	CY
STRUCTURE EXCAVATION (GROUND ANCHOR WALL)	240	CY
STRUCTURE BACKFILL (GROUND ANCHOR WALL)	12	CY
STRUCTURE BACKFILL (SOIL NAIL WALL)	20	CY
LEAN CONCRETE BACKFILL	30	CY
GROUND ANCHOR (SUBHORIZONTAL)	27	EA
SOIL NAIL	1,960	LF
STRUCTURAL CONCRETE, FASCIA	118	CY
CONCRETE SURFACE TEXTURE (FRACTURED RIB TRIANGULAR PATTERN)	2,486	SQFT
BAR REINFORCING STEEL (FASCIA)	30,912	LB
STRUCTURAL SHOTCRETE	95	CY
MINOR CONCRETE (GUTTER) (LF)	314	LF
CABLE RAILING	217	LF
CONCRETE BARRIER (TYPE 60D MODIFIED)	312	LF

NOTE:  
THE CONTRACTOR MUST VERIFY ALL CONTROLLING FIELD DIMENSIONS BEFORE ORDERING OR FABRICATING ANY MATERIAL.

DESIGN ENGINEER <u>Jose Higuera</u>	DESIGN	BY Gabriel Galo	CHECKED Fred Feng	LOAD & RESISTANCE FACTOR DESIGN	LIVE LOADING: HL93 W/"LOW-BOY"; PERMIT DESIGN VEHICLE	STATE OF CALIFORNIA DEPARTMENT OF TRANSPORTATION	DIVISION OF ENGINEERING SERVICES STRUCTURE DESIGN DESIGN BRANCH 15	BRIDGE NO.	55E0171	RETAINING WALL No. 335 GENERAL PLAN No. 1
	DETAILS	BY Stan Cholda	CHECKED Fred Feng	LAYOUT	BY Gabriel Galo			CHECKED Fred Feng		
	QUANTITIES	BY Gabriel Galo	CHECKED Fred Feng	SPECIFICATIONS	BY Karen Doll	CHECKED Karen Doll	PLANS AND SPECS COMPARED			

ORIGINAL SCALE IN INCHES FOR REDUCED PLANS	0	1	2	3
--	---	---	---	---

UNIT: 3604	PROJECT NUMBER & PHASE: 12120000181	CONTRACT NO.: 12-0M3504	DISREGARD PRINTS BEARING EARLIER REVISION DATES	REVISION DATES	SHEET 1 OF 19
------------	-------------------------------------	-------------------------	---	----------------	---------------

DIST	COUNTY	ROUTE	POST MILES TOTAL PROJECT	SHEET No.	TOTAL SHEETS
12	Ora	405	2.6/6.5	414	431


REGISTERED CIVIL ENGINEER	DATE
6-27-16	06-10-16
PLANS APPROVAL DATE	


REGISTERED PROFESSIONAL ENGINEER
Gabriel J. Galo
No. 52288
Exp. 12-31-16
CIVIL
STATE OF CALIFORNIA

The State of California or its officers or agents shall not be responsible for the accuracy or completeness of scanned copies of this plan sheet.


LEGEND:  
 ----- Indicates existing structure



**DETAIL X**  
 3/4" = 1'-0"



**SOIL NAIL WALL**



**GROUND ANCHOR WALL**

**TYPICAL SECTION**  
 1/4" = 1'-0"

NOTE:  
 THE CONTRACTOR MUST VERIFY ALL CONTROLLING FIELD DIMENSIONS BEFORE ORDERING OR FABRICATING ANY MATERIAL.

- NOTES:
- For Slope Paving Removal, see "ROADWAY PLANS".
  - Bottom of walls shall be placed against undisturbed material.
  - For Geocomposite Drain, see "DRAINAGE DETAILS No. 1", "DRAINAGE DETAILS No. 2" and "DRAINAGE DETAILS No. 3" sheets.
  - For Soil Nail locations and elevations, see "TABLE No. 1" on "STRUCTURAL DETAILS No. 1" sheet; "TABLE No. 3" on "STRUCTURAL DETAILS No. 7" sheet.
  - Concrete Surface Texture, (Fractured Rib Triangular Pattern) not shown for clarity.
  - For Ground Anchor locations and elevations, see "STRUCTURAL DETAILS No. 3" and "STRUCTURAL DETAILS No. 4" sheets.

DESIGN	BY Gabriel Galo	CHECKED Fred Feng	LOAD & RESISTANCE FACTOR DESIGN	LIVE LOADING: HL93 W/"LOW-BOY"; PERMIT DESIGN VEHICLE
DETAILS	BY Stan Cholda	CHECKED Fred Feng	LAYOUT	BY Gabriel Galo
QUANTITIES	BY Gabriel Galo	CHECKED Fred Feng	SPECIFICATIONS	BY Karen Doll

STATE OF CALIFORNIA  
 DEPARTMENT OF TRANSPORTATION

DIVISION OF ENGINEERING SERVICES  
 STRUCTURE DESIGN  
**DESIGN BRANCH 15**

BRIDGE NO. 55E0171  
 POST MILE 5.62


**RETAINING WALL No. 335**  
**GENERAL PLAN No. 2**


UNIT: 3604  
 PROJECT NUMBER & PHASE: 12120000181  
 CONTRACT NO.: 12-0M3504

DISREGARD PRINTS BEARING EARLIER REVISION DATES

REVISION DATES	SHEET	OF
09-28-15 02-27-16 03-25-16 2/17/16	2	19

USERNAME => s128284 DATE PLOTTED => 09-AUG-2016 TIME PLOTTED => 14:16

DIST	COUNTY	ROUTE	POST MILES TOTAL PROJECT	SHEET No.	TOTAL SHEETS
12	Ora	405	2.6/6.5	415	431
 REGISTERED CIVIL ENGINEER			06-10-16	DATE	
6-27-16			PLANS APPROVAL DATE		
The State of California or its officers or agents shall not be responsible for the accuracy or completeness of scanned copies of this plan sheet.					



**TYPICAL SECTION - GROUND ANCHOR WALL**                      **TYPICAL SECTION - SOIL NAIL WALL**  
**LIMITS FOR STRUCTURE EXCAVATION AND BACKFILL**  
 NO SCALE

**GENERAL NOTES - SOIL NAIL WALL**

- DESIGN:**  
 Federal Highway Administration Publication Geotechnical Engineering Circular No. 7  
 Soil Nail Walls, Publication No. FHWA-IF-03-017
- LIVE LOADING:**  
 No Live Loading
- REINFORCED CONCRETE:**  
 $f_y = 60$  ksi (Yield Strength of Reinforcement)  
 $f'_c = 3.6$  ksi (Compressive Strength at 28 days)  
 $n = 8$
- STRUCTURAL SHOTCRETE:**  
 $f'_c = 3.6$  ksi  
 $f_y = 65$  ksi (plain welded wire reinforcement)  
 $f_y = 60$  ksi (bar reinforcement)
- STRUCTURAL STEEL (BEARING PLATES):**  
 $f_y = 50$  ksi
- STUDS:**  
 $f_y = 55$  ksi
- SOIL NAILS:**  
 $f_y = 75$  ksi
- SOIL PARAMETERS:**  
 $\gamma = 120$  pcf  
 $\phi = 32^\circ$   
 $C = 0$
- GROUT:**  
 $f'_c = 3000$  psi at 28 Days
- SEISMIC LOADING:**  
 Soil Profile: Soil Shearwave velocity  $V_{30} \approx 886$  ft/sec  
 (Average shear wave velocity in top 100 ft of soil)  
 Moment Magnitude:  $M_{Max} = 7.0 \pm 0.25$   
 Peak Ground Acceleration:  $0.63g$   
 $kh = 0.2$


- NOTES:**
- For GENERAL NOTES (Ground Anchors): See "SUB HORIZONTAL GROUND ANCHOR DETAILS" sheet.
  - For Lean Concrete Backfill, see "STRUCTURAL DETAILS No. 4" sheet.

**INDEX TO PLANS**

SHEET No.	TITLE
1	GENERAL PLAN No.1
2	GENERAL PLAN No.2
3	INDEX TO PLANS
4	FOUNDATION PLAN
5	STRUCTURAL DETAILS No.1
6	STRUCTURAL DETAILS No.2
7	STRUCTURAL DETAILS No.3
8	STRUCTURAL DETAILS No.4
9	STRUCTURAL DETAILS No.5
10	STRUCTURAL DETAILS No.6
11	STRUCTURAL DETAILS No.7
12	STRUCTURAL DETAILS No.8
13	SUB HORIZONTAL GROUND ANCHOR DETAILS
14	DRAINAGE DETAILS No.1
15	DRAINAGE DETAILS No.2
16	DRAINAGE DETAILS No.3
17	ARCHITECTURAL DETAILS No. 1
18	ARCHITECTURAL DETAILS No. 2
19	LOG OF TEST BORINGS

**STANDARD PLANS DATED 2010**

A10A	ACRONYMS AND ABBREVIATIONS (A-L)
RSP A10B	ACRONYMS AND ABBREVIATIONS (M-Z)
A76A	CONCRETE BARRIER TYPE 60
A78I	THREE BEAM BARRIER CONNECTION TO CONCRETE BARRIER
B0-3	BRIDGE DETAILS
B3-6	RETAINING WALL DETAILS No. 2
RSP B11-47	CABLE RAILING



**SOIL NAIL WALL DESIGN TABLE**

Wall Zone	RW 335 LOL	Minimum Nail Embedment Length (ft)	Maximum Nail Spacing Vertical (ft)	Maximum Nail Spacing Horizontal (ft)	Pullout Resistance $Q_d$ (lb/ft)	Minimum Threaded Bar Size	Minimum Allowable Facing Resistance (Static/Seismic)
1	10+00.00 to 10+31.42	20	5	5	2,500	#8	(28/38) kips
2	11+43.98 to 13+11.13	20	5	5	2,500	#8	(28/38) kips

**NOTE:**  
 THE CONTRACTOR MUST VERIFY ALL CONTROLLING FIELD DIMENSIONS BEFORE ORDERING OR FABRICATING ANY MATERIAL.

STRUCTURES DESIGN DETAIL SHEET (ENGLISH) (REV. 09-01-10)	DESIGN	BY Gabriel Galo	CHECKED Fred Feng	<b>STATE OF CALIFORNIA</b> <b>DEPARTMENT OF TRANSPORTATION</b>	DIVISION OF ENGINEERING SERVICES STRUCTURE DESIGN <b>DESIGN BRANCH 15</b>	BRIDGE NO.	55E0171	<b>RETAINING WALL No. 335</b> <b>INDEX TO PLANS</b>	
	DETAILS	BY Stan Cholda	CHECKED Fred Feng			POST MILE	5.62		
	QUANTITIES	BY Gabriel Galo	CHECKED Fred Feng						
ORIGINAL SCALE IN INCHES FOR REDUCED PLANS					UNIT: 3604 PROJECT NUMBER & PHASE: 12120000181	CONTRACT NO.: 12-0M3504	DISREGARD PRINTS BEARING EARLIER REVISION DATES	REVISION DATES 05-07-15   01-05-16   02-22-16   03-18-16	SHEET 3 OF 19

DIST	COUNTY	ROUTE	POST MILES TOTAL PROJECT	SHEET No.	TOTAL SHEETS
12	Ora	405	2.6/6.5	416	431



06-10-16 DATE  
 REGISTERED CIVIL ENGINEER  
 6-27-16 PLANS APPROVAL DATE  
 The State of California or its officers or agents shall not be responsible for the accuracy or completeness of scanned copies of this plan sheet.



- ① Sta 26+17.06, "E" LINE, CULVER DR. =
- Sta 336+59.02, "A" LINE, C ROUTE 405
- Sta 25+18.70, "E" LINE, CULVER DR. =
- ② Sta 336+89.43, "C" LINE, SB RTE.405 ON-RAMP
- Sta 24+93.52, "E" LINE, CULVER DR. =
- ③ Sta 1+03.35, "C-RWL" LINE, RW-335

BRIDGE LOCATION (Br.#55-0249)

(A) 59.13 Ft Rt C Culver Dr, "E" Line, Sta 25+05.51, Elev= 75.68  
 (B) 30.88 Ft Lt C Culver Dr, "E" Line, Sta 24+76.21, Elev= 75.78

No.	R	Δ	T	L
(A)	3000.00'	03°40'28"	96.23'	192.39'
(B)	158.00'	244°12'19"	251.85'	673.43'
(C)	438.00'	05°13'47"	20.00'	39.98'

PRHV-552  
 N 2 190 588.337  
 E 6 083 115.468  
 Elev= 62.61



**SURVEY CONTROL**

PRHV-549  
 FND PK+Tin  
 99.21' Lt, C "A" LINE  
 Sta 338+56.33  
 N 2 190 824.718  
 E 6 082 930.201  
 Elev= 52.24

PRHV-552  
 FND PK+Tin  
 245.52' Lt, C "A" LINE  
 Sta 335+94.05  
 N 2 190 588.337  
 E 6 083 115.468  
 Elev= 62.61

PRHV-549  
 N 2 190 824.718  
 E 6 082 930.201  
 Elev= 52.24

NOTE:  
 THE CONTRACTOR MUST VERIFY ALL CONTROLLING FIELD DIMENSIONS BEFORE ORDERING OR FABRICATING ANY MATERIAL.

NOTES:  
 UNDERGROUND UTILITIES AS SHOWN ARE APPROXIMATE, SEE UTILITY PLANS FOR MORE INFORMATION


<b>PRELIMINARY INVESTIGATION SECTION</b>			DESIGN BY Gabriel Galo	CHECKED Fred Feng	<b>STATE OF CALIFORNIA</b> <b>DEPARTMENT OF TRANSPORTATION</b>	<b>DIVISION OF ENGINEERING SERVICES</b> <b>STRUCTURE DESIGN</b> <b>DESIGN BRANCH 15</b>	BRIDGE NO. 55E0171	<b>RETAINING WALL No. 335</b> <b>FOUNDATION PLAN</b>							
SCALE 1"=20'	VERT.DATUM NAVD88	PHOTOGRAMMETRY AS OF: X	DETAILS BY Stan Cholda	CHECKED Fred Feng			POST MILE 5.62								
ALIGNMENT TIES Dist. Traverse Sheet	SURVEYED BY District 12	CHECKED BY X	QUANTITIES BY Gabriel Galo	CHECKED Fred Feng											
STRUCTURES DESIGN DETAIL SHEET (ENGLISH) (REV. 09-01-10)			ORIGINAL SCALE IN INCHES FOR REDUCED PLANS		UNIT: 3604	PROJECT NUMBER & PHASE: 12120000181	CONTRACT NO.: 12-0M3504	DISREGARD PRINTS BEARING EARLIER REVISION DATES	<table border="1" style="font-size: small;"> <tr> <th>REVISION DATES</th> <th>SHEET</th> <th>OF</th> </tr> <tr> <td>6/28/15 03/25/16 09/27/15 12/28/15</td> <td>4</td> <td>19</td> </tr> </table>	REVISION DATES	SHEET	OF	6/28/15 03/25/16 09/27/15 12/28/15	4	19
REVISION DATES	SHEET	OF													
6/28/15 03/25/16 09/27/15 12/28/15	4	19													

USERNAME => s126284 DATE PLOTTED => 09-AUG-2016 TIME PLOTTED => 14:16

DIST	COUNTY	ROUTE	POST MILES TOTAL PROJECT	SHEET No.	TOTAL SHEETS
12	Ora	405	2.6/6.5	417	431

REGISTERED CIVIL ENGINEER DATE 06-10-16  
 PLANS APPROVAL DATE 6-27-16  
 The State of California or its officers or agents shall not be responsible for the accuracy or completeness of scanned copies of this plan sheet.

REGISTERED PROFESSIONAL ENGINEER  
 Gabriel J. Galo  
 No. 52288  
 Exp. 12-31-16  
 CIVIL  
 STATE OF CALIFORNIA



**TABLE No. 1**


LOCATION	ELEVATION (Soil Nail)					
	①	②	③	④	⑤	⑥
Row 1	54.794	56.689	58.584	60.479	62.374	64.269
Row 2			53.584	55.479	57.374	59.269
Row 3						54.269
Row 4		53.155			53.067	

LOCATION	ELEVATION (Proof Test Soil Nail)	
	A	B
Sta	10+14.92	10+24.92
ELEVATION	58.048	56.838

- NOTES:
- For Soil Nail elevations, see "TABLE No. 1"
  - Soil Nails to be installed normal to "RW 335 LOL" Line.
  - For "SECTION A-A", see "STRUCTURAL DETAILS No. 2" sheet.
  - Concrete Surface Texture, (Fractured Rib Triangular Pattern) not shown for clarity.
  - For Drainage Details, see "DRAINAGE DETAILS No. 1" AND "DRAINAGE DETAILS No. 2" sheets.


- LEGEND:
- ⊙ - Ground Anchor Assembly
  - - Soil Nail
  - △ - Proof Test Soil Nail
  - Indicates existing structure




NOTE:  
 THE CONTRACTOR MUST VERIFY ALL CONTROLLING FIELD DIMENSIONS BEFORE ORDERING OR FABRICATING ANY MATERIAL.

DESIGN BY Gabriel Galo CHECKED Fred Feng DETAILS BY Stan Cholda CHECKED Fred Feng QUANTITIES BY Gabriel Galo CHECKED Fred Feng	STATE OF CALIFORNIA DEPARTMENT OF TRANSPORTATION	DIVISION OF ENGINEERING SERVICES STRUCTURE DESIGN <b>DESIGN BRANCH 15</b>	BRIDGE NO. 55E0171 POST MILE 5.62	<b>RETAINING WALL No. 335</b> <b>STRUCTURAL DETAILS No. 1</b>	
	ORIGINAL SCALE IN INCHES FOR REDUCED PLANS 0 1 2 3	UNIT: 3604 PROJECT NUMBER & PHASE: 12120000181	CONTRACT NO.: 12-0M3504	DISREGARD PRINTS BEARING EARLIER REVISION DATES	REVISION DATES 05-07-15 02-17-16 02-22-16 03-25-16 SHEET 5 OF 19
	STRUCTURES DESIGN DETAIL SHEET (ENGLISH) (REV. 09-01-10)				

DIST	COUNTY	ROUTE	POST MILES TOTAL PROJECT	SHEET No.	TOTAL SHEETS
12	Ora	405	2.6/6.5	418	431


 REGISTERED CIVIL ENGINEER DATE 06-10-16  
 PLANS APPROVAL DATE 6-27-16  
 The State of California or its officers or agents shall not be responsible for the accuracy or completeness of scanned copies of this plan sheet.



- NOTES:
- For details of top of wall, see "SECTION B-B" on "STRUCTURAL DETAILS No. 4" sheet.
  - Bottom of Wall shall be placed against undisturbed material.
  - For additional Soil Nail details, see "STRUCTURAL DETAILS No. 1", "STRUCTURAL DETAILS No. 5" through "STRUCTURAL DETAILS No. 8" sheets.
  - For Concrete Surface Texture details, see "ARCHITECTURAL DETAILS No.1" and "ARCHITECTURAL DETAILS No. 2" sheets.
  - Electrical Conduit to be placed in stages prior to shotcrete. See "ROADWAY PLANS".

NOTE:  
 THE CONTRACTOR MUST VERIFY ALL CONTROLLING FIELD DIMENSIONS BEFORE ORDERING OR FABRICATING ANY MATERIAL.

**SECTION A-A**  
 3/4" = 1'-0"

DESIGN BY Gabriel Galo CHECKED Fred Feng DETAILS BY Stan Cholda CHECKED Fred Feng QUANTITIES BY Gabriel Galo CHECKED Fred Feng	STATE OF CALIFORNIA DEPARTMENT OF TRANSPORTATION	DIVISION OF ENGINEERING SERVICES STRUCTURE DESIGN <b>DESIGN BRANCH 15</b>	BRIDGE NO. 55E0171 POST MILE 5.62	<b>RETAINING WALL No. 335</b> <b>STRUCTURAL DETAILS No. 2</b>
	UNIT: 3604 PROJECT NUMBER & PHASE: 12120000181	CONTRACT NO.: 12-0M3504	REVISION DATES 12-29-15 02-27-16 03-25-16 02-11-16	SHEET OF 6 19
	STRUCTURES DESIGN DETAIL SHEET (ENGLISH) (REV. 09-01-10) ORIGINAL SCALE IN INCHES FOR REDUCED PLANS 0 1 2 3			

USERNAME => s128284 DATE PLOTTED => 09-AUG-2016 TIME PLOTTED => 14:16

DIST	COUNTY	ROUTE	POST MILES TOTAL PROJECT	SHEET No.	TOTAL SHEETS
12	Ora	405	2.6/6.5	419	431


  

<i>Signature</i>	06-10-16
REGISTERED CIVIL ENGINEER	DATE
6-27-16	
PLANS APPROVAL DATE	


  

Gabriel J. Galo
No. 52288
Exp. 12-31-16
CIVIL

*The State of California or its officers or agents shall not be responsible for the accuracy or completeness of scanned copies of this plan sheet.*



**ELEVATION**  
3/16" = 1'-0"



**PLAN**  
3/16" = 1'-0"

- NOTES:
- Concrete Surface Texture, (Fractured Rib Triangular Pattern) not shown for clarity.
  - For Drainage Details, see "DRAINAGE DETAILS No. 2" AND "DRAINAGE DETAILS No. 3" sheets.
  - Contractor shall verify all existing piles location prior to ground anchor construction.



- LEGEND:
- - - - - Indicates existing structure
  - ⊙ Indicates Ground Anchor Assembly

NOTE:  
THE CONTRACTOR MUST VERIFY ALL CONTROLLING FIELD DIMENSIONS BEFORE ORDERING OR FABRICATING ANY MATERIAL.

DESIGN	BY	Gabriel Galo	CHECKED	Fred Feng	STATE OF CALIFORNIA DEPARTMENT OF TRANSPORTATION	DIVISION OF ENGINEERING SERVICES STRUCTURE DESIGN DESIGN BRANCH 15	BRIDGE NO.	55E0171	<b>RETAINING WALL No. 335</b> <b>STRUCTURAL DETAILS No. 3</b>	
	DETAILS	BY	Stan Cholda	CHECKED			Fred Feng	POST MILE		5.62
	QUANTITIES	BY	Gabriel Galo	CHECKED			Fred Feng			

STRUCTURES DESIGN DETAIL SHEET (ENGLISH) (REV. 09-01-10)	ORIGINAL SCALE IN INCHES FOR REDUCED PLANS	0	1	2	3	UNIT: 3604	PROJECT NUMBER & PHASE: 12120000181	CONTRACT NO.: 12-0M3504	DISREGARD PRINTS BEARING EARLIER REVISION DATES	REVISION DATES	SHEET	OF			
										09-25-15	02-22-16	03-25-16	03-11-16	7	19



- NOTES:
1. For Ground Anchors layout and distribution, see "STRUCTURAL DETAILS No. 3" sheet.
  2. Bottom of Wall should be placed against undisturbed material.
  3. Begin Geocomposite Drain at center line of top Soil Nail or top Ground Anchor row.
  4. Remove unstable soil without damaging the footing. Do not expose bottom of the footing.

LEGEND:

Indicates Lean Concrete Backfill

TABLE No. 2

LOCATION	ELEVATION (Ground Anchor)								
	7	8	9	10	11	12	13	14	15
Row 1	62.736								
Row 2	57.736								
Row 3	53.236								

NOTE:  
 THE CONTRACTOR MUST VERIFY ALL CONTROLLING FIELD DIMENSIONS BEFORE ORDERING OR FABRICATING ANY MATERIAL.

SECTION B-B  
 3/4" = 1'-0"


DESIGN	BY Gabriel Galo	CHECKED Fred Feng
DETAILS	BY Stan Cholda	CHECKED Gabriel Galo
QUANTITIES	BY Gabriel Galo	CHECKED Fred Feng


STATE OF CALIFORNIA  
 DEPARTMENT OF TRANSPORTATION

DIVISION OF ENGINEERING SERVICES  
 STRUCTURE DESIGN  
 DESIGN BRANCH 15


BRIDGE NO.	55E0171
POST MILE	5.62

RETAINING WALL No. 335  
 STRUCTURAL DETAILS No. 4

DIST	COUNTY	ROUTE	POST MILES TOTAL PROJECT	SHEET No.	TOTAL SHEETS
12	Ora	405	2.6/6.5	421	431
 REGISTERED CIVIL ENGINEER			DATE	06-10-16	
6-27-16 PLANS APPROVAL DATE					
<small>The State of California or its officers or agents shall not be responsible for the accuracy or completeness of scanned copies of this plan sheet.</small>					



**DEVELOPED ELEVATION**  
 $\frac{3}{16}'' = 1'-0''$



NOTE:  
 THE CONTRACTOR MUST VERIFY ALL CONTROLLING FIELD DIMENSIONS BEFORE ORDERING OR FABRICATING ANY MATERIAL.

NOTES:


1. For Soil Nail elevations, see "TABLE No. 3" and "TABLE No. 4" on "STRUCTURAL DETAILS No. 7" sheet.
2. For "SOIL NAIL ASSEMBLY DETAIL" see "STRUCTURAL DETAILS No. 8" sheet.
3. See "GENERAL PLAN No. 1" sheet for alignment information.
4. (Concrete Surface Texture) not shown for clarity.
5. Soil Nail can be placed at 20° if needed to avoid conflict with existing footing.
6. Approximate location of electrical conduit. See "ROADWAY PLANS".
7. CIDH pile for lighting standard to be constructed at mid-point between soil nails. For additional information, see "ROADWAY PLANS".

LEGEND:


- ⊙ - Ground Anchor Assembly
- - Soil Nail
- △ - Proof Test Soil Nail
- - Indicates existing structure

<table border="1" style="width: 100%; border-collapse: collapse;"> <tr> <td style="width: 30%;">DESIGN</td> <td style="width: 30%;">BY Gabriel Galo</td> <td style="width: 30%;">CHECKED Fred Feng</td> </tr> <tr> <td>DETAILS</td> <td>BY Stan Cholda</td> <td>CHECKED Fred Feng</td> </tr> <tr> <td>QUANTITIES</td> <td>BY Gabriel Galo</td> <td>CHECKED Fred Feng</td> </tr> </table>	DESIGN	BY Gabriel Galo	CHECKED Fred Feng	DETAILS	BY Stan Cholda	CHECKED Fred Feng	QUANTITIES	BY Gabriel Galo	CHECKED Fred Feng	<b>STATE OF CALIFORNIA</b> DEPARTMENT OF TRANSPORTATION	DIVISION OF ENGINEERING SERVICES STRUCTURE DESIGN <b>DESIGN BRANCH 15</b>	BRIDGE NO. 55E0171 POST MILE 5.62	<b>RETAINING WALL No. 335</b> <b>STRUCTURAL DETAILS No. 5</b>
DESIGN	BY Gabriel Galo	CHECKED Fred Feng											
DETAILS	BY Stan Cholda	CHECKED Fred Feng											
QUANTITIES	BY Gabriel Galo	CHECKED Fred Feng											
STRUCTURES DESIGN DETAIL SHEET (ENGLISH) (REV. 09-01-10)		ORIGINAL SCALE IN INCHES FOR REDUCED PLANS 0 1 2 3	UNIT: 3604 PROJECT NUMBER & PHASE: 12120000181 CONTRACT NO.: 12-0M3504		DISREGARD PRINTS BEARING EARLIER REVISION DATES <table border="1" style="font-size: small;"> <tr> <th>REVISION DATES</th> <th>SHEET</th> <th>OF</th> </tr> <tr> <td>10-28-15 03-25-16 02-27-16 02-25-16</td> <td>9</td> <td>19</td> </tr> </table>	REVISION DATES	SHEET	OF	10-28-15 03-25-16 02-27-16 02-25-16	9	19		
REVISION DATES	SHEET	OF											
10-28-15 03-25-16 02-27-16 02-25-16	9	19											

DIST	COUNTY	ROUTE	POST MILES TOTAL PROJECT	SHEET No.	TOTAL SHEETS
12	Ora	405	2.6/6.5	422	431
REGISTERED CIVIL ENGINEER			DATE	06-10-16	
6-27-16			PLANS APPROVAL DATE		
The State of California or its officers or agents shall not be responsible for the accuracy or completeness of scanned copies of this plan sheet.					



**DEVELOPED ELEVATION**  
 $\frac{3}{16}'' = 1'-0''$



**PLAN**  
 $\frac{3}{16}'' = 1'-0''$


- NOTES:
1. For Soil Nail elevations, see "TABLE No. 3" and "TABLE No. 4" on "STRUCTURAL DETAILS No. 7" sheet.
  2. For "SOIL NAIL ASSEMBLY DETAIL" see "STRUCTURAL DETAILS No. 8" sheet.
  3. See "GENERAL PLAN No. 1" sheet for alignment information.
  4. Concrete Surface Texture, (Fractured Rib Triangular Pattern) not shown for clarity.
  5. For Drainage Details, see "DRAINAGE DETAILS No. 1" AND "DRAINAGE DETAILS No. 2" sheets.

- LEGEND:
- - Soil Nail
  - △ - Proof Test Soil Nail
  - Indicates existing structure

NOTE:  
 THE CONTRACTOR MUST VERIFY ALL CONTROLLING FIELD DIMENSIONS BEFORE ORDERING OR FABRICATING ANY MATERIAL.

DESIGN BY Gabriel Galo CHECKED BY Fred Feng DETAILS BY Stan Cholda CHECKED BY Fred Feng QUANTITIES BY Gabriel Galo CHECKED BY Fred Feng	STATE OF CALIFORNIA DEPARTMENT OF TRANSPORTATION DIVISION OF ENGINEERING SERVICES STRUCTURE DESIGN <b>DESIGN BRANCH 15</b>	BRIDGE NO.	<b>RETAINING WALL No. 335</b> <b>STRUCTURAL DETAILS No. 6</b>
		55E0171	
		POST MILE	
STRUCTURES DESIGN DETAIL SHEET (ENGLISH) (REV. 09-01-10) ORIGINAL SCALE IN INCHES FOR REDUCED PLANS	UNIT: 3604 PROJECT NUMBER & PHASE: 12120000181 CONTRACT NO.: 12-0M3504	DISREGARD PRINTS BEARING EARLIER REVISION DATES	REVISION DATES 12-28-15 03-25-16 07-28-15 10-28-15 SHEET 10 OF 19

DIST	COUNTY	ROUTE	POST MILES TOTAL PROJECT	SHEET No.	TOTAL SHEETS
12	Ora	405	2.6/6.5	423	431

  
 REGISTERED CIVIL ENGINEER DATE 06-10-16  
 6-27-16  
 PLANS APPROVAL DATE  


The State of California or its officers or agents shall not be responsible for the accuracy or completeness of scanned copies of this plan sheet.

**TABLE No. 3**

LOCATION	ELEVATION (Soil Nail)																						
	⑬	⑭	⑮	⑯	⑰	⑱	⑲	㉑	㉒	㉓	㉔	㉕	㉖	㉗	㉘	㉙	㉚	㉛	㉜	㉝	㉞	㉟	
Row 1	64.193	64.456	64.055	63.653	63.251	62.850	62.448	62.046	61.645	61.243	60.841	60.440	60.038	59.636	59.235	58.833	58.431	58.030	57.628	57.223	56.825	56.423	56.021
Row 2	59.193	59.456	59.055	58.653	58.251	57.850	57.448	57.046	56.645	56.243	55.841	55.440	55.038	54.636	54.235	53.833	53.431	53.030	52.628	52.226			
Row 3	53.422	54.456	54.055	53.653	53.251	52.850	52.448	52.149	52.120	52.091	52.061	52.032	52.003	51.973							51.822	51.739	51.679

**ELEVATION (Proof Test Soil Nail)**

LOCATION	C	D	E	F	G	H	I	J
Sta	11+61.48	11+81.48	12+01.50	12+21.48	12+41.48	12+61.48	12+81.48	13+01.48
ELEVATION	62.028	55.421	58.814	52.208	55.601	53.994	52.388	50.781

**TABLE No. 3 (Cont)**



LOCATION	ELEVATION (Soil Nail)										
	⑳	㉑	㉒	㉓	㉔	㉕	㉖	㉗	㉘	㉙	㉚
Row 1	55.620	55.218	54.816	54.415	54.013	53.612	53.210	52.808	52.407	52.090	51.760
Row 2											
Row 3	51.619	51.559	51.500	51.440							

NOTE:  
 THE CONTRACTOR MUST VERIFY ALL CONTROLLING FIELD DIMENSIONS BEFORE ORDERING OR FABRICATING ANY MATERIAL.


STRUCTURES DESIGN DETAIL SHEET (ENGLISH) (REV. 09-01-10)	DESIGN	BY Gabriel Galo	CHECKED Fred Feng	<b>STATE OF CALIFORNIA</b> DEPARTMENT OF TRANSPORTATION	DIVISION OF ENGINEERING SERVICES STRUCTURE DESIGN <b>DESIGN BRANCH 15</b>	BRIDGE NO.	<b>RETAINING WALL No. 335</b> <b>STRUCTURAL DETAILS No. 7</b>			
	DETAILS	BY Stan Cholda	CHECKED Fred Feng			55E0171				
	QUANTITIES	BY Gabriel Galo	CHECKED Fred Feng			POST MILE 5.62				
ORIGINAL SCALE IN INCHES FOR REDUCED PLANS					UNIT: 3604	PROJECT NUMBER & PHASE: 12120000181	CONTRACT NO.: 12-0M3504	DISREGARD PRINTS BEARING EARLIER REVISION DATES	REVISION DATES 7-16-15 8-14-15 12-29-15 03-25-16	SHEET 11 OF 19

FILE => 55e0171-f-sde+07.dgn

USERNAME => s128284 DATE PLOTTED => 09-AUG-2016 TIME PLOTTED => 14:16


DIST	COUNTY	ROUTE	POST MILES TOTAL PROJECT	SHEET No.	TOTAL SHEETS
12	Ora	405	2.6/6.5	424	431
 REGISTERED CIVIL ENGINEER			06-10-16 DATE		
6-27-16 PLANS APPROVAL DATE					
<small>The State of California or its officers or agents shall not be responsible for the accuracy or completeness of scanned copies of this plan sheet.</small>					

- NOTES:
1. The test nail embedment length,  $L_{eT}$ , must be equal to  $2/3$  of the embedment length,  $L_e$ , of the adjacent production soil nail assemblies, but not less than 13'-0"
  2. The total length of the test nail assembly equals the embedment length plus the length required for jacking equipment.
  3. For location of proof test nails, see "STRUCTURE PLAN" sheets.
  4. Contractor to determine drilled hole diameter.
  5. Finished grout surface to be normal to the bar.




**SOIL NAIL ASSEMBLY**  
3" = 1'-0"

NOTE:  
Wall section with Shotcrete shown,  
Section without Shotcrete similar.




**BEARING PLATE DETAIL**  
3" = 1'-0"



**TEST NAIL DETAIL**  
3" = 1'-0"

NOTE:  
THE CONTRACTOR MUST VERIFY ALL  
CONTROLLING FIELD DIMENSIONS BEFORE  
ORDERING OR FABRICATING ANY MATERIAL.



**DETAIL A**  
3" = 1'-0"

STRUCTURES DESIGN DETAIL SHEET (ENGLISH) (REV. 09-01-10) ORIGINAL SCALE IN INCHES FOR REDUCED PLANS 0 1 2 3	DESIGN	BY Gabriel Galo	CHECKED Fred Feng	<b>STATE OF CALIFORNIA</b> DEPARTMENT OF TRANSPORTATION DIVISION OF ENGINEERING SERVICES STRUCTURE DESIGN <b>DESIGN BRANCH 15</b> BRIDGE NO. 55E0171 POST MILE 5.62 UNIT: 3604 PROJECT NUMBER & PHASE: 12120000181 CONTRACT NO.: 12-0M3504	<b>RETAINING WALL No. 335</b> <b>STRUCTURAL DETAILS No. 8</b> SHEET 12 OF 19
	DETAILS	BY Stan Cholda	CHECKED Gabriel Galo		
	QUANTITIES	BY Gabriel Galo	CHECKED Fred Feng		
DISREGARD PRINTS BEARING EARLIER REVISION DATES				REVISION DATES 3-14-15 03-25-16 01-09-16 2-20-16	FILE => 55e0171-f-sdet08.dgn

### GENERAL NOTES

**DESIGN:**  
AASHTO LRFD Bridge Design Specifications, 4th Edition with California Amendments.

**PRESTRESSING STEEL:**

- Bars - 150 ksi ①
- Strand Tendons - 270 Ksi Low Relaxation steel ①
- ② FDL = Factored Design Load (Kips)
- FTL = Factored Test Load per anchor (Kips)
- ② LL = Lock Off Load (Kips)
- fpu = Minimum tensile strength of prestressing steel
- As = Minimum cross sectional area of prestressing steel in ground anchor (square inch)

②  $As(\text{Min}) = \frac{1.0 \text{ FTL}}{0.75 \text{ fpu}}$  (Strands)

②  $As(\text{Min}) = \frac{1.0 \text{ FTL}}{0.80 \text{ fpu}}$  (Bars)

**REINFORCED CONCRETE (FASCIA):**  
f'c = 3.6 ksi  
fy = 60 ksi


**SHOTCRETE:**  
f'c = 3.6 ksi  
fy = 60 ksi

**NOTES:**


- ① (A) Level of initial grouting for drilled hole 6" in diameter or smaller. See Note (H)
- (B) Level of secondary grouting
- (C) Level of initial grouting inside corrugated sheathing
- (D) Bonded length shall be determined by the contractor
- ① (E) Unbonded Length = 25 ft.
- ① (F) For inclination, see "SECTION B-B", on "STRUCTURAL DETAILS No. 4" sheet.
- (G) Face of Wall Excavation
- ② (H) Location of grout break outside corrugated sheathing.

**NOTES:**


- 1. Anchorage enclosure shall only be used when anchor head assembly is not enclosed in concrete.
- 2. Anchorage enclosure shall have provisions to allow injecting grout at low end and venting at high end. Galvanize after fabrication.
- 3. Silicone sealant to cover full width of flange.
- ① 4. Steel tube (Min thickness = 1/4") welded to bearing plate. Inside diameter of steel tube to be 1" greater than outside diameter of corrugated sheathing. Galvanize after fabrication.
- ① 5. Steel tube (Min thickness = 1/4") welded to bearing plate. Inside diameter of steel tube to be 1" greater than outside diameter of smooth sheathing. Galvanize after fabrication.
- ① 6. The steel tube must extend 6" Min into drilled hole.
- 7. For other wall details, see PROJECT PLANS.




**GROUND ANCHOR TENDON DETAIL (STRANDS)**



**GROUND ANCHOR TENDON DETAIL BAR(S)**



**ALTERNATIVE X**



**ALTERNATIVE Y ANCHORAGE ENCLOSURE DETAILS**

③

TABLE No. 5			
GROUND ANCHOR TEST LOAD (kip)			
LOCATION	FDL	FTL	LL
ROW 1	98.0	98.0	66.0
ROW 2	65.0	65.0	44.0
ROW 3	42.0	42.0	28.0


NO SCALE


STANDARD DRAWING	① Modified Note	③ Added "TABLE No. 5"
FILE NO. <b>xs12-040</b>	② Added Note	
APPROVAL DATE July 2014		

STATE OF CALIFORNIA	DIVISION OF ENGINEERING SERVICES	BRIDGE NO. 55E0171	RETAINING WALL No. 335
DEPARTMENT OF TRANSPORTATION		POST MILE 5.62	SUB HORIZONTAL GROUND ANCHOR DETAILS


UNIT: 3604	PROJECT NUMBER & PHASE: 12120000181	CONTRACT NO.: 12-0M3504
------------	-------------------------------------	-------------------------

DISREGARD PRINTS BEARING EARLIER REVISION DATES	REVISION DATES	SHEET 13 OF 19
---	----------------	----------------

DIST	COUNTY	ROUTE	POST MILES TOTAL PROJECT	SHEET No.	TOTAL SHEETS
12	Ora	405	2.6/6.5	426	431
 REGISTERED CIVIL ENGINEER			06-10-16 DATE		
6-27-16 PLANS APPROVAL DATE					
<small>The State of California or its officers or agents shall not be responsible for the accuracy or completeness of scanned copies of this plan sheet.</small>					



**PARTIAL ELEVATION**  
3/8" = 1'-0"



**SOIL NAIL SECTION**  
1/2" = 1'-0"

- NOTES:
1. Provide filter fabric where necessary to prevent soil from entering drain.
  2. Center Geocomposite Drains between Soil Nail columns.
  3. Geocomposite Drains must have filter fabric on soil side and wrapped around top and side edges, see "DRAINAGE DETAILS No. 2" sheet.
  4. Begin Geocomposite Drain at center line of top Soil Nail or top Ground Anchor row.

- LEGEND:
- - Indicates Soil Nail location. See "STRUCTURAL DETAILS No. 1" through "STRUCTURAL DETAILS No. 8" sheets for the layout of these elements and the location of the geocomposite strip placement.
  - △ - Indicates Proof Test Soil Nails

NOTE:  
THE CONTRACTOR MUST VERIFY ALL CONTROLLING FIELD DIMENSIONS BEFORE ORDERING OR FABRICATING ANY MATERIAL.


DESIGN	BY Gabriel Galo	CHECKED Fred Feng
DETAILS	BY Stan Cholda	CHECKED Gabriel Galo
QUANTITIES	BY Gabriel Galo	CHECKED Fred Feng


STATE OF CALIFORNIA  
DEPARTMENT OF TRANSPORTATION

DIVISION OF ENGINEERING SERVICES  
STRUCTURE DESIGN  
**DESIGN BRANCH 15**


BRIDGE NO.	55E0171
POST MILE	5.62

**RETAINING WALL No. 335**  
**DRAINAGE DETAILS No. 1**


DIST	COUNTY	ROUTE	POST MILES TOTAL PROJECT	SHEET No.	TOTAL SHEETS
12	Ora	405	2.6/6.5	427	431
 REGISTERED CIVIL ENGINEER			06-10-16 DATE		
6-27-16 PLANS APPROVAL DATE					
<small>The State of California or its officers or agents shall not be responsible for the accuracy or completeness of scanned copies of this plan sheet.</small>					




**WALL DRAIN DETAIL AT WEEPHOLE**  
**OPTION A**  
NO SCALE




**VIEW A-A**  
NO SCALE



**DRAIN SPLICE**  
NO SCALE



**SECTION B-B**  
NO SCALE



**WALL DRAIN DETAIL AT WEEPHOLE**  
**OPTION B**  
NO SCALE


NOTE:  
THE CONTRACTOR MUST VERIFY ALL CONTROLLING FIELD DIMENSIONS BEFORE ORDERING OR FABRICATING ANY MATERIAL.


NOTES:

- Center Geocomposite Drains between soil nail columns.
- Provide filter fabric where necessary to prevent soil from entering drain.
- Alternative drain outlet details may be submitted for Engineer's approval.
- Splice length for Geocomposite drain shall be 12".

STRUCTURES DESIGN DETAIL SHEET (ENGLISH) (REV. 09-01-10)	DESIGN	BY Gabriel Galo	CHECKED Fred Feng	<b>STATE OF CALIFORNIA</b> DEPARTMENT OF TRANSPORTATION	DIVISION OF ENGINEERING SERVICES STRUCTURE DESIGN <b>DESIGN BRANCH 15</b>	BRIDGE NO.	<b>RETAINING WALL No. 335</b> <b>DRAINAGE DETAILS No. 2</b>
	DETAILS	BY Stan Cholda	CHECKED Gabriel Galo			55E0171	
	QUANTITIES	BY Gabriel Galo	CHECKED Fred Feng			POST MILE 5.62	
ORIGINAL SCALE IN INCHES FOR REDUCED PLANS				UNIT: 3604	PROJECT NUMBER & PHASE: 12120000181	CONTRACT NO.: 12-0M3504	DISREGARD PRINTS BEARING EARLIER REVISION DATES REVISION DATES: 01-18-15, 03-25-16, 8-10-15, 01-20-16 SHEET 15 OF 19

USERNAME => s128284 DATE PLOTTED => 09-AUG-2016 TIME PLOTTED => 14:16

DIST	COUNTY	ROUTE	POST MILES TOTAL PROJECT	SHEET No.	TOTAL SHEETS
12	Ora	405	2.6/6.5	428	431
 REGISTERED CIVIL ENGINEER			06-10-16 DATE		
06-27-16 PLANS APPROVAL DATE					
<small>The State of California or its officers or agents shall not be responsible for the accuracy or completeness of scanned copies of this plan sheet.</small>					



**PARTIAL ELEVATION**  
3/8" = 1'-0"


**NOTES:**

1. Provide filter fabric where necessary to prevent soil from entering drain.
2. Center Geocomposite Drains between Ground Anchors columns.
3. Geocomposite Drains must have filter fabric on soil side and wrapped around top and side edges, see "DRAINAGE DETAILS No. 2" sheet.
4. Begin Geocomposite Drain at center line of top Ground Anchor row.

**LEGEND:**

- - Indicates Ground Anchor location. See "STRUCTURAL DETAILS No. 1" through "STRUCTURAL DETAILS No. 8" sheets for the layout of these elements and the location of the geocomposite strip placement.

**NOTE:**  
THE CONTRACTOR MUST VERIFY ALL CONTROLLING FIELD DIMENSIONS BEFORE ORDERING OR FABRICATING ANY MATERIAL.



**GROUND ANCHOR SECTION**  
1/2" = 1'-0"


DESIGN	BY Gabriel Galo	CHECKED Fred Feng
DETAILS	BY Stan Cholda	CHECKED Gabriel Galo
QUANTITIES	BY Gabriel Galo	CHECKED Fred Feng


**STATE OF CALIFORNIA**  
DEPARTMENT OF TRANSPORTATION

DIVISION OF ENGINEERING SERVICES  
STRUCTURE DESIGN  
**DESIGN BRANCH 15**


BRIDGE NO.	55E0171
POST MILE	5.62

**RETAINING WALL No. 335**  
**DRAINAGE DETAILS No. 3**


DIST	COUNTY	ROUTE	POST MILES TOTAL PROJECT	SHEET No.	TOTAL SHEETS
12	Ora	405	2.6/6.5	429	431
 REGISTERED CIVIL ENGINEER			06-10-16	DATE	
06-27-16			PLANS APPROVAL DATE		
					
<small>The State of California or its officers or agents shall not be responsible for the accuracy or completeness of scanned copies of this plan sheet.</small>					



**DEVELOPED ELEVATION**  
 $\frac{3}{16}'' = 1'-0''$



**SECTION A-A**  
 $\frac{1}{2}'' = 1'-0''$





**SECTION B-B**  
 $\frac{1}{2}'' = 1'-0''$

NOTE:  
 THE CONTRACTOR MUST VERIFY ALL CONTROLLING FIELD DIMENSIONS BEFORE ORDERING OR FABRICATING ANY MATERIAL.


<table border="1" style="width: 100%; border-collapse: collapse;"> <tr> <td style="width: 30%;">DESIGN</td> <td style="width: 30%;">BY Isaac Tasabia</td> <td style="width: 30%;">CHECKED Gabriel Galo</td> </tr> <tr> <td>DETAILS</td> <td>BY Isaac Tasabia</td> <td>CHECKED Gabriel Galo</td> </tr> <tr> <td>QUANTITIES</td> <td>BY Gabriel Galo</td> <td>CHECKED Fred Feng</td> </tr> </table>	DESIGN	BY Isaac Tasabia	CHECKED Gabriel Galo	DETAILS	BY Isaac Tasabia	CHECKED Gabriel Galo	QUANTITIES	BY Gabriel Galo	CHECKED Fred Feng	<b>STATE OF CALIFORNIA</b> DEPARTMENT OF TRANSPORTATION	DIVISION OF ENGINEERING SERVICES STRUCTURE DESIGN <b>DESIGN BRANCH 15</b>	<table border="1" style="width: 100%; border-collapse: collapse;"> <tr> <td>BRIDGE NO.</td> <td>55E0171</td> </tr> <tr> <td>POST MILE</td> <td>5.62</td> </tr> </table> <p style="text-align: center; font-weight: bold; font-size: 1.2em;">RETAINING WALL No. 335</p> <p style="text-align: center; font-weight: bold; font-size: 1.2em;">ARCHITECTURAL DETAILS No. 1</p>	BRIDGE NO.	55E0171	POST MILE	5.62		
DESIGN	BY Isaac Tasabia	CHECKED Gabriel Galo																
DETAILS	BY Isaac Tasabia	CHECKED Gabriel Galo																
QUANTITIES	BY Gabriel Galo	CHECKED Fred Feng																
BRIDGE NO.	55E0171																	
POST MILE	5.62																	
STRUCTURES DESIGN DETAIL SHEET (ENGLISH) (REV. 09-01-10)		ORIGINAL SCALE IN INCHES FOR REDUCED PLANS	UNIT: 3604 PROJECT NUMBER & PHASE: 12120000181	CONTRACT NO.: 12-0M3504	DISREGARD PRINTS BEARING EARLIER REVISION DATES	<table border="1" style="width: 100%; border-collapse: collapse;"> <tr> <td colspan="4">REVISION DATES</td> <td>SHEET</td> <td>OF</td> </tr> <tr> <td>10-01-15</td> <td>10-30-15</td> <td>12-29-15</td> <td>03-25-16</td> <td>17</td> <td>19</td> </tr> </table>	REVISION DATES				SHEET	OF	10-01-15	10-30-15	12-29-15	03-25-16	17	19
REVISION DATES				SHEET	OF													
10-01-15	10-30-15	12-29-15	03-25-16	17	19													

USERNAME => s128284 DATE PLOTTED => 09-AUG-2016 TIME PLOTTED => 14:16


DIST	COUNTY	ROUTE	POST MILES TOTAL PROJECT	SHEET No.	TOTAL SHEETS
12	Ora	405	2.6/6.5	430	431
 REGISTERED CIVIL ENGINEER			06-10-16 DATE		
06-27-16 PLANS APPROVAL DATE					
<small>The State of California or its officers or agents shall not be responsible for the accuracy or completeness of scanned copies of this plan sheet.</small>					




**1** **DETAIL**  
1/2" = 1'-0"




**2** **DETAIL**  
1/2" = 1'-0"




**3** **DETAIL**  
1/2" = 1'-0"



**5** **DETAIL**  
1/2" = 1'-0"



**4** **DETAIL**  
1/2" = 1'-0"



FRACTURED RIB TRIANGULAR PATTERN - ELEVATION VIEW

**CONCRETE SURFACE TEXTURE**  
NO SCALE

NOTE:  
THE CONTRACTOR MUST VERIFY ALL CONTROLLING FIELD DIMENSIONS BEFORE ORDERING OR FABRICATING ANY MATERIAL.

STRUCTURES DESIGN DETAIL SHEET (ENGLISH) (REV. 09-01-10)	DESIGN	BY Isaac Tasabia	CHECKED Gabriel Galo	STATE OF CALIFORNIA DEPARTMENT OF TRANSPORTATION	DIVISION OF ENGINEERING SERVICES STRUCTURE DESIGN DESIGN BRANCH 15	BRIDGE NO.	RETAINING WALL No. 335	
	DETAILS	BY Isaac Tasabia	CHECKED Gabriel Galo			55E0171		ARCHITECTURAL DETAILS No. 2
	QUANTITIES	BY Gabriel Galo	CHECKED Fred Feng			POST MILE 5.62		
ORIGINAL SCALE IN INCHES FOR REDUCED PLANS					UNIT: 3604 PROJECT NUMBER & PHASE: 12120000181	CONTRACT NO.: 12-0M3504	DISREGARD PRINTS BEARING EARLIER REVISION DATES	
						REVISION DATES	SHEET 18 OF 19	

DIST	COUNTY	ROUTE	POST MILES TOTAL PROJECT	SHEET No.	TOTAL SHEETS
12	Ora	405	2.6/6.5	431	431

*Sungro Cho* 12-18-15  
 REGISTERED CIVIL ENGINEER DATE


06-27-16  
 PLANS APPROVAL DATE

Sungro Cho  
 No. C75151  
 Exp. 12-31-17  
 CIVIL  
 STATE OF CALIFORNIA

The State of California or its officers or agents shall not be responsible for the accuracy or completeness of electronic copies of this plan sheet.

**BENCH MARK**

BM 3DD-14-91 Elev 61.76  
 Southeasterly corner of the intersection of Culver Drive and the Northbound 405 freeway off-ramp, 35' Southeasterly of the centerline of Culver Drive and 40' Northeasterly of the centerline of the Northbound off-ramp.  
 NAVD88



**PLAN**  
 1" = 40'



**PROFILE**  
 Horiz: 1" = 10'  
 Vert: 1" = 10'

<b>ENGINEERING SERVICES</b>		<b>MATERIALS AND GEOTECHNICAL SERVICES</b>		<b>STATE OF CALIFORNIA</b>		<b>DIVISION OF ENGINEERING SERVICES</b>		<b>BRIDGE No. 335</b>	
FUNCTIONAL SUPERVISOR		DRAWN BY: I. G-Remmen		DEPARTMENT OF TRANSPORTATION		STRUCTURE DESIGN		<b>LOG OF TEST BORINGS</b>	
NAME: D. Jang		CHECKED BY: N. Lee		FIELD INVESTIGATION BY: S. Cho		DESIGN BRANCH <b>15</b>		BRIDGE No. 55E0171	
OGS CIVIL LOG OF TEST BORINGS SHEET		ORIGINAL SCALE IN INCHES FOR REDUCED PLANS		PROJECT NUMBER & PHASE: 12120000181		POST MILE 5.62		CONTRACT No.: 12-0M3504	
				UNIT: 3650		DISREGARD PRINTS BEARING EARLIER REVISION DATES		REVISION DATES	
				0 1 2 3		12-09-15 12-30-15 02-22-16		SHEET 19 OF 19	

FILE => 55e0171-z-1+tb.dgn

USERNAME => s128284 DATE PLOTTED => 09-AUG-2016 TIME PLOTTED => 14:17